



Wisconsin Place Residential

Chevy Chase, MD



Jenna Marcolina
Construction Management



Technical Assignment #2
November 2, 2007





Wisconsin Place Residential
Chevy Chase, MD

Jenna Marcolina
Dr. Horman

Construction Management
Advisor

Table of Contents

| | |
|--|----------------|
| <i>Executive Summary</i> | <i>Page 2</i> |
| A. Detailed Project Schedule | Page 3 |
| B. Site Layout Planning | Page 5 |
| C. Assemblies Estimate | Page 7 |
| D. Detailed Structural Systems Estimate | Page 8 |
| E. General Conditions Estimate | Page 9 |
| <i>Appendix A: Detailed Project Schedule</i> | <i>Page 11</i> |
| <i>Appendix B: Site Layout Plan</i> | <i>Page 12</i> |
| <i>Appendix C: Assemblies Takeoffs & Calcs</i> | <i>Page 13</i> |
| <i>Appendix D: Structural Takeoffs & Calcs</i> | <i>Page 14</i> |



Wisconsin Place Residential
Chevy Chase, MD

Jenna Marcolina
Dr. Horman

Construction Management
Advisor

Executive Summary

This technical assignment analyzes the key features of Wisconsin Place Residential that affect its execution. More detailed schedules and estimates are performed to see where the majority of time and money are spent on the project. The hope in doing this is to discover a thesis research topic, some aspect of the project that could be done in a modified way. The detailed project schedule shows the major construction activities broken down by trade. The concrete schedule, in particular, shows the phasing of pouring columns and slabs to optimize efficiency. The site layout planning gives a snapshot of a critical phase of construction, which in this instance is the superstructure. Logical flow and placement of equipment is the main concern here. By sketching out the site plan with all of its components, a better layout can sometimes be configured. An assemblies estimate was performed on the exterior enclosure of WPR using RS Means Construction Cost Data 2007. Further estimating of the structural system sheds more light onto the breakdown of project expenses. Finally, a general conditions estimate explains the costs not directly associated with the building, but significant all the same. These include operational costs, supplies, and project staff.



A. Detailed Project Schedule

The detailed schedule in Appendix A depicts the construction process from beginning to end with some key milestones in between. One key phase to highlight is the concrete pour schedule for floors 2 through 15. The 200 item constraint did not allow for highly detailed phasing, but a more detailed schedule of concrete production would look something like this:

| |
|--|
| Level 3 |
| Level 3 - Part 1 Form/Pour Slabs & Columns |
| Level 3 - Part 1 Stress/Strip/Reshore |
| Level 3 - Part 2 Form/Pour Slabs & Columns |
| Level 3 - Part 3 Form/Pour Slabs & Columns |
| Level 3 - Part 2 Stress/Strip/Reshore |
| Level 3 - Part 3 Stress/Strip/Reshore |
| Remove Reshores @ 3rd Floor |
| Level 4 |
| Level 4 - Part 1 Form/Pour Slabs & Columns |
| Level 4 - Part 2 Form/Pour Slabs & Columns |
| Level 4 - Part 3 Form/Pour Slabs & Columns |
| Level 4 - Part 1 Stress/Strip/Reshore |
| Level 4 - Part 2 Stress/Strip/Reshore |
| Level 4 - Part 4 Form/Pour Slabs & Columns |
| Level 4 - Part 3 Stress/Strip/Reshore |
| Level 4 - Part 4 Stress/Strip/Reshore |
| Remove Reshores @ 4th Floor |

Each floor is broken into three to five sections to keep the pours manageable. The project specifications require that at least one floor be fully formed or shored with a minimum of 3 floors reshored at any time. Some of these activities occur simultaneously, which keeps the job moving right along. Below is an excerpt from a spreadsheet that Turner keeps on record to track the amount of concrete that is placed each day. This tally sheet is a quick and easy way to monitor progress. The site layout plan in Appendix B also shows a proposed sequencing of pours for the large WPR footprint. Since they are currently in the superstructure phase of the project, concrete production has been one of Turner's top priorities of late.



Wisconsin Place Residential
Chevy Chase, MD

Jenna Marcolina
Dr. Horman

Construction Management
Advisor

| Concrete Production | | | | | |
|---------------------|--------|-----------|-----------|-----------|-----------|
| Level | | Pour 1 | Pour 2 | Pour 3 | Pour 4 |
| 3 | SF | 9436 | 10286 | 5864 | 6120 |
| | Poured | 9436 | 10286 | 5864 | 6120 |
| | Date | 8/16/2007 | 8/30/2007 | 8/30/2007 | 9/11/2007 |
| 4 | SF | 9436 | 10286 | 5864 | 6120 |
| | Poured | 9436 | 10286 | 5864 | 6120 |
| | Date | 9/4/2007 | 9/10/2007 | 9/12/2007 | 9/19/2007 |

Please note that the slab on grade is not included in Turner's contract. The slab was poured by the parking garage contractor, who coincidentally, was run by a separate Turner team.

The WPR Turner team entered the Chevy Chase, MD site in June 2007 and began constructing this 15 story apartment building atop a four level parking garage. Therefore, no site work or foundation work was required. Also, all utilities were conveniently hooked up and delivered to the slab where Turner began building. This explains why no existing utilities are shown on the site plan. In fact, no civil drawings were issued for the Wisconsin Place project. The fact is simple: utilities are not a concern for Turner because another project has already taken care of them.



Wisconsin Place Residential
Chevy Chase, MD

Jenna Marcolina
Dr. Horman

Construction Management
Advisor

B. Site Layout Planning

The site plan in Appendix B shows the superstructure phase of the Wisconsin Place project. At first glance, it is evident that the site is very congested. Three other projects including an office tower, parking garage, and retail stores are happening concurrently on the same 1.1 million square foot plot of land. So, Turner has experienced many space and coordination issues thus far.

One potential way to divide the floor slabs into sections is shown on the layout. Most of the deliveries and staging happens in the northwest corner of the site, as there is limited space elsewhere. The concrete materials are close to the building footprint, which minimizes the swing of the crane for picking and placing forms and rebar cages. Two main entrances to the site are depicted on the plan as well. There is not a lot of room for circulation, so the idea with site access is to get in and get out as quickly as possible.

The concrete for the building structure is placed using a pump. Trucks enter at one of the gate openings and exit the other. They usually park near the concrete material laydown area. Since so many concrete trucks are needed to accomplish the massive pour areas, a steady traffic flow develops where the full truck comes in right behind the empty truck to resume placing.



The far right lane of Friendship Boulevard has been closed for construction and helps with the space constraint. Delivery trucks, however, are not allowed to unload from this section of road. It becomes dangerous when a thin metal fence is the only thing that separates passing vehicles from heavy machinery and materials. So, it is best to keep the hazardous material as far away from the public as possible.



Wisconsin Place Residential
Chevy Chase, MD

Jenna Marcolina
Dr. Horman

Construction Management
Advisor

Turner trailers are located by the northwest gate, a prime location for monitoring deliveries and controlling who enters the site. Trash chutes are a great way to manage waste on a job site. They keep debris contained until trucks haul it all away. These chutes are conveniently located along the driving path so that dump trucks can pick and go.

It would be interesting to see the tower cranes repositioned within the building footprint to increase space in the public areas. For example, the tower crane could be placed in the elevator shaft until the building tops out. Then, it can be removed and the elevators installed. As evidenced by the site photo on the previous page, the WPR construction site is extremely tight. Employees are no longer allowed to park on site due to congestion issues. To comment further, Tower Crane #1 seems to be placed in an inopportune spot, with nearly half of its boom swing wasted over Friendship Boulevard. Perhaps it could be positioned in a way that would make it more accessible to resources on site.



C. Assemblies Estimate: Building Enclosure

RS Means Assemblies Cost Data 2007 was used for all of the unit pricing, and these takeoffs and calculations can be found in Appendix C.

The building enclosure was analyzed for the assemblies estimate. The enclosure includes:

- Standard face brick backed w/ 16 gage steel studs @ 16" o.c.
- Aluminum and glass w/o transom wide stile doors
- Aluminum and glass revolving stock design doors
- Double hung aluminum standard glass windows
- Ashlar veneer w/ metal stud backup
- Insulated glazing panel, ½" thick, tinted

Assumptions:

- Use location factor for Baltimore, MD = 0.93
- Precast and aluminum panels were excluded because they comprise such a small portion of the façade
- Typical window size of 3' x 6'
- Typical door size of 3' x 7'
- Substitute ashlar veneer for cast stone – closest match
- Pricing includes waterproofing and sealants

| Assemblies Estimate Summary | |
|------------------------------------|--------------------|
| Building Enclosure | |
| Component | Cost |
| Brick Veneer | \$1,311,000 |
| Aluminum Doors | \$442,000 |
| Aluminum Windows | \$1,871,100 |
| Cast Stone Veneer | \$274,950 |
| Glass Curtainwall Panels | \$413,228 |
| | |
| Subtotal | \$4,312,278 |
| Location Factor | 0.93 |
| Total Assemblies Estimate | \$4,010,418 |



D. Detailed Structural Systems Estimate

The superstructure of Wisconsin Place Residential was estimated using RS Means Facilities Cost Data 2007. This is slightly different from “Assemblies” because it breaks building materials into their most basic units. Since none of the predefined structural systems in “Assemblies” were a close match to the post-tensioned system of WPR, “Facilities” was used to estimate the building more accurately. These calculations and takeoffs can be found in Appendix D.

Assumptions:

- Typical floor to ceiling height of 9' used for column and shear wall heights
- Use location factor for Baltimore, MD = 0.93
- Concrete strength = 5,000 psi for all components
- Concrete CY calculations do not subtract out the volume of the rebar
- Rebar was calculated on the basis of length – for ease of calculation it was assumed to run from one face of a column/beam/slab to the other – cover was not accounted for
- The 5th Floor was used as a “typical floor” for the takeoff since floors 5 through 11 are more or less the same – the estimate was then multiplied by 15 floor and the roof slab added to get the final number

| Detailed Structural Estimate Summary | | | |
|--------------------------------------|------------|-------------|--------------------|
| Component | Cost/Floor | x # Floors | Cost |
| Floor Slab | \$156,561 | x 15 floors | \$2,348,415 |
| Beams | \$16,005 | x 15 floors | \$240,075 |
| Columns | \$89,102 | x 15 floors | \$1,336,530 |
| Shear Walls | \$11,394 | x 15 floors | \$170,910 |
| | | | |
| Roof Slab | \$28,022 | x 1 floor | \$28,022 |
| | | | |
| Subtotal | | | \$4,123,952 |
| Location Factor | | | 0.93 |
| Total Structural Estimate | | | \$3,835,275 |



Wisconsin Place Residential
Chevy Chase, MD

Jenna Marcolina
Dr. Horman

Construction Management
Advisor

E. General Conditions Estimate

The General Conditions Estimate can be found on the next page.

Some of the unit costs from the general conditions estimate were taken from RS Means 2007 while others were ballpark figures from Turner. The general conditions for Wisconsin Place Residential come out around \$4 million. This figure does not include insurance, bonding, fee, or contingency. Those items are all handled under separate cover.

A project duration of 30 months was used for most of the GC estimate. This is the time from the Notice to Proceed to Substantial completion. The temporary electric service is only needed for 8 months because permanent power will be available to the building in March 2008.

Turner pays for employee relocation and travel expenses to make the job transition easier. Since their project executive is from Texas, his living and travel expenses are fully covered by Turner. This includes his apartment rent, utilities, mileage, flights, and vehicle. The superintendent and project manager also drive company vehicles and are reimbursed for them, as indicated in the estimate.

The staffing costs make up the bulk of the general conditions estimate at around 75%. Because WPR is such an immense undertaking, both the project manager and project executive are on site 100% of the time. In addition to this close supervision, the owner, Archstone-Smith, has a representative permanently placed on site at all times. Archstone-Smith pays for their GC costs like their trailer and temporary utilities.

Turner does not have a cleaning crew for their trailers. They purchased 1500 hours of cleaning from the concrete subcontractor and use some of these hours towards cleaning the trailers as well as for site cleanup. The General Conditions Estimate is around 4% of the total project cost.



Wisconsin Place Residential
Chevy Chase, MD

Jenna Marcolina
Dr. Horman

Construction Management
Advisor

| General Conditions Estimate for Wisconsin Place Residential | | | | |
|--|-----------------|-------------|-------------------|--------------------|
| Description | Quantity | Unit | Price/Unit | Amount |
| Protection & Safety | | | | |
| Security Guard | 30 | MO | \$4,000 | \$120,000 |
| First Aid Supplies | 1 | LS | \$1,000 | \$1,000 |
| Safety Signs | 1 | LS | \$1,000 | \$1,000 |
| Hardhats, Gloves, Goggles | 1 | LS | \$2,000 | \$2,000 |
| Perimeter Fence | 1 | LS | \$60,000 | \$60,000 |
| General Expenses | | | | |
| Living & Travel | 30 | MO | \$2,000 | \$60,000 |
| Trailers (3) | 30 | MO | \$900 | \$81,000 |
| Office Furnishings | 1 | LS | \$5,000 | \$5,000 |
| Office Supplies | 1 | LS | \$4,000 | \$4,000 |
| IT Equipment | 1 | LS | \$50,000 | \$50,000 |
| Parking | 30 | MO | \$1,000 | \$30,000 |
| Employee Vehicles (3) | 30 | MO | \$1,000 | \$90,000 |
| Telephones | 30 | MO | \$750 | \$67,500 |
| Dumpsters | 30 | MO | \$2,000 | \$60,000 |
| Toilets | 30 | MO | \$1,300 | \$39,000 |
| Project Staff | | | | |
| Project Executive | 30 | MO | \$30,000 | \$900,000 |
| Project Manager | 30 | MO | \$20,000 | \$600,000 |
| Superintendent | 30 | MO | \$15,000 | \$450,000 |
| Project Engineer | 30 | MO | \$10,000 | \$300,000 |
| Field Engineer | 30 | MO | \$10,000 | \$300,000 |
| Accounting | 30 | MO | \$5,000 | \$150,000 |
| Scheduling | 30 | MO | \$7,500 | \$225,000 |
| Purchasing | 30 | MO | \$7,500 | \$225,000 |
| Safety | 30 | MO | \$7,500 | \$225,000 |
| Temporary Utilities | | | | |
| Temporary Electric Service | 8 | MO | \$200 | \$1,600 |
| Temporary Water/Sewer Service | 30 | MO | \$300 | \$9,000 |
| Temporary Heat Service | 5 | MO | \$300 | \$1,500 |
| Total GC Estimate | | | | \$4,057,600 |



Wisconsin Place Residential
Chevy Chase, MD

Jenna Marcolina
Dr. Horman

Construction Management
Advisor

Appendix A: Detailed Project Schedule

| ID | Task Name | Duration | Start | Finish | 2007 | | | | | | | | | | | | 2008 | | | | | | | | | | | | 2009 | | | | | | | | | | | |
|----|---|----------|--------------|--------------|-------------|-----|-----|-------------|-----|-----|-------------|-----|-----|-------------|-----|-----|-------------|-----|-----|-------------|-----|-----|-------------|-----|-----|-------------|-----|-----|-------------|-----|-----|-------------|-----|-----|-------------|-----|-----|-------|-----|--|
| | | | | | 4th Quarter | | | 1st Quarter | | | 2nd Quarter | | | 3rd Quarter | | | 4th Quarter | | | 1st Quarter | | | 2nd Quarter | | | 3rd Quarter | | | 4th Quarter | | | 1st Quarter | | | 2nd Quarter | | | 3rd Q | | |
| | | | | | Sep | Oct | Nov | Dec | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | Jan | Feb | Mar | Apr | May | Jun | Jul | |
| 1 | Notice to Proceed | 0 days | Fri 10/20/06 | Fri 10/20/06 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2 | Ready to Start Structure | 0 days | Fri 7/27/07 | Fri 7/27/07 | ◆ 10/20 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4 | Concrete | 164 days | Thu 7/12/07 | Tue 2/26/08 | ◆ 7/27 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | Form/Pour 2nd Floor Slabs & Columns | 23 days | Thu 7/12/07 | Mon 8/13/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | Stress/Strip/Reshore 2nd Floor | 19 days | Wed 7/25/07 | Mon 8/20/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | Remove Reshores @ 2nd Floor | 16 days | Thu 9/20/07 | Thu 10/11/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | Form/Pour 3rd Floor Slabs & Columns | 14 days | Mon 8/13/07 | Thu 8/30/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | Stress/Strip/Reshore 3rd Floor | 16 days | Mon 8/20/07 | Mon 9/10/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11 | Remove Reshores @ 3rd Floor | 8 days | Fri 9/28/07 | Tue 10/9/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | Form/Pour 4th Floor Slabs & Columns | 18 days | Fri 8/24/07 | Fri 9/18/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 13 | Stress/Strip/Reshore 4th Floor | 9 days | Mon 9/17/07 | Thu 9/27/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 14 | Remove Reshores @ 4th Floor | 19 days | Thu 10/11/07 | Tue 11/6/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 15 | Form/Pour 5th Floor Slabs & Columns | 14 days | Mon 9/10/07 | Thu 9/27/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 16 | Stress/Strip/Reshore 5th Floor | 14 days | Mon 9/17/07 | Thu 10/4/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 17 | Remove Reshores @ 5th Floor | 22 days | Fri 10/19/07 | Mon 11/19/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 18 | Form/Pour 6th Floor Slabs & Columns | 18 days | Mon 9/17/07 | Wed 10/10/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 19 | Stress/Strip/Reshore 6th Floor | 17 days | Tue 9/25/07 | Wed 10/17/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 20 | Remove Reshores @ 6th Floor | 24 days | Tue 10/30/07 | Fri 11/30/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 21 | Form/Pour 7th Floor Slabs & Columns | 21 days | Thu 9/27/07 | Thu 10/25/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 22 | Stress/Strip/Reshore 7th Floor | 20 days | Mon 10/8/07 | Fri 11/2/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 23 | Remove Reshores @ 7th Floor | 21 days | Tue 11/13/07 | Tue 12/11/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 24 | Form/Pour 8th Floor Slabs & Columns | 25 days | Mon 10/8/07 | Fri 11/9/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 25 | Stress/Strip/Reshore 8th Floor | 23 days | Tue 10/16/07 | Thu 11/15/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 26 | Remove Reshores @ 8th Floor | 19 days | Mon 11/26/07 | Thu 12/20/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 27 | Form/Pour 9th Floor Slabs & Columns | 23 days | Thu 10/18/07 | Mon 11/19/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 28 | Stress/Strip/Reshore 9th Floor | 25 days | Thu 10/25/07 | Wed 11/28/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 29 | Remove Reshores @ 9th Floor | 13 days | Mon 1/7/08 | Wed 1/23/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 30 | Form/Pour 10th Floor Slabs & Columns | 23 days | Wed 10/31/07 | Fri 11/30/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 31 | Stress/Strip/Reshore 10th Floor | 22 days | Thu 11/8/07 | Fri 12/7/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 32 | Remove Reshores @ 10th Floor | 12 days | Mon 12/31/07 | Tue 1/15/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 33 | Form/Pour 11th Floor Slabs & Columns | 21 days | Tue 11/13/07 | Tue 12/11/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 34 | Stress/Strip/Reshore 11th Floor | 21 days | Tue 11/20/07 | Tue 12/18/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 35 | Remove Reshores @ 11th Floor | 7 days | Fri 1/11/08 | Mon 1/21/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 36 | Form/Pour 12th Floor Slabs & Columns | 34 days | Thu 11/29/07 | Tue 1/15/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 37 | Stress/Strip/Reshore 12th Floor | 32 days | Fri 12/7/07 | Mon 1/21/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 38 | Remove Reshores @ 12th Floor | 5 days | Tue 1/22/08 | Mon 1/28/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 39 | Form/Pour 13th Floor Slabs & Columns | 16 days | Fri 12/14/07 | Fri 1/4/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 40 | Stress/Strip/Reshore 13th Floor | 11 days | Thu 12/27/07 | Thu 1/10/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 41 | Remove Reshores @ 13th Floor | 7 days | Mon 2/4/08 | Tue 2/12/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 42 | Form/Pour 14th Floor Slabs & Columns | 5 days | Thu 12/27/07 | Wed 1/2/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 43 | Stress/Strip/Reshore 14th Floor | 8 days | Tue 1/8/08 | Thu 1/17/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 44 | Remove Reshores @ 14th Floor | 7 days | Mon 2/4/08 | Tue 2/12/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 45 | Form/Pour 15th Floor Slabs & Columns | 6 days | Thu 1/10/08 | Thu 1/17/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 46 | Stress/Strip/Reshore 15th Floor | 6 days | Thu 1/17/08 | Thu 1/24/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 47 | Remove Reshores @ 15th Floor | 7 days | Mon 2/4/08 | Tue 2/12/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 48 | Form/Pour Roof Slabs & Columns | 8 days | Mon 1/21/08 | Wed 1/30/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 49 | Top Out Structure | 0 days | Wed 1/30/08 | Wed 1/30/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 50 | Stress/Strip/Reshore Roof | 1 day | Tue 1/8/08 | Tue 1/8/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 51 | Remove Reshores @ Roof | 4 days | Thu 2/21/08 | Tue 2/26/08 | ◆ 1/30 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 52 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 53 | Exterior Studs | 143 days | Fri 9/28/07 | Tue 4/15/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 54 | Layout/Install 1st Floor Exterior Studs | 8 days | Fri 9/28/07 | Fri 10/9/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 55 | Layout/Install 2nd Floor Exterior Studs | 16 days | Wed 10/10/07 | Wed 10/31/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 56 | Layout/Install 3rd Floor Exterior Studs | 20 days | Mon 10/22/07 | Fri 11/16/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 57 | Layout/Install 4th Floor Exterior Studs | 19 days | Wed 11/7/07 | Mon 12/3/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 58 | Layout/Install 5th Floor Exterior Studs | 19 days | Tue 11/20/07 | Fri 12/14/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 59 | Layout/Install 6th Floor Exterior Studs | 17 days | Thu 12/6/07 | Fri 12/28/07 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 60 | Layout/Install 7th Floor Exterior Studs | 21 days | Wed 12/12/07 | Wed 1/9/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 61 | Layout/Install 8th Floor Exterior Studs | 19 days | Fri 12/21/07 | Wed 1/16/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 62 | Layout/Install 9th Floor Exterior Studs | 8 days | Thu 1/24/08 | Mon 2/4/08 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| | | | | | | | | | | |
|---|-------|--|-----------|--|-----------------|--|--------------------|--|----------|--|
| Wisconsin Place Residential Detailed Project Schedule by Trade November 2, 2007 | Task | | Progress | | Summary | | External Tasks | | Deadline | |
| | Split | | Milestone | | Project Summary | | External Milestone | | | |




Wisconsin Place Residential
Chevy Chase, MD


Jenna Marcolina
Dr. Horman

Construction Management
Advisor


Appendix B: Site Layout Plan



General Notes



| No. | Revision/Issue | Date |
|-----|----------------|------|
| | | |



 N

WISCONSIN PLACE RESIDENTIAL HOUSING
 34,395 SF (15 STORIES)

| | |
|---|------------------------------------|
| SITE LAYOUT BY: JENNA MARCOLINA | |
| Date: 11/02/07 | SUPERSTRUCTURE SITE LAYOUT PLAN |
| Scale: 1/75" = 1' | |



Appendix C: Assemblies Estimate Calculations and Takeoffs

See also hand calculations attached.

| Brick Veneer w/ Metal Stud Backup | | | | | |
|-----------------------------------|------|----------|---------|-------|-------------|
| Qty | Unit | Material | Install | Total | Cost |
| 60000 | SF | 7.45 | 14.4 | 21.85 | \$1,311,000 |

| Aluminum Doors | | | | | | |
|----------------|-----|------|----------|---------|-----------------|------------------|
| Type | Qty | Unit | Material | Install | Total | Cost |
| Wide Stile | 160 | each | 1575 | 855 | 2430 | \$388,800 |
| Revolving | 2 | each | 22600 | 4000 | 26600 | \$53,200 |
| | | | | | | |
| | | | | | Subtotal | \$442,000 |

| Aluminum Windows | | | | | |
|------------------|------|----------|---------|-------|-------------|
| Qty | Unit | Material | Install | Total | Cost |
| 1925 | each | 735 | 237 | 972 | \$1,871,100 |

| Cast Stone Veneer w/ Metal Stud Backup | | | | | |
|--|------|----------|---------|-------|-----------|
| Qty | Unit | Material | Install | Total | Cost |
| 9000 | SF | 14.9 | 15.65 | 30.55 | \$274,950 |

| Curtainwall Panels | | | | | |
|--------------------|------|----------|---------|-------|-----------|
| Qty | Unit | Material | Install | Total | Cost |
| 17850 | SF | 13.95 | 9.2 | 23.15 | \$413,228 |



Appendix D: Detailed Structural Systems Estimate Calculations and Takeoffs

See also hand calculations attached.

Floor Slabs

| Floor Slab | | | | | |
|----------------|-----------|-----------|-----------|--------|--|
| Perimeter (LF) | Area (SF) | Vol. (CF) | Vol. (CY) | SFCA | |
| 1350 | 41416 | 25885 | 958.7037 | 1687.5 | |

| Floor Slab Stressing Tendons #4 @ 24" sp | | | | |
|--|-----|--------|-----------------|----------------|
| No. | Qty | Length | Unit Wt (lb/ft) | Wt (lb) |
| 4 | 160 | 65 | 0.67 | 6968 |
| 4 | 35 | 300 | 0.67 | 7035 |
| 4 | 65 | 230 | 0.67 | 10016.5 |
| 4 | 80 | 70 | 0.67 | 3752 |
| | | | | |
| | | | Subtotal | 27771.5 |

| Floor Slab Stressing Tendons #4 @ 12" sp | | | | |
|--|-----|--------|-----------------|---------------|
| No. | Qty | Length | Unit Wt (lb/ft) | Wt (lb) |
| 4 | 65 | 10 | 0.67 | 435.5 |
| 4 | 80 | 10 | 0.67 | 536 |
| 4 | 150 | 10 | 0.67 | 1005 |
| 4 | 230 | 10 | 0.67 | 1541 |
| 4 | 160 | 10 | 0.67 | 1072 |
| | | | | |
| | | | Subtotal | 4589.5 |

| Elevated Slabs #4-#7 | | | | | |
|----------------------|----------|-------|-----------|---------------|----------|
| Total (lb) | Material | Labor | Equipment | Total Cost/lb | Cost |
| 32361 | 0.49 | 0.23 | 0 | 0.72 | \$23,300 |



Wisconsin Place Residential
Chevy Chase, MD

Jenna Marcolina
Dr. Horman

Construction Management
Advisor

Columns

| Columns | | | | | | | |
|-----------------|--------|--------------|------------|-------------|-----------------|-------------|--|
| L (in) | W (in) | Vol (CF) | Qty | Total CF | Total CY | SFCA | |
| 16 | 28 | 28 | 42 | 1176 | 43.55556 | 2772 | |
| 28 | 16 | 28 | 32 | 896 | 33.18519 | 2112 | |
| 16 | 36 | 36 | 4 | 144 | 5.333333 | 312 | |
| 16 | 32 | 32 | 8 | 256 | 9.481481 | 576 | |
| 10 | 84 | 52.5 | 2 | 105 | 3.888889 | 282 | |
| 32 | 16 | 32 | 4 | 128 | 4.740741 | 288 | |
| 28 | 18 | 31.5 | 4 | 126 | 4.666667 | 276 | |
| 12 | 108 | 81 | 2 | 162 | 6 | 360 | |
| 40 | 14 | 35 | 2 | 70 | 2.592593 | 162 | |
| 12 | 24 | 18 | 4 | 72 | 2.666667 | 216 | |
| 24 | 12 | 18 | 4 | 72 | 2.666667 | 216 | |
| 18 | 28 | 31.5 | 2 | 63 | 2.333333 | 138 | |
| 36 | 10 | 22.5 | 4 | 90 | 3.333333 | 276 | |
| 36 | 16 | 36 | 2 | 72 | 2.666667 | 156 | |
| 24 | 28 | 42 | 2 | 84 | 3.111111 | 156 | |
| 12 | 28 | 21 | 2 | 42 | 1.555556 | 120 | |
| 20 | 12 | 15 | 2 | 30 | 1.111111 | 96 | |
| 26 | 20 | 32.5 | 2 | 65 | 2.407407 | 138 | |
| 12 | 36 | 27 | 2 | 54 | 2 | 144 | |
| 12 | 24 | 18 | 2 | 36 | 1.333333 | 108 | |
| | | | | | | | |
| Subtotal | | 637.5 | 128 | 3743 | 138.6296 | 8904 | |

| Columns #3-#7 | | | | | |
|---------------|----------|-------|-----------|---------------|---------|
| Total (lb) | Material | Labor | Equipment | Total Cost/lb | Cost |
| 9400.32 | 0.47 | 0.44 | 0 | 0.91 | \$8,554 |

| Columns #8-#18 | | | | | |
|----------------|----------|-------|-----------|---------------|----------|
| Total (lb) | Material | Labor | Equipment | Total Cost/lb | Cost |
| 15227.82 | 0.47 | 0.29 | 0 | 0.76 | \$11,573 |



Wisconsin Place Residential
Chevy Chase, MD

Jenna Marcolina
Dr. Horman

Construction Management
Advisor

Beams

| Beams | | | | | | | |
|-----------------|------------|------------|-------------|-----|-----------------|-----------------|-----------------|
| Mark | Width (in) | Depth (in) | Length (LF) | Qty | Vol. (CF) | Vol. (CY) | SFCA |
| 5B-1 | 32 | 30 | 20 | 2 | 266.6667 | 9.876543 | 413.3333 |
| 5B-2 | 30 | 18 | 20 | 3 | 225 | 8.333333 | 480 |
| TB-1 | 8 | 20 | 16 | 1 | 17.77778 | 0.658436 | 74.66667 |
| TB-3 | 8 | 20 | 16 | 1 | 17.77778 | 0.658436 | 74.66667 |
| TB-4 | 8 | 24 | 16 | 1 | 21.33333 | 0.790123 | 85.33333 |
| TB-5 | 12 | 18 | 28 | 1 | 42 | 1.555556 | 140 |
| TB-6 | 12 | 18 | 22 | 1 | 33 | 1.222222 | 110 |
| TB-7 | 8 | 20 | 16 | 2 | 35.55556 | 1.316872 | 149.3333 |
| TB-8 | 8 | 20 | 9 | 2 | 20 | 0.740741 | 84 |
| Subtotal | | | | | 679.1111 | 25.15226 | 1611.333 |

| Beam Rebar | | | | |
|------------|-----|-------------|------------------|-----------------|
| No. | Qty | Length (ft) | Unit Wt. (lb/ft) | Wt. (lb) |
| 6 | 8 | 9 | 1.502 | 108.144 |
| 7 | 12 | 20 | 2.04 | 489.6 |
| 7 | 10 | 20 | 2.04 | 408 |
| 8 | 12 | 16 | 2.67 | 512.64 |
| 8 | 14 | 16 | 2.67 | 598.08 |
| 9 | 6 | 28 | 3.4 | 571.2 |
| | | | Subtotal | 2687.664 |

| Beams #3-#7 | | | | | |
|-------------|----------|-------|-----------|---------------|-------|
| Total (lb) | Material | Labor | Equipment | Total Cost/lb | Cost |
| 1005.744 | 0.47 | 0.41 | 0 | 0.88 | \$885 |

| Beams #8-#18 | | | | | |
|--------------|----------|-------|-----------|---------------|---------|
| Total (lb) | Material | Labor | Equipment | Total Cost/lb | Cost |
| 1681.92 | 0.47 | 0.24 | 0 | 0.71 | \$1,194 |



Shear Walls

| Shear Walls | | |
|-----------------|------------|-----------------|
| Mark | Vol. (CF) | Vol. (CY) |
| SW 1 | 90 | 3.333333 |
| SW 2 | 234 | 8.666667 |
| SW 3 | 90 | 3.333333 |
| SW 4 | 90 | 3.333333 |
| SW 5 | 180 | 6.666667 |
| SW 6 | 90 | 3.333333 |
| | | |
| Subtotal | 774 | 28.66667 |

| Shear Wall Rebar | | | | |
|------------------|-----|-------------|------------------|----------------|
| No. | Qty | Length (ft) | Unit Wt. (lb/ft) | Wt. (lb) |
| 4 | 124 | 9 | 0.67 | 747.72 |
| 4 | 108 | 10 | 0.67 | 651.24 |
| 4 | 18 | 22 | 0.67 | 108.54 |
| 4 | 18 | 28 | 0.67 | 108.54 |
| 6 | 92 | 9 | 1.5 | 1242 |
| 7 | 32 | 9 | 2.04 | 587.52 |
| | | | | |
| | | | Subtotal | 3445.56 |

| Shear Walls #3-#7 | | | | | |
|-------------------|----------|-------|-----------|---------------|---------|
| Total (lb) | Material | Labor | Equipment | Total Cost/lb | Cost |
| 3445.56 | 0.47 | 0.22 | 0 | 0.69 | \$2,377 |



Wisconsin Place Residential
Chevy Chase, MD

Jenna Marcolina
Dr. Horman

Construction Management
Advisor

Roof Slab

| Roof Slab | | | | | | |
|-----------------|----------------|-------------|-----------------|----------------|-----------------|--|
| Slab Thickness | Perimeter (LF) | Area (SF) | Vol. (CF) | Vol. (CY) | SFCA | |
| 6 | 65 | 230 | 115 | 4.259259 | 65 | |
| 7 | 400 | 4250 | 2479.167 | 91.82099 | 466.6667 | |
| 12 | 150 | 1100 | 1100 | 40.74074 | 300 | |
| | | | | | | |
| Subtotal | 615 | 5580 | 3694.167 | 136.821 | 831.6667 | |

| Roof Slab Rebar | | | | | |
|-----------------|-----|--------|-----------------|---------------|--|
| No. | Qty | Length | Unit Wt | Total Wt (lb) | |
| 4 | 75 | 55 | 0.67 | 2763.75 | |
| 4 | 55 | 75 | 0.67 | 2763.75 | |
| 4 | 55 | 15 | 0.67 | 552.75 | |
| 4 | 15 | 20 | 0.67 | 201 | |
| 4 | 15 | 35 | 0.67 | 351.75 | |
| 5 | 35 | 30 | 1.04 | 1092 | |
| 5 | 30 | 35 | 1.04 | 1092 | |
| | | | | | |
| | | | | | |
| | | | Subtotal | 8817 | |

| Elevated Slabs #4-#7 | | | | | |
|----------------------|----------|-------|-----------|---------------|---------|
| Total (lb) | Material | Labor | Equipment | Total Cost/lb | Cost |
| 8817 | 0.49 | 0.23 | 0 | 0.72 | \$6,348 |



Wisconsin Place Residential
Chevy Chase, MD

Jenna Marcolina
Dr. Horman

Construction Management
Advisor

Total Concrete

| Total Concrete - Typical Floor | | | |
|---------------------------------------|--------|-----------------|------------------|
| Component | CY | Cost/CY | Cost/Floor |
| Slabs | 958.70 | \$114 | \$109,292 |
| Beams | 25.15 | \$114 | \$2,867 |
| Columns | 138.63 | \$114 | \$15,804 |
| Shear Walls | 28.67 | \$114 | \$3,268 |
| | | | |
| | | Subtotal | \$131,231 |
| | | | |
| Plus Roof | 136.82 | \$114 | \$15,598 |

Total Formwork

| Total Formwork - Typical Floor | | | | | | |
|---------------------------------------|------|----------|-------|-----------|-----------------|-----------------|
| Component | SFCA | Material | Labor | Equipment | Total Cost/SFCA | Cost/Floor |
| Floor Slab | 1687 | 1.43 | 3.06 | 0 | \$4 | \$7,575 |
| Beams | 1612 | 0.9 | 5.25 | 0 | \$6 | \$9,914 |
| Columns | 8904 | 0.84 | 4.67 | 0 | \$6 | \$49,061 |
| Shear Walls | 1656 | 0.87 | 2.17 | 0 | \$3 | \$5,034 |
| | | | | | | |
| | | | | | Subtotal | \$71,584 |
| | | | | | | |
| Plus Roof | 832 | 1.43 | 3.06 | | \$4 | \$3,736 |

Total Concrete Placing

| Total Concrete Placing - Typical Floor | | | | | | |
|---|----------|----------|-------|-----------|-----------------|-----------------|
| Component | CY | Material | Labor | Equipment | Total Cost/CY | Cost/Floor |
| Floor Slab | 958.7037 | 0 | 12.4 | 4.7 | 17.1 | \$16,394 |
| Beams | 25.15226 | 0 | 33 | 12.5 | 45.5 | \$1,144 |
| Columns | 138.6296 | 0 | 21.5 | 8.15 | 29.65 | \$4,110 |
| Shear Walls | 28.66667 | 0 | 18.05 | 6.85 | 24.9 | \$714 |
| | | | | | | |
| | | | | | Subtotal | \$22,362 |
| | | | | | | |
| Roof Slab | 136.821 | | 12.4 | 4.7 | 17.1 | \$2,340 |