# Ingleside at King Farm

Technical Assignment # 2 Alternative Floor Systems Investigation Report



Prepared by: Stephen Dung Tat

Prepared for: Professor Kevin M. Parfitt



The Pennsylvania State University Department of Architectural Engineering Senior Thesis 2008-2009

### **Table of Contents**

Executive Summary
Introduction4
Existing Structural System Discussion
Codes and Standards10
Material Strength Summary10
Building Design Load Discussion 11 - 12
Floor Systems Analysis
1) Existing Floor System Analysis (Two-way Post-tension Flat Plate)14
2) Two-way Reinforced Concrete Flat Plate With Beams
3) Hollow-core Precast Concrete Plank Floor System
4) Composite Metal Deck on Steel Girders Floor System
Floor Systems Comparison
Conclusion
Appendices
Appendix A - Calculations
1) Existing Floor System Analysis (Two-way Post-tension Flat Plate)28
2) Two-way Reinforced Concrete Flat Plate With Beams
3) Hollow-core Precast Concrete Plank Floor System
4) Composite Metal Deck on Steel Girders Floor System60
Appendix B - Cost Data64 - 71

#### EXECUTIVE SUMMARY:

#### Purpose

An investigation on alternative floor systems aside from the existing two-way posttension flat plate concrete system of Ingleside at King Farm was made in this report. Three alternative systems were studied:

- 1) Two-Way Flat Plate with Reinforced Interior and Exterior Beams
- 2) Hollow Core Planks on Steel Girders
- 3) Composite Metal Deck on Steel Girders

#### Analysis

For the analysis of each floor system, design criteria and serviceability issues were addressed. These factors include cost, floor depth, system weight, deflection, fireproofing, impact on existing architectural and column layout, vibration, accoustics, and constructability.

A typical bay was chosen in one section of the building for simplification of analysis using hand calculations, structural theories, and design charts. Efforts were made to preserve the existing column layout, and any changes to the location of columns were kept to a minimum of 10 percent offset.

#### Results

The design criteria found for each floor system were compared with each other to determine its feasibility for further investigation. It seems that the existing system is the superior choice among the systems that were analyzed. The existing post-tension system preformed better than the three alternative systems in many of the categories. It was most predominate in deflection control, structural depth, cost, most flexible in terms of the building's floor geometry, time wise to construct, and in preserving the existing architectural plans and structural system.

Further investigation topics on the two-way concrete systems include polymer fiber reinforcements, and ways to improve the shear capacity and decrease its construction time even more. As for hollow-core precast planks, the system is the most expensive, and least flexible of the four systems that were analyzed; and thus will be further studied. The composite system does offer some possibilities, and pulturded shapes may be studied for its higher strength and comparable cost to that of steel. Vibration is an associated issue with the use of light weight systems, and various damping techniques and construction can investigated with this composite system. In addition, column elements were not analyzed in this report, but will be in the next report for lateral resistance. A staggered truss system or an exterior load bearing system (possibly tubular steel frame) is likely to be used in conjunction with the feasible systems analyzed in this report.

#### INTRODUCTION

This pro-con structural study report examines the existing floor system of Ingleside at King Farm and three alternative floor systems. The existing floor system is primary a post-tension two-way flat plate system. Several alternative systems that were analyzed and compared with the existing system were reinforced concrete two-way flat plate with concrete beams, hollow core precast concrete panels on steel girders, and composite metal deck on steel girders. Gravity loads determined in technical report one were used to design the alternative floor systems, along with their respective self weight of the building materials used. Criteria to address and compared with for the floor systems include cost, system weight, floor depth, constructability, fire proofing, construction time, vibrations, and its impact on the existing architecture and structural layout.

There are four expansion joints built into the building. The primary reasons for these expansion joints are due to the shrinkage of the concrete, reduce the amount of strength lost caused by the relaxation in the tendons, and to maintain a continuous construction schedule by preventing idle time; while the concrete in one section of the building is curing, the formwork and layout of reinforcements or concrete placement may be possible in another building section. A majority of the structural analysis and floor system design was done in section one of the building. Section one of the building has a more regular column grid than the other sections. See **Figure 1** for the section divisions of the entire building, which has an approximate floor area of 790,000 square feet.





#### EXISTING STRUCTURAL SYSTEM

#### Foundation

The sub level of the building is mainly used as a parking garage and contains most of the building's mechanical rooms. The loads from above are transferred down by 30" x 18" reinforced concrete columns with 10 #8 bars to spread footings. Beneath the spread footings is 3 feet of compact fill and then soil with a bearing capacity of 50 ksf. The 30" x 18" reinforced columns extends all the way to either the 6<sup>th</sup> or 7<sup>th</sup> floor. The structural slab in the foundation and sub level parking garage is a 5" concrete slab on grade reinforced with 6" x 6" W2.9 / W2.9 welded wire fabric over a vapor barrier and a 4" porous fill. It utilizes standard weight concrete with a 28 day minimum compressive strength of 4000 psi.

#### Typical Floor Frame

Ingleside at King Farm's primary structural system is a two-way flat plate post-tension concrete structure with 270 ksi unbonded  $\frac{1}{2}$  diameter 7 wire tendons. The post-tension concrete slabs are 8 inches thick for typical floors with a compressive strength of 4500 psi. All Concrete used in this building's construction is normal weight. There are no drop panels or beams supporting these typical slabs. The only drop panels in the building are found on the sub level columns holding up the 12 inch thick slab (f'c=6000 psi) that is supporting the weight of the court yard, and the 6<sup>th</sup> floor columns supporting the 7<sup>th</sup> floor loads due to the offset W 8 x 31 wide flange columns found on the 7<sup>th</sup> floor. All the drop panels are 5' x 5' x 10".

Due to the irregular column gird of the building, bays range from 15 feet to 29.5 feet. For the analysis of alternative floor systems, a bay area of  $30' \times 30'$  is utilized for a more conservative design, which is the typical interior bay area for the building.

#### Lateral System

Ingleside at King Farm has eleven shear walls to resist lateral loads from the sub level up to the 7<sup>th</sup> floor. Seven of the walls are ordinary reinforced concrete shear walls located at stairwells and elevator shafts with #4 horizontal reinforcing bars and #8 vertical reinforcing bars. Typical spacing of these bars is 12 inches. All these walls have a compressive strength of 5000 psi. The remaining four reinforced concrete shear walls have boundary elements and are 15 feet in length; two in east/west direction and two in north/south direction. Spacing of vertical and horizontal reinforcements is 30 inches and 12 inches respectively. Typical clear cover is 1  $\frac{1}{2}$  inches for the reinforcements.

On the 7<sup>th</sup> floor, in addition to the shear walls, there are also moment connections to resist the lateral loads. Based on lateral load analysis in technical report one, it was discovered that the loads were largest at the 7<sup>th</sup> floor roof line. Thus, these moment connections (framed seated beam connection) justify the high wind loads that were calculated in technical report one.

#### Columns

The building contains over 140 reinforced columns, which are either 18" x 30" or 12" x 30". Due to the building's irregular column grid, some columns are miss-counted for in the column schedule. These reinforced concrete columns extend from the sub level to the  $6^{th}$  floor.

All 7<sup>th</sup> floor columns are W 8 x 31 steel rolled. There are approximately 152 of these steel columns and 33 of them are offset from the concrete reinforced concrete columns below. Thus, 5' x 5' x 10" drop panels are present on the 6<sup>th</sup> floor to aid with the load transfer and punching shear resistance for the offset columns.

The column schedule also does not account for the  $6" \times 6" \times 3/8"$  steel tubular columns that are located in section two of the building where a majority of the public areas are found. These HSS columns support the gravity loads of areas whose roof line is at the first floor and second floor level.

#### Other Structural Elements

Several structural elements that have not been analyzed for this report, but they will be at a later time. They include structural components for the canopies, building envelope supports and load paths into the structural slabs, the steel joists and tubular steel members supporting the roof and roof up lift. An analysis of these structural members for structural strength and serviceability shall be done for the future, and as well as how the various systems work together. Figure 2: Existing structure with Structural Elements Highlighted - West



#### Figure 3: Existing structure with Structural Elements Highlighted - Center



#### Figure 4: Existing structure with Structural Elements Highlighted - East



### CODES AND STANDARDS

Codes and Standards in Original	Codes and Standards used for this
Design	Report
IBC 2003	International Building Code 2006
ASCE 7-98: Minimum Design Loads For	American Institute of Steel Construction
Buildings and other Structures.	13 <sup>th</sup> Edition
Rockville, MD City Codes: Local	ASCE 7-05: Minimum Design Loads For
amendments	Buildings and other Structures.
	American Concrete Institute: Building
	Code Requirements for Structural
	Concrete 318 - 05
	Post-Tensioning Institute (PTI) 1 <sup>st</sup> edition

#### MATERIAL STRENGTH SUMMARY

Structural Steel	
Wide Flange Shapes	Fy= 50 ksi
Hollow Structural Steel (HSS)	Fy=46 ksi
Anchor Rods	Fy=55 ksi
Channels	Fy=36 ksi
Angles	Fy=36 ksi
Concrete	
Structural Slab Supporting Court Yard	F' <sub>c</sub> = 6000 psi, Normal wt.
Slab on Grade/Foundation	F' <sub>c</sub> = 4000 psi, Normal wt.
Floor Slab	F' <sub>c</sub> = 4500 psi, Normal wt.
Cast-in-place Columns	F' <sub>c</sub> = 5000 psi, Normal wt.
Cast-in-place Walls	F' <sub>c</sub> = 5000 psi, Normal wt.
Shear Walls	F' <sub>c</sub> = 5000 psi, Normal wt.
Reinforcements	
Deformed Bars	ASTM A615, Fy=60 ksi
Welded Wire Fabric	ASTM A18, Fy=70 ksi
Post-Tension Tendons	ASTM A-416-74, 270 ksi

#### **BUILDING DESIGN LOAD DISCUSSION:**

#### Gravity Loads

Static and dynamic loads acting on the building were determined in order to analyze the structural behavior of the building. Information regarding the building's weight, code compliant loadings and material specifications were provided and referenced from the construction documents, specifications, AISC 13<sup>th</sup> edition, ASCE 7 - 05, and IBC 2006. The table below summarizes the type of gravity loads and the system it applies to.

Floor System Loads				
Load Type	Material / Usage		Reference	
	Normal Weight Concrete	150 pcf	ACS 318	
Cold-formed, light gauge steel stud wallsDeadwith insulation and 5/8" gypsum board		5 psf	WDG	
Load	Brick Masonry	40 psf	AISC 13th ed.	
Partition Walls		15 psf	Engineer's Judgment	
	Miscellaneous	10 psf	Engineer's Judgment	
Lobbies and Common Spaces		100 psf	ASCE 7 - 05	
	Theater Stage		ASCE 7 - 05	
	Corridors		ASCE 7 - 05	
Live	Living Units	40 psf	ASCE 7 - 05	
Loau	Balconies	60 psf	ASCE 7 - 05	
	Parking Garage	40 psf	ASCE 7 - 05	
	Retail Spaces	100 psf	ASCE 7 - 05	

Roof and Terrace System Loads				
Load Type	Material / Usage	Load	Reference	
	Normal Weight Concrete	150 pcf	ACS 318	
	Steel	by shape	AISC 13th ed.	
Dead	Steel Deck	2 psf	USD	
Load	Green Roof	100 psf	ASCE 7 - 05	
	Ballast, insulation, and waterproofing membrane		AISC 13th ed.	
	Miscellaneous (MEP, Ceilings, etc)	15 psf	Engineer's Judgment	
Line	Assembly Spaces		ASCE 7 - 05	
Live	Roof	30 psf	ASCE 7 - 05	
Ground Snow Load		25 psf	ASCE 7 - 05 & IBC 2006	
	Terrain Category		ASCE 7 - 05 & IBC 2006	
Snow	Ce Exposure		ASCE 7 - 05 & IBC 2006	
Show	Ct Thermal Factor	1	ASCE 7 - 05 & IBC 2006	
	Importance Factor	1	ASCE 7 - 05 & IBC 2006	
	Flat Roof Snow	17.5 psf	ASCE 7 - 05 & IBC 2006	

The miscellaneous gravity loads consist of lighting, plumbing, telecommunication, ACT, ductwork and anything that is not regarded as a live load. Because the building's roof is a mansard roof, snow drift will accumulate in the lower flat roof areas. The drift loads are not determined for this report, but will be for the analysis and design of the lateral system.

#### FLOOR SYSTEMS ANAYLSIS

The gross square footage of each floor level above grade is approximately 480,500 SF. Due to the massive size of the building and its irregular column grid, a small portion of the building was chosen for analysis and treated as a typical bay based on its column grid regularity, number of bays, and max span. The interior columns of **Frame B** is offset within less than 10 percent of the 18 feet span, and hence can be regarded as part of **Frame B** for frame analysis based on ACI code. The portion of the building that was chosen for the computational analysis of the existing floor system is shown in **Figure 5**.



Figure 5: Plan of floor section used for the analysis of the existing system

#### EXISTING FLOOR SYSTEM ANALYSIS (Two-way Post-tension Flat Plate)

The existing floor system, which is a two-way post-tension flat plate, was analyzed to serve as a reference in comparison with the alternative floor systems. The existing floor system design was hand calculated to verify the assumed basic loadings and design criteria with those used by the designer. The design calculations can be found in the Appendices of this report.

The numbers of banded tendons for **Frame B** were calculated to be the same as that specified by the designer, which is (18) tendons each with 7-wire strands. An exterior column of **Frame B**, **Column B1**, was chosen for punching shear analysis due to the nature of having the highest bending moment at the exterior span and support. It had failed in the punching shear analysis based on the calculations. Thus, reinforcement bars were needed.

Comparing the amount of reinforcements calculated with the designer's specifications, there seemed to be adequate top reinforcements for the critical section at **Column B1**. The designer's specified more reinforcements than the calculations had required. This was due to the dead load of the exterior wall system that was not factored into the calculations. If the exterior wall's dead load (brick masonry) was to be included, then the amount of rebar reinforcements calculated may be equivalent to that of the designer's specifications. The dead load from the brick masonry was not accounted for in the analysis of this report. It will be accounted for in future analysis as the transfer of the exterior walls' dead load to the slabs will be studied. The brick masonry does not envelope parts of the building where balconies and window dormers are present.

A computer model of the building's structural system will be made in the future for more accurate design. **Figure 6** compares the designer's structural specifications with the hand calculated design based on the assumed loading scenario.

Advantages and Disadvantages of a Two-way Post-tension Flat Plate System				
Pros	Cons			
<ul> <li>Deflection and vibration control</li> <li>Less floor depth</li> <li>Crack control</li> <li>Allows for the placement of columns in an irregular grid</li> <li>Flexible floor design (geometry wise)</li> <li>Reduced amount of steel reinforcements</li> <li>Increase of construction speed</li> <li>2 hour fire rating</li> </ul>	<ul> <li>Large amount of formwork</li> <li>High labor cost for tendons layout</li> </ul>			

#### Figure 6: Existing system - comparison of calculated designed VS Designer's



Note: Figures are not shown to scale

#### TWO-WAY REINFORCED CONCRETE FLATE PLATE WITH CONCRETE BEAMS

The same floor section used to analyze the existing floor system is used to analyze this alternative system. Instead of post-tension, it will utilize rebar reinforcements and concrete beams in order to give the floor slab more shear resistant. As shown in the calculations for the existing system, punching shear is a major issue around the columns, especially exterior columns. With the interior and edge beams, it will minimize the amount of reinforcements required for shear. However, based on the analysis and calculations, shear reinforcements is still required for punching shear. That can be solved by increasing the depth of the beams, or by increasing the thickness of the slab. Drop panels may also be used to remedy the shear resistance requirements. The disadvantage of this system is that the alignment of the columns had to adjust for the placement of beams and girders.

with Interior and Exter	rior Beams
Pros	Cons
<ul> <li>Deflection and vibration control</li> <li>Provide more shear capacity for areas around columns</li> <li>Flexible floor design (geometry wise)</li> <li>2 hour fire rating</li> </ul>	Large amount of formwork More steel reinforcements are required Relocation of columns for the placement of beams and girders

Figure 7: Two-way reinforced concrete flat plate with beams



#### HOLLOW-CORE PRECAST CONCRETE PLANK FLOOR SYSTEM

PCI design charts were used along with an altered column grid and girder layout to design this alternative system. The planks will rest on W 12 x 106 girders with 50 ksi strength based on calculations (see appendix). Loads are be transferred by W shape columns, which are not designed in this report. Per PCI 2.2.4, for deck members with 2 inch topping, 15 psf superimposed load, and 40 psf live load; the service load was 55 psf. Depth was not a factor since the largest plank depth listed in the charts is 12 inches, and the minimum story height of Ingleside at King Farm is 10 feet.

The primary design criteria that were used to determine the most efficient member size were the weight of the system, span length, and deflection. Light weight concrete is preferred due to the cost of transporting the materials to the site, and for other advantages such as higher thermal insulation and higher fire rating. As for the span factor, planks' span length of 15, 20, 23, 28, and 29 ft will be used (planks' width is 4 feet). See appendix for design charts. Columns were re-aligned (re-off setting in the north-south direction) for the bays to meet the span length of the panels used. Custom sized planks are needed for the floor areas such as balconies, around floor openings, and window dormers.

Design considerations for this alternative system include moment connections to help transfer lateral loads, and the redesigning of the column grid for the placement of steel girders and columns. This system will help reduce the construction time as curing and form work is not required. However, there is the issue with the geometry of floor sections where window dormers are located, which is the building's perimeter. Thus, custom sizes are required. The hollow planks will also reduce the overall weight of the building system.

Advantages and Disadvantages of Hollow-core Precast Concrete Plank Floor System		
Pros	Cons	
<ul> <li>Building weight reduction</li> <li>Faster construction compared to the existing system</li> <li>No formwork</li> <li>2 hour fire rating</li> </ul>	<ul> <li>Relocation of columns for the placement of beams and girders</li> <li>Custom made shapes for the building's perimeter</li> <li>Shipping cost (high oil prices)</li> <li>Increased floor depth</li> <li>Requires moment connections</li> </ul>	

The next few figures summarize the design of a typical floor using hollow-core precast concrete planks.



#### Figure 8 (a): Precast hollow core planks on steel girders - section one



Figure 8 (b): Precast hollow core planks on steel girders - section two



#### Figure 8 (c): Precast hollow core planks on steel girders - section three

#### COMPOSITE METAL DECK ON STEEL GIRDERS FLOOR SYSTEM

The United Steel Deck Catalog, along with hand calculations were used to determine the deck. The steel members were sized based on live loads and total loads deflection criteria, and were chosen from the AISC Steel Construction Manual 13<sup>th</sup> Edition. The composite action is contributed by <sup>3</sup>/<sub>4</sub>" diameter shear studs. The column gird used for the Hollow-core Precast Plank system was used for the design of this floor system as well.

This composite system is simple to construct, light weight, and shallow. However, moment frames would be required to help transfer lateral loads and will likely to increase cost of materials. In addition, a large amount of shear studs are required resulting in an increase cost in labor hours.

A possible solution is to utilize a staggered truss system in which the amount of columns and moment connections could be reduced, and would result in longer bay spans. However, it would greatly impact the architectural plan of the building in which the trusses will have to cut through certain rooms, or partition walls would have to be relocated.

As for construction, formwork and cure time may not be needed, but additional labor cost, transportation cost, and the lead time due to mill procedures would be the disadvantages.

Advantages and Disadvantages of a Composite Steel and Metal Deck Floor System			
Pros	Cons		
<ul> <li>Building weight reduction</li> <li>Simple Construction</li> <li>Faster construction compared to the existing system</li> <li>No formwork</li> <li>2 hour fire rating with spray on fire proofing</li> </ul>	<ul> <li>Relocation of columns for the placement of beams and girders</li> <li>Shipping cost (high oil prices)</li> <li>Long lead time due to shapes being rolled and shipped from the mill</li> <li>Requires moment connections</li> <li>Additional depth due to the girders</li> </ul>		

#### Figure 9: Composite metal deck on steel girders



#### FLOOR SYSTEMS COMPARISON

	System 1 (existing)	System 2	System 3	System 4
Issues to Address	Two-way Post- tension Flat Plate	Reinforced Concrete Two- way Flat Plate With Beams	Precast Hollow Core Planks on Steel Girders	Composite Metal Deck on Steel Girders
Cost	\$17.18/sq ft	\$19.95/sq ft	\$23.88/sq ft	\$19.35/sq ft
Floor Depth	8"	8" on 12" deep beams	6" slab with 2" topping on 12" girders	4.5" slab on deck, on 18" girders
System Weight	150 psf	150 psf	74 psf	34 psf
Architecture Plan Impact	None	None	None (Yes if used with a staggered truss system)	None (Yes if used with a staggered truss system)
Existing Column Grid Impact	None	Significant	Some	Significant
Fire Rating	2 hour	2 hour	2 hour (Spray on)	2 hour (Spray on)
Deflection	Little	Little	Medium	high
Vibration and Accoustics	Little to None	Little	Little	Medium to High
Construction Difficulty	Hard	Medium	Easy	Easy
Lead Time	Short	Short	Medium	Long
Further Investigation	Absolutely	Maybe	No	Yes

#### Comparison Criteria

When comparing the four floor systems, criteria of each system that were analyzed includes cost, floor depth, system's weight, its impact on existing architectural plans and column grid, fire rating, vibration, construction difficulty, deflection, and lead time.

#### Cost

The main reference for the cost comparison was made using RS Means Assemblies 2009 data. The cost data indicated in the comparison table is based on a typical 30' x 30' bay. The cheapest system is the existing post tension system as less steel reinforcements are needed, and less building material due to a thinner floor depth. The most expensive is the precast hollow core planks system, which does not account for custom made shapes. Thus, using precast hollow core planks is out of the question.

#### Depth

The average floor depth for the alternative systems, which includes the depth of the supporting beams and girders are 20 inches. Ingleside at King Farm is a mixed used building with most of its commercial areas on the first floor, which is about 14 feet in height. The typical residential floor height is 10 feet. If the other alternative systems are used, the average 20" will greatly dwarf the height of the residential floors. A majority of the residential apartments are high priced suites and condos. Thus, the existing system is the superior choice.

#### Weight

The major factor in determining the weight each floor system is its thickness and material. Precast hollow planks and composite metal deck offers the lightest weight. However, the weight of a system will also affect the accoustical and vibration performances of a building.

#### Fireproofing

Ingleside is a mixed-use building. Thus, a 2-hour fire rating is the typical requirement for such construction type. The three alternative systems were initially chosen based on fireproofing requirements. While the Precast core planks and composite metal deck offers fireproofing, the steel girders they rest on does not. Spray on fireproofing is cost effective, but it is not environment friendly. Yet a steel system does compose more recycled components. A composite steel and concrete encased system is a possible further investigation if the composite metal deck is to be considered.

#### Layout Changes

Due to the utilization of beams and girders, the three alternative systems will require that the columns be relocated or additional columns are needed. This will result in the changes of the architectural plans. Thus, the existing system offers a more flexable structural floor design. In addition, the window dormers also contribute to the un-uniform perimeter of the building. Any precast systems will have to be custom made or manually adjusted.

#### Lead Time

Although the project is not fast track, time is still a considerable factor as it affects cost, such as the rental of cranes and other equipments. Unlike cast in place system, the composite steel system may acquire lead time for the shipment of materials from the mill. This also includes the hollow core planks as custom sizes are required. In addition, approximately 90% of the condos are sold out, and the date of completion is delayed. Systems that require more lead time will result in more unhappy clients/owners.

#### Deflection

The two-way concrete flat-plate systems offer the best deflection control. Ingleside being a mixed-use building, design loads cannot be 100 percent certain. A typical floor construction of a typical thickness and typical amount of reinforcements may offer great serviceability in one section of the building, but not another that is of public usage on the same floor. Having to deal with numerous member sizes and construction details on the same floor may affect the speed and cost of construction and labor.

#### Accoustics/Vibrations

Although accoustics and vibrations were not analyzed in depth in this report, the performance of the floor systems in these two areas can be predicted or categorized based on the stiffness of the structure and its weight. The denser and heavier a structural element is, the less sound energy it will be conducted or transferred by the material, and stiffer structural components will also help dampen the transfer of sounds. The concrete systems are likely to be the most affective systems in dealing with accoustical and vibration performances. Numerical statistics shall be obtained from models or calculations if the structural system is to be further investigated.

#### CONCLUSION

The evaluation of the feasibility of the floor systems was based on multiply factors. After careful analysis, it appears that the existing two-way post-tension flat plate is the best floor system of choice. Rockville is within proximity of Washington DC. Thus, a concrete system was the choice the designers made. Due to the un-uniform perimeter of the floor, a cast in place system was selected. Any precast systems will require additional changes or custom made components, and connections will complicate the cost of material and labor. The post-tension aspect of the system reduced the amount of long term creep and deflections. Disadvantages with the existing system are the shear capacity, and the affect of pre-stress lost due to time and shrinkage. If further investigation is decided for this system, a study on possible solutions for the system's disadvantages is possible.

Composite Steel is another viable option. The geometry is not as flexible as the twoway flat-plat concrete systems. It also requires a more regular aligned column grid, connections, and solutions to limit serviceability issues such as creep, deflection, accoustics, and vibrations. If further investigation is decided for this system, a study on staggered truss system and pultrusion polymer shapes or light gage is possible. A staggered truss system will reduce the amount of required columns and allows for longer spans.

The reinforced concrete two-way flat plate system with interior and exterior concrete beams is very much like the existing system. Its most apparent difference is the higher shear capacity, and the greater amount of steel reinforcements used. A possible topic for further investigation with this floor system includes the usage of polymer fiber reinforcements in place of the steel.

### APPENDIX A: CALCULATIONS

Stephen Dung Tat The Pennsylvania Stat Architectural Enginee	te University ring	Thesis: Ingleside at King Farm	
LOADS :			
FRAMING PARTITION SUPERIMI LIVE LOAI	DEAD LOAD = SELF 1 WAILS = 15 POSED D.L. = 10 D = 40	EWEIGHT PSF PSF (MIE, misc.) PSF (RESIDENTIAL)	<b>第</b> 5
MATERIALS	<u>, ;</u>		
CONCRETE	: NORMAL WEIGHT	150 PCF	
	$f_{c_1} = 4,500 PSi$ $f_{c_1} = 3,000 PSi$		
REBAR :	Fy = 60,000 Ps	i	
PT :	UNBONDED TENDO $1/2 \phi$ , 7 wire $f_{pu} = 270 \text{ ksi}$ Estimated prestre	ons strands, Aps = 0.153 in <sup>2</sup> ass Losses = 15 ksi (ACI 18.6) as starte f = 0.2 (200 kci) - 15 h	in bei (Arijori
	EFFECTIVE FURCE	$P_{eff} = A \cdot f_{se} = (0.153)(174 \text{ Ksi}) =$	151 = 174 KSI (ACI 18.5.1) 26.6 Kips Hendon
DETERMIN	VE PRELIMINARY	SLAB THICKNESS	
L/h = : LONGES	45 T SPAN = 29'		
h = (	<sup>'</sup> 29') <i>[12"] / 45 = 7</i>	7.73"	
	· USE 8.	O" SLAB THICKNESS	

Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm			
LOADING				
D.L. = SELFWEIGHT = 8"(150 PCF) = 100 PSF SI.D.L. & PARTITION WALLS = 25 PSF LLO = 40 PSF				
IBC 2006, 1607.9.1 allows	for LL reduction			
EXTERIOR BAY : AT KLL =	$= (20')(29') = 580 \text{ fl}^{2}$ = 1 = LLo $\left(0.25 + \frac{15}{\sqrt{1 \times 580}}\right) = LLo \left(\frac{5}{\sqrt{1 \times 580}}\right)$ = 35 PSf	(0.873)		
INTERIOR BAY: AT KLL LL	$= (20')(29') = 580 \text{ H}^2$ = 1 = 35 Psf			
DESIGN OF SOUTH-NORTH	INTERIOR FRAME (FRAME B	)		
· USE EQUIVALENT FRAM	E METHOD, ACI 13,7 (EXCLUDIN	14 13.7.7.7.4-5)		
LL/DL = 35/125	= 0.28 < 3/4			
. NO PATTER	RN LOADING REQUIRED (A.C.I.	13.7.6)		
· CALCULATE SECTION PR	OPERTIES			
TWO-WAY SLAB MUST GROSS CROSS-SECTION	BE DESIGNED AS CLASS U AL PROPERTIES ALLOWED (ACI	(ACI 18.3.3) 18.3.4)		
A=bh=(14.75')(12")(8")= 1896 in2				
S = <u>(19.75)(12")(8"</u> 6	$2^{2} = 2528 in^{3}$			
• IGNORE COLUMN STIFFA OF HAND CALCULATIONS	NESS IN EQUATIONS FOR SIMPLI	сіту		

Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm	
· SET DESIGN PARAMETE	RS	
ALLOWABLE STRESSES :	CLASS U (ACI 18.3.3)	
AT TIME OF JACKIN F'c; COMPRESSION TENSION	$WGr (ACI 18.4.1) = 3,000 Psi = 0.60(f'c_i) = 0.6(3,000) = 1, = 3\sqrt{f'c_i} = 3\sqrt{3000} = 164 Psi$	800 PSi
AT SERVICE LOADS f'c COMPRESSION TENSION	$(A(I \ 18.4.7 (a) and \ 18.3.3)) = 4,500 \ Psi = 0.45 fc = 0.45 (4500) = - = $	2025 PSi Psi
AVERAGE PRECOMPRE	SSION LIMITS :	
P/A = 125 PS = 300 PS	і тіп. (ACI 18.12.4) і мах.	
TARGET LOAD BALANCE CODES DO NOT PRESC BUT WILL NEED TO LIMIT SLAB DEFLECT	ES : CRIBE LIMITATIONS FOR THESE DESIGN TO APPROPRIATE BAIANCI TIONS AND CRACKING.	PERCENTAGES, ING LOADS TO
COMMON LOAD-BALAN TO 80- PERCENT RAN	ICING PERCENTAGES ARE IN TH NGE AND IS KEPT CONSISTENT	IE 65-PERCENT BENTEEN SPANS.
AVERAGE OF 65-1 FOR SLABS SHALL	PERCENT OF DEAD LOAD (SELF BE USED IN THIS CALCULA	WEIGHT) TION.
0,65 WAL = 0.651	(100 PSF) = 65 PSF	



Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm	
• CHECK PRECOMPRESSION AU • DETERMINE NUMBER OF # TENDONS = 431.8 = 16.23	LLOWANCE TENDONS TO ACHIEVE 431.8 K / (26.6 K/TENDON)	
ACTUAL FORCE FOR PACTUAL = 16 (26.	BANDED TENDONS 6 k) = 425.6 K	8
· BALANCED LOAD FOR $W_{b_{ENDSHIM}} = (425, 6/43)$ · DETERMINE ACTUAL F PACTUAL /A = (425)	THE END SPAN ADJUSTED 1.8)(1.28K/H) = 0.77K/H - PRECOMPRESSION STRESS 5.6)(1000)/(1896 in <sup>2</sup> ) = 224	1. 42 .4 psi
2 2 4.4 >1	25 psi min V 300 psi max V	
<ul> <li>CHECK INTERIOR SPAN F</li> <li>P = (1.28*4+)/28-</li> <li>= 250.8 &lt; 424</li> </ul>	ORCE H)²/[8(6"/12")] 5.6 k ok√	
LESS FORCE IS /	REQUIRED IN THE CENTER BA	Y \$607 - 7 40
$W_6 / W_{0L} = \frac{2 \cdot 1^2}{1.975} = 109$	"Acceptable	<u>'H</u>
Peff = 425 Kip	5	
WEAVER = (WE END SPAN + W	6 INT SPAN + WE END SPAN) /3	5

Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm	
FRAME B:		
· DEAD LOAD MOMENTS WpL = 125 PSF (19.75)/1000	= 2,5 K/H	
W/2 W/2		
24		
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	2.5	
175.2" 145.2" 165.3" 165	3"× 175.2"K	
87.6 in 81.7 1K	87.6'K	
· LIVE LOAD MOMENTS WLL = 35 PSF(19.75')/1000	= 0.70 ×/4t	
	111 0.70 V V V T	
29' 28'	29	
49 49 45.3** 45.	1 45.9 <sup>10</sup> 44 <sup>10</sup>	
24.5'* 22.9'*	~ 24.5 <sup>104</sup>	
END SPAN MIT. SPAN	END SPAN	



Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm	
STAGE 1 : STRESSES IMMEDIATEL	Y AFTER JACKING (DL+PT) (ACI 18.	4.1)
· MID SPAN STRESSES	1 51	
$f_{top} = (-M_{DL} + M_{bal}),$ $f_{bot} = (+M_{DL} + M_{bal}),$	ls - P / A ls - P / A	
· INTERIOR SPAN		
Ftop = [1-81.7 + 3	30.7)(12)(1000)]/2560 -224.5	
= -463.5 P	SI (COMP.) < 0.60 fii = 1805	Psi ok V
foot = [(81.7 - 3	30.7)(12000)]/2560 - 224.5	
= 14,6 PSI	(TENSION) < 0.60 fci = 1800 Pri	ok V
- END SPAN		
flop = [(-87.6 +	32.9)(12000)]/2560-224.5	
= -480.9 F	>51 (comP.) < 0.60fci = 1800 lsi	ok
foot = [ (37-6-3	32.9)(12000)]/2560 - 224.5	
= 31.9 PSI	(TENSION) < 0.60 fc; = 1800 F	Bi ok
<ul> <li>SUPPORT STRESSES ftop = (+ MoL - Mbal)/ fbot = (- MoL + Mbal),         </li> </ul>	15 - P/A 15 - P/A	
· INTERIOR SPAN		
Ftop = [ (165.3 -	61.4)(12000)]/2560-224.5	
= 262.6 PSI	(TENSION) > 3 JFC = 164 PSi	NGX
· TRY INC	CREASING # OF TENDONS TO	18

Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm	
TRIAL 2 : USE 18 TENDO	INS (BANDED)	0
· PACTUAL = 18(26.6 K) =	= 478.8 K	
· BALANCE LOAD FOR END	SPAN	
WE END SPAN = (478.8) ADJUSTED	(431.1)(1.28 K/ft) = 1.42 K/ft	
WE MID SPAN = (478.8) ADJUSTED	(8) (6"/12")/28-11)" = 2.44 ×14	ict
TOTAL BALANCING MOMENTS $W_{6AVG} = [2(1.42) + 2.$	Mbal 44]/3 = 1.96 K/ff	
1.76 1.76 1.76 1.76 F + + + + + + + + + + + + + + + + + + +	1.76 111 1.76 1	
61.7 57.5	61.7 123.3 123.3	i.
P/A = 478.8/1896	= 252.5 PSi	

Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm	
STAGE 1 : STRESSES IMMEDI	ATELY AFTER JACKING (OL+PT,	)(ACI 18.4.1)
- MID SPAN STRESSES		
$f_{top} = (-M_{PL} + M_{bal})$ $f_{bot} = (+M_{DL} + M_{bal})$	)/s - P/A	
· INTERLOR SPAN		
ftop = [[-81.7+	57.5)(12000)]/2560 - 252.5	
= -365.9 PS	si (comp.) < 0.60 fti = 1800,	Psi ok V
foot = [ (81.7 -	57.5)(12000)]/2560-252.	5
= -139.1 PSI	(comp.) < 0.60 fci = 1800 P.	si ok V
· END SPAN		
-Stop = [ [-87,6-	+ 61.7)(12000)]/2560 - 252.5	
= -373.9 P	SI (Comp) < 0.60 tèi = 1800	Psi ok V
fbd = [137.6-6	(1.7)(12000)]/2566 - 252.5	
= - 131.1 PSI	(comp) < 0.60 fc; = 18001	Psi OK V
- SUPPORT STRESSES Ftop = (+ MOL - Mbal)/ fbol = (- MOL + Mbal)/	's - P/A 's - P/A	14. 
· INTERIOR SPAN		
ftop = [[165.3-11]	5)(12000)]/2560 - 252.5	
= - 16.75 /	(comp) < 3 \Fci = 164 Psi	ck V
fbot = [(-165.3+	115) (12000)]/2560 - 252.5	
= -488.3 (0	comp) < 0.60 fc; = 1800 PS;	ok V

Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm	
* END SPAN		
ftop = [175.2-	123.3)(12000)]/2560 -257.5	
= -9.25 /	$PSI (COMP) < 3\sqrt{f_{i}} = 164 P$	PSI OKV
fsot = [ (-175.2	+123.3)(12000)]/2560-252.	.5
= -373.9	PSI (LOMP) < 0.6 fc; = 1800	PSI ok
STAGE 2 : STRESSES AT SERV	NLE LOAD (OL + LL + PT) (ACI 18.5	5.3 and 17.4.2)
= MID SPAN STRESSES ftop = (-MOL - MLL + fbd = (+MOL + MLL -	Mbul) /s - P/A Mbal) /s - P/A	
. INTERIOR SP.	AN	
ftop = [(-81.3	9-22.9+57.5)(12000)]/2560-25	2.5
= -473.3	s PSI (COMP) < 0.45 F'C = 225	OPSI OK
foot = [ (81.	7 + 22.9 - 57.5) (12000)] /2560 -	252.5
= -31.75	5 PSI (COMP) < 6 JFC = 424	PSI OK V
· END SPAN		
ftop = [(- 8;	7.6 - 24.5 + 61.7)(12000)] /2560	-252.5
= -488.	8 PSI (comp) < 0.45 fc = 22	50 PSI OKV
$f_{bot} = [(87.$	6+24.5-61.7)[12000)]/2560	-252.5
= -16.3	$PSI(amp) < 6\sqrt{f'c} = 4241$	PSI OKV

Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm	
• SUPPORT STRESSES $f_{top} = (+M_{PL} + M_{LL} - M_{b})$ $f_{bot} = (-M_{DL} - M_{LL} + M_{b})$	(A)/S - P/A (AL)/S - P/A	
- INTERIOR SPI	AN	
flap = [(165.3+	45.7-115)/12000)]/2566-25	7.5
= 197.5 P	SI (TEN.) < 65FC = 424 PSI	OK /
foot = [ (-165.:	5 - 45.7 + 115)(12000)]/2560 - 2	57.5
= -702.5	PSI (comP.) < 0.45 fc = 2250	PSI OK
- END SPAN		
-ftop = [ (175.2	+ 49-123.3) (12000)]/2560-2	52.5
= 220.4	PSI (TEN.) < 6 VFC = 424 P)	si ok V
fbot = [(-175.	2-49+123.3)(12000)]/2560-	252.5
= -488.8	PSI (COMP.) < 0.45fc = 2250	PSI OK
54 104 - 102	82265 82 1825	
: ALL STRESSES ARE	JITHIN THE PERMISSIBLE C	CODE LIMITS,
-		
c		

Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm	
ULTIMATE STRENGTH		
PRIMARY POST-TEN	SIONING MOMENTS	
$M_{i} = P(e)$		
e = 0 " at the	erterior support	
e = 3.0" at th	se interior support (NA. to the c	inter of ten din)
M,= (478.8 K)(3	in)/12 = 119.7 1K	
SECONDARY POST - 7	ENSIGNING MOMENTS	
Msec = Mbal - MI		
= /23.3 - 0	= 123.3 at interior supports	
5. <sub>15</sub>		
THE TYPICAL LOAD DESIGN IS :	COMBINATION FOR ULTIMATE STR	ENG-714
Mu = 1.2 Mor +	1.6 MLL + 1.0 Msec	9
AT MIDSPAN =	Mu = 1.7 (87.6) + 1.6 (74.5) +1.	0(-61.7) = 82.61K
AT SUPPORT =	Mu=1.2(-175.2) +1.6(-49)+1.1	o (123.3) = -165.3 "K



Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm	
FOR PUNCHING SHEAR :		
Wu = 1.2 (125 PSF) + 1.6 1	35 PSf) = 0.206 K/ff	
Vu = Wu × Aven		
Vu = 0.206 K/H [(19.95	× 21/2) - (18"×30")(++)]	
Vu = 58.22 "K		
$M_{u(support)} = -165.3$ <sup>(K)</sup>		
$ \frac{V_{u}}{A_{c}} + \frac{V_{v}}{J_{c}} \frac{M_{u}}{M_{u}} + \frac{V_{v}}{J_{c}} \frac{M_{u}}{J_{c}} + \frac{V_{u}}{A_{c}} + \frac{V_{v}}{J_{c}} \frac{M_{u}}{J_{c}} + \frac$	$\frac{f_{4}}{f_{4}} = \frac{58.22}{1008.64} \frac{(1000)}{f_{4}} + \frac{0.337}{43570} \frac{(-165.33)}{43570} + \frac{0.337}{1008.64} + \frac{0.337}{435} \frac{(-165.33)}{435}$	3)(21.2)(12000) 3)(2.85)(12000) 70
V4 = 57.72 + (-3 57.72 + (-43, Max	25.3) = -267.5 < yourns .7) = 13.99	
bo = (2C, +C2 + do	$) = (2 \times 18 + 30 + 6, 4) = 72.4$	' <sup>''</sup>
as = 30 for edge col	usence	
Be = 30/18 = 1.667		

Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm	
$U_{c} = \begin{pmatrix} 2 + \frac{4}{B_{c}} \end{pmatrix} \sqrt{fc} = \\ (2 + \frac{\sigma_{s} d_{o}}{\delta_{o}}) \sqrt{fc} = \\ 4 \sqrt{fc} \leq 3^{o} \\ \text{Smallest} \end{cases}$	4.399√fc 4.652√fc verns (fc = 4500 PSi)	
$\mathcal{V}_{c} = 4\sqrt{4500^{7}} = 268.3$		
$\phi v_c = 0.95(268.3) =$	201. Z PSI	
Uu = 267.5 > 201	1.2	
: NG, FAI	L IN PUNCHING SHEAR (Due ?	MOMENT)
SOLUTIONS :		
- USE DROP PANEL - USE REINFORCEME	NTS	
- INCREASE SLAB THIC	(KNESS	
- ADD EDGE BEAM		
- INCREASE LARGER	CRITCAL SECTION	



DEFIEINAL AND DEFIECTION IS INDUCED UNDER DEAD LOAD ECCAUSE OF LOAD EALANCING. As SLAB IS LEVEL, NO ADDITIONAL LOAGE TERM DEFLECTION SHOULD THE ORE TICALLY BE RECORDED. ESTIMATE ELASTIC DEFLECTION DUE TO LIVE LOAD $\left( \Delta i \right) = K \frac{dM_{H}}{E_{L}h^{2}} \qquad \int_{a} = longer spon of ponel center to conter \left( \Delta i \right) = K \frac{dM_{H}}{E_{L}h^{2}} \qquad \int_{a} = longer spon of ponel center to conter \left( \Delta i \right) = K \frac{dM_{H}}{E_{L}h^{2}} \qquad \int_{a} L = longer spon of ponel center to conter \left( \Delta i \right) = K \frac{dM_{H}}{E_{L}h^{2}} \qquad \int_{a} L = longer spon of ponel center to conter \left( \Delta i \right) = K \frac{dM_{H}}{E_{L}h^{2}} \qquad \int_{a} L = longer spon of ponel center to conter \left( \Delta i \right) = \frac{1}{2} \int_{a} L = longer spon of ponel center to conter \left( \Delta i \right) = \frac{1}{2} \int_{a} L = longer spon of ponel center to conter \left( \Delta i \right) = \frac{1}{2} \int_{a} L = longer spon of ponel center to conter \left( \Delta i \right) = \frac{1}{2} \int_{a} L = longer spon of ponel center to conter \left( \Delta i \right) = \frac{1}{2} \int_{a} L = longer spon of ponel center to conter \left( \Delta i \right) = \frac{1}{2} \int_{a} L = longer spon of ponel center to conter \left( \Delta i \right) = \frac{1}{2} \int_{a} L = longer spon of ponel center to conter \left( \Delta i \right) = \frac{1}{2} \int_{a} L = longer spon of ponel center to conter \left( \Delta i \right) = \frac{1}{2} \int_{a} L = longer spon of ponel center to conter \left( \Delta i \right) = \frac{1}{2} \int_{a} L = longer spon of ponel center to conter \left( \Delta i \right) = \frac{1}{2} \int_{a} L = longer spon of ponel center to conter to conter \left( \Delta i \right) = \frac{1}{2} \int_{a} L = longer spon of ponel center to conter $	Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm	
•No DEFLECTION IS INDUCED UNDER DEAD LOAD BECAUSE OF LOAD EALANCING •A SLAB IS LEVEL, NO ADDITIONAL LONG-TERM DEFLECTION SHOULD THE ORETHLALLY BE RECORDED •ESTIMATE ELASTIC DEFLECTION DUE TO LIVE LOAD $\begin{aligned} L_R = lorger Jpmn of Poncel center do conter (Ai) = K \frac{lol}{K} K = Old (l.S - 0.S \frac{l_A}{l_B}) \\ & in which 1 \le \frac{l_B}{l_B} \le 2 \\ K = Old [1.S - 0.S (\frac{29}{21.S})] \\ K = 0.0908 \\ \frac{l_A}{l_6} = 1.3S = 1 \le 1.5S \le 2  ok \sqrt{2} \\ & in \le \frac{11}{12^n} = 0.243 \text{ Psi} \\ \end{aligned}$	DEFLETION		
As SLAB IS LEVEL, NO ADDITIONAL LONG-TERM DEFLECTION SHOULD THEORETICALLY BE RECORDED ESTIMATE ELASTIC DEFLECTION DUE TO LIVE COAD $ \begin{pmatrix} \Delta_{i} \end{pmatrix} = K \frac{dM_{n}^{4}}{E_{c}h^{2}} \qquad $	NO DEFLECTION IS INDU LOAD BALANCING	UCED UNDER DEAD LOAD BECAUS	SE OF
ESTIMATE ELASTIC DEFLECTION DUE TO LIVE COAD $ \begin{pmatrix} \Delta_{i} \end{pmatrix} = K \frac{ M _{h}^{4}}{E_{c}h^{2}} \qquad $	· AS SLAB IS LEVEL, NO SHOULD THE ORETICA	ADDITIONAL LONG-TERM DEF. ULY BE RECORDED	LECTION
$ \begin{pmatrix} \Delta_{i} \end{pmatrix} = \kappa \frac{\omega l_{n}^{4}}{\varepsilon_{c}h^{2}} \qquad $	· ESTIMATE ELASTIC	DEFLECTION DUE TO LIVE C	040
$in \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \$	$\left(\Delta i\right) = K \frac{\omega l_a^4}{E_c h^3}$	$l_{a} = longer span of panel centK = 0.11 (1.5 - 0.5 \frac{l_{a}}{l_{b}})$	ter to center
$K = 0.11 \left[ \frac{1.5}{5} - 0.5 \left( \frac{27}{21.5} \right) \right]$ $k = 0.0408$ $\frac{1_{A}}{1_{6}} = 1.35 \implies 1 \le 1.35 \le 2  ok \checkmark$ $\omega = 35 \frac{16}{41^{2}} \left( \frac{141}{12^{\circ}} \right)^{2} = 0.243 \text{ psi}$ $= \frac{0.0408 \left( 0.243 \right) \left( \frac{12 \times 24}{12^{\circ}} \right)^{4}}{53,000 \sqrt{4500} \left( 8 \right)^{2}} = 0.165 \text{ in}$	Fie	in which $1 \leq la \leq 2$ lb	
$\frac{l_{k}}{l_{b}} = 1.35 \implies 1 \le 1.35 \le 2  ok \checkmark$ $\omega = 35 \frac{l_{k}}{4t^{2}} \left(\frac{l_{ff}}{l_{2}}\right)^{2} = 0.243 \text{ psi}$ $= \frac{0.0908(0.243)(l_{2}\times24)^{4}}{57,000\sqrt{4500}(8)^{2}} = 0.165 \text{ in}$	K = 0.11 [1.5 - 0.5]	$\left(\frac{2\pi}{21.5}\right)$	
$ \mathcal{W} = 35 \frac{16}{4t^2} \left(\frac{14}{12^{"}}\right)^2 = 0.243 \text{ Psi} $ $ = \frac{0.0908(0.243)(12\times24)^4}{57,000\sqrt{4500}(8)^3} = 0.165 \text{ in} $	$\frac{l_{A}}{l_{6}} = 1.35 = >$	1 ≤ 1.35 ≤ 2 0k √	
$= \frac{0.0908(0.243)(12\times24)^4}{53,000\sqrt{1500}(8)^3} = 0.165 \text{ in}$	$W = 35 \frac{16}{4t^2} \left( \frac{14}{12''} \right)$	$e^2 = 0.243 \text{ psi}$	
$= \frac{0.0908(0.243)(12\times24)^4}{57,000\sqrt{4500}(8)^3} = 0.165 \text{ in}$			<u>(9</u>
	= 0.0908 (0.24. 57,000 J 4500	$\frac{3}{(12\times29)^4} = 0.165$ in $(8)^3$	







Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm
$\propto = \underbrace{EI_{BEAM}}_{EISLARS} \qquad I_{L} = I_{L}$	$\frac{sbwh^3}{12}  I_s = \frac{l_1 t^3}{12}$
$\frac{BEAMS}{EDGE} = BEAMS = I_{b} = I_{-208}$ $INTERIOR BEAMS = I_{b} = I_{-208}$	$\frac{(15'')(20')^3}{12} = 12,080 \text{ in }^4$ $\frac{(15'')(20')^3}{12} = 14,200 \text{ in }^4$ $12$
$\frac{5LABS}{29' INTERIOR} : I_S = (20 \times 1)$	$\frac{2}{2}(8)^{3} = \frac{10240}{10} \frac{10^{4}}{10}$
$29 \in XTERIOR : I_S = \underbrace{\left(\frac{1}{2} \times 1\right)}_{10}$ $20' INTERIOR : I_S = \underbrace{\left(\frac{29 \times 1}{1}\right)}_{10}$	$\frac{2}{2} \left( \frac{8}{8} \right)^{3} = 14348 \text{ in }^{4}$
$20' EXTERIOR: Z_{S} = \frac{24}{2} \times 1$	$\frac{2}{2}(8)^{3} = 7424$ in t
$ \begin{array}{c}         B \\                           $	
$\omega_{BI} = \frac{I_{b,int}}{I_{b,int}} = \frac{14,70}{14,70}$	3 10 = 1.387
$ \begin{aligned} \mathbf{I}_{s,29,int} & 1024 \\ \alpha_{B2} &= \frac{\mathbf{I}_{b,ext}}{\mathbf{I}_{s,29,ext}} &= \frac{12084}{5120} \\ \alpha_{B3} &= \frac{\mathbf{I}_{b,int}}{\mathbf{I}_{s,29,ext}} &= \frac{14,24}{5424} \\ \alpha_{B4} &= \frac{\mathbf{I}_{b,ext}}{\mathbf{I}_{s,20,int}} &= \frac{14,84}{1484} \\ \alpha_{B4} &= \frac{\mathbf{I}_{b,ext}}{\mathbf{I}_{s,20,ext}} &= \frac{1208}{7424} \end{aligned} $	$ \begin{array}{l} 0\\ 2 = 2.359\\ \frac{1}{6} = 0.956\\ \frac{1}{6} = 1.627\\ 4 \\ \end{array} $ $ \begin{array}{l} \infty m = \frac{1.58}{1.58} < 2.0\\ \hline \hline$

Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm
FOR MEADIUM STIFF BEAMS	Xm < 2,0 (ACI 9.5.3.3)
$M_{int} = \frac{Ln(0.8 + fy)}{36 + SB(0)}$	- 1200,000) XSm - 0.2)
$= \frac{[(29)(12) - 15](0)}{36 + 5(1.586)(10)}$	.8 + 60,000/200000) = 7,80 => 8.00 in 13 fine (1.58 -0.2)
LOADING	
WTL = 1.2 (150 PSF) + 1.6	(40 PSF) = 184 psf = 0.184 KSf
$M_o = \frac{1}{8} l_2 l_n^2 \omega$	
= = = (0.184) (20') (29	-18"/12) = 347.88 1K
FOR END SPAN MOMENTS Ext: Mint = 0,70 Mo M <sup>+</sup> = 0.57 Mo = Mert = 0,16 Mo =	[ACI 13.6.3.3] = 247.88 1 K = 198.29 1 K = \$5.66 1 K
FOR INTERLOR MOMENTS Int: MT = 0,65M0 = Mt = 0,75M0 =	[4(I 13,6.3,2] 226,12 11 121,76 11 121,76
FRAME B Moments (fl.k)	
193.29	121-76
- 55.66 -747.9 -	-776.17
11100 01111	2.00 M C

TORSION CONSTANT [ACI 18.7.5] (Sections that are chosen will give largest C)
$C = \mathcal{E}\left(1 - 0.63\frac{\pi}{\gamma}\right)\left(\frac{\pi^{3}}{3}\right)$ $I = \left[\left(1 - 0.63\left(\frac{\pi}{3}\right)\right)\left(\frac{\pi^{3}}{3}\right)\right] + \left[\left(1 - 0.63\left(\frac{\pi}{3}\right)\right)\left(\frac{5^{5}}{3}\right)\right]$ $I = \left[\left(1 - 0.63\left(\frac{\pi}{3}\right)\right)\left(\frac{5^{5}}{3}\right)\right]$ $C = 16835.04 + 1187.84 = 18022.9$
$C = \left[ (1 - 0.63 (\frac{18}{20})) (\frac{18^{3} \cdot 10}{3}) \right] + 2 \left[ (1 - 0.63 (\frac{1}{20})) (\frac{18^{3} \cdot 10}{3}) \right] + 2 \left[ (1 - 0.63 (\frac{1}{12})) (\frac{8^{3} \cdot 10}{3}) \right] $ $C = 16835.04 + 2 (1187.84) = 19210.7$
TRANSVERSE DISTRIBUTION OF LONG MOMENTS
Need: lz/2, , x, , B lz/1, = 20 = 0.690
FRAME B $ \begin{aligned} \alpha_{1} &= \frac{T_{b}}{T_{s}} = \frac{14  lov}{10  l4  0} = 1.337 \\ \vdots &= 0.938 \\ \end{bmatrix} $ $ \begin{aligned} \alpha_{1} &= \frac{C}{2  I_{s}} = \frac{19210.7}{2(10240)} = 0.938^{2} \\ \vdots &= \frac{19210.7}{2(10240)} = 0.938^{2} \\ \vdots &= \frac{19210.7}{2(10240)} = 0.65964 = 0.660 \end{aligned} $
mint to col stop [ACI 13.6.4.1]
$\frac{\ell_{2}/\ell_{1}}{(\alpha, \beta_{1})^{2}/\delta} = \frac{0.5}{90} = \frac{0.69}{184.37} = \frac{1.0}{75}$
$=247.9 \longrightarrow 84.3\% t_0 (5 = -208.98' K \longrightarrow 85° t_0 t_0 t_0 m = -177.6' K \\ \longrightarrow 15.7\% t_0 m s = -38.92' K \longrightarrow 15' t_0 t_0 slab = -31.3' K$
-226,12 -> 84,3% to cs = -190,62 " -> 85% to beam = -162.03 " > 15.7% to MS = -35.5 " > 15% to slas = -28.59"

lectural Engineering	niversity	Thes	is: Inglesi	de at King F	arm	
Men to	Col strip	EACI. 13.	6.4.2			
10/8,	0.5 0	69 1.	0			
$ l_i  \ge 0$ Bt = 0	100 11	50 10	го			
$B_t = 0.937$ $B_t \ge 2.5$	90 8	4.3	5			
-55.66 - 9 5 5	4.3% to C.	5 =-5 2,1 15 =-3,17	IR N	85%. t.	benn = • 4 5/46 = •	4,62 1K 7,87 1K
M+ to Col	1. strip L	ACI 13.6	.4.4]			
11/11 0 ×141, 20	90	0.69	1.0			
+198.29	84.3% to	C5 = 16 m5 = 31	3. 12 1K -	> 85%	to beam to slab =	= 13 8,6514c = 74,47 <sup>14c</sup>
121 21 -2 2	14.3% to to	C3 = 10 M3 = 14,	2.64 "K -	> 85 % 1 > 15 % e	to benn =	87.25 1K 15.34 1K
+101.76 51	5.7 60 20 "					
FRAME B :	total width	L=20',	column s	hip=10'	, midelle	stop=10'
RAME B :	Total width	L = 20',	column & Mint	hip=10' m-	, midelle mt	stop=10'
Total Morm.	Total width <u>mext</u> -55.66	L = 20', $M^{+}$ + 197.79	mint -297.9	m= -226.12	, midelle m <sup>+</sup> +121.76	stop=10'
Total Mom. Beam.	Total usdb <u>mext</u> -55.66 -44.62	$\frac{1}{2} = 20^{\prime},$ $\frac{1}{2} + 197.79$ $\frac{1}{2} + 738.65$	column 8 <u>M</u> int -297.9 -177.6	m - - 226.12 -162.03	, midelle mt +121.76 +37.25	stop=10'
Total Morm. Bearn. CS Slab	Total width <u>mext</u> -55.66 -44.62 -7.87	L = 20', M + +197.79 +/38.65 +/5.39	column 8 <u>M</u> -iht -297.9 -179.6 -31.3	m - - 726.12 -167.03 - 28.59	, midelle mt + 121.76 + 87.25 + 15.39	stip=10'
Total Morr. Beam. CS Slab MS Sab	Total width <u>mext</u> -55.66 -44.62 -7.87 -3.17	L = 20', M + +197.79 +/38.65 +/5.39 + 19.11	column 8 <u>m_iht</u> -297.9 -179.6 -31.3 -37.92	6.7p = 10' <u>m</u> - -zz6.1z -162.03 -28.59 -35.5	, midelle mt +/21.76 +87.25 +15.39 +19.11	stip=10'
Total Morr. Beam. CS Slab MS Sab	Total width <u>mext</u> -55.66 -44.62 -7.87 -3.17	L = 20', M + +197.79 +/38.65 +/5.39 +19.11	column 8 <u>m_iht</u> -297.9 -179.6 -31.3 -37.92	6.7p = 10' <u>m</u> - - 726.12 -167.03 - 28.59 - 35.5	, midelle mt + 121.76 + 87.25 + 15.39 + 19.11	stop=10'







Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm
TRIAL SIZE - HOLLOW CORE	SLAB
USE = 4'-0" × 6" HOLLON	J CORE SLABS WITH 2" ZOPPING
f'c = 5,000 psi Wt W/ f'ci = 3,500 psi	topping = 74 pst
MAX SPAN LENGTH = 21.	5'
:. USE 96-5 with	146 PSF Safe Superimposed Eurice load
TRADE NAME STANDARD	SPANCRETE
LICENSING ORGANIZATION	SPANCRETE, MILWAUKEE, WISCENSIN
LOADING:	
DEADLUAD: 74 PSF (Sel 10 psf (Pa 84 psf	thought) duct work, etc)
LIVE LOAD: 40 psf (res	scientral)
1.20 +1.6L = 1	1.2 (84) + 1.6 (40) = 164.8 PSF
TRIB WIDTH : 19.	75' (164.8) = 3.25 K/H
$M_{\mu} = \frac{\omega \ell^2}{8} =$	$\frac{3.25(24')^2}{8} = 341'^k$
GIRDERS :	40×19.75
$\Delta_{LL \; MASK} = \frac{1}{360} = \frac{29(12^{\circ})}{360} = \frac{1}{360}$	$= 0.97'' = \frac{5(0.74)}{384(28000)} \frac{(29\times12)^4}{2min}$
A TL MAX = I = <u>74(12"</u> ).	$= 1.45'' = \frac{5(1.44/12)(29 \times 12)^4}{334(2900) I_{min}}$

Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm	
ALLMAX: => Imin = 44	16.9 in #	
ATL MAX = => Imin = 97	3.4 int ( governs	
:. Use W12×106	$(I_{x} = 933 m.^{4})$	
Check:		
Mu = 341" < 615"	k / ok	
$V_{u} = \frac{\omega l}{z} = \frac{3.25(29)}{z}$	= 47.1 K < 236 K Vok	
		tii



#### 4HC6

No Topping

Table of safe superimposed service load (psf) and cambers (in.)

Strand Designation Code										S	ban, f	ť									
	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30
	444	382	333	282	238	203	175	151	131	114	100	88	77	68	59	52	46	40	33	28	
66-S	0.1	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.1	0.0	-0.1	-0.2	-0.4	-0.5	-0.7	1	
	0.2	0.2	0.2	0.2	0.3	0.3	0.2	0.2	0.2	0.1	0.1	0.0	-0.1	-0.3	-0.5	-0.7	-0.9	-1.2	-1.5	-1.9	
76-S		445	388	328	278	238	205	178	155	136	120	105	93	82	73	65	57	49	42	36	31
		0.2	0.2	0.2	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.2	0.1	0.1	0.0	-0.1	-0.3	-0.4	-0.6
		0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.2	0.1	0.0	-0.1	-0.2	-0.4	-0.7	-0.9	-1.2	-1.6	-2.0
		466	421	386	338	292	263	229	201	177	157	139	124	110	99	88	78	68	60	53	46
06.6		0.2	0.7	0.3	0.4	0.4	04	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.4	0.3	0.3	0.1	0.0	-0.1
90-3		0.3	0.5	0.4	0.5	0.5	0.5	0.6	0.6	0.6	0.5	0.5	0.4	0.3	0.2	0.1	-0.1	-0.3	-0.6	-0.9	-1.3
		0.0	0.4	0.9	0.0	202	200	264	240	212	188	167	140	124	119	107	95	85	76	68	60
07.0		4/8	433	398	302	022	230	204	0.7	07	0.7	0.7	0.8	0.8	0.7	0.7	0.7	0.6	0.5	0.4	0.3
87-5		0.3	0.4	0.4	0.5	0.0	0.0	0.0	0.7	0.7	0.7	0.0	0.7	0.7	0.6	0.5	0.3	0.2	0.0	-0.3	-0.6
		0.4	0.5	0.5	0.6	0.7	0.7	0,7	0.0	0.0	0.0	0.0	9.7	0.1	0.0	110	407	0.2	0.0	70	70
		490	445	407	374	346	311	276	242	220	203	186	166	148	133	119	107	90	60	78	10
97-S		0.4	0.4	0.5	0.5	0.6	0.7	0.7	0.8	0.8	0.9	0.9	0.9	0.9	1.0	0.9	0.9	0.9	0.8	0.7	0.6
10.000		0.5	0.6	0,6	0.7	0.8	0.8	0.9	0.9	1.0	1.0	1.0	1.0	0.9	0.9	0.8	0.7	0.5	0.3	0.1	-0.2

#### 4HC6 + 2

Table of safe superimposed service load (psf) and cambers (in.)

2 in. Normal Weight Topping

Strand Designation Code									S	pan, f	t								
	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30
	470	396	335	285	244	210	182	158	136	113	93	75	59	46	34				
66-S	0.2	0.2	0.2	0.2	0.2	02	0.2	0.2	0.2	0.2	0.1	0.1	0.0	-0.1	-0.2				
000	0.2	0.2	0.2	0.2	0.2	0.1	0.1	0.0	-0.1	-0.2	-0.3	-0.5	-0.7	-0.9	-1.2				_
	0.04	461	391	334	287	248	216	188	163	137	115	95	78	63	50	38	27		
76.9		0.2	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.2	0.1	0.1	-0.0	-0.1	-0.3		
70-0		0.2	0.2	0.2	0.2	0.2	0.2	0.1	0.1	0.0	-0.2	-0.3	-0.5	-0.7	-0.9	-1.2	-1.5		
		0.2	472	424	367	319	279	245	216	186	160	137	116	98	82	68	55	43	33
9.90			0.4	0.4	0.4	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.4	0.3	0.3	0.1	0.0	-0.1
30-3			0.4	0.4	0.4	0.4	0.4	0.4	0.3	0.3	0.2	0.1	-0.1	-0.3	-0.5	-0.7	-1.0	-1.4	-1.7
			485	446	415	377	331	292	258	224	195	169	147	127	109	94	80	67	55
07 C			405	0.5	0.6	0.6	0.7	0.7	0.7	0.7	0.8	0.8	0.7	0.7	0.7	0.6	0.5	0.4	0.3
07-3			0.5	0.5	0.5	0.6	0.6	0.6	0.5	0.5	0.4	0.4	0.2	0.1	-0.1	-0.3	-0.5	-0.8	-1.2
			0.0	455	474	20.0	367	227	288	251	219	192	168	146	127	110	95	82	70
07.0			494	435	421	334	0.0	n.9	0.0	0.0	0.0	0.9	1.0	0.9	0.9	0.9	8.0	0.7	0.6
97-S			0.5	0.6	0.7	0.7	0.0	0.7	0.7	0.7	0.6	0.6	0.5	0.4	0.2	0.0	-0.2	-0.5	-0.8

PCI Design Handbook/Sixth Edition

Strength is based on strain compatibility; bottom tension is limited to  $7.5\sqrt{l_c^2}$ , see pages 2–7 through 2–10 for explanation.

2-31

#### HOLLOW-CORE SLABS



Note: All sections are not available from all producers. Check availability with local manufacturers.

#### Figure 2.5.4 Section Properties - Normal Weight Concrete

Spancrete



Note: Spancrete is also available in 40 in. and 96 in. widths. All sections are not available from all producers. Check availability with local manufacturers.

2-36

PCI Design Handbook/Sixth Edition



Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm	
DEFLECTIONS		
$\Delta_{DL^{+}LL} = \frac{5\left[\frac{(88)L0}{1000 \times 12}\right](30 \times 12)}{384(24000)(I_{LB})}$	$\frac{2}{2}^{4} < \frac{1}{240} = \frac{30(12'')}{240} = 1.5''$	
ILB < 368.7 in 4	« governs	
$\Delta_{LL} = \frac{5\left[\frac{(40)10}{1000\times 12}\right](30\times 12)^4}{384(29000)(I_{LB})}$	$l \frac{l}{360} = \frac{30(12")}{360} = 1"$	
ILB < 251.4 in 4		
$beff = \frac{3PAN}{4} = \frac{30}{4} = 7.5$	e governs	
min beam spacing = 10'		
[STL MANUAL TABLE 3.20]		
TRY 6/14×26 => IBL = 587 1	7 <del>4</del>	5
[STL MANUAL TABLE 3-19]		
$W 14 \times 26  $$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$	I <sub>x</sub> = 118 m <sup>2</sup> PNA # 4 PNA # 4	
$a = \frac{\xi Q_n}{0.85  f'_c  best} = \frac{16  9}{0.75(3)(90)}$	= 0.736 in < 1.0 Vok	
$\Delta_{DL+LL} = \frac{5\left[\frac{88\times10}{1000\times10}\right](30\times12)^4}{384(29000)(587)}$	= 0.94" <1.5" /ok	
$\Delta_{LL} = 5 \left[ \frac{(40)10}{1070 \times 12} \right] (30 \times 12)^4 \\ 384 (29000) (587)$	= 0.43" < 1" Vok	

Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm	
$ \phi M p = 151^{1k} > M u = 136. $	81K VOR	
[STL. MANUAL TABLE 3-21]		
use · Wenk stud per rib = 1 · Light weight concr. - stud diameter : 3/4" - fc = 3 Ksj - Perpendicular to deck	$\begin{cases} Q_n = 17.2 \end{cases}$	
$\#$ studs = $\frac{226}{17.2} = 13$	.14 = 14 studs perside (1 stu 	1 /2.14")
GIRDER DESIGN	ON LIKOFR	
LL: 40 PSF DL: 48 PSF ULULUU A 30' A .	P P J J Beam self weight i For 10' 10' 20	= 1.2 K
$LL = 20(10)(50) = 6^{m} L$ $DL = 2f(10)(50) = 7.2^{m} D$	$L = 6^{n} \times 2 = 12^{n}$ $L = (7 - 2^{n})^{2} + 1 \cdot 2^{n} = 15, 6^{n}$	
ALL+DL = 27.6 (30) 3 (1928 28(29000) I LD	$2 = \frac{1}{240} = 1.5''$	3
ILB ≥ 1057.2 m4	~ governs	
ALL = <u>12 (30)<sup>3</sup> (1728)</u> = 28 (24000) 7LB	$\frac{1}{360} = 2''$	
ILB 2 689.5 in 4	Beam on both side	es of Girder
Pu= 1.2(1.56) + 1.6(12	) = 21.07 ×2 = 42.14 K	

Stephen Dung Tat The Pennsylvania State University Architectural Engineering	Thesis: Ingleside at King Farm	
$M_{u} = a (P_{u})(L) = 0.333(42)$	.14) (30) = 420 1k	
TRY W18×55 -> IBL = 1880	in 4 > 1057-2 in 4	
ØMp = 420' ≤ Mu = 420 "*		
Z Qn = 454 K		
$a = \frac{454}{0.85(3)(90)} = 1.987$	n < 4.5 (available conc. depth	above deck)
$\#$ studs = $\frac{454}{17.2} = 26.$	3 => 27 studs perside (1st	(1.11')
	- USE 54 studs on GI	rder
Summary :		
W18-X55		
W18×55 - W14×26 - W18×55		
		12
418×55	識	
$\Delta_{0L+LL} = \frac{27.6(30)^3(1728)}{28(28000)1880} =$	= 0.84" < 1.5" Vok	

#### APPENDIX B: COST DATA

# 03 23 Stressing Tendons

				Daily	Labor-	3		2009 Bo	ire Costs	20000	Total
03 23	05.50 Prestressing Steel		Crew	Output	Hours	Unit	Moterial	Labor	Equipment	Total	Incl O&P
1050	143 kip	G	6-3	4200	.015	lb.	1.12	.62	.02	1.76	2.26
1200	Ungrouted strand, 50' span, 100 kip	G	C-4	1275	.025		.62	1,13	.02	1.77	2.55
1250	300 kip	G		1475	.022		.62	.98	.02	1.62	2.30
1400	100' span, 100 kip	G		1500	.021		.62	.96	.02	1.60	2.27
1450	300 kip	G		1650	.019		.62	.87	.02	1.51	2.13
1600	2001 span, 100 kip	G		1500	.021		.62	.96	.02	1.60	2.27
1650	300 kip	G		1700	.019		.62	.85	.02	1.49	2.09
1800	Unarouted bars, 50' span, 42 kip	G	8 8	1400	.023		.78	1.03	.02	1.83	2.55
1850	143 kip	G		1700	.019		.78	.85	.02	1.65	2.26
2000	75' soon, 42 kip	G		1800	.018		.78	.80	.02	1.60	2.18
2050	143 kip	G		2200	.015		.78	.66	.01	1.45	1.93
2220	Unarouted single strand, 100' slab, 25 kip	G		1200	.027		.62	1.20	.02	1.84	2.67
2250	35 kip	G	7	1475	.022	-	.62	.98	.02	1.62	2.30

03	24 Fibrous Reinforci	ng				
03	24 05 - Reinforcing Fibers					
03 2	4 05.30 Synthetic Fibers					
0010	SYNTHETIC FIBERS					
0100	Synthetic fibers, add to concrete		Lb.	4.43	4.43	4.87
0110	1-1/2 lb. per C.Y.		C.Y.	6.85	6.85	7.55
03 2	4 05.70 Steel Fibers					
0010	STEEL FIBERS			A Starter		
0150	Steel fibers, add to concrete	G	Lb.	.70	.70	.77
0155	25 lb, per C.Y.	G	C.Y.	17.50	17.50	19.25
0160	50 lb, per C.Y.	G		35	35	38.50
0170	75 lb, per C.Y.	G		54	54	59.50
0180	100 lb, per C.Y.	G	7	70	70	77

# 03 30 Cast-In-Place Concrete

153 - Miscellaneous Cast-In-Place Concrete

0	ONCRETE IN PLACE										
	Including forms (4 uses), reinforcing steel, concrete, placement,										
	and finishing unless otherwise indicated	R033053-50									
1	Beams, 5 kip per L.E., 10' span		C-14A	15.62	12.804	C.Y.	400	515	49	964	1,300
	25' spon		30	18.55	10.782		430	430	41	901	1,200
	Chimney foundations, industrial, minimum		C-14C	32.22	3.476		166	133	.80 1	299.801	39
k.	Maximum			23.71	4.724		203	181	1.09	385.09	505
	Columns, square, 12" x 12", minimum reinforcing		(-14A	11.96	16.722		400	670	64	1,134	1,55
	Average reinforcing	R033105-85		10.13	19.743		720	790	75.50	1,585.50	2,10
	Maximum reinforcing			9.03	22.148		1,150	890	84.50	2,124.50	2,750
	16" x 16", minimum reinforcing			16.22	12.330		315	495	47	857	1,17
	Average reinforcing			12.57	15.911		625	640	61	1,326	1,75
	Maximum reinforcing			10.25	19.512		1,025	780	74.50	1,879.501	2,45
	24" × 24", minimum reinforcing			23.66	8.453		275	340	32.50	647.50	86
	Average reinforcing			17.71	11.293		570	455	43	1,068	1,375
	Maximum reinforcing			14.15	14,134		965	565	54	1,584	2,000
	36" x 36", minimum reinforcing			33.69	5.936		249	238	22.50	509.50	670
1	Average reinforcing			23.32	8.576		505	345	33	883	1,125

59.45 \$111.26 Incl. 0&P \$61.10

Crew Ho.         Bare Costs         Socio B P         Per laboritori           Over C15         H         Boly         Bare Boly	100000		and a stand of the second	10 × 10 × 10	Incl	-	-		and the second sec	A COLUMN AND A	1	c1	F.	
Orw 0.5         H.         Day         R.         Bars         Mode Display           Corrent inder State State         542.0         522.0<	Crew No.	Bar	e Costs	Sub	Incl. os O & P	Per Lat	oor-Hour	Crew No.	Bare	Costs	Subs	s O & P	Per La	oor-Hou
Concrete Frame         State	Crew C-15	Hr.	Daily	Hr.	Daily	Bare Costs	Incl. 0&P	Crew C-18	Hr.	Daily	Hr.	Daily	Bare Costs	Incl. 0&P
Convention         33.10         502.00         542.	1 Carpenter Foreman (out)	\$40.10	\$320.80	\$62.40	\$499.20	\$36.01	\$55.70	.125 Labor Foreman (out)	\$32.25	\$32.25	\$50.20	\$50.20	\$30.47	\$47,40
Lisbers         33.25         726.00         47.05         1192.00           Crew C16         Hr.         Day         Hr.         Day         Bare         Beta           Crew C16         Hr.         Day         Hr. </td <td>2 Carpenters</td> <td>38.10</td> <td>609.60</td> <td>59.30</td> <td>948.80</td> <td></td> <td></td> <td>1 Laborer</td> <td>30.25</td> <td>242.00</td> <td>47.05</td> <td>376.40</td> <td></td> <td></td>	2 Carpenters	38.10	609.60	59.30	948.80			1 Laborer	30.25	242.00	47.05	376.40		
Classes         State         <	3 Laborers	30.25	726.00	47.05	1129.20			1 Concrete Cart, 10 C.F.		56.40		62.04	6.27	6.89
Action and J         41.00         34.01         555.7         State	2 Cement Finishers	37.00	592.00	54.30	868.80			9 L.H., Daily Totals		\$330.65		\$488.64	\$36.74	\$54.29
Curr, Col, Singer, Col, Singer,	1 Xodman (reirit,)	45.00	595.00	10.55	04,40	635.01	855 78	2002223	525	10000	-	020000	Bare	Incl.
Crew C16         He         Daily         He         Daily         Bare         Bedd           Libor forema labeled         S122.5         S28.0         S20.2	72 L.H., Daily locals		32392.40	-	54010.40	536.01	500.70	Crew C-19	Hr.	Daily	Hr.	Daily	Costs	O&P
Liber forma isolation         State         State<	Crew C-16	Hr.	Daily	Hr.	Daily	Bare Costs	linci. 0&P	.125 Labor Foreman (out) 1 Laborer	\$32.25 30.25	\$32.25 242.00	\$50.20	\$50.20 376.40	\$30,47	\$47,40
Libborn         31.2         78.0         47.0         112.3         112.3           Gaue Structured         33.8         53.8         53.7         53.8         55.7         55.8         54.8         54.8         54.8         54.8         54.8         54.8         54.8         54.8         54.8         54.8         54.8         54.8         54.8         54.8         54.8         54.8         54.8         54.9         54.8         54.9         54.8         54.9         54.8         54.9         54.9         54.8         54.9         54.8         54.9         54.8         54.9         54.8         54.9         54.8         54.9         55.0 <td>1 Labor Forentan (outside)</td> <td>\$32.25</td> <td>\$258.00</td> <td>\$50.20</td> <td>\$401.60</td> <td>\$35.87</td> <td>\$55.68</td> <td>1 Concrete Cart, 18 C.F.</td> <td></td> <td>84.40</td> <td></td> <td>92.84</td> <td>9.38</td> <td>10.32</td>	1 Labor Forentan (outside)	\$32.25	\$258.00	\$50.20	\$401.60	\$35.87	\$55.68	1 Concrete Cart, 18 C.F.		84.40		92.84	9.38	10.32
Liener Franker Liener Franker Franker (Here) 4200 882.00 70.50 1128.00 Franker (Here) 421.00 7000 7000 7000 7000 7000 7000 7000	3 Laborers	30.25	726.00	47.05	1129.20			9.L.H., Daily Totals	-	\$358.65		\$519.44	\$39.85	\$57,72
Lab. U. or. (ntic.)         J. 20.         State         No.         State           Correct Arm promuti         72.0.2         6.0.1.2         1.1.1         1.1.1           Correct Arm promuti         72.0.2         6.0.1.2         1.1.1         1.1.1           Correct Arm promuti         72.0.2         6.0.1.2         1.1.1         1.1.1           Correct Arm promuti         72.0.2         7.0.0.0.         7.0.0.0.         7.0.0.0.         7.0.0.0.         7.0.0.0.0.0.0.0.0.0.0.0.0.0.0.0.0.0.0.0	2 Cement Finishers	37.00	592,00	54.30	868.80						0.02		Bare	Incl.
Audio Humin         South Program         South Prog	1 Equip. Oper, Imedua 2 Redmon Imini (	39.65	310,00	20.55	460.60			Crew C-20	Br.	Daily	Hr.	Daily	Costs	08P
Schuld Public         Classe         Control         Contro         Control <thcontrol< th=""></thcontrol<>	2 Rodines genus 1 Concesta Paran (smail)	43,00	725.20	10.00	801.02	10.11	11.13	1 Labor Foreman (outside)	\$32.25	\$258,00	\$50.20	\$401.60	\$32.54	\$49,98
Line and the second of the second o	721 H Dale Tetals		\$9911.00		\$4810.22	\$45.00	566.91	5 Laborers	30.25	1210.00	47.05	1882.00	1.1.2	
Crew C-17         Hr.         Daily         Hr.         Daily         Const. Output           33.84 State Toreme         51.4.0         552.25         552.85         551.85         12.32           33.84 State Toreme         51.4.0         552.25         552.85         551.85         12.32           33.84 State Toreme         51.4.0         552.25         552.80         552.85         551.85           Crew C-17         Hr.         Daily         Hr.         Daily         Costs         551.85         551.85           State Streker Toreme         514.40         552.25         551.85.2         551.85 <td>To carry they fullers</td> <td></td> <td>00011/00</td> <td></td> <td>01010.00</td> <td>2002</td> <td>Ind</td> <td>1 Certert Frisher</td> <td>37.00</td> <td></td> <td>54,30</td> <td>434,40</td> <td>6 0 5</td> <td>1.1.4</td>	To carry they fullers		00011/00		01010.00	2002	Ind	1 Certert Frisher	37.00		54,30	434,40	6 0 5	1.1.4
Build Winder Forement 3 Skell Winders 3 Skell Winder Forement 3 Skell Winders 3 Skell W	Crew C-17	Hr	Daily	Hr	Daily	Costs	Inci.	1 Equp. Oper. Imed.1	39.85	318.80	60.10	450.80	1 - a	
Same Band Notening         J.M.A.         Same Band	7 Chilled History Decomon	C 41 40	04 0222	11.132	\$1030.40	¢30 80	SET 99	2 Gas Eligible Violator	2	49.00 729.20		801.02	1215	12 37
Sind         Dirac         Dirac <thd< td=""><td>2 Skilled Workers</td><td>30 70</td><td>2521.60</td><td>51.25</td><td>3920.00</td><td>333.00</td><td>301.00</td><td>64.1 H. Daly Totale</td><td></td><td>02860 60</td><td></td><td>\$4054.32</td><td>\$44.70</td><td>25 532</td></thd<>	2 Skilled Workers	30 70	2521.60	51.25	3920.00	333.00	301.00	64.1 H. Daly Totale		02860 60		\$4054.32	\$44.70	25 532
Crew C17A         H         Daily         HA         Daily         Da	801 H. Daly Totals	45100	\$3184.00	0000	\$4950.40	\$39.80	861.88	er Ent, ouly joins	-	95000100		04004.00	214.00	lad
Crew C17A         Hr.         Daily         Kr.         Daily         Daily <thdaily< th=""> <thd< td=""><td>The second body for the</td><td>-</td><td>Lat Market</td><td>-</td><td>41300.10 ·</td><td>Para</td><td>Incl</td><td>Crew C-21</td><td>Hr</td><td>Daily</td><td>Hr</td><td>Oally</td><td>Costs</td><td>O&amp;P</td></thd<></thdaily<>	The second body for the	-	Lat Market	-	41300.10 ·	Para	Incl	Crew C-21	Hr	Daily	Hr	Oally	Costs	O&P
Side Woler Forenen         St.I.4         St.I.5         St.I.6	Crew C-17A	Hr	Daily	Bc.	Daily	Costs	0&P	1 Labor Economic (outrida)	\$20.05	\$258.00	\$50.20	na mag	\$32.54	\$10.62
Sinder Worker         324.0         Convert Converts         State Register         State Register<	2 Skilled Worker Foreman	S41 AR	04 6332	01.122	\$1030 AD	\$39.81	\$61.88	Flahmers	30.25	1210.00	47.05	1882.00	332.34	943130
125 Equ. Oper. formel       40.35       40.25       51.75       51.75       1.99       2.13         125 Equ. Oper. formel       161.25       177.38       1.99       2.13       54.64       55.852       54.850       56.07         125 Equ. Oper. formel       541.40       Daly       Hr.       Daly       Bare       Ind.         25 Educt. Oper. Lined.       541.40       S24.52.40       55.44.3       510.30.40       534.35       51.82.20       55.44.34       55.00.2 <td>8 Skilled Workers</td> <td>39.40</td> <td>2521.60</td> <td>61.25</td> <td>3920.00</td> <td>222.01</td> <td>991.00</td> <td>1 Certent Enisher</td> <td>37.00</td> <td>295.00</td> <td>54 30</td> <td>434.40</td> <td></td> <td></td>	8 Skilled Workers	39.40	2521.60	61.25	3920.00	222.01	991.00	1 Certent Enisher	37.00	295.00	54 30	434.40		
125 HgL Cone, 80 In         161,25         177,38         199         2.13           12 LL, Day Traité         5338,20         5518,52         541,80         554,07         554,00         552,00         5544,34         5338,20         5518,52         541,80         5538,20         5518,52         541,80         5538,00         552,80 <td>.125 Equip. Oper. (crane)</td> <td>40.95</td> <td>40.95</td> <td>61.75</td> <td>61.75</td> <td></td> <td></td> <td>1 Ecup. Oper. (med.)</td> <td>39.85</td> <td>318.80</td> <td>60.10</td> <td>480.80</td> <td></td> <td></td>	.125 Equip. Oper. (crane)	40.95	40.95	61.75	61.75			1 Ecup. Oper. (med.)	39.85	318.80	60.10	480.80		
BL LH, Daly finals         S3386.20         S5189.52         S41,80         S64,07           Crew C178         Hr.         Daly         Hr.         Daly         Bare         Incl.           23 Mide Worker Foremen         S41,40         S562,40         S103,00         S53,83         S61,85           25 Hyb. Cone, and Tom         32,42         222,50         S34,44         S562,40         S103,00           25 Hyb. Cone, and Tom         32,42         S22,50         S34,4,75         S563,00         S72,85         S560,00         S72,85	.125 Hyd. Crane, 80 Ton		161.25		177.38	1,99	2.19	2 Gas Engine Vibrator		49.60		54.56	1.1	
Crew C-178         Hr.         Daily         Hr.         Daily         Bare         Ind.           25 Med. Worker Forenen         554.0	81 L.H., Daily Totals	-	\$3386.20	<u></u>	\$5189.52	\$41.80	\$64.07	1 Concrete Conveyer		172.80	š	190.08	3.48	3.82
Crew C-178         Hr.         Daily         Costs         OBP           2 Statel Worker Foremen         S14.40         502.40         504.40         503.44 <td< td=""><td></td><td></td><td></td><td></td><td></td><td>Bare</td><td>Incl.</td><td>64 L.H., Daily Totals</td><td></td><td>\$2305.20</td><td></td><td>\$3443.44</td><td>\$36.02</td><td>\$53.80</td></td<>						Bare	Incl.	64 L.H., Daily Totals		\$2305.20		\$3443.44	\$36.02	\$53.80
Crew C-17C         Hr.         Daily         Hr.         Daily         Hr.         Daily         Hr.         Daily         Costs         O&P           25 Hard. Morkers         33-40         2521:50         61.25         390.00         539.02         543.02	Crew C-178	Hr.	Daily	Hr.	Daily	Costs	0&P	15 ASSA	-	82118	- 35	10000	Bare	Incl.
Statict Workers         334.0         251.00         61.25         398.00         57.32.5         590.00         57.32.5         590.00         57.32.5         590.00         57.32.5         590.00         57.32.5         590.00         57.32.5         590.00         57.32.5         590.00         57.32.5         590.00         57.32.5         590.00         57.32.5         590.00         57.32.5         57.00         5	2 Skilled Worker Foremen	\$41.40	\$662.40	\$64.40	\$1030.40	\$39.83	\$61.88	Crew C-22	Hr.	Daily	Hr.	Daily	Costs	0&P
25 Equ., Doe, Israel       40.95       61.75       123.50         25 Equ., Doe, Israel       322.50       334.75         25 Indel, 48° WalkBeind       9.95       10.95       4.05       4.46         21 LH, Daily Totals       53588.35       55439.60       \$54.38       \$56.34         21 LH, Daily Totals       53588.35       55439.60       \$54.38       \$66.34         21 Med Workers       33.40       522.50       61.25       3390.00       \$51.00       \$10.10.00       \$23.55         125 Equ., Det, Israel       40.35       122.55       61.75       53.23       \$4.85       \$10.00       \$10.00       \$23.46       \$10.80.00       \$23.46       \$10.80.00       \$25.95       \$25.95         125 Equ., Det, Israel       40.35       122.55       61.75       532.25       \$10.00       \$10.00       \$39.84       \$61.88         12 LH, Daily Totals       533790.60       55667.77       \$45.67       \$58.29       \$10.00       \$10.00       \$10.25       \$22.54.00       \$10.100       \$59.11       \$25.95       \$29.50       \$29.40       \$10.100       \$59.11       \$25.95       \$29.50       \$29.40       \$10.100       \$20.15       \$41.00       \$61.175       \$49.00       \$21.55       \$21.55	8 Skilled Workers	39.40	2521.60	61.25	3920.00			1 Rodman Foreman	\$45.00	\$360.00	\$73.85	\$590.80	\$43.14	\$70.55
25 mgel 39 MgBehrid       9.322.00       334.75       334.75       4.05       4.45	.25 Equip. Oper. (cranel	40.95	81.90	61.75	123,50			4 Rodmen (reint.)	43.00	13/6.00	10.55	Z257.50		
Correw C-17C         Hr.         Daily         Hr.         Daily         State         State           Crew C-17C         Hr.         Daily         Hr.         Daily         State         State <td< td=""><td>25 MyO, Urane, 80 Ion. 25 Touriel, 40t Walk Dahierd</td><td></td><td>322,50</td><td></td><td>304,75</td><td>1.05</td><td>2.75</td><td>126 Equip. Oper. (crane)</td><td>40.90</td><td>90.90</td><td>52.05</td><td>52.05</td><td>E.</td><td></td></td<>	25 MyO, Urane, 80 Ion. 25 Touriel, 40t Walk Dahierd		322,50		304,75	1.05	2.75	126 Equip. Oper. (crane)	40.90	90.90	52.05	52.05	E.	
Bare         Ind.         State         S	20 HOWEL 40 WERVOEINIG		20200.02		06.01	CU.P	0,40 CCC 25	125 Equip. Oper, oter 125 Had. Crana: 25 Tet	35.10	98.25	32.55	108.02	2.34	2.57
Crew C-17C         Hr.         Daily         Hr.         Daily         Bare         Incl.           13:Billed Worker Foremen         \$41.40         \$662.40         \$54.40         \$1030.40         \$39.84         \$61.88         Crew C-23         Hr.         Daily         Hr.         Daily         Costs         0&P           375 Equit, Oper. (noriel)         40.35         122.65         61.75         185.75         5.83         5.41           175 Hyd. Crane, 80 Ton         483.75         532.13         5.83         5.41         16.25         290.00         61.25         294.00         539.52         \$61.10           175 Hyd. Crane, 80 Ton         483.75         532.77         545.67         568.29         11.40         50.48         40.95         122.85         423.60           18 UH, Daily Totals         53790.60         55667.77         545.67         568.29         11.40         50.10         127.57         19.59         21.55           18 UH, Daily Totals         5379.00         51.92         280.00         52.95         423.60         128.265           11.40/cerse         539.90         54.140         530.90.0         54.75         57.03         280.00         52.95         423.60         52.95	oz Lini, bally ictais		\$3598.35		20403100	242,00	-300.34	421 H. Daly Totals		\$1910.30		\$3071.18	\$45.48	\$73.12
Crew C-23         Hr.         Daily         Costs         OLF           Stilled Worker Foremen         \$11.40         \$562.40         \$50.88         \$51.88         \$61.88         \$22.15.0         \$61.25         3320.00         \$39.64         \$61.88         \$41.40         \$562.40         \$64.40         \$103.040         \$39.52         \$61.10           375 Equip. Oper. (orane)         40.35         122.85         61.75         185.75         \$532.13         \$5.83         6.41           375 Equip. Oper. (orane)         40.35         33790.60         \$55667.77         \$54.567         \$588.29           12 LH, Daily Totals         \$33790.60         \$56667.77         \$54.567         \$588.29           Crew C-17D         Hr.         Daily         Hr.         Daily         Crests         0.8P           12 UK, Daily Totals         \$334.0         \$521.60         61.25         3300.00         1723.70         19.59         21.55           2 Stilled Worker Soremen         \$41.40         \$662.40         \$64.40         \$1030.40         \$339.85         \$61.87           2 Stilled Worker Soremen         \$41.40         \$662.40         \$64.40         \$1030.40         \$339.85         \$61.87           2 Stilled Worker Soremen         \$4	Crew C-17C	Hr	Daily	Hr	Daily	Cosis	Incl. 0&P	the end, and the					Rana	Incl
Six Block Workers         39.40         2521.60         61.25         3920.00         Six Block Workers           375 Equip. Oper. (crane)         40.95         122.85         61.75         185.25         5.83         6.41           375 Equip. Oper. (crane)         40.95         122.85         61.75         185.25         5.83         6.41           375 Equip. Oper. (crane)         433.75         5520.77         545.67         568.29         16.0L         0.95         327.50         61.25         2940.00         129.59         21.55           Crew C-17D         Hr.         Daily         Hr.         Daily         Bare         Incl.         0.541.60         541.40         5661.70         559.11         882.65           Stilled Workers         39.40         2521.60         61.25         3920.00         559.11         582.65         61.70         559.11         882.65           Stilled Workers         39.40         2521.60         61.25         3920.00         539.69         547.53         570.32           Stilled Workers         39.40         2521.60         61.25         3920.00         539.69         547.53         570.32           Stilled Workers         39.40         2521.60         61.25         3920	2 Shilled Worker Erromen	01:112	\$662.40	\$64.40	51030.40	530.84	561.8R	Crew C-23	Hr.	Daily	Hr,	Daily	Costs	0&P
STS Equip. Oper. (create)         40.95         122.85         61.75         185.25         5.83         6.41           375 Equip. Oper. (create)         483.75         532.13         5.83         6.41           371 Equip. Oper. (create)         30.14, 0 aly Totals         5379.060         55667.77         545.67         568.29           Crew C-17D         Hr.         Daily         Hr.         Daily         Bare         Incl.           2 Stilled Worker Foremen         541.40         564.40         5103.00         539.85         561.87           5 Equip. Oper. (crane)         40.95         645.00         709.50         7.58         8.45           5 Expl. Oper. (crane)         541.40         566.20         544.75         570.32         11.abtc         532.25         528.00         550.20         540.1.60         533.76         531.80           5 Expl. Oper. (crane)         40.95         543.20         709.50         7.58         8.45         1         1.abtc         532.60         550.20         \$401.60         533.76         531.80           1 Labor Foreman         541.40         566.240         564.40         5100.04.01         539.80         561.80         1         1         12.abtc         52.95         423.	8 Skilled Workers	39.40	2521.60	61.25	3920.00	002004	201100	2 Skilled Worker Foremen	\$41.40	\$662,40	\$64,40	\$1030.40	\$39.52	\$61.10
375 Hyd. Crane, 80 Ton         483.75         532.13         5.83         6.41           31 LH, Daly Totals         53790.60         55667.77         545.67         558.29           Crew C17D         Hr.         Daily         Bare Costs         Incl. Costs         Os.P         Other         35.10         220.80         52.95         423.60           1 Latice Boum Crane, 90 Ton         541.40         5662.40         564.40         51090.0pc. (crane)         39.40         255.160         61.75         249.40         53.98.5         561.87           5 Killed Worker Foremen 5 Expl. Orane, 80 Ton         40.95         32.760         61.75         494.00         58.91.87           Crew C-17E         Hr.         Daily         Hr.         Daily         Costs         0.84           1 Labor Foreman 541.40         5662.40         56.40         51.90         7.68         8.45           2 Skilled Worker Foremen 3 Skilled Worker Foreman 3 Skilled Worker Foreman 3 Skilled Worker Socie         33.90         561.83         531.80           2 Laborers         30.25         484.00         52.95         423.60         1744.60           1 Skilled Worker Foremen 3 Skilled Worker Foremen 3 Skilled Worker Socie         532.80         561.83         561.83           1 HyL	.375 Equip. Oper. (crate)	40.95	122.85	61.75	185.25			6 Skilled Workers	39,40	1891.20	61.25	2940.00		
31 LH, Dally Totals         \$3790.60         \$5567.77         \$45.67         \$588.29           Crew C-17D         Hr.         Daily         Bare         Incl.           Costs         08.P           2 Skilled Worker Foremen         \$41.40         \$662.40         \$100.00         \$100.00         \$1723.70         \$19.59         \$21.55           2 Skilled Worker S         39.40         \$251.60         \$125         3920.00         \$18.75         \$18.00         \$1723.70         \$19.59         \$21.55           5 Expl. Oper. (crane)         40.395         163.80         61.75         247.00         \$18.75         \$18.00         \$1725.70         \$19.59         \$21.55           5 Expl. Oper. (crane)         40.395         163.80         61.75         247.00         \$14.14.0         \$392.80         \$59.00         \$50.27         \$32.85         \$51.80           6 Hyd. Crane, 80 Ton         645.00         709.50         7.88         8.45         \$30.25         \$48.40         \$47.05         \$752.80         \$42.40         \$47.05         \$52.80         \$52.36         \$43.60         \$10.20         \$61.75         \$49.40         \$12.55         \$48.40         \$47.05         \$52.80         \$10.52.5         \$48.40         \$17.55	.375 Hyd. Crane, 80 Ton	0102.001	483.75	10010460	532.13	5.83	5.41	1 Equip. Oper. (crane)	40.95	327.60	61.75	494.00		
Crew C-17D         Hr.         Daily         Hr.         Daily         Bare         Incl.           Crew C-17D         Hr.         Daily         Costs         0&P           2 Skilled Worker Foremen         S4L40         S662.40         S64.40         S1030.40         S39.85         S61.87           3 Skilled Workers         39.40         2521.60         61.25         3920.00         -         -         -         -         -         -         Bare         Incl.         -	83 L.H., Daily Totals		\$3790.60		\$5667.77	\$45.67	\$68.29	1 Equip. Oper. Oller	- 35.10	280.80	52.95	423.60		
Crew C-17D         Hr.         Daily         Hr.         Daily         Costs         O&P           2 Skilled Worker Sreemen         S4L.40         S662.40         S64.40         S1030.40         S39.85         S61.87           2 Skilled Workers         39.40         2521.60         61.25         3920.00         - <td></td> <td></td> <td></td> <td></td> <td></td> <td>Bare</td> <td>Inci.</td> <td>1 Lattice Boom Crane, 90 Ton</td> <td></td> <td>1567.00</td> <td></td> <td>1723,70</td> <td>19.59</td> <td>21.55</td>						Bare	Inci.	1 Lattice Boom Crane, 90 Ton		1567.00		1723,70	19.59	21.55
Skilled Workers         S41.40         S662.40         S642.40         S1030.40         S39.85         S61.87           Skilled Workers         33.40         2521.60         61.25         3390.00         -         -         -         Daily         Hr.         Daily         Hr.         Daily         Hr.         Daily         K.         Costs         08P           5 Hyt. Crane, 80 Ton         645.00         709.50         7.68         8.45         S0.25         S28.00         S50.20         S40.60         S33.76         S33.76         S10.80           14 L.H., Daily Totals         S3992.80         S5906.90         S47.53         S70.32         16.00         Crew C-17E         Hr.         Daily         Hr.         Daily         Costs         O&P           2 Skilled Worker Foremen         S41.40         S64.40         S103.040         S10.80         52.35         484.00         1744.60         10 costs         59.45         50.18         11.126         <	Crew C-17D	Hr.	Daily	Hr.	Daily	Costs	0&P	80 L.H., Daily Totals		\$4729.00		\$6611.70	\$59,11	\$82.65
Skilled Workers         33.40         2521.60         61.25         339.00         Free C-23A         Hr.         Oaily         Hr.         Daily         Costs         O&P           5 Skilled Workers         5 Sup. Dger. (crane)         40.95         163.80         61.75         247.00         7.68         8.45           5 Styt. Crane, 50 Ton         645.00         709.50         7.68         8.45           34 LH., Daily Totals         53392.80         55906.90         \$47.53         \$70.32           Crew C-17E         Hr.         Daily         Hr.         Daily         Costs         O&P           2 Skilled Worker Foremen         541.40         \$66.40         \$61.25         390.00         \$32.40         1.05         1.16           1 Multi Rods         33.40         2521.60         61.25         390.00         \$38.80         \$61.85           1 Multi Rods         533268.00         550.42.80         \$30.40         1.05         1.16           1 Multi Rods         533268.00         550.42.80         \$40.85         \$63.00         1.05         1.16           1 Multi Rods         533268.00         55042.80         \$40.85         \$63.00         1.05         1.16           1 Multi Rods	2 Skilled Worker Foremen	\$41.40	\$662.40	\$64.40	\$1030.40	\$39.85	\$61.87						Bare	Incl.
5 Equip. Oper. (crane)         40.95         163.80         61.75         247.00         7.68         8.45           5 Hyd. Crane, 30 Ton         645.00         709.50         7.68         8.45           14 LH., Daly Totals         53992.80         55906.90         547.53         570.32           Crew C-17E         Hr.         Daily         Hr.         Daily         Costs         O&P           2 Skilled Worker Foremen         541.40         \$662.40         \$64.40         \$100.40         \$39.80         \$61.85           3 Skilled Worker S         39.40         2521.60         61.25         3900.00         \$40.85         \$63.03         \$40 LH, Daly Totals         \$353268.00         \$5042.80         \$50.42         \$40.85         \$61.85         \$30.40         \$100.40         \$39.80         \$61.85           1 Mod Jack with Bods         33.40         \$50.42         \$40.00         \$1.165         \$351.80         \$351.80         \$31.42         \$4450.20         \$87.81         \$111.26           1 Mod Jack with Bods         \$33268.00         \$50.42         \$1.05         \$1.16         \$360.00         \$24.41         \$1.05         \$1.16           1 Mod Jack with Bods         \$33268.00         \$50.428         \$40.85         \$63.03	8 Skilled Workers	39.40	2521.60	61.25	3920.00	1000	24 million	Crew C-23A	Hr.	Daily	Hr,	Daily	Costs	980 980
5 Hyd. Crane, 80 Ton         645.00         709.50         7.68         8.45           34 L.H., Daly Totals         S3992.80         S5906.90         \$47.53         \$70.32           Crew C-17E         Hr.         Daily         Hr.         Daily         Costs         O&P           2 Skilled Worker Foremen         \$41.40         \$662.40         \$64.40         \$100.40         \$2.95         42.46.0         \$47.45         \$49.40           2 Skilled Worker Foremen         \$41.40         \$662.40         \$64.40         \$100.40         \$39.80         \$61.85         \$39.80         \$61.85         \$30.25         \$44.50	.5 Equip. Oper. (crane)	40.95	163.80	61.75	247.00			1 Labor Foreman (outside)	\$32.25	\$258.00	\$50,20	\$401.60	\$33.76	\$51.80
V4 LH., Daly Totals         S3992.80         S5996.90         S47.5.3         S70.32           Crew C-17E         Hr.         Daily         Hr.         Daily         Bare         Incl.           2 Skilled Worker Foremen         S41.40         S662.40         S64.40         S1030.40         S39.80         S61.88           3 Skilled Worker Foremen         S41.40         S662.40         S64.40         S1030.40         S39.80         S61.88           1 Equip. Oper. Other         35.10         280.80         52.35         423.60         1744.60           1 Skilled Worker Foremen         S41.40         S662.40         S61.28         39.40         531.62         351.240         S4450.20         S87.81         S111.26           1 Hyd. Jack with Bods         S3268.00         S5042.80         S40.85         S63.03         S61.88         S312.40         S4450.20         S87.81         S111.26           1 Hyd. Jack with Bods         S3268.00         S5042.80         S40.85         S63.03         S61.88         S63.03         S40.85         S63.03         S40.85         S63.03         S40.85         S62.40         S64.40         S1030.40         S39.52         S61.10           2 Skilled Worker Foremen         S41.40         S662.40	.5 Hyd. Crane, 80 Ton	0.00	645.00	7	709.50	7.68	8.45	2 Laborers	30.25	484.00	47.05	752.80		
Crew C-17E         Hr.         Daily         Hr.         Daily         Bare Incl. Costs         Incl. O&P           2 Skilled Worker Foremen         S41.40         S662.40         S64.40         S100.40         S39.80         S61.88           3 Skilled Worker S         39.40         2521.60         61.25         3920.00         1.05         1.16           10 LH, Daily Totals         S3268.00         S5042.80         S40.85         S63.03         S41.40         S662.40         S64.40         S100.40         S39.80         S61.88           10 LH, Daily Totals         S3268.00         S5042.80         S40.85         S63.03         S41.40         S662.40         S64.40         S100.40         S39.20         S40.85         S63.03         S41.40         S662.40         S64.40         S100.40         S39.25         S61.10           2 Skilled Worker S         39.40         1.05         1.16         Crew C-24         Hr.         Daily         Hr.         Daily         Costs         O&P           2 Skilled Worker S         S39.40         1.801.00         1.05         1.16         Crew C-24         Hr.         Daily         Hr.         Daily         Costs         O&P           2 Skilled Worker S         39.40         1.8	84 L.H., Daily Totals		\$3992.80		\$5906.90	\$47.53	\$70.32	1 Equip. Oper. (cranel	40.95	327,60	61.75	494.00		
Crew C-17E         Hr.         Daily         Hr.         Daily         Costs         O&P           2 Skilled Worker Streamen         S41.40         S662.40         S64.40         S100.40         S39.80         S61.88           3 Skilled Worker S         39.40         2521.60         61.25         3920.00         1.05         1.16           1 Update Totals         S3268.00         92.40         1.05         1.16         S41.40         S662.40         S4450.20         S87.81         S111.26           1 Update Totals         S3268.00         92.40         1.05         1.16         Crew C-24         Hr.         Daily         Hr.         Daily         Costs         0&P           2 Skilled Worker S         S3268.00         S5042.80         S40.85         S63.03         S41.40         S662.40         S64.40         S102.40         S44.50.20         S33.52         S61.10           2 Skilled Worker S         39.40         1891.20         61.75         2940.00         S39.52         S61.10           1 Equip. Oper, (crane)         40.95         327.60         61.75         494.00         1 Equip. Oper, (crane)         40.95         327.60         61.75         494.00	*					Bare	Inci.	1 Equip. Oper. Oller	35.10	280.80	52.95	423.60		
Skilled Worker         S41.40         S662.40         S64.40         S100.40         S39.80         S61.88           1 Hyd. Jack with Rods         39.40         2521.60         61.25         3920.00         1.05         1.16           1 Hyd. Jack with Rods         84.00         32.40         1.05         1.16         1.1	Crew C-17E	Hr.	Daily	Hr.	Daily	Costs	0&P	3 Coort burket S C V		\$76.00		03,661	54.05	50.75
Skilled Workers         33.40         2521.60         61.25         3920.00         311.60           Hyd. Jack with Rods         84.00         92.40         L.05         1.15         Crew C-24         Hr.         Daily         Hr.         Daily         Costs         08.0           1 Hyd. Jack with Rods         53268.00         55042.80         \$40.85         \$63.03         Science         Science         Science         Science         Costs         08.0           2 Skilled Workers         39.40         1891.0         61.25         2940.00         Science	2 Skilled Worker Foremen	\$41.40	\$662.40	\$64.40	\$1030.40	\$39,80	\$61.88	AD L H. Dalo Table	-	00.010		00.000 \$4450.00	\$97.91	\$111.04
I Hyd. Jack with Rods         84.00         92.40         L.05         1.15           10 LH,, Daly Totals         53268.00         55042.80         \$40.85         \$63.03           2 Skilled Worker Foremen         \$41.40         \$662.40         \$64.40         \$10.25         \$0&P           2 Skilled Worker S         39.40         1891.20         61.25         2940.00         1 Equip. Oper. (crane)         40.95         \$327.60         61.75         494.00         1 Equip. Oper. (crane)         40.95         \$327.60         61.75         494.00         1 Equip. Oper. (crane)         35.10         298.80         \$238.80         \$238.80         \$238.80         \$243.80         \$243.80         \$243.80         \$243.80         \$249.80	8 Skilled Workers	39.40	2521.60	61.25	3920.00		1000	No Lin, Dary Iolais		00012.4U		0440U.20	007.01	0111.20
View Cx2*         rm.         Camp         rm.         Camp         rm.         Camp         Costs         Costs <thcosts< th=""> <thcosts< th=""> <thcosts< <="" td=""><td>I Hyd. Jack with Rods</td><td></td><td>84.00</td><td></td><td>92.40</td><td>1.05</td><td>1.16</td><td>Craw C.24</td><td>. He</td><td>Daily</td><td>He</td><td>Daily</td><td>Bare</td><td>Incl.</td></thcosts<></thcosts<></thcosts<>	I Hyd. Jack with Rods		84.00		92.40	1.05	1.16	Craw C.24	. He	Daily	He	Daily	Bare	Incl.
2 Stated Worker S 39,40 Stock-40 Stock-	80 L.H., Daily Totals		\$3268.00		55042.80	\$40,85	\$53.03	2 Collect Martin Country	205	Carro an	264.40	canan kn	0000	000
I Equip. Oper. (crane) 40,95 32,46 (0.1,20 0.1,20 2940,00 1.50 2940,00 1.50 1.50 494,00 1.50 1.50 494,00 1.50 1.50 1.50 1.50 1.50 1.50 1.50 1.								2 Skilled Worker Foremen	3941.40	1901-00	61.25	2030.00	309.92	301.10
1 Fearin One Dire 35 10 220 80 52 45 40								I Engin Oper (crane)	40.95	377.60	61.25	494.00		
								I Equip. Oper. Ofer	35.10	280.80	52.95	423.60		

I Equip. Oper. Oller I Lattice Boom Crane, 150 Ton

80 L.H., Daily Totals

1885.00

\$5047.00

2073.50

\$6961.50 \$53.09

23.56

25.92

\$87.02

RB1010-100 Floor Systems Cost

#### Table B1010-101 Comparative Costs (\$/S.F.) of Floor Systems/Type (Table Number), Bay Size, & Load

	1	Ca	st-In-Pla	ce Concr	rete		Pre	cast Concr	rete		St	ructural St	eel		Wo	bod
Bay Size	1 Way BM & Slab B1010-219	2 Way BM & Slab B1010-220	Flat Slab B1010-222	Flat Plate B1010-223	Joist Slab B1010-226	Waffle Slab B1010-227	Beams & Hollow Core Slabs B1010-236	Beams & Hollow Core Slabs Topped B1010-238	Beams & Double Tees Topped B1010-239	Bar Joists on Cols. & Brg. Walls B1010-248	Bar Joists & Beams on cols. B1010-250	Composite Beams & C.I.P. Slab B1010-252	Composite Deck & Slab, W Shapes B1010-254	Composite Beam & DK., Lt. Wt. Slab B1010-256	Wood Beams & Joists B1010-264	Laminated Wood Beams & Joists B1010-265
							Su	perimposed	d Load = 40	) PSF					15	1 m m
15 x 15	15.40	14.60	13.05	12.60	16.05	-	-	-		- 3	-	-	-	-	12.51	13.40
15 x 20 20 x 20 20 x 25 25 x 25	15.50 15.75 16.05 16.15	15.35 16.20 17.05 17.50	13.50 13.95 15.05 15.45	13.50 13.50 14.90 15.20	16.20 16.25 16.40 16.20		21.31 20.63 21.63	24.00 22.95 24.65		11.53 11.79 13.61 14.41	13.65 14.69 16.87 17.95	22.00 22.65	19.30 20.75 21.05 23.45	19.35 18.95	15.78 14.93 — —	13.40 13.61 —
25 X 30 30 X 30	18.35	10.40	10.00	-	17.00	18.50	20.75	23.55	23.75	14.04	18.73	24.50	25.70	19.35	-	-
30 x 35 35 x 35 35 x 40 40 x 40	19.10 20.55 21.00	21.50 22.60 23.95	18.65 18.95 —	1 1 1	18.15 18.35 19.05 19.70	18.85 19.75 20.40 21.20	21.16 22.26 22.40 23.40	24.35 24.90 25.75 26.75	21.00 23.55	16.48 16.92 —	21.00 21.55 —	25.55 26.60 28.80	28.10 28.60 29.50	20.20 21.30 23.40		
40 x 45	-	-	-	-	20.50	21./5		_	22.15		_	_	_			-
40 % 90	-	-	-	_			- Su	nerimnoser	11 oad - 7	5 PSF						
15 x 15	15.60	14.85	13.25	12.65	1610	-	-	-	-	_	-	-	-	-	15.53	16.63
15 x 20 20 x 20 20 x 25 25 x 25	16.10 17.15 17.60 17.55	16.65 17.60 19.30 19.05	14.05 14.65 16.05 16.30	14.10 14.20 15.20 15.90	16.90 17.15 17.30 17.25		22.41 20.63 22.38	25.10 23.95 24.65	111	12.52 13.38 15.57 15.36	15.54 16.90 17.76 19.50	 24.55 26.00	21.05 23.20 25.65 26.75	19.95 20.65	19.41 19.19 —	18.30 18.05 —
25 x 30 30 x 30 30 x 35 35 x 35	17.75 19.85 20.15 22.40	20.10 21.80 22.70 23.20	17.60 18.60 19.90 20.40	1 1 1	17.65 18.15 18.45 19.35	18.25 19.00 18.85 20.35	21.32 22.18 22.21 23.16	24.70 25.85 24.50 26.80	22.35 23.75 —	15.75 16.92 19.35 20.75	20.00 21.55 24.20 26.05	27.65 27.30 29.40 30.40	28.05 30.00 31.45 32.95	20.35 20.75 21.75 23.95		1 1 1
35 x 40	22.80	24.95	-	1	19.95	21.20			22.22	-	-	32.75	33.95	25.15	-	-
40 x 40	-	-	-	-	20.25	22.15			24.20		_		_	_	_	
40 x 45 40 x 50	-	_	_	-	20.70	22.70	_	_	22.25		-	_	-	-	_	-
10 1 00							Su	perimposed	Load = 125	5 PSF			a			
15 x 15 15 x 20 20 x 20	15.90 16.80 17.95	15.70 18.05 18.20	13.75 14.70 15.70	13.05 14.95 15.00	16.40 17.35 17.45	-	1	-		14.83 16.74			24.15 26.05		22.65 27.20 36.55	24.25 27.90 26.90
20 x 25 25 x 25 25 x 30	18.75 20.50 20.60	19.70 20.65 21.90	17.25 17.45 18.35	16.20 16.70	18.25 19.25 19.05	17.80 18.55 18.80	-		-	16.68 18.00 19.15	20.80 22.75 24.10	27.55 29.65 32.45	30.25 32.10 31.40	24.20 21.70 23.55	-	
30 x 30 30 x 35 35 x 35	21.25 22.65 24.10	23.15 24.95 26.10	19.35 20.65 21.05	1 1 1	19.30 19.40 19.45	19.35 20.00 20.85		111		21.30 22.00 24.35	26.95 27.45 28.65	32.35 36.15 35.45	35.05 37.50 38.70	24.70 25.45 27.85	=	1 1
35 x 40	24.35	26.40	-	-	19.95	22.05	1	E	-3-	E	1	38.00	40.10	28.45	_	-
40 x 40 40 x 45	2	2	1	_	21.50	23.70	<u></u>			-22	8 <del>24</del>	-	-	-	-	-
40 x 50		-	-		-	-			(1 <del></del>			100	0.77	-	-	-
							Su	perimposed	Load = 200	) PSF					10.05	12.05
15 x 15 15 x 20 20 x 20	16.65 18.30	16.85 19.55	14.35 15.15		17.05 18.05		-		-		-	-	29.35 30.65	-	43.35 39.10	42.00 37.20 39.30
20 x 25 25 x 25	20.35 22.40	21.65 23.90	17.90 18.10	1	19.30 20.05	18.75 19.15		-	-	-	_	33.90 35.10	33.30 36.45	26.85 28.70	-	
25 x 30 30 x 30 30 x 35	22.55 23.80 24.20	24.15 25.05 26.65	19.30 20.55	-	20.25 20.40 21.05	20.45 21.30 22.15	_			Ξ	E D	37.60 39.45 42.65	46.40 44.95	29.30 29.35		
35 x 35 35 x 40	26.30	27.50	-	-	20.95	22.60	-			-	-	43.85	49.55 50.65	32.05		-
40 x 40	-		_	-		-		2.1	: <u>2</u>	2	-	_	10	_	-	-
40 x 45	-	-	-	-	-	-				-		-	-	-		-
40 x 50	-	-		-		-		-	-		1077	1	-	2010	-	-

<b>B10</b>	Superstru	cture						
B10	10 Floor	Construction	Né					
B10	10 229		Precast	Plank with	No Topping	í.		
	SPAN	SUPERIMPOSED	TOTAL	DEAD	TOTAL	CC		
	(FT.)	LOAD (P.S.F.)	DEPTH (IN.)	LOAD (P.S.F.)	LOAD (P.S.F.)	MAT.	INST.	TOTAL
1700	45	40	12	70	110	9.15	1.88	11.03
B10	10 230	P	recast Plan	k with 2" C	oncrete Top	ping		
	SPAN	SUPERIMPOSED	TOTAL	DEAD	TOTAL	CC	OST PER S.F.	
	(FT.)	LOAD (P.S.F.)	DEPTH (IN.)	LOAD (P.S.F.)	LOAD (P.S.F.)	MAT.	INST.	TOTAL
2000	10	40	6	75	115	7.25	5.20	12.45
2100		75	8	75	150	8.35	4.74	13.09
2200		100	8	75	175	8.35	4.74	13.09
2500	15	40	8	75	115	8.35	4.74	13.09
2600		75	8	75	150	8.35	4.74	13.09
2700		100	8	75	175	8.35	4.74	13.09
2800	20	40	8	75	115	8.35	4.74	13.09
2900		75	8	75	150	8.35	4.74	13.09
3000		100	8	75	175	8.35	4.74	13.09
3100	25	40	8	75	115	8.35	4.74	13.09
3200		75	8	75	150	8.35	4.74	13.09
3300		100	10	80	180	9.05	4.41	13.46
3400	30	40	10	80	120	9.05	4.41	13.46
3500		75	10	80	155	9.05	4.41	13.46
3600		100	10	80	180	9.05	4.41	13.46
3700	35	40	12	95	135	9.50	4.15	13.65
3800		75	12	95	170	9.50	4.15	13.65
3900		100	14	95	195	10.15	3.94	14.09
4000	40	40	12	95	135	9.50	4.15	13.65
4500		75	14	95	170	10.15	3.94	14.09
5000	45	40	14	95	135	10.15	3.94	14.09

31010	241		W Sha	ipe Beams a	& Girders			
BA	V SIZE (FT)	SUPERIMPOSED	STEEL FRAMING	FIREPROOFING	TOTAL LOAD	00	OST PER S.F.	
BE	AM X GIRD	LOAD (P.S.F.)	DEPTH (IN.)	(S.F. PER S.F.)	(P.S.F.)	MAT.	INST.	TOTAL
50	25x30	40	16	.632	50	9.10	2.65	11.75
00	1	40	21	.76	90	12.55	3.57	16.12
50 1		75	24	.857	125	14.95	4.21	19.16
00		125	30	.983	175	18.70	5.40	24.10
50		200	33	1.11	250	23.50	5.50	29
00	30~25	40	16	.532	50	8.35	2.40	10.75
50	JUALJ	40	21	.672	96	12.80	3.56	16.36
1 1		75	24	.702	131	15.20	4.15	19.35
		125	27	1.020	175	19.75	5.50	25.25
00		200	30	1.160	250	25	6.85	31.85
10	20-25	40	18	.569	50	8.75	2.51	11.26
10	JUKEJ	40	24	740	90	12.20	3.47	15.67
100		75	24	787	125	15.25	4.23	19.48
		125	24	.874	175	19	5.40	24.40
		200	30	1.013	250	23.50	5.30	28.80
N	20-25	40	16	637	50	9.10	2.66	11.76
20 J	30720	40	24	839	90	12.90	3.72	16.63
		75	24	919	125	15.65	4.42	20.07
20 J		125	27	1.02	175	19.75	5.70	25.45
		200	30	1.160	250	25	5.70	30.70
0	20-20	200	21	52	50	9.35	2.63	11.98
	30230	40	24	629	103	14.45	3.93	18.38
		40	20	715	138	17.20	4,64	21.84
10 1		/0	30	822	206	22.50	6.30	28.80
50	11	120	26 -	978	281	25.50	5.60	31.10
00	22.00	200	00	610	50	9.75	2.80	12.55
0	30X30	40	24	706	90	13.20	3.67	16.87
0		40	24	010	125	15.60	4.33	19.9
1,		/5	27	010	175	20	5.70	25.70
HO O	II	125	30	.910	263	24.50	5.55	30.05
50		200	33	.333	50	10.45	297	13.42
30	30x30	40	10	.031	an	14.25	4	18.29
10		40	24	000	105	17	4.73	21.7
10 1		75	27	.033	123	21	6.05	27.0
50	II	125	30	1.010	1/5	21	5.75	30.7
0		200	36	1.148	200	10.70	2.04	13.6
iO	30x35	40	21	800.	50	15.95	4.27	20.1
0	11	40	24	100.	109	10.05	515	24.4
50 1		75	33	./32	100	19.20	5.60	20.6
00		125	36	.802	225	24	0.00	30.0
50		200	36	.888	300	31.30	0.00	12.0
00	30x35	40	24	.554	50	9,40	2.00	12.0
20	1-1	40	24	.655	90	13.80	3./9	1/.0
40		75	30	.751	125	17.25	4.68	21.9
00		125	33	.845	175	21	5.90	26.9
50		200	36	.936	263	27.50	6.10	33.6
00	30x35	40	21	.644	50	10.10	2.90	13
20	11	40	24	.733	90	14.55	4.02	18.5
40		75	30	.833	125	18.30	4.98	23.2
60		125	36	.941	175	21	5.95	26.9
100		200	36	1.03	250	28	6.25	34.2

B10	10 Floor	Construction							
B10	10 229		Precast	Plank with	No Topping	J			
	SPAN	SUPERIMPOSED	TOTAL	DEAD	TOTAL	COST PER S.F.			
	(FT.)	LOAD (P.S.F.)	DEPTH (IN.)	LOAD (P.S.F.)	LOAD (P.S.F.)	MAT.	INST.	TOTAL	
1700	45	40	12	70	110	9.15	1.88	11.03	
B10	10 230	P	recast Plan	k with 2" C	oncrete Top	ping			
_	SPAN	SUPERIMPOSED	TOTAL	DEAD	TOTAL	C	OST PER S.F.		
	(FT.)	LOAD (P.S.F.)	DEPTH (IN.)	LOAD (P.S.F.)	LOAD (P.S.F.)	MAT.	INST.	TOTAL	
2000	10	40	6	75	115	7.25	5.20	12.45	
2100		75	8	75	150	8.35	4.74	13,09	
2200		100	8	75	175	8.35	4.74	13.09	
2500	15	40	8	75	115	8.35	4.74	13.09	
2600		75	8	75	150	8.35	4.74	13.09	
2700		100	8	75	175	8.35	4.74	13.09	
2800	20	40	8	75	115	8.35	4.74	13.09	
2900		75	8	75	150	8.35	4.74	13.09	
3000		100	8	75	175	8.35	4,74	13.09	
3100	25	40	8	75	115	8.35	4,74	13.09	
3200		75	8	75	150	8.35	4.74	13.09	
3300		100	10	80	180	9.05	4.41	13.46	
3400	30	40	10	80	120	9.05	4.41	13.46	
3500		75	10	80	155	9.05	4.41	13.46	
3600		100	10	80	180	9.05	4.41	13.46	
3700	35	40	12	95	135	9.50	4.15	13.65	
3800		75	12	95	170	9.50	4.15	13.65	
3900		100	14	95	195	10.15	3.94	14.09	
4000	40	40	12	95	135	9.50	4.15	13.65	
4500		75	14	95	170	10.15	3.94	14.09	
5000	45	40	14	95	135	10.15	3.94	14.09	

### **B1010** Floor Construction



Description: Table below lists costs (\$/S.F.) for a floor system using composite steel beams with welded shear studs, composite steel deck, and light weight concrete slab reinforced with W.W.F. Price includes sprayed fiber fireproofing on steel beams.

Design and Pricing Assumptions: Structural steel is A36, high strength bolted.

Composite steel deck varies from 22 gauge to 16 gauge, galvanized.

Shear Studs are 3/4". W.W.F., 6 x 6 - W1.4 x W1.4 (10 x 10) Concrete f'c = 3 KSI, lightweight. Steel trowel finish and cure. Fireproofing is sprayed fiber (nonasbestos).

Spandrels are assumed the same as interior beams and girders to allow for exterior wall loads and bracing or moment connections.

Sustam Components			COST PER S.F.			
System Components	QUANTITY	UNIT	MAT.	INST.	TOTAL	
SYSTEM B1010 256 2400						
20X25 BAY, 40 PSF S. LOAD, 5-1/2" SLAB, 17-1/2" TOTAL THICKNESS						
Structural steel	4.320	Lb.	7.26	1.73	8.99	
Welded shear connectors 3/4" diameter 4-7/8" long	.163	Ea.	.12	.30	.42	
Metal decking, non-cellular composite, galv. 3" deep, 22 gauge	1.050	S.F.	3.08	.90	3.98	
Sheet metal edge closure form, 12", w/2 bends, 18 ga, galv	.045	L.F.	.26	.10	.36	
Welded wire fabric rolls, 6 x 6 · W1.4 x W1.4 (10 x 10), 21 lb/csf	1.000	S.F.	.20	.34	.54	
Concrete ready mix, light weight, 3,000 PSI	.333	C.F.	2.58		2.58	
Place and vibrate concrete, elevated slab less than 6", pumped	.333	C.F.		.47	.47	
Finishing floor, monolithic steel trowel finish for finish floor	1.000	S.F.		.78	.78	
Curing with sprayed membrane curing compound	.010	C.S.F.	.06	.08	.14	
Shores, erect and strip vertical to 10' high	.020	Ea.		.38	.38	
Sprayed mineral fiber/cement for fireproof, 1" thick on beams	.483	S.F.	.28	.43	.71	
TOTAL			13.84	5.51	19.35	

B10	10 256		Composi	te Beams, I	Deck & Slai	3		
	BAY SIZE	SUPERIMPOSED	SLAB THICKNESS	TOTAL DEPTH	TOTAL LOAD	C	OST PER S.F.	
	(FT.)	LOAD (P.S.F.)	(IN.)	(FTIN.)	(P.S.F.)	MAT.	INST.	TOTAL
2400	20x25	40	5-1/2	1 - 5-1/2	80	13.85	5.50	19.35
2500	BB1010	75	5-1/2	1 - 9-1/2	115	14.40	5.55	19.95
2750	-100	125	5-1/2	1 - 9-1/2	167	17.70	6.50	24.20
2900		200	6-1/4	1-11-1/2	251	19.85	7	26.85
3000	25x25	40	5-1/2	1-91/2	82	13.70	5.25	18.95
3100	0.000	75	5-1/2	1-11-1/2	118	15.30	5.35	20.65
3200		125	5-1/2	2 - 2-1/2	169	15.95	5.75	21.70
3300		200	6-1/4	2-6-1/4	252	22	6.70	28.70
3400	25x30	40	5-1/2	1 - 11-1/2	83	14	5,20	19.20
3600		75	5-1/2	1 - 11-1/2	119	15.10	5.25	20.35
3900		125	5-1/2	1 - 11-1/2	170	17.60	5.95	23.55
4000		200	6-1/4	2 - 6-1/4	252	22	6.80	28.80
4200	30x30	40	5-1/2	I · 11·1/2	81	13.95	5,40	19,35
4400		75	5-1/2	2 · 2·1/2	116	15.15	5.60	20.75
4500		125	5-1/2	2 - 5-1/2	168	18.40	6.30	24.70
4700		200	6-1/4	2 - 9-1/4	252	22	7.30	29.30
4900	30x35	40	5-1/2	2+2-1/2	82	14.65	5.55	20.20
5100		75	5.1/2	2 - 5-1/2	117	16.05	5.70	21.75
5300		125	5-1/2	2 - 5-1/2	169	19	6.45	25.45
5500		200	6-1/4	2 - 9-1/4	254	22	7.35	29.35