

Bar Chart/Progress Schedule

Monday, March 2, 2009



Natalie Bryner

Construction Management Option
Faculty Consultant: Dr. Anumba

Constitution Center

400 7th Street SE, Washington, DC 20024

NATALIE L. BRYNER

CONSTRUCTION MANAGEMENT OPTION

CONSTITUTION CENTER

400 7TH STREET SE, WASHINGTON, DC 20024



BUILDING STATISTICS

- Size: 1,500,000-SF base building and 600,000-SF parking garage
- Number of Stories: Three-level underground parking garage, 10 stories + Pent House
- Occupancy Type: Class A Office Space
- Cost: \$246 Million GMP
- Construction Dates: July 2007 - November 2009
- Delivery Method: Design-Bid-Build
- LEED Gold Project



MECHANICAL & ELECTRICAL

- Centralized Plant in the Penthouse Housing:
 - Two 800 h.p. Boilers
 - One 350 h.p. Boiler
 - Three 1200 ton Trane Chillers
 - Eight 30,000 CFM Trane Air Handlers
 - Eight 30,000 CFM Semco Energy Recovery Units
 - Four 1200 ton Cooling Towers utilizing 6,700 Active Chilled Beams
- Power distribution system of 13.8 kVA feed from four primary switchgear connected to Pepco feeders
- 10 secondary 4000A transformers within the garage and Pent House levels
- Two 1000 kilowatt generators are roof mounted to provide power back-up to the critical building systems during a power outage
- Two dedicated chiller/purifier drinking water systems that continuously circulate water throughout the building
- Custom made Chilled-Beam System from Germany

PROJECT TEAM

- Owner/Developer: David Nassif Associates
- General Contractor: James G. Davis Construction Corporation
- Owners Representative: Kramer Consulting
- Architect: SmithGroup, Inc.
- MEP Engineer: SmithGroup, Inc.
- Civil Engineer: Wiles Mensch Corporation
- Structural Engineer: SK&A

STRUCTURAL

- Precast panels found at all four corners of the building, which frame the spandrel glass
- Blast resistant curtainwall throughout at Streetscape and Courtyard, with floor two being the most resistant including an air barrier system
- Metal panel on the Pent House level to conceal the MEP equipment
- Blast protection in garage tenant space, entrance ramp, internal ramps, electrical rooms, telecom rooms, elevator shafts, egress stairs, and exposed columns
- Two-way waffle slab on all floors except the Pent House

ARCHITECTURE

- Renovation of an existing building, originally constructed in 1976 and occupied by the Department of Transportation (DOT)
- 4 separate, but integrated quadrants that have their own elevator, stairs ways, bathrooms, electrical closets, communication closets
- One acre of courtyard that is a private, secure green space with fountain, seating areas, sculpture, and 32 Honey Locust Trees that are 11'-15' tall
- White Marble and Jerusalem Limestone are located around the first level of the building, creating a boarder for the spandrel glass located at the storefront entrances
- Built-up roofing system and metal panels used to conceal the MEP equipment on the Pent House level



RENDERINGS PROVIDED BY SMITHGROUP, INC. AND STUDIO CHRISTEN

Milestone One (January 26, 2009):

~~TROX USA, Inc. Site Visit
Research the typical costs of an HVAC system
Become familiar with the curtain wall panels and installation requirements
Research weather during the installation duration
Determine the Rules of Credit using R.S. Means
Interview DAVIS to the availability of the daily curtainwall count~~

Milestone Two (February 9, 2009):

~~Evaluate publications on the chilled beams
Interview DAVIS project team for schedule, cost, and site logistics
Interview SmithGroup to find out why they chose the chilled beams
Interview Pierce Associates to determine how they familiarized themselves with the system
Compare chilled beam to typical system
Interview DAVIS for commissioning requirements
Send out Interview/Survey questions to industry members
Interview DAVIS with curtainwall questions
Create and compile Data Collection Tool –**Received the CD on Saturday**
Interview DAVIS to determine the schedule requirements
Interview the subcontractor to determine the renovation steps
Create and send out survey to be sent to industry members~~

Milestone Three (February 23, 2009):

~~Research current commissioning systems
Finalize Chilled Beam Research
Calculate expected and actual productivity
Calculate expected performance factor
Calculate planned and actual manning
Calculate actual percent complete
Calculate control budget
Determine the factors for delays
Research structural requirements for parking garage
Calculate loads the slabs are experiencing~~

Reason why Milestone was not met – Spread sheets are made, however I just received the CD on Saturday and was in Akron, OH for the SWE Region G Conference till Sunday evening.
Recovery Plan – I plan to work on it at the end of this week after my two exams. I will be utilizing spring break to get myself back on schedule.

Milestone Four (March 16, 2009):

Compare Constitution Center data to CE 533 semester project
Research how the waffle slab were renovated
Research what qualified a section to be renovated
Perform a two-way reinforced concrete system analysis
Compare current renovation system to two-way reinforced concrete system
Determine the safety requirements for the metro entrance on Constitution Center
Research the OSHA requirements
Interview DAVIS for special safety techniques
Compile survey results

