Prepared by **KSENIA TRETIAKOVA** Structural Option AE Consultant: Dr. Andres Lepage

#### 10.19.2011

Architectural Engineering Pennsylvania State University 2012

# Southwest Housing, Arizona State University

Technical Report #2 Floor Systems

# Southwest Student Housing

Tempe, Arizona Technical Assignment #2

# **Table of Contents**

Executive Summary	1
Introduction	2
Structural Systems	3
Foundation	
Floor System	
Gravity and Lateral System	
Roof System	5
Codes, References and Standards	6
Materials	7
Malenais	
Load Calculations	8
Gravity Loads	
Floor System Analysis	9
Existing Floor System - Composite Deck	9
Alternative Floor System - Non-Composite Deck	
Alternative Floor System - Long-Span Deck	
Alternative Floor System - Post-Tensioned Concrete	16
Summary and Conclusions	
Appendices	
Appendix A – Building Information Notes	
Appendix B – Gravity Load Calculations	
Appendix C – Existing Floor System: Composite Deck	
Appendix D – Alternative Floor System: Non-Composite Deck	
Appendix E – Alternative Floor System: Long-Span Deck	
Appendix F – Alternative Floor System: Post-Tensioned Concrete	
Appendix G – Cost Estimate Documentation	
Appendix H – Additional References	

#### Executive Summary | 1 Southwest Student Housing Tempe, Arizona Technical Assignment #2

## **Executive Summary**

In the report that follows, the existing floor system was analyzed alongside 3 potential alternative floor systems to investigate the advantages and disadvantages of each design. Each floor system was evaluated with regards to a typical bay in the building, which stretches from the end of one core to the start of the next. The typical bay dimensions are 62'-6"x52', with 5 bays of beams for the girders, spaced at 12'-6". The primary factors affecting the floor system sizing were the need for a 2-hr fire rating on each floor, and the deflection requirements.

The floor systems studied in this report are as follows:

- The existing system [3", 20 gauge composite deck with 3.25" lightweight concrete topping on structural steel frame]
- A non-composite system [3", 16 gauge form deck with 3" normal weight concrete topping on structural steel frame]
- A long-span deck system [6", 14 gauge form deck with 3.25" lightweight concrete topping on structural steel frame, 4 bays of beams instead of the existing 5 bays]
- A post-tensioned 2-way concrete slab system [7" slab with 14" wide shallow beams running in the long direction; (30) ½" φ 7-wire, 270 ksi tendons running in the wide shallow beams, banded in 3 bundles of 10 tendons, (64) if the same 7-wire 270 ksi tendons running in the short direction, distributed over the 62'-6" span]

A cost analysis is included, as well as a comparison of self-weight, constructability, architectural impact, foundation impact and lateral system impact.

Ultimately, the existing system was deemed the most appropriate for the construction style of this building. The existing system weighs 59 lb/square foot, is 2' deep, and costs about \$19.00/square foot. The non-composite system weighs 14 lb/square foot more for the same height, and costs about \$1.00/square foot more. The long-span deck system weighs almost the same as the existing system, but costs about \$8.00/square foot more for the same floor depth. Potential for decreasing the cost and optimizing this system is presented in the conclusions. The post-tensioned concrete system weighs the most of the systems investigated, at 99 lb/square foot. This system has the smallest depth, reducing floor thickness by 10" from the existing system, and provides the overall lowest cost at about \$9.30/square foot. Of all of the systems, the likelihood for the foundation and lateral systems to be impacted results the most from the post-tensioned system, due to its high self-weight.

#### Introduction | 2 Southwest Student Housing Tempe, Arizona Technical Assignment #2

# Introduction

The Southwest (SW) Student Housing building is a 20-story high-rise for students attending Arizona State University. The building site is located in a downtown area, at



Figure 1: Site Location, 1000 Apache Blvd. East, Tempe, AZ

1000 Apache Blvd. East in Tempe, Arizona (see Figure 1, the site is highlighted in red<sup>1</sup>). The building plans are designed to accommodate 528 beds in 268 units, with an emphasis on modularity for ease and economy of construction. There is additional potential to include an automated parking

facility on the first level, which can be accounted for in the initial building design. A rendering of the potential building design can be observed on the front cover of this report.

This particular building has a unique structure designed for easy assembly on site to enable extremely fast and efficient construction. The building's gravity and lateral systems are one and the same: a series of three 8-inch thick concrete cores, 25' wide and 25' long. These cores are constructed first using slip-forms to within a 1/8" tolerance. The roof of the building is then assembled on the ground around the cores in two parts and lifted into place using six 75-ton strand jacks. Each subsequent floor is then assembled on the ground, half the floor area at a time (with the joint located at the precise halfway point of the floor plan, as indicated in Figure 2), and lifted into place. The building is essentially constructed from the top, down.

The floors are constructed using metal deck with lightweight concrete and structural steel beams. Each floor has a similar and regular floor plan (and thus, loading), with residential areas for 23' on each side of a 6'-wide corridor running through the center of the building, lengthwise (see Figure 2 below).




Figure 2: Typical Building Floor Plan

<sup>&</sup>lt;sup>1</sup> Taken from http://maps.google.com

#### Structural Systems | 3 Southwest Student Housing Tempe, Arizona Technical Assignment #2

## **Structural Systems**

#### Foundation

The SW Student Housing building will exert significant loads to the foundation elements, according to the geotechnical report for the area. As a result, this building will require a deep foundation system that penetrates through to the second layer of soil on the site to limit settlement. The first layer of the site is Silty Sand and Poorly Graded Sand for a depth range from 10' to 35'. The second layer of soil on the site is Sand Gravel Cobble, from a depth of 35' to 100'.

The geotech report recommends drilled piers, with no pier shaft sized to a diameter of less than 12". Each pier should penetrate at least twice the shaft diameter into the second layer of soil. The predicted settlement for this pier configuration is less than one inch for an isolated pier shaft with a diameter of less than 60".

#### **Floor System**

The floor system is the same on all floors. This system consists of 3-1/4" lightweight concrete on 3" metal deck, with a minimum gauge of 20. The composite deck is supported by a structural steel frame, with wide-flange sizes ranging from W14x22 infill beams to W24x176 interior girders, as prescribed by the typical framing plan shown in Figure 3, and reiterated in the notes included in Appendix A. All four girders span the length of the building (250'), and all typical beams span the width of the building (52'). Infill beams span either 12'-6" or 24', depending on their location within the building. The typical members are labeled in Figure 3. Every structural steel element in the typical frame is cambered. Some members are cambered up to 4 inches at the cantilevered ends (See Appendix A for the project structural engineer's camber diagrams).





Figure 3: Typical Framing Plan (building is symmetric about line 14)

#### Structural Systems | 4 Southwest Student Housing Tempe, Arizona Technical Assignment #2

#### Gravity and Lateral System

Unlike some conventional construction, this building has no columns. The three 8inch thick, 25'x25' (at the centerline) concrete cores carry all of the gravity weight of each floor. As a result, the floors are cantilevered off of the cores (spaced at 62'-6" clear span), which support the structural steel floor framing via a wide-flange beam inserted through each of the four corners in every core, as illustrated in Figure 4. During construction, half of a floor is lifted via the 75-ton strand jacks and then fitted into place using the aforementioned corner details. The cores are designed as walls using ACI 318-05. As a result, each core has a minimal amount of reinforcement through the center (one layer of the smallest permitted rebar size by code).



Figures 4.1 and 4.2: Corner detail at every floor, framing into the interior girder to support each level

The concrete cores are also the building's sole lateral system, and provide lateral bracing in both directions in the form of shear walls. For clarity, the cores are highlighted in the typical building floor plan below in Figure 5, with boundaries at openings selected. It can be observed in Figure 6 on the next page that the openings are only present for a minimal height on each floor so that the shear walls can be reunited via large coupling beams for added rigidity and support. The coupling beams are approximately 2' high, and the floor-to-floor height is 10'.



Figure 5: Typical Building Floor Plan (Core areas are highlighted in red, core walls are highlighted in green)

### **Southwest Student Housing**

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

#### Tempe, Arizona Technical Assignment #2




Figure 6: Rendering of visible openings in concrete cores

The theory behind this building design seems to be simplicity: a single set of structural elements to resist all loading. The sizing of these elements was carried out using a combination of hand calculations employing ASD, and computer modeling for more precise answers. ASD hand calculations were found to be generally with 10% of the computer modeling outputs, which used the LRFD method of design.

#### **Roof System**

The roof system is a simple, long-lasting construction of the typical floor framing (3-1/4" lightweight concrete with 3" metal deck, minimum 20 gauge), 3" of rigid insulation and an Ethylene Propylene Diene Terpolymer (EPDM) membrane on top. There is no mechanical equipment on the roof- the major mechanical elements will be located on the ground floor, and will serve each unit in the building via a 2-pipe system.

Southwest Student Housing Tempe, Arizona Technical Assignment #2

### Codes, References and Standards

#### **Building Design Codes:**

Model Code:

International Building Code, 2006 Edition, as amended by the city of Tempe, AZ Design Codes:

American Institute of Steel Construction "Specifications for Structural Steel Buildings", AISC 360-05

American Concrete Institute "Building Code Requirements for Structural Concrete", ACI 318-05

#### Structural Standards:

American Society of Civil Engineers "Minimum Design Loads for Buildings and other Structures", ASCE7-05

#### Thesis Codes:

Model Code:

International Building Code, 2006 Edition

Design Codes:

American Institute of Steel Construction "Specifications for Structural Steel Buildings", AISC 360-05 (13<sup>th</sup> ed.) and AISC 360-10 (14<sup>th</sup> ed.) American Concrete Institute "Building Code Requirements for Structural

Concrete", ACI 318-05

Structural Standards:

American Society of Civil Engineers "Minimum Design Loads for Buildings and other Structures", ASCE7-05

#### **Deflection Criteria:**

Limit Unfactored Live Load deflections to L/360 or less Limit Total (Service) Load deflections to L/240 or less Limit building drift to h/400 or less

#### Fire Safety:

Floor systems must have a minimum 2-hour fire rating

# Materials | 7 Southwest Student Housing

Tempe, Arizona Technical Assignment #2

# **Materials**

Structural Steel:

- All Rolled Shapes ASTM A992 Grade 50
- All Plates and Connection Material ASTM A36
- All Tubular Sections ASTM A500 Grade B
- All Pipe Sections ASTM A53 Grade B
- Anchor Rods ASTM F1554

Cast-in-Place Concrete:

- Foundations 4000 psi normal weight
- Slab on Grade 4000 psi normal weight
- Structural Slab on Grade 5000 psi normal weight
- Lightweight Concrete 4000 psi
- Walls (core) 4000 5000 psi

Reinforcement:

- Deformed Bars ASTM A615 Grade 60 typ.; Grade 70 for #9, #10, #11
- Welded Wire Fabric ASTM A195

Welding Electrodes:

• E70xx Low Hydrogen

Bolting Materials:

• ASTM 325 or A490

# Load Calculations

#### **Gravity Loads**

See Appendix B for all calculations, including confirmation of structural steel allowance from typical framing plan and citations for calculating snow load.

#### Construction Dead Load:

Sum (CDL)	59.14 psf
Structural Steel Allowance	11 psf
3-1/4" Lightweight Concrete (110 PCF)	46 psf
3" Metal Deck (20 gage)	2.14 psf

#### Superimposed Dead Load:

Assumed, according to structural engineers	15 psf
Sum (SDL)	15 psf

#### Live Loads:

Building uses

Live Load (LL)	80 psf
Corridors	80 psf
Parking	40 psf
Residential	40 psf

#### Wall Loads:

Sum	15 psf
Curtain Wall	15 psf

#### Snow Loads:

Ground snow load for region	0 psf
Sum	0 psf

#### Floor System Analysis | 9 Southwest Student Housing Tempe, Arizona Technical Assignment #2

### Floor System Analysis

The floor system analyses in this report were carried out for a typical bay in the building plan, as highlighted in blue and outlined with a dashed line in Figure 7. The girders and wide shallow beams of the existing and alternative floor systems run in the East-West direction and span 62'-6". The typical beams and distributed post-tensioning in the existing and alternate systems run in the North-South direction (the short direction). The largest unsupported span is 26', and there is a 13' cantilever off of each support. One of the items that governed each design was the goal fire rating of 2 hours. Every floor system attained at least that rating.

The lateral system in this building is independent of the floor system, and thus was minimally considered in the analysis. Ultimately, the most important feature of the floor systems (with regard to the lateral system) was the floor weight, which is also discussed in the following sections.

An approximate cost evaluation was carried out for each floor system, the documentation of which can be found in Appendix G. Cost information was found from the online CostWorks RS Means database using 2008 1st quarter estimates. Any additional information used is included in Appendix H, including prestressing tendon properties and unit reinforcing bar weight. Any of the properties used are highlighted in blue on each of the included references.





Figure 7: Typical floor plan with the typical bay considered for alternate floor systems highlighted in blue

### **Southwest Student Housing**

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

Tempe, Arizona Technical Assignment #2



#### **Existing Floor System - Composite Deck**

The existing floor system design consists of 3" metal deck, 20-gauge minimum, with 3.25" of lightweight concrete to meet fire safety ratings. This system sits on top of structural steel wide flanges, as previously described in the structural systems summary. The estimated floor weight is about 59 lb/square foot (as seen in Load Calculations section), making it the lightest out of the analyzed

systems. The typical framing layout is featured in Figure 8, and a cross section of the floor system can be seen in Figure 9. Analysis of the existing floor system can be found in Appendix C.

The existing floor system has several advantages- the main advantage being the speed with which a floor can be erected. According to the projected schedule, half of a floor can be completed in 2 days: day 1 involves the deck placement and pouring




Figure 9: Cross-section of existing design floor system

concrete, day 2 involves fireproofing and MEP. The moment a half-floor is completed, it is elevated and fastened to the cores at its designated height. The overall cost is approximately \$19.00/square foot, which is only more expensive

Figure 8: Existing design framing layout for the chosen typical bay

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

### Floor System Analysis |11

### Southwest Student Housing

Tempe, Arizona

Technical Assignment #2

than the alternative floor system using post-tensioned concrete. A more indepth cost analysis can be found in Appendix G, for the floor system specified by the actual design, as well as the floor system obtained through the spotcheck calculations from Technical Assignment #1 (featured in Appendix C).

This particular floor system is at a disadvantage because of the overall height of the floor assembly. 3" deck with 3.25" concrete sitting on approximately 18" tall wide flange beams leads to a floor thickness of about 2', on top of the requisite 8' of floor-to-ceiling height for habitability.


Ultimately, the existing floor system is very practical for the intended goals of this building design: low-cost construction that can be erected at high speeds.

Ksenia Tretiakova, Structural Option

AE Consultant: Dr. Andres Lepage

### **Southwest Student Housing**

Tempe, Arizona Technical Assianment #2



#### Alternative Floor System - Non-Composite Deck


Figure 10: Non-composite (form) deck design framing layout for the chosen typical bay

The reasoning behind trying a non-composite deck as an alternative floor system was the commentary given by a member of the design team: he said that, though the existing system is a composite system, the deck does not, in reality, take advantage of the composite action. As a result of this statement, the non-composite deck analysis was carried out to compare the structural steel

and metal deck sizing to the existing system.

The typical framing plan is featured in Figure 10, and a cross section of the system is featured in Figure 11. The calculations carried out for the analysis of the non-composite floor system can be found in Appendix D.

The most notable difference



between the systems is the use of a much heavier gauge deck, thus resulting in a

Figure 11: Cross-section of non-composite floor system

slightly more expensive system. The non-composite floor system consists of 3" form deck, 16 gauge, with approximately the same size beams (compare

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

#### Floor System Analysis | 13

# Southwest Student Housing

Tempe, Arizona

Technical Assignment #2


W24x176 in the existing system vs. W24x146 in the non-composite system). There is a 3" normal weight concrete topping to adhere to the required fire rating, instead of the 3.25" lightweight topping used in the existing system. The overall cost is about \$20.00/square foot, as compared to the existing system's cost of \$19.00/square foot.

Ultimately, the analysis confirmed the statement made by the engineer on the design team for this building. As such, the non-composite system is ranked about even with the composite system in terms of its advantages and disadvantages: the non-composite system also has large floor plenums, but is quick and comparatively easy to construct. The method of construction planned for the existing system could be applied to the non-composite system as well, requiring no change of schedule. The non-composite system weighs about 73 lb/square foot, making it about 15 pounds heavier than the existing composite system. Of all of the analyzed systems, the non-composite system is only lighter than the post-tensioned slab system.

### Southwest Student Housing

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

Tempe, Arizona Technical Assignment #2



#### Alternative Floor System - Long-Span Deck

The third system analyzed was a long-span deck system aimed at reducing the number of beams in the design. This goal was achieved, as can be observed in the typical framing plan shown in Figure 12. An immediate and easily observable disadvantage to long-span deck is the considerably larger deck height. In order to get rid of one of the beams in each typical 62.5' girder span (so that there are only 4 bays instead of 5), the deck had to be sized to withstand 61 lb/square foot of floor weight over 16' spans. The final deck choice was for a 6'' roof and form deck, with references for allowable loads provided by

Diomede Enterprises (see Appendix H for the tables). A cross-section of the deck assembly can be found in Figure 13. Additionally, calculations for the long-span deck design can be found in Appendix E.

As a result of the much larger deck, the beams had to be sized accordingly to maintain the current floor-

to-floor height, which involves the use




Figure 13: Cross-section of long-span deck floor system

Figure 12: Long-span deck design framing layout for the chosen typical bay

10.19.2011 Ksenia Tretiakova, Struc

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

#### Floor System Analysis | 15 Southwest Student Housing

Tempe, Arizona

Technical Assignment #2

of heavy W14's in the place of the lighter W18's used in the existing system to correlate with the height of the W24 girders. This inconvenience of sizing and necessity to invest in heavier members can be seen as a disadvantage of this system.


The long-span deck is the most expensive floor system of all of the choices analyzed, with a cost per square foot of about \$27.60. This cost could be greatly reduced by increasing the floor-to-floor height to allow more room for structural steel members. With regards to constructability, this deck could be assembled much in the same way as the existing floor system, so there would be minimal (if any) hindrance to construction time and schedules. The long-span deck system is a solid floor system, but the overall cost (to maintain current floor heights) greatly cripples any advantages this system could provide, such as fewer beams (a potential, if minimal, increase in the construction speed).

Ksenia Tretiakova, Structural Option

AE Consultant: Dr. Andres Lepage

**Southwest Student Housing** 

Tempe, Arizona Technical Assianment #2



#### Alternative Floor System - Post-Tensioned Concrete

Figure 13: Post-tensioned two-way concrete slab design tendon layout for the chosen typical bay

62'-6"

A post-tensioned concrete system was chosen as another alternative floor system to see if an all-concrete construction would work as well as the existing system, with the potential to reduce the floor-to-floor heights or even squeeze in an extra floor for the current height. The large spans in this building required the use of wide shallow beams with banded tendons in the direction of the girders in the current design, as recommended by Dr. Lepage. In addition to these banded tendons, distributed tendons were required in the short direction (as seen in Figure 14).

Calculations for the post-tensioned concrete slab analysis can be found in Appendix F. These calculations follow an example of post-tensioned concrete design published by the Portland Cement Association, with additional information about tendon drape and wide shallow beam dimensions obtained from the Post-Tensioning Institute's Technical Note 3 and a May 2003 article from Concrete International titled "Guidelines for the Design of Post-Tensioned Floors." The formal references for these sources can be found on the "Thesis References" page of the CPEP website for this building project.

The post-tensioned concrete system was designed with the assumption that 1/2" diameter 7-wire, 270 ksi unbonded tendons would be used for both directions. The final post-tensioned concrete design yielded a 7" thick slab with

#### Floor System Analysis | 17 Southwest Student Housing

#### Tempe, Arizona

#### Technical Assignment #2

14" thick wide shallow beams, 42" in width. In the East-West direction (the long direction), there are (30) tendons running through the 42" wide shallow beams, banded into 3 bundles of 10 tendons. In the North-South direction (the short direction), there are 64 distributed tendons spread through the 62.5' slab width. The tendon drape profiles for both directions can also be found in Appendix F.

This particular design yielded a 14" floor thickness, which is 10" less than the existing floor system. Over the course of 20 floors, that floor thickness reduction yields about 16.5' of extra space, easily allowing for the insertion of another floor in the same building height, resulting in an increase of overall residents from 528 beds to 550 beds (an increase of 22 units). The cost of the post-tensioned system is about \$9.32/square foot, making the post-tensioned concrete system the cheapest (by about \$10) of the floor system choices.

Though the initial perception is that the post-tensioned system is highly economical, the costs and benefits so far mentioned do not take into account the drastically increased construction times involved in this system. The floors will no longer be lifted into the air at a rate of a floor every four days-- concrete needs to cure. The result of this would be a change in construction methodology, and a greatly extended construction schedule. The extended schedule would areatly impact any potential economic benefits of this floor system. Another thing to take into consideration when looking at this floor system is its weight- about 99 lb/square foot. The post-tensioned concrete system is by far the heaviest of the floor systems analyzed in this report, about 40 pounds heavier than the existing system, per square foot. The impact of this drastic increase in weight was not analyzed in depth in this report, but can be hypothesized to have an effect on the required foundations. The increase in the floor weight will also have an impact on the lateral system- there is potential that the current core design will be insufficient to withstand the increased design lateral forces.

Southwest Student Housing Tempe, Arizona

Technical Assignment #2

# **Summary and Conclusions**

Property	Existing - Composite	Non- Composite	Long-Span Deck	Post-Tensioned Concrete				
Self Weight (psf)	59.00	73.00	61.00	99.00				
Foundation Impact		Some	None	Significant				
Total Depth (in)	24.00	24.00	24.00	14.00				
Constructability	Easy	Easy	Easy	Hard				
Architectural Impact		None	None	Significant				
Total Cost per ft <sup>2</sup> (\$)	19.00	19.97	27.60	9.32				
Lateral System Impact = none for all systems, they are independent of the lateral system								
Additional Study?		No	Yes	Yes				

Table 1: Comparison of each floor system design based on listed criteria

The Southwest Student Housing building was designed with a particular construction philosophy. Namely, this philosophy demands easy, modular construction that can be completed at a very high speed. The existing system works very well with that philosophy, as it allows for a whole floor to be lifted into place every 4 days. The two alternative deck systems also operate on similar principles, and as a result, the construction philosophy can be implemented with non-composite and long-span deck designs as well.

The post-tensioned concrete system, on the other hand, poses several problems. The first of these problems is the need for the concrete to cure before it can be lifted into place; this necessity would suck up valuable time and extend the construction schedule, potentially negating any economic advantage it has over the other systems (namely it's comparatively low cost per square foot). The second problem has to do with current laws and practices in the United States: lift-slab construction has been deemed dangerous due to a fatal accident that killed 28 construction works (L'Ambiance Plaza).

This second problem also has potential implications with the other systems, since they operate on the same principle of building the floor on the ground and jacking it up to its required location. Another potential pitfall of the post-tensioned system is the large self-weight, which might require an alteration to the current foundation design. The weight of the post-tensioned system is about 40% higher than the weight of the existing system, which is a significant increase in the building weight. This increase in building weight also has potential to affect the lateral system design, because base shear forces

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

#### Summary and Conclusions | 19

#### Southwest Student Housing Tempe, Arizona

Technical Assignment #2

would be greater, thus causing a potential need for thicker and more heavily reinforced cores.

Despite the downfalls of the post-tensioned system, it does have a great economic benefit because of its small floor thickness and low cost (it could provide base construction savings of about \$2.5 million over the whole building, compared to the existing system). Further study is needed to ascertain whether the economic advantages outweigh the system disadvantages.

The other floor system that is worth addition study is the long-span system. There are no regional building requirements in Tempe, Arizona for the building's zone, which means that there is no real limit on the floor-to-floor heights. There are certainly fiscal and structural reasons to limit floor-to-floor height, but it becomes reasonable to alter them if a system is deemed advantageous enough. The long-span deck system can reduce the structural steel requirements on every floor by at least 200 linear feet, which allows for the system to have an overall potential cost savings compared to the existing system, given free reign to alter floor heights.

Ultimately, the existing system is a good choice for the current building design. The current design could potentially be improved by using long-span deck or posttensioned concrete slab, but there can be no definitive answer until additional study is carried out. With current analyses, as presented in the Appendices, the existing system is the best design with regards to weight, and theoretical construction speed and ease.


Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

#### Appendices | 20 Southwest Student Housing Tempe, Arizona Technical Assignment #1

# Appendices

**Southwest Student Housing** 

Tempe, Arizona Technical Assignment #1




#### Appendix A – Building Information Notes

### Southwest Student Housing

Tempe, Arizona

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

Technical Assignment #1



#### Appendices | 23

# Southwest Student Housing

Tempe, Arizona Technical Assignment #1

HPPENDICES - HPPENDIX A SOUTH WEST STUDENT HOUSING TET H BUILDING INFORMATION - MODEL CODE: IBC 2006 AS AMENDED BY THE CAY OF TEMPE, A REDNA "DESIGN CODES: AISC "SPEC FOR STRUKTURAL STL BLOGS" AISC 360-05 ACL "BUILDING GODE REQUIRE MENTS FOR SPUCTURAL CONC" ACL 318-05 - STRUCTURAL STANDANDS : ASCE 7-05 - 1 HILL USE ASCE 7-05, ALC 13TH ED, ACT 31-05, 16006 · DEFLECTION CRITERIA LASTRUCTURAL STEEL IS ALL CAMBERED TO DEAL W/ HIGH DEFLECTIONS. OUT OF CURIOSITY - HOW DOES ONE ASSEMBLE A CAMBERED STRUCTURAL STEEL ROOK IF THE METHOD IS TO SLIDE BEAMS THEOJEH PLASMA-CUT HOLES ON HYDRAULIC ROLLERS? CHARLIES: 1 FOR LIVE 1 FOR TOTAL H FOR DRIFT AMPAD - STRUCTURAL OVERVIEW: · FOUNDATIONS - HET SPREAD GOTING ACCORDING TO CHARLIE ACCORDING TO SOILS REPORT RECOMMENDATIONS-BLOG WILL EXERT SIGNIFICANT LOADS TO FOUNDATION ELEMENTS. SEMPLOY DEEP FOUNDATION SYSTEM TO LIMIT SEMLEMENTS Acres March 13 T'G PACKAGE : · DRILLED PERS + MAT (5) 350 403 CORE MATS, AXIAL CAPACITY = SKINFRICTION OF SHAFT + END BEARING AT TIP REPIRCTER CRADE BEAMS, Solas DEPTH END BEARING SEAN ON GRADE ON TOP FRICTION I SILTY SAND + POORLY 10-35 O.YKSF GRADED SAND I SAND GRAVEL COBBLE 35-100' 2.5 KSF 21 KSF PIER SHAFTS SHOULD PENETRATE AT LEAST 2.5x PIER & INTO I LAYER & NO PIER \$<12" MIN CLEAR SPACING = 3 × BIGGEST BOS ASENT PIER & PREDICTION! FOR ISOLATED PIER, \$ < 60", SETTLEMENT SI" Charle's . Blog Dogsn't Have, settling blo spans are longer - no differential struc NOTES LOCAL? • FLOOR SYSTEM - TYP. FOR ALL FLOORS - 3.25" LIGHTWEIGHT CONCRETE ON 5" DECK for HAME CARES, CHARLE ASTRICE 4.3" LIGHT MORALT CONCRETE THOPIS CULL ASTRICE 4.3" LIGHT MORALT CONCRETE WHEELING CORRECT 5. WHEELING CORRIGATED SO & LW.C. (P 14 IN PDF) 20 GAGE SUPPORTED BY STRUCTURAL STEEL PRAPHE > TUP. FRAMING. TYP CORE BOT WIRKSO TYP BEAM WIRKHO TYP INFILL BM = WI4 X22 THE WALL 8m - W/1x22. N SEC 1:33 TYP SHOWS TYP. 3 FRAMINE GIRDER= ii. W24×176 -20@ 12'-6" TYP CONTINUOUS EDGE BEAM = WHIX23 · FRAMING SYSTEM - SEE A GOVE FOR FLOOR FRAMING SYSTEM SEE BELOW FOR GRAVITY FRAMING SYSTEM · LATERAL SYSTEM-(3) CONCRETE ORES: 8" THICK, 25' × 25' ON CENTER (KIND OF) SPACED 62'-6" APART (STAPTING ATCOMER.)

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

## Appendices | 24

Southwest Student Housing

Tempe, Arizona Technical Assignment #1


B – Gravity Load Calculations	HIPPENDICES- APPENDIX D
TECH I	Southwest Student Housing
CALCULATED LOADS	
*GRAVITY	
- CONSTRUCTION DEAD LOAD	
· DECK - 3.0 VLI (VULCRAFT CON	MPOSITE DECK) 20 GAGE
3.25" LIGHTWEIGHT G	
DECK WEIGHT = 2.14 PSF	MAX UNSHORED SPAN
CONCRETE WEIGHT = 46 PSF	1 5PAN = 10-6"
TOTAL = 48.14 PSF	
· STRUCTURAL STEEL - ASSUME & S	35PAN= 13'-3"
CHECK CURRENT SIZES:	MAX SPAN ON PLAN? 121-6"
SIZE LENGTH #	WT (K) (ASSUME BELOW DECK
W18×50 (52) 6	15.6K ORIENTATION)
US18×40 52 12	.25K
WKIX22 13 6	1.7K
W24x 176 262.5 2	42.41K MAX SUPERIMPOSED LIVELOAD
AL MMX22 262.5 2	11.6" ON MAX SPAN? 73 PSF
김 씨는 물건에 다 가지를 만들려 다. 여러 가지 않는 것이다.	14634 C VERIEN THAT THIS IS LE OWEN
TYP FLOOR DIMENSIONS	(P55 of NUCOR DECK MAN.)
250'×52'= 13 000	
APPROX. WEIGHT OF STRUCT	VRAL STL:
$\frac{146.3 \times 10^3}{11200} = 11.25$	PSF
STRUCTURAL STEEL-ASSUME	I DCE V
>TOTAL CONSTRUCTION DEAD LOAD =	
	Bergspectronik
- SUPERIMPOSED DEAD LOAD	
→ASSUME SDL OF 15 PSF <- ASS	
- LIVE LOAD	PARTITIONS NOT INCLUDED.
· RESIDENTIAL = 40 PSF	
· PARKING = 40 PSF	
· CORRIDORS = 190 ON FLOORS ABOVE G	ROUND (PSF)
= 100 ON GROUND FLOOR	
(THERE IS A 6! WIDE OBREIDO OF THE BUILDING IN THE LOI	
SIL SI WINELK	T MASS WANT general IN DES IN S-2
LIVE LOAD REDUCTION:	
V/////////////////////////////////////	INCOLOFI
	unitation (10 10 10 10 10 10 10 10 10 10 10 10 10 1
777712227177773	
	- All All All All All All All All All Al
* 81'-3" * 87'-6"	

3

#### **Southwest Student Housing**

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

#### Tempe, Arizona Technical Assignment #1




#### Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

#### Appendices | 26

# Southwest Student Housing

Tempe, Arizona




Appendices | 27

Southwest Student Housing

Tempe, Arizona

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage




#### Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

#### Appendices | 28

### Southwest Student Housing

Tempe, Arizona

Technical Assignment #1



#### Appendices | 29

# Southwest Student Housing

Tempe, Arizona

**Technical Assignment #1** APPENDICES - HAPENDIX F 34 SOUTHWEST STUDENT HOUSING TECH ! SPOT CHECKS (CONTINUED) DEFLECTIONS ? LO (LIVE) LO (TOTAL) A 1872 W 312 - - 1248 W  $= \frac{\omega(4_{2})}{24 \epsilon i} \left[ \frac{(13)^{2}}{2} - (21)^{\frac{2}{2}} + \frac{(12 M 1)}{W 2} + \frac{(12 M 1$ SIMPLY SUPPORTED WI FIL WOWENTS 1563 3123 I= 311 + 329-31 = 320 14 L = 111 881 CANTILEVERED 196: 43.5 PSF - W= 0.544 Y2F . "AMPAD" TOTAL; 43.5+59+15 15F > W= 1.4169 KLF END SPANS:  $\frac{1}{360} = \frac{13 \times 12}{360} = 0.43^{\circ}$  $\Delta_{UVE} = \frac{(3.549 / iz) 12^4}{8 (2900) 320} \times (328 = 0.03' 0)$ 1 = 12 × 12 = 0.65" A = (1.469/12) 134 TOTAL = (2900) 320 × 1728 = 0.081 " MIDDLE SPAN! 360 = 0.86 Mary = 45.968 PT-K = 551.616 IN-K  $\Delta_{21Ve} = \frac{(0.544/12)(156'')}{24(29000)^{220}} \left| 156^3 - \frac{312^3}{2} + 1972\left(\frac{551.616}{5544/12}\right) + 312^3 + 1248\left(\frac{551.616}{0.544/12}\right) \right| = 0.841 \text{ OK}$ 1 = 1.3" M-10THL = 496.522 57-K = 5958.3 1N-K ATTINE = 4.23 " NG NOTE - THESE DEFLECTIONS DO NOT TAKE INTO ACCOUNT GIRDER DEFLECTIONS QUICK DEFLECTION CALCS FOR SPECIFIED BM SIZE ON TYP. FRAMING PLAN: W18×40 Assume a=2" -> "12= 5.25" PNA #6 \$MA=465 FT-K a= 1:584" < 2" OF I= 1190 m4 END SPANS! DLIVE = 0.008" OF (WILL CHECK OVERALL ATOTAL " 1.022" 04 DEFLECTION MCLUDING MIDDLE SPAN: Auve = 0.226" 01 GIRDER IN NEXT SPOT CHECK) ATOTAL= 1.157" 04 7

# Southwest Student Housing

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

Tempe, Arizona Technical Assignment #1

Typical Girder Calculations
-----------------------------

MOMENT DISTRIBUTION	I- FACTORE	D LOADS (	k-ft)							
Joint	А	В		C		C	)	E		F
Distribution Factor	0.500	0.714	0.286	0.286	0.714	0.714	0.286	0.286	0.714	0.500
Fixed End Moment	1575.00	-1575.00	1406.25	-1406.25	225.00	-225.00	1406.00	-1406.00	1575.00	-1575.00
Balance	-787.500	120.488	48.263	337.838	843.413	-843.234	-337.766	-48.334	-120.666	787.500
Carry Over	60.244	-393.750	168.919	24.131	-421.617	421.706	-24.167	-168.883	393.750	-60.333
Balance	-30.122	160.530	64.302	113.681	283.805	-283.843	-113.696	-64.312	-160.555	30.167
Carry Over	80.265	-15.061	56.840	32.151	-141.922	141.902	-32.156	-56.848	15.083	-80.278
Balance	-40.132	-29.831	-11.949	31.394	78.376	-78.359	-31.387	11.945	29.820	40.139
Carry Over	-14.915	-20.066	15.697	-5.974	-39.179	39.188	5.972	-15.694	20.069	14.910
Balance	7.458	3.119	1.250	12.914	32.240	-32.245	-12.916	-1.251	-3.124	-7.455
Carry Over	1.560	3.729	6.457	0.625	-16.122	16.120	-0.626	-6.458	-3.728	-1.562
Balance	-0.780	-7.273	-2.913	4.432	11.065	-11.063	-4.431	2.913	7.272	0.781
Carry Over	-3.636	-0.390	2.216	-1.457	-5.531	5.533	1.457	-2.216	0.391	3.636
Balance	1.818	-1.304	-0.522	1.999	4.989	-4.990	-1.999	0.522	1.303	-1.818
Carry Over	-0.652	0.909	0.999	-0.261	-2.495	2.495	0.261	-0.999	-0.909	0.652
Balance	0.326	-1.363	-0.546	0.788	1.968	-1.968	-0.788	0.546	1.363	-0.326
Carry Over	-0.681	0.163	0.394	-0.273	-0.984	0.984	0.273	-0.394	-0.163	0.681
Balance	0.341	-0.398	-0.159	0.359	0.897	-0.897	-0.359	0.159	0.398	-0.341
Carry Over	-0.199	0.170	0.180	-0.080	-0.449	0.449	0.080	-0.180	-0.170	0.199
Balance	0.099	-0.250	-0.100	0.151	0.377	-0.377	-0.151	0.100	0.250	-0.099
Carry Over	-0.125	0.050	0.076	-0.050	-0.189	0.189	0.050	-0.076	-0.050	0.125
Balance	0.062	-0.089	-0.036	0.068	0.170	-0.170	-0.068	0.036	0.089	-0.062
Carry Over	-0.045	0.031	0.034	-0.018	-0.085	0.085	0.018	-0.034	-0.031	0.045
Balance	0.022	-0.047	-0.019	0.029	0.074	-0.074	-0.029	0.019	0.047	-0.022
Carry Over	-0.023	0.011	0.015	-0.009	-0.037	0.037	0.009	-0.015	-0.011	0.023
Balance	0.012	-0.019	-0.007	0.013	0.033	-0.033	-0.013	0.007	0.019	-0.012
Carry Over	-0.009	0.006	0.007	-0.004	-0.016	0.016	0.004	-0.007	-0.006	0.009
Total	848	-1756	1756	-854	854	-854	854	-1755	1755	-848

# Southwest Student Housing

Tempe, Arizona Technical Assignment #1

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

MOMENT DISTRIBUTIO	N-LIVE LOAD	DS (k-ft)								
Joint	А	B		C		[		E		F
Distribution Factor	0.500	0.714	0.286	0.286	0.714	0.714	0.286	0.286	0.714	0.500
Fixed End Moment	285.00	-285.00	254.00	-254.00	41.00	-41.00	254.00	-254.00	285.00	-285.00
Balance	-142.500	22.134	8.866	60.918	152.082	-152.082	-60.918	-8.866	-22.134	142.500
Carry Over	11.067	-71.250	30.459	4.433	-76.041	76.041	-4.433	-30.459	71.250	-11.067
Balance	-5.534	29.125	11.666	20.480	51.128	-51.128	-20.480	-11.666	-29.125	5.534
Carry Over	14.562	-2.767	10.240	5.833	-25.564	25.564	-5.833	-10.240	2.767	-14.562
Balance	-7.281	-5.336	-2.137	5.643	14.088	-14.088	-5.643	2.137	5.336	7.281
Carry Over	-2.668	-3.641	2.822	-1.069	-7.044	7.044	1.069	-2.822	3.641	2.668
Balance	1.334	0.585	0.234	2.320	5.792	-5.792	-2.320	-0.234	-0.585	-1.334
Carry Over	0.292	0.667	1.160	0.117	-2.896	2.896	-0.117	-1.160	-0.667	-0.292
Balance	-0.146	-1.305	-0.523	0.795	1.984	-1.984	-0.795	0.523	1.305	0.146
Carry Over	-0.652	-0.073	0.397	-0.261	-0.992	0.992	0.261	-0.397	0.073	0.652
Balance	0.326	-0.232	-0.093	0.358	0.895	-0.895		0.093	0.232	-0.326
Carry Over	-0.116	0.163	0.179	-0.046	-0.447	0.447	0.046	-0.179	-0.163	0.116
Balance	0.058	-0.244	-0.098	0.141	0.353	-0.353		0.098	0.244	-0.058
Carry Over	-0.122	0.029	0.071	-0.049	-0.176	0.176	0.049	-0.071	-0.029	0.122
Balance	0.061	-0.071	-0.028	0.064	0.161	-0.161	-0.064	0.028	0.071	-0.061
Carry Over	-0.036	0.031	0.032	-0.014	-0.080	0.080		-0.032	-0.031	0.036
Balance	0.018	-0.045	-0.018	0.027	0.068	-0.068		0.018	0.045	-0.018
Carry Over	-0.022	0.009	0.014	-0.009	-0.034	0.034	0.009	-0.014	-0.009	0.022
Balance	0.011	-0.016	-0.006	0.012	0.031	-0.031	-0.012	0.006	0.016	-0.011
Carry Over	-0.008	0.006	0.006	-0.003	-0.015	0.015		-0.006	-0.006	0.008
Balance	0.004	-0.008	-0.003	0.005	0.013	-0.013		0.003	0.008	-0.004
Carry Over	-0.004	0.002	0.003	-0.002	-0.007	0.007	0.002	-0.003	-0.002	0.004
Balance	0.002	-0.003	-0.001	0.002	0.006	-0.006		0.001	0.003	-0.002
Carry Over	-0.002	0.001	0.001	-0.001	-0.003	0.003	0.001	-0.001	-0.001	0.002
Total	154	-317	317	-154	154	-154	154	-317	317	-154

# Southwest Student Housing

10.19.2011

#### Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

Tempe, Arizona Technical Assignment #1

MOMENT DISTRIBUTIO	N- TOTAL LC	DADS								
Joint	А	В		C	<u>,</u>	C	)	E		F
Distribution Factor	0.500	0.714	0.286	0.286	0.714	0.714	0.286	0.286	0.714	0.500
Fixed End Moment	810.00	-810.00	723.00	-723.00	116.00	-116.00	723.00	-723.00	810.00	-810.00
Balance	-405.000	62.118	24.882	173.602	433.398	-433.398	-173.602	-24.882	-62.118	405.000
Carry Over	31.059	-202.500	86.801	12.441	-216.699	216.699	-12.441	-86.801	202.500	-31.059
Balance	-15.530	82.609	33.090	58.418	145.840	-145.840	-58.418	-33.090	-82.609	15.530
Carry Over	41.305	-7.765	29.209	16.545	-72.920	72.920	-16.545	-29.209	7.765	-41.305
Balance	-20.652	-15.311	-6.133	16.123	40.252	-40.252	-16.123	6.133	15.311	20.652
Carry Over	-7.656	-10.326	8.062	-3.067	-20.126	20.126	3.067	-8.062	10.326	7.656
Balance	3.828	1.617	0.648	6.633	16.559	-16.559	-6.633	-0.648	-1.617	-3.828
Carry Over	0.808	1.914	3.317	0.324	-8.280	8.280	-0.324	-3.317	-1.914	-0.808
Balance	-0.404	-3.735	-1.496	2.275	5.680	-5.680	-2.275	1.496	3.735	0.404
Carry Over	-1.867	-0.202	1.138	-0.748	-2.840	2.840	0.748	-1.138	0.202	1.867
Balance	0.934	-0.668	-0.268	1.026	2.562	-2.562	-1.026	0.268	0.668	-0.934
Carry Over	-0.334	0.467	0.513	-0.134	-1.281	1.281	0.134	-0.513	-0.467	0.334
Balance	0.167	-0.700	-0.280	0.405	1.010	-1.010	-0.405	0.280	0.700	-0.167
Carry Over	-0.350	0.084	0.202	-0.140	-0.505	0.505	0.140	-0.202	-0.084	0.350
Balance	0.175	-0.204	-0.082	0.185	0.461	-0.461	-0.185	0.082	0.204	-0.175
Carry Over	-0.102	0.087	0.092	-0.041	-0.230	0.230	0.041	-0.092	-0.087	0.102
Balance	0.051	-0.128	-0.051	0.078	0.194	-0.194	-0.078	0.051	0.128	-0.051
Carry Over	-0.064	0.026	0.039	-0.026	-0.097	0.097	0.026	-0.039	-0.026	0.064
Balance	0.032	-0.046	-0.018	0.035	0.087	-0.087	-0.035	0.018	0.046	-0.032
Carry Over	-0.023	0.016	0.018	-0.009	-0.044	0.044	0.009	-0.018	-0.016	0.023
Balance	0.011	-0.024	-0.010	0.015	0.038	-0.038	-0.015	0.010	0.024	-0.011
Carry Over	-0.012	0.006	0.008	-0.005	-0.019	0.019	0.005	-0.008	-0.006	0.012
Balance	0.006	-0.010	-0.004	0.007	0.017	-0.017	-0.007	0.004	0.010	-0.006
Carry Over	-0.005	0.003	0.003	-0.002	-0.008	0.008	0.002	-0.003	-0.003	0.005
Total	436	-903	903	-439	439	-439	439	-903	903	-436

Ksenia Tretiakova, Structural Option

AE Consultant: Dr. Andres Lepage

#### Appendices | 33

### Southwest Student Housing

Tempe, Arizona

Technical Assignment #1

APPENDICES - HPDENDIX G 37 DUTHWEST STUDENT HOUSING TECH STAT CHECKS (CONTINUED) KTYPICAL GIRDER (INTERIOR) TRIB. WIDTH = 19.5" CONSERVATIVE ESTIMATE: A. SI.49 KLS LOAD POINT (21 BONS FRAME INTO  $W = \frac{51.98 \times 21}{250} = 4.32 \text{ KLF} (FACTOR60)$ 25 EACH GIRDER, 12'-6" SPACING ->UNIF LOOD?) MOMENT DISTRIBUTION (SEE ATTACHED GICEL SHEET) W = 4.32 KUF 60 MS WLIVE= 0.78 KLF 8 AMPAD 62.51 Wtona = 2.22 KLS 251 6251 251 25'  $\frac{4.32 (25')^2}{2} = 1350 \text{ K-FT}$ V FACTORED  $M = \frac{WL^2}{2} =$ 1/2 DIRECTION OF CHOICE DF= MLINE= 243.73 K-FT DISTRIBUTION GACTORS: 1- RIGHT AB = 0.5 k ·ft MITTAL = 693.75 (EI IS CONSTANT THEY OUT) BA = 0.714 BC= 0.286  $FEM = \frac{wL^2}{12}$ CB= 0.286 CD=0.714 DC=0.714 DE=0.286 3 EXCEL SHEETS INCLUDED REGARDING SYMMETRIC MOMENT DISTRIBUTION : ED= 0.286 V EF = 0.714 - FACTORED LOADS - LIVE LOAD ONLY { (UNRACTORED) FE = 0.5 - TOTAL LOAD \*SEE TYP. BM. SPOT CHECK BR. LOADS USED IN TNP. GIRBER SPOT CHECK. FIXED END MOMENTS: (K-87) SACTORED TOTAL DINT 1146 125+1350 41+244 116+694 AB 723 254 BC 1406.25 DESIGN LOADS : Mu= 1756 K-FT CD 116 225 41 DE 1406.25 254 723 EF 225+1350 116+694 41+244  $f^{\dagger}$ (10 PSF) (0.25 + 15 A= 4875 54 = 0.36 (10 mg) = 1= 40 PSF J4×48751 10

#### Appendices | 34

# Southwest Student Housing

Tempe, Arizona Technical Assignment #1

APPENDICES-APPENDIX G 39 OUTHWEST STUDENT HAVING TECH 1 SPOT CHECKS (CONTINNED) Assume a= 3.25"-> "12= 4.625" bess= = (SPAN) = 1/4 (62.5) = 7.813'= 9375" € 2 (SPACING) = 2 (25) = 12.5' EDGE DIFFANCE = 25' · TEY W27×103  $\Phi M_{0} = 1810 + (1840 - 1810) \left( \frac{4.625 - 4.5}{5 - 4.5} \right) = 1817.5 \ \text{RK} @ PNA \# 4 \\ a = \frac{1.879}{0.85(4)(93.75)} = 2.75 + 3.25'' \ OK \\ \end{array}$ "drampad" 848 17.2 = 51 SHEAR STUDS X 2 = 102 STUDS ENGINEER'S PRESCRIBED BEAM IS NOT IN COMPOSITE BIN THBLE IN ALSO '10 STEEL CONSTRUCTION MANUAL (TABLE 3-19) BUT IT'S A HEATY WZY X 176 , WHICH IS PROBABLY AS BEEFY OR MORE BEEFY THAN MY W27 XIOS DEFLECTIONS? I= 7230 + 0.25 (7430-7230) = 7280 W" 1°2° 3°4° (3°4 MMETRIC) 1°2° 3°4° (3°2°/1 SPAN 1:  $\Delta_{x} = \frac{\omega_{x}}{24E1} \left[ x^{3} - \left( 2L + \frac{4M_{1}}{\omega_{L}} - \frac{4M_{2}}{\omega_{L}} \right) x^{2} + \frac{12M_{1}}{\omega} x + L^{3} - \frac{8M_{1}L}{\omega} - \frac{4M_{2}L}{\omega} \right]$ (SINCE GUD MOMENTS ARE UNEQUAL... TAKEN FROM CASE 32, ALSO STEEL CONSTRUCTION MANUAL, 2010, 14TH ED)  $\Delta_{MAX} \stackrel{\circ}{\subset} X = \frac{L}{2} + \frac{M_1 - M_2}{TM_1}$ WL SPAN 2: X = 250.3" ALIVE 0.06" ATOTAL 0.17" SPAN 3: X = 415.1" ALIVE 20.33" DIOTAL 0.94" Span 4: X = 150" DLINE = 0.07" ATOTAL 0.19"

## Appendices | 35

# Southwest Student Housing

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

APPENDICES - APPENDIX G 39 SOUTHWEST STUDENT HOUSING TECH SPOT CHECKS (CONTINUED) (W18×210) TYPICAL BEAM DEFLECTIONS: NEW END SPANS: ALINE = 0.009 + 0.33 = 0.338 OK (CAMBERED) A = 0.022+0.94 = 0.962 NG MIDDLE SPAN 0.226+0.33=0.556" OK BLIVE "AMPAD" = 1.137 + 1.94 = 2.077" NG (CAMEERED) A TOTAL 12

Tempe, Arizona

Technical Assignment #1

Appendix D – Alternative Floor System: Non-Composite Deck NONCOMPOSITE FLOOR SYSTEM FIRE REQUIREMENTS: ZHE, EXPOSED GRID => 2-2"NW W 0.60, 1.00, 1.30, ISC. 3" NY W 3.46, 1.00, 1.50, 1.50 MIN 2 SPANS (TO DEAL W/ CANTILEVER) -DECK ORIENTATION 2 TYP. SPAN= 12.5' WILL GO W/ 2-2 "NW -> INITIAL SIZING: (BASED ON MAX UNSHORED CONDITION) 0.6022 - 4'7" (2 & 3 SPAN) ASSUME FLORAR 1.0020 - 7' 3" (2 & 3SPAN) WILL BE COASED ON! NG 1.3620 - 8' 4" A FINISH (AFFECTS (2 & 3 SPAN) MANNAN M 1.50 18 - 9' 9" ALLOWARLESLAR (2 SPAN) 10' 1" (3 SPAN). 10C 10 - 12 6" (2 SPAN) 12' 11" (3 SPAN) OK LAAD) - KINHIAL SIZING (FROM 2016 CANNOT HOLD LOADS ON SUCH WIDE SPANS VULLEAPT STEEL DECK CATALOG 3 CHEW 13" NW? . MAX ALLOWABLE UNIFORM LOAD FOR SS = 100 PSF LOADS : · (ONSTRUCTION: DECK WEIGHT= 59 PSF AMOMED STENCTURAL STE - ISPSF TOTAL = 58 +15 = 73, MP · Superimposeo: 15 psf TOTAL DEAD LOAD = 73 +15 - 38 PSF TOTAL LIVE LOAD = 80 PSF (COULD POTENTIALLY BE REDUCED BY N7 PSF) TOTAL SUPERIMPOSED UNIFORM LOAD= 15 PSF + 80 PSF = 95 PSF < 100 PSF OF USE 3" CONFORM DECK, 16 GAGE, WITH 3" N.W. CONCRETE 2 SPANSIMIN. TYP SPAN=12'-6" GIRDER DESIGN: REDUCTIONS: CORE 1 CORE .  $(90 \text{ ps}+)(0.25 + \frac{15}{14 \times 1625}) = 0.44 \text{ (qa)}$   $\implies \text{Live Land} = 0.5(80) = 40 \text{ ps}f$ 62.51 TRIEVIARY WOTH = 26' - A = 26 (62.5) = 1625 SF 2 ASSUMING THE EDGE GIRDER PROVIDES NO SUPPORT, THIS NO REDUCTION IN TRIE. WFACTORED 1.2 (88) + 1.6 (40) × 26° = 4.41 KLF WLIVE = (40 PSF) × 26' = 1.04 KLF W TOTAL = [88 + 40] ×26 = 3.32 KLF

# Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

### Appendices | 37

### Southwest Student Housing Tempe, Arizona

Technical Assignment #1

11/100

NONCOMPOSITE FLOOR SYSTEM (CONT'D) GIRDER DESIGN (CONTO) MAX MIMENT  $\approx \frac{WL^2}{11} \rightarrow M_u^2 \frac{(4.41)(62.5)^2}{11} = 1566 \text{ k-FT}$ 62.5 -> MAINTAIN SAME FLOOR HEIGHTS : W24X ----FROM TABLE 3-2 OF AISC STEEL CONSTRUCTION MANUAL, IST 40: \$ Mpx = 1570 K-FT FOR W24×146 > Mu= 1566 K-FT  $S = \frac{\omega \ell^{4}}{384 \text{ET}} \left(\frac{12}{11}\right) = \frac{\omega \ell^{4}}{352 \text{EI}}$ DEFLECTIONS Crocher 1 I= 4580 114  $S_{LIVE} = \frac{(1.04/12)(62.5 \times 12)^{44}}{352(29000)(4570)} = 0.587'' \qquad \frac{1}{360} = 2.09''$ OK  $\delta_{\text{TOTAL}^{2}} \frac{(3.33/12)(62.5 \times 12)^{4}}{352(29000)(4590)} = 1.878 " \frac{l}{240} = 3.125"$ OK USE W24 × 146 FOR 62'-6" SPAN BETWEEN ORES (AKA GIRDER) BEAM DESIGN: CONTINUOUS OVER BOTH SUPPORTS END MOMENT: WLZ (END LOADED CANTLEVER) 131 L for UNIFORM LOAD TRIB. WIDTH = 12.5' TO INCLUDE CURTAIN WALL > 12.5 × 52 = 6056 10' × 12.5' × 15 PS F= = 1.875 K END LOAD (50) (0.25+ 15 )= 0.544 (50)= 43.5 PSF + PQ WFACTORED [1.2 (17)+1.6 (43.5)] X12.5 = 2.2 KLS WLINE = 43.5 × 12.5'= 0.544 KLS WTOTOL= (89+43.5) × 12.5 = 1.644 KLF END MOMENTS= (2,2) (13') = 215.1 K-FT  $\frac{\text{midspan}}{13} = \frac{2}{2} \frac{(M_{end})}{2} = \frac{(2.2)(26)^2}{2} - 215 = -29.8 \text{ k-fr}$ FOR EASE OF APPLYING DECK. Mu=210.3 K-FT > MAINTAIN SAME FLODE HEIGHTS .. WISX. \$ Mpx = 249 K-FT FOR W18 x 35 > Mu=210.3 K-FT

### Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

# Southwest Student Housing

3/2 NONCOMPOSITE FLOOR SYSTEM (CONT'D) BEAM DESIGN (LONT'D)  $\frac{\text{Deflections}}{\text{I}=\text{Sio in }^{4}} = \frac{\omega_{X}}{S_{X}} \left[ \chi^{2} - \left(2\ell + \frac{4M_{1}}{\omega\ell} - \frac{4M_{2}}{\omega\ell}\right)\chi^{2} + \frac{12M_{1}}{\omega}\chi + \ell^{3} - \frac{8M_{1}\ell}{\omega} - \frac{4M_{2}\ell}{\omega} \right]$  $M_1 = M_2$ ,  $\chi = \frac{1}{2}$   $M_{1116} = \frac{(0.544)(13)^2}{2} + \frac{1}{2} + \frac{1}$  $S_{\chi} = \frac{\omega l}{48 \epsilon_1} \left[ \frac{l^3}{8} - \frac{l^3}{7} + \frac{16 M l}{10} + l^3 - \frac{12 M l}{10} \right] \qquad \text{M TOTAL= 163.3 } k - FT$  $S_{LIV6} = \frac{(0.544/12)(36.542)}{48(2900)(510)} \left[ (126.812)^3 - \frac{3(26.812)^3}{8} - \frac{6(46.842)}{(0.544/12)} (26.812) \right] z - 0.076^{11}$   $S_{TOTAL} = \frac{(1.644/12)(26.812)}{48(28000)(510)} \left[ (26.812)^3 - \frac{3(26.812)^3}{8} - \frac{6(162.3.812)}{(1.644/12)} (26.812) \right] z - 0.469^{11}$ NARAD'  $\frac{l}{360} = 0.867" > -0.076" OF (DETRECTIONS ARE NEGATIVE BECAUSE$  $<math display="block">\frac{l}{240} = 1.3" > -0.469" OF TO CAUSE THE BEAM. TO CURVE UP & MIDSPAN:$ SCANTILEVER DEFLECTIONS) 5\_LINE, END 8(2000) (\$19) + 3(2000) (\$19) = 0.227" < 1347 0.433" OF STOTALIEND = (1.644/12)(1342)4 + 1.875 (13×12)3 = 0.846" > 13×12 = 0.65 MG W18×46? J:712 · MIDSPAN - $S_{tive} = (-0.076) \left( \frac{\pi o}{\pi c} \right)^{2} - 0.054^{H} < 0.867^{H} ok$   $S_{TOTAL} = (-0.469) \left( \frac{510}{7c} \right)^{2} - 0.336^{H} < 1.3^{H} ok$ · END SPAN- $\begin{aligned} & \delta_{CLVE} = (0.227) \left(\frac{510}{742}\right) = 0.163 + < 0.433 + 0.55 \\ & S_{TOTTRL} = (0.846) \left(\frac{510}{742}\right) = 0.666 + < 0.453 + 0.55 \end{aligned}$ > USE WIRXAL FOR BEAMS @ 12'-6" SPACING.

## Appendices | 39


# Southwest Student Housing

Tempe, Arizona

Technical Assignment #1

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

# Appendix E – Alternative Floor System: Long-Span Deck



### Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

### Appendices | 40 Southwest Student Housing

Tempe, Arizona

Technical Assignment #1

2/3 LONG SPAN DECK (CONT'D) GIRDER DESLGN: SPAN= 62.5 - LIVE LOAD REDUCTION TO 40 PS& (SEE NON COMPOSITE CALCS)  $W_{\text{formed}} = \left| 1.2 \left( 46 + |5 + 15 \right) + 1.6 \left( 40 \right) \right| \times 26^{12} 3.57 \text{ kls}$ WINE = (40) ×26 = 1.04 KLS WHOTHE = (40+46+15+15) x 26 = 3.02 KLS MAX M ~ We - Hu= (3.57)(62.5)2 - 1268 K-FT 62.5 AMPAD" > MAINTAIN SAME FLOOR HEIGHTS : W24 X TABL 3-2 OF AISC STEEL CONSTRUCTION MANUAL, 13TH ED. -\$ MPY = 1390 FT-K FOR WEYK 131 7M4=1268 K-FT OL 1268 K.CT DEFLECTIONS Ix= 4020 1N4 Smax 352 E1  $S_{LIVE} = \frac{(1.64 | Iz) (62.5 \times 12)^{4}}{352 (29.04) (4020)} = 0.679^{*} \frac{1}{360} = 2.08^{*} \frac{01}{240}$   $S_{TOTAL} = \frac{(3.62 | Iz) (62.5 \times 12)^{4}}{352 (29.00) (4020)} = 1.94^{*} \frac{1}{240} = 3.125^{*} \frac{01}{240}$ BEAM DESIGN:  $(\underline{\qquad})M=\frac{\omega l^2}{2}+Pl$ P=1.875 M THE WISTH & 16' -> (16' x 52')= 832 55 -> (80) (0.25 + 14×832) = 0.51(PD)=40.8 PSF W = [1.2(46+15+15)+(.6(40.8)] X 16 = 2.504 KLS WINE = (40.8) X16= 0.653 KLS Wrother (40. +46+15+15) X16=1.969 KLS END MOMENTE  $M_{\mu^2} = \frac{(2.504)(13')^2}{2} + (1.875 \times 1.2)(13') = 244 \text{ kgr}$ MIDSPAN MOMENT: W12 - MEND = (2.504)(06)2 - 244 = -32.4 KAT C 6" DECK, NOT " 26 13' -> MAINTAIN FLOOR HEIGHT -> WIYX -\$ Mpx= 383 K-FT FOR WIG × 61 > Mu-244 K-FT 244 KET  $M_{int} = \frac{(0.653)(13)^2}{2} = 55.2 \text{ k-st}$ Tx = 640 m4  $M_{\text{torn}_{L}} = \frac{(1.964)(13^2)}{2} + 1.975 (13) = 182.3 \text{ k-st}$  $S_{x} = \frac{wl}{4861} \left| \frac{5}{8}l^3 - \frac{6Ml}{w} \right|$ @ MID SPAN T SIMPLIFIED BLC END MOMENTS ARE SUMMETRIC & MAX MISSPAN & IS IN THE VERY MIDDLE ( )

## Appendices | 41

# Southwest Student Housing

Tempe, Arizona Technical Assignment #1


Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

LONG SPAN DECK (CONT'D) BEAM DESIGN (CONTO) DEFLECTIONS  $\delta_{LIVE} = \frac{(0.653/12)(26 \times 12)}{48(29000)(640)} \left| \frac{5}{8} (26 \times 12)^3 - \frac{6(55.2 \times 12)}{0.653/12} (26 \times 12) \right| = -0.073'' < 0.867 \text{ OF}$ MAD SPAN  $\left| \left\{ S_{\text{TOTAL}}^{-} \frac{(1.869/12)(2.6 \times 12)}{4 \times (29000)(640)} \right|_{\frac{5}{8}(26 \times 12)^{3}}^{-} \frac{b(182.3 \times 12)}{1.869/12} (26 \times 12) \right]_{-}^{-} |-0.399''| < 1.3'' OK$  $S_{END} = \frac{W L^{9}}{8E I} + \frac{P R^{3}}{3E I}$  (AS OPPROPRIATE) CIMPAD  $\delta_{LNE} = \frac{(0.653/12)(13 \times 12)^9}{8 (29,000)(640)} = 0.217^{11} < 0.933 \text{ of }$ Sporks = (1.869/12)(1312)" + 1.875(13K2)3 = 0.749" > 0.65" NG WI4X74? I= 795 M4  $S_{LIVE} = (-0.073) \left( \frac{640}{795} \right) = (-0.059'') < 0.867'' 0 = 5 \\ S_{TOTAL} = (-0.399) \left( \frac{640}{795} \right) = (-0.321'') < 1.3''' 0 = 5 \\ S_{TOTAL} = (-0.399) \left( \frac{640}{795} \right) = (-0.321'') < 1.3''' 0 = 5 \\ S_{TOTAL} = (-0.399) \left( \frac{640}{795} \right) = (-0.321'') < 1.3''' 0 = 5 \\ S_{TOTAL} = (-0.399) \left( \frac{640}{795} \right) = (-0.321'') < 1.3''' 0 = 5 \\ S_{TOTAL} = (-0.399) \left( \frac{640}{795} \right) = (-0.321'') < 1.3''' 0 = 5 \\ S_{TOTAL} = (-0.399) \left( \frac{640}{795} \right) = (-0.321'') < 1.3''' 0 = 5 \\ S_{TOTAL} = (-0.399) \left( \frac{640}{795} \right) = (-0.321'') < 1.3''' 0 = 5 \\ S_{TOTAL} = (-0.399) \left( \frac{640}{795} \right) = (-0.321'') < 1.3''' 0 = 5 \\ S_{TOTAL} = (-0.399) \left( \frac{640}{795} \right) = (-0.321'') < 1.3''' 0 = 5 \\ S_{TOTAL} = (-0.399) \left( \frac{640}{795} \right) = (-0.321'') < 1.3''' 0 = 5 \\ S_{TOTAL} = (-0.399) \left( \frac{640}{795} \right) = (-0.321'') < 1.3''' 0 = 5 \\ S_{TOTAL} = (-0.399) \left( \frac{640}{795} \right) = (-0.321'') (-0.321'') < 1.3''' 0 = 5 \\ S_{TOTAL} = (-0.399) \left( \frac{640}{795} \right) = (-0.321'') (-0.321'') = (-0.3$ MIDSPAN · END SPAN SPAN (0.217) (640) = 0.175" < 0.433" OF Sutthe = (0.749) ( 640 )= 0.603" < 0.65" OK SUSE WIHX 74 FOR BEAMS ( 62.5 & 15'-6" SPACING (4 BANS/62.5' SPAN)

3/3

Tempe, Arizona

Technical Assignment #1




### Appendix F – Alternative Floor System: Post-Tensioned Concrete

### Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

# Appendices | 43

# Southwest Student Housing



### Appendices | 44

# Southwest Student Housing

Tempe, Arizona

Technical Assignment #1

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

3/6 POST-TENSIONED CONCRETE (2-WAY) (CONT'D) E-W TENDON PROPILE IN WIDE SHALLOW BEAM : SLAG CONTINUES OFF ON BOTH 4.33" ENDS , ... TENDONS DON'T 14 NEED TO RETURN TO THE NEUTRAL AXUS, AS THEY ALE CONTINUOS 62.5 Que = 14 - 4.33 - 1.0 = 8.67" So P= (2065.44) (62.5)2 = 1395.9 KIPS AMPAD"  $\frac{1395.9}{24.327} = 57.4 \rightarrow max \text{ acceptible tender Area: } \frac{P}{A} = 300 \text{ psi} \quad P = 300 \text{ (A)}$ Pacovar= 30 (24-327)= 729.9 K Wist PACTUAL (8x a INT) = 729.8 (8x8.67 /12) = 1.08 KLS WS.W. = 2.06 KLF Wb = 1.08 = 0.523 <1.0 0K Perr = 729.8 K A = 129.8 = 0.2945 KSI SLAG STRESSES : IMMEDIATELY AFTER JACKING: DEAD - WD= (99.3+15) (201)= 2.97 KLS · MIDSPAN: frot (-395.5443.8) -0.2945= -342.851 5269 W12 - W12 = 395.5 Ft-16 5 BOTT = (395.5-143.8) - 0.2945= -188 PSI · SUPPORTS! = 1055 FT-K  $S_{\text{top}} = \frac{(1055 - 3835)}{5269} = 0.2945 = -182 \text{ ps}$ WL= (50) (261)=1.3 KLS LIVG -SEOTT = (-1055 +393.5) - 0.2945= -579 #51 173.1 814 WITHIN CLASS U DESIGN 461.6 FT-16 PARAMETERS, OK BALANCING- WE=1.08 WF 393.5 K-FT -143.9 KFT

Ksenia Tretiakova, Structural Option

AE Consultant: Dr. Andres Lepage

## Appendices | 45 Southwest Student Housing

Tempe, Arizona

Technical Assignment #1

4/6 POST - TENSIONED CONCRETE (2-WAY) (CONT'D) STRESSES AT SERVICE LOAD : · MIDSPAN :  $S_{TOP} = \frac{(-395.5 - 173.1 + 143.2)}{S2.69} - 0.2945 = -375 PSI$ 5 Bott = (343.5+173.1-143.9) - U.2945 = -114 PSI · SUPPORTS : Stop = (1055 + 461.6 - 383.5) -0.2945 = - 79 ps/ AMPAD Seatt = (-1055-461.6+383.5) - 0.2945= -774 psi WITHIN CLASS U DESLEN PARAMETERS, OF ULTIMATE STRENGTH : M= Pe = (729.8K) (4.33-1.0) = 202.5K-IN-MSEC = MBAL - MI = 383.5 - 12 = 366.6 K ST EEQUAL @ BOTH SUPPORTS MINIMUM BONDED REINFORCEMENT : OVERALL, NO STRESSES IN TENSION > TENSILE REINFORCEMENT IS UNNECESSARY NEGATIVE MOMENT & GLOWS : 1  $A_{CF} = \begin{cases} \frac{(25+62\cdot5)}{2} = 43.75 \\ 26^{1} \end{cases} \times 12^{-1/1} \times 14^{11} = 7350 \text{ in } 2 \end{cases}$ As, min= 0,00075 Acs AS, MW = 0.00075 (7350) = 5.5125 1N2 (7) #8'S TOP (5.53 142) CAT BOTH SUPPORTS (7)#8% BONDED REINFORCING NEED to CHECK MIN REINFORDING RED'. 1.01 NIA. TENDON PROFILE

# Appendices | 46

# Southwest Student Housing

Tempe, Arizona

Technical Assignment #1

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

5/1 POST-TENSIONED CONCRETE (2-WAY) (CONT'D) A= 7" × (62.5' ×12) = 5250 IN2 S= bh2 = (750")(7")2 = 6125 1N3 NORTH - SOUTH DIRECTION DESIGN: (WBAL= (79.44) (62.5') = 4965 PLF = P= WBAL L2 = 3355.4 K 3355.4 MAX ACCEPTABLE TENDONS : = 137.9 24.327 P 300 MI 300 (5250)=1575 K PACAVAL= 64(24.327)=1556.9 K 1575 - 64 TENDONS  $W_{\rm b} = \frac{1556.9 \left( \frac{4 \times 8.67}{12} \right)}{(62.5)^2} = 2.3 \text{ kis} \}$ WE KING OF WS.W. = 9.965 KLF AMPAD  $\frac{P}{A} = \frac{1556.9}{5250} = 0.2965 \text{ ks}$ TENDON PROFILE: Ce=2.5 è 6 28 SLAB STRESSES ; DEAD - WD = (99.3+15) (62.5')=7.14 KE P= (10' × 62.5') × 15 PSE= 9.375 K ( 42 - MSIPPORT = 121.87 K-FT IMMEDIATELY AFTER JACKING . · MIDSPAN Stop= (-121.27 + 0.) -0.2965 = - 317 PSI 6125 SECTIONS (121.77+0) -0.2465 = -277 PSI 2 + P4= 725.2 K-FT LIVE- W1 = (50) (62.5') = 3.13 KLF 6125 • SUPPORTS Stop = (-725.2+194.35) 6125 - 0.2965 = -383 PSI , 0<sup>,1</sup> Sport = (725.2-194.35) 6125 -0.2965= -210 PSI N2=264.5 K-FT WITHIN CLASS U DESIGN PARAMETERS. OK BALANCING - WEAL = 2.3 KLF 194.35 KFF

"UNPAD"

# Appendices | 47

# Southwest Student Housing

Tempe, Arizona

6/6

Technical Assignment #1

AE Consultant: Dr. Andres Lepage

Ksenia Tretiakova, Structural Option

POST-TENSIONED CONCRETE (2-WAY) (CONT'D) STRESSES AT SERVICE LOAD : . MIDSPAN  $S_{top} = \frac{(-121.87 - 0 + 0)}{(-121.87 - 0 + 0)} = 0.2965 = -317 PSI$ 6123

 $f_{COTT} = \frac{(121.87+0.0)}{(121.87+0.0)} = 0.2965 = -277PSI$ 6125 · SUPPORTS  $S_{\text{top}} = \frac{(-725 \cdot 2 - 264.5 + 194.35)}{(-725 \cdot 2 - 264.5 + 194.35)} - 0.2965 = -926 \text{ psi}$ 6125 5 0017 = (723.2+264.5-194.35) -0.2965= -167 PSI 6125

WITHIN CLASS & PARAMETERS OF

VLTIMATE STRENGTH :

MI= Pe = (1556.9) (2.5") = 3892.25 K-IN MSEC = 194.35 - 3892.25 - 130 K-FT & EQUAL @ BOTH SUPPORTS

MINIMUM BONDED REINFORCEMENT: OVERALL, NO STRESSES IN TENSION => TENSILE REINFORCEMENT IS UNNECESSARY

NEGATIVE MOMENT REGIONS:  
As, min = 0.00075 Acs 
$$Acs = \begin{cases} \frac{13+26}{2} = 19.5 \\ 62.5 \end{cases} \times 12^{24} \times 7^{11} = 5250 \text{ max} \end{cases}$$

A5, MIN= 3.94 M2

( 5) #8'S TOP (3.951N2) ( AT BOTH SUPPORTS

Tempe, Arizona Technical Assignment #1

Material	Properties	Overall Cost	Material Cost	Units
Steel Floor Deck				
Non-Cellular 3	3" Composite Decl	<, Galvanized		
	20 Gauge	2.93	1.86	ft <sup>2</sup>
	18 Gauge	3.45	2.29	ft <sup>2</sup>
Open Deck, W	/ide Rib			
	3", 16 Gauge	4.26	3.16	ft <sup>2</sup>
	6", 14 Gauge	9.48	7.3	ft <sup>2</sup>
Structural Steel Members	, 5			
	W14x22	35.45	31.5	ft
	W14x74	106.12	89.5	ft
	W18x40	61.15	48.5	ft
	W18x46	69.15	55.5	ft
	W18x50	75.05	60.5	ft
	W24x131	201.43	177	ft
	W24x146	201.43	177	ft
	W24x176	201.43	177	ft
	W27x102	158.78	138	ft
Prestressing Steel				
	Span, 300 kip	3.27	1.79	lb
Reinforcing Steel	Average #0	1405	005	+ - 10
Typ. In-Place Concrete	Average, #8	1495	985	ton
Normal Weigh	+			
		110	100	yd <sup>3</sup>
	3000 psi		100	
	4000 psi	117	106	yd <sup>3</sup>
Light Weight	2000			.3
	3000 psi	161	146	yd <sup>3</sup>
	4000 psi	163	149	yd <sup>3</sup>

## Appendix G – Cost Estimate Documentation

Ksenia Tretiakova, Structural Option

AE Consultant: Dr. Andres Lepage

Prestressing strands/floor								
Weight (lb/1000 ft)	Estimated feet of tendons*	Weight						
775	32484	25175.1 lb						
* (#tendons x #bays	s x length of bay x 1.5 for drap	e and any additional factors)						

Reinfor	rcing B	ars		
Weight	(lb/ft)	Estimated feet	Weight (lb)	Weight (tons)
	2.67	1860	4966.2	2.4831

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

Existing - Composite Deck			
Material	Units/floor	Total	<b>Base Total</b>
Design			
3" 20 Gauge Deck	13000.00	38090.00	24180.00
W14x22	722.00	25594.90	22743.00
W18x40	624.00	38157.60	30264.00
W18x50	312.00	23415.60	18876.00
W24x176	500.00	100715.00	88500.00
L.W. 3000 psi, 3.25"	130.40	20994.60	19038.58
	SUM=	246967.70	203601.58
	Cost/ft <sup>2</sup> =	19.00	15.66
Calculated			
3" 18 Gauge	13000.00	44850.00	29770.00
W14x22	722.00	25594.90	22743.00
W18x40	936.00	57236.40	45396.00
W27x102	500.00	79390.00	69000.00
L.W. 3000 psi, 3.25"	130.40	20994.60	19038.58
	SUM=	228065.90	185947.58
	Cost/ft <sup>2</sup> =	17.54	14.30

Tempe, Arizona Technical Assignment #1

Ksenia Tretiakova, Structural Option AE Consultant: Dr. Andres Lepage

Alternative - Non-Composite Dec	k		
Material	Units/floor	Total	<b>Base Total</b>
3" Form, 16 Gauge	13000.00	55380.00	41080.00
W14x22	722.00	25594.90	22743.00
W18x46	936.00	64724.40	51948.00
W24x146	500.00	100715.00	88500.00
N.W. 3000 psi, 3"	120.37	13240.74	12037.04
	SUM=	259655.04	216308.04
	Cost/ft <sup>2</sup> =	19.97	16.64

Alternative - Long Span Deck			
Material	Units/floor	Total	Base Total
6" Form, 14 Gauge	13000.00	123240.00	94900.00
W14x22	722.00	25594.90	22743.00
W14x74	832.00	88291.84	74464.00
W24x131	500.00	100715.00	88500.00
L.W. 3000 psi, 3.25"	130.40	20994.60	19038.58
	SUM=	358836.34	299645.58
	Cost/ft <sup>2</sup> =	27.60	23.05

Alternative - Post-Tensioned Concrete								
Material	Units/floor	Total	<b>Base Total</b>					
300 kip prestressing tendons	25175.10	82322.58	45063.43					
#8 reinforcing steel	2.48	3712.23	2445.85					
N.W. 4000 psi, 7" slab, 14" beams	299.77	35072.92	31775.46					
	SUM=	121107.73	79284.75					
	Cost/ft <sup>2</sup> =	9.32	6.10					

Tempe, Arizona

Technical Assignment #1

### Appendix H – Additional References

Preformed Metal Roof Deck

MORE > < RETURN TO DECK INDEX

**Allowable Reactions** 

Gauge

20

18

16

14

Allowable Gauge

20

18

16

14

Bearing

Length (in)

3"

390

853

815

1477

1362

2316

2282

3721



S...

(ln3)

0.957

1.313


S+

(ln3)

0.924

1.266

# Deep Deck 4 1/2" and 6"



The top value reflects the allowable reaction at the panel end supports.
 The bottom value reflects the allowable reaction at the interior supports.
 Values are in pounds per linear foot.

 16
 4.69
 4.36
 1.608
 1.635

 14
 5.86
 5.49
 2.056
 2.056

 1. Section properties are based on minimum 33 ksi steel (Fy).
 36
 16
 16

L

(In4)

2.44

3.42

4 1/2" Deep Deck Section Properties

Weight

(psf)

2.86

3.74


Gauge

20

18

#### 4 1/2" Deep Deck Allowable Total (DL + LL) Uniform Load (psf) 1,2 (footnote page 26)

Span								Span					
Condition	Gauge		10'0"	12'0"	14'0"	16'0"	18'0"	20'0"	22'0"	24'0"	26'0"	28'0"	30'0"
	20	Stress	123	86	63	48	38	31	25	21	18	16	14
		Deflection	123	86	58	39	27	20	15	12	9	7	6
	18	Stress	169	117	86	66	52	42	35	29	25	22	19
SINGLE		Deflection	169	117	82	55	38	28	21	16	13	10	8
SPAN	16	Stress	214	149	109	84	66	54	44	37	32	27	24
		Deflection	214	149	104	70	49	36	27	21	16	13	11
	14	Stress	274	190	140	107	85	69	57	48	41	35	30
		Deflection	274	190	131	88	62	45	34	26	20	16	13



The top value reflects the allowable reaction at the panel end supports.
 The bottom value reflects the allowable reaction at the interior supports.
 Values are in pounds per linear foot.

Reactions	6" Deep	6" Deep Deck Section Properties								
Bearing	Gauge	Weight		S+	S-					
Length (in)		(psf)	(in4)	(In3)	(in3)					
<b>3</b> "	20	3.22	4.79	1.386	1.314					
793	18	4.22	6.68	1.892	1.966					
757	16	5.29	8.56	2.406	2.451					
1403	14	6.61	10.78	3.085	3.087					
1289		1 Contion n	roportion or	a based on r						
2226		1. Section properties are based on minimum 33 ksi steel (Fy).								
2188		33 KSI Steel (	гу).							

#### 6" Deep Deck Allowable Total (DL + LL) Uniform Load (psf) 1, 2 (footnote page 26)

Span								Span					
Condition	Gauge		10'0"	12'0"	14'0"	16'0"	18'0"	20'0"	22'0"	24'0"	26'0"	28'0"	30'0"
	20	Stress	185	128	94	72	57	46	38	32	27	24	21
		Deflection	185	128	94	72	54	39	29	23	18	14	12
	18	Stress	252	175	129	99	78	63	52	44	37	32	28
SINGLE		Deflection	252	175	129	99	75	55	41	32	25	20	16
SPAN	16	Stress	321	223	164	125	99	80	66	56	47	41	36
		Deflection	321	223	164	125	96	70	53	41	32	26	21
	14	Stress	411	286	210	161	127	103	85	71	61	52	46
		Deflection	411	286	210	161	121	88	66	51	40	32	26

3610

## Appendices | 52

Southwest Student Housing

Tempe, Arizona **Technical Assignment #1** 



# **SPECIFICATIONS FOR PC STRAND**

		ASTM A416 – SEVEN-	WIRE UNCOATE	D LOW RELAXATIO	ON STRAND		
Grade	Nominal Strand Diameter in [mm]	Strand Tolerance in [mm]	Minimum Breaking Strength Lbs [kgs]	Min. Yield Strength at 1% Extension Lbs [kgs]	Minimum Elongation at 24" Gauge	Nominal Area In <sup>2</sup> [mm <sup>2</sup> ]	Nominal Weight Lbs/1000 ft Kg/1000 m
	3/8" [9.5]	0.3910/0.3590 [9.93/9.13]	20,000 [9,072]	18,000 [8,165]		0.080 [51.61]	272 [405]
250K	7/16" [11.1]	0.4535/0.4215 [11.51/10.71]	27,000 [12,247]	24,300 [11,022]	3.5%	0.108 [69.68]	367 [548]
	1/2" [12.7]	0.5160/0.4840 [13.1/12.3]	36,000 [16,329]	32,400 [14,696]		0.144 [92.9]	490 [730]
	3/8" [9.5]	0.4010/0.3690 [10.18/9.38]	23,000 [10,433]	20,700 [9,389]		0.085 [55.03]	290 [432]
	7/16" [11.1]	0.4635/0.4315 [11.76/10.96]	31,000 [14,061]	27,900 [12,655]		0.115 [74.19]	390 [582]
270K	1/2" [12.7]	0.5260/0.4940 [13.35/12.55]	41,300 [18,733]	37,170 [16,860]	3.5%	0.153 [98.71]	520 [775]
2701	0.52" (1/2"HBS) [13.2]	0.5460/0.5140 [13.86/13.06]	45,000 [20,412]	40,500 [18,368]	0.070	0.165 [106.45]	563 [874]
	9/16" [14.3]	0.5885/0.5565 [14.94/14.14]	51,700 [23,451]	46,530 [21,102]		0.192 [123.87]	650 [967]
	0.6" [15.2]	0.6260/0.5940 [15.89/15.09]	58,600 [26,581]	52,740 [23,922]		0.217 [140.00]	740 [1,102]

RELAXATION PROPERTIES							
Initial Stress	Initial Stress Maximum Relaxation after 1000 Hours						
70% G.U.T.S.	2.5%						
80% G.U.T.S.	3.5%						

SUMIDEN WIRE PRODUCTS CORPORATION

Rev. 1/2009 Page 1 of 1

 East Coast Manufacturing: 710 Marshall Stuart Drive • Dickson, TN 37055 • 615-446-3199 • Fax 615-740-1518
 Page 1 of 1

 West Coast Manufacturing: 1412 El Pinal Drive • Sickson, CA 95205 • 209-466-8924 • Fax 209-941-2990

 PC Sales: • Region: AK, HI & Western Exports – Jeff Feitler, V.P. Sales/Mktg 866-491-5020 • Region: Western U.S. – Glen Gallamore, Reg. Sales Mgr. 303-947-4273

 • Region: Eastern U.S. – Steve Koch, Reg. Sales Mgr. 308-940-6652 • Region: Upper Midwest – Andy Ross/Bob Scheel, Sales Rep. 630-719-1687

 PC Sales Customer Service: Toll Free 866-491-5020 • Fax 615-446-8188 • East – Charlene Harris • West – Karen Davis