October 19th, 2011

# Technical Assignment 2



Additions and Renovations

Michael Beam | Construction Option | Advisor: Dr. Messner



### **Executive Summary**

**Technical Assignment Two** is aimed at providing a more detailed view of the Unionville High School Building Additions and Renovations project. The project consists of both new construction as well as renovations and has a total size of 319,000 square feet. Analyses within the report include a more detailed project schedule, an estimation of the structural system for the building, a general conditions estimate, a LEED evaluation based on the most recent rating system, and an analysis of the use or potential use of BIM for the Unionville High School Building Additions and Renovations.

As an educational project, the Unionville High School project proposes many issues. One of the main issues for this project in particular is the task of keeping specific portions of the building in use as other are under construction. In order to produce a high quality product on time without disturbing the building inhabitants, a detailed phasing plan was created to develop the schedule. A detailed schedule for the project has been created and is included within the report. Ultimately, the project **began on June 16<sup>th</sup> 2009** and is set to **conclude on September 28<sup>th</sup> 2012**. Note: the project is roughly three months ahead of schedule as of the creation of this report; the original completion date was December 28<sup>th</sup> 2012.

For the detailed structural system estimate, one of the new additions to the building was analyzed. Using a new portion of the building or this estimate, Area D, allowed for a more accurate structural system investigation. In total, the cost from the estimate structural system for Area D is approximately \$3,394,000.00. A general conditions estimate is also contained within the report, with the total estimate coming to \$4,400,000.00.

Green building is growing in importance and is arguably the most important factor for new construction in today's industry. In this report, an analysis is done on both the LEED 2007 system and the LEED 2009 system. The 2007 system is analyzed because the project was designed using this specification, while the 2009 system is also evaluated to determine how the project would have been rated using the most recent evaluation. Under the LEED 2007 system, the project is qualified to receive a **LEED 2007 Silver Certification**; due to changes and additional credits being added to the new system, the project is qualified to receive only a **LEED 2009 Certification**.

Finally, the use of BIM on the project is outlined. Although BIM was not used for this project as part of the original design, the potential use of BIM is outlined and detailed. In summary, it is in my opinion that **BIM use would have been of value** for the project if the circumstances of the project permitted. For the project as it was designed, however, BIM was not applicable and therefore was not employed.



# **Table of Contents**

Executive Summary —	i
Table of Contents —	ii
Detailed Project Schedule ————————————————————————————————————	1
Detailed Structural System Estimate ————————————————————————————————————	3
General Conditions Estimate —	8
LEED Evaluation ————————————————————————————————————	10
Building Information Modeling Use Evaluation ————	14
Appendix A – Phasing Plan and Building Area Key ———	18
Appendix B - Detailed Project Schedule ————————————————————————————————————	20
Appendix C - Detailed Structural System Estimate ———	31
Appendix D - General Conditions Estimate —————	40
Appendix E - LEED 2007 Scorecard ————————————————————————————————————	43
Appendix F - LEED 2009 Scorecard ————————————————————————————————————	48
Appendix G - BIM Evaluation ————————————————————————————————————	50



## **Detailed Project Schedule**

Projects including additions and renovations to a building require that some or most of the building remain in use during the construction process. As a result, the Unionville High School Building Additions and Renovations project follows a carefully designed phased construction schedule. The GMP contract was developed and agreed upon between UCFSD and Wohlsen Construction as a result of a hard bid publics work job. Overall, the project design spanned from June of 2008 until 2009, with construction initially slated to begin on June 22<sup>nd</sup>, 2009 and finish on December 28<sup>th</sup>, 2012. As of October 19<sup>th</sup> 2011 when this report was completed, the estimated finish for the project had moved up roughly three months and is expected to be completed on September 29th, 2012. With multiple phases during construction, the project team was able to develop a schedule in order to efficiently complete building construction while limiting the disruption of everyday life for students and faculty.

Each phase of construction focuses on one portion of construction, although some phases do incorporate multiple areas of the building. The first phase focuses on the addition of a new wing which will house District Offices and classroom space. Phase three focuses on the addition of the new Auditorium as well as the renovation of existing spaces within the building. The existing auditorium is renovated into Choral and Tech Ed rooms during phase three, and phase four sees the demolition of an existing portion of the building in order to make room for the new Gymnasium. Overall the project duration (as of this report) is set to span 39 months from June 15<sup>th</sup> 2009 until September 28<sup>th</sup> 2012. The phasing plan, as well as a map outlining the areas of the building, can be seen in APPENDIX A. Phase descriptions and phase timelines are listed below.

#### **Phase Descriptions**

- Phase 1: Construction of the New 3 story addition, set to house the Unionville-Chadds Ford School District Administrative Offices, Classrooms, and Science labs.
- Phase 2: Construction of the New Auditorium, Art rooms, and Family and Consumer Classrooms.
- Phase 2A: Renovation of existing Large Group Instruction, Library, Faculty Restrooms, Cafeteria, and Kitchen.
- Phase 2B & 2C: Renovation of existing District Administrative Offices into High School Offices, Science Labs, and Classrooms.
- Phase 2D: Renovation of existing High School Offices, Music Area, and Faculty Dining.
- **Phase 2E**: Renovation of existing Science Labs and Classrooms.
- Phase 2F: Renovation of existing Classrooms
- Phase 2G: Renovation of the existing Computer Applications Labs and Classrooms.
- Phase 2H, 2I, 2J: Renovation of existing Classrooms.
- Phase 3: Renovation of existing Auditorium into Choral Room and Tech Ed Classrooms.
- **Phase 4:** Demolition of existing Classroom and Tech Ed Wing and Weight Room.
- Phase 4A: Renovation of existing Gymnasium, Locker and Team Rooms.
- Phase 4B: Demolition of existing Auxiliary gym.



#### **Phase Timelines**

Design	June 16th 2008 - June 12th 2009
Phase 1	June 15th, 2009 - June 25th, 2010
Phase 2	June 9th 2010 - June 23rd 2011
Phase 2A	June 2 <sup>nd</sup> 2010 - July 28 <sup>th</sup> 2011
Phase 2B & 2C	June 30th 2010 - December 31st 2010
Phase 2D	January 6th 2011 - June 27th 2011
Phase 2E	January 3 <sup>rd</sup> 2011 - January 21 <sup>st</sup> 2011
Phase 2F	January 24th 2011 - February 11th 2011
Phase 2G	February 14th 2011 - March 4th 2011
Phase 2H	March 14th 2011 - April 1st 2011
Phase 2I & 2J	April 4th 2011 - June 3rd 2011
Phase 3	June 9th 2011 - December 30th 2011
Phase 4	July 7th 2011 - April 27th 2012
Phase 4A	May 24th 2011 - September 28th 2012
Phase 4B	April 30th 2012 - June 29th 2011

Overall, phased construction was easily the best choice for a project of this type. While working during school hours presents many challenges, phased construction allows for the careful planning of construction in order to manage the interaction between construction and everyday life. Thus far, construction has gone accordingly and the schedule has been met. As a result, normal school activities have gone uninterrupted while construction continues to be completed according to schedule.

The entire project schedule can be seen in APPENDIX B.



### **Detailed Structural System Estimate**

As a large project with both new additions and renovations there are many different types of construction going on throughout the project life cycle. This detailed structural estimate focuses on one of the major new additions to the building; Phase one for the Unionville High School Additions and Renovations projects encompasses the construction of a new wing containing the Administrative Office building for the Unionville-Chadds Ford School District as well as new classroom and science lab space (this area of the project is known as Area D, see Figure 1). Quantity takeoffs and specific cost information regarding each line item can be found, organized by CSI Masterformat, in APPENDIX C. The following items have been included in this estimate.

- Spread Footings
- Strip Footings
- Concrete Piers
- Slab-On-Grade
- CMU Foundation Walls
- Concrete Retaining Wall
- Structural Steel Columns and Beams
- Elevated Concrete Slabs on Metal Decking
- Metal Roof Decking

This detailed estimate has been produced using RS Means Building Construction Cost Data 2011. For the purpose of this estimate, total costs exclude overhead and profit. The estimate is broken down into cost estimates for typical bays based on specific floors, as the typical bay for the first and second floor was

the same while the third floor and roof needed analyses for individual bays. Organizing the estimate in this manner allowed for a more realistic estimate than assuming one typical bay for all three floors and the roof. Structural steel values throughout the estimate include all steel members but exclude connections. Descriptions, assumptions, and total costs for each floor can be seen below. A location factor of 108.9 for Westchester Pennsylvania will be applied to the final cost for the entire structural system. Values have been rounded up to allow for easier interpretation of the data.




Figure 1: Area D



#### **Foundation and First Floor**

The foundation for the portion of the building being analyzed for this estimate, Area D, includes spread footings, strip footings, concrete piers, slab-on-grade, CMU foundation walls, and a small concrete retaining wall. Typical bay size for this floor is assumed to be 24'-1" x 28'0", or 675 square feet. A 4" slab-on-grade is to be pumped into place on top of 4" of crushed stone (which has not been included in this estimate) with 6x6W1.4x1.4 WWF. Each structural steel column sits on a spread footing, with select columns resting on reinforced concrete piers. These piers as well as the strip footings, concrete retaining wall, and CMU foundation walls have all been accounted for in the overall cost per square foot of the foundation estimate by adding their entire value to the extrapolated data from the typical bay. These items have not been included as a part of the cost of the typical bay, as these items do not show up regularly. Cost information can be seen below.

#### Foundation and First Floor | Cost per bay

o- 20.	
Material	\$10,000.00
Labor	\$8,500.00
Equipment	\$350.00
Total	\$19,000

#### Foundation and First Floor | Cost per S.F.

Material	\$15.00
Labor	\$12.50
Equipment	\$0.50
Total	\$28.00

#### Foundation and First Floor | Cost for Entire Area D

Material	\$470,000.00
Labor	\$390,000.00
Equipment	\$15,500.00.00
Total	\$875.500.00



#### **Second Floor**

Like the foundation and first floor typical bay, the second floor bay is assumed to be  $24'-1'' \times 28'-0''$ , or 675 square feet. An elevated slab is composed of 1.5" thick 18 gauge metal decking and 3" of normal weight concrete. Concrete is to be pumped and is to have a compressive strength of 4000 psi with 6x6 W1.4x1.4 WWF.

Second Floor | Cost per bay

Material	\$18,000.00
Labor	\$2,000.00
Equipment	\$500.00
Total	\$20,500.00

Second Floor | Cost per S.F.

Material	\$27.00
Labor	\$3.00
Equipment	\$0.75
Total	\$30.75

Second Floor | Cost for Entire Area D

Material	\$800,000.00
Labor	\$90,000.00
Equipment	\$21,000.00
Total	\$910,000.00

#### Third Floor

The third floor typical bay is a bit larger than the previous two and is assumed to be 24'-8" x 37'-6", or 925 square feet. An elevated slab is to be used like the second floor, with a system using 1.5" thick metal decking and 3" of normal weight, pumped concrete with a compressive strength of 4000 psi with 6x6 W1.4x1.4 WWF making up the flooring system for the third floor.

Third Floor | Cost per bay

\$21,500.00
\$2,500.00
\$500.00
\$24,500

Third Floor | Cost per S.F.

Material	\$23.25
Labor	\$2.50
Equipment	\$0.50
Total	\$26.25

Third Floor | Cost for Entire Area D

Material	\$695,000.00
Labor	\$75,000.00
Equipment	\$16,000.00
Total	\$786,000.00



#### Roof

Larger than both of the two previous bays, the typical bay for the roof structure measures 24'-8" x 41'-10", or 1032 square feet. 1.5" thick metal roof decking will be installed to top out the structure for this portion of the building, with no concrete being applied to the top of the deck.

#### Roof | Cost per bay

Material	\$17,000.00
Labor	\$1,500.00
Equipment	\$500.00
Total	\$19,000

### Roof | Cost per S.F.

Material	\$16.50
Labor	\$1.50
Equipment	\$.50
Total	\$18.50

#### Roof | Cost for Entire Area D

Material	\$490,000.00
Labor	\$40,000.00
Equipment	\$14,000.00
Total	\$544.000.00



#### **Structural System Cost**

The data below displays information regarding the estimate for the cost for the entire project. Values for specific Material, Labor, Equipment, and Total Cost are calculated for Concrete, Structural Steel, and the Structural System as a whole, including the cost with the location factor applied.

#### Concrete | Cost per S.F.

Material	\$16.50
Labor	\$16.00
Equipment	\$0.10
Total	\$32.60

#### Structural Steel | Cost per S.F.

Material	\$66.75
Labor	\$4.40
Equipment	\$1.60
Total	\$72.75

#### Complete Structural System Cost | Total Cost

\$2,450,000.00
\$600,500.00
\$66,000.00
\$3,116,000.00
\$3,394,00.00

Overall, the estimated cost for the entire structural system for Area D comes to \$3,394,000.00.While this estimate has included most of the items within the structural system, some items have been left out. Exclusion of certain items, such as steel connections and construction joints, can change the value of the estimate. Another potential issue with using RS means is the accuracy of the cost data. RS means cost data provides national averages, which may not be on par with the cost of the material, labor, and equipment used for this specific project. Finally, a typical bay can provide a quality estimate but may not extrapolate quite accurately enough to truly represent the cost of the system. For this reason, typical bays were selected for each floor.

Again, all information regarding this structural estimate can be found in APPENDIX C, organized by floor and further by CSI Masterformat.



#### **General Conditions Estimate**

Rather than estimating just one portion of the project (as was done with the structural estimate), the entire project has been accounted for in this general conditions estimate. The source for the information used to develop this general conditions estimate comes from RS Means Building Construction Costs 2011.

Several assumptions have been used to produce this estimate:

- Project Information
  - Project Duration:
    - 183 Weeks
    - 42 Months (original schedule)
  - Construction Site size
    - 900,000 Square Feet
    - 21 Acres
  - o Construction Site Perimeter
    - Perimeter: 4,300 Linear Feet
- Field Personnel
  - 'Clerk' has been used to estimate the cost of a Project Assistant
  - o 'Field Engineer' has been used to estimate the cost of a Project Engineer
- Temporary Utilities
  - The only temporary utilities accounted for in this estimate refer to the utilities providing power, electricity, HVAC, etc. to the trailer. All power and other utilities for the project are assumed to have been provided by existing portions of the building.

Construction fees and contingencies have been excluded from this estimate. Due to the lack of some 'Total Cost' information for certain items used in this estimate, all costs have been quantified using 'Total Cost including O&P' data. Final values include a *location factor of 108.9* and have been rounded to more easily interpret the cost data. Based on these assumptions, the following cost information has been derived.

#### **General Conditions | Total Cost**

Total Cost including 0&P \$4,020,000.00
Total Cost with Location Factor \$4,400,000.00
Construction Cost \$52,000,000.00

**General Conditions % of Total Cost** \$8.5%

#### Unionville High School | Technical Assignment 2



At 8.5%, this estimate is within a reasonable range in terms of price relative to the overall project cost. Most costs were calculated to be incurred for the entire duration of the project, but several costs were estimated based on their estimated duration on the project. Small variations may have altered the value of the estimate due to the exclusion of specific items from the estimate, namely items that RS Means did not have a specific value for. A further breakdown of the estimate can be seen below, with the entire project cost being divided into monthly costs for four main categories: Field Personnel, Insurance and Bonds, General Construction Costs, and Office and Storage Space. These values are derived from the General Conditions Cost with the location factor (108.9) applied.

#### **General Conditions | Cost Per Month (including Location Factor)**

•	
Project Staff	\$41,500.00
<b>Insurance and Bonds</b>	\$37,000.00
<b>General Construction Costs</b>	\$25,000.00
Office and Storage Space	\$1,000.00
Total Cost	\$104,500.00

With more than \$100,000.00 per month in general conditions costs, it is clear that the schedule must be followed precisely. Not only would a delay produce direct costs, but liquidated damages (agreed upon in the contract) would be incurred as well. Note: Although some costs in the estimate are not incurred for the entire duration of the project, these values have been calculated as a division of the entire cost by the duration of the project in order to provide a rough estimate of monthly costs. This calculation allows for a quick view at which portions of the general condition contribute more to the job cost than others.

All General Conditions estimate information can be found in APPENDIX D.



### **LEED Evaluation**

LEED, Leadership in Energy and Environmental Design, is a major part of the construction industry and has grown significantly since its inception in March 2000. Green building promotes sustainable design and building construction practices and provides a rating system for owners or other perspective builders to follow in hopes of earning a LEED certification. This section will provide two analyses: LEED for Schools 2007 and LEED 2009 for New Construction and Major Renovations. As design and construction for the Unionville High School Building Additions and Renovations project began prior to the inception of LEED 2009, the project is eligible to be rated based on the 2007 system and will receive a 2007 certification upon completion should it meet the necessary requirements. An analysis of the project based on the 2007 system will provide information regarding the ranking that the project will receive (should all proposed requirements be met). A LEED 2009 scorecard is also filled out to determine which ranking the project would get if it were to be judged based on the new system, as well as certain categories and points that the project could target to improve the LEED rating.

#### **LEED for Schools 2007 Analysis**

The LEED for Schools 2007 rating system provides a checklist structured more towards educational projects offering a maximum of 79 points. Items such as "classroom acoustics, master planning, mold prevention, and environmental site assessment" (USGBC.org) are rated in order to provide an education specific rating for K-12 school projects. The rankings for the 2007 system are as follows:

#### **LEED for Schools 2007 Certification Ratings**

Certified 29-36 points
Silver 37-43 points
Gold 44-57 points
Platinum 58-79 points

After completing the checklist, the Unionville High School Building Additions and Renovations project team applied to qualify for **40 points** and ultimately aims to receive a LEED for Schools 2007 Silver Certification. Due to the fact that construction began before the LEED 2009 system was completely implemented, should these points be achieved the project will receive the **2007 Silver Certification**. A filled out LEED for Schools Scorecard showing in detail which points were achieved has been filled out and is available in APPENDIX E.



#### **LEED 2009 for New Construction and Major Renovations**

The Unionville High School Building Additions and Renovations project was developed before the LEED 2009 system, as mentioned above, and as such will be rated based on the 2007 system. This analysis is provided in order to outline which points the original design qualifies for based on the 2009 system as well as areas that the project could improve on or target in order to improve the rating. With nearly 140% as many points (110 total points compared to 79 points), it is safe to say that the new system has been developed to provide a more accurate assessment of how sustainable a given project is. The certification breakdown can be seen below.

#### **LEED 2009 Certification Ratings**

Certified 40-49 points
Silver 50-59 points
Gold 60-79 points
Platinum 80-110 points

Based on the 2009 system, the UHS project is set to earn **43 credits** and earn a LEED certified rating. While this in and of itself can be considered a success, there is certainly room for improvement should the owner be interested in earning a Silver or better certification. Based on the original design, there are several areas that could be improved slightly in order to earn more points as well as new areas that have not been targeted in the original sustainable design goals and could be achieved with a minimal amount of effort. Possible improvements will be mentioned but obtainability will not analyzed as it is difficult to determine exactly how feasible attaining extra credits might be based on the budget available, the desire to achieve these credits, and how the work to achieve these goals might affect the schedule. Each point category is outlined and suggested pursuit of additional points within each category is described.

#### **Sustainable Sites**

The first section in LEED 2009 is Sustainable Sites and is aimed at reducing pollution as a result of construction, minimalizing the projects' impact on the surrounding environment, and preservation of existing natural and green areas. A total of 26 points are possible within this category, with the majority of the points focusing on Alternative Transportation (12 points). For this project, just six points were obtained in the Sustainable Sites portion of the checklist. Alternative transportation is an area that was difficult for this project to target successfully. While one point was gained for Bicycle storage, the other points remained untouched. As both a high school and a school district administrative office, parking capacity needed to remain large enough to serve faculty, students, and administrative office personnel. Although not targeted as part of the initial LEED evaluation, the credit for Development Density and Community Connectivity may be an option as an additional credit as this project either meets all requirements or could do so with minimal effort. Overall, several points were gained here but the inability to target the alternative transportation credits within this section kept the score low.



#### **Water Efficiency**

As such a valuable commodity, water use reduction is of supreme importance in today's construction industry. The Water Efficiency section of the LEED scorecard focuses on improvement of water use efficiency, reduction wastewater production, and reduction of water use for landscaping purposes. With a score of two out of a possible ten credits, this area of the checklist was again difficult to target for this specific project. The two credits were gained as a result of reducing landscaping water use by 50%. With significant effort already being put into this area of the project to cut landscaping water usage in half, the complete reduction of potable water use may be a credit worth targeting. Waste water reduction was also targeted, but only to reduce the usage by a total of 20%. While this was worth one credit in the 2007 LEED rating system, the lowest threshold for reduction in the 2009 system is 30% reduction. An increase in reduction by 10% may be another reasonable goal for the project and gain two additional credits.

#### **Energy and Atmosphere**

The Energy and Atmosphere section provides the opportunity for a large quantity of points, targeting the reduction of energy use throughout the building, reduction of mechanical operating costs, increased energy efficiency, and the potential use of on-site and renewable energy sources. Targeting improvement of energy use is worth 19 of the 35 total credits for this section. As designed, the UHS project is aiming to improve energy performance by 24% for new buildings and 20% for renovations, worth seven credits. It is reasonable to believe that small changes could be made to improve this reduction, perhaps all the way to 28% improvement for new buildings and 24% for renovations. As for renewable energy, the implementation of solar panels on some or all areas of the roof could provide enough energy to receive an addition credit.

#### **Materials and Resources**

The Materials and Resources section focuses on the proper handling of materials during construction, namely the recycling of construction waste, reuse of existing structures, and the use of regional materials for the project. Overall, this project aims to achieve 11 out of a possible 14 credits. As designed, the project is aiming to reuse 75% of the original building and recycle or salvage 50% of construction waste. Improving these numbers to 95% reuse and 75% construction waste recycled could be achieved with minimal effort would add several credits to the building total.



#### **Indoor Environment Quality**

As the name indicates, the focus of this section is to increase or maintain a high indoor environment quality. This section focuses on the quality of the indoor environment during construction by implementing strict guidelines prior to construction as well as using low-emitting materials. Other areas of emphasis include pollutant control and inhabitant productivity and comfort. This building's design meets many of these requirements, achieving 11 out of 15 possible credits. Using low-emitting flooring systems as well (the only low-emission category not targeted) would gain an additional credit.

#### **Innovation and Design Process**

This section of the scorecard promotes the creation of new credits for project teams. Items that go beyond the requirement for other credits may be considered for additional credits in this section. Surpassing energy or water efficiency credit thresholds may be a way to gain such credits.

#### **Regional Priority Credits**

Regional Priority credits provide motivation for projects to target credits that are more important for buildings in their specific area. For this project, three regional priority credits were met: Materials and Resources credit 2: 50% Construction Waste Recycled or Salvaged, Sustainable Sites credit 5.1: Protect or Restore habitat, and Sustainable Sites credit 6.1: Stormwater design quantity control. These three credits are of more importance to the Southeastern Pennsylvania location and as such carry more important during this sustainability analysis.

#### Conclusion

Ultimately, the project has room for improvement in terms of the LEED 2009 rating system. Combined with the 43 original points, the addition of the previously mentioned suggestions could ultimately result in a **10 point** increase in points to a total of **53 points**. At 53 points, the project would qualify for a **Silver Certification** in the LEED 2009 system. Again, the suggestions made are very general; some of these addition credits may actually be attainable, while others may be completely unachievable and out of the scope for this particular project.

A filled out LEED 2009 for New Construction and Major Renovations scorecard can be viewed in APPENDIX F.



# **Building Information Modeling Use Evaluation**

As the construction industry continues to grow and technology continues to develop, the use of Building Information Modeling is emerging rapidly. For this project, BIM was not implemented as part of the original project design. In this section, the potential for BIM use on this project will be analyzed; project goals, potential BIM uses, and those uses that are most sensible for the project are outlined in this section.

With almost a countless number of uses for Building Information Modeling, it may be difficult to determine which ways to best use the technology. To begin this process, potential project goals are developed prior to design and analyzed to determine which of these goals are worth pursuing. Each goal serves a specific purpose, with some being of more value to the project than other. Some goals incorporate a single BIM use, while others use BIM for multiple reasons. Proposed goals are listed below, with the BIM uses ultimately determined for the project listed as well.

#### **Major BIM Goals and Potential BIM Uses**

PRIORITY (HIGH/ MED/ LOW)	GOAL DESCRIPTION	POTENTIAL BIM USES
High	Phased Construction and Project Flow Planning	3D Coordination, 4D Modeling, Design Authoring
High	Construction Progress Tracking	4D Modeling, Programming, Design Authoring, Record Modeling
Low	MEP Trade Clash Detection	3D Coordination, Design Authoring
Med	Increase Sustainable Design Goal efficiency	LEED Evaluation
High	Improve/Increase Construction Productivity	3D Coordination, 4D Modeling, Construction System Design, 3D Control and Planning,
Med	Cost Tracking and Estimating	Cost Estimation



#### **BIM Use Analysis**

X	PLAN	X	DESIGN	Х	CONSTRUCT	X	OPERATE
x	PROGRAMMING	х	DESIGN AUTHORING		SITE UTILIZATION PLANNING		BUILDING MAINTENANCE SCHEDULING
	SITE ANALYSIS		DESIGN REVIEWS		CONSTRUCTION SYSTEM DESIGN		BUILDING SYSTEM ANALYSIS
			3D COORDINATION	х	3D COORDINATION		ASSET MANAGEMENT
			STRUCTURAL ANALYSIS		DIGITAL FABRICATION		SPACE MANAGEMENT / TRACKING
			LIGHTING ANALYSIS	х	3D CONTROL AND PLANNING		DISASTER PLANNING
			ENERGY ANALYSIS	х	RECORD MODELING	х	RECORD MODELING
			MECHANICAL ANALYSIS				
			OTHER ENG. ANALYSIS				
		х	SUSTAINABLITY (LEED) EVALUATION				
			CODE VALIDATION				
x	PHASE PLANNING (4D MODELING)	х	PHASE PLANNING (4D MODELING)	х	PHASE PLANNING (4D MODELING)		PHASE PLANNING (4D MODELING)
x	COST ESTIMATION	х	COST ESTIMATION	х	COST ESTIMATION		COST ESTIMATION
	EXISTING CONDITIONS MODELING		EXISTING CONDITIONS MODELING		EXISTING CONDITIONS MODELING		EXISTING CONDITIONS MODELING

After analyzing the potential goals suggested early in this section and determining those that are worth pursuing, it is determined that BIM could be implemented during each phase of the project, with the majority of BIM use coming during the construct phase. Ultimately, 3D Planning and 4D Modeling appear to be of the highest value for this particular project, although cost evaluation could prove useful to track costs during a long project such as this. In total, eight BIM uses are to be implemented for the proposed use of BIM on this specific project; these uses and what they provide to a project are outlined below.

#### **Building Information Modeling Uses Implemented**

Record Modeling
3D Control and Planning
3D Coordination
Design Authoring
LEED Evaluation
Programming
4D Modeling
Cost Estimation



#### **BIM Use Descriptions**

- Record modeling refers to the process of depicting the physical and environmental aspects of a given project. Information regarding MEP and Architectural systems, as well as information regarding planning for the project is contained within this model. Pre-build specifications can be linked with as-built specifications, showing how the two phases of construction match up and can help to resolve disputes during construction.
- 3D Control and Planning uses a model in order to help layout the construction of the building. Component drawings can be created to aid foreman onsite and can lead to increased communication and more efficient layout.
- Similar to 3D Control and Planning, 3D Coordination uses a model to decrease errors during construction. Clash detection is performed using the model to determine areas of concern between multiple trades. The ability to detect potential hang ups prior to work being placed in the field is invaluable to any project where keeping the schedule is of critical importance. Other key values of 3D Coordination include more accurate as built drawings, construction visualization for specific trades, and overall project coordination.
- Design Authoring is the basic building block of any BIM model. Authoring software is used to create a Building Information Model, with design conditions based on each specific project. This model is used to depict the project, while other software is used in combination with this model in order to increase the type and amount of information that is incorporated with that model. Ultimately, design authoring is the first step in the process of utilizing a BIM model and allows for increased coordination and better project visualization.
- ❖ Using BIM to perform a LEED evaluation provides added value to a project that is already targeting a LEED certification. The ability to use BIM to evaluate the project based on LEED criteria allows for a more accurate depiction of the sustainable design and construction goals. Energy use within the building can be tracked more easily as all sustainable features of the project can be modeled and tracked throughout the lifecycle of the project.
- Programming helps to determine how efficiently a project's use of space is. The BIM model allows the visualization of the spatial qualities of the project and helps to expedite decisions regarding these requirements.
- 4D Modeling is one of the most important uses of BIM for this specific project. This process uses the 4D model to plan phased occupancy (a major feature of the Unionville High School Building project) for both additions and renovations. The project team benefits from the 4D model to better understand the phasing of the project, identify potential schedule or phasing issues, and track information regarding specific project materials.
- Cost estimation uses the BIM model in order to create accurate cost estimates as well as takeoffs of different materials used during construction. Change order costs as well as costs for other design changes can be determined with more efficiency.

Note: The Penn State BIM Execution Planning Guide V2.0 was used in large part to acquire this information. This guide can be found at www.engr.psu.edu/BIM.



#### **BIM Implementation**

In order to efficiently utilize BIM for a construction project, all affected parties must be involved. Using a Building Information Model is most effective when everyone in the project team can benefit from its use. For this specific project, it is proposed that a model is created by each individual party (Architect, Engineer, Trades, etc.) once the design process has concluded.


Each portion of the model will be created by a separate party (architecture, MEP, structural, site, etc.). Once each model has been constructed, each of these separate models is to be combined and held by the General Contractor. When coordination is scheduled, all parties will meet and each part of the model will be combined at that time. This allows all parties to remain abreast of the current state of the projects, see how their system fits relative to other systems, and see how other systems may be affected by theirs. The CM will maintain control over the model at all times in order to provide access to the model to the owner. At the completion of the project, the complete and up to date model will be turned over to the owner. At that time, any baseline training needed for the owner to understand use of the model would be administered.

For this project, BIM may not be appropriate based on the subcontractors selected, the knowledge of BIM for involved parties, and the owner's desire to have access to this information after construction is completed. Although BIM was *not* utilized on this project, it *would* in my opinion benefit the project team if the circumstances permitted. Several key areas of the project could benefit from the specific BIM uses outlined, especially in regards to the Phase Planning and Cost Estimation. The use of BIM would have to be determined prior to construction and even prior to bidding, as some potential subcontractors may be unable to effectively utilize this technology. Once selected, subcontractors, engineers, and the architect would be responsible for producing their specific models. The models would then be managed by the General Contractor, and all parties would come together in times of collaboration.


Overall, I believe that BIM use could have been beneficial for this project. The addition of this technology would allow more precise cost management for the project and would help to give everyone involve a better visual understanding of the project prior to construction as well as during construction. Under the circumstances (BIM experience and proficiency of all involved parties), however, BIM use may have been difficult to implement for this project and as a result was not used for the Unionville High School Building Additions and Renovations project.


A BIM Goal Use Analysis worksheet as well as a BIM Process map can be seen in APPENDIX G.

APPENDIX A	- Phasing Pla	nn and Buildi	ng Area Key	




# FIRST FLOOR LEVEL MASTER PHASING PLAN






### SECOND FLOOR LEVEL MASTER PHASING PLAN



# THIRD FLOOR LEVEL MASTER PHASING PLAN

PHASING K	PHASING KEY:					
PHASE 1	22 JUNE, 2009 - 25 JUNE, 2010					
PHASE 2	28 JUNE, 2010 - 01 JULY, 2011					
PHASE 2A	14 JUNE, 2010 - 15 AUGUST, 2010					
PHASE 2B	28 JUNE, 2010 - 31 DECEMBER, 2010					
PHASE 2C	06 SEPTEMBER, 2010 - 31 DECEMBER, 2010					
PHASE 2D	03 JANUARY, 2011 - 01 JULY 2011					
PHASE 2E	03 JANUARY, 2011 - 21 JANUARY, 2011					
PHASE 2F	24 JANUARY, 2011 - 11 FEBRUARY, 2011					
PHASE 2G	14 FEBRUARY, 2011 - 04 MARCH, 2011					
PHASE 2H	07 MARCH, 2011 - 25 MARCH, 2011					
PHASE 2I	28 MARCH, 2011 - 15 APRIL, 2011					
PHASE 2J	18 APRIL, 2011 - 06 MAY, 2011					
PHASE 3	04 JULY, 2011 - 30 DECEMBER, 2011					
PHASE 3A	13 JUNE, 2011 - 12 AUGUST, 2011					
PHASE 4	02 JANUARY, 2012 - 28 SEPTEMBER, 2012					
PHASE 4A	18 JUNE, 2012 - 02 NOVEMBER, 2012					
PHASE 4B	05 NOVEMBER, 2012 - 28 DECEMBER, 2012					

APPENDIX B -	Detailed Pro	oject Schedul	e	



ID	Task Mode	Task Name		Duration	Start	Finish	lanuary 1	October 1	July 1	April 1	January 1	October 1	July 1	April
26	Mode	First Flo	por	158 days?	Wed 11/18/09	Fri 6/25/10	1/13	5/25 10/5	2/15 6/28	11/8 3/21 8/1 First Floor	12/12 4/24	9/4 1/15	5/27	10/7 2/17
27	*	MEP	Rough In	56 days	Wed 11/18/09	Wed 2/3/10			MED Download					
28	*	MEP	Layout	39 days	Wed 12/2/09	Mon 1/25/10			MEP Rough In					
29	<b>★</b>	MEP	Installation	61 days	Wed 12/9/09	Wed 3/3/10			MEP Layout	1/25				
30	<b>☆</b>	Sprin	ıkler Installation	91 days	Thu 12/31/09	Thu 5/6/10			MEP Installation	3/3				
31			iors/Finishes	80 days	Thu 2/18/10				Sprinkler Installation	5/6				
									Interiors/Finis	shes 6/9				
32	A.	Punc	hlist	9 days	Tue 6/15/10	Fri 6/25/10				Punchlist 🛚 6/25				
33	*	Subs	stantial Completion First Flooi	r 0 days	Fri 6/25/10	Fri 6/25/10			Substantial Completi	ion First Floor 🔷 6/25				
34	<b>₹</b> ?	<nev< td=""><td>v Task&gt;</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></nev<>	v Task>											
35	3	Second	Floor	144 days?	Thu 11/19/09	Tue 6/8/10				Second Floor				
36	A <sup>2</sup>	MEP	Rough In	77 days	Thu 11/19/09	Fri 3/5/10			MEP Rough In	3/5				
37	*	MEP	Layout	42 days	Thu 12/10/09	Fri 2/5/10								
38	*	MEP	Installation	60 days	Fri 12/18/09	Thu 3/11/10			MEP Layout					
39	₹	Sprin	ıkler Installation	67 days	Fri 1/22/10	Mon 4/26/10			MEP Installation	3/11				
40	<b>☆</b>	Inter	iors/Finishes	76 days	Thu 2/11/10	Thu 5/27/10			Sprinkler Installation	on 4/26				
41		Punc				Tue 6/8/10			Interiors/Finis	shes 5/27				
				8 days						Punchlist 🛮 6/8				
42	*	Subs	tantial Completion 2nd Floor	0 days	Tue 6/8/10	Tue 6/8/10		9	Substantial Completio	on 2nd Floor 🔷 6/8				
43	***	<nev< td=""><td>v Task&gt;</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></nev<>	v Task>											
44	3	Third F	loor	151 days	Thu 11/26/09	Fri 6/25/10				Third Floor				
45	A.	MEP	Rough In	81 days	Thu 11/26/09	Thu 3/18/10			MEP Rough In	3/18				
46	*	MEP	Layout	50 days	Fri 12/11/09	Thu 2/18/10			MEP Layout					
47	*	MEP	Installation	65 days	Thu 12/24/09	Wed 3/24/10								
48	*	Sprin	kler Installation	51 days	Wed 2/3/10	Wed 4/14/10			MEP Installation					
49	*	Inter	iors/Finishes	84 days	Wed 2/10/10	Mon 6/7/10			Sprinkler Installati					
50	*	Punc	hlist	8 days	Tue 6/8/10	Thu 6/17/10			Interiors/Finis	shes 6/7				
				,.	,-,	,,				Punchlist <b>T</b> 6/17				
			Taali		Danie at Comme			Innation Milaston		Manual Conserver 2	allina	Dandina		
D!		- d Caba III	Task Split		Project Summ External Tasks			Inactive Milestone Inactive Summary	<b>\$</b>	Manual Summary R  Manual Summary	onup	Deadline Progress	+	
	:: Tech 2 Detai ri 10/14/11	ed Schedule	Split Milestone		External Miles			Manual Task		•		riogiess		
	-, -,		Summary	<u>.</u>	Inactive Task	e \_		Duration-only		Start-only Finish-only				
			Juilliary		mactive rask			Duration-Only	(28)	Fillish-Ullly				

ID	0	Task Mode	Task Name	Duration	Start	Finish	January 1 1/13	October 1 5/25 10/5	July 1 2/15 6/28 11/8	April 1 8 3/21 8/1	January 1 12/12 4/24	October 1 9/4 1/1	July 1 5 5/27	10/7	April 1 2/17
51		*	Substantial Completion 3rd Floor	0 days	Thu 6/17/10	Thu 6/17/10			Substantial Completion 3						
52		À	Phase 1 - Area D Substantial Completion and Occupancy	0 days	Fri 6/25/10	Fri 6/25/10		Phase 1 - Area D Subst	antial Completion and Oc	ccupancy 🔷 6/25					
53		3	Phase 2 - Area F New Auditorium Addition	272 days	Wed 6/9/10	Thu 6/23/11				Phase 2 - Area F Ne	ew Auditorium Addition				
54		3	Sitework	39 days	Mon 6/28/10	Thu 8/19/10				Sitework	•				
55		*	E & S Controls	2 days	Mon 6/28/10	Tue 6/29/10			F 2. 0	S Controls = 6/29					
56		*	Site Demolition	2 days	Wed 6/30/10	Thu 7/1/10				Demolition = 7/1					
57		*	Roads and Sidewalks	37 days	Wed 6/30/10	Thu 8/19/10				Sidewalks 2 8/19					
58		3	Foundations and Structure	119 days	Wed 6/9/10				nodus anu	Foundations and St	ructure				
59		*	Foundations	64 days	Wed 6/9/10	<b>11/22/10</b> Mon 9/6/10			Fau	ndations = = 0/6	•				
60		*	Steel Erection	36 days	Wed 7/28/10	Wed 9/15/10				ndations 9/6					
61		À	Roof Construction	67 days	Fri 8/20/10	Mon 11/22/1	0			teel Erection = 9/1					
62		3	Façade	56 days	Tue 8/31/10	Tue 11/16/10	)		Root	f Construction Façade	•				
63		*	East Elevation Building Façade	31 days	Tue 9/7/10	Tue 10/19/10					•				
64		*	North Elevation Building Façade	20 days	Thu 9/16/10	Wed 10/13/1	0			Building Façade 📺 1					
65		*	West Elevation Building Façade	56 days	Tue 8/31/10	Tue 11/16/10				Building Façade 📺 1					
66		*	2nd Floor	160 days	Tue 9/7/10	Mon 4/18/11			West Elevation B	Building Façade	11/16				
67		*	MEP Installation	111 days	Tue 9/7/10	Tue 2/8/11									
68		À	Structure	28 days	Thu 9/23/10	Mon 11/1/10			N	MEP Installation	2/8				
69		*	MEP Rough In	40 days	Tue 9/28/10	Mon 11/22/1	0			Structure 📺	11/1				
70		<b>☆</b>	Interiors/Finishes	81 days	Wed 12/15/10					MEP Rough In	11/22				
71		<b>→</b>	Punchlist	8 days		Mon 4/18/11				Interiors/Finishe	s 4/6				
72		↑ A	Substantial Completion	0 days		Mon 4/18/11					Punchlist # 4/18				
73		<b>→</b>	3rd Floor	86 days	Tue 9/21/10					Substantial Co	ompletion 🔷 4/18				
74		<u> </u>													
		A"	MEP Installation	39 days	Tue 9/21/10				ı	MEP Installation	11/12				
75		A.	MEP Rough In	40 days	Mon 10/4/10	FII 11/26/10				MEP Rough In	11/26				
			Tools		Deciest Com			Innerting Addition		Manual Communication		Dandlin -			
Project	· Tech	2 Detailer	Task Split		Project Summ External Tasks			<ul><li>Inactive Milestone</li><li>Inactive Summary</li></ul>	<b>♦</b>	Manual Summary Ro Manual Summary	pilup -	Deadline Progress	+		_
Date: F			d Schedule Split Milestone		External Miles			Manual Task	·	Start-only	· · ·	05. 233			
			Summary		Inactive Task			☐ Duration-only		Finish-only	_				
			, , ,	<u> </u>						,					
								Page 3							

			Task Name	Duration	Start	Finish	lanuary 1	October 1	July 1	April 1	January 1	October 1	July 1	April
Punchist			Interiors/Finishes	22 days	Wed 12/15/10	Thu 1/13/11	1/13	5/25 10/5 2,	/15 6/28 11			9/4 1/15	5/27	10/7 2/17
Part	77	<u>.</u>	Punchlist	3 days	Fri 1/14/11	Tue 1/18/11				Interiors/Finishe	es 📺 1/13			
Second   S										Punch	nlist <b>_</b> 1/18			
Mary Layout	78	AT .	Substantial Completion	0 days	Tue 1/18/11	Tue 1/18/11				Substantial Complet	ion 🔷 1/18			
Met Rough in	79	A <sup>®</sup>	Auditorium/Stage/Balcony	259 days	Mon 6/28/10	Thu 6/23/11								
Methodology   Total	80	A <sup>2</sup>	MEP Layout	14 days	Tue 10/5/10	Fri 10/22/10				MED Lawrent -	10/22			
Structure   Stru	81	A <sup>2</sup>	MEP Rough In	65 days	Tue 10/12/10	Mon 1/10/11				_				
Structure   1/10   Structure	82	<u>.</u>	Structure	56 days	Mon 10/25/10	) Mon 1/10/11				MEP Rough In	1/10			
Punchist   10 days   Fe 6/30/11   Thu 6/23/11   Punchist   6/3   Punchist   Punchist   6/3   Punchist   Punchist   6/3   Punchist   P										Structure	1/10			
Subtantial Completion   O days   Thu 6/23/11   Thu 6/23/	83	<b>7</b>	interiors/Finishes	143 days	rue 11/23/10	Inu 6/9/11				Interiors/Finishes	6/9			
Phase 2A - Renovate Library, Caf, Kitchen   First Floor   Size   Substantial Completion   6/23   First Floor   Size   First Floor   First Floor   Size   First Floor   Size   First Floor   Size   First Floor   Size   First Floor   First Floor   Size   First Floor   First Fl	84	A CONTRACT	Punchlist	10 days	Fri 6/10/11	Thu 6/23/11					Punchlist 6/23			
Phase 2A - Renovate Library, Caf, Kitchen   Ritchen	85	A .	Substantial Completion	0 days	Thu 6/23/11	Thu 6/23/11				Substant	tial Completion 🛦 6/2	1		
Area E - 1st Floor   39 days   Thu 6/3/10   Tue 7/27/10	86			41 days	Wed 6/2/10	Wed 7/28/10	)		Phase 2					
Demolition   S days   Thu 6/3/10   Wed 6/9/10   Demolition \( \frac{1}{2} \)   Demolition \	87									• •				
Demolition \( \frac{1}{2} \)	88	3	Area E - 1st Floor	39 days	Thu 6/3/10	Tue 7/27/10				Area E - 1st Floor				
Structure	89	*	Demolition	5 days	Thu 6/3/10	Wed 6/9/10			מ	Demolition = 6/9				
91	90	A <sup>2</sup>	Structure	5 days	Fri 6/18/10	Thu 6/24/10				_				
	91	A <sup>P</sup>	MEP Rough In	10 days	Fri 6/18/10	Thu 7/1/10				_				
93  Punchlist 2 days Mon 7/26/10 Tue 7/27/10  94  Substantial Completion 0 days Tue 7/27/10 Tue 7/27/10  95  Area E - 2nd Floor 41 days Wed 6/2/10 Fri 6/11/10  96  Structure 8 days Wed 6/9/10 Fri 6/25/10  98  MEP Rough In 13 days Wed 6/9/10 Fri 6/25/10  98  MEP Installation 8 days Mon 6/28/10 Wed 7/7/10  99  MEP Installation 2 days Tue 7/27/10 Wed 7/28/10  Punchlist 7/7  99  Punchlist 2 days Tue 7/27/10 Wed 7/28/10  Project: Tech 2 Detailed Schedule Date: Fri 10/14/11  Project: Tech 2 Detailed Schedule Date: Fri 10/14/11  Task Project Summary Inactive Milestone Manual Task Start-only External Milestone Summary Inactive Summary Duration-only Finish-only 1									ME	EP Rough In 🛮 7/1				
94			·						Interi	ors/Finishes 🖀 7/23				
Substantial Completion ↑ 7/27  Area E - 2nd Floor  41 days	93	স"	Punchlist	2 days	Mon 7/26/10	Tue 7/27/10				Punchlist7/27				
96	94	A <sup>P</sup>	Substantial Completion	0 days	Tue 7/27/10	Tue 7/27/10			Substantia	al Completion 🔷 7/27				
Structure	95	3	Area E - 2nd Floor	41 days	Wed 6/2/10	Wed 7/28/10				Area E - 2nd Floor				
97	96	*	Structure	8 days	Wed 6/2/10	Fri 6/11/10								
MEP Installation 8 days Mon 6/28/10 Wed 7/7/10  99 Interiors/Finishes 21 days Mon 6/28/10 Mon 7/26/10  100 Punchlist 2 days Tue 7/27/10 Wed 7/28/10  Project: Tech 2 Detailed Schedule Date: Fri 10/14/11  Task Split Inactive Milestone Manual Summary Manual Summary Progress  External Tasks Inactive Summary Manual Summary Progress  External Milestone Manual Task Start-only Externolly Inactive Task Duration-only Finish-only	97	A <sup>P</sup>	MEP Rough In	13 days	Wed 6/9/10	Fri 6/25/10				_				
MEP Installation 17/7  99 Interiors/Finishes 21 days Mon 6/28/10 Mon 7/26/10  Punchlist 2 days Tue 7/27/10 Wed 7/28/10  Project: Tech 2 Detailed Schedule Date: Fri 10/14/11  Project: Tech 2 Detailed Schedule Summary Inactive Summary Inactive Summary Manual Summary Progress  External Milestone Manual Task Summary Manual Summary Progress  MEP Installation 17/7  Interiors/Finishes 7/26  Manual Summary Rollup Deadline Progress  Manual Summary Manual Summary Progress  External Milestone Manual Task Start-only Inactive Summary Inactive Summary Manual Summary Progress  Duration-only Finish-only 1	98	A <sup>P</sup>	MEP Installation	8 days	Mon 6/28/10	Wed 7/7/10			ME	Р Kough In 📳 6/25				
Project: Tech 2 Detailed Schedule Date: Fri 10/14/11  Task Split Split Milestone Summary Milestone Sum			Interiors/Finishes						MEP	Installation T 7/7				
Project: Tech 2 Detailed Schedule Date: Fri 10/14/11  Task Split S		M.							Interio	ors/Finishes 📺 7/26				
Project: Tech 2 Detailed Schedule Date: Fri 10/14/11	100	A*	Punchlist	2 days	Tue 7/27/10	Wed 7/28/10				Punchlist7/28				
Project: Tech 2 Detailed Schedule Date: Fri 10/14/11														
Date: Fri 10/14/11 Milestone			Task		Project Summ	ary 🖵	-	Inactive Milestone	<b>♦</b>	Manual Summary Ro	ollup	Deadline	•	
Summary Inactive Task Duration-only Finish-only			Schedule Split		External Tasks			Inactive Summary		Manual Summary	<b>—</b>	Progress	_	
	Date: Fri 10/14/	/11	Milestone	•	External Miles	tone 🔷		Manual Task		Start-only	С			
Dans d			Summary	-	Inactive Task			Duration-only		Finish-only	3			
Page 4								Page 4						

ID		Task	Task Name	<u> </u>	Duration	Start	Finish	January 1	Octo	ober 1	July	, 1	April 1	January 1	Octobe	r 1	July 1		April 1
	0	Mode						1/13		0/5 2/1		/28 11/			9/4	1/15	5/27	10/7	2/17
101		*	Sub	stantial Completion	0 days	Wed 7/28/10	Wed 7/28/10					Substantial	Completion > 7/2	8					
102		3	Area H	- 1st Floor	41 days	Wed 6/2/10	Wed 7/28/10						Area H - 1st Floo	r					
103		*	Asbe	estos Abatement	4 days	Wed 6/2/10	Mon 6/7/10				,	Asbestos Ab	atement <b>T</b> 6/7						
104		*	Stru	cture	18 days	Thu 6/3/10	Sat 6/26/10				-		Structure <b>6</b> /26						
105		*	Four	ndations	9 days	Wed 6/9/10	Mon 6/21/10						_						
106		*	MEP	Rough In	11 days	Mon 6/14/10	Sat 6/26/10						Indations 6/21						
107		*	MEP	Install/Test	24 days	Fri 6/18/10	Wed 7/21/10						Rough In 6/26						
108		*	Inter	riors/Finishes	19 days	Wed 6/30/10	Mon 7/26/10						stall/Test 📺 7/21						
109		*	Pund	chlist	2 days	Tue 7/27/10	Wed 7/28/10					Interio	rs/Finishes 📺 7/26						
110		7 <sup>th</sup>	Sub	stantial Completion	0 days	Wed 7/28/10	Wod 7/29/10						Punchlist <u>7</u> 7/28	1					
110			Sub	stantial Completion	0 days	wed 7/28/10	weu //28/10					Substantial	Completion   7/2	8					
111		3	Phase 2B Office	& 2C - Renovate District	133 days	Wed 6/30/10	Fri 12/31/10					P	Phase 2B & 2C - Reno	ovate District Office					
112		3	Area E	- 2nd Floor	133 days	Wed 6/30/10	Fri 12/31/10						Area E - 2	nd Floor					
113		*	Dem	olition	15 days	Wed 6/30/10	Tue 7/20/10					ı	Demolition 🝵 7/20						
114		*	Four	ndations	12 days	Wed 7/21/10	Thu 8/5/10						Foundations 8/5						
115		*	Stru	cture	25 days	Thu 7/29/10	Wed 9/1/10						Structure 📺 9/	/1					
116		*	MEP	Install	84 days	Wed 7/21/10	Mon 11/15/10	D					MEP Install						
117		*	Inter	riors/Finishes	44 days	Tue 10/19/10	Fri 12/17/10						Interiors/Finishes	_					
118		*	Pund	chlist	10 days	Mon 12/20/10	Fri 12/31/10							hlist 12/31					
119		*	Sub	stantial Completion	0 days	Fri 12/31/10	Fri 12/31/10						Substantial Comple	_					
120		3	Phase 2D & Family	- Renovate HS Offices, Music	123 days	Thu 1/6/11	Mon 6/27/11							novate HS Offices, Musi	c & Family D	ining			
121		3	-	- 2nd Floor	84 days	Thu 1/6/11	Tue 5/3/11							Area E - 2nd Floor					
122		A <sup>2</sup>	Dem	olition	15 days	Thu 1/6/11	Wed 1/26/11						Demo	olition 🖀 1/26					
123		A <sup>2</sup>	Stru	cture	7 days	Thu 1/27/11	Fri 2/4/11							ructure <b>T</b> 2/4					
124		A <sup>2</sup>	MEP	Rough In	10 days	Thu 1/27/11	Wed 2/9/11							ough In <b>a</b> 2/9					
125		*	MEP	Install	47 days	Fri 2/25/11	Mon 5/2/11							_					
													M	EP Install 5/2					
				Task		Project Summ	ary		■ Inactive M	ilestone	<b>\$</b>		Manual Summary	Rollup	■ Deadlin	e			
Projec	t: Tech	2 Detailed	d Schedule	Split		External Tasks			■ Inactive Su	ımmary	$\nabla$		Manual Summary		Progres	s	_		—
	Fri 10/1			Milestone •		External Miles	tone 🔷		Manual Ta	sk		]	Start-only	Е					
				Summary		Inactive Task			☐ Duration-o	only			Finish-only	<b>ם</b>					
				<u> </u>					Page 5	*			·						
									rage 3										

December   Proceeding   Process	ID	_	Task	Task Name		Duration	Start	Finish	lanuary 1	October 1		July 1		April 1		January 1		October		July 1		April 1
Punchist   Suby   Wed		0	Mode	Inter	iors/Finishes	27 days	Mon 3/28/11	Tue 5/3/11	1/13	5/25 10/5	2/15	6/28	11/8	3/21	8/1 1	12/12	4/24	9/4	1/15	5/27	10/7	2/17
Substantial Completion   Odays   Tar. 5/3/11   Tar. 5/3/11   Tar. 5/3/11   Substantial Completion   5/3			<u></u>	inter	1013/111131163	27 ddys	141011 3/20/11	146 5/5/11						Inte	eriors/Finis	shes 📺 5	5/3					
28	127		A.	Punc	hlist	5 days	Wed 4/27/11	Tue 5/3/11							Pu	ınchlist 🐨 5	5/3					
23   Area G 2nd Floor   23 days   Thu 1/6/11   Mon 6/32/11	128		*	Subs	stantial Completion	0 days	Tue 5/3/11	Tue 5/3/11														
Demolition   15 days	120			A C	2-d Flaa-	122 dave	Th 1 /C /11	NA C /27/11						Substar		•						
	129		₽	Area G	- Zna Floor	123 days	Inu 1/6/11	IVION 6/2//11							Are							
33	130		A.	Dem	olition	15 days	Thu 1/6/11	Wed 1/26/11						Der	molition =	1/26						
132   Foundations   12 days   Thu 1/2/11   Fn 2/11/11   Fn 1/2/11   Mor Fn 1/2/11	131		*	Struc	ture	42 days	Wed 1/26/11	Thu 3/24/11						20.								
MEP Rough in   66 days   Thu 1/27/11   Thu 4/28/11   MEP Rough in   4/28   1/	122			F	4-4:	42 4	Th 1 /27 /11	F-: 2/11/11							Structure	3/24	4					
MEP Install	152		×.	Foun	dations	12 days	Thu 1/2//11	Fri 2/11/11						Fou	undations	2/11						
MEP Install	133		AP	MEP	Rough In	66 days	Thu 1/27/11	Thu 4/28/11						MFP	Rough In		/28					
135	134		*	MEP	Install	98 days	Thu 1/27/11	Mon 6/13/11									, = 0					
Interiors/Finishes	125			Intor	iors/Finishos	41 days	Wod 4/27/11	Wod 6/22/11						M	/IEP Install		6/13					
Substantial Completion   O days   Mon 6/27/11   Mon 6/27/11   Mon 6/27/11   Substantial Completion   6/27   Phase 2E - Renovate Existing Classroom   Classroom   Classroom   Mon 1/3/11   Fri 1/21/11   Phase 2E - Renovate Existing Classroom   Area E - 3rd Floor   Substantial Completion   3 days   Mon 1/3/11   Med 1/5/11   Demolition T.1/5   MEP Rough in T.1/7   MEP Rough in T.1/7   MEP Rough in T.1/7   MEP Rough in T.1/3   MEP Rough	133		X.	inter	iors/Finishes	41 days	weu 4/2//11	weu 6/22/11						Ir	nteriors/Fi	inishes 🌉	6/22					
Substantial Completion   O days   Mon 6/27/11   Mon 6/27/11   Substantial Completion   O days   Mon 1/3/11   Fri 1/21/11   Substantial Completion   O days   Mon 1/3/11   Fri 1/21/11   Phase 2E - Renovate Existing Classroom   Cassroom   Cass	136		A CONTRACT	Punc	hlist	3 days	Thu 6/23/11	Mon 6/27/11								Punchlist	t <del>-r.</del> 6/27					
138	137		*	Subs	stantial Completion	0 days	Mon 6/27/11	Mon 6/27/11									_					
Classroom   139	120		_	Dhasa 2F	Danavata Eviatina	1F dove	Man 1/2/11	F=: 1/21/11								•						
Demolition   3 days   Mon 1/3/11   Wed 1/5/11   Demolition 11/5	136				-	15 days	WOII 1/3/11	FII 1/21/11						Pilase ZE -		-	1455100111	!				
Demolition   3 days   Mon 1/3/11   Wed 1/5/11	139		3	Area E	- 3rd Floor	15 days	Mon 1/3/11	Fri 1/21/11														
141	140		*	Dem	olition	3 days	Mon 1/3/11	Wed 1/5/11														
MEP Install   3 days   Tue 1/11/11   Thu 1/13/11   MEP Install   1/13   MEP Install   1/13   MEP Install   1/13   MEP Install   1/14	141			MED	Rough In	2 days	Thu 1/6/11	Fri 1/7/11						Den	molition <u>T</u>	1/5						
143 Interiors/Finishes 7 days Thu 1/6/11 Fri 1/14/11  144 Punchlist 2 days Thu 1/20/11 Fri 1/21/11  145 Substantial Completion 0 days Fri 1/21/11 Fri 1/21/11  146 Phase 2F - Renovate Existing Classroom  147 Share E - 3rd Floor 15 days Mon 1/24/11 Fri 2/11/11  148 Demolition 3 days Mon 1/24/11 Fri 2/11/11  149 MEP Rough In 2 days Thu 1/27/11 Fri 1/28/11  150 MEP Install 1 day Thu 2/3/11 Thu 2/3/11  Task Project Summary Inactive Milestone Manual Summary Progress  Project: Tech 2 Detailed Schedule Date: Fri 10/14/11 Milestone External Tasks Inactive Summary Manual Summary Progress			<u></u>		<del>-</del>	z days								MEP R	Rough In 🛨	1/7						
144  Punchlist  2 days  Thu 1/20/11  Fri 1/21/11  Punchlist  1/21  Punchl	142		*	MEP	Install	3 days	Tue 1/11/11	Thu 1/13/11						ME	EP Install 7	<b>[</b> 1/13						
Punchlist  2 days  Thu 1/20/11  Fri 1/21/11  Substantial Completion  0 days  Fri 1/21/11  Punchlist 1/21  Substantial Completion 0 1/21  Substantial Completion 1/21  Phase 2F - Renovate Existing  Classroom  15 days  Mon 1/24/11  Fri 2/11/11  Phase 2F - Renovate Existing Classroom  Area E - 3rd Floor  15 days  Mon 1/24/11  Phase 2F - Renovate Existing Classroom  Area E - 3rd Floor  Demolition  3 days  Mon 1/24/11  MEP Rough In  10 day  Thu 2/3/11  Thu 2/3/11  Thu 2/3/11  Thu 2/3/11  Thu 2/3/11  Thu 2/3/11  MEP Install 1/2/3  MEP Install 1/2/3  Mer Install 1/2	143		*	Inter	iors/Finishes	7 days	Thu 1/6/11	Fri 1/14/11						I	/Finish as —	- 1/14						
Punchlist 1/21  145 Substantial Completion 0 days Fri 1/21/11 Fri 1/21/11  146 Phase 2F - Renovate Existing Classroom	144		<b>→</b>	Punc	hlist	2 days	Thu 1/20/11	Fri 1/21/11						interiors/	rinisnes <u>I</u>	[ 1/14						
Substantial Completion ↑ 1/21  146 Phase 2F - Renovate Existing Classroom  15 days Mon 1/24/11 Fri 2/11/11  147 Area E - 3rd Floor  15 days Mon 1/24/11 Fri 2/11/11  148 Pemolition  15 days Mon 1/24/11 Wed 1/26/11  149 MEP Rough In  15 days Mon 1/24/11 Fri 1/28/11  150 MEP Rough In  1 day Thu 2/3/11 Thu 2/3/11  Task  Project: Tech 2 Detailed Schedule Date: Fri 10/14/11  Project: Tech 2 Detailed Schedule Date: Fri 10/14/11  Task  Project Summary  Inactive Milestone  Manual Summary Rollup  Progress  Manual Summary  Manual Summary  Manual Summary  Progress  Start-only C														1	Punchlist =	<b>T</b> 1/21						
Classroom  147 Area E - 3rd Floor  15 days Mon 1/24/11 Fri 2/11/11  148 Demolition  3 days Mon 1/24/11 Wed 1/26/11  149 MEP Rough In  2 days Thu 1/27/11 Fri 1/28/11  150 MEP Install  1 day Thu 2/3/11 Thu 2/3/11  MEP Install  Project: Tech 2 Detailed Schedule Date: Fri 10/14/11  Task  Project Summary  Inactive Milestone  Manual Summary Rollup  Deadline  Progress  External Tasks  Inactive Summary  Manual Summary  Manual Summary  Manual Summary  Manual Summary  Progress  External Tasks  Manual Task  Manual Task  Start-only  External Milestone	145		*	Subs	stantial Completion	0 days	Fri 1/21/11	Fri 1/21/11					Su	ıbstantial Con	mpletion (	<b>♦ 1/21</b>						
Area E - 3rd Floor  15 days Mon 1/24/11 Fri 2/11/11  148 Demolition  3 days Mon 1/24/11 Wed 1/26/11  149 MEP Rough In  150 MEP Install  1 day Thu 2/3/11 Thu 2/3/11  Project: Tech 2 Detailed Schedule Date: Fri 10/14/11  Task Split External Tasks Inactive Summary Manual Summary Progress  External Milestone Manual Task  Task Split External Milestone Manual Summary Progress  Manual Summary Progress  External Milestone Manual Task  Manual Task  Start-only E	146		3			15 days	Mon 1/24/11	Fri 2/11/11						Phase 2F			Classroo	m				
Demolition  3 days  Mon 1/24/11 Wed 1/26/11  Demolition 1/26  149  MEP Rough In  2 days  Thu 1/27/11 Fri 1/28/11  MEP Rough In 1/28  150  MEP Install  1 day  Thu 2/3/11  Thu 2/3/11  MEP Install 1/2/3	147		3			15 days	Mon 1/24/11	Fri 2/11/11														
Demolition1/26  MEP Rough In 2 days Thu 1/27/11 Fri 1/28/11  MEP Rough In1/28  MEP Install 1 day Thu 2/3/11 Thu 2/3/11  MEP Install2/3  Project: Tech 2 Detailed Schedule Date: Fri 10/14/11  Demolition1/26  MEP Rough In1/28  MEP Install2/3  MEP Rough In1/28  MEP Rough In1/28  MEP Install	440							11/05/11							ı	•						
MEP Rough In 1/28  150 MEP Install 1 day Thu 2/3/11 Thu 2/3/11  MEP Install 1/2/3  Manual Summary Rollup Deadline 1/2/3  Project: Tech 2 Detailed Schedule Split	148		AT.	Dem	olition	3 days	Mon 1/24/11	Wed 1/26/11						De	emolition	<b>エ</b> 1/26						
MEP Install  1 day  Thu 2/3/11  Thu 2/3/11  MEP Install  2/3  MEP Install  1 day  Thu 2/3/11  Thu 2/3/11  MEP Install  2/3  Manual Summary Rollup  Deadline  Project: Tech 2 Detailed Schedule Date: Fri 10/14/11  Date: Fri 10/14/11  MIlestone  Manual Summary  Manual Summary  Progress  External Milestone  Manual Task  Start-only  C	149		*	MEP	Rough In	2 days	Thu 1/27/11	Fri 1/28/11						MED	Pough In	<del></del> 1/28						
Project: Tech 2 Detailed Schedule Date: Fri 10/14/11  Task  Project Summary  Project Summary  Inactive Milestone  Manual Summary Rollup  Deadline  Fixternal Tasks  Inactive Summary  Manual Summary  Manual Summary  Progress  Split  Milestone  Manual Summary  Progress  Start-only  C	150		*	MEP	Install	1 day	Thu 2/3/11	Thu 2/3/11						IVIE	Nough III,	<b>T</b> 1/20						
Project: Tech 2 Detailed Schedule Date: Fri 10/14/11 Split External Tasks Inactive Summary Manual Summary Progress  External Milestone Manual Task Start-only C						,								N	MEP Install	I <b>T</b> 2/3						
Project: Tech 2 Detailed Schedule Date: Fri 10/14/11  Split  External Tasks  Inactive Summary  Manual Summary  Progress  Manual Summary  Figure 10/14/11  Milestone  Manual Task  Start-only  C																						
Date: Fri 10/14/11 Milestone ♦ External Milestone ♦ Manual Task							•	•												4		
Third to the Control of the Control				d Schedule							ry 🛡				•	-		Progress				
Summary Inactive Task Duration-only Finish-only	Date: F	-ri 10/1	4/11			<b>•</b>		tone •						•								
					Summary	<del>-</del>	Inactive Task			Duration-only			Fi	nish-only		<u> </u>						
Page 6										Page 6												

Mode	July 1 April 2 5 5/27 10/7 2/17		April 1   January 1     11/8   3/21   8/1   12/12   4/24	July 1 15 6/28 11/8	October 1	lanuary 1 1/13	Finish	Start	Duration	e	Task Name	Task Mode	ID 6
152	5/2/ 10// 2/1/	3/4   1/15   5/.		13   0/26   11/8	5/25   10/5   2	1/13	Fri 2/4/11	Fri 1/28/11	6 days	riors/Finishes		-	
133			_				Fri 2/11/11	Thu 2/10/11	2 days	chlist	Pund	A.	152
15							Fri 2/11/11	Fri 2/11/11	0 days	estantial Completion	Sub	*	153
Computer Labs and Classrooms   15 days   Mon 2/14/11   Fri 3/4/11		bs and Classrooms		Pha			Fri 3/4/11	Mon 2/14/11	15 days	i - Renovate Existing	Phase 2G	=	154
Demolition   S days			Area F - 3rd Floor				Fri 3/4/11	Mon 2/14/11	15 days				155
MEP Rough in   2 days   Mon 2/21/11   Tue 2/22/11   MEP Rough in   2 days   Mon 2/21/11   Tue 2/22/11   MEP Rough in   2/22/21   MEP Rough in													
MEP Install   3 days   Wed 2/23/11   Fri 2/25/11   MEP Install   2/25   MEP Install   3 days   Wed 2/23/11   Fri 2/25/11   MEP Install   2/25   MEP Instal			Demolition <b> </b>				Fri 2/18/11	Mon 2/14/11	5 days	nolition	Dem	<b>A</b>	156
			MEP Rough In <u>∓</u> 2/22			1	Tue 2/22/11	Mon 2/21/11	2 days	P Rough In	MEP	A.	157
159			MEP Install <b>→ 2/2</b> 5				Fri 2/25/11	Wed 2/23/11	3 days	P Install	MEP	A.	158
160			<del>-</del>				Fri 3/4/11	Mon 2/21/11	10 days	riors/Finishes	Inter	*	159
161    Substantial Completion   0 days			<del>-</del>				Fri 3/4/11	Fri 3/4/11	1 day	chlist	Pund	*	160
162   Phase 2H - Renovate Existing   15 days   Mon 3/14/11   Fri 4/1/11   Phase 2H - Renovate Existing   15 days   Mon 3/14/11   Fri 4/1/11   Phase 2H - Renovate Existing   Classrooms   Area E - 2rd Floor   15 days   Mon 3/14/11   Fri 4/1/11   Phase 2H - Renovate Existing   Classrooms   Phase 2H - Renovate Existing   Phase 2H - Renova			Punchlist <sub>3</sub> /4				Fri 3/4/11	Fri 3/4/11	0 days	estantial Completion	Sub	<b>→</b>	161
Classrooms													
164		Classrooms	Phase 2H - Renovate Existing Class				Fri 4/1/11	Mon 3/14/11	15 days	-			162
165 MEP Rough In 5 days Tue 3/15/11 Mon 3/21/11 166 MEP Install 6 days Thu 3/17/11 Thu 3/24/11 167 MEP Install 1 days Thu 3/17/11 Thu 3/31/11 168 Punchlist 2 days Thu 3/31/11 Fri 4/1/11 169 Substantial Completion 0 days Fri 4/1/11 Fri 6/3/11 170 Phase 21 & 21 - Renovate Existing Classrooms Classrooms Classrooms Classrooms Phase 21 & 21 - Renovate Existing Classrooms Structure 3 days Mon 4/4/11 Fri 6/3/11 172 Demolition 3 days Tue 4/12/11 Thu 4/14/11 173 MEP Rough In 12 days Fri 4/8/11 Mon 4/25/11 175 MEP Rough In 12 days Thu 4/14/11 Fri 5/13/11  MEP Rough In 12 days Thu 4/14/11 Fri 5/13/11			Area E - 2rd Floor				Fri 4/1/11	Mon 3/14/11	15 days	- 2rd Floor	Area E	3	163
165         MEP Rough In         5 days         Tue 3/15/11         Mon 3/21/11         MEP Rough In ▼ 3/21           166         MEP Install         6 days         Thu 3/17/11         Thu 3/24/11         MEP Install ▼ 3/24           167         Interiors/Finishes         11 days         Thu 3/31/11         Thu 3/31/11         Interiors/Finishes ▼ 3/31           168         Punchlist         2 days         Thu 3/31/11         Fri 4/1/11         Punchlist ▼ 4/1           169         Substantial Completion         0 days         Fri 4/1/11         Fri 4/1/11         Substantial Completion ◆ 4/1           170         Phase 21 & 2J - Renovate Existing Classrooms         45 days         Mon 4/4/11         Fri 6/3/11         Area E - 1st Floor           171         Area E - 1st Floor         45 days         Mon 4/4/11         Fri 6/3/11         Area E - 1st Floor         Demolition ▼ 4/13           172         Demolition         8 days         Mon 4/2/11         Thu 4/14/11         Thu 4/14/11         Structure ▼ 4/14           173         MEP Rough In         12 days         Fri 4/8/11         Mon 4/25/11         MEP Rough In ■ 4/25           175         MEP Install         22 days         Thu 4/14/11         Fri 5/13/11			Demolition = 3/17			1	Thu 3/17/11	Mon 3/14/11	4 days	nolition	Dem	*	164
166       MEP Install       6 days       Thu 3/17/11       Thu 3/24/11         167       Interiors/Finishes       11 days       Thu 3/17/11       Thu 3/31/11       Interiors/Finishes ■ 3/31         168       Punchlist       2 days       Thu 3/31/11       Fri 4/1/11       Punchlist ■ 4/1         169       Substantial Completion       0 days       Fri 4/1/11       Fri 4/1/11       Substantial Completion ◆ 4/1         170       Phase 21 & 21 - Renovate Existing Classrooms       45 days       Mon 4/4/11       Fri 6/3/11         171       Area E - 1st Floor       45 days       Mon 4/4/11       Wed 4/13/11         172       Demolition       8 days       Mon 4/4/11       Wed 4/13/11         173       Structure       3 days       Tue 4/12/11       Thu 4/14/11         174       MEP Rough In       12 days       Fri 4/8/11       Mon 4/25/11         175       MEP Install       22 days       Thu 4/14/11       Fri 5/3/11			_			11	Mon 3/21/11	Tue 3/15/11	5 days	P Rough In	MEP	*	165
MEP Install \( \frac{1}{3} \)   MEP Install \( \frac{1}{3} \)   MEP Install \( \frac{1}{3} \)   MEP Rough In \( \frac{1}{3} \)   MILE Interiors/Finishes \( \frac{1}{3} \)   3/31   Interiors/Finishes \( \frac{1}{3} \)   3/31   Interiors/Finishes \( \frac{1}{3} \)   3/31   Punchlist \( \frac{1}{4} \)   Punchlist \( \frac{1}{4} \)   Fri \( \frac{1}{4} \)   1/11   Fri \( \frac{1}{4} \)   1/11   Substantial Completion \( \phi \) \( \frac{4}{1} \)   1/11   Substantial Completion \( \phi \) \( \frac{4}{1} \)   Phase 21 & 2J - Renovate Existing Classrooms \( \frac{1}{2} \)   Area \( \frac{1}{2} \) - 1/15   Phase 21 & 2J - Renovate Existing Classrooms \( \frac{1}{4} \)   Mon \( \frac{4}{4} \)   1/11   Wed \( \frac{4}{13} \)   1/11   Punchlist \( \frac{1}{2} \)   1/12   Phase 21 & 2J - Renovate Existing Classrooms \( \frac{1}{2} \)   2/13   Area \( \frac{1}{2} \) - 1/13   1/13   Phase 21 & 2J - Renovate Existing Classrooms \( \frac{1}{2} \)   2/13   Area \( \frac{1}{2} \)   1/13			MEP Rough In <b>1</b> 3/21			1	Thu 3/24/11	Thu 3/17/11	6 days	P Install	MEP	<del>7</del>	166
Punchlist			MEP Install 👚 3/24							riors/Einishes	Inter		167
Punchlist 1/4   Substantial Completion   O days   Fri 4/1/11   Fri 6/3/11   Substantial Completion → 4/1   Fri 6/3/11   Substantial Completion → 4/1   Phase 2I & 2J - Renovate Existing Classrooms   O days   Mon 4/4/11   Fri 6/3/11   Phase 2I & 2J - Renovate Existing Classrooms   O days   Mon 4/4/11   Fri 6/3/11   Phase 2I & 2J - Renovate Existing Classrooms   O days   Mon 4/4/11   Fri 6/3/11   O days   O days   Mon 4/4/11   Fri 6/3/11   O days   O			Interiors/Finishes 3/31			.1			·	· 			
Substantial Completion ◆ 4/1  170			Punchlist <u></u> 4/1				Fri 4/1/11	Thu 3/31/11	2 days	chlist	Pund	AT.	168
Classrooms  Area E - 1st Floor  45 days  Mon 4/4/11 Fri 6/3/11  Demolition  8 days  Mon 4/4/11 Wed 4/13/11  Demolition			Substantial Completion 🔷 4/1				Fri 4/1/11	Fri 4/1/11	0 days	estantial Completion	Sub	A.	169
171 Area E - 1st Floor 45 days Mon 4/4/11 Fri 6/3/11  172 Demolition 8 days Mon 4/4/11 Wed 4/13/11  173 Structure 3 days Tue 4/12/11 Thu 4/14/11  174 MEP Rough In 12 days Fri 4/8/11 Mon 4/25/11  175 MEP Install 22 days Thu 4/14/11 Fri 5/13/11		ting Classrooms					Fri 6/3/11	Mon 4/4/11	45 days	-		3	170
172       Demolition       8 days       Mon 4/4/11       Wed 4/13/11         173       Structure       3 days       Tue 4/12/11       Thu 4/14/11         174       MEP Rough In       12 days       Fri 4/8/11       Mon 4/25/11         175       MEP Install       22 days       Thu 4/14/11       Fri 5/13/11		or	Area E - 1st Floor				Fri 6/3/11	Mon 4/4/11	45 days			3	171
173 Structure 3 days Tue 4/12/11 Thu 4/14/11  174 MEP Rough In 12 days Fri 4/8/11 Mon 4/25/11  175 MEP Install 22 days Thu 4/14/11 Fri 5/13/11			• •			11	Wed 4/13/11	Mon 4/4/11	8 days	nolition	Dem	*	172
Structure4/14  174			Demolition <u>∓</u> 4/13			1	Thu 4/14/11	Tue 4/12/11	3 days	cture	Stru	*	173
MEP Rough In <b>a</b> 4/25  175 MEP Install 22 days Thu 4/14/11 Fri 5/13/11			Structure <u></u> 4/14										
			MEP Rough In 📋 4/25									M'	
			MEP Install 📋 5/13				Fri 5/13/11	Thu 4/14/11	22 days	' Install	MEP	AT.	175
Task Project Summary Inactive Milestone $\diamondsuit$ Manual Summary Rollup ————— Deadline	•	Deadline	Manual Summary Rollup	<b>♦</b>	Inactive Milestone		nary	Project Summ		Task			
Project: Tech 2 Detailed Schedule Split External Tasks Inactive Summary Manual Summary Progress		Progress	Manual Summary	$\nabla$	Inactive Summary		s 📟	External Tasks		Split	led Schedule	ch 2 Detaile	Project:
Date: Fri 10/14/11 Milestone ♦ External Milestone ♦ Manual Task Start-only			Start-only		Manual Task		stone 🔷	External Miles	<b>♦</b>	Milestone		0/14/11	Date: Fri
Summary Inactive Task Duration-only Finish-only			Finish-only		Duration-only			Inactive Task	-	Summary			
Page 7					Page 7					1			

ID		Task	Task Name	Duration	Start	Finish	lanuary 1	October 1	July 1	April 1	January 1	October 1		April 1
176		Mode_	Interiors/Finishes	25 days	Tue 4/26/11	Mon 5/30/11	1/13	5/25 10/5 2,	/15 6/28 11/8		12/12 4/24	9/4 1/15		2/17
170		~• 	interiors/finishes	25 days	Tue 4/20/11	101011 3/30/11				Interior	s/Finishes 📺 5/30			
177	5	r de la companya della companya della companya de la companya della companya dell	Punchlist	4 days	Tue 5/31/11	Fri 6/3/11					Punchlist <b>T</b> 6/3			
178	5	r e	Substantial Completion	0 days	Fri 6/3/11	Fri 6/3/11					_			
179		3	Dhasa 2 Danavata Evistina	147 dove	Th 6 /0 /11	F=: 12/20/11				Substantial	Completion 6/3	Frieding Auditorium		
1/9			Phase 3 - Renovate Existing Auditorium	147 days	Thu 6/9/11	Fri 12/30/11					Phase 3 - Renovate	Existing Auditorium		
180		3	Area G - 2nd Floor	147 days	Thu 6/9/11	Fri 12/30/11					Area G -	2nd Floor		
181	5	*	Demolition	15 days	Thu 6/9/11	Wed 6/29/11					•	•		
182		*	Structure	45 days	Tue 6/21/11	Mon 8/22/11					Demolition a 6/29	)		
102		···	Structure	45 days	Tue 0/21/11	101011 6/22/11					Structure	8/ <mark>2</mark> 2		
183	5	*	MEP Rough In	22 days	Thu 7/21/11	Fri 8/19/11					MEP Rough In 📺	8/19		
184	5	r e	MEP Install	44 days	Wed 9/21/11	Mon 11/21/1	1							
185		*	Interiors/Finishes	50 days	Mon 10/17/1	1 Fri 12/23/11					MEP Install	11/21		
			interiors/Tillishes	50 days	WIOTI 10/17/1	111112/23/11					Interiors/Finishe	es 12/23		
186	5	*	Punchlist	5 days	Mon 12/26/1	1 Fri 12/30/11					Pu	inchlist <u>T</u> 12/30		
187	,	r e	Substantial Completion	0 days	Fri 12/30/11	Fri 12/30/11								
188		3	Area E - 3rd Floor	43 days	Tuo 6/14/11	Thu 8/11/11	_				Substantial Comp Area E - 3rd F			
100		<b>₽</b>	Alea E - Siu Flooi	45 uays	Tue 6/14/11	111u 0/11/11					Area E - Sid F	1001		
189	5	A CONTRACT	Demolition	8 days	Tue 6/14/11	Thu 6/23/11					Demolition <b>π</b> 6/23			
190	,	r e	Structure	5 days	Mon 6/27/11	Fri 7/1/11					_			
191		÷	MEP Rough In	10 days	Mon 6/27/11	Eri 7/9/11					Structure <b>T</b> 7/1			
131		~• 	WEF ROUGH III	10 days	1011 0/27/11	1117/0/11					MEP Rough In 🛮 7/8			
192	5	<b>*</b>	MEP Install	10 days	Mon 7/11/11	Fri 7/22/11					MEP Install 7/2	22		
193	5	*	Interiors/Finishes	17 days	Mon 7/18/11	Tue 8/9/11				_	_			
194		r e	Punchlist	2 days	Wed 8/10/11	Thu 8/11/11				lı	nteriors/Finishes 📺 8	/9		
			Tuncinist	2 days							Punchlist <b>1</b> 8	/1 <mark>1</mark>		
195	5	*	Substantial Completion	0 days	Thu 8/11/11	Thu 8/11/11				Subst	antial Completion 🔷	8/11		
196		3	Phase 4 - Renovate Exsiting Tech Ed	212 days	Thu 7/7/11	Fri 4/27/12					Phase 4 - Renovate Exs		Weight Room	
197		3	Wing & Weight Room Area B - Foundations and Steel	89 days	Thu 7/7/11	Tue 11/8/11					Area B - Founda	ations and Steel		
		~	Area B Tourisations and Steel	os days	,,,,11	140 11/0/11					Area b Tourist			
198	5	<b>*</b>	Demolition	22 days	Thu 7/7/11	Fri 8/5/11					Demolition 📺 8	/5		
199	5	r e	Foundations	37 days	Mon 8/8/11	Tue 9/27/11								
200			Structure	35 days	Wed 9/21/11	Tue 11/9/11	-				Foundations	9/27		
200		<u> </u>	Structure	33 uays	**Eu 3/21/11	146 11/0/11					Structure	11/8		
			Task		Project Summ	ary		Inactive Milestone	<b>\$</b>	Manual Summary Rol	lup	Deadline	<b>+</b>	
			d Schedule Split		External Tasks	· =		Inactive Summary	$\overline{}$	Manual Summary	-	Progress		_
Date: F	ri 10/14/	/11	Milestone •		External Miles	stone 🔷		Manual Task		Start-only	Е			
			Summary		Inactive Task			Duration-only		Finish-only	3			
			I					Page 8						

201			Duration	Start	Finish	lanuary 1	October 1	July 1			October 1 July 1	
201	Mode 	Area B - Façade	52 days	Wed 10/12/11	Thu 12/22/11	1/13	5/25 10/5 2/	15 6/28 11/8	3 3/21 8/1	12/12 4/24 Area	9/4 1/15 5/27 B - Façade	10/7 2/17
202	*	East Elevation Building Façade	37 days	Wed 10/12/11	1 Thu 12/1/11				Fast Fleva	ation Building Façade	12/1	
203	*	North Elevation Building Façade	34 days	Wed 10/19/11	1 Mon 12/5/11					ation Building Façade		
204	*	South Elevation Building Façade	32 days	Wed 11/2/11	Thu 12/15/11					vation Building Façad		
205	*	West Elevation Building Façade	32 days	Wed 11/9/11	Thu 12/22/11					evation Building Façad	_	
206	3	Area B - First Floor	105 days	Wed	Tue 4/24/12				West Lie	vacion banding rayac	Area B - First Floor	
207	*	MEP Rough In	24 days	<b>11/30/11</b> Wed 11/30/11	1 Mon 1/2/12					MEP Rough	n In 📺 1/2	
208	*	MEP Install	38 days	Tue 1/3/12	Thu 2/23/12						Install 2/23	
209	*	Structure	6 days	Wed 11/30/11	1 Wed 12/7/11	-					ure <b>1</b> 12/7	
210	*	Interiors/Finishes	55 days	Wed 1/25/12	Tue 4/10/12						Finishes 4/10	
211	*	Punchlist	10 days	Wed 4/11/12	Tue 4/24/12					inceriors, i	Punchlist 4/24	
212	*	Substantial Completion	0 days	Tue 4/24/12	Tue 4/24/12					Substantia	al Completion   4/24	
213	3	Area B - First Floor Corridor	29 days	Tue 1/24/12	Mon 3/5/12						a B - First Floor Corridor	
214	*	MEP Layout	1 day	Tue 1/24/12	Wed 1/25/12					MEP	Layout 1/25	
215	*	MEP Rough In	2 days	Fri 1/27/12	Mon 1/30/12						ough In <b>1</b> /30	
216	*	MEP Install	15 days	Fri 1/27/12	Thu 2/16/12						P Install <b>2/1</b> 6	
217	*	Interiors/Finishes	19 days	Wed 2/8/12	Mon 3/5/12						/Finishes a 3/5	
218	3	Area C - Foundations and Steel	121 days	Thu 8/18/11	Thu 2/2/12						ndations and Steel	
219	*	Foundations	26 days	Thu 8/18/11	Thu 9/22/11					Foundations	9/22	
220	*	Structure	95 days	Fri 9/23/11	Thu 2/2/12					Structure F		
221	3	Area C - Façade	38 days	Wed 11/9/11	Fri 12/30/11					_	ea C - Façade	
222	*	North Elevation Building Façade	23 days	Wed 11/9/11	Fri 12/9/11				North Ele	evation Building Façad		
223	*	South Elevation Building Façade	23 days	Wed 11/23/11	1 Fri 12/23/11					levation Building Faça		
224	*	West Elevation Building Façade	23 days	Wed 11/30/12	1 Fri 12/30/11					levation Building Faça		
225	3	Area B - First Floor	116 days	Fri 11/18/11	Fri 4/27/12						Area B - First Floor	
		1					I				<b>Y</b>	
		Task		Project Summ	ary 🔻	<u> </u>	Inactive Milestone	<b>\$</b>	Manual Summary Rollup	0	Deadline	<b>•</b>
	ech 2 Detailed	Schedule Split		External Tasks			Inactive Summary	$\bigcirc$	Manual Summary	<del></del>	Progress	
Date: Fri 1	0/14/11	Milestone •		External Miles	tone 🔷		Manual Task		Start-only	С		
		Summary		Inactive Task			Duration-only		Finish-only	<b>3</b>		
							Page 9					

- 6	Task Mode	Task Name	Duration	Start	Finish	lanuary 1 1/13	October 1         July 1           5/25         10/5         2/15         6/28	April 11/8 3/2		January 1 12/12	4/24	October 1 9/4		July 1 5/27	10/7	April 2/17
226	rioue	Structure	21 days	Fri 11/18/11	Fri 12/16/11	1/13	3/23   10/3   2/13   0/26	11/6 3/2	.1 6/1	12/12		ire <b>= 12</b> /		3/2/	10//	
227	À	MEP Rough In	43 days	Mon 11/21/11	Wed 1/18/12					N		In <b></b> 1				
228	*	MEP Install	56 days	Mon 12/12/11	Mon 2/27/12							stall				
229	*	Interiors/Finishes	58 days	Wed 1/25/12	Fri 4/13/12											
230	À	Punchlist	9 days	Tue 4/17/12	Fri 4/27/12						interiors/i		4/13			
231	*	Substantial Completion	0 days	Fri 4/27/12	Fri 4/27/12								nlist 🛮 4/2			
232	3	Phase 4A - Renovate Existing	92 days	Thu 5/24/12	Fri 9/28/12								tion 🔷 4/2 e Existing G		um, Locke	r & Team
233	3	Gymnasium, Locker & Team Rooms Roof	-	Thu 5/24/12									Roof	·		
			-										W KOOI			
234	*	Demolition	10 days	Thu 5/24/12	Wed 6/6/12							Dem	olition 🛭 (	6/6		
235	3	1st Floor	91 days	Fri 5/25/12	Fri 9/28/12								1s	t Floor		
236	À	MEP Rough In	19 days	Mon 6/4/12	Thu 6/28/12							MEP R	ough In 📺	6/28		
237	A.	MEP Install	65 days	Fri 5/25/12	Thu 8/23/12							MEP	Install	- 8/	23	
238	*	Foundations	5 days	Wed 5/30/12	Tue 6/5/12								dations <b>T</b> (			
239	*	Structure	20 days	Mon 6/4/12	Fri 6/29/12								ructure <b>=</b>			
240	*	Interiors/Finishes	47 days	Fri 7/13/12	Mon 9/17/12								s/Finishes		1/17	
241	*	Punchlist	10 days	Mon 9/17/12	Fri 9/28/12							interior		chlist T		
242	*	Substantial Completion	0 days	Fri 9/28/12	Fri 9/28/12							Cultura		7		
243	3	Phase 4B - Demolish Esiting Auxiliary	45 days	Mon 4/30/12	Fri 6/29/12						Ph		tial Comple emolish Esi	- 1		n
244	*	<b>Gym</b> Demolition	22 days	Mon 4/30/12	Tue 5/29/12											
245	À	Sitework	23 days	Wed 5/30/12	Fri 6/29/12							Demol	ition 📺 5	729		
246	*	Project Substantial Completion and	0 days	Fri 6/29/12	Fri 6/29/12							Si	tework 📺	6/29		
		Turnover	o days	111 0/23/12	111 0/ 23/ 12				Droi	ject Substant	ial Cample	nion and 7	Turnover	6/29		

APPENDIX C -	- Detailed Structu	ral System Estimat	e and Takeoffs

# Foundation and 1st Floor | Cost For 1 Bay

CSI Division	ltem	Туре	Unit			Unit Cost		Total	Total Including O&P	Quantity	ı	Material	Labor	Equipment	Total	Total Including O&P
				М	laterial	Labor	Equipment									
Concrete																
03 11 13.25 5650	Forms in Place, Column	Job built, 12"x12" column, 4 use	SFCA	\$	0.71 \$	5.80	\$	6.51	\$ 9.70	16	\$	11.36 \$	92.80	\$	104.16	\$ 155.20
03 11 13.65 3000	Forms in Place, Slab on Grade	Edge forms, wood, on grade, to 6" high	L.F.	\$	0.27 \$	2.18	\$	2.45	\$ 3.64	750	\$	202.50 \$	1,635.00	\$	1,837.50	\$ 2,730.00
03 15 13.50 20	Waterstops	PVC, ribbed 3/16" thick, 4" wide	L.F.	\$	0.95 \$	2.22	\$	3.17	\$ 4.46	750	\$	712.50 \$	1,665.00	\$	2,377.50	\$ 3,345.00
03 21 10.60 600	Uncoated Reinforcing Steel	Slab on grade, #3-#7	Ton	\$	855.00 \$	515.00	\$	1,370.00	\$ 2,025.00	0.94	\$	803.70 \$	484.10	\$	1,287.80	\$ 1,903.50
03 22 05.50 100	Welded Wire Fabric	6x6 W1.4xW1.4 21 lb. per C.S.F.	C.S.F.	\$	12.50 \$	22.00	\$	34.50	\$ 49.50	55.56	\$	694.50 \$	1,222.32	\$	1,916.82	\$ 2,750.22
03 30 53.40 3850	Cast-In-Place Concrete	Footings 3000PSI, spread, > 5 CY	C.Y.	\$	171.00 \$	61.50	\$ 0.31 \$	232.81	\$ 283.00	8.61	\$	1,472.31 \$	529.52	\$ 2.67 \$	2,004.49	\$ 2,436.63
03 30 53.40 4650	Cast-In-Place Concrete	SOG 3500 PSI, 4" thick	C.Y.	\$	117.00 \$	61.50	\$ 0.38 \$	178.88	\$ 225.00	8.32	\$	973.44 \$	511.68	\$ 3.16 \$	1,488.28	\$ 1,872.00
03 30 53.40 6250	Cast-In-Place Concrete	Retaining Wall, 10' High	C.Y.	\$	129.00 \$	68.50	\$ 6.10 \$	203.60	\$ 254.00	37.04	\$	4,778.16 \$	2,537.24	\$ 225.94 \$	7,541.34	\$ 9,408.16
03 31 05.70 4650	Concrete Placement	SOG, Up to 6" thick, pumped	C.Y.		\$	12.75	\$ 4.26 \$	17.01	\$ 24.00	8.32		\$	106.08	35.44 \$	141.52	\$ 199.68
03 35 29.30 150	Finishing Floors	Bull float, manual float, broom finish w/ edging and joints	S.F.		\$	0.50	\$	0.50	\$ 0.74	674.33		\$	337.17	\$	337.17	\$ 499.00
03 35 29.30 300	Finishing Floors	Power screed, bull float, machine float, trowel (walk-behind)	S.F.		\$	0.39	\$ 0.04 \$	0.43	\$ 0.62	674.33		\$	262.99	\$ 26.97 \$	289.96	\$ 418.08
Metals																
05 05 23.05 70	Anchor Bolts	3/4", hooked w/ nut and washer, 8" long	Ea	\$	3.65 \$	2.17	\$	6.36	\$ 8.15	16	\$	58.40 \$	34.72	\$	101.76	\$ 130.40
05 12 23.65 500	Base Plates	1" thick	S.F.	\$	46.00		\$	46.00	\$ 50.50	4	\$	184.00		\$	184.00	\$ 202.00
05 12 23.75 900	Structural Steel Members	W10x49	L.F	\$	60.50 \$	4.82	\$ 2.95 \$	68.27	\$ 78.00	13	\$	786.50 \$	62.66	38.35 \$	887.51	\$ 1,014.00
											Tot	al Material To	otal Labor	Total Equipment	Total	Total Including O&P
										Cost Per Bay		10,677.37 \$	9,481.27		20,499.82	
										Cost Per S.F.	\$	15.83 \$	14.06	\$ 0.49 \$	30.40	\$ 40.13

# Foundation and 1st Floor | Cost for Entire Foundation

Note: These items have been estimated as a cost for the entire foundation, rather than one typical bay, as these items are not present in each bay and would not have been properly estimated using the typical bay method.

CSI Division	Item	Туре	Unit			Unit Cost		1	Total	Total Including O&P	Quantity	Material	Labor	Equipment	•	Total	Total Including O&P
				Mater	ial	Labor	Equipment										
03 31 05.35 300	Structural Concrete for Piers	4000psi	C.Y.	\$ 10	03.00			\$	103.00	\$ 113.00	10.52	\$ 1,083.56			\$	1,083.56	\$ 1,188.76
03 21 10.60 200	Uncoated Reinforcing Steel	Columns, #3-#7	Ton	\$ 9	00.00 \$	675.00		\$	1,575.00	\$ 2,075.00	2.06	\$ 1,854.00	\$ 1,390.50		\$	3,244.50	\$ 4,274.50
03 30 53.40 3920	Cast-In-Place Concrete	Strip Footings, 18" x 9", unreinforced	C.Y.	\$ 14	41.00 \$	132.00	\$ 0.67	\$	273.67	\$ 360.00	74	\$ 10,434.00	\$ 9,768.00	\$ 49.5	8 \$	20,251.58	\$ 26,640.00
Masonry																	
04 22 10.30 500	Concrete Unit Masonry	Interlocking, 8"x16" x 16" thick	S.F.	\$ :	11.05 \$	6.75	\$ 0.68	\$	18.48	\$ 23.00	800	\$ 8,840.00	\$ 5,400.00	\$ 544.0	0 \$	14,784.00	\$ 18,400.00
											Cost For Bldg	\$ 22,211.56	\$ 16,558.50	\$ 593.5	8 \$	39,363.64	\$ 50,503.26

# 2nd Floor | Cost for 1 Bay

CSI Division	Item	Туре	Unit	Unit Cost				Total		Total Including O&P		Quantity	ty Material		Labor		Equipment		t Total		Fotal Including O&P	
				N	1aterial		Labor	E	quipment													
Concrete																						
03 22 05.00 100	Welded Wire Fabric	6x6 W1.4xW1.4 21 lb. per C.S.F.	C.S.F.	\$	12.5	0 \$	22.00		\$	34.50	\$	49.50	6.74	\$	84.29	\$	148.35			\$ 232	2.64 \$	\$ 333.79
03 31 05.35 300	Structural Concrete	4000psi	C.Y.	\$	103.0	0			\$	103.00	\$	113.00	6.24	\$	642.72					\$ 642	2.72 \$	\$ 705.12
03 31 05.70 1400	Placing Concrete	Elevated slab, less than 6", pumped	C.Y.			\$	16.80	\$	5.60 \$	22.40	\$	31.50	6.24			\$	104.83	\$	34.94	\$ 139	9.78 \$	\$ 196.56
03 35 29.30 150	Finishing Floors	Bull float, manual float, broom finish w/ edging and joints	S.F.			\$	0.50		\$	0.50	\$	0.74	925			\$	462.50			\$ 462	2.50 \$	\$ 684.50
03 35 29.30 300	Finishing Floors	Power screed, bull float, machine float, trowel (walk-behind)	S.F.			\$	0.39	\$	0.04 \$	0.43	\$	0.62	674.33			\$	262.99	\$	26.97	\$ 289	9.96 \$	\$ 418.08
Metals																						
05 12 23.75 900	Structural Steel Members	W10x49	L.F	\$	60.5	0 \$	4.82	\$	2.95 \$	68.27	\$	78.00	13.5	\$	816.75	\$	65.07	\$	39.83	\$ 921	65 \$	\$ 1,053.00
05 12 23.75 3300	Structural Steel Members	W18x35	L.F	\$	43.5	0 \$	3.99	\$	1.80 \$	49.29	\$	56.50	52	\$	2,262.00	\$	207.48	\$	93.60	\$ 2,563	3.08 \$	\$ 2,938.00
05 12 23.75 3500	Structural Steel Members	W18x40	L.F	\$	49.5	0 \$	3.99	\$	1.80 \$	55.29	\$	63.50	72	\$	3,564.00	\$	287.28	\$	129.60	\$ 3,980	.88 \$	\$ 4,572.00
05 12 23.75 5500	Structural Steel Members	W24x76	L.F	\$	94.0	0 \$	3.45	\$	1.56 \$	99.01	\$	111.00	28	\$	2,632.00	\$	96.60	\$	43.68	\$ 2,772	.28 \$	\$ 3,108.00
05 12 23.75 5720	Structural Steel Members	W24x94	L.F	\$	116.0	0 \$	3.55	\$	1.60 \$	121.15	\$	136.00	28	\$	3,248.00	\$	99.40	\$	44.80	\$ 3,392	.20 \$	\$ 3,808.00
05 12 23.75 5920	Structural Steel Members	W27x114	L.F	\$	141.0	0 \$	3.33	\$	1.51 \$	145.84	\$	162.00	24	\$	3,384.00	\$	79.92	\$	36.24	\$ 3,500	).16 \$	\$ 3,888.00
05 31 13.50 5120	Floor Decking	1.5" Thick	S.F.	\$	1.9	2 \$	0.43	\$	0.03 \$	2.38	\$	2.90	674.33	\$	1,294.71	\$	289.96	\$	20.23	\$ 1,604	.91 \$	\$ 1,955.56
														Total Material Total Labor			al Labor	То	tal	Total	To	Total Including
														Total Material Total Labor		ai Laboi	Equip	ment	IUtai		O&P	
													Cost Per Bay	\$	17,928.47		2,104.39			\$ 20,502		\$ 23,660.61
													Cost Per S.F.	\$	26.59	\$	3.12	\$	0.70	\$ 30	).40 \$	\$ 35.09

# 3nd Floor | Cost for 1 Bay

CSI Division	ltem	Туре	Unit		Unit Cost		Total	Total Including O&P	Quantity	Material	Labor	Equipment Total	Total Including O&P
				Material	Labor	Equipment							
Concrete													
03 22 05.00 100	Welded Wire Fabric	6x6 W1.4xW1.4 21 lb. per C.S.F.	C.S.F.	\$ 12.50 \$	22.00	\$	34.50	\$ 49.50	9.25	\$ 115.63	\$ 203.50	\$ 319	13 \$ 457.88
03 31 05.30 300	Structural Concrete	4000psi	C.Y.	\$ 103.00		\$	103.00	\$ 113.00	8.56	\$ 881.68		\$ 881	.68 \$ 967.28
03 31 05.70 1400	Placing Concrete	Elevated slab, less than 6", pumped	C.Y.	Ç	16.80	\$ 5.60 \$	16.80	\$ 31.50	8.56		\$ 143.81	47.936 \$ 191	74 \$ 269.64
03 35 29.30 150	Finishing Floors	Bull float, manual float, broom finish w/ edging and joints	S.F.	Ç	0.50	\$	0.50	\$ 0.74	925		\$ 462.50	\$ 462	.50 \$ 684.50
03 35 29.30 300	Finishing Floors	Power screed, bull float, machine float, trowel (walk-behind)	S.F.	(	0.39	\$ 0.04 \$	0.43	\$ 0.62	925		\$ 360.75	\$ 37.00 \$ 397	75 \$ 573.50
Metals													
05 12 23.75 900	Structural Steel Members	W10x49	L.F	\$ 60.50	4.82	\$ 2.95 \$	68.27	\$ 78.00	15	\$ 907.50	\$ 72.30	\$ 44.25 \$ 1,024	.05 \$ 1,170.00
05 12 23.75 4500	Structural Steel Members	W21x62	L.F	\$ 76.50	3.70	\$ 1.67 \$	81.87	\$ 92.50	37.5	\$ 2,868.75	\$ 138.75	62.625 \$ 3,070	.13 \$ 3,468.75
05 12 23.75 4700	Structural Steel Members	W21x68	L.F	\$ 84.00 \$	3.70	\$ 1.67 \$	89.37	\$ 101.00	112.5	\$ 9,450.00	\$ 416.25	187.875 \$ 10,054	.13 \$ 11,362.50
05 12 23.75 4720	Structural Steel Members	W21x83	L.F	\$ 103.00 \$	3.83	\$ 1.73 \$	108.56	\$ 121.00	24.67	\$ 2,541.01	\$ 94.49	42.6791 \$ 2,678	.18 \$ 2,985.07
05 12 23.75 5500	Structural Steel Members	W27x94	L.F	\$ 116.00 \$	3.22	\$ 1.45 \$	120.67	\$ 135.00	24.67	\$ 2,861.72	\$ 79.44	35.7715 \$ 2,976	.93 \$ 3,330.45
05 31 13.50 5120	Floor Decking	1.5" Thick	S.F.	\$ 1.92	0.43	\$ 0.03 \$	2.38	\$ 2.90	925	\$ 1,776.00	\$ 397.75	27.75 \$ 2,201	50 \$ 2,682.50
										Total Material	Total Labor	Total Total Equipment	Total Including O&P
									Cost Per Bay	\$ 21,402.29	\$ 2,369.53	\$ 485.89 \$ 24,257	70 \$ 27,952.07
									Cost Per S.F.	\$ 23.14	\$ 2.56	\$ 0.53 \$ 26	.22 \$ 30.22

# Roof | Cost for 1 Bay

CSI Division	Item	Туре	Unit			Unit	Cost			Total	Total Including O&P	Quantity	Material	Labo	r	Equipment	Total	Tota	al Including O&P
				N	/laterial	Lab	oor	Equipment											
Metals																			
05 12 23.75 4100	Structural Steel Members	W21x44	L.F	\$	54.50	\$	3.60	\$ 1.6	3 \$	59.73	\$ 68.0	233.82	\$ 12,743.19	\$ 84	1.75	\$ 381.13	\$ 13,966.07	\$	15,899.76
05 12 23.75 4300	Structural Steel Members	W21x50	L.F	\$	62.00	\$	3.60	\$ 1.6	3 \$	67.23	\$ 76.0	0 41.83	\$ 2,593.46	\$ 150	0.59	\$ 68.18	\$ 2,812.23	\$	3,179.08
05 31 13.50 2100	Roof Decking	1.5", 22 gauge	S.F.	\$	1.42	\$	0.35	\$ 0.0	2 \$	1.79	\$ 2.2	1 1032	\$ 1,465.44	\$ 36	1.20	\$ 20.64	\$ 1,847.28	\$	2,280.72
													Total	Total La	hau	Total	Total	Tota	al Including
													Material	Total La	DOI	Equipment	TOLAI		O&P
												Cost Per Bay	\$ 16,802.09	\$ 1,35	3.54	\$ 469.95	\$ 18,625.58	\$	21,359.56
												Cost Per S.F.	\$ 16.28	\$	1.31	\$ 0.46	\$ 18.05	\$	20.70

### **Concrete | Cost for Entire Project**

CSI Division	ltem	Туре	Unit		Unit	t Cost			Total	Tota	al Including	Quantity		Material	Labor		Equipment	Total	Tota	al Including O&P
				Material	La	bor	Equipme	ent												
Concrete																				
03 11 13.25 5650	Forms in Place, Column	Job built, 12"x12" column, 4 use	SFCA	\$ 0.71	\$	5.80		\$	6.51	\$	9.70	16	\$	11.36	\$ 92	2.80	\$	104.16	\$	155.20
03 11 13.65 3000	Forms in Place, Slab on Grade	Edge forms, wood, on grade, to 6" high	L.F.	\$ 0.27	\$	2.18		\$	2.45	\$	3.64	750	\$	202.50	\$ 1,635	5.00	\$	1,837.50	\$	2,730.00
03 15 13.50 20	Waterstops	PVC, ribbed 3/16" thick, 4" wide	L.F.			2.22		\$			4.46	750	\$	712.50	· · · · · · · · · · · · · · · · · · ·	_	\$	2,377.50		3,345.00
03 21 10.60 600	Uncoated Reinforcing Steel	Slab on grade, #3-#7		\$ 855.00		515.00			1,370.00	_	2,025.00	0.94	\$	803.70	·	1.10	\$	1,287.80		1,903.50
03 22 05.50 100	Welded Wire Fabric	6x6 W1.4xW1.4 21 lb. per C.S.F.	C.S.F.		-	22.00		\$			49.50	6.74	\$	84.29	· ·	3.35	\$	232.64	_	333.79
03 30 53.40 3850	Cast-In-Place Concrete	Footings 3000PSI, spread, > 5 CY		\$ 171.00		61.50	•	0.31 \$			283.00	8.61	\$	1,472.31		9.52		2,004.49		2,436.63
03 30 53.40 4650	Cast-In-Place Concrete	SOG 3500 PSI, 4" thick		\$ 117.00		61.50		0.38 \$			225.00	8.32	\$	973.44		L.68		1,488.28		1,872.00
03 30 53.40 6250	Cast-In-Place Concrete	Retaining Wall, 10' High		\$ 129.00		68.50		6.10 \$			254.00	37.04	\$	•		7.24		7,541.34		9,408.16
03 31 05.70 4650	Concrete Placement	SOG, Up to 6" thick, pumped	C.Y.		\$	12.75	\$ 4	4.26   \$			24.00	8.32				5.08		141.52		199.68
03 35 29.30 150	Finishing Floors	Bull float, manual float, broom finish w/ edging and joints	S.F.		\$	0.50		\$		_	0.74	674.33				7.17	\$	337.17		499.00
03 35 29.30 300	Finishing Floors	Power screed, bull float, machine float, trowel (walk-behind)	S.F.		\$	0.39	\$ (	0.04 \$	0.43	\$	0.62	674.33			\$ 262	2.99	\$ 26.97 \$	289.96	\$	418.08
												Total per s.f.	\$	13.40	\$ 12	2.32	\$ 0.44 \$	26.16	\$	34.55
		2nd Floor										Total for floor	\$	424,311.18	\$ 386,255	5.29	\$ 13,681.73 \$	824,248.21	\$	1,087,134.53
CSI Division	Item	Туре	Unit		Unit	t Cost			Total	Tota	al Including O&P	Quantity		Material	Labor		Equipment	Total	Tota	al Including O&P
				Material	la	bor	Equipme	ent			UQF									UQF
Concrete				iviateriai	La	DOI	Equipine	.110												
03 22 05.00 100	Welded Wire Fabric	6x6 W1.4xW1.4 21 lb. per C.S.F.	C.S.F.	\$ 12.50	Ś	22.00		Ś	34.50	ċ	49.50	6.74	Ś	84.29	ć 140	3.35	Ś	232.64	Ļ	333.79
03 31 05.35 300	Structural Concrete	4000psi		\$ 103.00	۲	22.00		\$			113.00	6.24	\$	642.72	Ç 140	5.33	\$	642.72		705.12
03 31 05.70 1400	Placing Concrete	Elevated slab, less than 6", pumped	C.Y.	7 105.00	\$	16.80	ς ι	5.60 \$		_	31.50	6.24	7		\$ 104	1.83	Ψ	139.78		196.56
03 35 29.30 150	Finishing Floors	Bull float, manual float, broom finish w/ edging and joints	S.F.		\$	0.50	Υ .	\$			0.74	925				2.50	\$	462.50		684.50
03 35 29.30 300	Finishing Floors	Power screed, bull float, machine float, trowel (walk-behind)			\$		\$ (	0.04 \$		_	0.62	674.33				2.99		289.96		418.08
												Total per s.f.	\$	1.08	\$ 1	L.45	\$ 0.09 \$	2.62	\$	3.47
		3rd Floor										Total for floor	\$	32,343.72	\$ 43,539	9.81	\$ 2,754.61 \$	78,638.13	\$	104,016.93
CSI Division	Item	Туре	Unit		Unit	t Cost			Total	Tota	al Including O&P	Quantity		Material	Labor		Equipment	Total	Tota	al Including O&P
				Material	La	bor	Equipme	ent												
Concrete		<u> </u>				-	-1 Ja - 2 - 2	-		-										
03 22 05.00 100	Welded Wire Fabric	6x6 W1.4xW1.4 21 lb. per C.S.F.	C.S.F.	\$ 12.50	¢	22.00		\$	34.50	ć	49.50	9.25	Ś	115.63	\$ 202	3.50	Ś	319.13	¢	457.88
03 31 05.30 300	Structural Concrete	6x6 W1.4xW1.4 2110. per C.S.F. 4000psi		\$ 12.50	Ş	22.00		\$			113.00	9.25 8.56	\$	881.68	203 ر	5.50	\$	881.68		967.28
03 31 05.70 1400	Placing Concrete	Elevated slab, less than 6", pumped	C.Y.	y 103.00	\$	16.80	\$ 1	5.60 \$		_	31.50	8.56	<b>ب</b>	201.00	\$ 143	2 81	47.936 \$	191.74		269.64
03 35 29.30 150	Finishing Floors	Bull float, manual float, broom finish w/ edging and joints	S.F.		\$	0.50	. پ	5.00 S			0.74	925			·	2.50	47.930 \$	462.50		684.50
03 35 29.30 300	Finishing Floors	Power screed, bull float, machine float, trowel (walk-behind)			\$	0.39	\$ (	0.04 \$		_	0.62	925				).75		397.75		573.50
												Total per s.f.	\$	1.08	\$ 1	L.27		2.44	\$	3.19
												Total for floor	\$	32,345.03	\$ 37,964	1.04	\$ 2,754.68 \$	73,063.75	\$	95,766.32
											i-	Total for Entire Project	\$	488,999.92	\$ 467,759	9.15	\$ 19,191.02 \$	975,950.09	\$	1,286,917.79

### Structural Steel | Cost for Entire Project

	Foundations a	and 1st Floor																			
CSI Division	Item	Туре	Unit			Unit	Cost		Total	Total Includii	ng Quantity		Material		Labor	E	Equipment		Total	Tof	tal Including O&P
				IV	/laterial	Lal	or	Equipment													
05 05 23.05 70	Anchor Bolts	3/4", hooked w/ nut and washer, 8" long	Ea	\$			2.17		\$ 6.36	\$ 8.1	5 16	\$		\$	34.72			\$	101.76	\$	130.40
05 12 23.65 500	Base Plates	1" thick	S.F.	_	46.00				\$ 46.00	\$ 50.5	0 4	\$	184.00					\$	184.00	\$	202.00
<b>05 12 23.75 900</b> St	tructural Steel Members	W10x49	L.F	\$	60.50	\$	4.82	\$ 2.95	\$ 68.27	\$ 78.0	0 13	\$	786.50	\$	62.66	\$	38.35	\$	887.51	\$	1,014.00
											Total per s.f	. \$	1.53	\$	0.14	\$	0.06	\$	1.74	\$	2.00
											Total for floo	r \$	45,774.32	\$	4,332.30	\$	1,706.14	\$	52,197.14	\$	59,899.46
	2nd I	Floor																			
<b>05 12 23.75 900</b> St	tructural Steel Members	W10x49	L.F	\$	60.50	\$	4.82	\$ 2.95	\$ 68.27	\$ 78.0	0 13.5	\$	816.75	\$	65.07	\$	39.83	\$	921.65	\$	1,053.00
<b>05 12 23.75 3300</b> St	tructural Steel Members	W18x35	L.F	\$	43.50	\$	3.99	\$ 1.80	\$ 49.29	\$ 56.5	0 52	\$	2,262.00	\$	207.48	\$	93.60	\$	2,563.08	\$	2,938.00
<b>05 12 23.75 3500</b> St	tructural Steel Members	W18x40	L.F	\$	49.50	\$	3.99	\$ 1.80	\$ 55.29	\$ 63.5	0 72	\$	3,564.00	\$	287.28	\$	129.60	\$	3,980.88	\$	4,572.00
<b>05 12 23.75 5500</b> St	tructural Steel Members	W24x76	L.F	\$	94.00	\$	3.45	\$ 1.56	\$ 99.01	\$ 111.0	0 28	\$	2,632.00	\$	96.60	\$	43.68	\$	2,772.28	\$	3,108.00
<b>05 12 23.75 5720</b> St	tructural Steel Members	W24x94	L.F	\$	116.00	\$	3.55	\$ 1.60	\$ 121.15	\$ 136.0	0 28	\$	3,248.00	\$	99.40	\$	44.80	\$	3,392.20	\$	3,808.00
<b>05 12 23.75 5920</b> St	tructural Steel Members	W27x114	L.F	\$	141.00	\$	3.33	\$ 1.51	\$ 145.84	\$ 162.0	0 24	\$	3,384.00	\$	79.92	\$	36.24	\$	3,500.16	\$	3,888.00
05 31 13.50 5120	Floor Decking	1.5" Thick	S.F.	\$	1.92	\$	0.43	\$ 0.03	\$ 2.38	\$ 2.9	0 674.33	\$	1,294.71	\$	289.96	\$	20.23	\$	1,604.91	\$	1,955.56
											Total per s.f				1.67	-	0.61		27.78	-	31.62
											Total for floo	or Ş	765,269.09	\$	50,081.35	\$	18,150.23	Ş	833,500.68	<u>\$</u>	948,610.78
	3rd F	loor																			
<b>05 12 23.75 900</b> St	tructural Steel Members	W10x49	L.F	\$	60.50	\$	4.82	\$ 2.95	\$ 68.27	\$ 78.0	0 15	\$	907.50	\$	72.30	\$	44.25	\$	1,024.05	\$	1,170.00
<b>05 12 23.75 4500</b> St	tructural Steel Members	W21x62	L.F	\$	76.50	\$	3.70	\$ 1.67	\$ 81.87	\$ 92.5	0 37.5	\$	2,868.75	\$	138.75		62.625	\$	3,070.13	\$	3,468.75
<b>05 12 23.75 4700</b> St	tructural Steel Members	W21x68	L.F	\$	84.00	\$	3.70	\$ 1.67	\$ 89.37	\$ 101.0	0 112.5	\$	9,450.00	\$	416.25		187.875	\$	10,054.13	\$	11,362.50
<b>05 12 23.75 4720</b> St	tructural Steel Members	W21x83	L.F	\$	103.00	\$	3.83		\$ 108.56	1	0 24.67	\$	2,541.01	\$	94.49		42.6791	\$	2,678.18	\$	2,985.07
<b>05 12 23.75 5500</b> St	tructural Steel Members	W27x94	L.F	\$	116.00				\$ 120.67		0 24.67	\$	2,861.72	_	79.44		35.7715	\$	2,976.93	\$	3,330.45
05 31 13.50 5120	Floor Decking	1.5" Thick	S.F.	\$	1.92	\$	0.43	\$ 0.03	\$ 2.38	\$ 2.9	0 925	\$	1,776.00	\$	397.75		27.75	\$	2,201.50	\$	2,682.50
											Total per s.f	. \$	22.06	\$	1.30	\$	0.43	\$	23.79	\$	27.03
											Total for floo	r \$	661,783.14	\$	38,885.63	\$	13,003.80	\$	713,672.57	\$	810,787.14
	Ro	of																			
<b>05 12 23.75 410</b> 0 St	tructural Steel Members	W21x44	L.F	\$	54.50	\$	3.60	\$ 1.63	\$ 59.73	\$ 68.0	0 233.82	\$	12,743.19	\$	841.75	\$	381.13	\$	13,966.07	\$	15,899.76
<b>05 12 23.75 4300</b> St	tructural Steel Members	W21x50	L.F	\$	62.00	\$	3.60	\$ 1.63	\$ 67.23	\$ 76.0	0 41.83	\$	2,593.46	\$	150.59	\$	68.18	\$	2,812.23	\$	3,179.08
05 31 13.50 2100	Roof Decking	1.5", 22 gauge	S.F.	\$	1.42	\$	0.35	\$ 0.02	\$ 1.79	\$ 2.2	1 1032	\$	1,465.44	\$	361.20	\$	20.64	\$	1,847.28	\$	2,280.72
											Total per s.f				1.31		0.46		18.05		20.70
											Total for floo	r \$	488,484.92	\$	39,351.29	\$	13,662.78	\$	541,498.98	\$	620,983.63
										Total fo	or Entire Project	\$	1,961,311.47	\$	132,650.57	\$	46,522.95	\$	2,140,869.37	\$	2,440,281.01

# Entire Structural System | Cost Per Bay

Cost Per Bay							
	Material	Labor	Е	quipment	Total	To	otal Incl. O&P
Foundation/1st	\$ 10,067.16	\$ 8,407.30	\$	332.54	\$ 18,815.64	\$	24,647.45
2nd	\$ 17,928.47	\$ 2,104.39	\$	469.89	\$ 20,502.75	\$	23,660.61
3rd	\$ 21,402.29	\$ 2,369.53	\$	485.89	\$ 24,257.70	\$	27,952.07
Roof	\$ 16,802.09	\$ 1,353.54	\$	469.95	\$ 18,625.58	\$	21,359.56
Cost Per S.F.							
	Material	Labor	E	quipment	Total	To	otal Incl. O&P
Foundation/1st	\$ 14.93	\$ 12.47	\$	0.49	\$ 27.90	\$	36.55
2nd	\$ 26.59	\$ 3.12	\$	0.70	\$ 30.40	\$	35.09
3rd	\$ 23.14	\$ 2.56	\$	0.53	\$ 26.22	\$	30.22
Roof	\$ 16.28	\$ 1.31	\$	0.46	\$ 18.05	\$	20.70
Entire Building	\$ 80.94	\$ 19.46	\$	2.17	\$ 102.58	\$	122.56
Total Cost							
	Material	Labor	E	quipment	Total	To	otal Incl. O&P
Foundation/1st	\$ 470,085.51	\$ 390,587.59	\$	15,387.87	\$ 876,445.35	\$	1,147,033.99
2nd	\$ 797,612.81	\$ 93,621.16	\$	20,904.84	\$ 912,138.81	\$	1,052,627.72
3rd	\$ 694,128.16	\$ 76,849.67	\$	15,758.48	\$ 786,736.32	\$	906,553.46
Roof	\$ 488,484.92	\$ 39,351.29	\$	13,662.78	\$ 541,498.98	\$	620,983.63
Entire Building	\$ 2,450,311.39	\$ 600,409.71	\$	65,713.98	\$ 3,116,819.46	\$	3,727,198.79
W/Location Factor = 1.089	\$ 2,668,389.11	\$ 653,846.17	\$	71,562.52	\$ 3,394,216.39	\$	4,058,919.49

# Takeoffs | Foundations and 1st Floor

	Tomical Day	. Data	1				
Caluman Lines	Typical Ba		A (af)				
Column Lines	Distance (ft) 28.00	Distance (in) 336.00	Area (sf)				
DD to EE			674.33				
49 to 50	24.08	289.00					
		Slab on Grad	le				
Thickness (ft)	Thickness (in)	D1 (ft)	D2 (ft)	Volume (CY)			
0.33	4	28.00	24.08	8.32			
ww	F						
Туре	Area (sf)						
6x6 W1.4xW1.4	674.33						
Vapor Ba							
Туре	Area (sf)						
10 Mil	674.33						
\A/a+	tons						
Waters							
Type	L.F.						
Flexible PVC	750.00						
	Fo	oting (F10) Co	ncrete				
Thickness (ft)	Area (sf)		Quantity (CY)	Total Volume			
2.00	100.00	7.41	2.00	14.81			
	Fo	oting (F11) Co	ncrete				
Thickness (ft)	Area (sf)	Volume (CY)	Quantity	Total Volume			
2.00	121.00	8.96	1.00	8.96			
	Fo	oting (F12) Co	ncrete				
Thickness (ft)	Area (sf)	Volume (CY)	Quantity	Total Volume			
2.00	144.00	10.67	1.00	10.67			
2.00	144.00	10.07	1.00	10.07			
		F	ooting (F10) Reir	nforcement			
Size	Directions	Length (ft)	Bar Quantity	Footing Quantity	<b>Total Quantity</b>	Length (ft)	Weight (TON)
#6	2	9	12	2	48	432	0.32
		F	ooting (F11) Reir	nforcement			
Size	Directions	Length (ft)	Bar Quantity	<b>Footing Quantity</b>	<b>Total Quantity</b>	Length (ft)	
#8	2	10	10	1	20	200	0.27
				_			
			ooting (F12) Reir				
Size	Directions	Length (ft)	Bar Quantity	Footing Quantity	Total Quantity	Length (ft)	
#8	2	11	12	1	24	264	0.35
			Column	ıs			
Name	Туре	Height (ft)	Quantity	Length (linear ft)	Weight (lb)	Total Weight (lb)	
C2	W10x49	13	2	26	1274		
C3	W10x60	13	2	26	1560	2834	
Base Pl							
Size	Quantity						
1"x16"x16"	2						
1.25"x16"x16"	2	]					

			Anchor I	Bolts	,	
	Туре			<b>Quantity per Column</b>	# of Columns	Total Quantity
	netration, 4" hool hread w/ washers		on, standard	4	4	16
		Footing	g Formwork			
Name	Туре	Thickness (ft)	D1 (ft)	D2 (ft)	Length (ft)	Formwork Area (sf)
F10	Wooden	2	10	10	40	80
F11	Wooden	2	11	11	44	88
F12	Wooden	2	12	12	48	96
		S.O.G. Formw	ork			
Туре	Thickness (ft)	D1	D2	Length (ft)		
Wooden	0.33	24.08	28	104.16		
		crete Retainin				
Туре	Thickness (ft)	L.F.	Height	Volume (CY)		
Reinf. C.	1.00	100.00	10.00	37.04		
		Ct. d. E t.				
_	-1:1 (6:3	Strip Footing	_	14 1 (a)		
Туре	Thickness (ft)	Width (ft)	Length (ft)	Volume (CY)		
SF24	1.00	2.00	750.00	55.56		
	CMU	Block Foundat	ion Wall			
Туре	Thickness (ft)	Length (If)				
16" CMU	16"	800.00				
			Pier			
Туре	Thickness (ft)	D1	D2	Volume (CY)	Quantity	Total Volume
P1	2.00	1.83	1.83	0.25	39	9.71
Typo	Thickness (ft)	D1	D2	Volume (CY)	Quantity	Total Volume
<b>Type</b> P2	2.00	3.00	1.83	0.41	Qualitity 2	0.81
Γ Δ	2.00	3.00	1.85	0.41		0.81
			Pier Reinfo	rcement	l.	
Size	# of Piers	Quantity	Length (ft)	Sum of Length	Weight	Total Weight (TON
#8	39	8	2	624	1666.08	
#3	39	2	6	468	175.968	
ier P1 Reinforce		0	longil (fi)	C af I	\\\ -:- -+	2.06
Size	# of Piers	Quantity	Length (ft)	Sum of Length	Weight	
#8	2 2	12 2	6	48 24	128.16 90.24	

# Takeoffs | 2<sup>ND</sup> Floor

Typical Bay Data												
<b>Column Lines</b>	Column Lines Distance (ft) Distance (in) Area (sf)											
DD to EE	28.00	336.00	674.33									
49 to 50	074.33											

				Columns		
Name	Туре	Height (ft)	Quantity	Length (linear ft)	Weight (lb)	Total Weight (lb)
C2	W10x49	13.5	2	27	1323	2042
С3	W10x60	13.5	2	27	1620	2943

	•	В	Beams		
Type	Length (ft)	Quantity	Weight (lb)	Length (If)	Total Weight (lb)
W18x35	28	1	980	28	
W18x35	24	1	840	24	
W18x40	24	3	2880	72	12106
W24x76	28	1	2128	28	12196
W24x94	28	1	2632	28	
W27x114	24	1	2736	24	
				_	

	Slab on Metal Deck										
Name	Туре	Depth (in)	Gauge	Concrete Thickness (in)	Volume						
S-1	Composite	1.5	18	3	6.24						

### Takeoffs | 3<sup>rd</sup> Floor

Typical Bay Data											
Column Lines Distance (ft) Distance (in) Area (sf)											
GG to JJ	24.67	336.00	925.00								
47 to 48.3 37.50 289.00											

	Columns										
Name	Туре	Height (ft)	Quantity	Length (linear ft)	Weight (lb)	Total Weight (lb)					
C2	W10x49	15	2	30	1470	2270					
С3	W10x60	15	2	30	1800	3270					

Type	Length (ft)	Quantity	Weight (lb)	Total Length (If)	Total Weight (lb)
W21x73	37.50	3	8212.50	113	24638
W21x57	37.50	1	2137.50	38	2138
W21x76	24.67	1	1874.67	25	1875
W27x94	24.67	1	2318.67	25	2319

	ļ.	Slab on	Metal Deck	
Name	Туре	Depth (in)	Gauge	Concrete Thickness (in)
S-1	Composite	1.5	18	3

# Takeoffs | Roof

<b>Column Lines</b>	Distance (ft)	Distance (in)	Area (sf)
GG to JJ	24.67	336.00	1031.89
47 to 48.7	41.83	289.00	1051.89

<b>Column Lines</b>	Distance (ft)	Distance (in)	Area (sf)		Name	Туре	Depth (in)	Gauge
GG to JJ	24.67	336.00	1031.89		S-2	Roof Deck	1.5	22
47 to 48.7	41.83	289.00	1051.69					
		Beam	ıs					
Туре	Length (ft)	Quantity	Weight (lb)	Total Length (If)	Total Weight (lb)			
W21x44	41.83	5	9203.33	209	46017			
W21x44	24.67	1	1085.33	25	1085			
W21x50	41.83	1	2091.67	42	2092			

Metal Roof Deck

APPENDIX D -	- General Condit	tions Estimate	

# General Conditions Estimate | Total Costs (w/ Monthly Costs)


CSI Division	ltem	Туре	Unit	Unit Cost			Total	Total Including O&P	Quantity To		al Cost Including O&P	Total Cost Per Month
				Material	Labor	Equipment						
General Requirements												
Summary of Work												
01 11 31.20 0350	Construction Management Fees	\$50M job, min	Project				4%	4%		\$	2,080,000.00 \$	49,523.81
Project Management and	d Coordination											
01 31 13.20 20	Field Personnel	Clerk, average	Week		410		410	630	183	\$	115,290.00 \$	2,745.00
01 31 13.20 120	Field Personnel	Field Engineer, average	Week		1265		1265	1950	183	\$	356,850.00 \$	8,496.43
01 31 13.20 200	Field Personnel	Project Manager, average	Week		2075		2075	3175	183	\$	581,025.00 \$	13,833.93
01 31 13.20 260	Field Personnel	Superintendent, average	Week		1925		1925	2950	183	\$	539,850.00 \$	12,853.57
01 31 13.30 20	Insurance	Builder's risk, standard, minimum	Job					0.24%		\$	124,800.00 \$	2,971.43
01 31 13.90 20	Performance Bond	For buildings, minimum	Job					2.50%		\$	1,300,000.00 \$	30,952.38
<b>Construction Progress Do</b>	ocumentation											
01 32 13.50 650	Scheduling	Rule of Thumb, CPM, Large job (\$50M +)	Job					0.03%		\$	156,000.00 \$	3,714.29
<b>Regulatory Requirement</b>	ts											
01 41 26.50 20	Permits	Rule of Thumb, most cities, minimum	Job					0.50%		\$	2,600.00 \$	61.90
Quality Control												
01 45 23.50 50	Testing	Steel building, minimum	Job					5200	1	\$	5,200.00 \$	123.81
Construction Facilities												
01 15 13.80 1000	Temporary Facilities	Temporary toilets, rent portable toilet, chemical	Each	0.11	18.65	56	168	180.1	294	\$	52,949.40 \$	1,260.70
01 52 13.20 400	Office and Storage Space	Trailer, furnished, no hookups, 50'x10', buy	Each	23,300	1175		24475	27500	1	\$	27,500.00 \$	654.76
01 52 13.30 1200	Office and Storage Space	Storage Box, 40'x8' rent per month	Each	94			94	103	2	\$	206.00 \$	4.90
01 52 13.20 140	Field Office Expense	Telephone bill: avg bill/month inc. long dist.	Month	81			81	89	42	\$	3,738.00 \$	89.00
01 52 13.20 160	Field Office Expense	Lights and HVAC	Month	152			152	167	42	\$	7,014.00 \$	167.00
Construction Aids	· · · · · · · · · · · · · · · · · · ·								·		·	
0154 09.60 6220	Safety	Safety Supplies and First Aid Kits	Month	24.5			24.5	27	42	\$	1,134.00 \$	27.00
<b>Equipment Mobilization</b>	<u> </u>											
01 54 36.50 20	Mobilization	Doze, loader, backhoe, excav., grader, paver, roller	Each		69	116	185	233	1	\$	233.00 \$	5.55
01 54 36.50 2100	Mobilization	Crane, truck-mounted, over 75 ton	Each		259	46.5	305.5	440	1	\$	440.00 \$	10.48
Temporary Barriers and I	Enclosures											
01 55 23.50 50	Roads and Sidewalks	Roads, gravel fill, no surfaceing, 4" gravel depth	S.Y.	4	2.43	0.45	6.88	8.6	100	\$	860.00 \$	20.48
Temporary Barriers and I	Enclosures	, , , ,										
01 56 26.50 250	Temporary Fencing	Rented chain link, 6' high, over 1000' (up to 12 mo.)	L.F.	10.45	9		19.45	25	4300	Ś	107,500.00 \$	2,559.52
Project Identification		, , , , , , , , , , , , , , , , , , , ,									,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
01 56 13.50 20	Signs	High intensity reflectorized, no posts, buy	S.F.	26.5			26.5	29.5	25	Ś	737.50 \$	17.56
Examination and Prepara	<u> </u>									1	101100 7	
01 71 23.13 1100	Construction Layout	Crew for layout of bldg, trenching, 2 person crew	Day		690	69.5	759.5	1125	16	Ś	18,000.00 \$	428.57
Cleaning and Waste Mar	•	, , , , , , , , , , , , , , , , , , ,									,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
01 76 13.20 20	Cleaning Up	After job completion, minimum	Job				0.30%	0.30%	<u> </u>	Ś	156,000.00 \$	3,714.29
Commissioning	ereag op	Title: job compressing minimum	102				0.5070	0.5070		<u> </u>	250,000.00 φ	3,711123
01 91 13.50 150	Building Commisioning	Basic building commissioning, maximum	%				0.50%	0.50%		Ś	260,000.00 \$	6,190.48
01 31 13:30 130	Dunania commisioning	basic barraing commissioning, maximum	70				0.3070	0.3070			200,000.00 \$	0,150.40
Existing Condtions	<u> </u>											
Surveys												
02 21 13.09 20	Topographical Surveys	Topographical Surveying, conventional, minimum	Acre	18.2	340	21	379.2	565	21	\$	11,865.00 \$	282.50
02 21 13.13 320	Boundary and Survey Markers	Lot location and lines, large quantities, average	Acre	51.5	900	55.5	1007	1500	21	\$	31,500.00 \$	
Selective Demolition	Bournary and Sarvey Warkers	Ecot location and imes, large quantities, average	Acic	31.3	300	33.3	1007	1300	21	٦	31,300.00 7	750.00
02 41 19.23 800	Selective Demolition, Rubbish Handling	Dumpster, weekly rental, 1 dump/wk, 30 C.Y. capacity	Week	750			750	825	183	\$	150,975.00 \$	3,594.64
Erosion and Sedimentati		Dampster, weekly femal, 1 damp, wk, 50 c.f. capacity	WCCK	750			730	023	183	٧	150,575.00 \$	, 3,354.0-
31 25 14.16 1000		Silt fence, polypropylene, 3' high, ideal conditions	L.F.	0.41	0.58		0.99	1.34	4300	\$	5,762.00 \$	137.19
21 72 14.10 1000	Moneu Libsion Control Mats and Diankets	Sittlefice, polypropyrene, 3 fligh, fuedi conditions	L.F.	0.41	0.36		0.55	1.34	4500	Ş	3,702.00 \$	, 15/.15
										^	4.040.030.00	05.667.65
									Total Control to Lancian Foot		4,018,028.90 \$	
									Total Cost with Location Fact	or Ş	4,375,633.47 \$	104,181.75

### General Conditions Estimate | Sub Category Monthly Costs

Item	Туре	٦	Total Cost Including O&P	Mo	onthly Cost		onthly Cost W/ ocation Factor
Field Personnel		\$	1,593,015.00	\$	37,928.93	\$	41,304.60
Insurance and Bonds		\$	1,424,800.00	\$	33,923.81	\$	36,943.03
General Construction Costs		\$	961,755.90	\$	22,898.95	\$	24,936.96
Office and Storage Space		\$	38,458.00	\$	915.67	\$	997.16
	Total Cost	\$	4,018,028.90	\$	95,667.35	\$	104,181.75
	Total Cost with Location Factor	\$	4,375,633.47	\$	104,181.75	\$	113,453.93

Note: These categories have been developed in order to best summarize the items used in the general conditions estimate. Lumping of specific items gives a quick snapshot of which items contributed what quantity of the total cost.

**APPENDIX E - LEED for Schools 2007** 



Project Name: Unionville High School

Project Address: 750 Unionville Road, Kennett Square, PA

	Yes	?	No		e e e			
	40			Project Totals (Pre-Co	ertification Estimates)		79 Points	B
ľ	· · · · · · · · · · · · · · · · · · ·	SILVER		Certified: 29-36 points	Silver: 37-43 points	Gold: 44-57 points		

Prereq 1 Construction Activity Pollution Prevention Prereq 2 Environmental Site Assessment Rec Credit 1 Site Selection Credit 2 Development Density & Community Connectivity Credit 3 Brownfield Redevelopment Credit 4.1 Alternative Transportation, Public Transportation Credit 4.2 Alternative Transportation, Bicycle Use Credit 4.3 Alternative Transportation, Low-Emitting & Fuel Efficient Vehicles Credit 4.4 Alternative Transportation, Parking Capacity Credit 5.1 Site Development, Protect or Restore Habitat Credit 5.2 Site Development, Maximize Open Space Credit 6.1 Stormwater Design, Quantity Control Stormwater Design, Quality Control	
Prereq 2 Environmental Site Assessment Recommunity Connectivity Credit 1 Site Selection Credit 2 Development Density & Community Connectivity Credit 3 Brownfield Redevelopment Credit 4.1 Alternative Transportation, Public Transportation Credit 4.2 Alternative Transportation, Bicycle Use Credit 4.3 Alternative Transportation, Low-Emitting & Fuel Efficient Vehicles Credit 4.4 Alternative Transportation, Parking Capacity Credit 5.1 Site Development, Protect or Restore Habitat Credit 5.2 Site Development, Maximize Open Space Credit 6.1 Stormwater Design, Quantity Control	
Prereq 2 Environmental Site Assessment Recommunity Connectivity Credit 1 Site Selection Credit 2 Development Density & Community Connectivity Credit 3 Brownfield Redevelopment Credit 4.1 Alternative Transportation, Public Transportation Credit 4.2 Alternative Transportation, Bicycle Use Credit 4.3 Alternative Transportation, Low-Emitting & Fuel Efficient Vehicles Credit 4.4 Alternative Transportation, Parking Capacity Credit 5.1 Site Development, Protect or Restore Habitat Credit 5.2 Site Development, Maximize Open Space Credit 6.1 Stormwater Design, Quantity Control	linis.
Prereq 2 Environmental Site Assessment  Credit 1 Site Selection  Credit 2 Development Density & Community Connectivity  Credit 3 Brownfield Redevelopment  Credit 4.1 Alternative Transportation, Public Transportation  Credit 4.2 Alternative Transportation, Bicycle Use  Credit 4.3 Alternative Transportation, Low-Emitting & Fuel Efficient Vehicles  Credit 4.4 Alternative Transportation, Parking Capacity  Credit 5.1 Site Development, Protect or Restore Habitat  Credit 5.2 Site Development, Maximize Open Space  Credit 6.1 Stormwater Design, Quantity Control	Juired
Credit 1 Site Selection  Credit 2 Development Density & Community Connectivity  Credit 3 Brownfield Redevelopment  Credit 4.1 Alternative Transportation, Public Transportation  Credit 4.2 Alternative Transportation, Bicycle Use  Credit 4.3 Alternative Transportation, Low-Emitting & Fuel Efficient Vehicles  Credit 4.4 Alternative Transportation, Parking Capacity  Credit 5.1 Site Development, Protect or Restore Habitat  Credit 5.2 Site Development, Maximize Open Space  Credit 6.1 Stormwater Design, Quantity Control	•
Credit 3 Brownfield Redevelopment Credit 4.1 Alternative Transportation, Public Transportation Credit 4.2 Alternative Transportation, Bicycle Use Credit 4.3 Alternative Transportation, Low-Emitting & Fuel Efficient Vehicles Credit 4.4 Alternative Transportation, Parking Capacity Credit 5.1 Site Development, Protect or Restore Habitat Credit 5.2 Site Development, Maximize Open Space Credit 6.1 Stormwater Design, Quantity Control	uirea
Credit 4.1 Alternative Transportation, Public Transportation Credit 4.2 Alternative Transportation, Bicycle Use Credit 4.3 Alternative Transportation, Low-Emitting & Fuel Efficient Vehicles Credit 4.4 Alternative Transportation, Parking Capacity Credit 5.1 Site Development, Protect or Restore Habitat Credit 5.2 Site Development, Maximize Open Space Credit 6.1 Stormwater Design, Quantity Control	1
Credit 4.2 Alternative Transportation, Bicycle Use Credit 4.3 Alternative Transportation, Low-Emitting & Fuel Efficient Vehicles Credit 4.4 Alternative Transportation, Parking Capacity Credit 5.1 Site Development, Protect or Restore Habitat Credit 5.2 Site Development, Maximize Open Space Credit 6.1 Stormwater Design, Quantity Control	1
Credit 4.3 Alternative Transportation, Low-Emitting & Fuel Efficient Vehicles Credit 4.4 Alternative Transportation, Parking Capacity Credit 5.1 Site Development, Protect or Restore Habitat Credit 5.2 Site Development, Maximize Open Space Credit 6.1 Stormwater Design, Quantity Control	1
Credit 4.4 Alternative Transportation, Parking Capacity Credit 5.1 Site Development, Protect or Restore Habitat Credit 5.2 Site Development, Maximize Open Space Credit 6.1 Stormwater Design, Quantity Control	1
Credit 4.4 Alternative Transportation, Parking Capacity Credit 5.1 Site Development, Protect or Restore Habitat Credit 5.2 Site Development, Maximize Open Space Credit 6.1 Stormwater Design, Quantity Control	1
Credit 5.1 Site Development, Protect or Restore Habitat Credit 5.2 Site Development, Maximize Open Space Credit 6.1 Stormwater Design, Quantity Control	1
Credit 6.1 Stormwater Design, Quantity Control	1
The second secon	1
Credit 6.2 Stormwater Design, Quality Control	1
	1
Credit 7.1 Heat Island Effect, Non-Roof	1
Credit 7.2 Heat Island Effect, Roof	1
Credit 8 Light Pollution Reduction	1
Credit 9 Site Master Plan	1
1 Credit 10 Joint Use of Facilities	1.



# LEED for Schools 2007 Registered Project Checklist

	Yes	?	No				
!	2			Walle's	Fifteleney		
				Credit 1.1	Water Eff	icient Landscaping, Reduce by 50%	
				Credit 1.2			1
				Credit 2		icient Landscaping, No Potable Use or No Irrigation e Wastewater Technologies	1
	1			Credit 3		Reduction	1
						20% Reduction	1 to 3
					Credit 3.2	30% Reduction	1
					Credit 3.3	40% Reduction	2
				Credit 4		ater Use Reduction, 20% Reduction	3
		,				neduction, 20% reduction	1
	Yes	?	No				
	6			a Briefy	Ceannes	)je/e	
	V						WEDIEF
				Prereq 1	Fundamen	tal Commissioning of the Bui <b>ldi</b> ng Energy Systems	Required
	150			Prereq 2		Energy Performance	Required
				Prereq 3		tal Refrigerant Management	Required
	*Note for EA	c1: All LE	ED for Sch	ools projec	ts registered a	ofter June 26, 2007 are required <b>to a</b> chieve at least two (2) points	
	5			Credit 1		nergy Performance	
					Credit 1.2	14% New Buildings / 7% Existing Building Renovations	2 to 10
					Credit 1.3	17.5% New Buildings / 10.5% Existing Building Renovations	2
	,				Credit 1,4	21% New Buildings / 14% Existing Building Renovations	- 3
				>	Credit 1.5	24.5% New Buildings / 17.5% Existing Building Renovations	4
					Credit 1.6	28% New Buildings / 21% Existing Building Renovations	5
					Credit 1.7	31.5% New Buildings / 24.5% Existing Building Renovations	. 6
			•		Credit 1.8	35% New Buildings / 28% Existing Building Renovations	7
				•	Credit 1.9	38.5% New Buildings / 31.5% Existing Building Renovations	8
_		<del></del>			Credit 1.10	42% New Buildings / 35% Existing Building Renovations	9
L				Credit 2	On-Site Ren	ewable Energy	10
						2.5% Renewable Energy	1 to 3
						7.5% Renewable Energy	1
_						12.5% Renewable Energy	2
-			(	Credit 3		ommissioning	3
-	1		(	Tredit 4	Enhanced R	efrigerant Management	1
L				redit 5		nt & Verification	. 1
			(	redit 6	Green Powe	r	1
							1

Adobe LiveCycle



# LEED for Schools 2007 Registered Project Checklist

Yes	?	No			
9			Maileth	ils v Hespilurges	
. Yes			Prereq 1	Storage & Collection of Recyclables	Elkonis
1			Credit 1.1	Building Reuse, Maintain 75% of Existing Walls, Floors & Roof	Required
			Credit 1.2	Building Reuse, Maintain 95% of Existing Walls, Floors & Roof	1
1			Credit 1.3		1
100			Credit 2.1	Building Reuse, Maintain 50% of Interior Non-Structural Elements  Construction Waste Management, Divert 50% from Disposal	1
			Credit 2.2		1
1			Credit 3.1	Construction Waste Management, Divert 75% from Disposal  Materials Reuse, 5%	1
1			Credit 3.2	Materials Reuse, 10%	1
4			Credit 4.1	•	1
1			Credit 4.2	Recycled Content, 10% (post-consumer + 1/2 pre-consumer)	1
			Credit 5.1	Recycled Content, 20% (post-consumer + 1/2 pre-consumer)	. 1
<b>i</b>			Credit 5.2	Regional Materials, 10% Extracted, Processed & Manufactured	1
1			Credit 6	Regional Materials, 20% Extracted, Processed & Manufactured	1
			Credit 7	Rapidly Renewable Materials  Certified Wood	1
		SANTAN TRATE	2.33.(7	Certified WOOD	1



# LEED for Schools 2007 Registered Project Checklist

,	Yes	?	No			
	13				Bavironmental Otality	4 20 Ponnies
	Yesi			Prereq 1	Minimum IAQ Performance	Dogulard
	Yes .		. '	Prereq 2	Environmental Tobacco Smoke (ETS) Control	Required
	Yes	S. Owen		Prereq 3	Minimum Acoustical Performance	Required
				Credit 1	Outdoor Air Delivery Monitoring	Required
		化(40%)		Credit 2	Increased Ventilation	·
	1			Credit 3.1	Construction IAQ Management Plan, During Construction	1
	1			Credit 3.2	Construction IAQ Management Plan, Before Occupancy	1
	1			Credit 4	Low-Emilting Materials	1 4 - 4
	1			Credit 5	Indoor Chemical & Pollutant Source Control	1 to 4
	1			Credit 6.1	Controllability of Systems, Lighting	1
			A TOPPES AT BERNEY POS	Credit 6.2	Controllability of Systems, Thermal Comfort	1
				Credit 7.1	Thermal Comfort, Design	1
				Credit 7.2	Thermal Comfort, Verification	
	. 2			Credit 8.1	Daylight & Views, Daylight 75% of Spaces	1 to 3
				>	75% of classrooms (Required for either points below)	1 (0 3
1		•		>	90% of classrooms	2
					75% of other spaces	3
				Credit 8.2	Daylight & Views, Views for 90% of Spaces	. 1
	1			Credit 9	Enhanced Acoustical Performance, 40 dBA / RC level of 32	1
					Enhanced Acoustical Performance, 35 dBA / RC level of 27	1
	1			Credit 10	Mold Prevention	1
					·	'
	Yes	7	No			
ı	2	· ·	Te Te			
					on & Design Process	was divid
				Credit 1.1	Innovation in Design: Provide Specific Title	1
				Credit 1.2	Innovation in Design: Provide Specific Title	1
				Credit 1.3	Innovation in Design: Provide Specific Title	1
				Credit 1.4	Innovation in Design: Provide Specific Title	1
	1			Credit 2	LEED® Accredited Professional	1
	1			Credit 3	School as a Teaching Tool	,

Adobe\* LiveCycle\*

APPENDIX	F – LEED 2009 fo	or New Construct	ion and Major Rei	novations



# LEED 2009 for New Construction and Major Renovations

Unionville High School Building Additions and Renovations

Proje	ct Checklist		October 15th, 2011
	inable Sites Possible P	oints: 26	Materials and Resources, Continued
Credit 4. Credit 4. Credit 5. Credit 5. Credit 5. Credit 6. Credit 6. Credit 6.	Alternative Transportation—Bicycle Storage and Changing Rod Alternative Transportation—Low-Emitting and Fuel-Efficient Alternative Transportation—Parking Capacity Site Development—Protect or Restore Habitat Site Development—Maximize Open Space Stormwater Design—Quantity Control Stormwater Design—Quality Control	Vehicles 3 2 1 1 1 1 1 1 1 1 1 1	Credit 4 Recycled Content Credit 5 Regional Materials 1 to 2 Credit 6 Rapidly Renewable Materials 1 Credit 7 Certified Wood 1  Indoor Environmental Quality Possible Points: 15  Y Prereq 1 Minimum Indoor Air Quality Performance Prereq 2 Environmental Tobacco Smoke (ETS) Control Credit 1 Outdoor Air Delivery Monitoring 1 Credit 2 Increased Ventilation 1 Credit 3.1 Construction IAQ Management Plan—During Construction 1 Credit 3.2 Construction IAQ Management Plan—Before Occupancy 1 Credit 4.1 Low Emitting Materials, Adherives and Scalants
1 Credit 8	Light Pollution Reduction  Efficiency  Possible	1 1 Points: <b>10</b>	1 Credit 4.1 Low-Emitting Materials—Adhesives and Sealants 1 1 Credit 4.2 Low-Emitting Materials—Paints and Coatings 1 Credit 4.3 Low-Emitting Materials—Flooring Systems 1 1 Credit 4.4 Low-Emitting Materials—Composite Wood and Agrifiber Products 1
Y Prereq 1 2 Credit 1 Credit 2 Credit 3	Water Use Reduction—20% Reduction Water Efficient Landscaping Innovative Wastewater Technologies Water Use Reduction  y and Atmosphere Possible Possible	2 to 4 2 2 to 4 2 oints: <b>35</b>	Credit 5 Indoor Chemical and Pollutant Source Control  Credit 6.1 Controllability of Systems—Lighting  Credit 6.2 Controllability of Systems—Thermal Comfort  Credit 7.1 Thermal Comfort—Design  Credit 7.2 Thermal Comfort—Verification  Credit 8.1 Daylight and Views—Daylight  Credit 8.2 Daylight and Views—Views  1
Y Prereq 1 Y Prereq 2 Y Prereq 3 7 Credit 1 Credit 2 Credit 3 Credit 4 Credit 5 Credit 6	Fundamental Commissioning of Building Energy Systems Minimum Energy Performance Fundamental Refrigerant Management Optimize Energy Performance On-Site Renewable Energy Enhanced Commissioning Enhanced Refrigerant Management Measurement and Verification Green Power	1 to 19 1 to 7 2 2 3 2	1 Innovation and Design Process Possible Points: 6  Credit 1.1 Innovation in Design: Specific Title 1 Credit 1.2 Innovation in Design: Specific Title 1 Credit 1.3 Innovation in Design: Specific Title 1 Credit 1.4 Innovation in Design: Specific Title 1 Credit 1.5 Innovation in Design: Specific Title 1 Credit 2 LEED Accredited Professional 1  Regional Priority Credits Possible Points: 4
11   Mater	3 , , ,	1 to 3	Credit 1.1 Regional Priority: MRc2: Recycle/Salvage 50% 1 Credit 1.2 Regional Priority: SSc5.1 1 Credit 1.3 Regional Priority: SSc6.1 1 Credit 1.4 Regional Priority: Specific Credit 1  Total Possible Points: 110 Certified 40 to 49 points Silver 50 to 59 points Gold 60 to 79 points Platinum 80 to 110

# **APPENDIX G - BIM Use Evaluation**

BIM Use*	Value to Project	Responsible Party	Value to	Cap	pability Ra	ating	Additional Resources / Competencies Required	Notes	Proceed with Use
	High / Med / Low		High / Med / Low		Scale 1-3 (1 = Low				YES / NO / MAYBE
				Resources	Competency	Experience			
Record Modeling	MED	Contractor Owner	MED HIGH	2	2	2	Software/Training for software Software/Training for software		YES
Site Utilization Planning	MED	Designer	MED	3	1	3			NO
3D Control and Planning	MED	Contractor	HIGH	2	2	2			YES
		Subcontractors	HIGH	2	2	2			
3D Coordination	HIGH	Contractor	HIGH	2	2	2	Software/Training for software		YES
	_	Subcontractors Designer	HIGH MED	1	1 3	1	Software/Training for software		
Design Authoring	HIGH	Contractor	HIGH	2	2	2	Software/Training for software		YES
<del>U</del>		Owner Designer	HIGH MED	1	1 3	1	Software/Training for software		
LEED Evaluation	HIGH	Contractor	HIGH	2	3	3		LEED Project, value is high	YES
		Owner Designer	HIGH	2	1 3	1	Software/Training for software Software/Training for software	3,227, 222, 2	
Programming	MED	Contractor Owner	HIGH	2	2	2	Software/Training for software		MAYBE
		Designer	MED	3	3	3	Contware/ Fraiming for Software		
4D Modeling	HIGH	Contractor	HIGH	2	2	2	Software/Training for software	Uses: Phasing and Construction New software required	MAYBE
Cost Estimation	MED	Contractor	HIGH	3	2	2			YES
									]

