

## Presentation Outline

Alec Hanley

Construction Management

Advisor: Ray Sowers

Cardinal Wuerl North Catholic High School

Cranberry Township, PA

Wednesday, April 2<sup>nd</sup>, 2014

### **Introduction (0:15)**

#### **1. Project Overview (1:30)**

- a. Project History
- b. Project Delivery System
- c. Building Statistics

#### **2. Analysis I – Sto Panel Prefabricated Masonry Panels (4:00)**

- a. Problem Identification
  - i. Quality Control intensive façade assembly
  - ii. Opportunity to save money by reducing critical path & substantial completion date
- b. Suggestions
  - i. Sto Panel Brick Insulated system to reduce overall project duration and increase quality
- c. Results
  - i. Sto Panel Brick Insulated system greatly reduces project duration
  - ii. Panelized system is much more expensive but reduces critical path
  - iii. *Architectural Breadth*
  - iv. *Structural Breadth*
- d. Recommendation
  - i. Do not use Sto Panel system. Cost savings are not significant enough for owner to yield usage on project where schedule is not critical.

#### **3. Analysis II – Lifetime VE Finish Costs (2:00)**

- a. Problem Identification
  - i. \$800,000 of accepted VE reduction (\$2,740,000) focused on finishes
  - ii. Did not consider lifecycle cost of maintenance, replacement, cleaning, etc.
- b. Suggestions
  - i. Lifecycle costs of tile reduction, linoleum reduction, linear wood reduction in upstairs corridors, VCT reduction, and Ultima Ceiling Tile change may cost more throughout lifecycle
- c. Results
  - i. Tile/linoleum/linear wood/VCT/Ceiling Tile Reductions cost more over lifetime
- d. Recommendations
  - i. Use originally suggested alternatives materials.

4. **Analysis III – Efficient & Effective Turnover of FM Information (2:00)**
  - a. Problem Identification
    - i. Critical Industry Research
    - ii. FM planned to be heavily integrated with BIM at CWNCHS
  - b. Suggestions
    - i. Determine best way to go about training FM
    - ii. Determine best course of action to implement FM software
  - c. Results
    - i. Onuma Software being used at CWNCHS is best fit
    - ii. Training and Software implementation have areas of improvement
    - iii. Owner’s Guide Developed
  - d. Recommendations
    - i. Follow owner’s guide when considering
    - ii. Clearly define goals from the beginning of the project
5. **Analysis IV – Alternative Roofing Systems Analysis (3:00)**
  - a. Problem Identification
    - i. TPO Roofing could not be installed during winter months. Caused critical path problems
  - b. Suggestions
    - i. Evaluate alternative systems such as Built-Up Roofing and PVC
    - ii. Use Duro-Last PVC prefabrication methods
  - c. Results
    - i. Duro-Last PVC is competitively priced and saves time
    - ii. Overall cost savings reported in general conditions savings
  - d. Recommendations
    - i. Use Duro-Last PVC system as originally suggested
6. **Conclusions & Recommendations (1:00)**
7. **Acknowledgements (0:15)**

**Total Estimated Time (14:00)**



## PROJECT OVERVIEW | Building Statistics

### Project Overview

Prefabricated Masonry Panels

Breadths – Arch & Structural

Lifetime Costs of VE Finish

Efficient/Effective FM Info Turnover

Alternative Roof Systems Analysis

Final Recommendations

Acknowledgements



SIZE | 177,129 SF  
 PROJECT COST | \$72.5 million  
 CONTRACT TYPE | GMP  
 DELIVERY METHOD | Design-Bid-Build, Multiple Prime, GC Lead with CM Agency  
 SCHEDULE | June 2012 – June 2014  
 OWNER | Catholic Diocese of Pittsburgh  
 GENERAL CONTRACTOR | Mascaro Construction Company  
 CM AGENCY | Campayno Consulting Services  
 ARCHITECT | Astorino



## PREFAB PANELS | Problem Identification

### Project Overview

Prefabricated Masonry Panels

Breadths – Arch & Structural

Lifetime Costs of VE Finish

Efficient/Effective FM Info Turnover

Alternative Roof Systems Analysis


Final Recommendations

Acknowledgements



## Existing System

- Stick-built cold-formed metal framing with sheathing, continuous vapor barrier, insulation and brickvener
- Very congested jobsite
  - Scaffolding
  - Equipment
  - Manpower
- \$1,516,000 to complete
- Critical path item for 62 days



Typical Wall Section

## PREFAB PANELS | Problem Identification

### Project Overview

Prefabricated Masonry Panels

Breadths – Arch & Structural

Lifetime Costs of VE Finish

Efficient/Effective FM Info Turnover

Alternative Roof Systems Analysis

Final Recommendations

Acknowledgements



## Existing System

- Stick-built cold-formed metal framing with sheathing, continuous vapor barrier, insulation and brickvener
- Very congested jobsite
  - Scaffolding
  - Equipment
  - Manpower
- \$1,516,000 to complete
- Critical path item for 62 days



Scaffolding Congestion – Area E North Elevation