

October 16, 2013

# Sunnyvale Plaza

Mid-Atlantic Region, United States

Nathan Braskey – Construction Management

Technical Assignment #2

FACULTY CONSULTANT: CRAIG DUBLER



## Executive Summary

The conception of Sunnyside Plaza took place in 1999 with the need for a convention headquarters in the Mid-Atlantic city. After many complications, on September 24, 2007 the proposal was accepted and design began. Ground was broken on November 10, 2010. A detailed schedule was developed to analyze the unique top-down construction method utilized on the project. This was most important for the lengthy excavation process that was necessary. A summary short interval production schedule was also developed to review the hotel room finishes phase.

A detailed structural estimate was established for the entire structural system. This was important to ensure accuracy during the takeoff due to the unique nature of the underground structural system. This yielded an estimate of \$47 million, which is approximately 29% less than the square foot structural estimate.

The assemblies MEP estimate also yielded a lower value than produced from the square foot estimate. Due to the large difference between each system cost within the square foot estimate, the costs were expected to be lower for some of the more inflated systems. An average system cost was determined to better understand the difference between the actual construction cost, the square foot estimate, and the assemblies estimate.

Project site layouts were developed for three different phases of construction. These phases included the excavation of the slurry wall and substructure, the superstructure installation, and the finishes phase. These three phases were crucial for site coordination due to the complexity of the below-grade construction and the limited site area. Another area of interest was the temporary closing of the east street during the concourse excavation and construction.

The general conditions estimate yielded a more expensive field personnel cost due to the complexity of the project and need for a more extensive project team. Other items that were evaluated include office trailer usage, temporary utility needs, and commissioning. This evaluation was important to assess the savings involved in any major schedule changes.

There were several constructability challenges during different construction phases. The most primary concerns included the unique top-down excavation process and the concourse excavation and construction. This construction phase needed extra attention concerning the east street and underground utilities in the area. The top-down excavation also prolonged the schedule extensively. Other concerns included existing buildings within the project site, lead time for the statue construction, and the limited space within the project site.

A LEED evaluation was produced for the sustainability strategies utilized on the project. Great care was taken in the selection of regional and recycled products as well as optimizing energy performance within the building. It was also fairly easy to acquire points for alternative transportation due to the location of the project. Other sustainability priorities included materials and resources, indoor environmental quality, and water efficiency.

**TABLE OF CONTENTS**

**Executive Summary .....i**

**Table of Contents .....ii**

**Project Schedule ..... 1**

**Detailed Structural Estimate ..... 4**

**Assemblies MEP Estimate ..... 5**

**Site Layout Planning ..... 6**

**General Conditions Estimate ..... 7**

**Constructability Challenges ..... 9**

**LEED Evaluation ..... 11**


Project Schedule – See Appendix A for detailed schedule

OVERVIEW

The concept for Sunnyvale Plaza came in 1999 with a proposal to construct a convention headquarters neighboring the city’s convention center. Initial estimates proposed that the hotel would cost roughly \$200 million, which would need to be reduced by about \$30 million in order to be profitable. A proposal from a nearby hotel to expand into a convention headquarters was also vying for approval, but was later rejected due to a risk of poor revenue production. The September 11th attacks on the United States caused a substantial economic downturn that postponed the awarding of the proposal until late October of 2002. Economists alleged that the initial financing proposal was controversial in that it would lower sales tax revenue within the area. In April of 2004, the city council began debating on whether or not to consider building the headquarters on a different site. On December 3, 2004, the council voted in favor of continuing the plan to build on the original site. On August 22, 2005, the Plumbers Union Building was sold to the developer to obtain more of the property to develop. In June of 2006 the first financing package was approved by the council and in February of 2007 private financing came together to complete the proposal. On September 24, 2007, after several reconsiderations for the size of the hotel to reduce financing, the developer signed an agreement to jointly finance the hotel. Ground was finally broken on November 10, 2010 and construction began.

Phase	Start Date	End Date	Duration
Design	11/1/2008	3/27/2013	1149
Procurement	12/26/2012	8/16/2013	168
Excavation & Substructure	3/25/2013	7/15/2013	81
Superstructure	4/2/2013	7/15/2013	75
Building Envelope	2/22/2013	11/13/2013	189
Building Fit-Out	8/1/2012	3/12/2014	421
Finishes	2/4/2013	3/17/2014	291

Table 1: Project Schedule Summary





## BUILDING CONSTRUCTION

### Design & Preconstruction

The official Request For Proposal was released in April of 2001, for a 1,100-room convention headquarters hotel. The original design created 1,500 rooms. After various attempts to gather funding, the hotel design was scaled back from the original design to 1,150 rooms. Sunnyvale released details of the design in October of 2008. The design was submitted to the National Capital Planning Commission late in 2008 and approved early in February of 2009.

### Excavation & Substructure

Ground was broken on November 10, 2010 for Sunnyvale Plaza. Due to the more complicated excavation process, construction was expected to be extended by an entire year. Each below-grade slab was poured on-grade, then excavated underneath. This process was done one level at a time down to the bottom level. Utilizing this unique method made it possible to excavate to such a large depth below the street. A slurry wall construction was also used to secure the subgrade levels. The perimeter of the building was excavated, reinforced, and poured first. This slurry wall created a suitable shoring method and a secure subgrade exterior support system.

### Superstructure

The superstructure utilizes pre-cast columns and beams with a steel composite deck. Utilizing pre-cast assembly methods created a faster erection process for the above-grade structure. The entire above grade structure took about four months to complete. The structural frame was broken into two towers, North and South.

### Building Envelope

The first phase of the building envelope began late in February of 2013. While this side of the curtain wall began early, the other sides did not begin until April. The first phase was the North Elevation, followed by the West Elevation, East Elevation, and South Elevation. The procedure for the envelope construction began with the installation of the exterior frame and punch windows. Once the frame was secured, the primary curtain wall components were installed. These consisted of hundreds of metal panels and windows. Each elevation of the curtain wall consisted of a duration of about 100 - 150 workdays.

### Building Fit-Out

The primary mechanical and electrical chases are located within the four corners of the building. Neighboring the elevator areas are telecom/data and mechanical/electrical rooms. These rooms are used to house Panelboards and vertical shafts for ducts and mass conduit runs.




Figure 1: Excavation of Level M1




Figure 2: Level M1 Slab-On-Grade




Figure 3: Excavation of Level M2




Figure 4: Level M2 Slab-On-Grade



Detailed Structural Systems Estimate – See Appendix B for detailed takeoff

OVERVIEW

The structural system of Sunnyvale Plaza differs between the substructure and superstructure. The below-grade structure consists of steel columns and a slurry wall construction. The superstructure is made up of all concrete construction and steel deck. The substructure is unique in that it is also connected to the neighboring convention center. This created a complicated condition for working underneath an active street. The complete structural system was estimated to cost about \$47 million using a detailed structural estimate method. The total cost for the structural system using RS Means Square Foot Analysis was estimated at \$66 million. This detailed estimate is approximately 29% less than the square foot approximation. This can be due to and value engineering utilized to succeed on such a complicated project. Reed Construction Data RS Means Online was utilized to estimate the structural components. The following descriptions define the breakdown of each structural system.

Structural Item	Cost	Breakdown
Total Structural Cost	\$ 47,000,000.00	-
Steel Construction	\$ 8,400,000.00	18%
Atrium Construction	\$ 1,240,000.00	3%
Slurry Wall Construction	\$ 9,800,000.00	21%
Concrete Structural System	\$ 27,000,000.00	57%

Table 2: Structural Estimate Breakdown

SUBSTRUCTURE

The substructure began with a slurry wall construction around the entire perimeter. This acted as the exterior structural support and as shoring while the rest of the site was excavated. The slurry wall was composed of 4000 psi concrete with local aggregate, sand, and Portland cement. Column boring was then utilized to create shafts for the steel columns to be placed. The slurry wall construction accounted for approximately \$9.8 million. Once the columns were set, concrete was poured within the boreholes to encase the steel. The encasements were also reinforced with rebar. Natural formwork played a major role in the concrete pouring for all substructure components. The steel columns were composed of wide flange W14 columns that ranged from 90 to 398 lbs per linear foot. There are also two W14x665 columns located near the two primary elevator shafts. The complete steel substructure costs accounted for roughly \$8.4 million and about 18% of the entire structural cost.

The concourse also created a difficult structural process wherein the slurry walls and street needed to be temporarily secured while the openings were created. There were various underground utilities that needed to be relocated due to the concourse construction. These utilities were temporarily supported while the concourse area was excavated, then rerouted closer to the street.

---

## SUPERSTRUCTURE

The superstructure utilizes concrete precast columns and beams with a composite deck. The columns were set on a typical grid throughout most of the above-grade structure. The large opening of the atrium was unique in that the amount of structural space was very small throughout each side. Within the upper levels, there was not actually much space aside from hotel rooms and corridors. This made it very difficult to fit some columns within intersections and elevator lobbies. The concrete columns range from 16x16 columns to a 44x48 column. The concrete beams range from 12x12 beams to two 50x66 beams. Typical reinforcing is located within each column and beam. The concrete structural system cost was roughly \$27 million which accounted for about 57% of the overall structural estimate.

The atrium skylight was a unique part of the superstructure. Several large triangular steel trusses span the atrium from the north corridor to the south corridor. These trusses are the structural support for the skylight frame. The steel trusses were a substantial part of the steel construction because the only other major steel utilized in the building was the below-grade structure.

Assemblies MEP Estimate – *See Appendix C for detailed takeoff*

---

## OVERVIEW

The assemblies MEP estimate was assessed using Reed Construction RSMeans Data. The estimated cost for the mechanical, electrical, and plumbing system totaled \$78,200,105. This cost is translated to approximately \$104 per square foot. This is substantially lower than the RSMeans construction costs breakdown. Analysis of this cost breakdown yields several possibilities for error.

The construction cost breakdown for the plumbing system was extensively higher than the other building systems. This is believed to be inaccurate as it is roughly double the cost of any other system. Calculating an average building systems cost for the other systems yields a cost of roughly \$43 million per building system.

Another source of error originates from the lack of options available within RSMeans Data. This made it difficult to choose the exact components that make up the mechanical and electrical system. Components that were similar were chosen for any components that were not available. Certain components were substantially different and needed to be extrapolated to make up for the extensive size difference. This limited data can create various errors throughout the entire estimate that in-turn add up to a substantial difference for each building system.

Assemblies Item	Overall Cost	Percentage of Cost
Mechanical System	\$ 38,858,400.00	50%
Electrical System	\$ 13,685,365.00	18%
Plumbing System	\$ 16,932,960.00	22%
<b>Total Assemblies Cost</b>	<b>\$ 78,200,105.00</b>	
<b>Cost / S.F.</b>	<b>\$ 103.99</b>	

Table 3: MEP Estimate Breakdown




Figure 6: MEP Estimate Breakdown

Site Layout Planning – See Appendix D for detailed site plans

EXCAVATION – SLURRY WALL

One of the most difficult phases of construction was the slurry wall installation and excavation. Due to the high complicity for this phase, the construction was extended an entire year longer than initially intended. Before this phase, the site preparation and mobilization took place. The project trailers are located on a neighboring parking lot just north of the project site. The north gate will be utilized for entrance from the project trailers, and it is important to ensure a safe traverse across the active street. Due to the tight project site, the primary material laydown areas are located just north of the PEPCO Substation. At this point in the construction process, there are two existing buildings that are located within the project site. It is crucial to maintain a safe excavation process considering the load that is on the soil within close proximity of the excavation. The street east of the project site will also be excavated while the underground utilities are temporarily supported. Some utilities will also be moved due to the concourse construction.

Holes will be left in each slab as they are poured on-grade, then excavated underneath. A protection barrier is placed underneath each slab to tear down once the excavation is completed. This protects the bottom of the slab from any dirt or debris during excavation. Cranes and hoists located near each of the major slab openings are used to excavate through the openings. Once there is sufficient room, larger equipment is lowered into the sub-grade levels to excavate across the entire slab. This process will be continued through the same holes on each below-grade level.

---

## SUPERSTRUCTURE

Once the substructure is completed and the primary substructure is in place, the slabs can be used to store material. The primary material laydown will still be located north of the PEPCO Substation and a secondary material laydown area will open on the east side of the project site. Both the north and south side of the project site will now be used for material delivery via trucks. The Plumbers Union Building will now be connected to the new structure, and considered a part of the building. Dumpsters are also located on the northeast corner of the project site. The east street will still be closed during this phase of construction for structural completion. A temporary platform will be placed so that the area can be utilized during this phase. A concrete placement area is also created near the north entrance of the project site.

---

## FINISHES

As the finishing phase begins, site cleanup must begin. Landscaping and exterior construction will start to take place and the surrounding areas must be available. Material laydown will default to the area north of the PEPCO Substation. The fence on the east street can now be moved back to the sidewalk, which will open the street to more traffic. This also creates a situation in which materials can fall into the street. More caution needs to be taken while working on the east side to ensure that no materials or debris are dropped.

General Conditions Estimate – *See Appendix E for detailed takeoff*

---

## OVERVIEW

The general conditions estimate was created utilizing a general project team format for the general contractor and conditions represented by the construction process. The general conditions estimate includes the field personnel on the project team, all temporary utilities utilized on the jobsite, insurance, scheduling, and other contingencies. Reed Construction Data RS Means Online was utilized to estimate the general conditions components.

---

## MAJOR EXPENSES

### **Field Personnel**

The general contractor utilizes a unique project team. This project team consists of two field engineers and three office engineers. There are also numerous levels of superintendents which include area superintendents, project superintendents, and general superintendents. The project also included project engineers, project managers, and executive project managers. Employing such an extensive project team

was necessary due to the complexity and size of the project. This produced a much larger field personnel cost.

Field Personnel: \$ 8,750,000

### **Office Trailers**

A minimal amount of trailers were utilized for the project team. The available area around the building perimeter was very small, and did not allow any room for office trailers. Therefore, trailers were staged on a neighboring parking lot and had minimal space to take advantage of. This produced a lower cost in office trailer use.

Office Trailers: \$ 18,000

### **Temporary Utilities**

The most extensive part of the temporary utilities was the power needed for the entire project and to light the entire building. All 22 floors were being utilized at the same time and needed temporary lighting. The temporary utilities included three tower cranes, one near each corner of the building. Other temporary utilities consist of restrooms, heating for two winters, fences, and waste management.

Temporary Utilities: \$ 1,006,911

### **Commissioning**

Commissioning is a very important part of any complicated project today. Measurement and Verification was a crucial portion of the final schedule and generated a substantial cost towards the general conditions estimate.

Commissioning: \$ 1,250,000

Due to the high general conditions costs, any schedule delays can result in substantially more loss. Just one week of extra work can cost up to \$30,000. Therefore it is inherent that the project schedule is maintained and closely controlled to reflect the completion date.

## Constructability Challenges

### TOP – DOWN EXCAVATION

One of the most difficult phases of the construction process is the excavation and construction of the seven sub-grade levels. The project team determined that the only way to excavate the 100 feet below grade was to utilize a top-down construction method. This method consisted of pouring the top level as a slab-on-grade, with some sections of the slab missing. The level below that slab would then be excavated through the holes that were left. Once the entire level was excavated, a new slab-on-grade was poured. This process was continued for all seven below-grade levels.



Figure 7: Top-Down Excavation

The top-down excavation took an extensive amount of time. The excavation process used small machines and hoists to excavate through the holes, then larger machines were lowered into the ground to help excavate more. The mining of dirt under each slab was a difficult process and was a substantial part of the construction schedule. I look forward to utilizing this phase of the construction process as an in-depth analysis for a future report.

### CONCOURSE CONSTRUCTION / EXCAVATION

As a major hotel within the city center, it was a priority to create a relationship with the neighboring convention center. An underground concourse was designed to connect the below-grade levels of the hotel, levels which consisted of grand ballrooms and junior ballrooms, to the parking deck of the convention center. This concourse created a substantial amount of construction due to the pair of slurry walls and underground utilities that ran between the two sites.

Both the new hotel and the neighboring convention center utilize a slurry wall construction method. Thus, the construction team needs to temporarily brace the slurry walls while demolition part of them to make room for the entrances. Once the openings are created, new slurry wall parts will be formed around new steel columns.



---

## EXISTING BUILDINGS ON-SITE

There are two existing buildings within the site of the new hotel. The larger of the two is a PEPCO Substation that is independent of the construction process and will be closely monitored. There are strict separation requirements for the allowable openings between the PEPCO Substation and the new building. At the shortest interval, the new structure will only be five inches from the PEPCO Substation and will naturally look as if they are one complete building. Certainly, this makes for a very tight and difficult construction area and needs to be carefully monitored to ensure that neither building is damaged.

The smaller building is a Plumber's Union Building, which will be stripped and renovated to be incorporated into the new hotel. The Plumber's Union Building is an eleven story brick building that will be utilized to house roughly seven hotel suites on each floor and a fitness center.



Figure 8: Plumbers Union Building

---

## STATUE LEAD TIME

Another schedule concern is the lead time for the unique sculpture being delivered. The sculpture was designed by Rodney Carroll of Baltimore who is nationally recognized for large-scale sculptures. The piece is a five story high steel sculpture that was reassembled nearby and lifted with a helicopter into the atrium of the hotel. The delivery of the sculpture created a restriction to finishing the atrium skylight. Since it needed to be flown into the hotel the skylight could not be finished, or even substantially started, to allow an opening for the entire sculpture piece. Lead time for the sculpture completion plays a very important role in maintaining the schedule for the rest of the project.




Figure 9: Statue Lift

---

## VERY TIGHT PROJECT SITE

It is also very important to ensure that the surrounding buildings and community are safe from the construction process. The project site is located within a small city center block with major streets being utilized around it. It is important to ensure safety of pedestrian traffic that is around the perimeter of the building. During the finishing phases of the construction process, the East street fence can be moved back to allow more traffic flow. This creates more hazard from falling objects due to the hotel being so close to the street. It is important to ensure that appropriate safety measurements are taken to create a safe working environment.

Leading Industry Practice Evaluation – See Appendix F for LEED Scorecard

---

## LEED EVALUATION

All project stakeholders were motivated to consider pursuing a LEED certification for Sunnyvale Plaza. The project team initially estimated to receive a total of 36 points towards a LEED certification. This will earn a LEED Silver certification. The project team also five other points as possibilities to be later defined. This is typically a strategy to ensure successful completion of the expected number of points. If the extra points are also earned, Sunnyvale Plaza will be LEED Gold certified. The most heavily grossed sections of the LEED point system were Sustainable Sites and Indoor Environmental Quality.

Sustainable sites requirements consisted primarily of alternative transportation. This was very easy to achieve due to the fact that the project site is located within a dense city center. Public transportation was already implemented within the area of the project site. Bicycle storage and changing rooms were also provided within the hotel to allow for non-vehicular transportation to and from the area. The parking garage design implemented a low-emitting, fuel-efficient, vehicle parking area. This rewarded environmentally friendly vehicle users with a more desirable parking space. The parking deck was also designed to provide sufficient parking capacity for the overall hotel capacity. The project team is also projecting to be awarded points for development density within a community. This is due to the project site being located within a dense city instead of being located on the edge of a city, thus creating expansion. The design of the roof for Sunnyvale Plaza is projected to earn several points towards sustainable sites. A vast majority of the roof consists of the atrium skylight, while a smaller portion of the rooftop terrace is covered with garden area. This earns points towards heat island effect for having no roof and a vegetated roof. Stormwater design also played a role in creating sustainable site.

The project team expects to earn four points under the water efficiency category. Water efficient landscaping plays a major role in this category. The landscape watering needs are reduced by at least 50% due to the majority of the landscape being sidewalk. The landscape was also designed to survive without

any artificial irrigation. The design will also reduce the water use by at least 30%, earning another water efficiency point.

Another seven points are expected within the Energy and Atmosphere category. These points are primarily earned through the optimizing energy performance requirement. Five of the seven points are earned by having at least 17.5% of the overall structure consist of an existing building renovation. The other two points are earned by utilizing enhanced commissioning. Measurement and verification of the buildings systems will also be completed towards the end of the construction phase. Green power was considered for Sunnyvale Plaza, and has been listed as a possible point.

The materials and resources category play an important role in the construction process. Several points are earned by monitoring construction waste, recycled content, and regional materials. At least 75% of the construction waste is diverted from standard disposal methods and at least 10% of construction waste is recycled. Construction waste management and recycled content is a difficult component for this specific project due to the small project site. There is very limited spaced surrounding the building perimeter, therefore it is difficult to maintain various dumpsters and recycling containers for all of the materials. Regional content is primarily earned through masonry construction within the hotel.

Indoor environmental quality is a crucial aspect of the hotel design. The primary goal of the hotel manager is to ensure the highest quality experience for every customer that stays at Sunnyvale Plaza. Warranting a high quality indoor environment will benefit in creating a more enjoyable atmosphere and experience for the costumer. Points are earned within the indoor air quality category by monitoring the outdoor air delivery and the thermal comfort of the hotel. The indoor air quality will also be monitored throughout the entire construction process to ensure that no harmful components are released within the building. The project team is also expecting to earn five points within the innovation and design process category, one of which is due to employing a LEED Accredited Professional as a major stakeholder on the project.

I believe that the choices made were fulfilling and efficient for the project. Pursuing other points within each category would have been more costly and disadvantageous. The most necessary factors were pursued to the fullest extent. Features comprising of alternative transportation and water efficiency will be most beneficial to the efficiency of the building and the satisfaction of the customer.

Appendix A:  
Detailed Project Schedule


#	Activity Name	Start	Finish	Original Duration	2013								2014		
					Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q1	Q2	
1	<b>NFB Sunnyvale Plaza</b>	03-Nov-08	28-Apr-14	1407	[Summary Bar]										
2	Design	03-Nov-08	27-Mar-13	1129	[Design Bar]										
3	Procurement	26-Dec-12	16-Aug-13	165	[Procurement Bar]										
4	<b>NFB.Site Preperation (New)</b>	11-Jul-11	31-Oct-13	591	[Site Preperation Summary Bar]										
5	Equipment & Site Utilization	11-Jul-11	31-Oct-13	591	[Equipment & Site Utilization Bar]										
6	<b>NFB.Structure (New WBS)</b>	20-Mar-13	19-Jul-13	86	[Structure Summary Bar]										
7	<b>NFB.Structure.Below Grade Str</b>	25-Mar-13	19-Jul-13	83	[Below Grade Structure Summary Bar]										
8	Level P2	25-Mar-13	26-Jun-13	67	[Level P2 Bar]										
9	Level P1	01-Apr-13	03-Jul-13	67	[Level P1 Bar]										
10	Level M4	05-Apr-13	08-Jul-13	65	[Level M4 Bar]										
11	Level M3	09-Apr-13	10-Jul-13	65	[Level M3 Bar]										
12	Level M2	15-Apr-13	16-Jul-13	65	[Level M2 Bar]										
13	Level M1	18-Apr-13	19-Jul-13	65	[Level M1 Bar]										
14	Level A	22-Apr-13	09-Jul-13	55	[Level A Bar]										
15	Helix	25-Apr-13	06-Jun-13	30	[Helix Bar]										
16	<b>NFB.Structure.Above Grade Str</b>	20-Mar-13	15-Jul-13	82	[Above Grade Structure Summary Bar]										
17	<b>NFB.Structure.Above Grade Str</b>	20-Mar-13	11-Jun-13	59	[Above Grade Structure North Tower Summary Bar]										
18	Level 1-3	20-Mar-13	17-Apr-13	21	[Level 1-3 Bar]										
19	Level 4-6	25-Mar-13	23-Apr-13	22	[Level 4-6 Bar]										
20	Level 7-9	28-Mar-13	25-Apr-13	21	[Level 7-9 Bar]										
21	Level 10-12	02-Apr-13	02-May-13	23	[Level 10-12 Bar]										
22	Level 14-16	09-Apr-13	11-Jun-13	45	[Level 14-16 Bar]										
23	Roof Level	06-May-13	29-May-13	17	[Roof Level Bar]										
24	<b>NFB.Structure.Above Grade Str</b>	17-Apr-13	15-Jul-13	62	[Above Grade Structure South Tower Summary Bar]										
25	Level 10-11	17-Apr-13	07-Jun-13	37	[Level 10-11 Bar]										
26	Level 1-2	25-Apr-13	13-Jun-13	35	[Level 1-2 Bar]										
27	Level 8-9	25-Apr-13	16-May-13	16	[Level 8-9 Bar]										
28	Level 3-4	06-May-13	28-May-13	16	[Level 3-4 Bar]										
29	Level 12-14	10-May-13	26-Jun-13	33	[Level 12-14 Bar]										
30	Level 5-6	17-May-13	10-Jun-13	16	[Level 5-6 Bar]										
31	Level 6-7	28-May-13	18-Jun-13	16	[Level 6-7 Bar]										
32	Level 15-16	31-May-13	11-Jul-13	29	[Level 15-16 Bar]										
33	Roof Level	20-Jun-13	15-Jul-13	17	[Roof Level Bar]										
34	<b>NFB.Building Envelope (N)</b>	22-Feb-13	13-Nov-13	186	[Building Envelope North Summary Bar]										
35	<b>NFB.Building Envelope.Pepco C</b>	01-Apr-13	02-Aug-13	88	[Building Envelope Pepco Drive Summary Bar]										
36	Ext. Frame & Punch Windows	01-Apr-13	28-May-13	41	[Ext. Frame & Punch Windows Bar]										
37	Curtian Wall	25-Apr-13	05-Jul-13	50	[Curtian Wall Bar]										
38	10th St. Roof	01-May-13	14-May-13	10	[10th St. Roof Bar]										
39	Metal Panels	16-May-13	02-Aug-13	55	[Metal Panels Bar]										
40	<b>NFB.Building Envelope.L St. Sid</b>	22-Feb-13	29-Oct-13	175	[Building Envelope L St. Side Summary Bar]										
41	Ext. Frame & Punch Windows	22-Feb-13	23-May-13	65	[Ext. Frame & Punch Windows Bar]										
42	Curtain Wall	25-Apr-13	29-Oct-13	131	[Curtain Wall Bar]										
43	L St. Roof	09-May-13	26-Jun-13	34	[L St. Roof Bar]										
44	Metal Panels	24-May-13	29-Aug-13	68	[Metal Panels Bar]										
45	L St. Canopy	06-Sep-13	03-Oct-13	20	[L St. Canopy Bar]										
46	<b>NFB.Building Envelope.9th St. S</b>	05-Apr-13	29-Oct-13	145	[Building Envelope 9th St. Side Summary Bar]										

█ Actual Level of Effort   
 █ Remaining Work   
 ◆ Milestone   
 █ Critical Remaining Work   
 ▼ summary

Sunnyvale Plaza					Classic Schedule Layout								08-Oct-13 16:17		
#	Activity Name	Start	Finish	Original Duration	2013								2014		
					Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2			
47	Ext. Frame & Punch Windows	05-Apr-13	15-Jul-13	70											
48	Curtain Wall	05-Apr-13	26-Aug-13	100											
49	Metal Panels	05-Jul-13	25-Sep-13	58											
50	9th St. Roof	01-Aug-13	19-Sep-13	35											
51	9th St. Canopy	02-Oct-13	29-Oct-13	20											
52	<b>NFB.Building Envelope.Mass. A</b>	<b>25-Apr-13</b>	<b>12-Nov-13</b>	<b>141</b>											
53	Ext. Frame & Punch Windows	25-Apr-13	12-Nov-13	141											
54	Curtain Wall	25-Apr-13	29-Oct-13	131											
55	Metal Panels	12-Jul-13	09-Oct-13	63											
56	Mass. Ave Canopy	25-Jul-13	05-Sep-13	30											
57	Mass. Ave Roof	09-Aug-13	18-Oct-13	50											
58	<b>NFB.Building Envelope.Pepco E</b>	<b>25-Apr-13</b>	<b>18-Sep-13</b>	<b>102</b>											
59	Exterior Masonry	25-Apr-13	28-May-13	23											
60	Ext. Frame & Punch Windows	25-Apr-13	23-Jul-13	62											
61	Curtain Wall	05-Jun-13	16-Aug-13	52											
62	Metal Panels	24-Jul-13	18-Sep-13	40											
63	<b>NFB.Building Envelope.Atrium S</b>	<b>08-Apr-13</b>	<b>13-Nov-13</b>	<b>155</b>											
64	<b>NFB.Building Envelope.Atrium</b>	<b>11-Apr-13</b>	<b>25-Sep-13</b>	<b>117</b>											
65	Guestroom Walls & GFRG	11-Apr-13	25-Sep-13	117											
66	Curtain Wall	07-May-13	27-Aug-13	79											
67	<b>NFB.Building Envelope.Atrium</b>	<b>08-Apr-13</b>	<b>13-Nov-13</b>	<b>155</b>											
68	Curtain Wall	08-Apr-13	18-Jul-13	72											
69	Guestroom Walls & GFRG	14-May-13	13-Nov-13	129											
70	<b>NFB.Building Envelope.Atrium</b>	<b>08-Apr-13</b>	<b>25-Sep-13</b>	<b>120</b>											
71	Curtain Wall	08-Apr-13	22-Aug-13	97											
72	Guestroom Walls & GFRG	03-May-13	25-Sep-13	101											
73	<b>NFB.Building Envelope.Atrium</b>	<b>01-May-13</b>	<b>09-Oct-13</b>	<b>113</b>											
74	Curtain Wall	01-May-13	09-Jul-13	48											
75	Guestroom Walls & GFRG	09-May-13	09-Oct-13	107											
76	<b>NFB.Building Fit-Out (New</b>	<b>01-Aug-12</b>	<b>12-Mar-14</b>	<b>412</b>											
77	<b>NFB.Building Fit-Out.Below Gra</b>	<b>01-Aug-12</b>	<b>27-Feb-14</b>	<b>403</b>											
78	<b>NFB.Building Fit-Out.Below Gr</b>	<b>14-Jan-13</b>	<b>17-Jun-13</b>	<b>110</b>											
79	HW-P1 Hot Water Riser (L1-M	14-Jan-13	12-Jun-13	107											
80	CH-P1 Chilled Water Riser (L1	14-Jan-13	12-Jun-13	107											
81	Mech Shaft 1 (P2-L1)	21-Jan-13	17-Jun-13	105											
82	Mech Shaft 2 (P1-L1)	21-Jan-13	17-Jun-13	105											
83	Mech Shaft 3 (P1-L2)	21-Jan-13	17-Jun-13	105											
84	Mech Shaft 4 (P2-L1)	21-Jan-13	17-Jun-13	105											
85	<b>NFB.Building Fit-Out.Below Gr</b>	<b>28-Jan-13</b>	<b>19-Feb-14</b>	<b>273</b>											
86	Mechanical, Electrical, Telecom	28-Jan-13	15-Aug-13	142											
87	Perimeter	14-Mar-13	03-Jun-13	57											
88	Back of House	14-Mar-13	19-Feb-14	240											
89	Restrooms	18-Mar-13	11-Nov-13	168											
90	Kitchen, Dining, Laundry	20-Mar-13	14-Oct-13	146											
91	Elevator Lobbies	20-Jun-13	27-Jan-14	154											
92	<b>NFB.Building Fit-Out.Below Gr</b>	<b>27-Aug-12</b>	<b>03-Feb-14</b>	<b>367</b>											
93	Perimeter	27-Aug-12	03-May-13	176											

█ Actual Level of Effort   
 █ Remaining Work   
 █ Critical Remaining Work   
 ◆ Milestone   
 ▼ summary





█ Actual Level of Effort   
 █ Remaining Work   
 █ Critical Remaining Work   
 ◆ Milestone   
 ◆ Milestone   
 ▶ summary

#	Activity Name	Start	Finish	Original Duration	2013								2014			
					Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2				
142	Convention Center	31-May-13	30-Sep-13	85												
143	NFB.Building Fit-Out.Belc	25-Apr-13	15-May-13	15												
144	Relocation	25-Apr-13	15-May-13	15												
145	De-Commissioning	25-Apr-13	08-May-13	10												
146	NFB.Building Fit-Out.Above Gra	29-Jan-13	12-Mar-14	287												
147	Level 5 SIPS	11-Mar-13	08-Oct-13	149												
148	Level 7 SIPS	08-Apr-13	05-Nov-13	149												
149	Level 8 SIPS	22-Apr-13	19-Nov-13	149												
150	Level 6 SIPS	25-Apr-13	22-Oct-13	126												
151	Level 9 SIPS	06-May-13	05-Dec-13	150												
152	Level 10 SIPS	20-May-13	19-Dec-13	150												
153	Level 11 SIPS	04-Jun-13	06-Jan-14	151												
154	Level 12 SIPS	18-Jun-13	16-Jan-14	149												
155	Level 14 SIPS	02-Jul-13	23-Jan-14	144												
156	Level 15 SIPS	17-Jul-13	30-Jan-14	139												
157	NFB.Building Fit-Out.Above Gr	25-Apr-13	20-Aug-13	82												
158	HW-P1 Hot Water Riser (L2-Ro	25-Apr-13	06-Aug-13	72												
159	CH-P1 Chilled Water Riser (L2	25-Apr-13	06-Aug-13	72												
160	Mech Shaft 1A (L2-Roof)	25-Apr-13	20-Aug-13	82												
161	Mech Shaft 2 (L2-L3)	25-Apr-13	01-May-13	5												
162	Mech Shaft 3 (LA-L11)	25-Apr-13	17-Jul-13	58												
163	NFB.Building Fit-Out.Above Gr	18-Feb-13	28-Feb-14	265												
164	East Lobby & Restrooms	18-Feb-13	26-Feb-14	263												
165	Sports Grille	20-Feb-13	21-Jan-14	235												
166	3 Meal Restaurant	21-Feb-13	11-Feb-14	249												
167	Retail & Loading Dock	22-Feb-13	21-Oct-13	169												
168	Registration	11-Mar-13	31-Jan-14	230												
169	Specialty Restaurant	25-Apr-13	14-Jan-14	184												
170	Service Area	25-Apr-13	10-Jan-14	182												
171	Fire Alarm Control Room	19-Jul-13	26-Sep-13	49												
172	NFB.Building Fit-Out.Above	25-Apr-13	28-Feb-14	217												
173	Sculpture	25-Apr-13	14-Nov-13	143												
174	Atrium	27-Aug-13	28-Feb-14	131												
175	NFB.Building Fit-Out.Above Gr	11-Apr-13	27-Jan-14	203												
176	SIPS	11-Apr-13	26-Aug-13	96												
177	Area A - Meet. Rooms / Banq. S	25-Apr-13	21-Nov-13	148												
178	Event Terrace / Monumental St	25-Apr-13	27-Jan-14	193												
179	Area B - Meet. Rooms / Hosp. S	09-May-13	06-Dec-13	148												
180	Area B / C - SE Corner	23-May-13	26-Dec-13	151												
181	NFB.Building Fit-Out.Above Gr	21-Mar-13	10-Sep-13	121												
182	SIPS	21-Mar-13	10-Sep-13	121												
183	MEP Closets	25-Apr-13	03-Jul-13	49												
184	NFB.Building Fit-Out.Above Gr	18-Mar-13	24-Sep-13	134												
185	SIPS	18-Mar-13	24-Sep-13	134												
186	MEP Closets	13-May-13	21-Jun-13	29												
187	NFB.Building Fit-Out.Above Gr	17-May-13	12-Sep-13	82												
188	North Penthouse	17-May-13	21-Aug-13	67												
189	South Penthouse	10-Jul-13	12-Sep-13	46												


█ Actual Level of Effort   
 █ Remaining Work   
 █ Critical Remaining Work   
 ◆ Milestone   
 ◆ summary



Sunnyvale Plaza					Classic Schedule Layout								08-Oct-13 16:17			
#	Activity Name	Start	Finish	Original Duration	2013								2014			
					Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2				
190	<b>NFB.Building Fit-Out.Above Gr</b>	29-Jan-13	12-Mar-14	287												
191	PUB Demo and Core & Shell (T	29-Jan-13	02-Jan-14	238												
192	PUB Fit-Out (Top-Down)	30-Apr-13	12-Mar-14	222												
193	General Building	03-Jan-14*	23-Jan-14	15												
194	<b>NFB.Building Fit-Out.Site Work</b>	24-Jun-13	12-Feb-14	164												
195	Massachusetts Ave. Improvements	24-Jun-13	12-Feb-14	164												
196	L St. Improvements	19-Sep-13	21-Jan-14	87												
197	9th Ave. Improvements	20-Sep-13	10-Jan-14	79												
198	10th St. Improvements	13-Dec-13	22-Jan-14	28												
199	<b>NFB.Commissioning (New</b>	25-Apr-13	28-Apr-14	258												
200	Commissioning	25-Apr-13	28-Mar-14	237												
201	Substantial Completion	28-Mar-14*	28-Mar-14	1												
202	Hotel Open	28-Apr-14	28-Apr-14	1												

█ Actual Level of Effort    █ Remaining Work    ◆ Milestone  
█ Actual Work    █ Critical Remaining Work    ▶ summary





<b>SIPS Area Phasing</b>	
Sunnyvale Plaza	
Mid-Atlantic Region	Tech #2
Nathan Braskey	10/16/13

Appendix B:  
Detailed Structural Estimate























Nathan Braskey

Withheld  
Withheld, Withheld  
Date: 01-Oct-13

Structural Estimate  
Year 2013 Quarter 3  
Unit Detail Report

Prepared By:  
Nathan Braskey  
Penn State University

LineNumber			Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
<b>Division 03 Concrete</b>							
032105750100			Splice rebar, standard, self-aligning type, taper threaded, #4 bars	30,000.00	Ea.	\$17.11	\$513,300.00
032105750305			Splice rebar, standard, self-aligning type, taper threaded, #9 bars	30,000.00	Ea.	\$67.64	\$2,029,200.00
033053401400			Structural concrete, in place, column (4000 psi), round, less than 2% reinforcing, 24" diameter, includes forms(4 uses), Grade 60 rebar, concrete (Portland cement Type I), placing and finishing	60.00	C.Y.	\$613.24	\$36,794.40
033053401900			Structural concrete, in place, elevated slab (4000 psi), flat slab with drop panels, 125 psf superimposed load, 20' span, includes forms(4 uses), Grade 60 rebar, concrete (Portland cement Type I), placing and finishing	13,000.00	C.Y.	\$698.68	\$9,082,840.00
033105350300			Structural concrete, ready mix, normal weight, 4000 psi, includes local aggregate, sand, Portland cement (Type I) and water, delivered, excludes all additives and treatments	64,000.00	C.Y.	\$137.31	\$8,787,840.00
033105350400			Structural concrete, ready mix, regular weight, 5000 psi, includes local aggregate, sand, Portland cement (Type I) and water, delivered, excludes all additives and treatments	13,000.00	C.Y.	\$145.89	\$1,896,570.00
033105350411			Structural concrete, ready mix, normal weight, 6000 PSI, includes local aggregate, sand, Portland cement (Type I) and water, delivered, excludes all additives and treatments	22,000.00	C.Y.	\$165.51	\$3,641,220.00
033105350412			Structural concrete, ready mix, normal weight, 8000 PSI, includes local aggregate, sand, Portland cement (Type I) and water, delivered, excludes all additives and treatments	18,000.00	C.Y.	\$270.95	\$4,877,100.00
033105350412			Structural concrete, ready mix, normal weight, 8000 PSI, includes local aggregate, sand, Portland cement (Type I) and water, delivered, excludes all additives and treatments	10,000.00	C.Y.	\$270.95	\$2,709,500.00
034105101400			Precast beam, rectangular, 30' span, 12" x 36", includes material only	300.00	Ea.	\$5,662.79	\$1,698,837.00
034105101450			Precast beam, rectangular, 30' span, 18" x 44", includes material only	150.00	Ea.	\$6,798.52	\$1,019,778.00
034105101500			Precast beam, rectangular, 30' span, 24" x 52", includes material only	100.00	Ea.	\$8,225.37	\$822,537.00
<b>Division 03 Concrete Subtotal</b>							<b>\$37,115,516.40</b>

LineNumber			T	Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
<b>Division 05 Metals</b>								
051223177350				Column, structural, 2-tier, W14x74, A992 steel, incl shop primer, splice plates, bolts	1,280.00	L.F.	\$128.16	\$164,044.80
051223177400				Column, structural, 2-tier, W14x120, A992 steel, incl shop primer, splice plates, bolts	3,433.00	L.F.	\$204.62	\$702,460.46
051223177450				Column, structural, 2-tier, W14x176, A992 steel, incl shop primer, splice plates, bolts	2,234.00	L.F.	\$296.95	\$663,386.30
051223700200				Stressed skin steel roof & ceiling system, structural, double panel arched roof, spans to 300'	32,000.00	S.F.	\$38.78	\$1,240,960.00
052123508000				Trusses, WT chords, 40-ton job lots, shop fabricated, incl shop primer	0.00	Ton	\$6,966.55	\$0.00
053113505200				Metal floor decking, steel, non-cellular, composite, galvanized, 2" D, 22 gauge	1,900,000.00	S.F.	\$2.98	\$5,662,000.00
<b>Division 05 Metals Subtotal</b>								<b>\$8,432,851.56</b>
<b>Division 1B</b>								
1B				Precast beam, rectangular, 30' span, 36x50	10.00	Ea.	\$8,600.00	\$86,000.00
<b>Division 1B Subtotal</b>								<b>\$86,000.00</b>
<b>Division 1S</b>								
1S				Structural Steel Column - W14x193, W14x211, W14x233, W14x257, W14x283	3,053.00	L.F.	\$308.00	\$940,324.00
<b>Division 1S Subtotal</b>								<b>\$940,324.00</b>
<b>Division 2B</b>								
2B				Precast beam, rectangular, 30' span, 48x48	5.00	Ea.	\$8,870.00	\$44,350.00
<b>Division 2B Subtotal</b>								<b>\$44,350.00</b>
<b>Division 2S</b>								
2S				Structural Steel Columns - W14x311, W14x342, W14x370, W14x398	633.00	L.F.	\$310.00	\$196,230.00
<b>Division 2S Subtotal</b>								<b>\$196,230.00</b>
<b>Division 3B</b>								
3B				Precast beam, rectangular, 30' span, 50x66	2.00	Ea.	\$9,250.00	\$18,500.00
<b>Division 3B Subtotal</b>								<b>\$18,500.00</b>
<b>Division 3S</b>								
3S				Structural Steel Columns - W14x665	159.00	L.F.	\$310.00	\$49,290.00
<b>Division 3S Subtotal</b>								<b>\$49,290.00</b>

Steel Column Takeoff

Location	W14x109	W14x120	W14x132	W14x145	W14x159	W14x176	W14x193	W14x211	W14x233	W14x257	W14x283	W14x311	W14x342	W14x90	W14x99	Grand Total
B.1-10.7	58		25													83
B.9-1.4	58	25														83
B.9-10			58		25											83
B.9-2			58	25												83
B.9-3			58	25												83
B.9-4						58		25								83
B.9-5						58		25								83
B.9-6						58		25								83
B.9-7						58		25								83
B.9-8						58		25								83
B.9-9					58	25										83
B-1.5	25													58		83
B-10									25							25
B-2				58	25											83
B-3				58	25											83
B-4				58	25											83
B-5				58	25											83
B-6				58	25											83
B-7				58	25											83
B-8				58	25											83
B-9									58							58
C.4-10.2							58		25							83
C.5-8.8										58	25					83
C.7-1.4		57		35												92
C.7-1.9		57	35													92
C.7-5				57		25										82
C.7-6							55		25							80
C.7-7					57		25									82
C.7-8						57	25									82
C-11						58	25									83
D.3-1.4		59.5		35												94.5
D.3-7				57		25										82
D.3-8						57		25								82
D.5-10.2								57		25						82
D.5-8.9										57	25					82
D-11						56		25								81
E-11						57		25								82
F-11							57	25								82
G.5-11	25													52		77
G-11							60		25							85
H.2-10.1					55.5		35									90.5
H.2-11			52		25											77
MA-M10												49	25			74
MA-M11								49	25							74
MA-M12								49	25							74
MA-M13						49	25									74
MA-M9.1												49	25			74
MF-M18	34														58.5	92.5
MG.8-M16.7														90.5		90.5
MG.8-M8.2														90.5		90.5
MG-M18	34														58.5	92.5
<b>Grand Total</b>	<b>234</b>	<b>198.5</b>	<b>286</b>	<b>640</b>	<b>444.5</b>	<b>675</b>	<b>340</b>	<b>380</b>	<b>208</b>	<b>140</b>	<b>50</b>	<b>98</b>	<b>50</b>	<b>291</b>	<b>117</b>	<b>4152</b>

Steel Column Takeoff

Location	W14x109	W14x120	W14x132	W14x145	W14x159	W14x176	W14x193	W14x211	W14x233	W14x257	W14x283	W14x342	W14x370	W14x90	W14x99	Grand Total
MA-M14							49	25								74
MA-M15								49		25						74
MA-M15.9												49	25			74
MA-M8.3														84.5		84.5
MB-M10														28		28
MB-M11														28		28
MB-M12.1	15													43.5		58.5
MB-M12.9														43		43
MB-M14														12.5		12.5
MB-M15														12.5		12.5
MB-M15.9		43														43
MB-M16.6						60			25							85
MB-M8.3			94.5													94.5
MB-M9.1		58.5														58.5
MC-M10														29		29
MC-M11														29		29
MC-M12.1														28.5	30	58.5
MC-M12.9														52.5		52.5
MC-M14														22		22
MC-M15														22		22
MC-M15.9		52.5														52.5
MC-M16.6					57.5		35									92.5
MC-M8.3						65.5			35							100.5
MC-M9.1		59.5														59.5
MD-M10														29		29
MD-M11														29		29
MD-M12.1														29.5	30	59.5
MD-M12.9														52.5		52.5
MD-M14														22		22
MD-M15														22		22
MD-M15.9		52.5														52.5
MD-M16.6						58.5			34							92.5
MD-M8.3				55.5			35									90.5
MD-M9.1		59.5														59.5
ME-M10														22		22
ME-M11														22		22
ME-M12.1														52.5		52.5
ME-M12.9														52.5		52.5
ME-M14														22		22
ME-M15														22		22
ME-M16.6									51.5		34					85.5
ME-M8.3							84.5									84.5
ME-M9.1		52.5														52.5
ME-ME15.9		52.5														52.5
MF-M17.5			58.5			34										92.5
<b>Grand Total</b>	<b>15</b>	<b>430.5</b>	<b>153</b>	<b>55.5</b>	<b>57.5</b>	<b>218</b>	<b>203.5</b>	<b>74</b>	<b>145.5</b>	<b>25</b>	<b>34</b>	<b>49</b>	<b>25</b>	<b>812</b>	<b>60</b>	<b>2357.5</b>

Steel Column Takeoff

Location	W14x109	W14x120	W14x132	W14x145	W14x159	W14x176	W14x193	W14x211	W14x233	W14x257	W14x283	W14x311	W14x342	W14x398	W14x665	Grand Total
MF-M7					95											95
MF-M7.8	61		34													95
MG-M10												79.5				79.5
MG-M11													34	46		80
MG-M12											46		34			80
MG-M13											47	34				81
MG-M14													34	47		81
MG-M15											46	34				80
MG-M15.9															79.5	79.5
MG-M16.6							45.5	34								79.5
MG-M17.5		56.5		34												90.5
MG-M7								58	34							92
MG-M7.8		59		34												93
MG-M8.3									77							77
MG-M9.1															79.5	79.5
MH-M10				56.5			34									90.5
MH-M11									35		75.5					110.5
MH-M12				56.5			34									90.5
MH-M13				56.5			34									90.5
MH-M14									35		75.5					110.5
MH-M15				57.5			34									91.5
MH-M16									56.5		34					90.5
MH-M17.3					56.5			34								90.5
MH-M18			57.5	34												91.5
MH-M7.6						58	34									92
MH-M9								62		34						96
MJ-M10						51					34					85
MJ-M11						50				34						84
MJ-M12						50				34						84
MJ-M13						50					34					84
MJ-M14						50				34						84
MJ-M15						50					34					84
MJ-M16									51				34			85
MJ-M17.3					56.5					34						90.5
MJ-M18			56.5			34										90.5
MJ-M7.6						58				34						92
MJ-M9								55.5				34				89.5
RE-R3						57		25								82
RE-R4					57		25									82
RG-R4						49		25								74
<b>Grand Total</b>	<b>61</b>	<b>115.5</b>	<b>148</b>	<b>329</b>	<b>265</b>	<b>557</b>	<b>240.5</b>	<b>293.5</b>	<b>288.5</b>	<b>204</b>	<b>426</b>	<b>181.5</b>	<b>136</b>	<b>93</b>	<b>159</b>	<b>3497.5</b>



Row Labels	12	14	16	18	30	14	18	81	24	24	42	20	18	32	46	24	30	36	40	46	51	36	48	Grand Total	
01B01											70													70	
01B02											70														70
01B03																					102				102
01B04																					102				102
01B05																	67								67
01B06															98										98
01B07																					102				102
01B08																									53
01B09																									53
01B10																									53
01B11																									53
01B12																									53
01B13																									53
01B14																									53
01B15																									40
01B16											40														40
01B17											40														40
01B18																									67
01B19																									53
01B20																									53
01B21																									53
01B22																									67
01B23																									113
01B24																									113
01B25																									53
01B26																									105
01B27																									105
01B28																									213
01B29																									213
01B30																									213
01B31																									100
02B1																									89
02B10																									20
02B11																									36
02B12																									36
02B13																									36
02B14																									36
02B15																									36
02B16																									36
02B17																									80
02B18																									16
02B19																									20
02B2																									18
02B20																									23
02B21																									23
02B22																									36
02B23																									20
02B24																									18
02B25																									18
02B26																									20
02B27																									18
02B28																									16
02B29																									16
02B3																									16
02B30																									16
02B31																									16
02B32																									20
02B33																									59
02B34																									59
02B35																									33
02B36																									33
02B37																									16
02B38																									33
02B39																									13
<b>Grand Total</b>	<b>13</b>	<b>109</b>	<b>107</b>	<b>100</b>	<b>67</b>	<b>47</b>	<b>210</b>	<b>249</b>	<b>80</b>	<b>140</b>	<b>33</b>	<b>119</b>	<b>98</b>	<b>587</b>	<b>200</b>	<b>80</b>	<b>89</b>	<b>307</b>	<b>227</b>	<b>100</b>	<b>640</b>	<b>3600</b>			

Concrete Beam Takeoff

Row Labels	12	16	18	20	24	30	14	24	16	24	18	24	20	24	Grand Total
	14	16	18	20	24	30	18	24	18	24	18	24	24	24	
02B4		18													18
02B40					27										27
02B41		18													18
02B42					27										27
02B43			20												20
02B44													44		44
02B45													44		44
02B46													44		44
02B5														53	53
02B50									36						36
02B51									36						36
02B52									36						36
02B53									36						36
02B54					27										27
02B55					27										27
02B56									31						31
02B57									31						31
02B58			20												20
02B59			20												20
02B6			20												20
02B7									31						31
02B8													44		44
02B9					27										27
03B1											30				30
03B10		18													18
03B11		18													18
03B12		18													18
03B13		18													18
03B14		18													18
03B16			20												20
03B17							23								23
03B18					27										27
03B19	16														16
03B2											30				30
03B20			20												20
03B21					27										27
03B3											30				30
03B4											30				30
03B5		18													18
03B6								27							27
03B7			20												20
03B8									31						31
03B9		18													18
04B1						33									33
09B1			20												20
10B1			20												20
10B2		18													18
10B3												40			40
10B4												40			40
10B5							23								23
11B1			20												20
11B2			20												20
11B3			20												20
11B4			20												20
12B1			20												20
12B2		18													18
14B1		18													18
14B2		18													18
14B3		18													18
14B4		18													18
14B5		18													18
14B7					22										22
14B8					22										22
15B1		18													18
<b>Grand Total</b>	<b>16</b>	<b>302</b>	<b>280</b>	<b>44</b>	<b>187</b>	<b>33</b>	<b>47</b>	<b>124</b>	<b>27</b>	<b>142</b>	<b>120</b>	<b>80</b>	<b>178</b>	<b>53</b>	<b>1633</b>

Row Labels	8	12						14					16		18		21		24		36		Grand Total		
	16	14	16	18	21	30	37	47	12	18	24	30	47	63	63	40	45	47	18	24	25	37		47	24
15B2			18																						18
15B3			18																						18
15B4			18																						18
15B5			18																						18
15B6			18																						18
16B10													61												61
16B11												61													61
16B12												61													61
16B13												61													61
16B17											31														31
16B18			18																						18
16B19					23																				23
16B2			18																						18
16B20																					56				56
16B21											31														31
16B22			18																						18
16B23																							104		104
16B24																		91							91
16B25													82												82
16B25A												82													82
16B26												82													82
16B27												82													82
16B27A												82													82
16B28														93											93
16B29													82												82
16B3			18																						18
16B30													82												82
16B31												82													82
16B32							41																		41
16B33							41																		41
16B34							41																		41
16B35								52																	52
16B36								52																	52
16B37																		91							91
16B38										23															23
16B39			16																						16
16B40					23																				23
16B41				20																					20
16B42	12																								12
16B43									16																16
16B44																									40
16B45											39														39
16B46																									67
16B5			16														67								16
16B6				20																					20
16B7					23																				23
16B9												61													61
MB1						33																			33
MB2						33																			33
MB3						33																			33
MB4						33																			33
PHB1																								80	80
PHB12											31														31
PHB13											31														31
PHB14											31														31
PHB2																								80	80
PHB22																		75							75
PHB23																							53		53
PHB24																							53		53
PHB25																							53		53
PHB26																							53		53
PHB27																								82	82
PHB3																								80	80
PHB31																								53	53
<b>Grand Total</b>	<b>12</b>	<b>31</b>	<b>160</b>	<b>40</b>	<b>70</b>	<b>133</b>	<b>123</b>	<b>104</b>	<b>16</b>	<b>23</b>	<b>156</b>	<b>39</b>	<b>305</b>	<b>653</b>	<b>93</b>	<b>67</b>	<b>75</b>	<b>183</b>	<b>40</b>	<b>267</b>	<b>56</b>	<b>82</b>	<b>104</b>	<b>240</b>	<b>3072</b>

Concrete Beam Takeoff

Row Labels	8	12							18		20	24			36		50	Grand Total			
	24	14	16	18	24	42	79	83	97	24	45	24	24	37	45	53	60	72	66		
PHB32											75									75	
PHB33											75										75
PHB34											75										75
PHB35											75										75
PHB36											75										75
PHB37											75										75
PHB38															53						53
PHB40					27																27
PHB42												44									44
PHB43						47															47
PHB44														82							82
PHB45							88														88
PHB46						47															47
PHB49															100						100
PHB50																118					118
PHB51			18																		18
PHB52					27																27
PHB53		16																			16
PHB54				20																	20
PHB55									108												108
PHB56								92													92
TB1				20																	20
TB10			18																		18
TB11				20																	20
TB12				20																	20
TB13				20																	20
TB14				20																	20
TB15				20																	20
TB16				20																	20
TB17				20																	20
TB18	18																				18
TB19		16																			16
TB2				20																	20
TB20				20																	20
TB21		16																			16
TB22		16																			16
TB23			18																		18
TB24			18																		18
TB25		16																			16
TB26		16																			16
TB27				20																	20
TB28		16																			16
TB29				20																	20
TB3				20																	20
TB30		16																			16
TB31		16																			16
TB32		16																			16
TB33				20																	20
TB34				20																	20
TB35				20																	20
TB36				20																	20
TB37									40												40
TB38		16																			16
TB4		16																			16
TB5		16																			16
TB6		16																			16
TB7		16																			16
TB8		16																			16
TB9			18																		18
TG101																				306	306
TG102																		240			240
TG104																	200				200
TG105																			306		306
TG106																		240			240
<b>Grand Total</b>	<b>18</b>	<b>249</b>	<b>89</b>	<b>360</b>	<b>53</b>	<b>93</b>	<b>88</b>	<b>92</b>	<b>108</b>	<b>40</b>	<b>450</b>	<b>44</b>	<b>53</b>	<b>82</b>	<b>100</b>	<b>118</b>	<b>200</b>	<b>480</b>	<b>611</b>	<b>3329</b>	

Concrete Column Takeoff

Row Labels	16	18	20	20	28	28	30	30	44	Grand Total
	16	18	20	18	28	20	30	28	40	
1-RA		41								41
1-RB		41								41
B.1-10.8					220					220
B.1-11.9					220					220
B.9-1					254			26		280
B.9-1.4					289					289
B.9-10					289					289
B.9-10.7	8									8
B.9-2					289					289
B.9-3					289					289
B.9-4					289					289
B.9-5					289					289
B.9-6					289					289
B.9-7					289					289
B.9-8					289					289
B.9-9					289					289
B-1				22	225			26		273
B-1.5				22	237					259
B-10				22	237					259
B-2				22	237					259
B-3				22	237					259
B-4				22	237					259
B-5				22	237					259
B-6				22	237					259
B-7				22	237					259
B-8				22	237					259
B-9				22	237					259
C.7-1					271					271
C.7-1.4					289					289
C.7-2 / C.7-1.9					289					289
C.7-3					271					271
C.7-4					271					271
C.7-5					289					289
C.7-6					289					289
C.7-7					289					289
C.7-8					289					289
C-11						271				271
C-12			174							174
D.3-1					271					271
D.3-1.4					289					289
D.3-2					289					289
D.3-3					289					289
D.3-4					289					289
D.3-5					289					289
D.3-6					289					289
D.3-7					289					289
D.3-8					52	237				289
D-11						271				271
D-12			174							174
E-11			152			35				187
E-12			22			237				259
F-11			152			35				187
F-12			22			237				259
G-11			152			35				187
G-12			22			237				259
H.2-10.1						271				271
H-11						271				271
H-12			174							174
J-11						35	355			390
J-12						220			54	274
<b>Grand Total</b>	<b>8</b>	<b>82</b>	<b>1047</b>	<b>244</b>	<b>11062</b>	<b>2390</b>	<b>355</b>	<b>52</b>	<b>54</b>	<b>15294</b>

Concrete Column Takeoff

Row Labels	20	18	20	28	28	20	Grand Total
J-9.9						271	271
M10-MF				289			289
M10-MG	9			271			280
M10-MG.7				35			35
M10-MH				237			237
M10-MJ				220			220
M11-MF				289			289
M11-MG	9			271			280
M11-MG.7				17			17
M11-MH				220			220
M11-MJ				220			220
M12-MF				289			289
M12-MG	9			271			280
M12-MG.7				17			17
M12-MH				220			220
M12-MJ				220			220
M13-MF				289			289
M13-MG	9			271			280
M13-MG.7				17			17
M13-MH				220			220
M13-MJ				220			220
M14-MF				289			289
M14-MG	9			271			280
M14-MG.7				17			17
M14-MH				220			220
M14-MJ				220			220
M15-MF				289			289
M15-MG	9			271			280
M15-MG.7				17			17
M15-MH				237			237
M15-MJ				220			220
M16.7-MF				289			289
M16.7-MG	9			271			280
M16-MF				289			289
M16-MG	9			271			280
M16-MG.7				35			35
M16-MH				237			237
M16-MJ				220			220
M17.5-MF		174		17			192
M17.5-MG	9			271			280
M17-MG.7				237			237
M17-MH				237			237
M17-MJ				185			185
M18-MF		174					174
M18-MG				271			271
M18-MG.7				237			237
M18-MH				237			237
M18-MJ				185			185
M19-MF		56					56
M19-MG				271			271
M19-MG.7				52			52
M19-MH				237			237
M19-MJ				185			185
M3-E.9				237			237
M3-MJ				220			220
M4-E.9				237			237
M4-MH				237			237
M4-MJ				220			220
M5-MG.3			169				169
M5-MH				237			237
<b>Grand Total</b>	<b>78</b>	<b>404</b>	<b>169</b>	<b>11769</b>		<b>271</b>	<b>12691</b>

Concrete Column Takeoff

Row Labels	12	25	16	18	20	18	28	36	48	28	Grand Total
	12	25	16	18	14	18	28	36	48	20	
M5-MJ							220				220
M6-MF						174					174
M6-MG							271				271
M6-MH							237				237
M6-MJ							220				220
M7.1-E.8				41							41
M7.3-MF						174					174
M7.3-MG							271				271
M7.6-MH									121		121
M7.6-MJ							71				71
M7.8-E.8				41							41
M7.8-ME				41							41
M7.8-MF								91			91
M7-MF						174					174
M7-MG							271				271
M7-MG.7							237				237
M7-MH							237				237
M7-MJ							220				220
M8.2-MF							289				289
M8.2-MG							289				289
M8-MG.7							237				237
M8-MH							237				237
M9-MF							289				289
M9-MG					9		271				280
M9-MG.7							35				35
M9-MH							237				237
M9-MJ							220				220
ME-9.9			92								92
R.4-9.9			8								8
R1-ME										271	271
R1-RA		9								271	281
R1-RB		9								271	281
R1-RC		9								271	281
R1-RD		9								271	281
R2-ME										271	271
R2-RA										271	271
R2-RB										271	271
R2-RC										271	271
R2-RD										271	271
R3-ME										271	271
R3-RE										271	271
R3-RG										271	271
R3-RJ										271	271
R3-RL										271	271
R3-RN										271	271
R4-ME		9								271	281
R4-RE		9								271	281
R4-RF		9									9
R4-RG		9					237			35	281
R4-RH		9									9
R4-RJ		9					237			35	281
R4-RK		9									9
R4-RL		9					237			35	281
R4-RM		9									9
R4-RN		9								271	281
R4-RP		9								271	281
RP.3-9.9			8								8
S12LP	18										18
<b>Grand Total</b>	<b>18</b>	<b>139</b>	<b>108</b>	<b>123</b>	<b>9</b>	<b>523</b>	<b>5066</b>	<b>91</b>	<b>121</b>	<b>5531</b>	<b>11730</b>

Concrete Column Encasement Takeoff

Row Labels	23	24		26	Grand Total
	23	24	28	26	
B.1-10.7			149		149
B.9-1.4			149		149
B.9-10			149		149
B.9-2			149		149
B.9-3			149		149
B.9-4			149		149
B.9-5			149		149
B.9-6			149		149
B.9-7			149		149
B.9-8			149		149
B.9-9			149		149
B-1.5	118				118
B-10			149		149
B-2			149		149
B-3			149		149
B-4			149		149
B-5			149		149
B-6			149		149
B-7			149		149
B-8			149		149
B-9			149		149
C.4-10.2				150	150
C.5-8.8				150	150
C.7-1.4			174		174
C-.7-1.9			174		174
C.7-5			149		149
C.7-6			149		149
C.7-7			149		149
C.7-8			149		149
C-11			149		149
D.3-1.4			174		174
D.3-7			149		149
D.3-8			149		149
D.5-10.2				150	150
D.5-8.9				150	150
D-11			149		149
E-11			149		149
F-11			149		149
G.5-11		128			128
G-11			149		149
H.2-10.1			174		174
<b>Grand Total</b>	<b>118</b>	<b>128</b>	<b>5326</b>	<b>601</b>	<b>6173</b>



Concrete Column Encasement Takeoff

Row Labels	24	28	26	28	Grand Total
H.2-11	128				128
MA-M10				145	145
MA-M11				145	145
MA-M12				145	145
MA-M13				145	145
MA-M14				145	145
MA-M15				145	145
MA-M15.9				145	145
MA-M8.3				174	174
MA-M9.1				145	145
MB-M10	21				21
MB-M11	21				21
MB-M12.1	64				64
MB-M12.9	64				64
MB-M14	21				21
MB-M15	21				21
MB-M15.9	64				64
MB-M16.6			150		150
MB-M8.3	149				149
MB-M9.1	64				64
MC-M10	43				43
MC-M11	43				43
MC-M12.1	85				85
MC-M12.9	85				85
MC-M14	43				43
MC-M15	43				43
MC-M15.9	85				85
MC-M16.6			175		175
MC-M8.3			175		175
MC-M9.1	85				85
MD-M10	43				43
MD-M11	43				43
MD-M12.1	85				85
MD-M12.9	85				85
MD-M14	43				43
MD-M15	43				43
MD-M8.3			175		175
MD-M9.1	85				85
RE-R3		149			149
RE-R4		149			149
RG-R4				174	174
<b>Grand Total</b>	<b>1557</b>	<b>299</b>	<b>676</b>	<b>1510</b>	<b>4042</b>

Slurry Wall Steel Deck Takeoff

Slurry Wall Volume		
<b>Perimeter</b>	167	Feet
<b>Perimeter</b>	1667	Feet
<b>Total Perimeter</b>	1833	Feet
<b>Width</b>	8	Feet
<b>Area</b>	13750	Sq. Ft.
<b>Depth</b>	124	Feet
<b>Volume</b>	1705000	Feet
	63148	Yards

Steel Deck Area	
Level	Area
P2	95000
P1	95000
M4	95000
M3	95000
M2	95000
M1	95000
A	95000
1	83,000
2	75000
3	75000
4	75000
5	75000
6	75000
7	75000
8	75000
9	75000
10	75000
11	75000
12	75000
13	75000
14	75000
15	75000
16	75000
<b>Total:</b>	1873000
Cubic Feet	312166.6667
Cubic Yards	11561.73

Appendix C:  
Assemblies MEP Estimate

**Assemblies MEP Estimate**  
**Year 2013 Quarter 3**  
**Assembly Detail Report**

**Prepared By:**  
**John Smith**  
**PSU**

Assembly Number		Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
<b>A Substructure</b>						
A1000000000		Strip footings	8.00	S.F.	\$0.00	\$0.00
<b>A Substructure Subtotal</b>						<b>\$0.00</b>
<b>D Services</b>						
D20202502260		Gas fired water heater, commercial, 100< F rise, 600 MBH input, 576 GPH	30.00	Ea.	\$28,350.00	\$850,500.00
D20402102040		Roof drain, DWV PVC, 4" diam, diam, 10' high	14.00	Ea.	\$1,325.00	\$18,550.00
D20402102080		Roof drain, DWV PVC, 4" diam, for each additional foot add	215.00	Ea.	\$34.65	\$7,449.75
D20908101400		Copper tubing, hard temper, solder, type K, 4" diameter	66,140.00	L.F.	\$164.00	\$10,846,960.00
D30105101880		Apartment building heating system, fin tube radiation, forced hot water, 30,000 SF area,300,000 CF vol	752,000.00	S.F.	\$8.07	\$6,068,640.00
D30106842560		Solar passive heating, direct gain, 2'-6" x 5', double glazed window, one panel wide	3,200.00	Ea.	\$1,110.00	\$3,552,000.00
D30201041560		Large heating systems, electric boilers, hydronic, 223,300 SF, 3,600 KW, 12,283 MBH, 14 floors	752,000.00	S.F.	\$8.36	\$6,286,720.00
D30301154400		Packaged chiller, water cooled, with fan coil unit, schools and colleges, 4,000 SF, 15.33 ton	752,000.00	S.F.	\$20.90	\$15,716,800.00
D30501704000		Splt sys, air cooled condensing unit, schools and colleges, 1,000 SF, 3.83 ton	752,000.00	S.F.	\$9.62	\$7,234,240.00
D50102400560		Switchgear installation, incl switchboard, panels & circuit breaker, 277/480 V, 1000 A	9.00	Ea.	\$30,475.00	\$274,275.00
D50102400620		Switchgear installation, incl switchboard, panels & circuit breaker, 277/480 V, 2000 A	2.00	Ea.	\$51,975.00	\$103,950.00
D50102503020		Panelboard, 4 wire w/conductor & conduit, NQOD, 120/208 V, 400 A, 10 stories, 75' horizontal	2.20		\$32,700.00	\$71,940.00
D50201150200		Receptacle systems, underfloor duct, 5' on center, low density	752,000.00	S.F.	\$10.07	\$7,572,640.00
D50202080640		Fluorescent fixtures, type A, 23 fixtures per 1600 SF	752,000.00	S.F.	\$7.53	\$5,662,560.00
<b>D Services Subtotal</b>						<b>\$64,267,224.75</b>
<b>F Special Construction</b>						
F10405100100		Special construction, tanks, steel, ground level, 100,000 gal	23.00	Ea.	\$226,500.00	\$5,209,500.00
<b>F Special Construction Subtotal</b>						<b>\$5,209,500.00</b>

Plumbing Assemblies Takeoff

Level	Restrooms	Water Closets	Sinks	Showers	Drains	Urinals
P2	1	1	1	-	1	-
P1	8	53	35	1	16	10
M4	3	22	15	1	8	4
M3	6	49	32	1	18	10
M2	5	24	16	1	10	4
M1	2	10	8	9	4	2
A	7	27	19	3	10	11
1	5	20	14	3	6	3
2	45	45	45	45	-	-
3	104	104	104	104	-	-
4	111	111	111	111	-	-
5	104	104	104	104	-	-
6	111	111	111	111	-	-
7	111	111	111	111	-	-
8	111	111	111	111	-	-
9	111	111	111	111	-	-
10	104	104	104	104	-	-
11	104	104	104	104	-	-
12	104	104	104	104	-	-
14	104	104	104	104	-	-
15	104	104	104	104	-	-


















Level	Vertical Runs	Height	Vertical Pipe	Horizontal Pipe	Total Linear Feet
P2	100	12.5	1250	200	1450
P1	100	12.5	1250	200	1450
M4	100	12.5	1250	600	1850
M3	200	10	2000	700	2700
M2	200	12.5	2500	750	3250
M1	150	12.5	1875	500	2375
A	150	10	1500	500	2000
1	450	10	4500	900	5400
2	450	10	4500	400	4900
3	330	8.5	2805	300	3105
4	330	9	2970	300	3270
5	330	8.5	2805	300	3105
6	330	8.5	2805	300	3105
7	330	9	2970	300	3270
8	330	8.5	2805	300	3105
9	330	8.5	2805	300	3105
10	330	9	2970	300	3270
11	330	8.5	2805	300	3105
12	330	8.5	2805	300	3105
14	330	9	2970	300	3270
15	250	9	2250	200	2450
16	200	12.5	2500	1000	3500
<b>Total</b>	<b>5980</b>	<b>219.5</b>	<b>56890</b>	<b>9250</b>	<b>66140</b>

Plumbing Assemblies Takeoff

Level	Fixtures	Sq. Ft.	Fixture / Sq. Ft.	1000	1600	2000	3000	4000
P2	150	50000	0.003	3	5	6	9	12
P1	150	50000	0.003	3	5	6	9	12
M4	353	21500	0.016	16	26	33	49	66
M3	353	21500	0.016	16	26	33	49	66
M2	353	21500	0.016	16	26	33	49	66
M1	353	21500	0.016	16	26	33	49	66
A	353	21500	0.016	16	26	33	49	66
1	150	30000	0.005	5	8	10	15	20
2	150	30000	0.005	5	8	10	15	20
3	280	30000	0.009	9	15	19	28	37
4	280	30000	0.009	9	15	19	28	37
5	280	30000	0.009	9	15	19	28	37
6	280	30000	0.009	9	15	19	28	37
7	280	30000	0.009	9	15	19	28	37
8	280	30000	0.009	9	15	19	28	37
9	280	30000	0.009	9	15	19	28	37
10	280	30000	0.009	9	15	19	28	37
11	280	30000	0.009	9	15	19	28	37
12	280	30000	0.009	9	15	19	28	37
14	280	30000	0.009	9	15	19	28	37
15	280	30000	0.009	9	15	19	28	37
16	280	30000	0.009	9	15	19	28	37
<b>Total</b>	<b>6005</b>	<b>657500</b>	<b>0.219</b>	<b>10</b>	<b>16</b>	<b>20</b>	<b>30</b>	<b>40</b>

Appendix D:  
Detailed Site Layout Planning

**Legend**

-  Excavation Area
-  Existing Buildings
-  Grass
-  Sidewalk
-  Street
-  Laydown Area
-  Dumpster
-  Concrete Placement Area
-  Trailer
-  Slab Opening
-  Material Hoist
-  Temporary Restroom
-  Fence
-  Gate Opening
-  Traffic Flow
-  Truck Delivery
-  Tower Crane

**Slurry Wall - Excavation**


Sunnyvale Plaza

Mid-Atlantic Region

Tech #2


















Nathan Braskey

10/16/13





**Legend**

-  Building Area
-  Existing Buildings
-  Grass
-  Sidewalk
-  Street
-  Laydown Area
-  Dumpster
-  Concrete Placement Area
-  Trailer
-  Slab Opening
-  Material Hoist
-  Temporary Restroom
-  Fence
-  Gate Opening
-  Traffic Flow
-  Truck Delivery
-  Tower Crane

**Superstructure**


Sunnyvale Plaza

Mid-Atlantic Region

Tech #2

















Nathan Braskey

10/16/13






**Legend**

-  Building Area
-  Existing Buildings
-  Grass
-  Sidewalk
-  Street
-  Laydown Area
-  Dumpster
-  Concrete Placement Area
-  Trailer
-  Slab Opening
-  Material Hoist
-  Temporary Restroom
-  Fence
-  Gate Opening
-  Traffic Flow
-  Truck Delivery
-  Tower Crane

**Finishes**

Sunnyvale Plaza	
Mid-Atlantic Region	Tech #2
Nathan Braskey	10/16/13



Appendix E:  
General Conditions Estimate

Date: 08-Oct-13

General Conditions Estimate  
Year 2013 Quarter 3  
Unit Detail Report

Prepared By:  
John Smith  
PSU

LineNumber	Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
<b>Division 01 General Requirements</b>					
013113200120	Field personnel, field engineer, average	950.00	Week	\$2,050.00	\$1,947,500.00
013113200140	Field personnel, field engineer, maximum	190.00	Week	\$2,325.00	\$441,750.00
013113200180	Field personnel, project manager, minimum	190.00	Week	\$2,900.00	\$551,000.00
013113200200	Field personnel, project manager, average	190.00	Week	\$3,350.00	\$636,500.00
013113200220	Field personnel, project manager, maximum	190.00	Week	\$3,825.00	\$726,750.00
013113200240	Field personnel, superintendent, minimum	190.00	Week	\$2,825.00	\$536,750.00
013113200260	Field personnel, superintendent, average	190.00	Week	\$3,100.00	\$589,000.00
013113200280	Field personnel, superintendent, maximum	190.00	Week	\$3,550.00	\$674,500.00
015113800100	Temporary Heat, per week, 12 hours per day, incl. fuel and operation	342.00	CSF Flr	\$36.20	\$12,380.40
015113800450	Temporary Power, for temp lighting only, 23.6 KWH/month	342.00	CSF Flr	\$3.63	\$1,241.46
015113800650	Temporary Utilities, power for job duration, incl. elevator, etc, max	342.00	CSF Flr	\$121.00	\$41,382.00
015213200550	Office Trailer, furnished, rent per month, 50' x 12', excl. hookups	48.00	Ea.	\$375.00	\$18,000.00
015433406410	Rent toilet portable chemical, Incl. Hourly Oper. Cost.	48.00	Month	\$222.42	\$10,676.16
015433600500	Rent tower crane, static, 130' high, 106' jib, 6200 lb capacity at 400 fpm, Excl. Hourly Oper. Cost.	48.00	Month	\$18,150.00	\$871,200.00
015626500100	Temporary Fencing, chain link, 6' high, 11 ga	1,400.00	L.F.	\$5.76	\$8,064.00
015813500020	Project signs, sign, high intensity reflectorized, buy, excl. posts	250.00	S.F.	\$37.50	\$9,375.00
017413200050	Cleaning up, cleanup of floor area, continuous, per day, during construction	752.00	M.S.F.	\$46.00	\$34,592.00
<b>Division 01 General Requirements Subtotal</b>					<b>\$7,110,661.02</b>

General Conditions Takeoff

Item	Quantity	Unit	Cost / Unit	Total Cost
<b>Field Personnel</b>				
Operations Manager	190	Weeks	\$ 3,825.00	\$ 726,750.00
Executive Project Manager	190	Weeks	\$ 3,350.00	\$ 636,500.00
Project Manager	190	Weeks	\$ 2,900.00	\$ 551,000.00
Project Engineer	190	Weeks	\$ 2,325.00	\$ 441,750.00
Office Engineer (3)	570	Weeks	\$ 2,050.00	\$ 1,168,500.00
General Superintendent	190	Weeks	\$ 3,550.00	\$ 674,500.00
Project Superintendent	190	Weeks	\$ 3,100.00	\$ 589,000.00
Area Superintendent	190	Weeks	\$ 2,825.00	\$ 536,750.00
Field Engineer (2)	380	Weeks	\$ 2,050.00	\$ 779,000.00
<b>Temporary Utilities</b>				
Power	342	CSF / Flr	\$ 124.63	\$ 42,623.46
Restrooms	48	Months	\$ 222.42	\$ 10,676.16
Heat	342	CSF / Flr	\$ 36.20	\$ 12,380.40
Trailer	48	Months	\$ 375.00	\$ 18,000.00
Crane (3)	48	Months	\$ 18,150.00	\$ 871,200.00
Fencing	1400	L.F.	\$ 5.76	\$ 8,064.00
Project Signs	250	S.F.	\$ 37.50	\$ 9,375.00
Waste Management	752	M.S.F.	\$ 46.00	\$ 34,592.00
<b>Subtotal</b>				<b>\$ 7,110,661.02</b>
<b>Measurement &amp; Verification</b>	0.25%	%	\$ 500,000,000	\$ 1,250,000.00
<b>Insurance</b>				
Builder's Risk	0.50%	%	\$ 500,000,000	\$ 2,500,000.00
General Liability	0.50%	%	\$ 500,000,000	\$ 2,500,000.00
Payment & Performance Bond	0.75%	%	\$ 500,000,000	\$ 3,750,000.00
<b>Scheduling</b>	0.05%	%	\$ 500,000,000	\$ 250,000.00
<b>Miscellaneous Contingency</b>	1.0%	%	\$ 500,000,000	\$ 5,000,000.00
<b>Total Cost</b>				<b>\$ 22,360,661.02</b>

Appendix F:  
Project LEED Scorecard



# LEED for New Construction v2.2 Registered Project Checklist

Project Name: Sunnyvale Plaza  
Project Address:

Yes ? No

<b>9</b>	<b>5</b>	<b>Sustainable Sites</b>	<b>14 Points</b>
----------	----------	--------------------------	------------------

Y	1	2	3	4	5	Prereq	Credit	Description	Points	Required
						Prereq 1	<b>Construction Activity Pollution Prevention</b>			Required
	1					Credit 1	<b>Site Selection</b>		1	
	1					Credit 2	<b>Development Density &amp; Community Connectivity</b>		1	
			1			Credit 3	<b>Brownfield Redevelopment</b>		1	
	1					Credit 4.1	<b>Alternative Transportation, Public Transportation Access</b>		1	
	1					Credit 4.2	<b>Alternative Transportation, Bicycle Storage &amp; Changing Rooms</b>		1	
	1					Credit 4.3	<b>Alternative Transportation, Low-Emitting &amp; Fuel-Efficient Vehicles</b>		1	
	1					Credit 4.4	<b>Alternative Transportation, Parking Capacity</b>		1	
			1			Credit 5.1	<b>Site Development, Protect or Restore Habitat</b>		1	
			1			Credit 5.2	<b>Site Development, Maximize Open Space</b>		1	
	1					Credit 6.1	<b>Stormwater Design, Quantity Control</b>		1	
			1			Credit 6.2	<b>Stormwater Design, Quality Control</b>		1	
	1					Credit 7.1	<b>Heat Island Effect, Non-Roof</b>		1	
	1					Credit 7.2	<b>Heat Island Effect, Roof</b>		1	
			1			Credit 8	<b>Light Pollution Reduction</b>		1	

Yes ? No

<b>4</b>	<b>1</b>	<b>Water Efficiency</b>	<b>5 Points</b>
----------	----------	-------------------------	-----------------

1				Credit 1.1	<b>Water Efficient Landscaping, Reduce by 50%</b>	1
1				Credit 1.2	<b>Water Efficient Landscaping, No Potable Use or No Irrigation</b>	1
			1	Credit 2	<b>Innovative Wastewater Technologies</b>	1
1				Credit 3.1	<b>Water Use Reduction, 20% Reduction</b>	1
1				Credit 3.2	<b>Water Use Reduction, 30% Reduction</b>	1

7 1 9

<b>7</b>	<b>1</b>	<b>Energy &amp; Atmosphere</b>	<b>17 Points</b>
----------	----------	--------------------------------	------------------

Y				Prereq 1	<b>Fundamental Commissioning of the Building Energy Systems</b>	Required
Y				Prereq 2	<b>Minimum Energy Performance</b>	Required
Y				Prereq 3	<b>Fundamental Refrigerant Management</b>	Required

**\*Note for EA1:** All LEED for New Construction projects registered after June 26<sup>th</sup>, 2007 are required to achieve at least two (2) points under EA1.

5	5			Credit 1	<b>Optimize Energy Performance</b>	1 to 10
					10.5% New Buildings or 3.5% Existing Building Renovations	1
					14% New Buildings or 7% Existing Building Renovations	2
					17.5% New Buildings or 10.5% Existing Building Renovations	3
					21% New Buildings or 14% Existing Building Renovations	4
	5				24.5% New Buildings or 17.5% Existing Building Renovations	5
					28% New Buildings or 21% Existing Building Renovations	6
					31.5% New Buildings or 24.5% Existing Building Renovations	7
					35% New Buildings or 28% Existing Building Renovations	8
					38.5% New Buildings or 31.5% Existing Building Renovations	9
					42% New Buildings or 35% Existing Building Renovations	10
			3	Credit 2	<b>On-Site Renewable Energy</b>	1 to 3
					2.5% Renewable Energy	1
					7.5% Renewable Energy	2
					12.5% Renewable Energy	3
1				Credit 3	<b>Enhanced Commissioning</b>	1
			1	Credit 4	<b>Enhanced Refrigerant Management</b>	1
1				Credit 5	<b>Measurement &amp; Verification</b>	1
	1			Credit 6	<b>Green Power</b>	1

continued...



Yes ? No

4 2 7

**Materials & Resources**

13 Points

Y	Yes	?	No	Prereq	Requirement	Points
				Prereq 1	<b>Storage &amp; Collection of Recyclables</b>	Required
			1	Credit 1.1	<b>Building Reuse</b> , Maintain 75% of Existing Walls, Floors & Roof	1
			1	Credit 1.2	<b>Building Reuse</b> , Maintain 100% of Existing Walls, Floors & Roof	1
			1	Credit 1.3	<b>Building Reuse</b> , Maintain 50% of Interior Non-Structural Elements	1
1				Credit 2.1	<b>Construction Waste Management</b> , Divert 50% from Disposal	1
1				Credit 2.2	<b>Construction Waste Management</b> , Divert 75% from Disposal	1
			1	Credit 3.1	<b>Materials Reuse</b> , 5%	1
			1	Credit 3.2	<b>Materials Reuse</b> , 10%	1
1				Credit 4.1	<b>Recycled Content</b> , 10% (post-consumer + ½ pre-consumer)	1
	1			Credit 4.2	<b>Recycled Content</b> , 20% (post-consumer + ½ pre-consumer)	1
1				Credit 5.1	<b>Regional Materials</b> , 10% Extracted, Processed & Manufactured Regio	1
	1			Credit 5.2	<b>Regional Materials</b> , 20% Extracted, Processed & Manufactured Regio	1
			1	Credit 6	<b>Rapidly Renewable Materials</b>	1
			1	Credit 7	<b>Certified Wood</b>	1

Yes ? No

7 2 6

**Indoor Environmental Quality**

15 Points

Y	Yes	?	No	Prereq	Requirement	Points
				Prereq 1	<b>Minimum IAQ Performance</b>	Required
Y				Prereq 2	<b>Environmental Tobacco Smoke (ETS) Control</b>	Required
1				Credit 1	<b>Outdoor Air Delivery Monitoring</b>	1
			1	Credit 2	<b>Increased Ventilation</b>	1
1				Credit 3.1	<b>Construction IAQ Management Plan</b> , During Construction	1
			1	Credit 3.2	<b>Construction IAQ Management Plan</b> , Before Occupancy	1
1				Credit 4.1	<b>Low-Emitting Materials</b> , Adhesives & Sealants	1
1				Credit 4.2	<b>Low-Emitting Materials</b> , Paints & Coatings	1
1				Credit 4.3	<b>Low-Emitting Materials</b> , Carpet Systems	1
	1			Credit 4.4	<b>Low-Emitting Materials</b> , Composite Wood & Agrifiber Products	1
1				Credit 5	<b>Indoor Chemical &amp; Pollutant Source Control</b>	1
			1	Credit 6.1	<b>Controllability of Systems</b> , Lighting	1
			1	Credit 6.2	<b>Controllability of Systems</b> , Thermal Comfort	1
1				Credit 7.1	<b>Thermal Comfort</b> , Design	1
	1			Credit 7.2	<b>Thermal Comfort</b> , Verification	1
			1	Credit 8.1	<b>Daylight &amp; Views</b> , Daylight 75% of Spaces	1
			1	Credit 8.2	<b>Daylight &amp; Views</b> , Views for 90% of Spaces	1

Yes ? No

5

**Innovation & Design Process**

5 Points

Y	Yes	?	No	Credit	Requirement	Points
1				Credit 1.1	<b>Innovation in Design</b> : Provide Specific Title	1
1				Credit 1.2	<b>Innovation in Design</b> : Provide Specific Title	1
1				Credit 1.3	<b>Innovation in Design</b> : Provide Specific Title	1
1				Credit 1.4	<b>Innovation in Design</b> : Provide Specific Title	1
1				Credit 2	<b>LEED® Accredited Professional</b>	1

Yes ? No

36 5 28

**Project Totals (pre-certification estimates)**

69 Points

**Certified:** 26-32 points, **Silver:** 33-38 points, **Gold:** 39-51 points, **Platinum:** 52-69 pc