



ELIZABETH HOSTUTLER STRUCTURAL OPTION

SENIOR THESIS-SPRING 2006 ADVISOR: DR. LINDA HANAGAN

THE PENNSYLVANIA STATE UNIVERSITY

GATEWAY PLAZA

500 DELAWARE AVE., WILMINGTON, DE

ELIZABETH HOSTUTLER, STRUCTURAL OPTION



PROJECT INFORMATION

LOCATION: 500 DELAWARE AVE.

SIZE: 387,000 SF

No. of Stores: 15 (ABOVE GRADE)

Overall Project Cost: \$52 million

Dates of Construction (Start-finish):

July 2005-December 2006 (Projected)

Function: Multi-story Office Tower with

Lower Level Retail, Bank, and Cafe and 5-story

PARKING GARAGE.

PROJECT TEAM

OWNER/DEVELOPER: BUCCINI/POLLIN GROUP, INC. GENERAL CONTRACTOR: GILBANE

ARCHITECT: GENSLER

ENGINEERS:

- CIVIL: LANDMARK ENGINEERS
- GEOTECH: DUFFIELD ASSOCIATES, INC.
- MEP: BALA CONSULTING ENGINEERS
- STRUCTURAL: O'DONNELL, NACCARATO & MACINTOSH

MAJOR TENATS:

- LAW-FIRM OF MORRIS, JAMES, HITCHENS & WILLIAMS
- WSFS FINANCIAL CORP.

ARCHITECTURAL FEATURES

- BOWED, GLASS CURTAIN WALL FACADE
- CROWN TRELLIS ON ROOF FRAMING MECHANICAL PENTHOUSE
- ZINC METAL PANEL ON FIRST AND SECOND FLOOR BELT WITH PRECAST CONCRETE PANELS ON REAR.
- 14 FLOORS OF TENANT FIT-OUT
- FIRST FLOOR CAFE FEATURES KINKED ROOF AND PROTRUDES FROM TOWER FOOTPRINT.

LIGHTING/ELECTRICAL SYSTEM

LIGHTING

INTERIOR: 6" OPEN REFLECTOR DOWNLIGHT PENDANTS W/ COMPACT FLOURESCENT LAMPS.

EXTERIOR: METAL HALIDE DOWNLIGHTS AND LED ILLUMINATING STRIPS W/ TEMPERED GLASS LENSES.

ELECTRICAL

- 480/277V & 208/120V POWER W/ (2) 2500/3325 KVA TRANSFORMERS & 1600A BUS RISERS.
- 750 kw, 938 kva emergency generator

STRUCTURAL SYSTEM

FOUNDATION: 12" DIA. AUGER-CAST PILES & GRADE BEAMS SUPPORTING 5" SLAB ON GRADE. **SUPERSTRUCTURE:**

- OFFICE TOWER: COMPOSITE STEEL FRAMING
- Garage: Pre-cast Concrete double tees on cast-in-place beams & columns.

LATERAL SYSTEM:

- OFFICE TOWER: MIX OF BRACED, MOMENT, AND CHEVRON FRAMES AT 9 LOCATIONS
- Garage: Pre-cast concrete shearwalls Structural Slabs: Slabs on Grade are 5" NWT. Concrete over 6" compact fill and elevated slabs are 3 1/4" LWT. Concrete on 3" composite lok-floor deck.

MECHANICAL SYSTEM

- 3-CELL WATER COOLING TOWER
- DIRECT EXCHANGE, 18-TON AIR CONDITIONING FAN COIL UNITS
- RISERS FOR 24,000 CFM ON EACH FLOOR PROVIDING 4800 CFM OUTDOOR AIR.

TABLE OF CONTENTS

1.0 EXECUTIVE SUMMARY	3
2.0 BUILDING INFORMATION	4
2.I Primary Engineering Systems	7
2.2 Additional Engineering Systems	8
3.0 STRUCTURAL SYSTEM DESCRIPTION	9
4.0 PROBLEM STATEMENT AND SOLUTION PROPOSAL	13
5.0 DESIGN CRITERIA	15
5.1 Design Objectives	15
5.2 Design Procedure	15
5.3 Loading Conditions	16
6.0 STRUCTURAL DEPTH	21
6.I Post-tensioning2	21
6.I.I Slab	21
6.I.2 Post-tensioned Beams	22
6.I.3 RAM Concept	24
6.2 Regularly Reinforced2	28
6.2.I Columns	28
6.2.2 Lateral System Design	30
6.3 Foundations	33
7.0 STRUCTURAL SUMMARY	34
8.0 BREADTH STUDIES	36
8.I Mechanical Study	36
8.2 Construction Study4	
9.0 CONCLUSIONS	
CREDITS AND ACKNOWLEDGEMENTS	44
REFERENCES	

GATEWAY PLAZA Wilmington, Delaware

500 Delaware Ave.

I.0 EXECUTIVE SUMMARY

Gateway Plaza is a 15-story office tower located in the Central Business District of downtown Wilmington, Delaware. The \$52 million project began in July 2005 and is projected for completion in December 2006. The 16-story, 210'-6" tower will offer 387,000 square feet of rentable office space



Figure 1-Rendering of the front of Gateway Plaza. (Photo courtesy of Gensler).

for tenant fit-out. The architect of design is Gensler and the property owner is Buccini

Pollin Group. The ground floor is a public plaza level including a restaurant, post-office, and WSFS branch bank. In the rear of the building there is a 5-story parking garage housing 600 car parking spaces for the building's employees.

This report is an in-depth study of the structural system of Gateway Plaza. The objective of the report is to gain knowledge and experience in post-tensioned concrete design and methods for reducing floor depth. RAM Concept software was utilized to determine deflection and stress plans for various loading conditions. The design resulted in a one-way post-tensioned slab that is 8" thick, with 6-strand unbonded tendons spaced approximately 6.25' o.c. The beams supporting this slab are also post-tensioned and range in size from 20"x24" using 12 strands to 36"x24" using 39 strands. The columns and floor system use 6000 psi concrete. Additionally, concrete shearwalls were designed to be 12" thick using 4000 psi concrete and work in conjunction with the concrete frames to resist lateral loads, which were developed using ASCE 7-02.

Two breadth studies were also performed to understand design from the point of view of the other building systems. These studies focus on how concrete design has impacted the mechanical system, specifically the layout of ducts, and the cost and schedule factors in managing the construction.

Through these feasibility studies it has been determined that the post-tensioned concrete redesign of the structure is a good alternative, but not likely to be utilized in the given building market of Wilmington, Delaware.

2.0 BUILDING INFORMATION




Figure 2-Front of side elevations of the office tower and parking garage. (Drawings courtesy of Gensler)

Gateway Plaza is a 15-story office tower located in the Central Business District of downtown Wilmington, Delaware. The \$52 million project began in July 2005 and is projected for completion in December 2006. The 16-story, 210'-6" tower will offer 387,000 square feet of rentable office space for tenant fit-out. Two of the building's major occupants include the law firm of Morris, James, Hitchens & Williams and the WSFS Financial Corporation. The ground floor will play host for public retail including an indoor/outdoor café, post-office, and WSFS branch bank. In the rear of the building there is a 5-story parking garage housing 600 car parking spaces for the building's employees.

Primary Project Team

- Owner/Developer: Buccini/Pollin Group
- General Contractor: Gilbane
- Architect: Gensler
- Engineers:
 - o Civil: Landmark Engineering
 - o Geotech: Duffield Associates, Inc.
 - o *MEP*: BALA Consulting Engineers, Inc.
 - o Structural: O'Donnell, Naccarato & MacIntosh
- Project Delivery Method: Design-Bid-Build

Zoning

- Office tower
 - o C-4 Use Group
 - o Business Use Group B
- Garage
 - o S-2 Garage
 - Construction Type: IB
 - Type 1 Protected

Location and Site

Gateway Plaza is located at 500 Delaware Avenue, between West and Washington Streets. The building and its amenities are situated in the northwestern quadrant of the Wilmington's Central Business District, which is home to many of the nation's largest financial corporations. It is on the top of a hill with views in all directions of the city, including the waterfront in the south. To get a better view of the location, see the map on the right.

The urban site on which Gateway Plaza is constructed is currently a privately owned parking lot. To determine the soil composition, borings were taken by a subcontractor to the geotechnical engineer, Duffield Associates. Ten samples were taken, and the results of laboratory tests are summarized in the soils report. Such an urban site generally consists of contains a layer of miscellaneous fill (i.e. concrete, asphalt, brick, metal, etc.) that ranges in depth from 12'-16' below the existing ground surface. 'Medium to dense, coarse



Figure 6-Map of downtown Wilmington and location of Gateway Plaza. (Photo courtesy of Mapquest)



Figure 6-Projected site plan.



Figure 6-Rendering of northwest corner from ground level.



Figure 6-Aerial view of Wilmington with rendering of Gateway Plaza superimposed. (All three renderings courtesy of Gensler)

grained soils and medium to stiff consistency silt and clay soils lay beneath the miscellaneous fill layer. Their depths range from approximately 57'-63' below the existing ground surface." Finally, dense to very dense sand soils, evidence of weathered bedrock, lay below the sandy silt layer.

Architecture

Gateway Plaza is the first new building to be constructed in Wilmington's Central Business District (CBD) in 15 years. The tower will fill in the gap between neighboring office towers. It is predicted to be a landmark among all of the CBD's office towers because it will have one of the few all-glass curtain walls in town. The curtain wall will give the façade a more modern feel than the dated 1970s architecture of the DuPont Hotel and the "cookie-cutter" appearance of the Sheraton Hotel, which both have concrete facades. The northeast quadrant of the tower features a corner that appears to be "sliced" off at an angle that imitates the angle of Delaware Ave.

The main entrance to the lobby has a 5-story cut-out of the front façade. The public café on the ground level adds interest to the building because it protrudes out of the footprint of the main tower and features a kinked, standing seam, metal roof. The protrusion creates a courtyard in front of the entrance and allows for shaded outdoor seating, a new feature to the CBD. The remaining 14 stories of the tower remain office space for tenant fit-outs.

Building Envelope

The bulk of Gateway Plaza's primary office tower is enclosed with a glass curtain wall system featuring a reflective glazing. It is characterized by the overlapping, shingle-type construction of blue-tinted glazing. The first floor, however, is a flat lock, zinc wall panel system which is also carried up the office tower on the spine of the south end. The parking garage is clad with pre-cast concrete panels. There is a painted, metal panel screen wall on the roof serves to hide the mechanical penthouse. The roof is an



Figure 7-Mock up of curtain wall system. (Photo courtesy of Gilbane).

EPDM system using polyisocyanurate insulation over fiberglass sheathing on metal deck.

2.I Primary Engineering Systems

Mechanical

The variable volume mechanical system of Gateway Plaza is located on the roof in a mechanical penthouse. Here, the 3-cell water cooling tower and heat pumps supply conditioned air to all 15 floors of the building. On floors 2-15, there are direct exchange air conditioning units using R-22 refrigerant. In the building's IT/Telephone room on the first floor, there is a Liebert Challenger 3000 air conditioning unit to provide up to 5 tons of cooling control the temperature and humidity required by the sensitive computing equipment.

Since the building is to be fit out, space for the risers has been designated to a mechanical room found on each floor in the tower's service core. Return air from each floor is dumped into the mechanical room and is exhausted. There are outdoor air louvers in each room to replace the exhausted air and provide ventilation.

Electrical

Gateway Plaza's electrical system is powered by both 480/277V and 208/120V panel boards. Power is supplied to the building by two 2500/3325 kVA transformers. There are two main distribution panels that service floors 1-8 and floors 9-roof, respectively. The voltage is stepped down through transformers on the second, fifth, eighth, eleventh, and fourteenth floors in electrical rooms in the building's core. A 1600A bus riser supplies power to the typical office levels for lighting and receptacles. There is a 750kW, 938 kVA emergency generator which services the fire pumps.

Lighting

Lighting for the service core of the typical office floors is provided with 6" open reflector down lights with compact fluorescent lamps. For the tenant spaces, the lighting plans will be finalized upon fit-out. On the exterior plaza area, metal halide downlights flood the walls of the first floor with light. Illuminating strips with tempered glass lenses are located under trees to light the plaza and seating areas.

2.2 Additional Engineering Systems

Fire Protection

Almost every area of Gateway Plaza is protected by a wet sprinkler system with a 4" wet standpipe in each of the two stairwells. The water is supplied to the standpipes by a fire pump and a jockey pump for the higher floors; both are located on the 1st floor in the water service room. The fire pump has a capacity of 750 GPM and the jockey pump has a capacity of 109 GPM. These can run on emergency power supplied by a diesel generator.

Transportation

Gateway Plaza has a central service core servicing most of the building's transportation needs. There are 5 public elevators, 1 service elevator, and two stairwells in the core. The public elevators and stairwells run to all floors of the office tower and the service elevator will also run to the mechanical penthouse.

The main entrance to the public is on Delaware Ave. and will have a vestibule to control air loss. The service core can be accessed from this main entrance, while the public areas will have separate entrances also along Delaware Ave. including one to the café and one to the WSFS bank.

Telecommunications

The building has a main technology/data center on the ground floor. It is located in the parking garage and will service all of the security systems and telephone lines in the building.

3.0 STRUCTURAL SYSTEM DESCRIPTION

Gateway Plaza has two distinct buildings and two distinct building systems. The office tower is composite steel construction with braced frames and the parking garage is pre-cast concrete with pre-cast shearwalls. The two structures are separated using a 2" expansion joint. The structural engineer is responsible for designing the office tower and the pre-cast supplier is responsible for the design of the garage. For this reason, focus will be centered on the office tower design.

Foundations

Due to the poor soil conditions on site, deep foundations were deemed necessary for the high gravity column loads and overturning moments from lateral resisting elements. The soils report recommended end-bearing caissons, but due to designer preference, concrete filled, steel tube piles were chosen. The piles are 12" in diameter and use high strength concrete to develop 120 tons of end-bearing capacity per pile. Most of the piles are drilled 70' down to bedrock. The clusters are topped with pile caps that range from 40"-65" thick. Grade beams span the pile caps around the entire building's perimeter, and a 5" slab on grade span the grade beams in much of the foundation and are intermittently supported by single piles.

The office tower's steel columns sit on pile caps of various shapes. The columns from the lateral load resisting system generally sit on clusters of 18 piles or more where those from the gravity system sit on clusters of 6-12. The larger foundations under the lateral frames are to resist the overturning moment from wind and seismic loading. The pile clusters in the office tower are on a 30'x52' grid on the north side and a 30'x36' grid on the south side (see the foundation plan on next page).

The vertical support members in the parking garage sit on pile caps that are 40-50" thick and are generally square. The lateral load resisting system of the garage, pre-cast concrete shearwalls, sits on 7-pile clusters while the cast-in-place concrete columns rest on 4-pile clusters. The clusters in the parking garage are on a 30'x62' grid (not shown).




Figure 8-Foundation plan

Framing

Gateway Plaza uses two types of framing systems for its two types of use: composite steel for the office tower and precast/cast-in-place concrete for the parking garage.

The composite steel in the office tower uses two grid systems: one orthogonal and one rotated. As aforementioned, the grids are 30'x52' and 30'x36'. The rotated grid is an adaptation of the orthogonal grid that is turned 14° clockwise from

plan north, and is used to create the sliced surface on the northeast face. The columns are spliced



Figure 9-Steel framing during construction. (Photo courtesy of Gilbane)

every other floor or 27'. All framing members on the office floors use wide-flange shapes of A992, Gr. 50 steel where the framing of the penthouse and screen-wall on the roof use HSS tube shapes of A36 steel. All of the columns, in both the lateral and gravity systems, are W14 shapes of various sizes. The girders and beams range in size but are usually W18 or W24 shapes. The plan below shows the framing for a typical floor. The dashed lines indicate the locations of the braced frames.

The garage is typical construction of cast-in-place concrete columns and pre-cast concrete beams. The pre-cast double tee beams span girders that are pre-cast L-beams. Sizing of these members is left to the pre-cast contractor.




Figure 10-Framing plan of a typical floor.

Structural Slabs

There are 6 types of structural slabs used in Gateway Plaza: three slabs on grade and three supported metal deck slabs.

Each type of slab on grade is normal-weight concrete cast over 6" crushed stone and compacted fill. The first type of slab on grade (SOG) is used in the on a majority of the ground level where there will be retail space and parking. This type is 5" of concrete with 6x6-W2.9x2.9 WWF reinforcing. Another type of slab on grade is 6" of concrete with 6x6-W2.0x2.0 WWF reinforcing. This SOG can be found in the loading area for the retail occupants. The final type of SOG is 12" concrete reinforced with #8 @ 12" o.c. each way in the top and #6 @ 12" o.c. each way in the bottom. This larger slab is used in the loading dock that is accessible by the entire building.


All three types of supported slabs on deck utilize ¾"\$\phi\$ shear studs and concrete with a compressive strength of 3000 psi. Two types of supported slabs are 3-1/4" light-weight concrete on 3" Lok-Floor composite deck and use 6x6 W1.4x1.4 WWF reinforcing. The difference between them is the gage of the deck. One type is 20 gage and used in the office area of all the elevated floors, the other is 16 gage which will be shored during construction and will be used in the mechanical areas of each floor. The third type of supported slab is

found on the penthouse floor and is 2-1/2" of normal-weight concrete on 1-1/2" Lok-Floor composite deck. It, too, uses 6x6 W1.4xW1.4 WWF reinforcing.

Lateral Load Resisting System

The lateral load resisting system for Gateway Plaza utilizes ordinary moment frames and concentrically braced frames. The bracing members are not the traditional, A36, angles but are A992 wide flange shapes. There are five frames resisting load in the north-south direction, and four in east-west direction. The braced frames are located around the service core of the building, where bracing is not a concern. The moment frames are located on the

east and west edges of the building, which is exposed by curtain wall. The location of these frames does a good job at preventing torsion by keeping the floor's center of rigidity very close to its center of mass. However, this is only the case for loads in the north-south direction. The structure may be subjected to torsion in the case of loads in the east-west direction because the center of rigidity is further from the center of mass.






Figure 11-Location of braced frames and centers of mass and rigidity.

4.0 PROBLEM STATEMENT AND SOLUTION PROPOSAL

An area for redesign was difficult to pinpoint with Gateway Plaza. After the research and analysis performed during Technical Assignments 1-3, it has been determined that the current structural systems--steel framing, concentrically braced frames, and deep foundations--was the best given building type, local conditions and accepted practice. Though no feasible framing alternatives were found during research for *Technical Report 2: Pro-con Study of Alternate Framing Systems*, further research and faculty consultation has suggested that a one-way post-tensioned concrete slab system is worth considering. There are no height restrictions dictated by the architect or zoning ordinances, but the post-tensioned system could add a significant amount of ceiling space. The purpose behind this design is to gain knowledge and experience in the design of post-tensioned concrete systems in buildings.

Proposed Problem Solution

As mentioned in the problem statement above, post-tensioned concrete slabs and beams will be designed to replicate the architectural requirements of the building by adhering to the given column grids. To achieve this, cast-in-place columns, post-tensioned beams and slabs, and shearwalls will be designed. Although foundations will not be explicitly designed, they will be sized approximately for end bearing strength. Making an appropriate comparison of the concrete system to the steel system will require the consideration of the following factors: cost, project duration, and impact on foundations.

Method for Solution

In order to redesign the building using post-tensioned concrete slabs, research must initially be performed to gain knowledge in how to design such a system. By researching texts, journals, and code manuals, a good deal of technical knowledge should be gained. By talking with students whose thesis buildings use post-tensioned concrete in their existing designs and professionals in the industry, significant knowledge of practical design shall be gained.

Once a significant amount of information has been gathered, schematic designs will commence. A preliminary framing plan will be laid out and the office floors will be designed using loads obtained in *Technical Report 1: Existing Building Conditions*. The first round of analysis for all members will be performed by hand calculations using ACI 318-05 *Building Code Requirements for Reinforced Concrete* and *The Post-tensioning Manual*. Further analysis will be completed using structural software including: ENERCALC, RAM Structural System, and Concept. Finally, wind and seismic loads will be computed by hand and applied to the structure. A design for the lateral system will be designed and checked in RAM Frame for all possible loading cases and combinations as laid out in Chapter 2 of ASCE 7-02.

Once the design has been finalized, a proper comparison shall be made between the composite steel framing and the post-tensioned concrete framing based on the factors mentioned above.

5.0 DESIGN CRITERIA

5.I Design Objectives

The main objective of this project is to find an alternative structural system that will perform as well as steel in achieving long-span bays. Additionally, the chosen type of system should allow greater control in determining floor depths. Therefore, keeping these depths to a minimum will be of great importance. In order to meet this goal, the following standards must be met:

- Long bay spans must be preserved.
- Service spaces in the building's core must remain unchanged.
- Limit the overall floor depth to 24".
- Keep shearwalls in locations similar to those of the braced frames.
- Design must be in compliance with model codes set forth by ACI 318-05, IBC 2003, and ASCE 7-05.

5.2 Design Procedure

To make this project manageable, one of the main assumptions considered is that floors 2-5 are one type of typical floor and floors 6-15 are a second type of typical floor. Since the office tower is the responsibility of the structural designer, it alone will be considered for the redesign. The garage will be omitted from design because it is the responsibility of the precast manufacturer.

All schematic designs will be performed by traditional hand calculations using procedures outlined in concrete design texts by Antoine Naaman and Charles Nilson as well as ACI 318-05. Spreadsheets containing the calculations embedded in these procedures will be created to ease repetition. The preliminary designs yielded by the spreadsheets (available in *Appendix B: Preliminary Member Design*) will be entered into ENERCALC to confirm hand calculations. A structure of these preliminary members will be modeled in RAM structural design software for refinement. The gravity system will be checked and refined using RAM Concrete and post-tensioned elements including slabs and beams will use RAM Concept. Concept will be used to check concrete stresses and deflections under service conditions as well as design minimum reinforcing. The lateral system will be analyzed

GATEWAY PLAZA Wilmington, Delaware

500 Delaware Ave.

further using RAM Frame to scrutinize lateral loads and compare them to hand calculations, as well as obtain building drifts under various load cases and combinations.

5.3 Loading Conditions

5.3.1 Gravity Loads

5.3.I.I Dead and Live

Dead loads include the self-weight of the structure and any additional loads accounting for sprinklers, MEP, and collateral loading. It is evident that the total dead load is greater for the concrete design than it was for the composite steel design, 115 psf compared to 65 psf. The live loading conditions comply with those set forth in IBC 2003.

A majority of the office tower is classified as office occupancy which results in a live load of 60 psf, plus an additional 20 psf for partitions. Although the loads are not consistent with those of the original designer, they are still

LOADING IN POUNDS/SQUARE FOOT									
	Office Floors	Mechanical Rooms	Penthouse Floor	Main roof	Penthouse Roof				
Concrete Slab	100	100	100	50	50				
Roof & Insulation				5	5				
Ceiling	5	5	5	5	5				
Collateral	5	5	5	5	5				
Mechanical	5	5	5	10	10				
Total Dead Load	115	115	115	65	65				
Total Live Load	80	125	150	60	60				

Table 1-Gravity loading information.





Figure 12-Diagram of loading conditions.

conservative and comply with IBC 2003. There are portions on each floor considered to be service spaces which house HVAC and electrical equipment in mechanical rooms. These spaces, subjected to heavy equipment loads, will be designed for a 125 psf live load. This area is illustrated on the typical floor in the diagram above. The table above summarizes the gravity loading conditions in each type of occupancy.

5.3.I.2 Snow Loads

The roof will inevitably be designed for snow loading. But since there is a building setback where the main roof meets the penthouse, drifting has the possibility of becoming an issue. Drifting can occur on the north and west sides the penthouse indicated by the lavender areas

labeled 1 and 2 in the diagram to the right. A spreadsheet was developed according to the ASCE 7-02 guidelines set out in Chapter 7. In section 1, the



maximum drift load was found to be 49

Figure 13-Areas of concern for snow drift.

psf and in section 2, the load was found to be 63 psf. For further details on the calculations, please refer to *Appendix A.1: Snow Loading*.

5.3.2 Lateral Loads

The lateral loads, both wind and seismic, for the building were found using the guidelines set forth in IBC 2003 and ASCE7-02. Complete calculations were found using spreadsheets; please refer to *Appendix A.2: Lateral Loading* for intermediate steps. Although the wind loads for Gateway Plaza did not change due the redesign, seismic loads increased dramatically due to the increase in the structure's weight.

The wind load is distinctly greater in the north-south direction because the building dimension perpendicular to this direction is 270', which is three times larger than that in the opposite direction, and collects a great deal more pressure. In the east-west direction, however, seismic loads were found to control due to the increase in building weight. Considering both load types--seismic and all four cases of wind--and including accidental eccentricity, the only cases that resulted in unfavorable results were those that included eccentricity. In addition to the existing eccentricity between the center of rigidity and the center of mass, the accidental eccentricity created unfavorable rotations. Load combinations checked by RAM Frame include those from ASCE 7-02 in Chapter 2.0 for strength design:

- 1. 1.4(D)
- 2. $1.2(D)+1.6(L)+0.5(L_r or S)$
- 3. $1.2(D)+1.6(L_r or S)+(0.5 Lor 0.8 W)$
- 4. $1.2(D)+1.6(W)+L+0.5(L_{r}orS)$ Controls in N-S
- 5. 1.2D + 1.0E + 0.5L + 0.2S
- 6. 0.9(D)+1.6(W)
- 7. 0.9(D) + 1.0(E) Controls in E-W

5.3.2.1 Wind Loading

Wind Loads on the Main Wind Force Resisting System were found according to the Analytical Procedure, outlined in Section 6.5. To find the story forces and shears, a tributary area approach was taken. The pressure at each floor level was distributed over an area equal to half the floor height above and below the level. As would be expected from a building on

the coastal Northeastern United States, wind is the controlling load case in the north-south direction.

The basic wind loading characteristics are:

• Basic Wind Speed: 90 mph

• Wind Load Importance: 1.0

Exposure Category: B

• Internal Pressure Coefficient: +/- 0.18

• Height: 210.5"

• Maximum wind pressure at roof: 23.3 psf

These characteristics were used to find the following loads on the building in both




Figure 14-Structure under wind loads in north direction.

characteristic directions. The loads and controlling drift tabulated on page 20 are summaries of RAM output, which are similar to the hand calculations performed according to ASCE 7-02. ASCE 7's Case 4 resulted in a building drift of 2.96", approximately h/850, which is considered very acceptable.

5.3.2.2 Seismic Loading

Seismic Loads were found using the Equivalent Lateral Force Procedure as laid out in Section 9.5.5 of ASCE 7-02. Seismic loading characteristics include:

• Site Class: D

• Spectral Response: 0.3

• 1-second Spectral Response: 0.075

• Design Spectral Response: 0.32




Figure 15-Structure under seismic loads in the eastwest direction.

• 1-second Design Spectral Response: 0.12

• Seismic Use Group: II

• Seismic Design Category: B

• Seismic Importance Factor: 1.0

• Response Modification Factor: 3

• Base shear: 709 k

These characteristics were used to find the following loads on the building in both characteristic directions. The loads and controlling drift are tabulated on the next page. Case 7 was shown to control drift in the east-west direction, 2.25". Again, this is an acceptable drift limit.

The table on the next page summarizes the story shears in both, north-south and east-west, directions according to RAM Frame and hand calculations performed according to ASCE 7-02. Additionally, it tabulates the maximum story drifts according to the controlling load combinations. The diagrams below depict how these forces act on the building in both directions.

	Sı	tory Shear di	ue to Wind		Story She	ar due to	Story Drift	Story Drift
		X		Y	Both X & Y		X	Y
	ASCE 7	RAM	ASCE 7	RAM	ASCE 7	RAM	1.2D+1.0E+.5L _r	1.2D+1.6W+.5L _r
R	24.6	15 k	90 k	48 k	55 k	88 k	2.255 in	2.963 in
15	46.8	42 k	172 k	139 k	156 k	205 k	2.383 in	2.703 in
14	68.5	69 k	253 k	225 k	251 k	306 k	2.193 in	2.457 in
13	90	95 k	332 k	310 k	335 k	393 k	1.998 in	2.212 in
12	111.1	121 k	411 k	393 k	408 k	467 k	1.799 in	1.967 in
11	131.6	146 k	488 k	476 k	472 k	528 k	1.596 in	1.726 in
10	151.9	170 k	564 k	556 k	526 k	579 k	1.392 in	1.488 in
9	171.7	193 k	639 k	634 k	572 k	619 k	1.190 in	1.259 in
8	190.9	216 k	712 k	709 k	610 k	679 k	0.992 in	1.038 in
7	209.4	237 k	783 k	782 k	639 k	672 k	0.801 in	0.829 in
6	227.3	256 k	852 k	852 k	662 k	686 k	0.620 in	0.634 in
5	244.4	274 k	919 k	918 k	680 k	695 k	0.446 in	0.458 in
4	260.7	289 k	984 k	980 k	692 k	698 k	0.301 in	0.304 in
3	275.9	301 k	1045 k	1036 k	699 k	695 k	0.178 in	0.177 in
2	281.6	311 k	1068 k	1110 k	702 k	695 k	0.082 in	0.081 in

Table 2-Comparison of hand calculations to computer analysis results and worst case story drifts.

NS-direction wind forces EW-direction wind forces Seismic Forces




Figure 16-Story forces on the building due to lateral loads.

6.0 STRUCTURAL DEPTH

6.I Post-tensioning

6.I.I Slab

Spanning 52.5' with regular reinforced concrete is very difficult, and nearly impossible to stay within reasonable floor depths. For this reason, it has been concluded that a one-way post-tensioned floor system is the best candidate for redesign. The 52.5' span also requires the concrete to have a high compressive strength to withstand the large stress imposed by the prestressing tendons. For this reason, the monolithically cast slab and beam floor system will be designed using 6000 psi concrete. The slab spans the 30'-0" direction and is framed out by post-tensioned beams along column grid lines. Initial designs and hand calculations were performed following an example published by the Portland Cement Association. The example conforms to the concrete and steel stress limits provided by Chapter 18 in ACI 318-02 and is classified as Class U, uncracked. For detailed calculations, see *Appendix B.1: Post-tensioned Slab*.

An 8" thick slab was initially chosen according to an 1/44 guideline set forth by the Post-tensioning Institute and accepted practice. The tendon profile was laid out in order to preserve the 2-hour fire rating of the existing system, requiring 1.75" of cover for prestressing tendons. This restricted the strands to a depth of 6.75" from the top of the slab at mid-span, 1.75" at the interior supports, and 4" at exterior supports (see **Figure 17**-Tendon profile in slab). With this profile, the effective prestressing force is found to be 1303 k. This translates into 49 tendons that need to be evenly distributed across the 52'-6" span. For constructability purposes, 8 ducts with 6 wires in each were distributed evenly across the bay. The ducts were routed around any slab openings to preserve the continuity of the prestressing force. In the angled northeast corner of the building where the slab area decreases, every other tendon was removed to prevent over-stressing the concrete (see **Figure 18**-Tendon layouts in slab).

GATEWAY PLAZA Wilmington, Delaware

500 Delaware Ave.




Figure 17-Tendon profile in slab.




Figure 18-Tendon layouts in slab.

6.1.2 Post-tensioned Beams

The beams are included in the design because the aspect ratio of the bay is greater than the 2:1 ratio necessary for a two-way flat slab system. Therefore, post-tensioned beams will need to frame out the slab. They will need to be massive because of the large spans and heavy slab loads that they must support. To keep with the original goal of decreasing floor depth, the beams were kept to a maximum of 24" deep, including slab depth. Therefore, the beams are unconventionally wide and utilize a large amount of slab to aide in compression. The beams were initially designed according to Chapter 18 in ACI 318 and designed as Class T, the transition between uncracked and cracked. They are analyzed as T-beams to account for the additional compressive strength found in the slab. Detailed hand calculation that account for prestress losses can be found in *Appendix B.3: Beams*. These calculations consider the tendon profile to have a single drape, rather than a parabolic profile, which simplifies the calculation and provides a sufficient initial design. A feasible domain of

acceptable initial forces and tendon eccentricities was constructed where an initial force, number of strands, and tendon profile were chosen.

The desired beam geometries were entered into ENERCALC to determine section properties including: area, moment of inertia, section modulus, and neutral axis. The geometry and loading for the 52.5' beam require 39 tendons with a profile of 14" at the ends and 5" at mid-span. The 36' beam requires 16 strands with the same profile. Because these calculations do not consider the beams to be continuous, they are just approximations and require closer evaluation. When the tendons from interior beams span shearwalls, they require a straight tendon profile.




Figure 19-Cross sections of beams with section properties found in ENERCALC.




Figure 20-Tendon layout in continuous beams.

6.I.3 RAM Concept

The slab and beams, designed by hand calculations, were modeled in RAM Concept and are considered to be typical of all floors in the building. The program was used to determine concrete stresses and deflections for multiple load cases including: initial, sustained, and long-term service loading. Transverse shear reinforcement for beams and minimum required reinforcement for the slab were also determined with RAM Concept.

When modeled, column and middle design strips were generated according the ACI 318-02 for the maximum flange width of beams. Minimum reinforcement in the beams and slab was also indicated to be 0.0018 using #4 bars (see illustrations below for design strips).




Figure 21-Longitude design strips generated by RAM Concept.




Figure 22-Latitude design strips generated by RAM Concept.

The preliminary designs worked well when modeled, and required only a few minor adjustments. The following beam schedule summarizes the location of beams, sizes, initial prestressing force, and number of strands. See the following two pages for transverse shear reinforcing details and deflection plans for various loading conditions. For minimum slab reinforcement plans, see *Appendix C: Plans*.

Properties	B-I		B-2		B-3		B-4		B-5		B-6	
Dimensions	24x	24	36x	24	18x	24	24x	24	20x	24	24x	24
Shape	L		T		L		T		L		T	
Fi	638	8 k	1064 k		266 k		1064 k		319 k		1064 k	
# Strands	2	4	40		10		4	0	1	2	4	0
dsupports	17in	18in	14in	18in	18in	17in	18in	17in	17in	17in	18in	17in
dmid	1.75 in											

Properties	B-7	B-8	B-9	B-10	B-II	B-12	
Dimensions	18x 24	18x 24	20x 24	20x 24	20x 24	36x 24	
Shape	L	L	T	T/L	L	T	
Fi	319 k	319 k	319 k	319 k	319 k	1064 k	
# Strands	12	12	12	12	12	40	
dsupports	17in	14in 17in	17in 20in	14in 17in	14in 20in	14in 20in	
dmid	1.75 in	1.75 in	1.75 in	1.75 in	1.75 in	1.75 in	

Properties	B-13		B-14		B-15		B-16	
Dimensions	36x	24	36x	24	24x	24	16x	12
Shape	T		T		L		L	
Fi	713	8 k	718 k		559 k		0 k	
# Strands	2	7	27		21		0	
dsupports	14in	18in	14in	18in	17in	18in	-	
dmid	1.75 in		1.75 in		1.75 in		-	

Table 3-Beam schedule including tendon profile, dimensions, and number of strands.




Figure 23-3D view of underside of typical floor.

Transverse Reinforcing Details




Figure 24-Transverse, shear reinforcement layouts for beams as designed by RAM Concept. See framing plan in *Appendix C.4: Post-tensioned concrete typical floor framing*.

Deflection Plans




Figure 25-Deflection plans for three loading conditions from RAM Concept.

6.2 Regularly Reinforced

6.2.1 Columns

Columns were designed in a traditional manner by determining axial forces at each level and approximating moments applied to the top and bottom of the column from beams framing into it. The axial forces were found based on tributary area where live loads were reduced based on Chapter 4.8 in ASCE 7-02. Preliminary calculations can be found in *Appendix B.2: Columns*. With these axial loads and approximate moments, interaction diagrams were used to determine initial reinforcing details.

These initial column sizes were modeled in RAM Concrete and their reinforcing was analyzed more closely. The reinforcing is spliced at every other level, and patterns and bar sizes have been narrowed down for constructability purposes. All columns have transverse shear reinforcing of #3 closed bars at 9" o.c. The following page contains the final column schedule, and the foundation plan can be found in *Appendix C.3: Post-tensioned concrete foundation*.




Figure 26-Reinforcing for columns (see column schedule on next page).

Floor	C-I	C-2	C-3	C-4	C-5	C-6	C-7	C-8
_	22x 22	18x 18	24x 24	24x 24	22x 22	22x 26	22x 26	
R	(16)- #9	(18)- #4	(18)- #6	(16)- #9	(20)- #8	(16)- #8	(16)- #6	
	2228k	1212k	2218k	2533k	2221k	2389k	2171k	
	22x 26	18x 24	32x 32	22x 26	22x 26	22x 26	22x 26	
15	(16)- #6	(18)- #5	(18)- #7	(16)- #9	(20)- #7	(16)- #9	(16)- #6	
	2171k	1648k	3816k	2520k	2364k	2520k	2171k	
	22x 26	18x 24	32x 32	22x 26	22x 26	22x 26	22x 26	
14	(16)- #6	(18)- #5	(18)- #7	(16)- #6	(20)- #5	(16)- #6	(16)- #6	
	2171k	1648k	3816k	2171k	#N/A	2171k	2171k	
7.0	22x 26	18x 24	32x 32	22x 26	22x 26	22x 26	22x 26	
13	(16)- #6	(18)- #5	(18)- #7	(16)- #6	(20)- #5	(16)- #6	(16)- #6	
	2171k	1648k	3816k	2171k	#N/A	2171k	2171k	
70	22x 26	18x 24	32x 32	22x 26	22x 26	22x 26	22x 26	
12	(16)- #6	(18)- #5	(18)- #7	(16)- #6	(20)- #5	(16)- #6	(16)- #6	
	2170.740k	1647.594k	3815.760k	2170.740k	#N/A	2170.740k	2170.740k	
7.7	22x 26	18x 24	32x 32	22x 26	22x 26	22x 26	22x 26	
II	(16)- #6	(18)- #5	(18)- #7	(16)- #6	(20)- #5	(16)- #6	(16)- #6	
	2171k	1648k	3816k	2171k	#N/A	2171k	2171k	
10	22x 32	18x 28	32x 32	22x 32	22x 32	22x 30	22x 30	
10	(16)- #6	(18)- #5	(18)- #7	(16)- #6	(20)- #6	(16)- #6	(16)- #6	
	2608k	1886k	3816k	2608k	2677k	2462k	2462k	
9	22x 32	18x 28	32x 32	22x 32	22x 32	22x 30	22x 30	
9	(16)- #6	(18)- #5	(18)- #7	(16)- #6	(20)- #6	(16)- #6	(16)- #6	
	2608k	1886k	3816k	2608k	2677k	2462k	2462k	
8	22x 32	18x 28	32x 32	22x 32	22x 32	22x 30	22x 30	
	(16)- #6	(18)- #5	(18)- #7	(16)- #6	(20)- #6	(16)- #6	(16)- #6	
	2608k	1886k	3816k	2608k	2677k	2462k	2462k	
7	22x 32	18x 28	32x 32	22x 32	22x 32	22x 30	22x 30	
,	(16)- #6	(18)- #5	(18)- #7	(16)- #6	(20)- #6	(16)- #6	(16)- #6	
	2608k	1886k	3816k 32x 32	2608k 22x 32	2677k	2462k	2462k	
6	22x 32	18x 28			22x 32	22x 30	22x 30	
	(16)- #6 2608k	(18)- #5 1886k	(18)- #7 3816k	(16)- #6 2608k	(20)- #6 2677k	(16)- #6 2462k	(16)- #6 2462k	
	2008K 32	18x 28	34x 34	22x 32	2077K	22x 30	22x 30	12x 12
5	(16)- #6	(18)- #5	(18)- #8	(16)- #6	(20)- #6	(16)- #6	(16)- #6	(8)- #4
	2608k	1886k	4387k	2608k	2677k	2462k	2462k	539k
	22x 32	18x 28	34x 34	22x 32	22x 32	22x 30	22x 30	12x 12
4	(16)- #6	(18)- #5	(18)- #9	(16)- #8	(20)- #8	(16)- #8	(16)- #6	(8)- #4
	2608k	1886k	4534k	2827k	2950k	2681k	2462k	539k
	22x 32	18x 28	34x 34	2027K	2930K 22x 32	22x 30	22x 30	12x 12
3	(16)- #6	(18)- #5	(18)- #11	(16)- #10	(20)- #10	(16)- #10	(16)- #6	(8)- #4
	2608k	1886k	4927k	3126k	3324k	2980k	2462k	539k
	2006K 22x 32	18x 28	34x 34	22x 32	22x 32	22x 30	22x 30	12x 12
2	(16)- #6	(18)- #6	(18)- #14	(16)- #11	(20)- #11	(16)- #11	(16)- #6	(8)- #4
	2608k	1980k	5412k	3307k	3551k	3161k	2462k	539k
	2000K	1 70UK	J412K	3307K	SSSIK	STOIK	2402K	JJYK

Table 4-Column schedule. See foundation plan in *Appendix C.3: Post-tensioned concrete-typical floor framing*.

6.2.2 Lateral System Design

Initially, the lateral system was planned to be cast-in-place shearwalls in similar locations to the braced frames in the composite steel structure. After running lateral load analyses in RAM considering all of the load combinations discussed in the section 5.3.2 Lateral Loads, story drifts were too large in certain load combinations. Without the freedom to add more shearwalls, the concrete frames needed to be included. Because this building is designed as a cast-in-place concrete structure with connections similar to moment connections, every frame that has been designed for gravity loading can be considered in resisting lateral load. However, these frames are not enough to resist all of the lateral loads alone and need to be incorporated with the shearwalls. Concrete shearwalls are used as the main structural elements that resist lateral forces and concrete frames supplement in resisting lateral loads.




Figure 27-Lateral systems under 1.2D+0.5L+1.4E when seismic loading is in the east-west direction and considers 5% accidental eccentricity.

The shearwalls are sufficient in resisting load combinations considering dead, live, and most cases of wind loading. However, the load combinations considering seismic loading introduce large deflections, around 12" when load is applied in the east-west direction, and torsional problems, around 1.15°. Since this drift was not drastically decreased by increasing wall thickness or material strength, the introduction of concrete moment frames to help in resisting loads is necessary.

Shearwall Design: The reinforcement was designed to resist only shear forces, and not checked in bending for overturning. Initial designs for shearwalls were performed using the controlling load cases in each direction that were found by hand calculations. Wind loads were found to control in the north-south direction while seismic




Figure 28-Shear wall dimension and loading diagram.

loads were found to control in the east-west direction. Shearwalls were designed using basic strength principles of $V_u \le \phi V_n$ and $V_n = V_c + V_s$ and modeled as a cantilevered beam with a series wall shears acting as point loads.

The walls were designed for the most heavily loaded level in shear and bending. The greatest loading, shear of 308 k and moment of 270 ft-k, exists in walls 1 and 4 (see diagram below) during wind loading in the north-south direction. A trial wall size of 12" thick with a compressive strength of 4000 psi were used for both directions and found to work. The steel used is #6 @ 14" in both horizontal and vertical directions.




Figure 29-Location of shearwalls in plan.

To determine the distribution of lateral forces to the shearwalls, their stiffnesses were calculated by the following equation: $k = \frac{Et}{4(h/l)^3 + 3(h/l)}$ and the story shears were

distributed accordingly. From these forces, the overturning moments and uplift at the base of each wall were found. All of these values are tabulated in the table on the next page and shown acting on the shearwalls. Refer to *Appendix B.4: Shearwalls* for further calculations on shearwalls.

Direct Shear on Shear Walls Due to Controlling Lateral Forces											
		N-	S		E-W						
Floor	I	2	3	4	5	6	7	8			
R	29 k	17 k	17 k	29 k	14 k	14 k	14 k	14 k			
15	54 k	32 k	32 k	54 k	39 k	39 k	39 k	39 k			
14	80 k	47 k	47 k	80 k	63 k	63 k	63 k	63 k			
13	105 k	61 k	61 k	105 k	84 k	84 k	84 k	84 k			
12	130 k	76 k	76 k	130 k	102 k	102 k	102 k	102 k			
II	154 k	90 k	90 k	154 k	118 k	118 k	118 k	118 k			
10	178 k	105 k	105 k	178 k	132 k	132 k	132 k	132 k			
9	201 k	119 k	119 k	201 k	143 k	143 k	143 k	143 k			
8	223 k	133 k	133 k	223 k	152 k	152 k	152 k	152 k			
7	245 k	147 k	147 k	245 k	160 k	160 k	160 k	160 k			
6	265 k	161 k	161 k	265 k	166 k	166 k	166 k	166 k			
5	284 k	175 k	175 k	284 k	170 k	170 k	170 k	170 k			
4	300 k	191 k	191 k	300 k	173 k	173 k	173 k	173 k			
3	312 k	210 k	210 k	312 k	175 k	175 k	175 k	175 k			
2	308 k	226 k	226 k	308 k	176 k	176 k	176 k	176 k			
Overturning	249,327	150,208	150,208	249,327	172,127	172,127	172,127	172,127			
Uplift	6,926 k	5,007 k	5,007 k	6,926 k	5,738 k	5,738 k	5,738 k	5,738 k			

Table 5-Shear on walls due to direct shear.




Figure 30-Direct shear acting on walls with resulting uplift and overturning moment.

6.3 Foundations

The concrete structure adds 30% more weight to the foundation when compared to the composite steel structure. The undesirable soil conditions in the city of Wilmington warrant deep foundations to support the gravity loads and overturning moment imposed on them. Since the clusters of auger-cast piles are already 10-18, increasing the size of clusters will begin to compromise the already poor soil. The objective of changing the foundations to caissons is to preserve the integrity of the soil, to limit settlement, and eliminate the need for a 60" pile cap. Their capacity was found based on the end soil bearing pressure of the caisson. For those underneath shearwalls, they will be reinforced to take tension due to overturning.

	Caissons											
		Amount	Material	Labor	Equip- ment	Cost						
A1020-310	4'-0" dia. x 100'	20 Ea	4358	70459		\$1,496,329						
	5'-0" dia. x 100'	6 Ea	8064	144990		\$918,324						
	6'-0" dia. x 100'	10 Ea	11730	172277		\$1,840,069						
					TOTAL	\$4,254,722						
	Conc	crete Fil	lled, Dril	led Piers	3							
A1020-130	End Bearing Steel Piles					Cost						
2380	4 pile cluster	5	5625	3325		\$44,750						
2460	6 pile cluster	8	8425	5025		\$107,600						
2480	7 pile cluster	7	9825	5850		\$109,725						
2500	8 pile cluster	5	12600	7525		\$100,625						
2560	12 pile cluster	9	15400	9200		\$221,400						
03310-240	Pile caps, incl. forms and reinf.	612	108	49	0.31	\$96,309						
					TOTAL	\$680,409						

Table 6-Cost estimate and comparison between caissons and concrete filled, steel piles.

In addition to the caissons, grade beams will be provided to engage all of the deep foundations when the shearwalls and frames are forced into action. Although the caissons and the grade beams have not been explicitly designed for, the impact that the structure has on them has been estimated. The foundation plan can be found in **Figure 29**-Foundation Plan.


7.0 STRUCTURAL SUMMARY

The concrete in the super-structure including: columns, girders, and slabs, will have a compressive strength of 6000 psi, but the shearwalls will be 4000 psi. The need for such high strength concrete in the gravity framing comes from the long-span feature of the office floors. In order to preserve the 52'-6" spans, the concrete needed to have enough strength to withstand the amount of stress caused by the post-tensioning force.

Post-tensioned Slab: The post-tensioned slab will be 8" thick and contribute 100 psf of dead load to the structure. The ungrouted tendons in the slab will be spaced about 6' o.c. and span the 30' direction of each bay. The tendons will be banded in groups of (6) ½" diameter strands and have yield strength of 270 ksi. They will have a parabolic profile of 6.75" above the bottom of the slab at supports and 1.75" from the bottom of the slab at mid-span.

Columns: The columns in the building range in size from 18"x28" to 30"x30". See page 28 for a full column schedule, and refer to the foundation plan in *Appendix C.3: Post-tensioned concrete-foundation* for column locations.

Beams: The beams will use post-tensioning steel with yield strength of 270 ksi. The steel strands will be grouted solid. Interior beams spanning 52'-6" will be 16"x36" and have approximately 35 strands in them, and interior beams spanning 36'-0" will be 16"x24" and have approximately 20 strands in them. In order to develop the full compressive capacity in the slab, the beams will be analyzed as T-beams. Beam designs have achieved the objective of decreasing floor depth by 7.25" over the composite steel system, when fire-proofing is considered.



POST-TENSIONED CONCRETE SECTION

Figure 31-Section of concrete floor system.

GATEWAY PLAZA Wilmington, Delaware

500 Delaware Ave.




Figure 32-Post-tensioned concrete framing plan for typical floor.

Shearwalls: Shearwalls will be identical in each direction: 12" thick, 4000 psi, and #6 @ 14" both vertically and horizontally. Though shearwalls will resist a majority of the lateral loads, they are not the only lateral resisting elements.

Foundations: The foundations will be caissons to support the additional weight of the concrete frame. Their sizes range from 4'-0" to 6'-6" in diameter. The caissons under shearwalls will be reinforced at the top to prevent overturning. They will be connected by a network of grade beams to more evenly distribute load and prevent differential settlement. The foundation plan is pictured below.




Figure 33-Foundation plan.

8.0 BREADTH STUDIES

The post-tension concrete design of Gateway Plaza will have an impact on all of the systems in the building, including the construction of the project. In particular, this report will focus on how supply air ducts, part of the mechanical system, can be designed according to ASHRAE Standard 62.1 and how the project can be scheduled efficiently.

8.I Mechanical Study

The main goal of the mechanical study is to design supply and return air ducts in a typical floor in Gateway Plaza. To keep with the objective of the structural design, minimizing floor depth, these ducts will be designed to minimize their depth. Since the building is for tenant fit-out, there is no existing duct plan to compare. However, the riser on each floor has a main supply duct with a depth of 26". To handle air return, the ceiling will be used as a plenum for collecting return air, a system that works well when drop ceilings are used. The mechanical room is equipped with two 90"x32" grilles to pull in air from the plenum, and the room has a louver to exhaust air outside.

8.1.1 Indoor Air Quality

Before ducts could be laid out, it is necessary to check that the building is receiving the required amount of outdoor air for proper ventilation. The layout for the new structural system was designed according to ASHRAE Standard 62.1: Ventilation for Acceptable Indoor Air Quality using the Ventilation Rate Procedure laid out in section 6.2. This procedure "determines outdoor air intake rates based on space type, occupancy level, and floor area." The actual amount of outdoor air supplied by the mechanical equipment has been compared to the minimum amount of outdoor air intake typical of the office floor (shown on the next page) as determined by the above procedure.

Since the building is for tenant fit-out, a basic design was established where the typical office floor was subdivided into five separate offices, seen in the diagram below. To estimate the occupancy of each office, it was assumed that each person occupied a 10'x10' cubicle, or 100 ft², including hallway circulation space.




Figure 34-Typical layout of offices, with square footage, for tenant fit-out.

The ventilation rate procedure has been outlined below for the office type 1.

Step I: Breathing Zone Outdoor Airflow

Step 2: Zone Outdoor Airflow

$$V_{oz} = \frac{V_{bz}}{E_z}$$
 (Eq. 6-2)
 $\circ E_z = 1.0$ (From Table 6-2 for ceiling supply of cool air.)
 $V_{oz} = \frac{325cfm}{1.0} = 325cfm$

Step 3: Multiple-Zone Recirculation System

o Primary Outdoor Air Fraction

$$Z_p = \frac{V_{oz}}{V_{pz}} \qquad \text{(Eq. 6-5)}$$

$$Z_p = \frac{325cfm}{\frac{2911sf}{17,491sf}(22,725sf)} = .0859cfm \text{ where } V_{pz} \text{ is taken to be the ratio of the}$$

area of the office being supplied to the total area of all of the offices multiplied by the total area of the typical floor.

o Uncorrected Outdoor Air Intake

$$V_{ou} = D\Sigma_{allzones} R_p P_z + D\Sigma_{allzones} R_a A_z$$
 (Eq. 6-6)

 The occupancy diversity is taken to be 1.0, which is conservative, because each office is being designed as having the same occupancy requirements.

$$V_{ou} = 325 cfm$$

Outdoor Air Intake

$$V_{ot} = \frac{V_{ou}}{E_{..}}$$

• Ventilation Efficiency: $E_v = 1.0$ because $Z_p < 0.15$.

$$V_{ot} = 325 cfm$$

Step 4: Outdoor Air Comparison

After all of the spaces have been calculated, the total amount of outdoor air that must be supplied to office space #1 is found to be 1942 cfm (see *Appendix D.1 Mechanical* for calculation of all spaces). This value is greatly less than the 4545 cfm that is supplied to the area by the existing equipment. Therefore, the typical office floor is capable of handling the ventilation requirements. This oversize is to be expected for a tenant fit-out space where space requirements are unknown.

8.I.2 Diffuser Layout

Since the requirements for each office space have been found according to ASHRAE Standard 62.1, the ducts can be laid out to achieve the necessary supply loads. Assuming that each supply diffuser will have a throw range of a 6'-16' radius, the diffusers can be laid out for each office space, taking care to cover the entire area. The diffusers specified by the architect are 24"x24" so that they will fit into the 24"x48" acoustic ceiling grid. See the diagram below for the preliminary diffuser lay-out and the throw area.

Return grills have been laid out in such a manner to create a natural circulation of air. The returns, about three supplies to each return, have been positioned between rows of supply diffusers. While the air will be supplied to the offices through forced air, ceiling plenum return will bring air back to the mechanical room.




Figure 35-Diffuser layout and ranges of throw.

8.I.3 Duct Layout

The diffusers were connected using the shortest run of ducts from the riser originating in the mechanical room in each floor. The only obstacle that needed to be avoided was the shearwalls flanking the mechanical room and stairwells. Therefore, the runs to the ducts in office spaces 5 and 6 were unusually long. The ducts originated in the mechanical room at a size of 96x26 and eventually branched off to a size of 10x10 at their smallest. To size the ducts, the Duct Designer (duct-o-lator) supplied from the Loren Cook Company was used. A friction loss of 0.08" of water per 100' of duct was assumed.

As was previously mentioned, air will be returned to the mechanical room through the ceiling plenum. To better direct the air in such a large ceiling plenum, duct stubs will be connected to the return grilles to direct the air to the mechanical room.

The plan below shows the layout of ductwork, both supply and return, to each office.




Figure 36-Duct layout.

8.2 Construction Study

8.2.I Scheduling Impact

There is a significant difference in tasks and sequence of tasks that take place when building a concrete structure and building a composite steel structure. There are more trades on site




Figure 37-Lifts in the construction sequence.

with concrete construction due to the necessary formwork, reinforcement, post-tensioning, and placing of concrete. This leads to the necessity of coordinating these trades to minimize down-time and preventing trades from interfering with one another.

Since there is virtually no lead time for concrete, compared to steel, a post-tensioned concrete floor can be produced from start to finish in around 5 days, so the structure can be erected quickly.

Due to the large size of the elevated slabs, approximately 24,000 $\rm ft^2$ and 640 cubic yards of concrete per floor, and the limited capacity of concrete trucks, about 10 cubic yards per truck, tasks will be completed in the 3 sections. The diagram below depicts the three sections the building has been divided into: column lines B-E, E-H, and H-L. The areas of these sections are more manageable for crews and for delivery coordination: $A=7650 \rm ft^2$, $B=7400 \rm ft^2$, $C=7000 \rm ft^2$.




Figure 38-Schematic of how construction will take place with lift sequencing.

The following events and their durations, on a floor by floor and section by section basis, were considered when scheduling this project:

- Columns (F/R/P): 2 days
 - o Forming

o Tying Reinforcement

o Pouring and curing

Construct/Erect shoring and formwork: 3 days

• Tie reinforcement for slab and beams: 1 day

• Rough-in for MEP: 1 day

• Concrete (for each section):

o Pour and finish: 1 day

o Cure: 2 days

• Strip formwork and install reshoring: 2 days

• Jack the post-tensioning tendons: 1 day

The previous tasks were scheduled using Primavera project management software and compared to the Primavera schedule obtained from the Gilbane Construction Manager for the composite steel structure. For the full schedule, refer to *AppendixD.2: Construction*. The composite steel construction lasted 140 days while the post-tensioned concrete construction lasted 156 days. Though these construction times are comparable, it does not include the lead time needed to obtain and fabricate steel.

8.2.2 Cost Analysis

Structural Framing Costs: The following cost comparisons take into consideration only the structural systems including: slabs, beams, columns, and lateral elements, and do not include foundation costs. Estimates for both systems were compiled using material takeoffs for a typical floor and finding unit prices for each material in RS Means 2005. Although, this is not the year when the project was bid, the estimates are both done using RS Means 2005, so they are in direct comparison. See *Appendix D.2: Construction*.


Cost Comparison					
	С	ost/Floor	cost/sf		
Concrete	\$	654,702	\$	27.98	
Steel	\$	616,892	\$	26.36	

Table 7-Cost comparison between post-tensioned concrete structure and composite steel structure.

As evidence by the cost comparison for the two systems, the post-tensioned concrete system is more expensive by \$1.62/ft² and approximately \$626,940 for the whole project. This is a 7% increase over the existing composite steel structure.

Foundations Costs: Since the foundations were changed as part of the post-tensioned concrete design, the change needs to be accounted for when considering project feasibility. Again, material takeoffs, available in *Appendix D.2: Construction*, were compiled and then assembly costs were taken from RS Means 2005. Caissons proved to be much more expensive than the existing concrete filled steel piles. The price for caissons is over \$4 million where the price for the piles was only \$700,000.

The charts below accurately illustrate differences in price, duration, and foundation costs between the composite steel and post-tensioned concrete systems.







Figure 40-Comparison charts.


9.0 CONCLUSIONS

This report contains a thorough investigation of the existing composite steel structure and an analysis and design of the new post-tensioned concrete structural framing system. After this investigation, the systems were compared based on cost, schedule, and impact on foundations. The post-tensioned design is a good alternative based on cost and schedule, but its impact on foundations is unfavorable. If a caisson foundation system was implemented, it would drastically increase the cost of foundations by \$3.5 million.

Although these comparisons show that the post-tensioned system is a good alternative, comparison based strictly on these factors is not enough. Architectural requirements and local market conditions tend to drive design more than the engineer. Taking these factors into consideration, the original composite steel framing is the favorable system. Wilmington, and most of Delaware, has remained dominated by steel design. Though composite steel has proved favorable for Gateway Plaza's requirements, the original objective of decreasing floor depth was achieved with the new design. Each floor had a savings of 7.25". This is an overall savings of 116", or 9.66', but not enough to add another floor level.



COMPOSITE STEEL SECTION



POST-TENSIONED CONCRETE SECTION

Figure 41-Floor section comparison.

Breadth studies also allowed a good deal of understanding to be gained into how the structural system affects the other systems in the building as well as the impact it has on construction.

Despite the final recommendation that the original system is the best design for Gateway Plaza, a great deal of knowledge was gained through extensive research and the original objective of decreasing floor depths was achieved.

CREDITS AND ACKNOWLEDGEMENTS

I would like express my sincere gratitude for helping along the way for this Senior Thesis Project. This project could not have been executed so professionally without their time, knowledge, and patience. Words cannot express my gratitude for how you have helped shape me as an engineer. Thank you.

O'Donnell Naccarato & MacIntosh

Peter Paton, Structural Engineer

Gilbane

Craig Hedlund, Construction Manager

AE Advisors

Dr. Linda M. Hanagan
Dr. Thomas Boothby
Professor M. Kevin Parfitt

AE Students

David J. Melfi
Justin Mulhollan
Anthony Lucositic
Chad Illig

I would also like to thank my boyfriend, Steve, because we got through this project together. Finally, I would like to thank my family: Jim, Kathy, Matt, Megan, and Mark Hostutler, Ann and Joseph Barnes and Jessie Hostutler. Your support, encouragement, and inspiration have helped me through the years in ways that words cannot express. I am blessed to have the most wonderful support group and cheering section in the world. I love you.

REFERENCES

Structural

American Concrete Institute. *Building Code Requirements for Structural Concrete* (ACI 318-05) and Commentary (ACI 318R-05). Farmington Hills, MI: 2005.

Atlas Prestressing Corp. Post-tensioned Concrete Design Workbook: Prepared for a One Day Symposium. Panorama City, CA: 1970.

Naaman, Antoine E. Prestressed Concrete Analysis and Design, Second edition. Techno Press 3000. Ann Arbor, Michigan: 2004.

Nilson, Arthur H, et al. *Design of Concrete Structures*, 13th ed. McGraw Hill Higher Education. New York, NY: 2004.

Portland Cement Association. *Two-Way Post-tensioned design example*. http://www.cement.org/buildings/Timesaving-2WayPost-IA.pdf

Post-Tensioning Institute. Post-Tensioning Manual, Second edition. Glenview, Illinois: 1976.

Mechanical

ANSI/ASHRAE Standard 62.1-2004: Ventilation for Acceptable Indoor Air Quality.

American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. Atlanta, GA: 2004. p10-15.

McQuiston, Faye, et al. Heating, Ventilating, and Air Conditioning Analysis and Design, 5th edition. John Wiley & Sons, Inc. New York, NY: 2000. p 362-89.

Construction

RSMeans Construction Cost Data: 2005.

Madsen, Jana J. Concrete v. Steel.

http://www.buildings.com/Articles/detail.asp?ArticleID=2511.

GATEWAY PLAZA		Wilmington, Delaware
500 Delaware Ave.	APPENDICES	Wilmington, Delaware

APPENDICES

APPEN	NDIX	A: LOAD CALCULATIONSiii
1	A.I	Snow Loadingiv
1	A.2	Lateral Loadingvi
		A.2.I Windvi
		A.2.2 Seismic xi
APPEN	NDIX	B: PRELIMINARY MEMBER DESIGNxiii
]	B.I	Post-tensioned Slabxiv
]	B.2	Columnsxvi
]	В.3	Beamsxix
]	B. 4	Shearwallsxxi
APPEN	NDIX	C: PLANSxxii
(C.I	Composite Steel-Foundationxxiii
(C.2	Composite Steel-Typical Floorxxiv
(C.3	Post-tensioned Concrete-Foundationxxv
(C.4	Post-tensioned Concrete-Floor Framingxxvi
(C.5	Post-tensioned Concrete-Reinforcementxxviii
APPEN	NDIX	D: BREADTH STUDIES xxxii
]	D.I	Mechanical Studies
]	D.2	Construction Studiesxxxiv
		D.2.1 Material Takeoffsxxxiv
		D.2.2 Estimatesxxxv
		D.2.3 Schedule xxxvii

GATEWAY PLAZA	Wilmington, Delaware
500 Delaware Ave.	
APPENDIX A: LOAD CALCU	LATIONS
T. Control of the con	


Elizabeth Hostutler - Structural Option

A.I Snow Loading

		Design Parameters
P_{g}	25.00 psf	Ground Snow Load - Figure 1608.2
1 g	Above Tree	Ground Show Load - Figure 1008.2
	Line	Terrain Category - Section 1609.4
	Fully Exposed	Roof Exposure - Table 1608.3.1b
C_{e}	0.8	Exposure Factor - Table 1608.3.1
C_{t}	1.00	Thermal Factor - Section 1608.3.2
	I	Importance Category - Table 1604.5
I	1.0	Importance Factor - Table 1609.5
P_{f}	20.00 psf	Flat Roof Snow Load, Pf = 0.7 * Ce * Ct * Is * Pg - Section 1608.3
D	17 pcf	Snow density,D = 0.13 Pg + $14 \le 30$ pcf - 1608.7
h_b	1'	Height of minimum roof snow load, (Default, Pf/D) - 1608.7
$h_{\rm r}$	19'	Difference in height between upper and lower roofs
h_c	17'	Difference in height between upper roof and top of flat roof snow
$l_{u, high}$	36'	Horizontal dimension of upper roof normal to the line of change of roof level
$l_{u, low}$	48'	Horizontal dimension of lower roof normal to the line of change of roof level

Drift Calculations							
Drift location	Calc. h _d (ft)	Corrected h _d (ft)	P _d (psf)	P _{max} (psf)	$\mathbf{W_d}$		
Windward Drift	1.73	1.73	29.77	49.77	6.90		
Leeward Drift	1.95	1.95	33.70	53.70	7.81		
Design Drift	1.95	1.95	33.7	53.7	7.8		

X	Y	A1 (psf)	A2 (psf)	Total (psf)
2.0	45	45	4	49
4.0	36	36	4	41
6.0	28	28	4	32
7.8	20	20	4	24



		Design Parameters
P_{g}	25.00 psf	Ground Snow Load - Figure 1608.2
	Above Tree Line	Terrain Category - Section 1609.4
	Fully Exposed	Roof Exposure - Table 1608.3.1b
C _e	0.7	Exposure Factor - Table 1608.3.1
C_{t}	1.00	Thermal Factor - Section 1608.3.2
	I	Importance Category - Table 1604.5
I	1.0	Importance Factor - Table 1609.5
$P_{\rm f}$	20.00 psf	Flat Roof Snow Load, Pf = 0.7 * Ce * Ct * Is * Pg - Section 1608.3
D	17.25 pcf	Snow density,D = $0.13Pg + 14 \le 30 pcf - 1608.7$
h _b	1.16'	Height of minimum roof snow load, (Default, Pf/D) - 1608.7
h _r	18.5'	Difference in height between upper and lower roofs
h _c	17.3'	Difference in height between upper roof and top of flat roof snow
$l_{u, high}$	44'	Horizontal dimension of upper roof normal to the line of change of roof level
$l_{u, low}$	130'	Horizontal dimension of lower roof normal to the line of change of roof level

Drift Calculations						
Drift location	Calc. h _d (ft)	Corrected h _d (ft)	P _d (psf)	P _{max} (psf)	$\mathbf{W_d}$	
Windward Drift	2.85	2.85	49.14	69.14	11.39	
Leeward Drift	2.19	2.19	37.82	57.82	8.77	
Design Drift	2.85	2.85	49.1	69.1	11.4	

X	Y	A1 (psf)	A2 (psf)	Total (psf)
2.0	61	61	4	65
4.0	52	52	4	56
6.0	43	43	4	48
8.0	35	35	4	39
10.0	26	26	4	30
11.4	20	20	3	23

A.2 Lateral Loading

A.2.I Wind

Input Information

	L: Length of Building in X- Direction	B: Length of Building in Y - Direction	L/B	B/L	Story Heights (ft)	Building Story Height (ft)
						210.50 ft
R	270.00 ft	88.00 ft	3.07	0.33	14.50 ft	210.50 ft
15	270.00 ft	88.00 ft	3.07	0.33	13.50 ft	196.00 ft
14	270.00 ft	88.00 ft	3.07	0.33	13.50 ft	182.50 ft
13	270.00 ft	88.00 ft	3.07	0.33	13.50 ft	169.00 ft
12	270.00 ft	88.00 ft	3.07	0.33	13.50 ft	155.50 ft
11	270.00 ft	88.00 ft	3.07	0.33	13.50 ft	142.00 ft
10	270.00 ft	88.00 ft	3.07	0.33	13.50 ft	128.50 ft
9	270.00 ft	88.00 ft	3.07	0.33	13.50 ft	115.00 ft
8	270.00 ft	88.00 ft	3.07	0.33	13.50 ft	101.50 ft
7	270.00 ft	88.00 ft	3.07	0.33	13.50 ft	88.00 ft
6	270.00 ft	88.00 ft	3.07	0.33	13.50 ft	74.50 ft
5	270.00 ft	88.00 ft	3.07	0.33	13.50 ft	61.00 ft
4	270.00 ft	88.00 ft	3.07	0.33	13.50 ft	47.50 ft
3	270.00 ft	88.00 ft	3.07	0.33	13.50 ft	34.00 ft
2	270.00 ft	88.00 ft	3.07	0.33	10.25 ft	20.50 ft
Int.	270.00 ft	88.00 ft	3.07	0.33	10.25 ft	10.25 ft

210.50 ft

0.50 ft
0.50 ft
0.030
0.750
.60 Hz
.0 deg
0 mph
1.00
В
2

Mean Roof Height of Building

Total Height of Roof

Fundamental Period Coefficient, ASCE 7-02 Table 9.5.5.3.2

Fundamental Period Factor, ASCE 7-02 Table 9.5.5.3.2

Structure is flexible so G will be calculated per ASCE Section 6.5.8.2

Angle of Roof Slope

Is roof diaphragm considered rigid or flexible??

Calculated Information

Height	HIGH
Cp-w	0.8
Cp-S	-0.7
Kd	0.85
Gcpi	0.18

"High" for Buildings > 60', "Low" for Buildings < 60' Windward Wall Pressure Coefficient, ASCE 7-02 Figure 6-6 Side Wall Pressure Coefficient, ASCE 7-02 Figure 6-6 Wind Directionality Factor, ASCE 7-02 Table 6-4

Internal Pressure Coefficients for Enclosed Buildings, ASCE 7-02 Figure 6-5

Criteria			Reference/Description
h	210.5		height of building
zmin	30		RIGID: From Table 6-2 of ASCE 7-02
zbar	126.3		RIGID: 0.6*h > zmin: ASCE 7-02 Section 6.5.8.1
C	0.3		RIGID: From Table 6-2 of ASCE
g _q	3.4		per section 6.5.8.1 and 6.5.8.2 of ASCE 7-02
g _v	3,4		per section 6.5.8.1 and 6.5.8.2 of ASCE 7-02
1	320		RIGID: Table 6-2 of ASCE 7-02
e	0.33		RIGID: Table 6-2 of ASCE 7-02
n ₁ , Y-dir	0.561		Natural Period
n ₁ , X-dir	0.81		Natural Period
ь	0.05		Damping Factor
V	90		Basic Wind Speed
bbar	0.45		FLEXIBLE: Table 6-2 ASCE 7-02
abar	0.25		FLEXIBLE: Table 6-2 ASCE 7-02
I _z	0.2398684		Equation 6-5 ASCE 7-02
Lz	500.52643		Equation 6-7 ASCE 7-02
	Y - Direction	X - Direction	
g _c	4.0493434	4.1389373	FLEXIBLE: Equation 6-9
V _z	75.529414	75.529414	FLEXIBLE: Equation 6-14
h	10.384339	10.384339	FLEXIBLE: Section 6.5.8.2
Rh	0.0916621	0.0916621	FLEXIBLE: Section 6.5.8.2
N_1	5.367795	5.367795	FLEXIBLE: Equation 6-12
R_n	0.0485013	0.0485013	FLEXIBLE: Equation 6-11

	Stif	f Build	ling Ca	alculat	tions	Flexib	le Buil	ding Ca	lculatio	ns	
Level	Height	В	L	Q	G stiff X-dir	nl	nb	R1	Rb	R	G flex X-dir
Int.	10.25	88	270	0.829	0.833	44.592	4.341	0.0222	0.204	0.099	0.838
3	13.5	88	270	0.829	0.833	44.592	4.341	0.0222	0.204	0.099	0.838
4	13.5	88	270	0.829	0.833	44.592	4.341	0.0222	0.204	0.099	0.838
5	13.5	88	270	0.829	0.833	44.592	4.341	0.0222	0.204	0.099	0.838
6	13.5	88	270	0.829	0.833	44.592	4.341	0.0222	0.204	0.099	0.838
7	13.5	88	270	0.829	0.833	44.592	4.341	0.0222	0.204	0.099	0.838
8	13.5	88	270	0.829	0.833	44.592	4.341	0.0222	0.204	0.099	0.838
9	13.5	88	270	0.829	0.833	44.592	4.341	0.0222	0.204	0.099	0.838
10	13.5	88	270	0.829	0.833	44.592	4.341	0.0222	0.204	0.099	0.838
-11	13.5	88	270	0.829	0.833	44.592	4.341	0.0222	0.204	0.099	0.838
12	13.5	88	270	0.829	0.833	44.592	4.341	0.0222	0.204	0.099	0.838
13	13.5	88	270	0.829	0.833	44.592	4.341	0.0222	0.204	0.099	0.838
14	13.5	88	270	0.829	0.833	44.592	4.341	0.0222	0.204	0.099	0.838
15	13.5	88	270	0.829	0.833	44.592	4.341	0.0222	0.204	0.099	0.838
R	14.5	88	270	0.829	0.833	44.592	4.341	0.0222	0.204	0.099	0.838
0	0	0	0	0.856	0.848	0.000	0.000	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!

	Stif	f Build	ling Ca	alculat	ions	Flexib	le Buil	ding Ca	lculatio	ns	
Level	Height	В	L		G stiff Y-dir	nl	nb	R1	Rb	R	Gflex Y-dir
Int.	10.25	270	88	0.787	0.811	10.066	9.225	0.0944	0.103	0.072	0.813
3	13.5	270	88	0.787	0.811	10.066	9.225	0.0944	0.103	0.072	0.813
4	13.5	270	88	0.787	0.811	10.066	9.225	0.0944	0.103	0.072	0.813
5	13.5	270	88	0.787	0.811	10.066	9.225	0.0944	0.103	0.072	0.813
6	13.5	270	88	0.787	0.811	10.066	9.225	0.0944	0.103	0.072	0.813
7	13.5	270	88	0.787	0.811	10.066	9.225	0.0944	0.103	0.072	0.813
8	13.5	270	88	0.787	0.811	14.534	13.320	0.0664	0.072	0.060	0.812
9	13.5	270	88	0.787	0.811	14.534	13.320	0.0664	0.072	0.060	0.812
10	13.5	270	88	0.787	0.811	14.534	13.320	0.0664	0.072	0.060	0.812
-11	13.5	270	88	0.787	0.811	14.534	13.320	0.0664	0.072	0.060	0.812
12	13.5	270	88	0.787	0.811	14.534	13.320	0.0664	0.072	0.060	0.812
13	13.5	270	88	0.787	0.811	14.534	13.320	0.0664	0.072	0.060	0.812
14	13.5	270	88	0.787	0.811	14.534	13.320	0.0664	0.072	0.060	0.812
15	13.5	270	88	0.787	0.811	14.534	13.320	0.0664	0.072	0.060	0.812
R	14.5	270	88	0.787	0.811	14.534	13.320	0.0664	0.072	0.060	0.812
0	0	0	0	0.856	0.848	0.000	0.000	#DIV/01	#DIV/01	#DIV/01	#DIV/01

Summary

h			G flex Y-dir	Gflex X-dir		height	par to short	par to long	
10	0	1	0.813	0.838	1	0	0.813	0.838	
24	20	3	0.813	0.838	2	15	0.813	0.838	
37.3	30	5	0.813	0.838	3	20	0.813	0.838	
50.8	50	7	0.813	0.838	4	25	0.813	0.838	
64	60	8	0.813	0.838	5	30	0.813	0.838	
78	70	9	0.813	0.838	6	40	0.813	0.838	
91	90	11	0.812	0.838	7	50	0.813	0.838	
105	100	12	0.812	0.838	8	60	0.813	0.838	
118	110	13	0.812	0.838	9	70	0.813	0.838	
132	130	15	0.812	0.838	10	80	0.813	0.838	
145	140	16	0.812	0.838	11	90	0.812	0.838	
159	150	17	0.812	0.838	12	100	0.812	0.838	
172	170	19	0.812	0.838	13	110	0.812	0.838	
172	170	19	#DIV/0!	#DIV/0!	14	120	0.812	0.838	

Design Wind Pressures on Main-Wind-Force-Resisting-Systems
ASCE Section 6.5

	_	_	_	_	_	_		_	_	_		_			_	_				_	_	_	_
Building Floor Elevation	10.25 ft	20.50 ft	34.00 ft	47.50 ft	61.00 ft	74.50 ft	\$8.00 ft	101.50 ft	115.00 ft	128.50 ft	142.00 ft	155.50 ft	169.00 ft	182.50 ft	196.00 ft	210.50 ft	210.50 ft						
Total Pressure for MWFRS in Y- Dir	15.2 psf	15.2 psf	15.8 psf	16.3 psf	16.7 psf	17.4 psf	17.9 psf	18.4 psf	18.9 psf	19.3 psf	19.6 psf	19.9 psf	20.6 psf	$21.1\mathrm{psf}$	$21.6 \mathrm{psf}$	$22.0\mathrm{psf}$	22.4 psf	23.3 psf					
Total Pressure for MWFRS in X-Dir	11.2 psf	11.2 psf	11.8 psf	12.3 psf	12.7 psf	13.4 psf	14.0 psf	14.5 psf	14.9 psf	15.4 psf	15.7 psf	16.1 psf	16.7 psf	17.3 psf	17.8 psf	18.2 psf	18.6 psf	19.6 psf					
Design Design Leeward Wall Leeward Wall Pressure in X- Pressure in Y- Dir	-8.6 psf	-8.6 psf	-8.6 psf	-8.6 psf	-8.6 psf	-8.6 psf	-8.6 psf	-8.6 psf	-8.6 psf	-8.6 psf	-8.6 psf	-8.6 psf	-8.6 psf	-8.6 psf	-8.6 psf	-8.6 psf	-8.6 psf	-8.6 psf	3				
	-4.4 psf	-4.4 psf	-4.4 psf	-4.4 psf	-4.4 psf	-4.4 psf	-4.4 psf	-4.4 psf	-4.4 psf	-4.4 psf	-4.4 psf	-4.4 psf	-4.4 psf	-4.4 psf	-4.4 psf	-4.4 psf	-4.4 psf	-4.4 psf					
Design Windward Wall Pressure in Y-Dir	9.6 psf	9.6 psf	7.2 psf	7.6 psf	3.0 psf	8.7 psf	9.3 psf	9.8 psf	10.2 psf	10.6 psf	11.0 psf	11.3 psf	11.9 psf	12.5 psf	12.9 psf	13.4 psf	13.8 psf	14.7 psf					
Design Windward Wall Pressure in X- Dir	$6.8 \mathrm{psf}$	$6.8\mathrm{pst}$	7.4 psf	Jsd 6.7	8.3 psf	3sd 0.6	3.6 psf	10.1 psf	$10.5\mathrm{psf}$	$11.0\mathrm{psf}$	11.3 psf	$11.7\mathrm{psf}$	12.3 psf	$12.9\mathrm{psf}$	$13.4 \mathrm{psf}$	$13.8\mathrm{psf}$	$14.2\mathrm{psf}$	15.2 psf	100				
Velocity Pressure, qh	$21.2 \mathrm{psf}$	$21.2 \mathrm{psf}$	21.2 psf	$21.2 \mathrm{psf}$	21.2 psf	21.2 psf	$21.2 \mathrm{psf}$	21.2 psf	21.2 psf	$21.2 \mathrm{psf}$	$21.2 \mathrm{psf}$	$21.2 \mathrm{psf}$	21.2 psf	$21.2 \mathrm{psf}$	$21.2 \mathrm{psf}$	$21.2 \mathrm{psf}$	$21.2 \mathrm{psf}$	21.2 psf	100				
Velocity Pressure, qz	10.1 psf	$10.1 \mathrm{\ psf}$	$11.0 \mathrm{psf}$	$11.7\mathrm{psf}$	12.3 psf	13.4 psf	14.3 psf	15.1 psf	15.7 psf	16.3 psf	16.9 psf	17.4 psf	18.3 psf	$19.2 \mathrm{psf}$	$19.9 \mathrm{psf}$	$20.6\mathrm{psf}$	21.2 psf	22.6 psf		3			
Cp Leeward Y-Dir	-0.500	-0.500	-0.500	005.0-	-0.500	-0.500	-0.500	-0.500	005.0-	-0.500	-0.500	-0.500	-0.500	-0.500	-0.500	005.0-	-0.500	-0.500		9			
Cp Leeward X-Dir	-0.248	-0.248	-0.248	-0.248	-0.248	-0.248	-0.248	-0.248	-0.248	-0.248	-0.248	-0.248	-0.248	-0.248	-0.248	-0.248	-0.248	-0.248					
BL	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33		30	0		
L/B	3.07	3.07	3.07	3.07	3.07	3.07	3.07	3.07	3.07	3.07	3.07	3.07	3.07	3.07	3.07	3.07	3.07	3.07					
G Y-Dir	0.8131	0.8131	0.8131	0.8131	0.8131	0.8131	0.8131	0.8131	0.8131	0.8131	0.8124	0.8124	0.8124	0.8124	0.8124	0.8124	0.8124	0.8124	0.8124	0.8124	0.8124	0.8124	0.8124
G X-Dir	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378	0.8378 0.8124
Kz	0.575	0.575	0.624	0.665	0.701	0.761	0.811	0.854	0.892	0.927	0.959	0.988	1.041	1.088	1.130	1.169	1.205	1.284	1.353	1.414	1.469	1.519	1.565
Height above ground level, z	0 ff.	15 ft	20 ft	25 ft	30 ft	40 ft	50 ft	# 09	70 ft	80 ft	₩ 06	100 ft	120 ft	140 ft	160 ft	180 ft	200 ft	250 ft	300 ft	350 ft	400 ft	450 ft	\$00 ft

Total Pressure for Frames Resisting Wind Forces Parellel to Y Direction
Total, Windward, Leeward? Total

Height above Tota ground level, z Pr	Total Design Pressure	5.0	7	ь	4	S	9	۲-	œ	6	10	11	12	13	14	15	Я
Floor To Floor Heights		10.25 ft	10.25 ft	13.50 ft	13.50 ft	13.50 ft	13.50 ft	13.50 ft	14.50 ft								
Story Elevations		10.25 ft	20.50 ft	34.00 ft	47.50 ft	61.00 ft	74.50 ft	88.00 ft	101.50 ft	115.00 ft	128.50 ft	142.00 ft	155.50 ft	169.00 ft	182.50 ft	196.00 ft	210.50 ft
Mid - Story Elevations		15.38 ft	27.25 ft	40.75 ft	54.25 ft	67.75 ft	81.25.ft	94.75 ft	108.25 ft	121.75 ft	135.25 ft	148.75 ft	162.25 ft	175.75 ft	189.25 ft	203.25 ft	210.50 ft
0 ft 15	15.2 psf																
15ft 15	15.2 psf	156.0 plf	228.3 pH	228.3 plf	228.3 plf	228.3 plf	228.3 plf	228.3 plf	228.3 plf								
20 ft 15	15.8 psf		78.9 plf	78.9 plf	78.9 pH	78.9 plf	78.9pH	78.9 plf									
25 ft 16	16.3 psf		8.1 plf	81.3 plf	81.3 plf	81.3 plf	81.3 plf	81.3 plf	81.3 plf	81.3 plf	81.3 plf	81.3 plf	81.3 plf	81.3 plf	81.3 plf	81.3 plf	81.3 plf
30 ft 16	16.7 psf			83.3 plf	83.3 plf	83.3 plf	83.3 plf	83.3 plf	83.3 plf								
40 ft 17	17.4 psf			69.4 plf	173.5 plf	173.5 plf	173.5 plf	173.5 plf	173.5 plf	173.5 plf	173.5 plf	173.5 plf	173.5 plf	173.5 plf	173.5 plf	173.5 plf	173.5 plf
50 ft 17	17.9 psf				134.5 plf	179.3 plf	179.3 plf	179.3 plf	179.3 plf	179.3 pff	179.3 plf						
80 ft 18	18.4 psf					184.2 plf	184.2 plf	184.2 plf	184.2 plf	184.2 plf	184.2 plf						
70 ft 18	18.9 psf					18.9 plf	188.7 plf	188.7 plf	188.7 plf	188.7 plf	188.7 plf	188.7 plf	188.7 plf	188.7 plf	188.7 plf	188.7 plf	188.7 plf
80 ft 15	19.3 psf						36.7 pH	192.6 plf	192.6 plf	192.6 plf	192.6 plf	192.6plf	192.6 plf	192.6 plf	192.6 plf	192.6plf	192.6 plf
90.ft 15	19.6 psf							156.9 plf	196.1 plf	196.1 plf	196.1 plf	196.1 plf	196.1 plf	196.1 plf	196.1 plf	196.1 plf	196.1 plf
100 ft 15	Jsd 6/61								199.5 plf	199.5 plf	199.5 plf	199.5 plf	199.5 plf	199.5 plf	199.5 plf	199.5 plf	199.5 plf
120 ft 20	20.6 psf								30.8 plf	308.3 plf	411.0 plf	411.0 plf	411.0 plf	411.0 plf	411.0 plf	411.0 pff	411.0 plf
140 ft 21	21.1 psf										179.3 plf	421.8 plf	421.8 plf	421.8 plf	421.8 plf	421.8plf	421.8 plf
160 ft 21	21.6 psf											43.1 plf	334.4 plf	431.5 plf	431.5 plf	431.5 plf	431.5 plf
180 ft 22	22.0 psf													198.1 plf	440.3 plf	440.3 plf	440.3 plf
200 ft 22	22.4 psf														56.1 plf	358.8plf	448.5 plf
250 ft 23	23.3 psf																245.0 plf
300 ft											1						
350 ft																	
400 ft																	
450 ft																	
500 ft																	
Total Story Shear @ Floor	r @ Floor	JId0	31d 78	313 plf	552 plf	799 plf	1056 plf	1319plf	1588 plf	1866 plf	2148 plf	2433 plf	2725 plf	3020 plf	3318plf	3621 plf	3956 plf
Story Force per Floor	per Floor	0.000 k if	0.087 klf	0.226 klf	0.239 kH	0.248 kH	0.256 kif	0.263 klf	0.270 kff	0.277 KI	0.282 klf	0.286 k If	0.291 klf	0.295 kIf	0.298 kH	0.303 KIF	0.335 klf

25
Ē
.9
1
e
-
ï
Z
in
70
*
F
\mathbf{r}
1
1
2
on
O BEET
orce
-
,0
\mathbf{x}
P
ind
Ţ.
5
4
ota
\Box

			E													
Floor Level	0.5	2	દ	4	ĸ	9	7	8	6	10	11	12	13	14	15	R
Length of Building	270.0 ft	270.0 ft	270.0 ft	270.0 ft	270.0ft	270.0 ft	270.0ft	270.0 ft								
Frame Story Force per Floor	0.0k	23.5 k	61.0 k	64.4k	46.99	69.2 k	71.0k	72.8 k	74.9k	76.1 k	77.1k	78.6k	79.7 K	80.5 k	81.7 k	90.4 k
Frame Story Shear per Floor	1068.0 k	1068.0 k	1044.5 k	983.5 k	919.1 k	852.1 k	782.9 k	711.9k	639.2 k	564.2 k	488.1 k	411.0k	332.3 k	252.6 k	172.1 k	90.4 k

Total Pressure for Frames Resisting Wind Forces Parellel to X Direction Total, Windward, Leeward? Total, Windward, Leeward?

Part	right above ground level, z	Total Design Pressure	Int.	2	8	4	ĸ	9	7	∞	6	10	11	12	13	14	15	я
112 pri	or To Floor Heights		10.25 ft	10.25 ft		13.50 ft	13.50 ft	13.50 ft	13.50 ft	13.50 ft	13.50 ft	13.50 ft	13.50 ft	13.50 ft	13.50 ft	13.50 ft	13.50 ft	14.50 ft
11.5 pt 15.5 pt 27.5 pt 40.7 pt 18.5	ry Elevations		10.25 ft	20.50 ft	34.00 ft	47.50 ft	61.00 ft	74.50 ft	\$8.00 ft	101.50 ft	115.00 ft	128.50 ft	142.00 ft	155.50 ft	169.00 ft	182.50 ft	196.00 ft	210.50 ft
112 psf 118	d - Story Elevations		15.38 ft	27.25 ft	40.75 ft	54.25 ft	67.75 ft	81.25 ft	94.75 ft	108.25 ft	121.75 ft	135.25 ft	148.75 ft	162.25 ft	175.75 ft	189.25 ft	203.25 ft	210.50 ft
132 pdf 612 pdf 612 pdf 613	¥0	11.2 psf																
13.7 psf 13.7 psf 13.3 psf	20 ft	11.8 psf		58.9 plf	58.9 plf	38.9 plf	58.9 plf	58.9 plf	38.9 plf	38.9 plf	58.9 plf	58.9 plf	38.9 plf	58.9 plf	58.9 plf	38.9 plf	38.9 pH	38.9 plf
1279pt 1279pt 1359pt 1	25 ft	12.3 psf		6.1 plf	61.3 plf	61.3 plf	61.3 plf	61.3 plf	61.3 plf	61.3 plf	61.3 plf	61.3 plf	61.3 plf	61.3 plf	61.3 plf	61.3 plf	61.3 plf	61.3 plf
134 psf 133	30 ft	12.7 psf			63.4 plf	63.4 plf	63.4 plf	63.4 plf	63.4 plf	63.4 plf	63.4 plf	63.4 plf	63.4 plf	63.4 plf	63.4 plf	63.4 plf	63.4 plf	63.4 plf
140 psf 140 psf 140 psf 130 spf 130	40 ft	13.4 psf			53.6 plf	133.9 plf	133.9 pff	133.9 plf	133.9 plf	133.9 plf	133.9 plf	133.9 plf	133.9 plf	133.9 plf	133.9 plf	133.9 plf	133.9 plf	133.9 plf
145 psf 145 psf 144	50 ft	14.0 psf				104.8 plf	139.8pH	139.8plf	139.8 plf	139.8 plf	139.8plf	139.8 plf	139.8 plf	139.8pff	139.8plf	139.8 pH	139.8 plf	139.8 plf
149 psf 149	£09	14.5 psf					144.9 pff	144.9 plf	144.9 plf	144.9 plf	144.9plf	144.9 plf	144.9 plf	144.9pff	144.9 plf	144.9 plf	144.9 plf	144.9 plf
154 psf 155 psf 153	70 ft	14.9 psf					14.9 plf	149.5 plf	149.5 plf	149.5 plf	149.5 plf	149.5 plf	149.5 plf	149.5 plf	149.5 plf	149.5 plf	149.5 plf	149.5 plf
157 psf 1573 psf	# 08	15.4 psf					1000	69.1 plf	153.6 plf	153.6 plf	153.6plf	153.6 plf	153.6 plf	153.6plf	153.6plf	153.6 plf	153.6 plf	153.6 plf
161 psf 160	30 ft	15.7 psf							125.8 plf	157.3 plf	157.3 plf	157.3 plf	157.3 plf	157.3 plf	157.3 plf	157.3 plf	157.3 plf	157.3 plf
167 psf 167 psf 158	100 ft	16.1 psf								160.8 plf	160.8 plf	160.8 plf	160.8 plf	160.8plf	160.8plf	160.8 plf	160.8 plf	160.8 plf
173 psf 173	120 ft	16.7 psf								25.1 plf	250.5 plf	334 0 plf	334.0 plf	334.0 plf	334.0 plf	334.0 plf	334.0 plf	334.0 plf
178 psf 178 psf 182	140 ft	17.3 psf										146.7 plf	345.1 plf	345.1 plf	345.1 plf	345.1 plf	345.1 plf	345.1 plf
186 psf 186	160 ft	17.8 psf											35.5 plf	275.2 plf	355.1 plf	355.1 plf	355.1 plf	355.1 plf
186 psf 186	180 ft	18.2 psf													163.9 plf	364.2 plf	364.2 plf	364.2 plf
196 psf 196 psf 196 psf 196 psf 196 psf 197	200 ft	18.6 psf														46.6plf	298.1 plf	372.7 plf
Story Force per Floor Cook off C3271 plf 4222 plf 6171 plf 8207 plf 10310 plf 12473 splf 1473 splf 17040 plf 1357 plf 2414 plf 2684 plf 2919 plf Story Force per Floor 0.000 kl 0.005 kl 0.172 kl 0.135 kl 0.210 kl 0.217 kl 0.225 kl 0.255 kl	250 ft	19.6 psf																205.5 plf
Story Force per Floor 0.00plf 6.50 plf 2.371 plf 4.223 plf 6.171 plf 820 7 plf 10310 plf 1.2483 plf 1473 8 plf 1473	300 ft																	
Story Force per Floor O.000 kf 0.005 kf 0.172 kf 0.155 kf 0.204 kf 0.225 kf 0.225 kf 0.225 kf 0.225 kf 0.225 kf 0.225 kf	350 ft																	
Story Force per Floor G.O.Op.E 650 piE 627 piE 617 piE 6217 kif 6217 kif 6210 kif 6217 kif 6217 kif 6210 kif 6217 kif 6217 kif 6210 kif 6225 kif <td>400 ft</td> <td></td>	400 ft																	
Study Study Steep Floor Copil 650pil 2371pil 4223pil 6171pil 8207pil 10310pil 12483pil 1473spil 17040pil 18779pil 2471spil 2471kil 2528kil 2528kil 0.254kil 0.254kil 0.254kil 0.254kil 0.254kil 0.254kil 0.254kil 0.254kil 0.254kil 0.255kil 0.255kil	450 ft					9-9-									0			
0.0pli 65.0pli 620.pli 237.1pli 422.3pli 617.1pli 820.7pli 1031.0pli 1248.3pli 1473.8pli 1704.0pli 1937.9pli 2177.6pli 2471.4pli 248.4pli 2399.pli 2199.pli 0.250.kli	500 ft																	
0.065 KI 0.172 KI 0.185 KI 0.195 KI 0.204 KI 0.210 KI 0.217 KI 0.225 KI 0.230 KI 0.234 KI 0.234 KI 0.247 KI 0.247 KI 0.247 KI 0.252 KI	Total Stor	ry Shear @ Floor		65.0 plf	Second 1	422.3 plf	617.1 plf	820.7 plf	1031.0 plf	1248.3 plf	1473.8plf	1704.0 plf	1937.9 plf	2177.6plf	2421.4 plf	2668.4 plf	2919.9 plf	3200.0 plf
	Stor	y Force per Floor	0.000 klf	0.065 klf		0.185 kff	0.195 klf	0.204 kff	0.210 klf	0.217 kif	0.225 kF	0.230 kff	0.234 kIf	0.240 kIf	0.244 kff	0.247 kIf	0.252 klf	0.280 kIf

rection
XDi
Sin
MWFR
Force on
Wind
rotal

Floor Level	Int.	2	8	4	5	9	7	oo 8	6	10	II	12	13	14	15	M 2
Length of Building	88.U II	38:UIL	38.0.10	88.U.IL	88:UIL	38.0 It	88.U II	28.U.II	SS.UIL	38:U II	88.U II	38:UII	38.UIL	88.U II	38:UIL	
Frame Story Force per Floor	0.0 k	5.7 k	15.1 k	16.3 k	17.1 k	17.9k	18.5 k	19.1 床	19.8 k	20.3 k	20.6 k	21.1 k	21.5 k	21.7 k	22.1 k	
Frame Story Shear per Floor	281.6 k	281.6 k	275.9 k	260.7 k	244.4 k	227.3 k	209.4 k	190.9 k	171.7 k	151.9k	131.6k	111.1 k	90.0k	68.5 k	46.8 k	

A.2.2 Seismic

Input Information

D	Site Class - Section 1615.1.1
II	Seismic Use Group - Section 1616.2
В	Seismic Design Category - Section 1616.3
.300g	S _S , Spectral Accelerations for Short Periods - Section 1615.1
.075g	S ₁ , Spectral Accelerations for 1 Second Period - Section 1615.1
1.56	F _a , Site Coefficient - Table 1615.1.2(1)
2.4	F _v , Site Coefficient - Table 1615.1.2(2)
0.468	S _{MS} , Maximum Spectral Accelerations for Short Periods - Section 1615.1.2
0.18	S _{M1} , Maximum Spectral Accelerations for 1 Second Period - Section 1615.1.2
0.312	S _{DS} , Design Spectral Accelerations for Short Periods - Section 1615.1.3
0.12	S _{D1} , Design Spectral Accelerations for 1 Second Period - Section 1615.1.3
0.03	C _T , Building Period Coefficient - Section 1617.4.2.1
0.75	X
210.5 ft	h _n , Building Height - Section 1617.4.2.1
1.66	$T_a = C_T * h_n^{3/4}$ - Approximate Fundamental Period - Section 1617.4.2.1
0.077	$T_O = 0.2 * (S_{D1}/S_{DS})$ - Section 1615.1.4
0.385	$T_S = S_{D1}/S_{DS}$ - Section 1615.1.4
0.072	S _a , Spectral Response Acceleration - Section 1615.1.4
1.25	I _e , Seismic Occupancy Importance Factor - Table 1604.5
5	R, Response Modification Factor - Table 1617.6
0.0780	C _S , Seismic Response Coefficient - Section 1617.4.1.1
0.0172	C _S (min) - Section 1617.4.1.1
0.0181	C _S (Max) - Section 1617.4.1.1
0.0181	C _S (Actual) - Section 1617.4.1.1
39,207 k	W, Effective Seismic Weight of Structure - Section 1617.4.1
709.4	$V = C_S *W$ - Seismic Base Shear - Section 1617.4.1
1.579	k, Distribution Exponent - Section 1617.4.3





	5										
			Mass Calo	ss Calculations				Force	Force Calculations	ons	
Floor	Floor-Floor Height (ft)	Area (ft²)	Floor Load (psf)	Perimeter	Wall Loading (psf)	Weight	Height from Ground	$\mathbf{w}_{\mathbf{y}}^{\mathbf{x}}$	Cvx, (Eq. 9.5.4-2)	Story Force (k)	Story Shear (k)
						0 k	210.5 ft	0	0	$0.0\mathrm{k}$	0.0 k
R		21,900	65.0 psf	718 ft	15.0 psf	1424 k	210.5 ft	6632316	0.0889	$63.1\mathrm{k}$	63.1 k
15	14.5 ft	21,900	115.0 psf	718 ft	15.0 psf	2597 k	13 96 L	10,808,579	0.145	102.8 k	165.9 k
14	13.5 ft	21,900	115.0 psf	718 ft	15.0 psf	2669 k	182.5 ft	9,927,131	0.133	94.4 K	$260.3 \mathrm{k}$
13	13.5 ft	21,900	115.0 psf	718 ft	15.0 psf	2664 k	169 ft	8,775,004	0.118	83.5 k	343.8 k
12	13.5 ft	21,900	115.0 psf	718 ft	15.0 psf	2664 k	155.5 ft	7,694,106	0.103	73.2 k	416.9 k
11	13.5 ft	21,900	115.0 psf	718 ft	15.0 psf	2664 k	142 ft	6,666,241	680'0	63.4 k	480.3 k
10	13.5 ft	21,900	115.0 psf	718 ft	15.0 psf	2664 k	128.5 ft	5,693,479	9200	54.2 k	534.5 k
6	13.5 ft	21,900	115.0 psf	718 ft	15.0 psf	2664 k	115 ft	4,778,194	0.064	45.4 k	579.9 k
8	13.5 ft	21,900	115.0 psf	718 ft	15.0 psf	2664 k	101.5 ft	3,923,145	0.053	$37.3\mathrm{k}$	617.3 k
7	13.5 ft	21,900	115.0 psf	718 ft	15.0 psf	2664 k	¥88	3,131,594	0.042	29.8 k	647.0 k
9	13.5 ft	21,900	115.0 psf	718 ft	15.0 psf	2664 k	74.5 ft	2,407,495	0.032	$22.9\mathrm{k}$	669.9 k
5	13.5 ft	23,000	115.0 psf	773 ft	15.0 psf	2802 k	61 ft	1,846,499	0.025	17.6 k	687.5 k
4	13.5 ft	23,000	115.0 psf	773 ft	15.0 psf	2802 k	47.5 ft	1,243,992	0.017	$11.8\mathrm{k}$	699.3 k
3	13.5 ft	23,000	115.0 psf	773 ft	15.0 psf	2802 k	34 ft	733,7 20	0.010	7.0 K	706.3 k
2	13.5 ft	23,000	115.0 psf	773 ft	15.0 psf	2802 k	20.5 ft	330,061	0.004	$3.1\mathrm{k}$	709.4 k
Gnd	20.5 ft	23,000					TOTAL	74,591,555	1.000	709.45	
TOTAL	210.5 ft	355,900				39,207 k					

500 Delaware Ave.	
APPENDIX B: PRELIMINARY MEMBER	
DESIGN	
Elizabeth Hostutler - Structural Option	xiii

GATEWAY PLAZA

Wilmington, Delaware

B.I Post-tensioned Slab

Given: Live Load = 80 psf

<u>Dead Load = 100 psf</u> (assuming 8" thick slab)

Total Load = 180 psf

Preliminary Design:

- Balance Load:
- Net Load: $\omega_n = TL \omega_{pre}$ $\omega_n = 180 \, psf - 90 \, psf = 90 \, psf$
- Design limits
 - O Cover: 3/4" from top and bottom
 - Allowable Stresses: Class U
 - At time of jacking
 - $f'_{c} = 6,000 \, psi$
 - Compression $(18.4.2a) = 0.60 f'_c = 0.6(6,000 psi) = 3,600 psi$
 - Tension $(18.4.2b) = 3\sqrt{f'_c} = 3\sqrt{6000 psi} = 232 psi$
 - At service
 - $f'_c = 6,000 \, psi$
 - Compression = $0.45f'_c = 0.45(6,000 psi) = 2,700 psi$
 - Tension = $6\sqrt{f'_c} = 6\sqrt{6000 psi} = 465 psi$
 - Average pre-compression limits = 125 psi (min)
 = 300 psi (max)
 - o Target Load Balances: 60%-80% of selfweight for slabs. Use 75%

$$\omega_{pre} = 0.75 slab$$

$$\omega_{pre} = 0.75 (100 psf) = 75 psf$$

- Tendon profile
 - o $a_A = 4.0$ "
 - $a_B = \frac{(4.0"+7.0")}{2} 1.75" = 3.75"$
- Prestress Force Required to Balance 70% of selfweight

o
$$w_b = 0.70(100 \, psf)(52.5') = 3675 \, plf = 3.68 \, klf$$

• Force needed in tendons to counteract the load in bay A-B.

$$P = \frac{w_b l^2}{8a_A} = \frac{3.68klf(30')^2}{8(3.75''/12)} = 1323k$$

• Check Precompression

$$\circ #tendons = \frac{(1323k)}{26.6k/tendon} = 49 tendons$$

• Actual force for banded tendons: $P_{actual} = (49tendons)(26.6k) = 1303k$

o Actual precompression stress:
$$\frac{P_{actual}}{A} = \frac{1303k}{630in^2 \times 8''} = 259 \, psi$$

o Check Interior Span Force

•
$$P = \frac{(3.68klf)(30')^2}{8(6'')} = 827k < 1303k$$
 Less force is required in the center bay.

Check balance load for interior

•
$$w_b = \frac{(1303k)(8)(6"/12)}{(30')^2} = 5.7klf$$

•
$$\frac{w_b}{w_{DL}} = \frac{5.7klf}{5.25klf} = 100\%$$

o Effective prestress force, $P_{eff} = 1303 \text{ k}$

For further analysis, this layout was entered into RAM Concept and checked further.

B.2 Columns

Typical Columns Along Column Line 1

k	2	trib. W	30'
\mathbf{A}_{t}	790 sf	fс	6 ksi
span l _{ab}	52.5'	beam	800 plf
span l _{bc}	36'		

	\mathbf{w}_{LL}	A _t (ft ²)	$A_{i} (ft^{2}) = A_{t} x k$	Reduction = $0.25+^{15}/_{\sqrt{Ai}}$	LL (k)	W _{DL}	DL (k)	Pu (k)	W _{uTL} (psf)	FEM _{ab}
R	60	790	1,580	0.63	30	65	72	134 k	3.24	447'k
15	80	1,580	3,160	0.52	65	115	224	373 k	7.98	1100'k
14	80	2,370	4,740	0.47	89	115	336	545 k	7.98	1100'k
13	80	3,160	6,320	0.44	111	115	447	714 k	7.98	1100'k
12	80	3,950	7,900	0.42	132	115	559	883 k	7.98	1100'k
11	80	4,740	9,480	0.40	153	115	671	1050 k	7.98	1100'k
10	80	5,530	11,060	0.40	177	115	783	1223 k	7.98	1100'k
9	80	6,320	12,640	0.40	202	115	895	1397 k	7.98	1100'k
8	80	7,110	14,220	0.40	228	115	1007	1572 k	7.98	1100'k
7	80	7,900	15,800	0.40	253	115	1119	1747 k	7.98	1100'k
6	80	8,690	17,380	0.40	278	115	1230	1921 k	7.98	1100'k
5	80	9,480	18,960	0.40	303	115	1342	2096 k	7.98	1100'k
4	80	10,270	20,540	0.40	329	115	1454	2271 k	7.98	1100'k
3	80	11,060	22,120	0.40	354	115	1566	2445 k	7.98	1100'k
2	80	11,850	23,700	0.40	379	115	1678	2620 k	7.98	1100'k

	b	h	γ	Rn	Kn	ρ	$\mathbf{A}_{\mathbf{s}}$		
R	20 in	20 in	0.80	0.1717	0.0862	0.031	12.4	(8)	#11
15	20 in	26 in	0.85	0.2503	0.1839	0.042	21.84	(14)	#11
14	20 in	26 in	0.85	0.2503	0.2685	0.048	24.96	(16)	#11
13	20 in	26 in	0.85	0.2503	0.3522	0.048	24.96	(16)	#11
12	20 in	26 in	0.85	0.2503	0.4353	0.048	24.96	(16)	#11
11	20 in	26 in	0.85	0.2503	0.5180	0.048	24.96	(16)	#11
10	20 in	26 in	0.85	0.2503	0.6029	0.048	24.96	(16)	#11
9	20 in	30 in	0.87	0.1880	0.5972	0.047	28.2	(18)	#11
8	20 in	30 in	0.87	0.1880	0.6718	0.047	28.2	(18)	#11
7	20 in	30 in	0.87	0.1880	0.7464	0.047	28.2	(18)	#11
6	20 in	30 in	0.87	0.1880	0.8211	0.047	28.2	(18)	#11
5	20 in	30 in	0.87	0.1880	0.8957	0.075	45	(20)	#14
4	20 in	30 in	0.87	0.1880	0.9704	0.075	45	(20)	#14
3	20 in	30 in	0.87	0.1880	1.0450	0.075	45	(20)	#14
2	20 in	30 in	0.87	0.1880	1.1197	0.075	45	(20)	#14

Typical Columns Along Column Line 3

k	2	trib. W	30'
\mathbf{A}_{t}	540 sf	fc	6 ksi
span l _{ab}	52.5'	beam	800 plf
span l _{bc}	36'		

	\mathbf{w}_{LL}	A _t (ft ²)	$A_{i} (ft^{2})$ $= A_{t} x k$	Reduction= $0.25+15/\sqrt{A_i}$	LL (k)	w _{DL} (psf)	DL (k)	Pu (k)	w _{uTL} (psf)	w _{uDL} (psf)	FEM _{bc}
R	60	540	1,080	0.71	23	65	50	96 k	3.24	2.34	152'k
15	80	1,080	2,160	0.57	49	115	153	263 k	7.98	4.14	268'k
14	80	1,620	3,240	0.51	67	115	230	382 k	7.98	4.14	268'k
13	80	2,160	4,320	0.48	83	115	306	499 k	7.98	4.14	268'k
12	80	2,700	5,400	0.45	98	115	383	616 k	7.98	4.14	268'k
11	80	3,240	6,480	0.44	113	115	459	732 k	7.98	4.14	268'k
10	80	3,780	7,560	0.42	128	115	536	847 k	7.98	4.14	268'k
9	80	4,320	8,640	0.41	142	115	612	962 k	7.98	4.14	268'k
8	80	4,860	9,720	0.40	156	115	689	1076 k	7.98	4.14	268'k
7	80	5,400	10,800	0.40	173	115	765	1194 k	7.98	4.14	268'k
6	80	5,940	11,880	0.40	190	115	842	1314 k	7.98	4.14	268'k
5	80	6,480	12,960	0.40	207	115	918	1433 k	7.98	4.14	268'k
4	80	7,020	14,040	0.40	225	115	995	1553 k	7.98	4.14	268'k
3	80	7,560	15,120	0.40	242	115	1071	1672 k	7.98	4.14	268'k
2	80	8,100	16,200	0.40	259	115	1148	1792 k	7.98	4.14	268'k

	b	h	γ	Rn	Kn	ρ	As		
R	18 in	18 in	0.78	0.080	0.076	0.022	7.128	(9)	#8
15	18 in	24 in	0.83	0.080	0.156	0.022	9.504	(12)	#8
14	18 in	24 in	0.83	0.080	0.227	0.08	34.56	(10)	#8
13	18 in	24 in	0.83	0.080	0.296	0.08	34.56	(10)	#8
12	18 in	24 in	0.83	0.080	0.366	0.08	34.56	(10)	#8
11	18 in	24 in	0.83	0.080	0.434	0.08	34.56	(10)	#8
10	18 in	24 in	0.83	0.080	0.503	0.08	34.56	(10)	#8
9	18 in	24 in	0.83	0.080	0.571	0.03	12.96	(16)	#8
8	18 in	28 in	0.86	0.058	0.548	0.03	15.12	(16)	#8
7	18 in	28 in	0.86	0.058	0.608	0.03	15.12	(16)	#8
6	18 in	28 in	0.86	0.058	0.668	0.03	15.12	(16)	#8
5	18 in	28 in	0.86	0.058	0.729	0.05	25.2	(16)	#11
4	18 in	28 in	0.86	0.058	0.790	0.05	25.2	(16)	#11
3	18 in	28 in	0.86	0.058	0.851	0.05	25.2	(16)	#11
2	18 in	28 in	0.86	0.058	0.912	0.05	25.2	(16)	#11

Column Schedule

	C 1	C 2	C 2	C 4	C 5	C (C 7	C 9
	C-1	C-2	C-3	C-4	C-5	C-6	C-7	C-8
	22x 22	18x 18	24x 24	24x 24	22x 22	22x 26	22x 26	
R	(16)- #9	(18)- #4	(18)- #6	(16)- #9	(20)- #8	(16)- #8	(16)- #6	
	2228k	1212k	2218k	2533k	2221k	2389k	2171k	
	22x 26	18x 24	32x 32	22x 26	22x 26	22x 26	22x 26	
15	(16)- #6	(18)- #5	(18)- #7	(16)- #9	(20)- #7	(16)- #9	(16)- #6	
	2171k	1648k	3816k	2520k	2364k	2520k	2171k	
	22x 26	18x 24	32x 32	22x 26	22x 26	22x 26	22x 26	
14	(16)- #6	(18)- #5	(18)- #7	(16)- #6	(20)- #5	(16)- #6	(16)- #6	
	2171k	1648k	3816k	2171k	#N/A	2171k	2171k	
	22x 26	18x 24	32x 32	22x 26	22x 26	22x 26	22x 26	
13	(16)- #6	(18)- #5	(18)- #7	(16)- #6	(20)- #5	(16)- #6	(16)- #6	
	2171k	1648k	3816k	2171k	#N/A	2171k	2171k	
	22x 26	18x 24	32x 32	22x 26	22x 26	22x 26	22x 26	
12	i i			i				
12	(16)- #6	(18)- #5	(18)- #7	(16)- #6	(20)- #5	(16)- #6		
	2170.740k	1647.594k	3815.760k	2170.740k	#N/A	2170.740k	2170.740k	
11	22x 26	18x 24	32x 32	22x 26	22x 26	22x 26	22x 26	
11	(16)- #6	(18)- #5	(18)- #7	(16)- #6	(20)- #5	(16)- #6	(16)- #6	
	2171k	1648k	3816k	2171k	#N/A	2171k	2171k	
10	22x 32	18x 28	32x 32	22x 32	22x 32	22x 30	22x 30	
10	(16)- #6	(18)- #5	(18)- #7	(16)- #6	(20)- #6	(16)- #6	(16)- #6	
	2608k	1886k	3816k	2608k	2677k	2462k	2462k	
	22x 32	18x 28	32x 32	22x 32	22x 32	22x 30	22x 30	
9	(16)- #6	(18)- #5	(18)- #7	(16)- #6	(20)- #6	(16)- #6	(16)- #6	
	2608k	1886k	3816k	2608k	2677k	2462k	2462k	
	22x 32	18x 28	32x 32	22x 32	22x 32	22x 30	22x 30	
8	(16)- #6	(18)- #5	(18)- #7	(16)- #6	(20)- #6	(16)- #6	(16)- #6	
	2608k	1886k	3816k	2608k	2677k	2462k	2462k	
	22x 32	18x 28	32x 32	22x 32	22x 32	22x 30	22x 30	
7	(16)- #6	(18)- #5	(18)- #7	(16)- #6	(20)- #6	(16)- #6	(16)- #6	
	2608k	1886k	3816k	2608k	2677k	2462k	2462k	
	22x 32	18x 28	32x 32	22x 32	22x 32	22x 30	22x 30	
6	(16)- #6	(18)- #5	(18)- #7	(16)- #6	(20)- #6	(16)- #6	(16)- #6	
	2608k	1886k	3816k	2608k	2677k	2462k	2462k	
	22x 32	18x 28	34x 34	22x 32	22x 32	22x 30	22x 30	12x 12
5	(16)- #6	(18)- #5	(18)- #8	(16)- #6	(20)- #6	(16)- #6	(16)- #6	(8)- #4
	2608k	1886k	4387k	2608k	2677k	2462k	2462k	539k
	22x 32	18x 28	34x 34	22x 32	22x 32	22x 30	22x 30	12x 12
4	(16)- #6	(18)- #5	(18)- #9	(16)- #8	(20)- #8	(16)- #8	(16)- #6	(8)- #4
	2608k	1886k	4534k	2827k	2950k	2681k	2462k	539k
3	22x 32	18x 28	34x 34	22x 32	22x 32	22x 30	22x 30	12x 12
3	(16)- #6	(18)- #5	(18)- #11	(16)- #10	(20)- #10	(16)- #10	(16)- #6	(8)- #4
	2608k	1886k	4927k	3126k	3324k	2980k	2462k	539k
	22x 32	18x 28	34x 34	22x 32	22x 32	22x 30	22x 30	12x 12
2	(16)- #6	(18)- #6	(18)- #14	(16)- #11	(20)- #11	(16)- #11	(16)- #6	(8)- #4
	2608k	1980k	5412k	3307k	3551k	3161k	2462k	539k


B.3 Beams

Note: All beams analyzed in a similar manner to the following two procedures.


Detailed Calculation of 52' Post-tensioned beams

Detalled	Caiculat	10H 01 52	Post-te			
Str	esses	Los	ses			
f'c	6000 psi	σ_{ci}	3 ksi			
f_{ci}	5000 psi	σ_{cs}	4 ksi			
f_{pu}	270 ksi	σ_{ti}	0 ksi			
f_{pi}	181 ksi	σ_{ts}	-1 ksi			
f_{py}	243 ksi	η	0.85			
	Input Info	ormation				
L span	53'	A_{ps}	0 sq in			
dc,min	2 in	h	24 in			
Section Properties						
A (in ²)	I (in ⁴)	y _b (in)	yt (in)			
1792	75057	16.1429	7.8571			
z _b (in)	z _t (in)	k _b (in)	k _t (in)			
4650	9553	5.33	-2.59			
	M _{mid-spai}	ı (in-k)				
ω _g (plf)	ω _{LL} (plf)	\mathbf{M}_{\min}	M _{max}			
3600	2.400	10.825	18 0/11			

Selection	on of Force
IV	V
F_i	1078 k
Selection	on of Steel
0.8fpu	216 ksi
0.7fpu	189 ksi
As	5.96 sq in
# _{strands}	39
F_{i}	1080 k
$e_{o,u}$	14 in
$e_{o,l}$	14 in
$e_{o,mid}$	14 in
$e_{o,supp}$	5 in



3000	2,100	10,025	10,011			
1/Fi						
e_o	I	II	III	IV	V	
-30	-0.0027	-0.0011	0.0018	-0.0015	14.1429	
30	0.0019	0.0013	-0.0013	0.0018	14.1429	





Elizabeth Hostutler - Structural Option


Detailed Calculation of 36' Interior Post-tensioned Beam

Detailed Calculation of 30 Three to						
Str	esses	Losses				
f'c	6000 psi	σ_{ci}	3 ksi			
f_{ci}	5000 psi	σ_{cs}	4 ksi			
f_{pu}	270 ksi	σ_{ti}	0 ksi			
f_{pi}	181 ksi	$\sigma_{ m ts}$	-1 ksi			
f_{py}	243 ksi	η	0.85			
Input Information						
L_{span}	36'	A_{ps}	0.15 sq in			
$d_{c,min}$	2 in	h	24 in			
Section Properties						
A (in ²)	I (in ⁴)	y _b (in)	yt (in)			
			J · ()			
1600	56702	17.12	6.88			
1600 z _b (in)	56702 z _t (in)					
		17.12	6.88			
z _b (in)	z _t (in) 8242	17.12 k _b (in) 5.15	6.88 k _t (in)			
z _b (in)	z _t (in) 8242	17.12 k _b (in) 5.15 _{nn} (in-k)	6.88 k _t (in) -2.07			
z _b (in) 3312 ω _g	z _t (in) 8242 M _{mid-spa}	17.12 k _b (in) 5.15	6.88 k _t (in)			

Selection of Force					
IV	V				
F_{i}	430 k				
Selection of Steel					
0.8fpu	216 ksi				
0.7fpu	189 ksi				
As	2.37 sq in				
# _{strands}	16				
F_{i}	443 k				
$e_{o,u}$	15 in				
$e_{o,l}$	15 in				
$e_{o,mid}$	15 in				
e _{o,supp}	5 in				







B.4 Shearwalls

The shearwalls are designed using 4000 psi concrete and use the forces for wind in the north-south direction for the north-south walls and use the forces for seismic activity in the east-west direction. The hand calculations below show preliminary designs and the formulas used in the following spreadsheets.

$$V_u \le \phi V_n$$
$$V_n = V_c + V_s$$

•
$$V_c = 2\sqrt{f'_c}hd = 2\sqrt{4000 psi} (12") (0.8 \times 36' \times 12 in/ft) = 525k$$

$$\bullet V_s = \frac{A_v f_y d}{s}$$

o Horizontal Reinforcing

$$\rho_{h,\min} = 0.0025$$

$$A_{h,\text{min}} = 0.0025(13.5 \times 12")(36 \times 12") = 175in^2$$

$$s_{\text{max}} = \min \begin{cases} \frac{l_w}{5} = 86.4'' \\ 3h = 36'' = 18'' \\ 18'' \end{cases}$$

Try #6 @ 14":
$$A_h = 183in^2$$
, $\rho = 0.0026$

o Vertical Reinforcing

$$\rho_{v, \min} = 0.0025$$

$$\rho_{v} = 0.0025 + 0.5 \left(2.5 - \frac{211'}{36'} \right) \left(0.0026 - 0.0025 \right) = 0.0023 : 0.0025$$

$$s_{\text{max}} = \min \begin{cases} \frac{l_{w}}{3} = 144'' \\ 3h = 36'' = 18'' \\ 18'' \end{cases}$$

Try #6 @ 14":
$$A_v = 183in^2$$
, $\rho = 0.0026$


$$V_s = \frac{A_v f_y d}{s} = \frac{183in^2 (60ksi)(0.8 \times 36' \times 12'')}{14''} = 271k$$

$$V_n = 525k + 271k = 796k$$


$$\phi V_n = 0.75(796k) = 597k$$

GATEWAY PLAZA	Wilmington, Delaware
500 Delaware Ave.	
APPENDIX C:	PLANS
Elizabeth Hostutler - Structural Option	xxii

C.I Composite Steel-Foundation




C.2 Composite Steel-Typical Floor




Elizabeth Hostutler - Structural Option

C.3 Post-tensioned Concrete-Foundation




Post-tensioned Concrete-Floor Framing C.4



FLOORS 2-5 FRAMING PLAN


- INDICATES 8" THK, POST-TENSIONED CONCRETE SLAB. SEE POST-TENSIONED SLAB PLAN. REFER TO BEAM SCHEDULE FOR BEAM SIZES AND REINFORCEMENT.



TYPICAL FRAMING PLAN

INDICATES 8" THK. POST-TENSIONED CONCRETE SLAB. SEE SLAB TENDON PLAN. REFER TO BEAM SCHEDULE FOR BEAM SIZES AND REINFORCEMENT.


C.5 Post-tensioned Concrete-Reinforcement



ONGITUDE TOP REINFORCING PLAN
--- INDICATES COLUMN STRIP REINFORCING.
---- INDICATES MIDDLE STRIP REINFORCING.


Elizabeth Hostutler - Structural Option

XXV111



LONGITUDE BOTTOM REINFORCING PLAN


. ——— INDICATES COLUMN STRIP REINFORCING.
.. ———— INDICATES MIDDLE STRIP REINFORCING.



ATITUDE TOP REINFORCING PLAN

INDICATES COLUMN STRIP REINFORCING. INDICATES MIDDLE STRIP REINFORCING.

Elizabeth Hostutler - Structural Option



JDE BOTTOM REINFORCING PLAN

. ——— INDICATES COLUMN STRIP REINFORCING.

. ---- INDICATES MIDDLE STRIP REINFORCING.

GATEWAY PLAZA	Wilmington, Del	.aware
500 Delaware Ave.		
APPENDIX D: BREADTH STUI	DIES	
Elizabeth Hestutler, Structural Option		:

D.I Mechanical Studies

ASHRAE Standard 62-Ventilation for Indoor Air Quality

Office	A_z (ft ²)	R₽	Pz	Ra	Az (ft²)	V _{bz} (cfm)	V _{oz} (cfm)	V _{pz} (cfm)	Z _P (cfm)	Vou (cfm)	# diffusers	cfm/ duct
I	2911	5	30	0.06	2911	325	325	3782	0.0859	325	6	630
2	3738	5	38	0.06	3738	415	415	4857	0.0855	415	9	540
3	3513	5	36	0.06	3513	391	391	4564	0.0857	391	6	761
4	2137	5	22	0.06	2137	239	239	2776	0.0861	239	4	694
5	2600	5	26	0.06	2600	286	286	3378	0.0847	286	5	676
6	2592	5	26	0.06	2592	286	286	3368	0.0849	286	5	674
Σ	17491				17491		1942			1942		

D.2 Construction Studies

D.2.I Material Takeoffs

	Post-ten	sioned	l Conc	rete		
Beams and Slab from RAM (Beam	Formwo	ork	
Volume	687 CY	Type	#	A	Contact Area	
Perimeter	719'	B-1	1.5	228 SF	341 SFCA	
Floor Area	24000 SF	B-2	7.5	298 SF	2231 SFCA	
Slab thickness	8 in	B-3	2	150 SF	300 SFCA	
Prestressing	26350 lb	<i>B-4</i> 4 168 SF 672 SFCA				
Reinforcing	46.18 tons	<i>B-5</i> 25 140 SF 3500 SFCA				
Slab Formwork	21910 sf	Total 7045 SFCA				
Slab Edge Forms	479 SFCA	Shearwalls				
Colum	ns	#	length	height	Area	
Volume/column	2 CY	6	30'	14'	2430 SF	
# columns/floor	36	2	36'	14'	972 SF	
Volume/floor	72			Total	3402 SF	

	Compo	site Steel	
Structural	Steel: Tak	ceoffs from RAM	Beam
Steel	107 tons	Slab Thickness	4 in
# shear studs	27352	Frames	50 tons
	Firep	roofing	
Веат	#	\boldsymbol{A}	Totals
W24x55	28	295	8260
W24x55	20	202	4040
W24x76	27	185	4995
Column			
W14x120	36	97.4	3506.4

		Caiss	sons			
		Amount	Material	Labor	Equipment	Cost
A1020-310	4'-0" dia. x 100'	20 Ea	4358	70459		\$1,496,329
	5'-0" dia. x 100'	6 Ea	8064	144990		\$918,324
	6'-0" dia. x 100'	10 Ea	11730	172277		\$1,840,069
					TOTAL	\$4,254,722
	Conc	crete Filled	l, Drilled	Piers		
A1020-130	End Bearing Steel Piles					Cost
	4 pile cluster	5	5625	3325		\$44,750
2460	6 pile cluster	8	8425	5025		\$107,600
2480	7 pile cluster	7	9825	5850		\$109,725
2500	8 pile cluster	5	12600	7525		\$100,625
	12 pile cluster	9	15400	9200		\$221,400
	Pile caps, incl. forms and					
03310-240	± ′	612	108	49	0.31	\$96,309
					TOTAL	\$680,409

D.2.2 Estimates


					ne Typical l	
Slabs Systen	m	Amount	Material	Labor	Equipment	Cost
03110-405	Beam formwork	7044 SFCA	0.91	4.05		\$63,466
03110-420	slab edge forms	479 SFCA	0.48	4.6		\$2,432
	slab formwork	21910 sf	1.3	2.86		\$216,471
03210-600	Slab Reinforcing	46.18 tons	800	380		\$72,041
032230-600	Ungrouted Post-tensioned strand	26350 lb	0.47	0.87	0.02	\$58,761
03300-220	6000 psi Concrete	687 CY	109			\$74,883
03310-700	Placing	687 CY	11.5	4.7		\$11.129
	Total					\$499,183
Columns						
03310-240	24"x24" average reinforcing including 4 use forms, concrete, placement, reinforcing	72 CY	370	400	41	\$58,392
	Total					\$58,392
Shearwalls						
B2010-101	12" thick, plain finish, 4000 psi wall including 4 use forms, reinforcing, concrete, placement	3402 sf	6.6	15.35	21.95	\$97,127
	Total					\$97,127
	•				Total	\$654,702


	Estimate of Composi	te Steel D	esign for	One Typ	oical Floor	
Slabs Systen	n	Amount	Material	Labor	Equipment	Total Cost
05310-300	20 ga. 3-1/4" Metal Deck	23403 SF	1.88	0.34	0.02	\$60,380
03210-200	6x6 W1.4xW1.4	234 CSF	19.35	17.35		\$12,649
03300-220	6000 psi concrete	253 CY	81			\$20,478
03310-700	Placing concrete	253 CY		13.1	5.35	\$4,664
05120-260	Curb Edging	718 LF	14	4.95	0.33	\$17,397
	Total					\$98,171
Structural S	teel					
05120-680	Offices over 15-stories	107 TON	1900	345	109	\$251,878
05090-840	3/4" dia Shear Studs	27352	0.49	0.67	0.28	\$57,713
	Total					\$309,591
Frames						
05120-680	Columns, Beams, and Braces	50 TON	1900	345	109	\$117,700
Fireproofing	7					
07800-600	Decking	22000 SF	0.62	0.54	0.09	\$51,260
	Beams	17295 SF	0.41	0.45	0.07	\$31,650
	Columns	3506 SF	0.47	0.62	0.1	\$8,521
	Total					\$91,430
					TOTAL Cost/sf	\$616,892 \$26


D.2.3 Schedule


Purality Sart 1 y 2006										
1 1 1 1 1 1 1 1 1 1		Original Start	lly 2005	August 2005	September 2005	October 2005		December 2005		ebruary 2006
2A 3 29-Jul-05 2 11-Jul-05 A FRIP 2 15-Jul-05 2 13-Jul-05 2 2 19-Jul-05 2 2 19-Jul-05 2 2 19-Jul-05 2 3 21-Jul-05 2 3 21-Jul-05 3 29-Jul-05 3 3 22-Jul-05 3 3 29-Jul-05 3 3 29-Jul-05 3 3 29-Jul-05 3 3 29-Jul-05 3 3 3 2-Jul-05 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3		Duration		31 07		02 09 16 23	30 06 13 20 27	18 25	01 08 15	05 12
2 11-Jul-05 A FRP Col 2 15-Jul-05 3 13-Jul-05 3 13-Jul-05 3 13-Jul-05 3 13-Jul-05 1 18-Jul-05 1 12-Jul-05 1 12-Jul-05 1 12-Jul-05 1 12-Jul-05 1 22-Jul-05 3 29-Jul-05 2 23-Jul-05 2 23-Jul-05 2 23-Jul-05 2 23-Jul-05 2 23-Jul-05 3 23-Jul-05 2 23-Jul-05 3 23-Jul-05 3 23-Jul-05 1 03-Aug-05	Gateway Plaza	156 11-Jul-05 A		0.00						
2 15-Jul-05	F/R/P Columns 1A	2 11-Jul-05 A		Jumns 1A						
2 19-Jul-05 Shoring 3 13-Jul-05 Shoring 3 13-Jul-05 Shoring 3 13-Jul-05 Shoring 1 18-Jul-05 Shoring 1 18-Jul-05 Shoring 1 18-Jul-05 1 19-Jul-05 1 19-Jul-05	F/R/P Columns 1B	2 15-Jul-05*	F.RA	Columns 1B						
3 13-Jul-05 Shoring 3 13-Jul-05 Shoring 3 21-Jul-05 Shoring 1 18-Jul-05 Shoring 1 18-Jul-05 Shoring 1 25-Jul-05 Shoring 1 25-Jul-05 Shoring 1 25-Jul-05 Shoring 1 25-Jul-05 Shoring 2 25-Jul-05 Shoring 2 25-Jul-05 2 25-Jul-05 Shoring 2 25-Jul-05 Shoring 2 25-Jul-05 Shoring 2 25-Jul-05 Shoring 3 22-Jul-05 Shoring 3 22-Jul-05 Shoring 3 22-Jul-05 Shoring 1 03-Jul-05 Sh	F/R/P Columns 1C	2 19-Jul-05	THE THE	/P Columns 1C						
3 19-Jul-05 3 21-Jul-05 1 18-Jul-05 1 26-Jul-05 1 26-Jul-05 1 26-Jul-05 1 26-Jul-05 3 20-Jul-05 3 20-Jul-05 2 29-Jul-05 2 29-Jul-05 2 29-Jul-05 2 29-Jul-05 2 29-Jul-05 3 29-Jul-05 3 29-Jul-05 3 29-Jul-05 1 03-Aug-05 1 03-Aug-05 1 03-Aug-05 1 04-Aug-05 1 08-Aug-05 3 03-Aug-05 1 08-Aug-05 1 08-Aug-05 3 03-Aug-05 1 08-Aug-05 1 08-Aug-05 3 03-Aug-05 3 03-Aug-05	Shoring / Formwork 2A	3 13-Jul-05	Shoring	g/ Formwork 2A						
3 21-Jul-05 1 12-Jul-05 1 12-Jul-05 1 12-Jul-05 1 12-Jul-05 3 20-Jul-05 3 20-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 3 22-Jul-05 3 32-Jul-05 3 32-Jul-05 1 02-Aug-05 1 02-Aug-05 1 03-Aug-05 1 03-Aug-05	Shoring / Formwork 2B	3 19-Jul-05	ნ ₽1	oring / Formwork 2B						
1 18-Jul-05 Reinford 1 18-Jul-05 Reinford 1 22-Jul-05 Reinford 1 25-Jul-05 2 25-Jul-05 1 03-Aug-05 1 03-Aug-	Shoring / Formwork 2C	3 21-Jul-05	Ţ	Shoring / Formwork	2C					
1 22-Jul-05 1 26-Jul-05 1 25-Jul-05 3 26-Jul-05 3 26-Jul-05 3 26-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 3 27-Jul-05 3 27-Jul-05 1 03-Aug-05 1 03-Aug-05	Reinforcement 2A	1 18-Jul-05	Rein	forcement 2A						
1 26-Jul-05 1 19-Jul-05 1 25-Jul-05 3 26-Jul-05 3 26-Jul-05 3 29-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 3 27-Jul-05 3 27-Jul-05 1 03-Aug-05 1 03-Aug-05	Reinforcement 2B	1 22-Jul-05	A.	inforcement 2B						
1 19-Jul-05 1 25-Jul-05 3 26-Jul-05 3 28-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 3 27-Jul-05 3 27-Jul-05 1 03-Aug-05 1 03-Aug-05 1 03-Aug-05 1 06-Aug-05 3 03-Aug-05 3 03-Aug-05 3 03-Aug-05 3 03-Aug-05 3 03-Aug-05	Reinforcement 2C	1 26-Jul-05	J 1	Reinforcement 2C						
1 25-Jul-05 3 20-Jul-05 3 28-Jul-05 1 03-Aug-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 3 27-Jul-05 1 03-Aug-05 1 03-Aug-05	MEP Rough-In 2A	1 19-Jul-05	¥ T 1	Rough-In 2A						
1 27-Jul-05 3 20-Jul-05 3 28-Jul-05 1 03-Aug-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 3 27-Jul-05 3 27-Jul-05 1 03-Aug-05 1 03-Aug-05 1 03-Aug-05 1 04-Aug-05 3 03-Aug-05 3 03-Aug-05 3 03-Aug-05 3 03-Aug-05 3 03-Aug-05	MEP Rough-In 2B	1 25-Jul-05	Ŧ	WEP Rough-In 2B						
3 20-Jul-05 3 26-Jul-05 1 03-Aug-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 27-Jul-05 3 27-Jul-05 1 03-Aug-05 1 03-Aug-05 1 03-Aug-05 1 04-Aug-05 3 03-Aug-05 3 303-Aug-05 1 08-Aug-05 3 303-Aug-05 3 303-Aug-05 3 303-Aug-05 3 303-Aug-05 3 303-Aug-05 3 303-Aug-05 3 303-Aug-05	MEP Rough-In 2C	1 27-Jul-05	Ţ	MEP Rough-In 2C						
3 28-Jul-05 1 03-Aug-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 27-Jul-05 3 27-Jul-05 3 27-Jul-05 1 03-Aug-05 1 03-Aug-05 1 03-Aug-05 1 04-Aug-05 3 03-Aug-05 3 03-Aug-05 3 03-Aug-05 3 03-Aug-05	Pour / Finish /Cure 2A		<u>-</u>	vir / Finish /Cure 2A						
3 29-Jul-05 1 03-Aug-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 3 27-Jul-05 3 32-Jul-05 1 03-Aug-05 1 02-Aug-05 1 08-Aug-05 3 03-Aug-05 3 03-Aug-05 3 03-Aug-05 3 03-Aug-05	Pour / Finish /Cure 2B		7	Pour / Fihish /Cure	32B					
1 03-Aug-05 2 25-Jul-05 2 29-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 2 27-Jul-05 3 3 27-Jul-05 4 3 2 3 27-Jul-05 4 3 3 3 27-Jul-05 1 03-Aug-05 1 03-Aug-05 1 08-Aug-05 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3	Pour / Finish /Cure 2C	3 29-Jul-05	T	Pour / Finish /C	ure 2C				r	
2 25-Jul-05 2 29-Jul-05 2 29-Jul-05 2 25-Jul-05 2 27-Jul-05 2 27-Jul-05 2 27-Jul-05 2 37-Jul-05 2 37-Jul-05 3 3 29-Jul-05 1 03-Aug-05 1 03-Aug-05 1 08-Aug-05 3 3 03-Aug-05 3 3 03-Aug-05	Tension 2	1 03-Aug-05		Tension 2						
2 29-Jul-05 2 03-Aug-05 2 25-Jul-05 2 29-Jul-05 3 3 27-Jul-05 3 3 29-Jul-05 3 3 29-Jul-05 4 3 2 3 29-Jul-05 1 01-Aug-05 1 03-Aug-05 1 08-Aug-05 1 08-Aug-05 3 3 03-Aug-05	Strip / Reshore 2A	2 25-Jul-05	7	Strip / Reshore 2A						
2 25-Jul-05 2 25-Jul-05 2 25-Jul-05 4 3A 3 27-Jul-05 6 3C 3 29-Jul-05 6 3C 3 29-Jul-05 7 1 01-Aug-05 1 03-Aug-05 1 02-Aug-05 1 04-Aug-05 3 3 03-Aug-05 1 08-Aug-05 3 3 03-Aug-05	Strip / Reshore 2B	2 29-Jul-05	<u> </u>	Strip / Reshore	2B					
2 25-Jul-05* 2 27-Jul-05 4 3A 3 27-Jul-05 4 3C 3 02-Aug-05 4 3C 1 01-Aug-05 1 03-Aug-05 1 08-Aug-05 3 3 03-Aug-05 3 3 03-Aug-05	Strip / Reshore 2C	2 03-Aug-05		Strip / Reshore	e 2C					
2 27-Jul-05 x 3A 3 27-Jul-05 x 3B 3 29-Jul-05 x 3C 3 02-Aug-05 x 3C 1 01-Aug-05 1 03-Aug-05 1 04-Aug-05 1 08-Aug-05 3A 3 03-Aug-05	F/R/P Columns 2A	2 25-Jul-05*	5	R/R/P Columns 2A						
K3A 3 27-Jul-05 K3B 3 29-Jul-05 K3C 3 02-Aug-05 1 03-Aug-05 1 03-Aug-05 1 02-Aug-05 1 04-Aug-05 3 03-Aug-05	F/R/P Columns 2B	2 27-Jul-05	T	F/R/P Columns 2B						
K 3A 3 27-Jul-05 K 3C 3 29-Jul-05 K 3C 3 02-Aug-05 1 03-Aug-05 1 03-Aug-05 1 04-Aug-05 1 08-Aug-05 3A 3 03-Aug-05	F/R/P Columns 2C	2 29-Jul-05	T	F/R/P Columns	3C					
k 3B 3 29-Jul-05 k 3C 3 02-Aug-05 1 03-Aug-05 1 03-Aug-05 1 02-Aug-05 1 04-Aug-05 3 03-Aug-05	Shoring / Formwork 3A		F	Shoring!/ Formwor	rk 3A					
k 3C 3 02-Aug-05 1 01-Aug-05 1 03-Aug-05 1 02-Aug-05 1 04-Aug-05 1 08-Aug-05 3A 3 03-Aug-05	Shoring / Formwork 3B	3 29-Jul-05	₹	Shoring/ Form	work 3B					
1 03-Aug-05 1 03-Aug-05 1 02-Aug-05 1 04-Aug-05 1 08-Aug-05 3 03-Aug-05	Shoring / Formwork 3C	3 02-Aug-05		Shoting / Form	nwork 3C					
1 03-Aug-05 1 02-Aug-05 1 04-Aug-05 1 08-Aug-05 3 03-Aug-05	Reinforcement 3A	1 01-Aug-05		Reinforcement 3	3A					
1 05-Aug-05 1 02-Aug-05 1 04-Aug-05 1 08-Aug-05 3A 3 03-Aug-05	Reinforcement 3B	1 03-Aug-05		Reinforcement	38					
1 02-Aug-05 1 04-Aug-05 1 08-Aug-05 3A 3 03-Aug-05	Reinforcement 3C	1 05-Aug-05		Reinforcemen	30					
1 04-Aug-05 1 08-Aug-05 3A 3 03-Aug-05	MEP Rough-In 3A	1 02-Aug-05		MEP Rough-In	3A					
3A 3 03-Aug-05	MEP Rough-In 3B	1 04-Aug-05		MER Rough-In	138					
3 03-Aug-05	MEP Rough-In 3C	1 08-Aug-05		MER Rough	r-In 3C					
Pt 000000000000000000000000000000000000	Pour / Finish /Cure 3A	3 03-Aug-05		Pour /Finish /	/Cure 3A					
					_	-				


Activity Name		Start	ily 2005	August 2005	100	September 2005	October 2005	November 2005	December 2005	January 2006	ebruary 2006
	Duration		10 17 24	31 07 14	21 28	14 21 28 04 11 18 25	02 09 16 23	30 06 13 20 27	7 04 11 18 25	01 08 15 22 2	29 05 12 19
Pour / Finish /Cure 3B	3	3 05-Aug-05		no'd	r/Finish	Pour / Finish /Cure 3B					
Pour / Finish /Cure 3C	8	3 09-Aug-05		a T	ur / Finis	Pour / Finish /Cure 3C					
Tension 3C	-	1 12-Aug-05		F¹	Tension 3C						
Strip / Reshore 3A	2	2 08-Aug-05		易日	Strip / Reshore 3A	re 3A					
Strip / Reshore 3B	2	2 10-Aug-05		to.	Strip / Reshore 3B	ore 3B					
Strip / Reshore 3C	2	2 15-Aug-05		7	Strip / R	Strip / Reshore 3C					
F/R/P Columns 3A	2	2 08-Aug-05		E T	F/R/P Columns 3A	ns 3A					
F/R/P Columns 3B	2	2 10-Aug-05		7	F/R/P Columns 3B	nns 3B				0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	
F/R/P Columns 3C	2	2 12-Aug-05		P	F/R/P Cc	F/R/P Columns 3C					
Shoring/Formwork 4A	3	3 10-Aug-05		S.	oring/Fo	Shoring/Formwork 4A					
Shoring/Formwork 4B	3	3 12-Aug-05			Shoring/	Shoring/Formwork 4B					
Shoring/Formwork 4C	3	3 16-Aug-05		Ţ	Shoring	Shoring/Formwork 4C					
Reinforcement 4A	-	1 15-Aug-05		T	Reinforce	Reinforcement 4A					
Reinforcement 4B	•	1 17-Aug-05		T	Reinford	Reinforcement 4B					
Reinforcement 4C	-	1 19-Aug-05		T	Reinfo	Reinforcement 4C					
MEP Rough-In 4A	-	1 16-Aug-05		F	MEP Ro	MEP Rough-In 4A					
MEP Rough-in 4B	-	1 18-Aug-05		J .1	MEP R	MEP Rough-in 4B					
MEP Rough-in 4C	-	22-Aug-05		-	MEP MEP	MEP Rough-in 4C					
Pour/Finish /Cure 4A	3	3 17-Aug-05		•	Pour/F	Pour/Finish /Cure 4A					
Pour/Finish /Cure 4B	3	3 19-Aug-05		•	Pod.	Pour/Finish /Cure 4B					
Pour/Finish /Cure 4C	3	3 23-Aug-05			2	Pour/Finish /Cure 4C					
Tension 4	-	1 26-Aug-05			Ţ	Tension 4					
Strip/Reshore 4A	2	2 22-Aug-05		T	Strip	Strip/Reshore 4A					
Strip/Reshore 4B	2	2 24-Aug-05			ts T	Strip/Reshore 4B					
Strip/Reshore 4C	2	2 26-Aug-05			7	Strip/Reshore 4C					
F/R/P Columns 4A	2	2 22-Aug-05			F/R	F/R/P Columns 4A					
F/R/P Columns 4B	2	2 24-Aug-05			古	F/R/P Columns 4B					
F/R/P Columns 4C	2	2 26-Aug-05			₽	F/R/P Columns 4C					
Shoring/ Formwork 5A	9	3 24-Aug-05			5	Shoring/ Formwork 5A	5A :				
Shoring/ Formwork 5B	3	3 26-Aug-05			Ţ	Shoring/ Formwork 5B	K 5B				
Shoring/ Formwork 5C	3	3 30-Aug-05			7	Shoring/ Formwork 5C	ork 5C				
Reinforcement 5A	-	1 29-Aug-05			J	Reinforcement 5A					
Reinforcement 5B	•	1 31-Aug-05			Ţ	Reinforcement 5B					
Reinforcement 5C	•	1 02-Sep-05			<u>J</u>	Reinforcement 5C	ξς 				
Actual Work		Critical Remaining Work	ning Work	8	Summary	Page 2 of 9		TASK filter: All Activities	s		
	0.00					_					

















GATEWAY PLAZA	Wilmington, Delay	vare
500 Delaware Ave.		
Elizabeth Hostutler - Structural Option		xlvi