77 K STREET

Washington, DC



Todd Povell Dr. John Messner October 5, 2007

77 K Street

Technical Assignment #1

Table of Contents

Executive Summary	
Client Information	
Project Delivery System	<u> </u>
General Contractor Staffing Plan	
Local Conditions	
Site Plan	
Building Systems Summary	10
Schedule Summary	
Cost Summary	14
Appendix A: Project Delivery Selection System	18
Appendix B: R.S. Means Source Data	21

Executive Summary

The 77 K Street project is a class A core and shell office base building project consisting of 11 above grade levels and 3 levels of below grade parking garage. The site is located at the intersection of 1st and K Streets in Washington, DC in the North of Massachusetts development district north of the Capitol Building. The project includes approximately 350,000 gross square feet of above grade office space and an additional 100,000 square feet of below grade parking.

The project is not pursuing LEED certification though the idea was considered. ING Clarion approached Brookfield Properties with the idea of looking into obtaining a LEED rating. After conducting a LEED benchmark survey, the design team realized that the building only achieved a 4.8% energy savings, significantly shy of the 14% minimum LEED prerequisite requirement. Because the idea was first considered late in the project and significant time and cost implications would be incurred, the project team opted not to pursue certification though minor LEED items are being pursued for the sake of sustainability and efficiency.

The following report provides a comprehensive overview of the 77 K Street project. Delivery method, contractual relationships, major building systems, schedule, and cost are all explored in an effort to both study the existing project conditions and explore alternative methods. Of particular interest for future study is the sequencing of the project, in particular the building envelope.

Client Information

The owner of this project, 77 K Street LLC, is a joint venture between Brookfield Properties and ING Clarion. The original partnership at project startup was between Cafritz Company and ING Clarion but in July 2006 Brookfield Properties replaced Cafritz Company and the partnership as it is today was born.

Brookfield Properties is a New York City based real estate company with buildings in twelve major cities in the United States and Canada. In June 2006, Brookfield Properties purchased Trizec Properties, Inc. and Trizec Canada, Inc. for a price of US \$8.9 billion. As part of the company's expansion, they saw an opportunity to enter the Washington, DC construction and development market by buying into the 77 K Street partnership in July 2006, one month after the merger. They believed that their investment in a project already underway would prove more beneficial than starting on a new development project.

Brookfield Properties had a number of goals and expectations that they sought to achieve on the project.

Tenant: Though none have been named to date, the developer is seeking to lease

the building to either a government or private sector tenant on a minimum

ten year lease.

Cost: The firm is extremely determined to finish the project within budget.

Their decision to abandon contract negotiations with a general contractor in favor of opening up the project to a competitive bid in an effort to drive

down the costs is a testament to this.

Quality: The building is class A construction. The owner wants high quality

finishes and a first class commercial environment.

Schedule: Schedule is important and the contractor must meet the substantial

completion date of July 18, 2008 and the final completion date of


September 18 or face liquidated damages.

Safety: Above all the project must achieve the above objectives with a superb

safety record and no accidents resulting in lost time or injury.

If the project team is able to successfully meet these objectives by providing a high quality end product within budget with a minimal number of change orders and on time, the owner will be a satisfied client. Of primary importance, the owner is targeting the exterior skin enclosure as a sequencing issue of particular importance. They are pushing Davis to get the facade erected soon after topping out the concrete in order to allow critical interior work to commence.

Project Delivery System



Contractual Arrangements


This project was developed via a design-bid-build delivery system. The ownership entity, 77 K Street LLC, sought to invest in a commercial development project in Washington, DC. After Davis, Carter, Scott developed a design the project was put out to bid. The initial general contractor selection was based on a negotiated contract but after the owner sought a cheaper bid, the project was put out for competitive bid to a group of three shortlisted contractors. The ultimate decision was based on a number of criteria including cost, schedule, contractor's team, reputation, and qualifications with similar sized projects. Davis won the job in November 2006.

The owner-general contractor agreement is AIA A111, a cost plus fee contract with a guaranteed maximum price. The guaranteed maximum price for the project is \$41,005,150 with a stipulated, lump sum fee of \$1,372,221. The contract includes clauses for increases in the fee based upon approved increases in the cost of construction. Additionally, there are stipulations for liquidated damages starting at \$1,000 per day for delays in substantial completion.

The owner-general contractor agreement requires that James G. Davis Construction Corporation obtain the following insurance policies: Worker's Compensation, Employer Liability, Commercial General Liability, Automobile Liability, Umbrella Liability with a minimum limit of \$50,000,000 per occurrence, Contractor's Pollution Liability, Pollution Legal Liability, Professional Liability, and All Risk. The contract does not require the purchase of payment or performance bonds though Davis Construction does require most subcontractors that furnish and install work to be bonded.

Based upon the "Project Delivery Selection System" developed by Victor Sanvido, the model would suggest that the project be delivered via a traditional design-bid-build arrangement with a lump sum contract between the owner and the general contractor. Though the traditional arrangement was utilized on the 77 K Street project, the owner opted for a cost plus fixed lump sum fee contract with a guaranteed maximum price. Overall, I would agree that the traditional delivery method was the best choice for this project but I would disagree with the model and suggest that a cost plus fee contract, as was utilized, allowed the owner to achieve a reduced construction cost and minimize their financial risk. The "Project Delivery Selection System" decision tree can be found in Appendix A.

General Contractor Staffing Plan



The general contractor's staffing is appropriate for the scope of the work being performed. As with most companies, the senior project manager as well as the administrator, accountant, and vice president do not work exclusively on this project. The two project managers, one assistant project manager, and two superintendents on the other hand do devote one hundred percent of their time to the 77 K Street project. Two field employees overseeing the trades in addition to three management staff devoted to this project is an adequate level of staffing. Of note, during the course of the project Greg Ghent was promoted from the position of Assistant Project Manager to the position of Project Manager.

A staff to volume ratio was calculated yielding a result of 0.022.

$$SV\ Ratio = \frac{Staff\ Base\ Salary}{Volume}$$

A general contractor's goal is to have a SV ratio between 2 and 3 percent. Thus, the project is adequately staffed.


Local Conditions

Washington, DC has an ordinance restricting the height of all buildings in order to prevent any structure from standing taller than the nation's capitol building. Consequently, designers have turned to concrete design to maximize their design potential. Cast in place concrete allows for long spans with a decreased floor to floor height as compared to steel construction. When concrete is post tensioned, even longer spans are possible, such is the case in the 77 K Street project. By reducing floor heights and providing open floor plans, developers are able to maximize their rental space square footage in the district. Consequently, nearly every newly constructed building within Washington, DC will have a concrete structural system.

Do to the project's location and congested site space, parking is not provided on site for subcontractors. This was clearly outlined in the general scope of work provided to each contractor during the bidding process. Numerous pay parking facilities are in the surrounding area though.

Tipping fees for garbage disposal are approximately \$850 per 20 CY dumpster. This includes pickup, disposal, and return of the dumpster. Dumpsters 40 CY in size are approximately double this cost. Recycling efforts were not pursued on this project.

The project is located in what is known as the Coastal Plain Physiographic Province of Washington, DC which contains mostly sedimentary soil materials. Stratum I which extends to a depth of between 13 and 22 feet below site grade consists of old fill predominantly composed of silty, clayey, and gravelly sand with varying amounts of organics, rock fragments, and gravel, as well as soils with stiff consistencies, classified as sandy clay. Stratum II which is first encountered at a depth between 13 and 22 feet below site grade consists of loose to dense silty and clayey sand with varying amounts of gravel and rock fragments. It also consists of cohesive soils classifying as clay with varying amounts of silt and sand. Such soil conditions in combination with groundwater conditions encountered at a depth between 18 and 39 feet below grade warranted the design of a mat foundation system.



SENIOR THESIS

77 K STREET

Technical Assignment #1

Building Systems Summary

YES	NO	WORK SCOPE
Х		Demolition Required
	X	Structural Steel Frame
X		Cast in Place Concrete
X		Precast Concrete
X		Mechanical System
X		Electrical System
	X	Masonry
X		Curtain Wall
X		Support Excavation

Demolition

The project is being constructed on the lot of the former 65 K Street building. 65 K Street was a two story masonry building with a basement. The building sat on 16,486 SF at the northwest corner of the lot. A fifty-two car asphalt parking lot wrapped around the south and east sides of the building. Demolition of the existing building was not included in the scope of work for the 77 K Street contract. The removal of 65 K Street, the asphalt parking lot, select utility lines, and certain site features took place prior to the general contractor selection for the new building.

Cast in Place Concrete

77 K Street is a cast in place concrete structure with a foundation system composed of 60" diameter concrete caissons and a mat foundation, each constructed with 4,000 psi concrete. Typical columns have a compressive strength of 5,000 psi with select columns having increased capacity up to 10,000 psi. Slab capacities range from 3,000 psi at the lowest garage level to 5,000 psi for above grade slabs. Additionally, all slabs are post tensioned with a force of between 130 and 1290 kips. Concrete is placed using two tower cranes, both staged within the footprint of the building.

Precast Concrete

The facade of the structure is a precast and glazing system. Precast panels are either exposed architectural cladding or support units with stone veneer. Precast pieces are being casted by Universal Concrete Products Corporation in Stowe, Pennsylvania and being erected by E.E. Marr Erectors. The southern and western facades will be erected utilizing the tower cranes already mobilized on site by the cast in place concrete contractor, Miller & Long. The precast on the northern and eastern facades will be erected using a mobile crane stationed on the sidewalk within the project worksite. Precast panels will be connected to the structure by embeds cast into the concrete during slab pours.

Mechanical System

The base building project has mechanical rooms located in the core of each floor with the primary mechanical equipment located on the roof of the building. Three 91,560 CFM cooling tower units supply chilled air to the building. Each floor contains a 27,000 CFM air conditioning unit for distribution to VAV boxes located in the tenant spaces. In order to reduce the fire risk to the building, above grade levels have a wet pipe fire suppression system, whereas the garage and loading dock areas have a typical dry pipe suppression system.

Electrical System

77 K Street contains a standard 408/277V and 208/120V electrical system. The main switchgear room, located on the P1 level, contains three 4000A switchboards. Two of which power the normal operations of the building with the third dedicated to emergency systems. A 750kW diesel powered generator located on the roof powers the emergency systems in case of a power outage. Power is distributed throughout the building by 4000A plug-in feeder busways and panelboards ranging in size from 150 to 400 amps.

Curtain Wall

The exterior of the building is a precast cladding and glass curtain wall system. Precast panels are attached at each slab level and extend both horizontally as well vertically throughout the building. Insulating vision glass windows and shadow boxes contain metal mullions with metal mullions extending through precast elements to create a linear visual appearance. At the lower lobby entrances precast panels support a granite veneer. Precast and glazing system design will be closely coordinated between Universal Concrete Products Corporation and TSI Exterior Wall Systems, Inc. The curtain wall will be constructed using the tower cranes, mobile cranes, and from within the building.

Support of Excavation

In order to support the excavation of the three level underground parking garage, a system of piles, soldier beams, lagging, and tiebacks was utilized. Testing by ECS Mid Atlantic estimated that groundwater would be found between 18 an 39 feet below site grade, thus a temporary dewatering system was installed during excavation and construction with a discharge on the southeast corner of the building on 1st street. Discharge rates in the range of 50 to 100 gallons per minute were to be expected and additional sump pumps were needed as excavation progressed. A permanent sump pump is to be installed in the building as well.

Schedule Summary

Excavation of the lot began in mid-December 2006. The project required that the excavating crew remove soil to an approximate depth of thirty-four feet below street level. Given the limited site space and the need for an open excavation pit to pour the mat foundation, a pile, lagging, soldier beam, and tie back system was used. In late March work on the foundation system began. The forming and pour proceeded from the north to the south. Soon after the mat pour, erection of the tower cranes began.

As the summer progressed the concrete crew worked its way out of the hole and made its way up to street level by mid-July. From this point forward, the concrete crew is given ten days to complete each floor, though anticipated production was expected to only take eight. A critical sequencing date occurs on November 16th. Concrete shoring and reshoring occupies five levels below the current work crew. On the 16th of November the concrete crew is scheduled to begin work on level 11. This will allow a mobile crane to begin erecting precast on the east elevation on levels 1 through 5. If the reshoring is still in place because of a delay in the concrete crew, there will be a delay in the enclosure of the building. Window installation will follow a similar procession as the precast installation.

Mechanical and plumbing installation will begin in October 2007 with the installation of plumbing risers followed by ductwork, mechanical piping, plumbing, fixtures, and finally VAV boxes. Electrical installation will begin in January 2008 followed by the fire protection sprinkler contractor soon thereafter.

Also beginning in January 2008 the drywall and masonry contractors will begin their work on the second level with the stone, miscellaneous metals, ceramic tile, painting and specialty contractors following soon thereafter. The drywall contractor is allotted approximately forty days per floor but will essentially be working throughout the entire building from January through late March 2008.

Substantial completion is July 17, 2008 with a two month punchlist period following. The final completion date is September 18, 2008.

EET				1 00 11101	Apr M	lay Jun Jul	I Aug Sep Oct	Nov Dec Jan	eb Mar	Apr	May Jun	Jul Aug Sep Oct Nov Dec	Jan Feb Mar	Apr May	Jun Jul	Aug Sep Oct
	909 03-Jan-05							i i i i	i i		i i				▼ 17-J	ul-08, 77 K STREE
/ CONTRACTOR SELECTION	470 03-Jan-05					. 05		03-Nov-06, DESIGN / C	ONTRACTO	R SELE	CTION					
Initial Planning through CDs	293 03-Jan-05			Initial I	Planning thro	ugh CDs										
0 General Contractor Selection	33 20-Sep-06	03-Nov-06						General Contractor Sele	: :							
O Project Awarded to Davis	0 03-Nov-06							Project Awarded to Davi	3							
RUCTION	430 17-Nov-06														1/-J	ul-08, CONSTRUC
0 Notice to Proceed	0 17-Nov-06							◆ Notice to Proceed								
0 Excavation	112 18-Dec-06	-									Excava					
0 Foundation and Substructure	94 23-Mar-07											Foundation and Substructure		Superstructure	Concrete	
Superstructure ConcreteMechanical and Plumbing	167 03-Aug-07		 											- Superstructure		cal and Plumbing
Nechanical and Plumbing Precast Fascade	193 05-Oct-07 79 20-Nov-07*	01-Jul-08 07-Mar-08											Pr	ecast Fascade	Wechan	car and r furnishing
5 Windows	110 12-Dec-07												- ''	; ;	indows	
Drywall and Accoustical Ceiling T		16-May-08												1 1	rywall and Accoust	ical Ceiling Tile
Electrical and Fire Alarm	126 08-Jan-08	01-Jul-08													Flectrica	l and Fire Alarm
0 Elevators	100 22-Jan-08		 									- 			= Elevators	
0 Fire Protection	59 22-Jan-08													Fire Protect		
0 Completely Watertight	0 09-Apr-08	117\p1-00												◆ Completely	1 1 1	
5 MEP System Start-Up	0 09-May-08														P System Start-Up	
0 Final Inspections	11 02-Jul-08	16-Jul-08														Inspections
Substantial Completion	0 17-Jul-08	10 001 00	 													stantial Completion

Cost Summary

BUILDING CONSTRUCTION					
Construction Cost	\$41,005,150				
Cost Per Square Foot	\$91.30				

TOTAL PROJECT					
Project Cost	\$125,000,000				
Cost Per Square Foot	\$278.32				

BUILDING SYSTEM OVERALL AND SQUARE FOOT COSTS					
03300	Cast in Place Concrete	\$11,296,000	\$25.15		
03450	Precast Concrete	\$2,950,000	\$6.57		
08800	Curtainwall	\$3,734,000	\$8.31		
09250	Drywall	\$1,482,000	\$3.30		
14200	Elevators	\$2,334,000	\$5.20		
15000	Mechanical & Plumbing	\$4,764,000	\$10.61		
15300	Fire Protection	\$605,000	\$1.35		
16000	Electrical System	\$3,588,000	\$7.99		

D4Cost 2002 Estimate

	77 K -	Jan 2007 - District o	f Columbia		
3.	Prepared By: T. Povell		Prepared For:		
	Fax: Building Sq. Size: 449130 Bid Date: 9/1/2006 No. of floors: 14 No. of buildings: 1 Project Height: 130 1st Floor Height: 14 1st Floor Size: 31173		Site Sq. Size: Building use: Foundation: Exterior Walls: Interior Walls: Roof Type: Floor Type: Project Type:	Fax: 159840 Commercial CON PRE GYP MEM CON NEW	
Division		Percent		Sq. Cost	Amount
01	General Requirements General Requirements Untitled	3.75 3.75 0.00		3.18 3.18 0.00	1,426,838 1,426,838 0
03	Concrete Concrete	23.75 23.75		20.14 20.14	9,044,484 9,044,484
04	Masonry Masonry	2.96 2.96		2.51 2.51	1,127,786 1,127,786
05	Metals Metals	17.40 17.40		14.75 14.75	6,626,330 6,626,330
06	Wood & Plastics Wood & Plastics	1.17 1.17		1.00 1.00	447,411 447,411
07	Thermal & Moisture Protection Thermal & Moisure Protection	1.27 1.27		1.08 1.08	482,829 482,829
08	Doors & Windows Doors & Windows	5.76 5.76		4.89 4.89	2,194,545 2,194,545
09	Finishes Finishes	15.70 15.70		13.31 13.31	5,979,316 5,979,316
10	Specialties Specialties	1.02 1.02		0.86 0.86	387,890 387,890
11	Equipment Equipment	0.29 0.29		0.25 0.25	111,354 111,354
14	Conveying Systems Elevators	2.64 2.64		2.24 2.24	1,005,525 1,005,525
15	Mechanical Mechanical	12.71 12.71		10.78 10.78	4,840,11 5 4,840,115
16	Electrical Electrical	11.58 11.58		9.82 9.82	4,409,753 4,409,753
Total Bui	ilding Costs	100.00		84.80	38,084,177
02	Site Work Site Work	100.00 100.00		21.97 21.97	3,512,253 3,512,253
Total No	n-Building Costs	100.00		21.97	3,512,253
Total Pro	eject Costs ==	-		-	41,596,430

R.S. Means 2007 Estimate

Please reference Appendix B for R.S. Means sources for square foot costs.

Office Building Space

11 floors, 346,431 SF, 772 LF Perimeter, 11'-9" floor height

Exterior Wall	S.F. Area	260000	346,431	400000
Exterior vvali	L.F. Perimeter	530	573	600
Precast Concrete Façade	R/Concrete Frame	\$117.40	\$113.02	\$110.30
	Perimeter Adjustment	\$3.65	\$2.85	\$2.35
	Story Height Adjustment	\$1.85	\$1.54	\$1.35

Square Footage Estimate	\$113.02
Perimeter Adjustment	\$5.67
Story Height	\$2.65
Adjusted Square Foot Cost	\$121.34

Underground Parking Garage Space

3 floors, 102,699 SF, 737 LF Perimeter, 10' floor height

Exterior Wall	S.F. Area	100000	102,699	125000
Exterior wall	L.F. Perimeter	900	911	1000
Reinforced Concrete	R/Concrete Frame	\$63.35	\$63.20	\$62.00
	Perimeter Adjustment	\$1.00	\$0.98	\$0.85
	Story Height Adjustment	\$0.85	\$0.84	\$0.80

Square Footage Estimate	\$63.20
Perimeter Adjustment	-\$1.71
Story Height	\$0.00
Adjusted Square Foot Cost	\$61.49

	SQUARE FOOTAGE	COST/SF	TOTAL COST
Office Building Space	346,431	\$121.34	\$42,035,900
Underground Parking Garage Space	102,699	\$61.49	\$6,315,000
			\$48,350,900
R.S. Mear	ns Location Factor (Was	hington, DC)	0.98
	To	otal Estimate	\$47,383,882


The D4Cost estimate proved to be extremely accurate, wavering from the actual GMP contract by only \$600,000. Though the per square footage costs of the individual systems were not directly on par with the actual building system costs, the overall estimate was still very accurate and shows how potentially useful the software package can be.

R.S. Means on the other hand wavered quite substantially from the actual project costs. The estimate was nearly \$6.5 million, or fifteen percent, over the project costs. Efforts were made to account for the underground parking structure of the 77 K Street project by combining estimates using two facility types, underground parking garage and 11-20 story office building. Nonetheless, the R.S. Means estimate of the office building square footage alone was over the actual project costs even without considering the additional space in the garage.

Of note though, the 77 K Street project is a base building job. Consequently, tenant build out is not included in the contract whereas the R.S. Means estimate does include the base building and tenant build out costs associated with office building construction. This discrepancy in the project scope is a likely factor in the cost discrepancy between the R.S. Means estimate and the actual project's costs.

APPENDIX A

Project Delivery Selection System



SLOPE DEFINITION		WELL DEFINED SCOPE	UNDEFINED SCOPE	WELL DEFINE	UNDEFINED SCOPE
	121	1	2	3	4
12	CELL NUMBER	ORGANIZATIONAL STRUCTURE	ORGANIZATIONAL STRUCTURE	CONTRACT STRATEGY	CONTRACT STRATEGY
	1	TD	CMA, CMGC	LS	GMP, CPF
4.	2	TD, D/B	CMGC, CMA	LS	GMP
	3	TD	CMA, CMGC	LS	GMP, CPF
1	4	TD, D/B	CMGC	LS	GMP
	5	TD	CMA	LS	GMP
	6	TD	CMA	LS	GMP
. 1	7	TD, CMA	CMA	LS	GMP
	8	TD, CMA	CMA	LS	GMP
	9	TD	CMA, CMGC	LS	GMP
	10	TD, D/B	CMGC, CMA	LS	GMP
	11	TD TD	CMA, CMGC	LS	GMP
	12	TD, D/B, CMGC	CMA, CMGC	LS	GMP
	13		DON'T BUILD	DON'T BUILD	DON'T BUILD
	14	DON'T BUILD DON'T BUILD	DON'T BUILD	DON'T BUILD	DON'T BUILD
	. 15	DON'T BUILD	DON'T BUILD	DON'T BUILD	DON'T BUILD
	16	DON'T BUILD	DON'T BUILD	DON'T BUILD	DON'T BUILD
	17	CMA, D/B	CMGC, CMA, D/B	GMP, CPF	CPF, GMP
	18	CMGC, D/B	CMGC, CMA, D/B	GMP	CPF, GMP
	19	D/B, CMA	CMGC, CMA, D/B	CPF	CPF, GMP
1	20	CMGC, D/B	CMGC, CMA	GMP	CPF, GMP
- 1	21	CMA	CMA	GMP, LS	GMP
1	22	CMA	CMA	GMP, LS	GMP
ŀ	23	CMA	CMA	GMP	GMP
- t	24	CMA	CMA	GMP	GMP
ł	25	D/B, CMA	CMGC, D/B	GMP	CPF, GMP
ŀ	26	D/B, CMGC	CMGC, D/B	GMP	CPF, GMP
-	27	D/B, CMA	CMA, D/B	GMP	CPF, GMP
ŀ	28	D/B, CMGC	CMA, D/B	GMP	CPF, GMP
1	29	DON'T BUILD	DON'T BUILD	DON'T BUILD	DON'T BUILD
- 1	30			DONTBUILD	DON'T BUILD
ŀ		DON'T BUILD	DON'T BUILD	DON'T BUILD	DON'T BUILD
ŀ	31 32	DON'T BUILD DON'T BUILD	DON'T BUILD DON'T BUILD	DON'T BUILD	DON'T BUILD

LEGEND (Organizational Structure):

TD- Traditional D/B- Design-Build

CMA- Construction Management (Agency)

CMGC- Construction Management (General Contractor)

Table 5: The PDSS Model - Tabulated Solutions

LEGEND (Contract Strategy):


LS - Lump Sum

GMP- Guaranteed Maximum Price CPF- Cost Plus Fee


GCM@RISK

APPENDIX B

R.S. Means Source Data



Reference R.S. Means 2007, Page 180



Reference R.S. Means 2007, Page 138