

# TURNBERRY TOWER ARLINGTON

ARLINGTON, VIRGINIA



Lawrence P. Warner Jr.

Construction Management

Dr. David Riley

April 7<sup>th</sup>, 2009

Final Thesis Report

Table of Contents

**1. Abstract..... 4**

**2. Acknowledgements ..... 5**

**3. Executive Summary ..... 6**

**4. Project Introduction ..... 7**

**5. Project Team Overview..... 7**

    5.1 Client Information ..... 7

    5.2 Project Delivery System ..... 9

    5.3 Project Staffing Plan ..... 10

**6. Existing Conditions ..... 11**

    6.1 Site Plan of Existing Conditions ..... 11

    6.2 Local Conditions ..... 11

    6.3 Demolition of Existing Building ..... 12

**7. Project Logistics..... 12**

    7.1 Project Schedule Summary ..... 12

    7.2 Detailed Project Schedule ..... 14

    7.3 Project Cost Evaluation ..... 15

    7.4 General Conditions Estimate..... 17

    7.5 Detailed Structural System Estimate ..... 17

**8. Introduction to Thesis Analysis ..... 20**

**9. Analysis 1 – Window Wall Attachment with Reinforced Concrete ..... 21**

    9.1 Introduction ..... 21

    9.2 Problem Statement ..... 21

    9.3 Goal ..... 21

    9.4 Research Steps ..... 22

    9.5 Tools ..... 22

    9.6 Expected Outcome ..... 22

    9.7 Use of Post Tension Concrete ..... 22

    9.8 Redesigning the Floor Slabs Using Direct Design Method ..... 23

    9.9 Scheduling the Project: Post Tension Concrete vs. Reinforced Concrete ..... 25

9.10 Schedule Comparison..... 26

9.11 Cost Comparison between Post Tension Concrete Slabs and Reinforced Concrete Slabs ..... 26

    9.11.1 Post Tension Concrete ..... 27

    9.11.2 Reinforced Concrete Removing One Story ..... 29

    9.11.3 Reinforced Concrete Adjusting Story Heights..... 30

9.12 Conclusion & Recommendation..... 31

**10. Analysis 2 – Supply Water System..... 34**

    10.1 Introduction ..... 34

    10.2 Problem Statement ..... 34

    10.3 Goal ..... 34

    10.4 Research Steps ..... 35

    10.5 Tools ..... 35

    10.6 Expected Outcome..... 35

    10.7 Existing Supply Water System - CPVC ..... 35

    10.8 Use of Propress Supply Water System..... 36

    10.9 Redesigning the CPVC System Utilizing the Propress System..... 37

    10.10 Comparing the CPVC System vs. Propress System..... 37

    10.11 LEED Impact ..... 38

    10.12 Conclusion & Recommendation..... 38

**11. Analysis 3 – Site Logistics Plan for Drywall Deliveries ..... 40**

    11.1 Introduction ..... 40

    11.2 Problem Statement ..... 40

    11.3 Goal ..... 40

    11.4 Research Steps ..... 40

    11.5 Tools ..... 41

    11.6 Expected Outcome..... 41

    11.7 Understanding the Existing Site Plan ..... 41

    11.8 Referring to Arlington County About Logistic Changes..... 44

    11.9 Modifying the Site Plan for the Drywall Subcontractor ..... 44

    11.10 Comparing Site Plans ..... 47

    10.11 Conclusion & Recommendation..... 48

---

|  |           |
|--|-----------|
| <b>Appendix A – Project Schedules .....</b>                              | <b>50</b> |
| <b>Appendix B – Project Estimates .....</b>                              | <b>57</b> |
| <b>Appendix C – Structural Calculations .....</b>                        | <b>72</b> |
| <b>Appendix D – Structural System Schedule and Cost Estimates .....</b>  | <b>83</b> |
| <b>Appendix E – Supply Water System Takeoff Notes and Estimates.....</b> | <b>92</b> |
| <b>Appendix F – Site Logistics Plan for Material Delivery .....</b>      | <b>95</b> |

# TURNBERRY TOWER ARLINGTON

1881 North Nash Street  
Arlington, Virginia



## PROJECT FEATURES

**Total Cost:** \$140 Million

**Size:** 750,000 Square Feet

**Levels:** 6 Underground Parking and 26 Above Ground

**Method:** Design-Bid-Build with GMP

**Function:** Luxury Condominiums

**Duration:** March 2007 - September 2009

**LEED Rating:** Certified

## PROJECT TEAM

**Owner:** 1881 Rosslyn Associates, LLC c/o Turnberry Associates

**General Contractor:** Facchina-McGaughan, LLC.

**Architect:** BBG-BBGM Architects & Interiors

**Structural Engineer:** Smislova, Kehnemui & Associates, PA

**MEP Engineer:** GHT Limited

**Civil Engineer:** Vika Incorporated

**LEED Consultant:** Sustainable Design Consulting

**Geotechnical Engineer:** Langan Engineering

**Landscape Architect:** LaPierre Studio

**Interior Design:** Nick Luaces Design Associates

## ARCHITECTURE

- Exterior skin is stone and glass on lower levels and curtain wall and window wall on upper floors
- Stone is Blue Pearl Granite that will be imported from Norway
- Floor-to-ceiling glass is all units for maximum sunlight and sightlines
- Private elevator lobbies for units
- Ceiling heights vary from 9 to 12 feet
- Access to fitness center, indoor pool and spa, café, social room, and media room
- Roof will be EPDM with tapered insulation



## ELECTRICAL

- Power is supplied from Dominion Power under ground with two feeds into the transformers
- First feed is stepped down to 480Y/277V 3-phase power and is fed into a 4000 amp box for all public areas and elevators including lighting fixtures
- Second feed is stepped down to 208Y/120V 3-phase power and is fed into one of two 4000 amp boxes where it feeds units for receptacles and luminaires

## STRUCTURAL

- Continuous footings used for the perimeter wall and spread footings used for columns and shear walls
- Parking levels use 10,000 PSI concrete for columns and shear walls and 5,000 PSI for slabs
- Tower levels use two-way post-tension deck with varying PSI concrete for columns and shear walls and 5,000 PSI for slabs
- Flying form system used for faster erection of tower slabs
- Pump and tremie method used for pouring of concrete on tower levels

## MECHANICAL

- All spaces in the lobby level will be serviced with one of three AHU's located in the ceiling space
- Each residential unit will have between one to three heat pumps depending on the size of the unit



## 2. Acknowledgements

I would like to thank the following people for the help and support to assist me in completing my senior thesis:

### **Penn State Architectural Engineering Faculty**

- Dr. David Riley
- Professor Kevin Parfitt
- Professor Robert Holland
- Dr. Michael Horman

### **Facchina Construction (Formerly Facchina-McGaughan, LLC.)**

- Tony Cortés
- Derek Dickenson
- Richard Roberts
- G. R. Nicholas Holland
- Josue Leon

### **Turnberry Limited**

- Mark Babbitt
- Dave White

### **Facchina Development**

- Robert Mitchell

### **J.J. Magnolia Plumbing**

- Bill Stewart

### **Fellow AE students, especially**

- Nicole Lucas
- Kim McKitish

### **Friends & Family**

Especially Mom, Dad, and Joey

### 3. Executive Summary

This senior thesis final report provides background information on Turnberry Tower Arlington, as well as examines the construction and technical aspects of the project. The different studies will discuss what was done during construction and what could be changed to help reduce the schedule or decrease the overall cost. The analysis will end with a recommendation of the success or failure of the proposed change.

The first analysis that will be investigated is the window wall attachment using reinforced concrete instead of the engineered post tension concrete decks. The post tension concrete decks failed during the installation of the window wall when banded tendons were hit. If reinforced concrete decks were used, it would eliminate the problem of striking post tension tendons. After designing the decks using reinforced concrete, it was determined that the decks needed to be 11 inches thick. When comparing the schedules, the analysis showed that the reinforced concrete construction would have no impact. The cost of the post tension decks was \$20.6 million and the analysis showed that the reinforced concrete would cost \$22.6 million. Because the two reinforced systems analyzed will cost more money than the cost of repairing the damage from the post tension failures, it is recommended that the existing post tension concrete be used over the proposed reinforced concrete decks.

The second analysis investigated was the supply water system that feeds each residential unit. The current system utilizes CPVC piping that connects to the copper pipe risers through the building. I wanted to introduce a new system in the building and see if it would improve the schedule or the cost of the project. The Propress system uses copper piping and an easily connected fitting that makes installation of the supply water system much faster than the typical soldering of copper pipe. Unlike the installation of CPVC, there is no glue necessary to connect the piping because the fittings are mechanically installed with a special tool, which would be a plus for LEED and sustainable construction. When the cost and schedule was analyzed, it was predicted the Propress system would cost \$160,000 more. This was due to the fact that the cost of copper in 2006 was very high when the project was designed. The installation of the system would save 17 man hours per unit, but that cost is not offset by the cost increase of the system. It is recommended that since the project was designed in 2006 and the price of copper was high, the CPVC system be used for the supply water to each unit.

The third analysis looks at the current site logistics plan and the overtime cost that needed to be paid to load drywall into the building. There was a large area on the east side of the site that was not used. If the logistics plan used that side of the site during concrete construction to load drywall into the building, it was determined that there could be a cost savings on labor of \$750 to \$2000 per 1000 boards loaded. This project has 91,000 sheets of drywall to load into the building. The new logistics plan would not affect the SIP schedule and would only require one window wall not to be installed during concrete construction. After looking at the plan and seeing that it is possible to use this site logistics plan, it is recommended that this site logistics plan be used to help reduce the overtime cost needed to load drywall into the building during construction.

#### **4. Project Introduction**

The Turnberry Tower Arlington project is being built in the Rosslyn section of Arlington, Virginia. The building consists of 6 levels of below ground parking and 25 levels of residential units equating to approximately 740,000 square feet. The building is finished only in the below ground parking levels, lobby level, the kitchens and the bathrooms of the residential units.

In order for Turnberry Tower Arlington to attain a LEED Certified Certification for New Construction, certain points were obtained in designing the building as well as recycling materials during construction. All materials were sorted during demolition and sold to private parties so that it can all be reused. Luckily, no special measures were needed during demolition because no harmful asbestos or lead paint needed to be removed.

The project began in September of 2006 with the demolition of the existing hotel on site. Working through the SIPS schedule being utilized on this project and with the current work rate, a date of September 2009 has been set for the substantial completion.

Turnberry Tower Arlington's primary structural systems consist of two way post tension concrete with shear walls and columns. The building will house 11 elevators with almost 2 miles of rail. All units will have their own heat pumps with their own mechanical closets. A sovent system will be used for the plumbing that will help reduce the need for vent stacks.

The general contractor on the project is Facchina-McGaughan, with BBG-BBGM acting as the project architect and Turnberry Limited and Facchina Development as the owners. The building cost of \$155 million is contracted under a guaranteed maximum price between Facchina-McGaughan and Turnberry Limited. The total project cost for this project is \$250 million.

#### **5. Project Team Overview**

##### 5.1 Client Information

Turnberry Limited are the primary owners of this project with Facchina Development as the secondary owners. The project was owned by Facchina initially and needed another party to come in, back the project and become the primary owner. Turnberry is known for picking sites that are "dramatic" and providing something that can't be duplicated. Some of their other sites include Paradise Island in the Bahamas and Las Vegas, Nevada. Further expansion includes on the water in Boston, Massachusetts.

This site was selected because of the views that will be offered. At the top, you will have unobstructed views to all of the District of Columbia and Georgetown and parts of the Anacostia River. The building has been outfitted since Turnberry has purchased the building to fit their décor. High ceilings in the lobby level with plenty of down light and magnificent finishes will greet guests as they enter the



building. Turnberry will also have installed two water features that will be noticed by anyone who passes by the building. These few features along with stone from Norway and the full height window walls will allow Turnberry Tower Arlington to become a symbol for the Rosslyn section of Arlington County.

Cost, quality, and schedule are the three most important factors in achieving a successful project. In the case of this project an interesting approach was taken. When Facchina sold the building to Turnberry and became the secondary owner, one stipulation was that Facchina's general contractor division would be used to build and manage the job. The hope was that by having the owner and general contractor work together and be one in the same that it would be possible to achieve cost, quality, and schedule which is not typical on most projects. When there was a delay from permitting problems, both sides worked together very well. The project fell behind three months and it did not sit well with any of the parties. Both sides worked together and were able to speed up the project to get back on the original schedule and they did this without increasing any cost or decreasing any quality.


Throughout construction there was also constant communication between the owner and general contractor dealing with all changes. In an effort to keep costs down, quality high, and schedule on track, these parties would meet regularly to discuss any and all changes. This showed that when the general contractor has a vested interest in a project they will try to do what they can to keep cost, quality, and schedule in check.

When asked what safety expectations were required, the only answer from the owner was "100% at all times."

In order to complete this project so the owner is satisfied, all of the units must have the kitchens and bathrooms finished and have the rest of the unit roughed out with junction boxes for lights and power to the receptacles. The corridors on the typical floors must be finished as well. The lobby level will need to be completely finished including the pool, spa, gym, and mezzanine level. The parking garage will need to have all private garage doors installed. All the systems in the building must be commissioned, online and ready to work properly for turnover.

## 5.2 Project Delivery System

Turnberry Tower Arlington Organizational Chart




This project is being delivered in a design-bid-build approach. This was chosen because Turnberry wanted the building to fit their exact needs so it could be a building they would be proud to own.

Between the owner and the general contractor there is GMP contract. In parts of the budget where items were not yet purchased or it was not decided what was exactly needed, an allowance was put in. A lump sum contract is used between the general contractor and subcontractors. The subcontractors were picked by the use of a hard bid. In some cases it was required for the subcontractor to bond 1.5% of their bid in the form of a payment and performance bond. The project uses a CCIP Insurance program so all subcontractors were required to participate in this program.


### 5.3 Project Staffing Plan

Below is the organization chart and the staffing plan for the Turnberry Tower Arlington project being used by the general contractor. The organization chart is set so there is one project executive that deals primarily with the owner while everyone else has who they should report to. Because of the flexibility of this project and the open communication between the owner and general contractor, everyone on the job is able to communicate with everyone on the owner's side and vice versa. The staffing chart was set up before the job and describes what the job will need in regards to the onsite personal.

Facchina-McGaughan Organization Chart



Facchina-McGaughan Staffing Chart



## 6. Existing Conditions

### 6.1 Site Plan of Existing Conditions

A site plan of existing conditions was created. On the first diagram the limits of the property, garage, and proposed building are drawn. All adjacent buildings are labeled as well as all local roads running around the site. The covered walkway that will be up through the duration of construction is shown along with the temporary office trailers and other temporary facilities. The second diagram shows all existing utilities and how they will be routed into the new building.

### 6.2 Local Conditions

In the Washington D.C. Metropolitan area, post-tension concrete is most utilized due to the height restriction inside the District of Columbia. Although this height restriction is not enforced in Arlington, Virginia, the use of the post-tension concrete allows for larger bays between columns and a thinner floor slab which is a huge advantage in a condominium building. Combine these advantages to the efficiency the crews already have with using P-T concrete, it was deemed appropriate to use this system on this project.

Weather in the Washington D.C. area is quite extreme. Because of the location of swamp lands, the weather can change dramatically from day to day. In the winter months, very cold temperatures can be expected which can impact schedules with concrete pours and on this job with hanging exterior stone work. Parts of the exterior building and floors will have to be tented in and heated to allow for concrete and mortar to set.

The summer months for this project were also tough on the project and the workers. The summer of 2007 was especially hot with many days of 100% humidity. This is tough on workers to get the work done that is necessary to keep up with the schedule. Summer of 2008 proved not to be any easier. Along with many hot and humid days, there were many large thunderstorms that provided the area with much precipitation and knocked out power to the area for hours and even days. This weather also led to the area's public transportation system to be shut down and disabled for large amounts of time. Large construction the Metro's Orange Line led to an increase in traffic on all major roads and highways in the area. This traffic would lead to an increase in time for all deliveries and pickups from the site.

The site located at 1881 North Nash Street has some height restrictions because of the approach path of aircrafts landing at Reagan National Airport. The tower cranes are restricted to their height which makes it hard for critical picks for the heavy roof top machinery onto the building.

This site causes problems with traffic flow and patterns because of the adjacencies to a county "major roadway." Fort Myer Drive is designated as a main route as it allows the passage of cars through

Arlington County from both Interstate-66 and Georgetown. This restricts the site deliveries because they can't occur during rush hour traffic in the morning and afternoon.

The soils in the area are a combination of sand and clay for about 30' down for excavation and then disintegrated rock for the next 30'. This is typical in the Rosslyn section of Arlington County.

### 6.3 Demolition of Existing Building

Previously on this site was the Rosslyn Best Western which was 11 stories in height with an in-ground pool on the south of the site. The geotechnical engineer provided a Phase I and Phase II site assessment. In their findings there was no evidence of "recognized environmental conditions" as defined by ASTM were observed. The limited asbestos survey revealed the presence of Regulated Asbestos Containing Materials in the form of surface applied ceiling materials in the parking garage. Category I non-friable asbestos containing floor tiles were also detected in storage and linen rooms in the hotel structure. None of the asbestos found was harmful and out of regulatory limits so special precautions were not needed to remove it from the building.

In order to achieve a LEED certification, certain criteria needed to be met during demolition to achieve the required amount of LEED points. All the furniture and contents from the hotel were taken out of the building and sold off to private parties. The materials that made up the building including the structural steel and aluminum were recycled and sold off to be reused in another project. The concrete was also recycled where it was going to be made into new concrete.

## **7. Project Logistics**

### 7.1 Project Schedule Summary

When the plans for 1881 North Nash Street were purchased by Turnberry Limited and Facchina Development in 2005, the process for developing a project schedule for the newly named Turnberry Tower Arlington began immediately. On September 26<sup>th</sup>, 2006, demolition on the existing building began. The schedule has a substantial completion date set for July 7<sup>th</sup>, 2009 and the owner expects to move in on September 4, 2009. The schedule that is attached in Appendix A breaks down the major activities into different phases including procurement, temporary construction, new construction, and project commissioning and testing.

#### *Foundation*

From the soil boring reports prepared by the geotechnical engineer, it was discovered that this site would have a significant amount of rock that would need to be removed. When the site was brought down to approximately elevation 70', dynamite was needed to bring the site down to approximately elevation 50'. Some over excavation was needed for the continuous footings that were poured for

under the perimeter wall. After the extra rock was removed, 2500 PSI lean concrete was needed to be poured and this was used for leveling the excavated hole to place the perimeter walls. This has a major impact on the schedule because of the amount of rock that needed to be removed (approximately 4200 BCY) as well as the limitations on how much could be blasted each day. On blast days all roads around the site would have to be closed for a period of time which caused traffic on major highways and roads. On site, it would put a stop to excavation because of the placement of live explosives.

### *Structure*

The structure of this building is designed in two different ways; one in the parking levels and one in the tower levels. In the parking levels, two tower cranes with two separate crews were used to erect the concrete structure. This footprint of the parking level has a large enough area that allowed two crews to work independently of one another and still be fully efficient. They worked in a clockwise matter going from one zone to another until the parking level was complete.

The tower level of the building was done utilizing only one of those crews from the parking level erection and the use of one tower crane. The slabs were split into three zones and each would be poured on a separate day. The columns would be poured on a fourth day. At the rate the project was going and with the available man power, the project was averaging about a floor a week.

### *Finishing Sequences*

This job uses the Short Interval Production Schedule or SIPS method to complete the interior of the building. Refer to Appendix A for the SIPS schedule for Turnberry Tower Arlington. Some of the finish activities include:

- Install curtain wall and window wall
- HVAC / Plumbing rough-in
- Electrical rough-in
- Drywall
- Install plumbing fixtures
- Install lighting fixtures
- Install doors, hardware, and toilet accessories
- Testing and balancing

These activities were all done in a sequence agreed upon by all the subcontractors involved before the start of construction and was created to maximize productivity. Although tweaking was needed during the first few floors of construction, this schedule is helping to keep everyone on track and responsible for their own work. The subcontractors can schedule crews at their discretion because they know how much work they will need to complete during the week.

## 7.2 Detailed Project Schedule

The schedule that has been created is based on the two phases of construction for Turnberry Tower Arlington. The first phase includes the erection of the 6 story underground parking garage and the second phase includes the erection of the 26 story residential tower. The detailed schedule can be found in Appendix A. Below in *Table 7.1* you can find the abridged version of the detailed schedule which includes only the summary activities.




Table 7.1 – Abridged Detailed Schedule

From the above schedule, some of the key completion dates for Turnberry Tower Arlington include:

|                                |                                 |
|--------------------------------|---------------------------------|
| Structure Excavation           | July 2 <sup>nd</sup> , 2007     |
| Building Structure Erection    | December 8 <sup>th</sup> , 2008 |
| Condo Rough-in (MEP & Framing) | February 3 <sup>rd</sup> , 2009 |
| Window Wall / Curtain Wall     | November 5 <sup>th</sup> , 2008 |
| Building Finishes              | June 3 <sup>rd</sup> , 2009     |
| Elevators                      | August 28 <sup>th</sup> , 2009  |
| Substantial Completion         | August 30 <sup>th</sup> , 2009  |

The schedule that has been created shows the Short Interval Production Schedule (SIPS) that is being used on this project. Building structure erection, rough-in, window wall / curtain wall, drywall, and finishes are broken down according to each level. Both the garage and the tower levels were grouped together where the same type of work would be taking place (concrete placement) and separated where different work would be occurring (different types of finishing). A copy of the SIPS being used on this job that was utilized to create the detailed schedule can be found in Appendix A. Durations and start dates for the activities in the detailed schedule were obtained from the general contractor.

### 7.3 Project Cost Evaluation

Below in *Tables 7.2 to 7.4* are the costs associated with the construction of Turnberry Tower Arlington.

#### Actual Cost

##### Actual Building Construction Cost (CC)

|                        |               |
|------------------------|---------------|
| Construction Cost (CC) | \$155,500,000 |
| CC / SF                | \$210.14      |

Table 7.2 – Actual Building Construction Cost

##### Total Project Costs (TC)

|                         |               |
|-------------------------|---------------|
| Total Project Cost (TC) | \$250,000,000 |
| TC / SF                 | \$337.84      |

Table 7.3 – Total Project Cost

##### Major Building Systems Cost (BSC)

|                                  |              |
|----------------------------------|--------------|
| Structural                       | \$28,600,000 |
| MEP                              | \$33,200,000 |
| Fire Protection                  | \$2,300,000  |
| Curtain Wall / Window Wall       | \$15,200,000 |
| Major Building System Cost (BSC) | \$79,300,000 |
| BSC / SF                         | \$105.73     |

Table 7.4 – Major Building Systems Cost

#### R.S. Means Square Foot Estimate

R.S. Means 2008 was used to develop an estimate for both the residential tower of the building as well as the parking deck. Once the square foot estimates were calculated, a total building estimate was created. An 8-24 story apartment building was used at 500,000 SF. Perimeter adjustments were calculated in the estimates. Additions include elevators and fully furnished kitchens. For the parking garage, a perimeter adjustment was needed and the typical height of the parking garage was kept the same. Below in *Table 7.5 and 7.6* are the calculated values and the details for the calculations can be found in Appendix B.

##### R.S. Means SF Total Building Estimate

|  | Square Feet | Cost / SF | Total Cost                          |
|--|-------------|-----------|-------------------------------------|
| Residential Tower                          | 500,000     | \$169.79  | \$84,895,000                        |
| Parking Garage                             | 240,000     | \$77.90   | \$18,696,000                        |
|  |             |           | \$103,591,000                       |
| R.S. Means Location Factor (Arlington, VA) |             |           | 1.04                                |
|  |             |           | <b>Total Estimate \$107,734,640</b> |

Table 7.5 – R.S. Means 2008 Estimate



Actual Building Construction Cost (CC) vs. R.S. Means 2008 SF Estimate

| Estimate Type                   | Cost                | Cost / SF      |
|---------------------------------|---------------------|----------------|
| Building Construction Cost (CC) | \$155,500,000       | \$210.14       |
| R.S. Means Estimate             | \$107,734,640       | \$145.59       |
| <b>Difference in Estimates</b>  | <b>\$47,765,360</b> | <b>\$64.55</b> |

Table 7.6 – Actual Building Cost vs. R.S. Means Estimate

To compare the R.S. Means estimate to the actual estimate, the total estimate was divided by the total square footage of the tower and garage. The estimate above shows \$145.59/SF. When this is compared to the building construction cost obtained from the general contractor of \$210.14/SF, this method is off by \$64.55/SF. The reason for the error in calculation can be because of the following reasons:

- The use of post-tension concrete instead of reinforced concrete
- The actual building has varying ceiling heights
- The building has very high end kitchen appliances, tile floors, and bathroom accessories
- No fire suppression or life safety devices is included in the R.S. Means estimate
- Elevators for the additions in R.S. Means do not include the use of 3 hydraulic elevators

#### D4 Cost Analysis

In the database for D4 Cost 2002 there are no buildings that match Turnberry Tower Arlington. To get an approximate cost, 5 buildings that were the same type and above \$15 million were used. Below in *Table 7.7* are the calculated values obtained by D4 Cost compared to the actual building construction cost. The details from the D4 Cost Analysis can be found in Appendix B.

Actual Building Construction Cost (CC) vs. D4 Cost 2002

| Estimate Type                   | Cost                | Cost / SF      |
|---------------------------------|---------------------|----------------|
| Building Construction Cost (CC) | \$155,500,000       | \$210.14       |
| D4 Cost 2002                    | \$95,416,943        | \$128.94       |
| <b>Difference in Estimates</b>  | <b>\$60,083,057</b> | <b>\$81.19</b> |

Table 7.7 – Actual Building Cost vs. D4 Cost 2002

The estimate above gives \$128.94/SF from the D4 Cost Analysis. When this is compared to the number obtained from the general contractor for building construction cost of \$210.14/SF, there is a difference of \$81.19/SF. Some of the possible errors in this estimate are:

- Buildings in the database are not close to the complexity or cost of finishes in the actual building
- There is a much more complex conveying system than the compared buildings
- The use of post-tension concrete instead of reinforced concrete
- The building has very high end kitchen appliances, tile floors, and bathroom accessories
- A 6-story underground parking garage

#### 7.4 General Conditions Estimate

A general conditions estimate was created by the general contractor for the Turnberry Tower Arlington project. Because of the complexity of this project and the owner’s expectation to pay close attention to cost, schedule, and quality, the general conditions are very specific. Appendix B has the complete breakdown of the general conditions estimate including the prices, percentages, units, unit costs, and cost per month. Some of the numbers have been slightly modified based on the request of the general contractor. *Table 7.8* below shows the main breakdown of the general conditions for this project.

| General Conditions      |                     |             |
|-------------------------|---------------------|-------------|
| Item                    | Cost                | % of GC     |
| Staff                   | \$5,881,000         | 43.62%      |
| Site Work               | \$1,193,000         | 8.85%       |
| Temporary Utilities     | \$1,300,000         | 9.64%       |
| Site Office & Job Needs | \$985,500           | 7.31%       |
| Site Security           | \$491,000           | 3.64%       |
| Contracts               | \$77,000            | 0.57%       |
| Insurance               | \$3,555,000         | 26.37%      |
| <b>TOTAL</b>            | <b>\$13,482,500</b> | <b>100%</b> |

Table 7.8 – General Conditions Breakdown

The final estimate for the general conditions totals \$13.5 million which is approximately 9% of the \$150 million total project cost. There is a Contractor Controlled Insurance Policy (CCIP) for this job but there is still a need for the umbrella liability, general liability, and workers compensation insurance policies to be added to make the insurance complete. Although the general contractor’s site offices will be housed inside of the future café of the building, a space needed to be rented out until such time that the café area was complete and enclosed by the window walls to make the space watertight. This explains why the cost of the site office is not lower than one would anticipate.

Like most general conditions on any given project, a majority goes towards paying the staff of the general contractor. This project is staffed so most of the people on the project team are on the project for the entire duration.

#### 7.5 Detailed Structural System Estimate

Turnberry Tower Arlington’s primary structural system is post-tension concrete for the tower level and cast in place concrete for the parking levels. A structural system estimate was created from takeoff notes for the entire structural system of the building. Below in *Table 7.9 through Table 7.11* are the results from the estimate. All takeoff notes can be found in Appendix B.

| Total Material Cost |           |                     |
|---------------------|-----------|---------------------|
| Item                | Amount    | Total Cost          |
| Concrete            | 37,351 CY | \$4,668,875         |
| Reinforcing Steel   | 3071 Tons | \$3,071,000         |
| Miscellaneous Items |           | \$2,481,385         |
| <b>Total</b>        |           | <b>\$10,221,260</b> |
| <b>Total per CY</b> |           | <b>\$273.65</b>     |

Table 7.9 – Total Material Cost

| Average Labor and Equipment |                 |                |           |
|-----------------------------|-----------------|----------------|-----------|
| Description                 | Labor           | Equipment      | Unit      |
| Footings                    | \$54.50         | \$0.33         | CY        |
| Columns                     | \$435.00        | \$42.50        | CY        |
| Slab on Grade               | \$55.00         | \$0.41         | CY        |
| Slabs                       | \$207.00        | \$19.60        | CY        |
| Beams                       | \$490.00        | \$48.50        | CY        |
| Shear Walls                 | \$430.00        | \$42.50        | CY        |
| Curbs, Pads, Toppings       | \$129.00        | \$1.78         | CY        |
| <b>Average per CY</b>       | <b>\$257.21</b> | <b>\$22.23</b> | <b>CY</b> |

Table 7.10 – Average Labor and Equipment Costs

| Construction Cost of Concrete System for Turnberry Tower Arlington   |       |      |          |          |              |                       |
|--|-------|------|----------|----------|--------------|-----------------------|
| Description  | Qty   | Unit | Material | Labor    | Equipment    | Total Cost            |
| Cast In Place Concrete including placing and stripping formwork, placing rebar, placing concrete, and finishing concrete | 37351 | CY   | \$273.65 | \$257.21 | \$22.23      | \$20,658,837          |
|  |       |      |          |          | <b>TOTAL</b> | <b>\$27.55 per SF</b> |

Table 7.11 – Construction Cost of Structural System

R.S. Means 2008 Building Construction was used to find the average price of labor and materials that were needed to create this construction estimate. Prices for concrete per cubic yard, rebar per ton, and PT cable cost per pound were obtained directly from the subcontractor. Prices that were given include:

Concrete = \$125 / cubic yard

Rebar = \$1000 / ton

PT Cable = \$1.15 / pound

These numbers were used with the takeoff values to obtain the material cost for the structural system which totaled \$10,221,260. When this number is divided by the number of cubic yards of concrete for this project the total is \$273.65 per cubic yard. This number was added to the average cost of labor

(\$257.21 per cubic yard) and equipment (\$22.23 per cubic yard) and the total cost of \$20,658,837 was obtained for the construction of the concrete structural system. This number, when divided by the projects 750,000 square feet, yields \$27.55 per square foot (as seen in *Table 7.11*).

The price of \$27.55 is a bit high for concrete construction. Normal construction averages \$25 per square foot. Some of the reasons that this estimate may be high include:

1. Rise in prices for steel and rebar
2. Transportation costs to get the material to site
3. Cost of the automatic climbing formwork and flying formwork to gain time on the schedule
4. Post-tension steel cables
5. Much larger waste factor was calculated than was necessary

*Figure 7.1* shows a typical tower level with rebar cages for shear walls and columns, part of a concrete deck poured, and exposed PT cables laid out and ready for a concrete pour. *Figure 7.2* shows the use of the Automatic Climbing System (ACS) for the core of the building.




Figure 7.1 - Working Deck



Figure 7.2 – ACS Formwork for Core

## 8. Introduction to Thesis Analysis

### Analysis 1 – Attachment of the Window Wall to Reinforced Concrete

#### *Structural Breadth*

This analysis will focus on the problems that occurred on the jobsite with attachment of the structural supports for the building's exterior window wall system to the post tension concrete decks. With lack of coordination between the design team and the contractors, drilling needed to occur in the post tension decks. Many tendons failed when they were struck during the drilling process. With this occurring halfway up the building, steps were immediately taken to remedy this process. The goal for this analysis is to go back to the preconstruction phase of the project and propose the use of reinforced concrete. This would help with all of the designs that were not yet in place and would reduce the risk of having to drill into post tension decks. I will compare the cost and schedule problems from failed post tension tendons to the same project if reinforced concrete had been used.

### Analysis 2 – Supply Water System

#### *Mechanical Breadth & Critical Industry Issue*

During some of the value engineering that occurred in the beginning phases of construction, one idea that was utilized on this project was the use of the Sovent System which helped in sustainable construction for the waste piping. I will now look more closely at the supply water system and propose ways to make this system more sustainable while at the same time decreasing the cost and schedule for installation. Utilizing propress fittings and prefabrication, I plan to investigate to see if these construction methods would have been more beneficial for this project. I will then see if any of these construction methods could have helped to obtaining more LEED points for the project.

### Analysis 3 – Site Logistics Plan

Turnberry Tower Arlington is surrounded on three sides by main roads. The country has put time restrictions on some of the roads so construction does not create more traffic during certain times of the day. With those restrictions, the site plan that was utilized throughout the project used one road for deliveries to the site. This one main passageway was also the road used when concrete was delivered and where the material hoist was accessed. The goal of this analysis is to redesign the site logistics plan and to utilize another part of the site for more deliveries, which will reduce the amount of overtime the drywall subcontractor needed for this project. Cost savings would occur if the drywall subcontractor did not have to accept as many deliveries on the weekends.

## 9. Analysis 1 – Window Wall Attachment with Reinforced Concrete (Structural Breadth)

### 9.1 Introduction

Turnberry Tower Arlington’s exterior skin is made up of both curtain wall and window wall. When the general contractor was given the contract documents during bidding, it was noted that the exterior skin system did not have a design in place showing how to connect it to the structure of the building. Because the building structure is post tension concrete, not having a design for the connections made it very difficult for a connection to be designed in the existing conditions. Any connection design could have had a large impact on the structure design and may have caused a redesign of the post tension slabs.

### 9.2 Problem Statement

As a result of not having the detail for the window wall connection design, drilling into the cured post tension decks had to occur to attach the window and curtain wall. This led to having more than 20 tendons hit and fail during the window wall installation process. After this had occurred, the exterior skin installer was forced to use a Ferroskan unit to scan the post tension decks before every bolt was installed. The result of the busted post tension tendons can be seen below in *Figure 9.1*.



Figure 9.1 - Failed Post Tension Tendons

### 9.3 Goal

The goal of this analysis to act as the general contractor during the preconstruction process and suggest the post tension concrete slabs be replaced with reinforced concrete decks. This will allow for more design flexibility in connecting the exterior skin to the building. Once redesigned, a cost and schedule analysis will be performed to see which design would be better taking in to account all of the problems that occurred from the post tension tendon blow outs. I will also find out why post tension concrete was used on this building.

#### 9.4 Research Steps

1. Investigate why post tension concrete was used by talking to the architect, structural engineer, and developer and ask if reinforced concrete could have been an option.
2. Use the direct design method and the CRSI handbook to design the building using normal concrete (structural breadth).
3. Consult with the scheduler to determine the correct durations for the use of reinforced concrete construction on this project and see what other activities this may impact.
4. Price the project using reinforced concrete.
5. Compare both the schedule and cost for the two different structural systems
6. Conclusion & Recommendation

#### 9.5 Tools

1. CRSI Handbook
2. ACI Handbook
3. Direct Design Method
4. Architectural Engineering Professors
5. General Contractor and Design Team
6. R.S. Means Cost Analysis
7. Primavera / Microsoft Project
8. Microsoft Excel

#### 9.6 Expected Outcome

When this project was designed and given to the general contractor, certain subcontractors were not yet onboard, including the exterior skin subcontractor. By the time the package was picked up and all of the submittals were approved by the architect, there was not time to place an embed into the post tension decks that would support the window wall. This led to the problems of ruptured post tension tendons and having to x-ray all future window wall installations. All of these additional costs to the project should show that if a suggestion was made to use reinforced concrete instead of post tension concrete then time and money would have been saved.

#### 9.7 Use of Post Tension Concrete

The first step in the research process was to investigate why post tension concrete was used for this project. While going through documents that were available during the preconstruction process, many design details, including the window wall supports, were not yet supported so it seemed like a good time to go ahead and use post tension concrete which would cause more of a problem than reinforced concrete.

The post tension concrete allowed the slab thickness on the typical residential levels 2 through 26 to be 7 inches. With the parking garage below the structure, the 10 foot ceilings in some of the units as desired by the owner, and the sunshade on the roof, the final height of the building is at elevation 409.70. The building is located in Arlington, Virginia in the Rosslyn District. This site is in close proximity to Reagan National Airport which gives the Federal Aviation Administration the final approval on how high the building can be. The FAA says the elevation of the building is within 1/8 of an inch of the allowable height.

With the elevation requirement that needed to be met, and with the County of Arlington requiring that the building meet the zoning requirements of the “C-O District,” the only way for the building to get an extra floor with the desired floor heights would be to use post tension concrete. This extra floor that was able to be incorporated into the design allows the owner to gain \$17.6 million of sales from the residential units. If the height of the building from the reinforced concrete becomes an issue, the option for taking out one floor of the building becomes very unlikely based on this price.

### 9.8 Redesigning the Floor Slabs Using Direct Design Method

To see if it was even possible to use reinforced concrete on this project, first I needed to redesign the slabs to see what the impact there would be on the cost and schedule. I started out by taking a typical floor and dividing a section into typical bays that would give me a general representation. I used the following general assumptions:

- 20” x 20” columns
- Per ASCE 7-05 Table 4.1, Live Load = 40 psf
- Dead Load (Concrete Self Weight) = 137.5 psf
- The whole deck would be #6 Rebar at 60 ksi

The general bay that was used for this analysis is shown in *Figure 9.2*:




Figure 9.2 - Bay

To come up with the thickness of the slab, I used an equation from ACI 318 Building Code Chapter 9 Table 9.5c 2008, *Table 9.1* below.



| fy, psi | Without Drop Panels |                 |                 | With Drop Panels   |                 |                 |
|---------|---------------------|-----------------|-----------------|--------------------|-----------------|-----------------|
|         | Exterior Panels     |                 | Interior Panels | Exterior Panels    |                 | Interior Panels |
|         | Without Edge Beams  | With Edge Beams |                 | Without Edge Beams | With Edge Beams |                 |
| 40,000  | ln/33               | ln/36           | ln/36           | ln/36              | ln/40           | ln/40           |
| 60,000  | <b>ln/33</b>        | ln/33           | ln/33           | ln/33              | ln/36           | ln/36           |
| 75,000  | ln/28               | ln/31           | ln/31           | ln/31              | ln/34           | ln/34           |

Table 9.1 – ACI Table 9.5c

Using the exterior panels without drop panels and without drop beams, the equation to use is  $ln/33$ . To be conservative, the largest bay size of 30 feet was chosen from the above *Table 9.1*. When the calculation is done, the thickness of the slab will be 11 inches.

The rest of the Direct Design Method helps to find the amount of steel and where it needs to be placed in the concrete slabs. The factored moment was found for both frames both within the column strip and in the middle strip. The steel was then divided between the positive and negative moments in both the column strips and middle strips. *Table 9.2 and Table 9.3* below summarize the results of the moments on the structure and *Table 9.4* shows the amount of steel that will be needed in each slab. The full structural analysis can be found in Appendix C including verification of the calculations.

*Moments on Each Slab*

| FRAME A      |          |          |
|--------------|----------|----------|
|              | + Moment | - Moment |
| Column Strip | 92 ft-k  | 214 ft-k |
| Middle Strip | 62 ft-k  | 72 ft-k  |

Table 9.2- Moments in Frame A

| FRAME B      |          |          |
|--------------|----------|----------|
|              | + Moment | - Moment |
| Column Strip | 87 ft-k  | 201 ft-k |
| Middle Strip | 58 ft-k  | 67 ft-k  |

Table 9.3 – Moments in Frame B

| Amount of #6 Rebar per foot |                        |                     |                        |                     |
|-----------------------------|------------------------|---------------------|------------------------|---------------------|
|                             | FRAME A                |                     | FRAME B                |                     |
|                             | + Moment (Bottom Bars) | - Moment (Top Bars) | + Moment (Bottom Bars) | - Moment (Top Bars) |
| Column Strip                | 8                      | 13                  | 8                      | 12                  |
| Middle Strip                | 8                      | 8                   | 8                      | 8                   |

Table 9.4 – Rebar Required

### 9.9 Scheduling the Project: Post Tension Concrete vs. Reinforced Concrete

When observing the problems with post tension blowouts on this project, the first question that comes to mind is how many days were wasted on the schedule having to fix those decks? Upon further investigation of the schedule, this project was very fortunate that all of the repairs that needed to be done to the floor slabs did not affect the concrete work going on above and did not delay the interior trades on the SIP Schedule.

Next I wanted to look at was the formwork itself. The project was using a flying form system called the Peri Girder Truss Tables. These flying tables helped to speed up the erection of the tower, but they were designed for the post tension slabs that weigh less than the proposed reinforced concrete slabs. After talking to the concrete subcontractor, it was determined that the same formwork could handle the extra weight. That meant that there would be no delay in the construction from being forced to use other formwork or needing to move around more reshores.

After that I needed to investigate how the pour schedule for the reinforced concrete would compare to the pour schedule of the post tension concrete. To keep consistency between the two different types of decks, three zones were used to complete the pours. Each zone would take one day to pour. The post tension slabs utilized a 5 hour pour day and took between 10-11 days to complete. The reinforced concrete decks would need to use 8 hour pour days because of the thicker slabs and would need 12 days to complete (4 days for each zone). Below in *Table 9.5* is an abridged schedule that compares the pour schedules of post tension concrete slabs to the reinforced concrete slabs. The full schedule can be found in Appendix D.




Table 9.5 – Schedule Comparison

### 9.10 Schedule Comparison

Taking a closer look at the schedules from *Section 1.9*, both the post tension concrete construction and the reinforced concrete construction would begin the erection of floor 2 on December 28<sup>th</sup>, 2007.

The post tension concrete will be a few days shorter for each floor in the beginning of the project than the reinforced concrete. The workers for the post tension concrete would need to get used to the layout of the post tension tendons and rebar, and how to stress the post tension tendons correctly. The reinforced concrete would have similar time adjustments needed for a learning curve by the workers, but the main factor they need to adjust to is the volume of concrete and rebar. Both structural systems would have a learning curve due to moving and setting up formwork, setting embeds, and getting use to the working conditions on the project.

The advantage that the reinforced concrete system has on the schedule is that workers will be able to accelerate the construction of those decks faster than the post tension decks. More workers could be put on to help move the formwork, set up rebar, and place concrete. The post tension is limited to how fast it can move because of the inspectors. The inspectors would have to approve the concrete to be tensioned and then again approve that the tensioning is satisfactory before the workers could move the formwork up to the next level. In the abridged schedule in *Table 9.5* and full schedule in Appendix D, it is noticeable at certain floors were additional days were required for post tension slabs.

In the end, the post tension concrete construction tops out at floor 26 on September 8<sup>th</sup>, 2008 and the reinforced concrete construction tops out at floor 26 on September 2<sup>nd</sup>, 2008. The difference is only 4 work days.

### 9.11 Cost Comparison between Post Tension Concrete Slabs and Reinforced Concrete Slabs

To compare the costs of the different structural systems, takeoffs were completed on three different options. The first option is what was actually done on the project and shows the cost for the post tension concrete. The next option shows the cost for reinforced concrete if one floor of the building is removed to meet the height requirements. The last option shows the cost for reinforced concrete if all the floors are built but the height of each floor is reduced to meet the building height requirement.

All of the estimates used R.S. Means 2008 Building Construction to find the average price of labor and materials and can be found below in *Table 9.6*.

| Average Labor and Equipment |                 |                |           |
|-----------------------------|-----------------|----------------|-----------|
| Description                 | Labor           | Equipment      | Unit      |
| Footings                    | \$54.50         | \$0.33         | CY        |
| Columns                     | \$435.00        | \$42.50        | CY        |
| Slab on Grade               | \$55.00         | \$0.41         | CY        |
| Slabs                       | \$207.00        | \$19.60        | CY        |
| Beams                       | \$490.00        | \$48.50        | CY        |
| Shear Walls                 | \$430.00        | \$42.50        | CY        |
| Curbs, Pads, Toppings       | \$129.00        | \$1.78         | CY        |
| <b>Average per CY</b>       | <b>\$257.21</b> | <b>\$22.23</b> | <b>CY</b> |

Table 9.6 – Average labor and Equipment Costs

Prices for concrete per cubic yard, rebar per ton, and PT cable cost per pound were obtained directly from the subcontractor. Prices that were given included:

Concrete = \$125 / cubic yard

Rebar = \$1000 / ton

PT Cable = \$1.15 / pound

#### 9.11.1 Post Tension Concrete

The estimate for the post tension concrete system can be found below in *Table 9.7 through Table 9.10*. All of the takeoff notes can be found in Appendix B.

| Reinforcing Steel |              |              |                    |
|-------------------|--------------|--------------|--------------------|
| Area              | Amount (Ton) | Cost per Ton | Total Cost         |
| Columns           | 916          | \$1,000      | \$916,000          |
| Shear Walls       | 1402         | \$1,000      | \$1,402,000        |
| Slabs             | 753          | \$1,000      | \$753,000          |
| <b>TOTAL</b>      | <b>3071</b>  |              | <b>\$3,071,000</b> |

Table 9.7 – Rebar for Post Tension Concrete Slab

| Miscellaneous Items |             |               |                    |
|---------------------|-------------|---------------|--------------------|
| Item                | Amount      | Cost per      | Total Cost         |
| Post Tension Cables | 626,999 LBS | \$1.15 / lbs  | \$721,049          |
| Grout PT Ends       | 14,456 EA   | \$0.50 EA     | \$7,228            |
| WWF 6x6 W1.4/W1.4   | 19,312 SF   | \$18.05 / CSF | \$348,582          |
| WWF 6x6 W2.1/W2.1   | 53,001 SF   | \$26.50 / CSF | \$1,404,527        |
| <b>TOTAL</b>        |             |               | <b>\$2,481,385</b> |

Table 9.8 – Miscellaneous Items for Post Tension Concrete Slab

| Total Material Cost |           |                     |
|---------------------|-----------|---------------------|
| Item                | Amount    | Total Cost          |
| Concrete            | 37,351 CY | \$4,668,875         |
| Reinforcing Steel   | 3071 Tons | \$3,071,000         |
| Miscellaneous Items |           | \$2,481,385         |
| <b>TOTAL</b>        |           | <b>\$10,221,260</b> |
| <b>TOTAL PER CY</b> |           | <b>\$273.65</b>     |

Table 9.9 – Total Material Cost

| Construction Cost of Post Tension Concrete System  |       |      |              |                |               |              |
|--|-------|------|--------------|----------------|---------------|--------------|
| Description  | Qty   | Unit | Material     | Labor          | Equipment     | Total Cost   |
| Cast In Place Concrete including placing and stripping formwork, placing rebar, placing concrete, and finishing concrete | 37351 | CY   | \$273.65     | \$257.21       | \$22.23       | \$20,658,837 |
|  |       |      | <b>TOTAL</b> | <b>\$27.55</b> | <b>per SF</b> |              |

Table 9.10 – Construction Cost of Post Tension Structural System

The prices obtained for concrete per cubic yard, rebar per ton, and post tension tendons per pound were multiplied by the amount of these materials on the project and a total material price of \$10,221,260 was calculated. When this number is divided by the number of cubic yards of concrete on the job you obtain \$273.65 per cubic yard. This number was added to the average costs of labor and equipment and the total cost of \$20,658,837 was obtained for the construction of the concrete structural system. This number when divided by the projects 750,000 square feet yields \$27.55 per square foot (as seen in *Table 9.10* above).

*Figure 9.3* shows a typical tower level with rebar cages for shear walls and columns, part of a concrete deck poured, and exposed PT cables laid out and ready for a concrete pour. *Figure 9.4* shows the use of the Automatic Climbing System (ACS) for the core of the building.




Figure 9.3 – Working Deck



Figure 9.4 – ACS Formwork for Core

### 9.11.2 Reinforced Concrete Removing One Story

The estimate for the first reinforced concrete system, which includes the removal of one story of the building, can be found below in *Table 9.11 through Table 9.14*. All of the takeoff notes can be found in Appendix D.

| Reinforcing Steel |              |              |                    |
|-------------------|--------------|--------------|--------------------|
| Area              | Amount (Ton) | Cost per Ton | Total Cost         |
| Columns           | 354          | \$1,000      | \$354,200          |
| Shear Walls       | 1944         | \$1,000      | \$1,944,000        |
| Slabs             | 1065         | \$1,000      | \$1,065,000        |
| <b>TOTAL</b>      | <b>3363</b>  |              | <b>\$3,363,200</b> |

Table 9.11 - Rebar for Reinforced Concrete Slab Removing One Story

| Miscellaneous Items |           |               |                    |
|---------------------|-----------|---------------|--------------------|
| Item                | Amount    | Cost per      | Total Cost         |
| WWF 6x6 W1.4/W1.4   | 19,312 SF | \$18.05 / CSF | \$348,582          |
| WWF 6x6 W2.1/W2.1   | 53,001 SF | \$26.50 / CSF | \$1,404,527        |
| <b>TOTAL</b>        |           |               | <b>\$1,753,108</b> |

Table 9.12 – Miscellaneous Items for Reinforced Concrete Slab Removing One Story

| Total Material Cost |           |                     |
|---------------------|-----------|---------------------|
| Item                | Amount    | Total Cost          |
| Concrete            | 43355 CY  | \$5,419,369         |
| Reinforcing Steel   | 3363 Tons | \$3,363,200         |
| Miscellaneous Items |           | \$1,753,108         |
| <b>TOTAL</b>        |           | <b>\$10,535,677</b> |
| <b>TOTAL PER CY</b> |           | <b>\$243.01</b>     |

Table 9.13 – Total Material Cost

| Construction Cost of Reinforced Concrete System (Removing One Floor)   |       |      |          |              |                       |              |
|--|-------|------|----------|--------------|-----------------------|--------------|
| Description  | Qty   | Unit | Material | Labor        | Equipment             | Total Cost   |
| Cast In Place Concrete including placing and stripping formwork, placing rebar, placing concrete, and finishing concrete | 43355 | CY   | \$243.01 | \$257.21     | \$22.23               | \$22,651,046 |
|  |       |      |          | <b>TOTAL</b> | <b>\$30.20 per SF</b> |              |

Table 9.14 – Construction Cost for Reinforced Concrete Slab Removing One Story

The prices obtained for concrete per cubic yard, rebar per ton, and post tension tendons per pound were multiplied by the amount of these materials on the project and a total material price of \$10,535,677 was calculated. When this number is divided by the number of cubic yards of concrete on the job you obtain \$243.01 per cubic yard. This number was added to the average costs of labor and equipment and the total cost of \$22,651,046 was obtained for the construction of the concrete structural system. This number when divided by the projects 750,000 square feet yields \$30.20 per square foot (as seen in *Table 9.14* above).

### 9.11.3 Reinforced Concrete Adjusting Story Heights

The estimate for the second reinforced concrete system, which includes the adjustment of story heights, can be found below in *Table 9.15 through Table 9.18*. All of the takeoff notes can be found in Appendix D.

| Reinforcing Steel |              |              |                    |
|-------------------|--------------|--------------|--------------------|
| Area              | Amount (Ton) | Cost per Ton | Total Cost         |
| Columns           | 354          | \$1,000      | \$354,200          |
| Shear Walls       | 1944         | \$1,000      | \$1,944,000        |
| Slabs             | 1100         | \$1,000      | \$1,100,000        |
| <b>TOTAL</b>      | <b>3398</b>  |              | <b>\$3,398,200</b> |

Table 9.15 - Rebar for Reinforced Concrete Slab Adjusting Story Height

| Miscellaneous Items |           |               |                    |
|---------------------|-----------|---------------|--------------------|
| Item                | Amount    | Cost per      | Total Cost         |
| WWF 6x6 W1.4/W1.4   | 19,312 SF | \$18.05 / CSF | \$348,582          |
| WWF 6x6 W2.1/W2.1   | 53,001 SF | \$26.50 / CSF | \$1,404,527        |
| <b>TOTAL</b>        |           |               | <b>\$1,753,108</b> |

Table 9.16 - Miscellaneous for Reinforced Concrete Slab Adjusting Story Height

| Total Material Cost |           |                     |
|---------------------|-----------|---------------------|
| Item                | Amount    | Total Cost          |
| Concrete            | 44072 CY  | \$5,508,994         |
| Reinforcing Steel   | 3983 Tons | \$3,398,200         |
| Miscellaneous Items |           | \$1,753,108         |
| <b>TOTAL</b>        |           | <b>\$10,660,302</b> |
| <b>TOTAL PER CY</b> |           | <b>\$241.88</b>     |

Table 9.17 – Total Material Cost

| Construction Cost of Reinforced Concrete System (Adjusting Story Height)   |       |      |          |          |                |               |
|--|-------|------|----------|----------|----------------|---------------|
| Description  | Qty   | Unit | Material | Labor    | Equipment      | Total Cost    |
| Cast In Place Concrete including placing and stripping formwork, placing rebar, placing concrete, and finishing concrete | 44072 | CY   | \$241.88 | \$257.21 | \$22.23        | \$22,975,867  |
| <b>TOTAL</b>   |       |      |          |          | <b>\$30.63</b> | <b>per SF</b> |

Table 9.18 – Construction Cost for Reinforced Concrete Slab Adjusting Story Height

The prices obtained for concrete per cubic yard, rebar per ton, and post tension tendons per pound were multiplied by the amount of these materials on the project and a total material price of \$10,660,302 was calculated. When this number is divided by the number of cubic yards of concrete on the job you obtain \$241.88 per cubic yard. This number was added to the average costs of labor and equipment and the total cost of \$22,975,867 was obtained for the construction of the concrete structural system. This number when divided by the projects 750,000 square feet yields \$30.63 per square foot (as seen in *Table 1.18* above).

After calculating the cost differences in the systems, below in *Table 1.19* is a summary of the final cost for each structural system (both as a total cost and a cost per square foot). The table also lists how many units each structural system would allow to be built based on the total height restriction of the building.

| Structural Systems Cost Comparison for Turnberry Tower Arlington |                   |                       |             |
|--|-------------------|-----------------------|-------------|
| Structural System  | Residential Units | Total Structural Cost | Cost per SF |
| Post Tension Concrete  | 247               | \$20,658,837          | \$27.55     |
| Reinforced Concrete (Removing 1 Story)                           | 235               | \$22,651,046          | \$30.20     |
| Reinforced Concrete (Adjusting Story Height)                     | 247               | \$22,975,867          | \$30.63     |

Table 9.19 – Comparison of Costs for Structural Systems

Note: The cost per square foot is a bit higher than expected for this building (average is around \$25/SF). This may be caused to the rise in prices for steel and material transportation to the site. The formwork used on this project is also more expensive than typical formwork.

## 9.12 Conclusion & Recommendation

From the schedule analysis, it was seen that all of the systems were basically identical and took the same amount of time to construct. Not enough time would be saved to come up with a definitive reason to use one system over another.

The post tension concrete option gives the best cost result. It will cost approximately \$20.7 million and will provide the owner with all of the desired units at their desired heights. The next best option is the



reinforced concrete option with removing one story. This option will cost \$22.7 million. Unfortunately this option has to cut 12 units out of the building. The most costly option will be the reinforced concrete with adjusting the story heights. This option will cost approximately \$23 million and will provide all of the units desired by the owner, but at a reduced floor to ceiling height.

The more important items to compare are how much the reinforced concrete systems would cost compared to the post tension system, and the problems associated with its construction. The post tension concrete system cost approximately \$20.7 million to construct, which includes \$100,000 to fix and remediate the damage done by broken tendons. This is far less than the other systems proposed.

The other costs that go along with a tendon failure are not able to have a cost associated. Inspectors may feel obligated or pressured from local building officials to inspect the building more thoroughly. This could delay the construction schedule a few days. Broken tendons can lead to bad publicity in the construction industry. If a developer is thinking about putting up a new post tension building, and they have heard about the company's poor reputation in managing these types of buildings in the past, it could be the reason not to hire that company.

Luckily for Turnberry Tower Arlington, the local building officials did not delay the schedule significantly so no time was lost on construction. To make sure that the window wall subcontractor did not hit any more post tension tendons, they started to use a Ferrosan unit. This unit would tell the user precisely where all of the tendons and rebar were located in the slab. Everyone that was drilling into the slab was required to attend a training session on post tension tendons and how to properly use the Ferrosan unit.

If the decision was made to change to one of the reinforced concrete systems, the problem of the overall building height would need to be addressed. Because the reinforced concrete slabs would add 4 inches per floor to the building, the additional 9 feet would need to be taken into account. Presently with the post tension concrete design, the final building height would be at 409.70 feet, which is within 1/8 of an inch of the allowable height in the area.

The first thought is to attempt to make up the 9 feet by squeezing more space out of the plenum area. Unfortunately for this project, most of the space has vaulted ceilings that extend all the way to the slab above. That would mean that either of the scenarios would need to take place to use reinforced concrete; change the floor to ceiling heights in the units to make up the additional 9 feet, or take out one floor to make up the 9 feet.




Figure 9.5 – Comparing Structural Systems

The above *Figure 9.5* compares the three different systems visually. The left structure is the tower erected in the post tension concrete with a floor to ceiling height of 9'6" with a 7" slab. This tower has 25 floors. The middle structure is the tower erected in reinforced concrete with a floor to ceiling height of 9'2" with an 11" slab. This tower has 25 floors. The structure on the right is the tower erected in reinforced concrete with a floor to ceiling height of 9'6" with an 11" slab. This tower has 24 floors. All three towers start at elevation +129.00 and end at +409.70 which is within the allowable limits.

If the structure in the middle is used, the cost will be greater and the owner will not get the desired ceiling to floor heights, which is a selling point for these units. If the tower on the right is used the owner will achieve the desired floor to ceiling heights, but will lose 1 level of rentable units will decrease their profits by \$17.6 million.

After reviewing the results for both the schedule and the cost for all of the proposed alternative options (reinforced concrete), I believe that the best option is post tension concrete system, which is the system that was used. If the ceiling to floor height on each level is reduced, the owner will not be as happy because a major selling point of the building is the above average height in each apartment. This method will also add approximately \$2.2 million to the building. This cost is more than the mistakes caused by the post tension blowouts. If one floor is removed from the building, all of the floor to ceiling heights will remain, but the owner will lose \$17.6 million. This method also costs \$2 million more than the post tension system.

Using the post tension system is the cheapest and most efficient way to gain the desired floor to ceiling heights and get the maximum amount of rentable units in the building.

## **10. Analysis 2 – Supply Water System**

*(Mechanical Breadth & Critical Industry Issue)*

### 10.1 Introduction

When the developer obtained the finished set of plans from the architect, they went right to the general contractor for any value engineering ideas they had that may help to reduce cost or obtain more LEED points. A big VE item that was added was the Sovent System. This system helped to reduce the amount of waste pipe that was needed in the building by utilizing one stack for the drain, waste, and venting of waste products. I would like to take a closer look at VE ideas for the supply water.

### 10.2 Problem Statement

I would like to see if any value engineering ideas could have been used on the supply water piping. Then I would like to see if these materials could have saved time on the schedule, reduced the cost of the project, or helped to use fewer harmful products and make the project more LEED friendly.

### 10.3 Goal

I will start out the research by looking extensively at the existing system in the building which supplies the water to the different units. This system is a hybrid system that uses both copper and CPVC pipe. I will look at both methods of the pipes and see what can be done to speed up the installation process and lower the cost of installation. I will look at an alternative method of soldering the copper pipes, especially with Propress fittings, and see if prefabrication is an option for this project.

After the redesign of the system is proposed, I will check this new system to the existing system and see if there is any cost saving or schedule reduction. A LEED analysis will be performed to see how beneficial the new system may be, and what impact it played on gaining points.

#### 10.4 Research Steps

1. Research the existing system by interviewing the MEP Engineer, general contractor, and the owner's representatives. I will also look at construction progress photos to learn as much as possible.
2. Speak with other members of the construction and design community to learn about what products could be used to help speed up and/or reduce project cost.
3. Redesign the system using these new products and possible prefabrication options (Mechanical Breadth & Critical Industry Issue).
4. Compare the two systems in a cost and schedule analysis.
5. Learn what impact the redesigned system would have on obtaining LEED points.
6. Recommendation & Conclusion

#### 10.5 Tools

1. LEED Point Checklist
2. R.S. Means Cost Analysis
3. Microsoft Excel
4. Websites & Engineering Journals
5. Arlington Country tax rebate information
6. National Plumbing Code
7. MEP Engineer, General Contractor, and Owner's Representatives

#### 10.6 Expected Outcome

I expect that by using materials such as the Propress fittings, and utilizing construction techniques such as prefabrication, the schedule should accelerate the installation of the supply water system. I do think that the initial cost will increase because the Propress fittings will be more expensive, but I believe that the cost for the fittings will be offset by the labor cost for installation. I do expect to gain more LEED points because the harmful glues and soldering that contains VOC's will not have to be used if the Propress fittings are used.

#### 10.7 Existing Supply Water System - CPVC

The supply water system that was constructed for Turnberry Tower Arlington was a hybrid of copper pipe and CPVC pipe. The CPVC branches off of the copper riser pipes and runs directly into the residential units.

The CPVC pipe varies in size in the units between ½", ¾" and 1" diameter pipes. The pipe is connected with different elbows, tees, and reducers that are cemented together with glue. The glue has a VOC content that was said to be within the limits to achieve a LEED rating.

The pipes that are running above the finished ceiling in the units are connected with hangers. These hangers are connected to the above concrete deck with the use of the embeds that were placed during concrete erection. The picture below in Figure 10.1 shows the CPVC supply water pipe with hangers




Figure 10.1 – Use of CPVC Pipe

### 10.8 Use of Propress Supply Water System

An alternative system that is becoming well known is the Propress system. This system, in place of a traditional PVC or CPVC piping system, uses copper pipes to run water throughout the building. *Figure 10.2* shows different parts of the system that can be used.



Figure 10.2 – Propress System

What makes the Propress system different from the traditional copper pipe system is that it eliminates the need for soldering the pipes. The fittings are a clean and simple way to connect the pipe and they only need the use of a special drill to complete the connection. This eliminates the use of an expensive person to solder which in turn saves money. It also saves time on scheduling in order to complete the installation. This will save time and money since much more piping can be installed in the same amount of time. *Figure 10.3* shows the three step process to connect ends of pipes.




Figure 10.3 – Installing Propress Fittings

### 10.9 Redesigning the CPVC System Utilizing the Propress System

With the help of the mechanical subcontractor, I was able to redesign the supply water system using the Propress system for a typical residential unit in the building. The takeoff notes can found below in *Table 10.1*. The complete takeoff notes can be found in Appendix E. The price used for copper was \$3.10 which was the price of copper in 2006 when the original bids were estimated for this project.

| Propress System (2006) |                   |            |                |                |
|------------------------|-------------------|------------|----------------|----------------|
| Item                   | Mat. Cost         | Total Hrs. | Labor Cost     | Total Cost     |
| Pipe                   | \$956.42          | 10         | \$648          | \$1,604        |
| Fittings               | \$2,010.92        | 41         | \$2,735        | \$4,746        |
| Hanger Components      | \$405.87          | 34         | \$2,261        | \$2,667        |
| Misc. Components       | \$54.57           | 0          | \$0            | \$55           |
| <b>Total</b>           | <b>\$3,427.78</b> | <b>85</b>  | <b>\$5,644</b> | <b>\$9,072</b> |

Table 10.1 – Propress System Takeoff Notes Summary

### 10.10 Comparing the CPVC System vs. Propress System

After taking a look at the numbers I see both systems will utilize the same amount of pipe and same components to make the systems work. The material cost of the CPVC system will be \$1670 and the material cost of the Propress System will be \$3428. The material cost increase for the Propress System is because of the price of the actual copper.

The material cost is slightly made up for in the installation of the system. The installation of the CPVC system would be \$6754, and it would take 102 man hours to complete each residential unit. The Propress system would cost \$5644 and would take 85 man hours to complete. The total cost of the CPVC supply water system to install (with labor) per residential unit will be \$8424 and the total cost of the Propress system to install (with labor) per residential unit will be \$9072. The results can be found below in *Table 10.2*. The price for copper used came from the 2006 cost of copper which was \$3.10 per pound. The price for CPVC was approximately the same in 2006 as it is today.

| Comparing CPVC vs. Propress Supply Water Systems (Per Typical Unit) |                |            |                |                |                        |                |            |                |                |
|---|----------------|------------|----------------|----------------|------------------------|----------------|------------|----------------|----------------|
| CPVC System   |                |            |                |                | Propress System (2006) |                |            |                |                |
| Item  | Mat. Cost      | Total Hrs. | Labor Cost     | Total Cost     | Item                   | Mat. Cost      | Total Hrs. | Labor Cost     | Total Cost     |
| Pipe  | \$856.48       | 10         | \$649          | \$1,505        | Pipe                   | \$956.42       | 10         | \$648          | \$1,604        |
| Fittings  | \$350.26       | 58         | \$3,844        | \$4,194        | Fittings               | \$2,010.92     | 41         | \$2,735        | \$4,746        |
| Hanger Components   | \$405.87       | 34         | \$2,261        | \$2,667        | Hanger Components      | \$405.87       | 34         | \$2,261        | \$2,667        |
| Misc. Components  | \$56.90        | 0          | \$0            | \$57           | Misc. Components       | \$54.57        | 0          | \$0            | \$55           |
| <b>Total</b>  | <b>\$1,670</b> | <b>102</b> | <b>\$6,754</b> | <b>\$8,424</b> | <b>Total</b>           | <b>\$3,428</b> | <b>85</b>  | <b>\$5,644</b> | <b>\$9,072</b> |

Table 10.2 – Comparing Systems

The mechanical subcontractor has used the Propress system before so there would be no cost incurred for the tools to install the equipment and no time lost to account for the learning curve to use the equipment.

10.11 LEED Impact

The CPVC was being assembled and connected using glues and cement agents that give off harmful Volatile Organic Compounds (VOC’s). To qualify for the Indoor Air Quality Credit 4.1 (Low Emitting Materials: Adhesives & Sealants), the VOC level given off needed to be below the LEED required levels that were:

|                             |         |
|-----------------------------|---------|
| Adhesive Primer for Plastic | 550 g/L |
| Contact Adhesive            | 80 g/L  |

The actual materials used were not able to be found, but were said to be below the required VOC levels set forth by the specifications and LEED.

Since the products used to connect the CPVC pipes were below the LEED required levels, using the Propress system will not have an impact on gaining LEED points. There is not another point that is able to be obtained for using a product that does not give out a VOC level. Indoor Air Quality Credit 4.1 (Low Emitting Materials: Adhesives & Sealants) will be obtained if either system is utilized.

10.12 Conclusion & Recommendation

The first item to compare is the cost difference between both systems. A takeoff was performed for the supply water system using both the CPVC system and the proposed Propress system for a typical residential unit. The takeoff included material cost, labor hours to install, and installation costs for the entire system per unit. The total cost for the CPVC system would be \$2,080,728 and the total cost for the Propress system would be \$2,240,784, as seen below in *Table 10.3*.

| Cost of Supply Water System to Units in Turnberry Tower Arlington |                          |                    |                           |                        |                          |                    |                           |
|---|--------------------------|--------------------|---------------------------|------------------------|--------------------------|--------------------|---------------------------|
| CPVC System   |                          |                    |                           | Propress System (2006) |                          |                    |                           |
| Cost Per Unit   | Total Cost for 247 Units | Man Hours per Unit | Total Hours for 247 Units | Cost Per Unit          | Total Cost for 247 Units | Man Hours per Unit | Total Hours for 247 Units |
| \$8,424   | \$2,080,728              | 102                | 25,194                    | \$9,072                | \$2,240,784              | 85                 | 20,995                    |
| Time Savings Using Propress System over CPVC System (Man Hours)   |                          |                    |                           |                        |                          |                    | 4,199                     |
| Cost Savings Using Propress System over CPVC System (\$)          |                          |                    |                           |                        |                          |                    | (\$160,056)               |

Table 10.3 – Total Cost Comparing Systems

There is a cost increase of approximately \$160,000 if the Propress system is used for Turnberry Tower Arlington. The bulk of the cost increase comes from the price of copper in the third quarter of 2006. Even though on average, 17 man hours is saved per residential unit, the cost savings from the less labor does not offset the high cost of copper.

The reason believed that this system was not used was because of the fast rising cost of copper. As the cost of copper keeps rising, so does the likelihood that it will disappear off the site and be stolen. This construction site was constantly monitored so the expensive supplies and materials such as copper would not be stolen. On this project, a dedicated room was built and fit with an alarm so if someone did try to break in and steal the copper they would be caught. In addition, a security guard was on duty after hours to protect the site from theft and damage.

Even if the Propress system was used and the mechanical subcontractor, general contractor, and architect wanted to take the chance that copper would not have been stolen, the project would cost much more than the CPVC system. At the beginning of construction in 2006, the price of copper was around \$3.10 a pound. No one could tell if the price of copper was going to continue to rise or start to decrease because of the huge construction boom in both the United States as well as overseas in places like Dubai and China.

Since Turnberry Tower Arlington is going for a LEED certification, a reason to pay the additional \$160,000 would be to gain the extra LEED point that may have come with using the Propress system. To obtain the Indoor Air Quality Credit 4.1 (Low Emitting Materials: Adhesives & Sealants), the VOC level of the adhesive materials used to connect the piping needed to be below the given levels. The Propress system utilizes a mechanical bond so no VOC's are released in the air, but the adhesives and cement products that would be used for the CPVC system would be below the required LEED levels. Thus, both systems would meet the LEED requirements so that would mean to go with the less expensive system.

Even though the Propress system was a viable option during the beginning of construction, because of the price of copper in 2006, using CPVC Pipe for the supply water system of Turnberry Tower Arlington was the right decision. Currently in the first quarter of 2009, the cost of copper is significantly lower, and when the numbers are run the cost of the Propress system would be significantly less. Thus, if Turnberry Tower Arlington was being designed today, I would recommend using the Propress system for the supply water system.



## **11. Analysis 3 – Site Logistics Plan for Drywall Deliveries**

### 11.1 Introduction

Every construction project requires a site logistics plan that enables the building to be built. The site logistics plan for this project utilizes one road on the north side of the site for most of the site deliveries, as well as the access road for all of the concrete trucks to stage. During certain times of the week while deliveries and trucks are trying to move around, traffic around the site was slowed down which caused law enforcement in the area to get involved. Stop work orders by the county were threatened a few times.

### 11.2 Problem Statement

There were always problems with drywall deliveries. The drywall deliveries would always need to be planned to occur around the concrete deliveries. This was due to the fact that there was so much drywall on this project; many of the deliveries had to occur outside the normal work day. This caused overtime to be paid to the workers that were forced to work during night and weekend deliveries.

### 11.3 Goal

I would like to research why the site logistics plan was created the way it was and explore other options that would allow for drywall to deliveries to occur simultaneously while concrete is being delivered. Utilizing the other parts of the site should allow for this to be possible.

### 11.4 Research Steps

1. Speak to the superintendent who created the site logistics plan and learn about their logic.
2. Talk to Arlington County in Virginia and learn about local ordinances and requirements for construction sites and see if another loading dock would be allowed.
3. Propose another site plan that would help deliveries for the drywall subcontractor.
4. Compile the research and compare the new site plan to the existing site plan and see if it would help to reduce overtime costs.
5. Conclusion & Recommendation

### 11.5 Tools

1. General Contractor Personnel
2. Drywall Subcontractor
3. Arlington County Code Officials
4. Microsoft Powerpoint
5. Adobe Fireworks

### 11.6 Expected Outcome

After working on the project site for two summers and seeing how congested the delivery lane was because of all the deliveries, I believe re-evaluating the site logistics plan would increase material delivery during the normal work day. Utilizing the other main road that surrounds the site, another site logistics plan can be developed that allows for more deliveries including the drywall, which would then reduce the need for deliveries on the weekends and reduce the cost of overtime.

### 11.7 Understanding the Existing Site Plan

To better understand the area, below in *Figure 11.1* is an image from googlemaps.com that shows the surrounding Rosslyn area of Arlington Virginia.




Figure 11.1 – Aerial Photo

Below in *Figure 11.2* is the site plan that was used for the construction of Turnberry Tower Arlington. (An enlarged version of the site plan below can be found in Appendix F.)




Figure 11.2 – Existing Site Plan

Looking at the satellite image and the site plan, it is easy to see that this site is in a very congested neighborhood with tall buildings and main roads that help connect this area directly to Washington, D.C. The ability to close roads and sidewalks in the area required constant communication with traffic officials working for the County of Arlington at a hefty cost.

In order to maximize productivity around the site and allow for the least disturbance to traffic flow around the site, the sidewalk on the construction site side of Fort Myer Drive was covered over and included behind the temporary covered sidewalk. Additionally, one lane of traffic was closed on Fort Myer Drive and the temporary covered sidewalk was built to allow for undisturbed pedestrian flow around the construction site.

Since Fort Myer Drive is a heavily traveled road, the covered sidewalk was built with jersey barriers and 4x4's place 18 inches on center with a 20 year built up roof, which you can see below in *Figure 11.3*.



Figure 11.3 – Covered Walkway

On the west side of the site there were three lanes, one lane of parking and two travel lanes. The general contractor decided to rent out the lane of parking meters on a renewable one year lease and then rerouted the traffic into the other two lanes that were available. The rented out parking meters allowed for the material delivery lane that can be seen in Figure 11.2.

The site was secured completely around the perimeter. On the north side was an existing parking garage that belonged to the hotel next door. On the east and south of the site was the covered walkway that can be seen in *Figure 11.3* above. On the west of the site, where the material delivery lane was located, jersey barriers were installed which contained 12 foot high chain link fence with barbed wire on top.

The site plan that is seen in Figure 11.2 was used for two primary reasons. The county was very strict with enforcing that vehicular traffic could not be impacted, especially during rush hour. That eliminated the use of Fort Myer Drive as a main point of access because deliveries would need to be brought to site starting early in the day. Losing two hours during the designated rush hour would greatly affect the schedule. By using Nash Street on the west side of the site, deliveries would be allowed to begin earlier.

The second reason that this site plan was used was because of the location of the building on the west side of the site. This side led directly into the building's main lobby without having to deal with the slope of the land and gave access to the building's loading dock. If you were to stand on grade on the Fort Myer Drive side of the building, you would actually be 3 levels below the lobby as seen below in Figure 11.4.

Lobby Level



Figure 11.4 – Standing on Fort Myer Drive

Using Nash Street was the best way to utilize the lay of the land and the features of the building being constructed. The loading dock was used to take deliveries that semi-trucks were able to back into the loading dock. The material hoist was located on top of the material hoist. As you can see from the site plan above in Figure 11.2, all of the necessary services for material deliveries were located around this material delivery lane.

#### 11.8 Referring to Arlington County About Logistic Changes

Fort Myer Drive is deemed by Arlington County as a main access road because it leads directly from Key Bridge into Arlington County. This road is heavily used at all times of the day and backed up during peak hours which include rush hour in both the morning and afternoon.

In order to be able to use Fort Myer Drive to accept any deliveries on a regular basis, a plan would need to be developed that would assure county officials that more vehicular traffic would not be created. The county was very upset during excavation of the site because the Fort Myer Drive side of the site was used as the main access point for all dump trucks entering and exiting the site.

These dump trucks would start early in the morning, during rush hour, and would cause delays that would extend back all the way over Key Bridge. This brought law enforcement on the site who threatened to shut down the site with a stop work order. Thus, any logistic plan would be very carefully reviewed by the county and would be subject to suspension if any problems occurred that caused traffic.

#### 11.9 Modifying the Site Plan for the Drywall Subcontractor

After studying the site plan used and noticing how much overtime was being put in by some of the trades to stock materials, especially the drywall subcontractor, I have come up with a modification of the existing site plan that utilizes the space on Fort Myer Drive more efficiently.

Below in *Figure 11.5* is the proposed modification to the existing site plan. As you can see, the Fort Myer Drive section has been modified with 2 swing gates that will allow semi-trucks to enter and exit the site with no problems. This site plan can also be found in Appendix F.




Figure 11.5 – Modification to Existing Site Plan

The material hoists are located on the other side of the building so there is no way to load the drywall directly into the building at this level. The solution to this problem is to load the drywall on the crane on the back of a 42' drywall truck. As you can see in the above Figure 11.5, the drywall truck will stay stationed on site while drywall is being delivered via other flatbed trucks.




Figure 11.6 – 2<sup>nd</sup> Floor of Turnberry Tower Arlington

As can be seen in *Figure 11.6* above, the materials will be lifted up to the 2<sup>nd</sup> floor of the building into residential unit B East. To allow for the materials to be loaded through this unit, the exterior railing and the window wall for this unit will not be installed until after the concrete erection is complete and the drywall can be delivered to site via the material delivery lane. In place of the window wall, heavy plastic will be hung to keep out moisture from the inside of the building and OSHA certified rope will be hung in the place of the railing.

Above in *Figure 11.6*, it shows where the material will be brought into the 2<sup>nd</sup> floor of the building, but there exists a problem in being able to get the drywall from the access point to the material hoists. The material hoists are in the upper right hand corner and colored green. Below, *Figure 11.7* shows how I plan to get the drywall to the material hoists.




Figure 11.7 – Propose 2<sup>nd</sup> Floor of Turnberry Tower Arlington during Drywall Delivery

By not framing out and completing some of the units on the 2<sup>nd</sup> floor, it will allow for the drywall to be carted from the point where it is dropped off from the crane to the access point for the material hoists. Once the concrete erection is complete and the drywall can be delivered via the material delivery lane, the 2<sup>nd</sup> floor can be finished. Both *Figure 11.6 and 11.7* can be found in Appendix F.

### 11.10 Comparing Site Plans

The existing site plan that was used for construction of the building only allowed for one main delivery lane. Concrete had the primary use over this lane to erect the concrete decks. When the concrete was not being brought to site, other trades could bring in their materials. While concrete was being erected and other trades needed to bring in materials to keep up with the schedule, trades like the drywall subcontractor resorted to stocking the building with drywall after normal working hours or during the weekends. This resulted in having to pay out overtime in some cases.

If the proposed site logistics plan is used by the drywall subcontractor and helps to reduce the amount of overtime needed, it will help save money. Below in *Table 11.1* is an example of how the proposed site logistics plan would help this project for stocking a certain amount of drywall boards. A standard labor rate of \$22 per person per hour is used and time and half is used for overtime. It is assumed that the modified site logistics plan only increases the productivity of stocking materials by 200 drywall boards during a regular 40 hour week and the remainder of the work is done in an overtime period. In this example, the overtime for the proposed site logistics plan would be 1/3 less based on the productivity done during the 40 hour work week.

| Existing Site Logistics Plan                      |                                     |                                     |   |
|---|-------------------------------------|-------------------------------------|---|
| # of Boards Stocked During 40 Hour Week           | Cost for 4 Man Crew (Standard Wage) | # of Boards Stocked During Overtime | Cost for 4 Man Crew (1.5 Standard Wage) |
| 400   | \$22 per person per hour            | 600                                 | \$33 per person per hour                |
| <b>Total Cost for 4 Man Crew for 1000 Boards:</b> |                                     |                                     | <b>\$5,632</b>                          |
| Proposed Site Logistics Plan                      |                                     |                                     |   |
| # of Boards Stocked During 40 Hour Week           | Cost for 4 Man Crew (Standard Wage) | # of Boards Stocked During Overtime | Cost for 4 Man Crew (1.5 Standard Wage) |
| 600   | \$22 per person per hour            | 400                                 | \$33 per person per hour                |
| <b>Total Cost for 4 Man Crew for 1000 Boards:</b> |                                     |                                     | <b>\$4,880</b>                          |

Table 11.1 - Existing vs. Proposed Site Plan (OT needed for Proposed Site Plan)

Assuming the productivity only increases by 20% during the 40 hour work week, a savings on labor over \$750 will be credited to the project per 1000 boards. This project has 91,000 sheets of drywall to load into the building.



If the site logistics plan works and can save the project from having to pay any overtime to stock drywall, the results can be seen below in *Table 11.2*.

| Existing Site Logistics Plan                      |                                     |                                     |   |
|---|-------------------------------------|-------------------------------------|---|
| # of Boards Stocked During 40 Hour Week           | Cost for 4 Man Crew (Standard Wage) | # of Boards Stocked During Overtime | Cost for 4 Man Crew (1.5 Standard Wage) |
| 400   | \$22 per person per hour            | 600                                 | \$33 per person per hour                |
| <b>Total Cost for 4 Man Crew for 1000 Boards:</b> |                                     |                                     | <b>\$5,632</b>                          |
| Proposed Site Logistics Plan                      |                                     |                                     |   |
| # of Boards Stocked During 40 Hour Week           | Cost for 4 Man Crew (Standard Wage) | # of Boards Stocked During Overtime | Cost for 4 Man Crew (1.5 Standard Wage) |
| 1000  | \$22 per person per hour            | 0                                   | \$33 per person per hour                |
| <b>Total Cost for 4 Man Crew for 1000 Boards:</b> |                                     |                                     | <b>\$3,520</b>                          |

Table 11.2 – Existing vs. Proposed Site Plan (No OT for Proposed Site Plan)

A savings can be seen in this example of a little more than \$2000 per 1000 drywall boards. This project has 91,000 sheets of drywall to load into the building.

It is seen in the above examples that on a building such as Turnberry Tower Arlington that requires drywall to be constantly stocked that if another access point is created to deliver drywall during the normal 40 hour week that it will save the project overtime costs tremendously.

The biggest comparison to the two site plans is that the proposed site plan, seen in Figure 11.5, requires 2 new access points to allow these drywall trucks to enter and exit the site. This will require the need for a flagman to help these trucks exit the site onto the heavily trafficked Fort Myer Drive.

### 10.11 Conclusion & Recommendation

The biggest hurdle to overcome that would make it possible to modify the existing site logistics plan would be to get Arlington County to approve the plan and agree that it would not create any more traffic around the site than there already is. Once the county is satisfied with the modified plan, the analysis shows how another delivery point for drywall would help.

Not completing part of the 2<sup>nd</sup> level of the building will make the 3<sup>rd</sup> level of the building all that much more important. The 2<sup>nd</sup> level was going to be used as the mock up to identify and MEP clashes and have them corrected on the upper floors. If the modified site plan is used, the third floor would have to be the first floor completed on the SIP Schedule.

The SIPS was created so that concrete erection was above a few floors above the deck that was to be roughed in with drywall tracks. Even though risers were attached, this process eliminated the chance that reshores would be in the way of drywall studs and MEP could be installed with nothing in the way.

Since the reshores only had to be placed 3 floors below the working deck, the existing SIPS has the first activity occurring on the 2<sup>nd</sup> floor when the 7<sup>th</sup> floor is being erected. If instead work began on the 3<sup>rd</sup> floor during this week, the 2<sup>nd</sup> floor could be complete later on in the project and no time will be lost on the SIPS. This would allow the modified site plan to be used with no schedule impact.

The material hoist time would need to be divided up a little more thoroughly. With the existing site plan, whichever trade is in the loading dock would have access to the material hoist. If there are two points where materials are being delivered, the time on the hoist would need to be divided, or since there are two hoists each material would get only one hoist instead of two. Luckily for the drywall, if this modified site plan is used, the second floor will remain relatively empty which will allow for some material storage. This can allow for use of the material hoist while concrete erection is occurring and there are no other deliveries.

Looking at the examples that show money could be saved, and showing that the schedule would not be impacted from this modified site plan, I recommend that this site plan be implemented on this project if Arlington County approves the plan.

## Appendix A

### Project Schedules


Contents:

- Project Summary Schedule
- Short Interval Production Schedule (SIPS)
- Detailed Project Schedule

| ID | Task Name                                   | Duration | Start        | Finish       | Timeline |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
|----|---|----------|--------------|--------------|----------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|-----|-----|-----|-----|-----|-----|------|-----|-----|-----|--|--|--|--|--|
|    |   |          |              |              | 4th Qtr  | 1st Qtr | 2nd Qtr | 3rd Qtr | 4th Qtr | 1st Qtr | 2nd Qtr | 3rd Qtr | 4th Qtr | 1st Qtr | 2nd Qtr | 3rd Qtr | 4th Qtr | 1st Qtr | 2nd Qtr | 3rd Qtr | 4th Qtr |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
|    |   |          |              |              | Oct      | Nov     | Dec     | Jan     | Feb     | Mar     | Apr     | May     | Jun     | Jul     | Aug     | Sept    | Oct     | Nov     | Dec     | Jan     | Feb     | Mar | Apr | May | Jun | Jul | Aug | Sept | Oct | Nov | Dec |  |  |  |  |  |
| 1  | Abatement - Existing Structure              | 22 days  | Wed 9/27/06  | Thu 10/26/06 |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 2  | Demolition - Existing Structure             | 50 days  | Wed 9/27/06  | Tue 12/5/06  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 3  | Notice to Proceed                           | 0 days   | Mon 11/20/06 | Mon 11/20/06 | ◆ 11/20  |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 4  | Line Drill & Pile Work                      | 97 days  | Thu 12/28/06 | Fri 5/11/07  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 5  | Soldier Piles and Underpinning              | 131 days | Thu 12/28/06 | Thu 6/28/07  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 6  | Sheet & Bracing - Elevation 110 to Subgrade | 121 days | Fri 1/12/07  | Fri 6/29/07  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 7  | Structure Excavation                        | 116 days | Thu 2/8/07   | Thu 7/19/07  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 8  | Soil & Rock Excavation 90 to subgrade       | 101 days | Mon 2/26/07  | Mon 7/16/07  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 9  | Concrete Foundation through Level 1         | 184 days | Tue 7/31/07  | Fri 4/11/08  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 10 | Masonry                                     | 124 days | Wed 2/13/08  | Mon 8/4/08   |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 11 | MEP Rough In / Risers                       | 225 days | Wed 3/19/08  | Tue 1/27/09  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 12 | Concrete Level 2 through Roof               | 172 days | Mon 4/7/08   | Tue 12/2/08  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 13 | Curtain Wall                                | 191 days | Mon 6/2/08   | Mon 2/23/09  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 14 | Drywall                                     | 179 days | Mon 6/2/08   | Thu 2/5/09   |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 15 | Waste & Recycle System Installation         | 230 days | Wed 6/4/08   | Tue 4/21/09  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 16 | MEP Horizontal and Trim                     | 192 days | Mon 7/7/08   | Tue 3/31/09  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 17 | Tower Elevators                             | 138 days | Tue 9/30/08  | Thu 4/9/09   |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 18 | Doors and Hardware                          | 128 days | Thu 10/2/08  | Mon 3/30/09  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 19 | Painting                                    | 150 days | Tue 10/7/08  | Mon 5/4/09   |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 20 | Install Kitchen and Vanity Cabinets         | 129 days | Fri 10/17/08 | Wed 4/15/09  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 21 | Tile Walls and Floors                       | 137 days | Fri 10/17/08 | Mon 4/27/09  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 22 | Stone Counter Tops (Kitchen and Bathroom)   | 127 days | Tue 10/21/08 | Wed 4/15/09  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 23 | Install Signs & Identification              | 109 days | Thu 12/11/08 | Tue 5/12/09  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 24 | Install Roof - Building Watertight          | 30 days  | Wed 1/14/09  | Tue 2/24/09  |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 25 | Life Safeties and Building Commissioning    | 60 days  | Fri 4/10/09  | Thu 7/2/09   |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 26 | Substantial Completion                      | 0 days   | Tue 7/7/09   | Tue 7/7/09   | ◆ 7/7    |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 27 | Post Completion Testing & Commissioning     | 42 days  | Wed 7/8/09   | Thu 9/3/09   |          |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |
| 28 | Certificate of Occupancy                    | 0 days   | Wed 9/9/09   | Wed 9/9/09   | ◆ 9/9    |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |         |     |     |     |     |     |     |      |     |     |     |  |  |  |  |  |

|   |           |   |                     |   |                    |  |                  |   |
|---|-----------|---|---------------------|---|--------------------|--|------------------|---|
| Turnberry Tower Arlington<br>Project Summary Schedule | Task      |   | Summary             |   | Rolled Up Progress |  | Project Summary  |   |
|   | Progress  |   | Rolled Up Task      |   | Split              |  | Group By Summary |   |
|   | Milestone | ◆ | Rolled Up Milestone | ◇ | External Tasks     |  | Deadline         | ↓ |





Project: Project1.mpp  
Date: Wed 10/22/08

Task Progress Summary External Tasks Deadline

Split Milestone Project Summary External Milestone

| ID  | Task Name                                 | Duration        | Start              | 1st Half    |     |     |             |     |     |             |     |     | 1st Half    |     |     |             |     |     |             |     |     | 1st Half    |     |     |             |     |     |  |  |  |
|-----|---|-----------------|--------------------|-------------|-----|-----|-------------|-----|-----|-------------|-----|-----|-------------|-----|-----|-------------|-----|-----|-------------|-----|-----|-------------|-----|-----|-------------|-----|-----|--|--|--|
|     |   |                 |                    | 1st Quarter |     |     | 3rd Quarter |     |     | 1st Quarter |     |     | 3rd Quarter |     |     | 1st Quarter |     |     | 3rd Quarter |     |     | 1st Quarter |     |     | 3rd Quarter |     |     |  |  |  |
|     |   |                 |                    | Nov         | Jan | Mar | May         | Jul | Sep | Nov         | Jan | Mar | May         | Jul | Sep | Nov         | Jan | Mar | May         | Jul | Sep | Nov         | Jan | Mar | May         | Jul | Sep |  |  |  |
| 56  | Level P1                                  | 73 days         | Mon 5/26/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 57  | <b>Condo Rough-in (MEP &amp; Framing)</b> | <b>169 days</b> | <b>Thu 6/12/08</b> |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 58  | Floor 02                                  | 32 days         | Thu 6/12/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 59  | Floor 03                                  | 32 days         | Mon 6/23/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 60  | Floor 04                                  | 32 days         | Tue 7/1/08         |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 61  | Floor 05                                  | 32 days         | Thu 7/10/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 62  | Floor 06                                  | 32 days         | Wed 7/16/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 63  | Floor 07                                  | 32 days         | Mon 7/28/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 64  | Floor 08                                  | 32 days         | Wed 8/6/08         |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 65  | Floor 09                                  | 32 days         | Mon 8/18/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 66  | Floor 10                                  | 32 days         | Tue 8/26/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 67  | Floor 11                                  | 32 days         | Thu 9/4/08         |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 68  | Floor 12                                  | 32 days         | Fri 9/12/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 69  | Floor 14                                  | 32 days         | Fri 9/19/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 70  | Floor 15                                  | 32 days         | Tue 9/30/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 71  | Floor 16                                  | 32 days         | Tue 10/7/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 72  | Floor 17                                  | 32 days         | Tue 10/14/08       |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 73  | Floor 18                                  | 32 days         | Mon 10/20/08       |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 74  | Floor 19                                  | 32 days         | Thu 10/30/08       |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 75  | Floor 20                                  | 32 days         | Thu 11/6/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 76  | Floor 21                                  | 32 days         | Wed 11/12/08       |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 77  | Floor 22                                  | 32 days         | Thu 11/20/08       |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 78  | Floor 23                                  | 32 days         | Mon 12/1/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 79  | Floor 24                                  | 32 days         | Fri 12/5/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 80  | Floor 25                                  | 32 days         | Fri 12/12/08       |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 81  | Floor 26                                  | 32 days         | Mon 12/22/08       |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 82  | <b>Window Wall / Curtain Wall</b>         | <b>143 days</b> | <b>Mon 4/21/08</b> |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 83  | Floor 02                                  | 28 days         | Mon 4/21/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 84  | Floor 03                                  | 28 days         | Mon 4/28/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 85  | Floor 04                                  | 28 days         | Mon 5/5/08         |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 86  | Floor 05                                  | 28 days         | Mon 5/12/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 87  | Floor 06                                  | 28 days         | Mon 5/19/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 88  | Floor 07                                  | 28 days         | Mon 5/26/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 89  | Floor 08                                  | 28 days         | Mon 6/2/08         |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 90  | Floor 09                                  | 28 days         | Mon 6/9/08         |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 91  | Floor 10                                  | 28 days         | Mon 6/16/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 92  | Floor 11                                  | 28 days         | Mon 6/23/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 93  | Floor 12                                  | 28 days         | Mon 6/30/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 94  | Floor 14                                  | 28 days         | Mon 7/7/08         |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 95  | Floor 15                                  | 28 days         | Mon 7/14/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 96  | Floor 16                                  | 28 days         | Mon 7/21/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 97  | Floor 17                                  | 28 days         | Mon 7/28/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 98  | Floor 18                                  | 28 days         | Mon 8/4/08         |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 99  | Floor 19                                  | 28 days         | Mon 8/11/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 100 | Floor 20                                  | 28 days         | Mon 8/18/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 101 | Floor 21                                  | 28 days         | Mon 8/25/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 102 | Floor 22                                  | 28 days         | Mon 9/1/08         |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 103 | Floor 23                                  | 28 days         | Mon 9/8/08         |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 104 | Floor 24                                  | 28 days         | Mon 9/15/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 105 | Floor 25                                  | 28 days         | Mon 9/22/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 106 | Floor 26                                  | 28 days         | Mon 9/29/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 107 | <b>Drywall &amp; Tape</b>                 | <b>136 days</b> | <b>Mon 7/7/08</b>  |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 108 | Floor 02                                  | 21 days         | Mon 7/7/08         |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 109 | Floor 03                                  | 21 days         | Mon 7/14/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |
| 110 | Floor 04                                  | 21 days         | Mon 7/21/08        |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |             |     |     |  |  |  |










|   |       |  |           |  |                 |  |                    |  |          |  |
|---|-------|--|-----------|--|-----------------|--|--------------------|--|----------|--|
| Project: Project1.mpp<br>Date: Wed 10/22/08 | Task  |  | Progress  |  | Summary         |  | External Tasks     |  | Deadline |  |
|   | Split |  | Milestone |  | Project Summary |  | External Milestone |  |          |  |





| ID  | Task Name                      | Duration        | Start              | 1st Half    |     |     |     |             |     |     |     |     | 1st Half    |     |     |     |             |     |     |     |     | 1st Half    |     |     |     |             |     |  |  |  |
|-----|--------------------------------|-----------------|--------------------|-------------|-----|-----|-----|-------------|-----|-----|-----|-----|-------------|-----|-----|-----|-------------|-----|-----|-----|-----|-------------|-----|-----|-----|-------------|-----|--|--|--|
|     |                                |                 |                    | 1st Quarter |     |     |     | 3rd Quarter |     |     |     |     | 1st Quarter |     |     |     | 3rd Quarter |     |     |     |     | 1st Quarter |     |     |     | 3rd Quarter |     |  |  |  |
|     |                                |                 |                    | Nov         | Jan | Mar | May | Jul         | Sep | Nov | Jan | Mar | May         | Jul | Sep | Nov | Jan         | Mar | May | Jul | Sep | Nov         | Jan | Mar | May | Jul         | Sep |  |  |  |
| 166 | Floor 03                       | 35 days         | Mon 8/18/08        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 167 | Floor 04                       | 35 days         | Mon 8/25/08        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 168 | Floor 05                       | 35 days         | Mon 9/1/08         |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 169 | Floor 06                       | 35 days         | Mon 9/8/08         |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 170 | Floor 07                       | 35 days         | Mon 9/15/08        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 171 | Floor 08                       | 35 days         | Mon 9/22/08        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 172 | Floor 09                       | 35 days         | Mon 9/29/08        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 173 | Floor 10                       | 35 days         | Mon 10/6/08        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 174 | Floor 11                       | 35 days         | Mon 10/13/08       |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 175 | Floor 12                       | 35 days         | Mon 10/20/08       |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 176 | Floor 14                       | 35 days         | Mon 10/27/08       |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 177 | Floor 15                       | 35 days         | Mon 11/3/08        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 178 | Floor 16                       | 35 days         | Mon 11/10/08       |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 179 | Floor 17                       | 35 days         | Mon 11/17/08       |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 180 | Floor 18                       | 35 days         | Mon 11/24/08       |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 181 | Floor 19                       | 35 days         | Mon 12/1/08        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 182 | Floor 20                       | 35 days         | Mon 12/8/08        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 183 | Floor 21                       | 35 days         | Mon 12/15/08       |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 184 | Floor 22                       | 35 days         | Mon 12/29/08       |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 185 | Floor 23                       | 35 days         | Mon 1/5/09         |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 186 | Floor 24                       | 35 days         | Mon 1/12/09        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 187 | Floor 25                       | 35 days         | Mon 1/19/09        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 188 | Floor 26                       | 35 days         | Mon 1/26/09        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 189 | <b>Elevators</b>               | <b>247 days</b> | <b>Thu 9/18/08</b> |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 190 | Set Temporary Elevators        | 67 days         | Fri 12/12/08       |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 191 | Use Temporary Elevators        | 123 days        | Wed 3/11/09        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 192 | Tower Elevators                | 146 days        | Thu 9/18/08        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 193 | <b>General Items</b>           | <b>323 days</b> | <b>Thu 2/14/08</b> |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 194 | Building Water-tight           | 30 days         | Tue 1/13/09        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 195 | Building Masonry               | 124 days        | Thu 2/14/08        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 196 | Drywall (Lobby & Public Areas) | 178 days        | Tue 6/3/08         |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 197 | Painting (Public Areas)        | 154 days        | Wed 10/8/08        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 198 | Tile Walls & Floors            | 126 days        | Mon 10/20/08       |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |
| 199 | Substantial Completion         | 0 days          | Sun 8/30/09        |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |     |     |     |             |     |     |     |             |     |  |  |  |

Project: Project1.mpp  
Date: Wed 10/22/08

Task  Progress  Summary  External Tasks  Deadline   
 Split  Milestone  Project Summary  External Milestone 

## **Appendix B**

### Project Estimates

#### Contents:

- R.S. Means 2008 Estimate
- D4 Cost 2002 Estimate
- General Conditions Estimate
- Structural System Estimate (Post Tension Concrete)

### R.S. Means 2008 Data

#### Tower

|                               |                   |          |          |          |
|-------------------------------|-------------------|----------|----------|----------|
| Exterior Wall                 | S.F Area          | 400,000  | 500,000  | 600,000  |
|                               | L.F. Perimeter    | 570      | 600      | 630      |
| Ribbed Precast Concrete Panel | R/ Concrete Frame | \$159.10 | \$156.98 | \$154.85 |
| Perimeter Adjustment          |                   | \$2.35   | \$1.93   | \$1.50   |
| Story Height Adjustment       |                   | \$1.25   | \$1.08   | \$0.90   |

| Additions                   | Cost Per Unit | Total Cost         |
|-----------------------------|---------------|--------------------|
| Appliances                  | \$8,625       | \$2,233,875        |
| Elevators                   | N/A           | \$2,228,000        |
| Elevator Additional Stops   | N/A           | \$1,323,000        |
| <b>Total Additions</b>      |               | <b>\$5,784,875</b> |
| <b>Cost per Square Foot</b> |               | <b>\$11.57</b>     |

|                      |                 |
|----------------------|-----------------|
| Square Foot Estimate | \$156.98        |
| Perimeter Adjustment | \$1.24          |
| Additions            | \$11.57         |
| <b>Total per SF</b>  | <b>\$169.79</b> |

#### Parking Levels

|                               |                   |         |
|-------------------------------|-------------------|---------|
| Exterior Wall                 | S.F Area          | 40,000  |
|                               | L.F. Perimeter    | 600     |
| Ribbed Precast Concrete Panel | R/ Concrete Frame | \$73.00 |
| Perimeter Adjustment          |                   | \$2.45  |
| Story Height Adjustment       |                   | \$1.45  |

|                      |                |
|----------------------|----------------|
| Square Foot Estimate | \$73.00        |
| Perimeter Adjustment | \$4.90         |
| <b>Total per SF</b>  | <b>\$77.90</b> |

#### Total

|  | Square Feet | Cost per SF | Total Cost           |
|--|-------------|-------------|----------------------|
| Residential Tower                          | 500,000     | \$169.79    | \$84,895,000         |
| Parking Garage                             | 240,000     | \$77.90     | \$18,696,000         |
|  |             |             | \$103,591,000        |
| R.S. Means Location Factor (Arlington, VA) |             |             | 1.04                 |
| <b>Total Estimate</b>                      |             |             | <b>\$107,734,640</b> |

**D4 COST 2002**

Sunday, September 21, 2008

**Statement of Probable Cost**

Page 1

Turnberry Tower Arlington - Sep 2009 - VA - Arlington

Prepared By: **Larry Warner**

Prepared For:

Building Sq. Size: **500000**  
 Bid Date:  
 No. of floors: **31**  
 No. of buildings: **1**  
 Project Height: **210**  
 1st Floor Height: **10**  
 1st Floor Size: **20000**

Site Sq. Size: **853426**  
 Building use: **Residential**  
 Foundation: **CON**  
 Exterior Walls: **CUR**  
 Interior Walls: **GYP**  
 Roof Type: **EPD**  
 Floor Type: **CON**  
 Project Type: **NEW**

| Division  |  | Percent      | Sq. Cost     | Amount            |
|-----------|--|--------------|--------------|-------------------|
| <b>00</b> | <b>Bidding Requirements</b>              | <b>2.33</b>  | <b>4.45</b>  | <b>2,223,882</b>  |
|           | Bidding Requirements                     | 2.33         | 4.45         | 2,223,882         |
| <b>01</b> | <b>General Requirements</b>              | <b>7.50</b>  | <b>14.31</b> | <b>7,155,875</b>  |
|           | General Requirements                     | 7.50         | 14.31        | 7,155,875         |
| <b>02</b> | <b>Site Work</b>                         | <b>4.36</b>  | <b>8.32</b>  | <b>4,162,246</b>  |
|           | Site Work                                | 4.36         | 8.32         | 4,162,246         |
| <b>03</b> | <b>Concrete</b>                          | <b>6.67</b>  | <b>12.73</b> | <b>6,365,136</b>  |
|           | Concrete                                 | 6.67         | 12.73        | 6,365,136         |
| <b>04</b> | <b>Masonry</b>                           | <b>4.09</b>  | <b>7.81</b>  | <b>3,904,365</b>  |
|           | Masonry                                  | 4.09         | 7.81         | 3,904,365         |
| <b>05</b> | <b>Metals</b>                            | <b>0.93</b>  | <b>1.77</b>  | <b>882,877</b>    |
|           | Metals                                   | 0.93         | 1.77         | 882,877           |
| <b>06</b> | <b>Wood &amp; Plastics</b>               | <b>6.34</b>  | <b>12.10</b> | <b>6,049,079</b>  |
|           | Wood & Plastics                          | 6.34         | 12.10        | 6,049,079         |
| <b>07</b> | <b>Thermal &amp; Moisture Protection</b> | <b>4.19</b>  | <b>8.00</b>  | <b>3,999,200</b>  |
|           | Thermal & Moisture Protection            | 4.19         | 8.00         | 3,999,200         |
| <b>08</b> | <b>Doors &amp; Windows</b>               | <b>3.34</b>  | <b>6.37</b>  | <b>3,183,470</b>  |
|           | Doors & Windows                          | 3.34         | 6.37         | 3,183,470         |
| <b>09</b> | <b>Finishes</b>                          | <b>9.77</b>  | <b>18.65</b> | <b>9,324,642</b>  |
|           | Finishes                                 | 9.77         | 18.65        | 9,324,642         |
| <b>10</b> | <b>Specialties</b>                       | <b>0.61</b>  | <b>1.17</b>  | <b>585,671</b>    |
|           | Specialties                              | 0.61         | 1.17         | 585,671           |
| <b>11</b> | <b>Equipment</b>                         | <b>1.30</b>  | <b>2.48</b>  | <b>1,240,021</b>  |
|           | Equipment                                | 1.30         | 2.48         | 1,240,021         |
| <b>12</b> | <b>Furnishings</b>                       | <b>0.77</b>  | <b>1.46</b>  | <b>731,467</b>    |
|           | Furnishings                              | 0.77         | 1.46         | 731,467           |
| <b>13</b> | <b>Special Construction</b>              | <b>0.29</b>  | <b>0.55</b>  | <b>273,867</b>    |
|           | Special Construction                     | 0.29         | 0.55         | 273,867           |
| <b>14</b> | <b>Conveying Systems</b>                 | <b>1.47</b>  | <b>2.81</b>  | <b>1,403,343</b>  |
|           | Conveying Systems                        | 1.47         | 2.81         | 1,403,343         |
| <b>15</b> | <b>Mechanical</b>                        | <b>13.26</b> | <b>25.31</b> | <b>12,654,937</b> |
|           | Mechanical                               | 13.26        | 25.31        | 12,654,937        |
| <b>16</b> | <b>Electrical</b>                        | <b>8.39</b>  | <b>16.01</b> | <b>8,002,735</b>  |
|           | Electrical                               | 8.39         | 16.01        | 8,002,735         |
| <b>21</b> | <b>Fire Suppression</b>                  | <b>1.25</b>  | <b>2.38</b>  | <b>1,191,954</b>  |
|           | Fire Suppression                         | 1.25         | 2.38         | 1,191,954         |

Sunday, September 21, 2008

Page 2

|                                 |                                       |               |               |                   |
|---------------------------------|---------------------------------------|---------------|---------------|-------------------|
| 22                              | <b>Plumbing</b>                       | 4.42          | 8.44          | 4,218,617         |
|                                 | Plumbing                              | 4.42          | 8.44          | 4,218,617         |
| 23                              | <b>HVAC</b>                           | 7.64          | 14.57         | 7,287,076         |
|                                 | HVAC                                  | 7.64          | 14.57         | 7,287,076         |
| 26                              | <b>Electrical</b>                     | 6.58          | 12.56         | 6,281,739         |
|                                 | Electrical                            | 6.58          | 12.56         | 6,281,739         |
| 27                              | <b>Communications</b>                 | 0.48          | 0.92          | 457,780           |
|                                 | Communications                        | 0.48          | 0.92          | 457,780           |
| 28                              | <b>Electronic Safety and Security</b> | 0.12          | 0.24          | 118,191           |
|                                 | Electronic Safety and Security        | 0.12          | 0.24          | 118,191           |
| 31                              | <b>Earthwork</b>                      | 1.87          | 3.57          | 1,787,112         |
|                                 | Earthwork                             | 1.87          | 3.57          | 1,787,112         |
| 32                              | <b>Exterior Improvements</b>          | 1.40          | 2.68          | 1,337,766         |
|                                 | Exterior Improvements                 | 1.40          | 2.68          | 1,337,766         |
| 33                              | <b>Utilities</b>                      | 0.62          | 1.19          | 593,894           |
|                                 | Utilities                             | 0.62          | 1.19          | 593,894           |
| <b>Total Building Costs</b>     |                                       | <b>100.00</b> | <b>190.83</b> | <b>95,416,943</b> |
| <b>Total Non-Building Costs</b> |                                       | <b>100.00</b> | <b>0.00</b>   | <b>0</b>          |
| <b>Total Project Costs</b>      |                                       | <b>--</b>     | <b>--</b>     | <b>95,416,943</b> |

| General Conditions Estimate |                    |               |       |               |                  |
|-----------------------------|--------------------|---------------|-------|---------------|------------------|
| Item                        | Price              | % of GC       | Units | Cost Per Unit | Cost Per Month   |
| <b>Staff</b>                |                    |               |       |               |                  |
| Project Managers            | \$2,500,000        | 18.54%        | 3     | \$833,333     | \$65,789         |
| Superintendents             | \$1,300,000        | 9.64%         | 3     | \$433,333     | \$34,211         |
| Safety Man                  | \$379,000          | 2.81%         | 1     | \$379,000     | \$9,974          |
| Accountant                  | \$250,000          | 1.85%         | 1     | \$250,000     | \$6,579          |
| Secretary                   | \$455,000          | 3.37%         | 1     | \$455,000     | \$11,974         |
| Purchase Agent              | \$225,000          | 1.67%         |       |               | \$5,921          |
| Scheduler                   | \$113,000          | 0.84%         | 1     | \$113,000     | \$2,974          |
| Laborers                    | \$350,000          | 2.60%         |       |               | \$9,211          |
| Carpenters                  | \$95,000           | 0.70%         |       |               | \$2,500          |
| Safety Labor                | \$31,000           | 0.23%         |       |               | \$816            |
| Elevator / Hoist Operations | \$183,000          | 1.36%         | 2     | \$91,500      | \$4,816          |
| <b>Total</b>                | <b>\$5,881,000</b> | <b>43.62%</b> |       |               | <b>\$154,763</b> |
| <b>Site Work</b>            |                    |               |       |               |                  |
| Pre-Survey                  | \$22,000           | 0.16%         | 1     | \$22,000      | \$579            |
| Surveys                     | \$175,000          | 1.30%         | 1     | \$175,000     | \$4,605          |
| Permits                     | \$379,000          | 2.81%         | 13    | \$29,154      | \$9,974          |
| Progress Photos / Webcam    | \$17,000           | 0.13%         | 1     | \$17,000      | \$447            |
| Dewatering                  | \$17,000           | 0.13%         |       |               | \$447            |
| Exterior Cleaning           | \$94,000           | 0.70%         | 1     | \$94,000      | \$2,474          |
| Final Clean                 | \$120,000          | 0.89%         | 1     | \$120,000     | \$3,158          |
| Cleanup                     | \$72,000           | 0.53%         |       |               | \$1,895          |
| Access Roads / Parking      | \$50,000           | 0.37%         |       |               | \$1,316          |
| Miscellaneous Tools         | \$10,000           | 0.07%         |       |               | \$263            |
| Facility Operation          | \$118,000          | 0.88%         |       |               | \$3,105          |
| Temporary Toilets           | \$119,000          | 0.88%         | 20    | \$5,950       | \$3,132          |
| <b>Total</b>                | <b>\$1,193,000</b> | <b>8.85%</b>  |       |               | <b>\$31,395</b>  |

| Temporary Utilities             |                    |              |    |           |                 |
|---------------------------------|--------------------|--------------|----|-----------|-----------------|
| Temporary Power                 | \$300,000          | 2.23%        | 1  | \$300,000 | \$7,895         |
| Temporary Heat                  | \$220,000          | 1.63%        | 1  | \$220,000 | \$5,789         |
| Telephone / Data / Nextel       | \$112,000          | 0.83%        | 14 | \$8,000   | \$2,947         |
| Temporary Water                 | \$13,000           | 0.10%        | 1  | \$13,000  | \$342           |
| Temporary Utilities             | \$10,000           | 0.07%        | 1  | \$10,000  | \$263           |
| Temporary Hoist                 | \$245,000          | 1.82%        | 2  | \$122,500 | \$6,447         |
| Rubbish Chute                   | \$78,000           | 0.58%        | 1  | \$78,000  | \$2,053         |
| Temporary Elevators             | \$22,000           | 0.16%        | 1  | \$22,000  | \$579           |
| Rubbish Removal                 | \$300,000          | 2.23%        |    |           | \$7,895         |
| <b>Total</b>                    | <b>\$1,300,000</b> | <b>9.64%</b> |    |           | <b>\$34,211</b> |
| Site Office & Job Needs         |                    |              |    |           |                 |
| Temporary Office                | \$200,000          | 1.48%        | 2  | \$100,000 | \$5,263         |
| Office Set Up                   | \$55,000           | 0.41%        | 2  | \$27,500  | \$1,447         |
| Field Office Furniture          | \$40,000           | 0.30%        | 1  | \$40,000  | \$1,053         |
| Project Signs                   | \$5,000            | 0.04%        |    |           | \$132           |
| Postage                         | \$35,000           | 0.26%        |    |           | \$921           |
| Copier                          | \$35,000           | 0.26%        | 1  | \$35,000  | \$921           |
| Job Office Supplies             | \$53,000           | 0.39%        |    |           | \$1,395         |
| Travel                          | \$20,000           | 0.15%        |    |           | \$526           |
| Vehicles                        | \$161,000          | 1.19%        | 5  | \$32,200  | \$4,237         |
| Telephone                       | \$13,500           | 0.10%        | 14 | \$964     | \$355           |
| Computer                        | \$23,000           | 0.17%        | 14 | \$1,643   | \$605           |
| Blueprints                      | \$55,000           | 0.41%        |    |           | \$1,447         |
| Job Signs                       | \$5,000            | 0.04%        |    |           | \$132           |
| Gross Receipts Tax              | \$240,000          | 1.78%        |    |           | \$6,316         |
| Closeout Submittals             | \$35,000           | 0.26%        |    |           | \$921           |
| Fill Pool                       | \$10,000           | 0.07%        | 1  | \$10,000  | \$263           |
| <b>Total</b>                    | <b>\$985,500</b>   | <b>7.31%</b> |    |           | <b>\$25,934</b> |
| Site Security                   |                    |              |    |           |                 |
| Pest Control                    | \$2,500            | 0.02%        |    |           | \$66            |
| Site Fence                      | \$11,500           | 0.09%        |    |           | \$303           |
| Security                        | \$10,500           | 0.08%        |    |           | \$276           |
| Watchman Services               | \$280,000          | 2.08%        |    |           | \$7,368         |
| Temporary Barriers & Enclosures | \$75,000           | 0.56%        |    |           | \$1,974         |
| Safety Material                 | \$16,500           | 0.12%        |    |           | \$434           |
| Temporary Protection            | \$95,000           | 0.70%        |    |           | \$2,500         |
| <b>Total</b>                    | <b>\$491,000</b>   | <b>3.64%</b> |    |           | <b>\$12,921</b> |

| Contracts                       |                     |               |   |             |                  |
|---------------------------------|---------------------|---------------|---|-------------|------------------|
| Legal Services                  | \$10,000            | 0.07%         |   |             | \$263            |
| Miscellaneous Contracts         | \$10,000            | 0.07%         |   |             | \$263            |
| Constructware                   | \$57,000            | 0.42%         | 1 | \$57,000    | \$1,500          |
| <b>Total</b>                    | <b>\$77,000</b>     | <b>0.57%</b>  |   |             | <b>\$2,026</b>   |
| Insurance                       |                     |               |   |             |                  |
| Umbrella Liability Insurance    | \$1,110,000         | 8.23%         | 1 | \$1,110,000 | \$29,211         |
| General Liability Insurance     | \$1,095,000         | 8.12%         | 1 | \$1,095,000 | \$28,816         |
| Workers Compensation Insurance  | \$1,350,000         | 10.01%        | 1 | \$1,350,000 | \$35,526         |
| <b>Total</b>                    | <b>\$3,555,000</b>  | <b>26.37%</b> |   |             | <b>\$93,553</b>  |
| <b>General Conditions Total</b> | <b>\$13,482,500</b> |               |   |             | <b>\$354,803</b> |



**Structural System Takeoff Notes and Estimates**

| <b>COLUMN REBAR</b> |           |            |          |                   |           |  |
|---------------------|-----------|------------|----------|-------------------|-----------|--|
| Column Number       | # of Bars | Bar Number | LBS / FT | Total Height (ft) | Total LBS |  |
| 101                 | 10        | 9          | 3.4      | 330.83            | 11248     |  |
| 102                 | 10        | 9          | 3.4      | 330.83            | 11248     |  |
| 103                 | 10        | 9          | 3.4      | 124.75            | 4242      |  |
|                     | 10        | 11         | 5.313    | 60.5              | 3214      |  |
|                     | 14        | 11         | 5.313    | 50.41             | 3750      |  |
|                     | 22        | 11         | 5.313    | 20.17             | 2358      |  |
|                     | 26        | 11         | 5.313    | 75                | 10360     |  |
| 104                 | 16        | 9          | 3.4      | 312.83            | 17018     |  |
|                     | 16        | 11         | 5.313    | 9                 | 765       |  |
|                     | 20        | 11         | 5.313    | 9                 | 956       |  |
| 105                 | 8         | 10         | 4.303    | 330.83            | 11388     |  |
| 106                 | 8         | 10         | 4.303    | 124.75            | 4294      |  |
|                     | 12        | 11         | 5.313    | 50.42             | 3215      |  |
|                     | 20        | 11         | 5.313    | 60.49             | 6428      |  |
|                     | 24        | 11         | 5.313    | 20.17             | 2572      |  |
|                     | 22        | 11         | 5.313    | 57                | 6663      |  |
|                     | 30        | 11         | 5.313    | 18                | 2869      |  |
| 107                 | 12        | 9          | 3.4      | 255.83            | 10438     |  |
|                     | 12        | 11         | 5.313    | 57                | 3634      |  |
|                     | 20        | 11         | 5.313    | 18                | 1913      |  |
| 108                 | 10        | 9          | 3.4      | 255.83            | 8698      |  |
|                     | 10        | 10         | 4.303    | 75                | 3227      |  |
| 109                 | 8         | 9          | 3.4      | 260.37            | 7082      |  |
|                     | 8         | 10         | 4.303    | 75                | 2582      |  |
| 110                 | 8         | 9          | 3.4      | 260.37            | 7082      |  |
|                     | 8         | 10         | 4.303    | 75                | 2582      |  |
| 111                 | 12        | 9          | 3.4      | 134.83            | 5501      |  |
|                     | 12        | 11         | 5.313    | 50.42             | 3215      |  |
|                     | 16        | 11         | 5.313    | 40.33             | 3428      |  |
|                     | 26        | 11         | 5.313    | 87.25             | 12053     |  |
|                     | 36        | 11         | 5.313    | 18                | 3443      |  |
| 112                 | 12        | 9          | 3.4      | 134.83            | 5501      |  |
|                     | 12        | 11         | 5.313    | 50.42             | 3215      |  |
|                     | 16        | 11         | 5.313    | 40.33             | 3428      |  |
|                     | 26        | 11         | 5.313    | 87.25             | 12053     |  |
|                     | 36        | 11         | 5.313    | 18                | 3443      |  |
| 113                 | 8         | 9          | 3.4      | 260.37            | 7082      |  |
|                     | 8         | 10         | 4.303    | 75                | 2582      |  |

|     |    |    |       |                 |               |
|-----|----|----|-------|-----------------|---------------|
| 114 | 8  | 9  | 3.4   | 260.37          | 7082          |
|     | 8  | 10 | 4.303 | 75              | 2582          |
| 115 | 12 | 9  | 3.4   | 255.83          | 10438         |
|     | 12 | 11 | 5.313 | 57              | 3634          |
|     | 20 | 11 | 5.313 | 18              | 1913          |
| 116 | 8  | 10 | 4.303 | 124.75          | 4294          |
|     | 12 | 11 | 5.313 | 50.42           | 3215          |
|     | 20 | 11 | 5.313 | 60.49           | 6428          |
|     | 24 | 11 | 5.313 | 20.17           | 2572          |
|     | 22 | 11 | 5.313 | 57              | 6663          |
|     | 30 | 11 | 5.313 | 18              | 2869          |
| 117 | 8  | 10 | 4.303 | 330.83          | 11388         |
| 118 | 10 | 9  | 3.4   | 124.75          | 4242          |
|     | 10 | 11 | 5.313 | 60.5            | 3214          |
|     | 14 | 11 | 5.313 | 50.41           | 3750          |
|     | 22 | 11 | 5.313 | 20.17           | 2358          |
|     | 26 | 11 | 5.313 | 75              | 10360         |
| 119 | 10 | 9  | 3.4   | 285.83          | 9718          |
|     | 10 | 11 | 5.313 | 45              | 2391          |
| 120 | 10 | 9  | 3.4   | 285.83          | 9718          |
|     | 10 | 11 | 5.313 | 45              | 2391          |
|     |    |    |       | <b>Subtotal</b> | <b>325987</b> |
| 201 | 12 | 11 | 5.313 | 75              | 4782          |
| 202 | 12 | 11 | 5.313 | 75              | 4782          |
| 203 | 12 | 11 | 5.313 | 75              | 4782          |
| 204 | 20 | 11 | 5.313 | 18.5            | 1966          |
|     | 22 | 11 | 5.313 | 56.5            | 6604          |
| 205 | 20 | 11 | 5.313 | 18.5            | 1966          |
|     | 22 | 11 | 5.313 | 56.5            | 6604          |
| 206 | 20 | 11 | 5.313 | 18.5            | 1966          |
|     | 22 | 11 | 5.313 | 56.5            | 6604          |
| 207 | 20 | 11 | 5.313 | 75              | 7970          |
| 208 | 8  | 8  | 2.67  | 75              | 1602          |
| 209 | 8  | 8  | 2.67  | 75              | 1602          |
| 210 | 8  | 8  | 2.67  | 75              | 1602          |
| 211 | 8  | 8  | 2.67  | 75              | 1602          |
| 212 | 8  | 8  | 2.67  | 75              | 1602          |
| 213 | 8  | 10 | 4.303 | 75              | 2582          |
| 214 | 8  | 8  | 2.67  | 18.5            | 395           |
| 215 | 8  | 8  | 2.67  | 18.5            | 395           |
|     |    |    |       | <b>Subtotal</b> | <b>59406</b>  |

|     |    |   |      |                                      |            |
|-----|----|---|------|--------------------------------------|------------|
| 301 | 10 | 9 | 3.4  | 56.54                                | 1922       |
| 302 | 10 | 9 | 3.4  | 56.54                                | 1922       |
| 303 | 10 | 9 | 3.4  | 56.54                                | 1922       |
| 304 | 6  | 8 | 2.67 | 56.54                                | 906        |
| 305 | 6  | 8 | 2.67 | 56.54                                | 906        |
| 306 | 6  | 8 | 2.67 | 56.54                                | 906        |
| 307 | 6  | 8 | 2.67 | 56.54                                | 906        |
| 308 | 10 | 9 | 3.4  | 56.54                                | 1922       |
| 309 | 10 | 9 | 3.4  | 56.54                                | 1922       |
| 310 | 10 | 9 | 3.4  | 56.54                                | 1922       |
| 311 | 10 | 9 | 3.4  | 56.54                                | 1922       |
| 312 | 6  | 8 | 2.67 | 56.54                                | 906        |
| 313 | 10 | 9 | 3.4  | 56.54                                | 1922       |
| 314 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 315 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 316 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 317 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 318 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 319 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 320 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 321 | 4  | 9 | 3.4  | 45                                   | 612        |
| 322 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 323 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 324 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 325 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 326 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 327 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 328 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 329 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 330 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 331 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 332 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 333 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 334 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 335 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 336 | 8  | 8 | 2.67 | 56.54                                | 1208       |
| 337 | 8  | 8 | 2.67 | 20.5                                 | 438        |
| 338 | 8  | 8 | 2.67 | 20.5                                 | 438        |
|     |    |   |      | Subtotal                             | 47965      |
|     |    |   |      | Rebar Columns (LBS)                  | 433358     |
|     |    |   |      | Waste Factor (5%)                    | 1.05       |
|     |    |   |      | TOTAL REBAR FOR COLUMNS (Lbs)        | 455026     |
|     |    |   |      | <b>TOTAL REBAR FOR COLUMNS (Ton)</b> | <b>228</b> |

| Concrete Slabs                       |             |                |             |              |
|--------------------------------------|-------------|----------------|-------------|--------------|
| Level                                | Area (Ft^2) | Thickness (Ft) | Volume (CF) | Volume (CY)  |
| P-6                                  | 40,000      | 0.67           | 26800       | 993          |
| P-5                                  | 40,000      | 0.67           | 26800       | 993          |
| P-4                                  | 40,000      | 0.67           | 26800       | 993          |
| P-3                                  | 40,000      | 0.67           | 26800       | 993          |
| P-2                                  | 40,000      | 0.67           | 26800       | 993          |
| P-1                                  | 40,000      | 0.67           | 26800       | 993          |
| L                                    | 25,000      | 1              | 25000       | 926          |
| 2                                    | 20,100      | 0.583          | 11718.3     | 434          |
| 3                                    | 20,100      | 0.583          | 11718.3     | 434          |
| 4                                    | 20,100      | 0.583          | 11718.3     | 434          |
| 5                                    | 20,100      | 0.583          | 11718.3     | 434          |
| 6                                    | 20,100      | 0.583          | 11718.3     | 434          |
| 7                                    | 20,100      | 0.583          | 11718.3     | 434          |
| 8                                    | 20,100      | 0.583          | 11718.3     | 434          |
| 9                                    | 20,100      | 0.583          | 11718.3     | 434          |
| 10                                   | 20,100      | 0.583          | 11718.3     | 434          |
| 11                                   | 20,100      | 0.583          | 11718.3     | 434          |
| 12                                   | 20,100      | 0.583          | 11718.3     | 434          |
| 14                                   | 20,100      | 0.583          | 11718.3     | 434          |
| 15                                   | 20,100      | 0.583          | 11718.3     | 434          |
| 16                                   | 20,100      | 0.583          | 11718.3     | 434          |
| 17                                   | 20,100      | 0.583          | 11718.3     | 434          |
| 18                                   | 20,100      | 0.583          | 11718.3     | 434          |
| 19                                   | 20,100      | 0.583          | 11718.3     | 434          |
| 20                                   | 20,100      | 0.583          | 11718.3     | 434          |
| 21                                   | 20,100      | 0.583          | 11718.3     | 434          |
| 22                                   | 20,100      | 0.583          | 11718.3     | 434          |
| 23                                   | 20,100      | 0.583          | 11718.3     | 434          |
| 24                                   | 20,100      | 0.583          | 11718.3     | 434          |
| 25                                   | 20,100      | 0.583          | 11718.3     | 434          |
| 26                                   | 20,100      | 0.583          | 11718.3     | 434          |
| MPH                                  | 20,100      | 0.583          | 11718.3     | 434          |
| Total (CY)                           |             |                |             | 17732        |
| Waste Factor (5%)                    |             |                |             | 1.05         |
| <b>TOTAL CONCRETE FOR SLABS (CY)</b> |             |                |             | <b>18618</b> |

| Concrete      |             |            |            |             |             |  |
|---------------|-------------|------------|------------|-------------|-------------|--|
| Column Number | Length (ft) | Width (ft) | Depth (ft) | Volume (CF) | Volume (CY) |  |
| 101           | 7           | 7          | 3.33       | 163.33      | 6           |  |
| 102           | 7           | 7          | 3.33       | 163.33      | 6           |  |
| 103           | 8           | 6          | 3.33       | 160         | 6           |  |
| 104           | 10.5        | 6          | 3.67       | 231         | 9           |  |
| 105           | 7           | 7          | 3.33       | 163.33      | 6           |  |
| 106           | 8           | 8          | 4.00       | 256         | 9           |  |
| 107           | 8.5         | 8.5        | 5.00       | 361.25      | 13          |  |
| 108           | 8           | 6          | 3.33       | 160         | 6           |  |
| 109           | 7           | 7          | 3.33       | 163.33      | 6           |  |
| 110           | 7           | 7          | 3.33       | 163.33      | 6           |  |
| 111           | 8           | 6          | 3.67       | 176         | 7           |  |
| 112           | 8.5         | 8.5        | 5.00       | 361.25      | 13          |  |
| 113           | 7           | 7          | 3.33       | 163.33      | 6           |  |
| 114           | 7           | 7          | 3.33       | 163.33      | 6           |  |
| 115           | 8.5         | 8.5        | 5.00       | 361.25      | 13          |  |
| 116           | 8           | 8          | 4.00       | 256         | 9           |  |
| 117           | 8           | 6          | 3.33       | 160         | 6           |  |
| 118           | 8           | 6          | 3.33       | 160         | 6           |  |
| 119           | 10.5        | 6          | 3.33       | 210         | 8           |  |
| 120           | 10.5        | 6          | 3.33       | 210         | 8           |  |
| 201           | 8           | 8          | 4.00       | 256         | 9           |  |
| 202           | 8           | 8          | 4.00       | 256         | 9           |  |
| 203           | 8           | 8          | 4.00       | 256         | 9           |  |
| 204           | 8           | 8          | 4.00       | 256         | 9           |  |
| 205           | 8           | 8          | 4.00       | 256         | 9           |  |
| 206           | 8           | 8          | 4.00       | 256         | 9           |  |
| 207           | 9           | 7          | 4.00       | 252         | 9           |  |
| 208           | 4           | 4          | 4.00       | 64          | 2           |  |
| 209           | 4           | 4          | 4.00       | 64          | 2           |  |
| 210           | 4           | 4          | 4.00       | 64          | 2           |  |
| 211           | 4           | 4          | 4.00       | 64          | 2           |  |
| 212           | 4           | 4          | 4.00       | 64          | 2           |  |
| 213           | 4           | 4          | 4.00       | 64          | 2           |  |
| 301           | 5           | 5          | 2.00       | 50          | 2           |  |
| 302           | 5           | 5          | 2.00       | 50          | 2           |  |
| 303           | 5           | 5          | 2.00       | 50          | 2           |  |

|  |   |   |      |     |            |
|--|---|---|------|-----|------------|
| 304                                    | 4 | 4 | 2.00 | 32  | 1          |
| 305                                    | 4 | 4 | 2.00 | 32  | 1          |
| 306                                    | 4 | 4 | 2.00 | 32  | 1          |
| 307                                    | 4 | 4 | 2.00 | 32  | 1          |
| 308                                    | 6 | 6 | 2.83 | 102 | 4          |
| 309                                    | 6 | 6 | 2.83 | 102 | 4          |
| 310                                    | 6 | 6 | 2.83 | 102 | 4          |
| 311                                    | 6 | 6 | 2.83 | 102 | 4          |
| 312                                    | 3 | 3 | 2.00 | 18  | 1          |
| 313                                    | 6 | 6 | 2.83 | 102 | 4          |
| 314                                    | 4 | 4 | 2.00 | 32  | 1          |
| 315                                    | 4 | 4 | 2.00 | 32  | 1          |
| 316                                    | 4 | 4 | 2.00 | 32  | 1          |
| 317                                    | 4 | 4 | 2.00 | 32  | 1          |
| 318                                    | 4 | 4 | 2.00 | 32  | 1          |
| 319                                    | 4 | 4 | 2.00 | 32  | 1          |
| 320                                    | 4 | 4 | 2.00 | 32  | 1          |
| 321                                    | 4 | 4 | 2.00 | 32  | 1          |
| 322                                    | 4 | 4 | 2.00 | 32  | 1          |
| 323                                    | 4 | 4 | 2.00 | 32  | 1          |
| 324                                    | 4 | 4 | 2.00 | 32  | 1          |
| 325                                    | 4 | 4 | 2.00 | 32  | 1          |
| 326                                    | 4 | 4 | 2.00 | 32  | 1          |
| Concrete for Columns (CY)              |   |   |      |     | 281        |
| Waste Factor (5%)                      |   |   |      |     | 1.05       |
| <b>TOTAL CONCRETE FOR COLUMNS (CY)</b> |   |   |      |     | <b>296</b> |

| <b>Post Tension Tendons</b> |                    |             |                  |  |
|-----------------------------|--------------------|-------------|------------------|--|
| Floor                       | Amount of PT (Lbs) | Cost Per Lb | Total Cost       |  |
| 2                           | 25835              | \$1.15      | \$29,710         |  |
| 3                           | 25835              | \$1.15      | \$29,710         |  |
| 4                           | 25835              | \$1.15      | \$29,710         |  |
| 5                           | 25835              | \$1.15      | \$29,710         |  |
| 6                           | 25835              | \$1.15      | \$29,710         |  |
| 7                           | 25835              | \$1.15      | \$29,710         |  |
| 8                           | 25835              | \$1.15      | \$29,710         |  |
| 9                           | 25835              | \$1.15      | \$29,710         |  |
| 10                          | 25835              | \$1.15      | \$29,710         |  |
| 11                          | 25835              | \$1.15      | \$29,710         |  |
| 12                          | 25835              | \$1.15      | \$29,710         |  |
| 14                          | 25835              | \$1.15      | \$29,710         |  |
| 15                          | 25835              | \$1.15      | \$29,710         |  |
| 16                          | 25835              | \$1.15      | \$29,710         |  |
| 17                          | 25835              | \$1.15      | \$29,710         |  |
| 18                          | 25835              | \$1.15      | \$29,710         |  |
| 19                          | 25835              | \$1.15      | \$29,710         |  |
| 20                          | 25835              | \$1.15      | \$29,710         |  |
| 21                          | 25835              | \$1.15      | \$29,710         |  |
| 22                          | 25835              | \$1.15      | \$29,710         |  |
| 23                          | 25835              | \$1.15      | \$29,710         |  |
| 24                          | 25835              | \$1.15      | \$29,710         |  |
| 25                          | 25835              | \$1.15      | \$29,710         |  |
| 26                          | 25835              | \$1.15      | \$29,710         |  |
| MPH                         | 6959               | \$1.15      | \$8,003          |  |
| <b>TOTAL</b>                | <b>626999</b>      |             | <b>\$721,049</b> |  |

| <b>Reinforcing Steel</b> |              |              |                    |  |
|--------------------------|--------------|--------------|--------------------|--|
| Area                     | Amount (Ton) | Cost per Ton | Total Cost         |  |
| Columns                  | 228          | \$1,000      | \$228,000          |  |
| Shear Walls              | 1944         | \$1,000      | \$1,944,000        |  |
| Slabs                    | 899          | \$1,000      | \$899,000          |  |
| <b>TOTAL</b>             | <b>3071</b>  |              | <b>\$3,071,000</b> |  |

| <b>Miscellaneous Items</b> |             |               |                    |
|----------------------------|-------------|---------------|--------------------|
| Item                       | Amount      | Cost per      | Total Cost         |
| Post Tension Cables        | 626,999 LBS | \$1.15 / lbs  | \$721,049          |
| Grout PT Ends              | 14,456 EA   | \$0.50 EA     | \$7,228            |
| WWF 6x6 W1.4/W1.4          | 19,312 SF   | \$18.05 / CSF | \$348,582          |
| WWF 6x6 W2.1/W2.1          | 53,001 SF   | \$26.50 / CSF | \$1,404,527        |
| <b>TOTAL</b>               |             |               | <b>\$2,481,385</b> |

| <b>Total Material Cost</b> |           |                     |
|----------------------------|-----------|---------------------|
| Item                       | Amount    | Total Cost          |
| Concrete                   | 37,351 CY | \$4,668,875         |
| Reinforcing Steel          | 3071 Tons | \$3,071,000         |
| Miscellaneous Items        |           | \$2,481,385         |
| <b>TOTAL</b>               |           | <b>\$10,221,260</b> |
| <b>TOTAL PER CY</b>        |           | <b>\$273.65</b>     |

| <b>Average Labor and Equipment</b> |                 |                |           |
|------------------------------------|-----------------|----------------|-----------|
| Description                        | Labor           | Equipment      | Unit      |
| Footings                           | \$54.50         | \$0.33         | CY        |
| Columns                            | \$435.00        | \$42.50        | CY        |
| Slab on Grade                      | \$55.00         | \$0.41         | CY        |
| Slabs                              | \$207.00        | \$19.60        | CY        |
| Beams                              | \$490.00        | \$48.50        | CY        |
| Shear Walls                        | \$430.00        | \$42.50        | CY        |
| Curbs, Pads, Toppings              | \$129.00        | \$1.78         | CY        |
| <b>Average per CY</b>              | <b>\$257.21</b> | <b>\$22.23</b> | <b>CY</b> |

| <b>Construction Cost of Concrete System for Turnberry Tower Arlington</b>  |       |      |              |                |               |              |
|--|-------|------|--------------|----------------|---------------|--------------|
| Description  | Qty   | Unit | Material     | Labor          | Equipment     | Total Cost   |
| Cast In Place Concrete including placing and stripping formwork, placing rebar, placing concrete, and finishing concrete | 37351 | CY   | \$273.65     | \$257.21       | \$22.23       | \$20,658,837 |
|  |       |      | <b>TOTAL</b> | <b>\$27.55</b> | <b>per SF</b> |              |



## **Appendix C**

### Structural Calculations

#### Contents:

- Charts from the ACI 318-08 Building Code Requirements for Structural Concrete
- Calculations to design reinforced concrete slabs

CODE

COMMENTARY

9.5.3.2 — For slabs without interior beams spanning between the supports and having a ratio of long to short span not greater than 2, the minimum thickness shall be in accordance with the provisions of Table 9.5(c) and shall not be less than the following values:

- (a) Slabs without drop panels as defined in 13.2.5..... 5 in.;
- (b) Slabs with drop panels as defined in 13.2.5 ..... 4 in.

9.5.3.3 — For slabs with beams spanning between the supports on all sides, the minimum thickness, *h*, shall be as follows:

(a) For  $\alpha_{fm}$  equal to or less than 0.2, the provisions of 9.5.3.2 shall apply;

(b) For  $\alpha_{fm}$  greater than 0.2 but not greater than 2.0, *h* shall not be less than

$$h = \frac{\ell_n \left( 0.8 + \frac{f_y}{200,000} \right)}{36 + 5\beta(\alpha_{fm} - 0.2)} \quad (9-12)$$

and not less than 5 in.;

(c) For  $\alpha_{fm}$  greater than 2.0, *h* shall not be less than

$$h = \frac{\ell_n \left( 0.8 + \frac{f_y}{200,000} \right)}{36 + 9\beta} \quad (9-13)$$

and not less than 3.5 in.;

(d) At discontinuous edges, an edge beam shall be provided with a stiffness ratio  $\alpha_f$  not less than 0.80 or the minimum thickness required by Eq. (9-12) or (9-13)

R9.5.3.2 — The minimum thicknesses in Table 9.5(c) are those that have been developed through the years. Slabs conforming to those limits have not resulted in systematic problems related to stiffness for short- and long-term loads. These limits apply to only the domain of previous experience in loads, environment, materials, boundary conditions, and spans.

R9.5.3.3 — For panels having a ratio of long to short span greater than 2, the use of Eq. (9-12) and (9-13), which express the minimum thickness as a fraction of the long span, may give unreasonable results. For such panels, the rules applying to one-way construction in 9.5.2 should be used.

The requirement in 9.5.3.3(a) for  $\alpha_{fm}$  equal to 0.2 made it possible to eliminate Eq. (9-13) of the 1989 Code. That equation gave values essentially the same as those in Table 9.5(c), as does Eq. (9-12) at a value of  $\alpha_{fm}$  equal to 0.2.

TABLE 9.5(c)—MINIMUM THICKNESS OF SLABS WITHOUT INTERIOR BEAMS\*

| <i>f<sub>y</sub></i> , psi† | Without drop panels‡ |                  | With drop panels‡  |                  |
|-----------------------------|----------------------|------------------|--------------------|------------------|
|                             | Exterior panels      | Interior panels  | Exterior panels    | Interior panels  |
|                             | Without edge beams   | With edge beams§ | Without edge beams | With edge beams§ |
| 40,000                      | $\ell_n/33$          | $\ell_n/36$      | $\ell_n/36$        | $\ell_n/40$      |
| 60,000                      | $\ell_n/33$          | $\ell_n/33$      | $\ell_n/33$        | $\ell_n/36$      |
| 75,000                      | $\ell_n/28$          | $\ell_n/31$      | $\ell_n/31$        | $\ell_n/34$      |

\*For two-way construction,  $\ell_n$  is the length of clear span in the long direction measured face-to-face of supports in slabs without beams and face-to-face center-to-center of supports in other cases.  
 †For *f<sub>y</sub>* between the values given in the table, minimum thickness shall be determined by linear interpolation.  
 ‡Drop panels as defined in 13.2.5.  
 §Slabs with beams between columns along exterior edges. The value of  $\alpha_{fm}$  at the edge beam shall not be less than 0.2.

CODE

COMMENTARY




Fig. R13.6.2.5—Examples of equivalent square section for supporting members.

**13.6.3.2** — In an interior span, total static moment,  $M_o$ , shall be distributed as follows:

|                               |      |
|-------------------------------|------|
| Negative factored moment..... | 0.65 |
| Positive factored moment..... | 0.35 |

**13.6.3.3** — In an end span, total factored static moment,  $M_o$ , shall be distributed as follows:

|                                   | (1)                        | (2)                                  | (3)  | (4)               | (5)            |
|-----------------------------------|----------------------------|--------------------------------------|--|-------------------|----------------|
|                                   | Exterior edge unrestrained | Slab with beams between all supports | Slab without beams between interior supports | Without edge beam | With edge beam |
| Interior negative factored moment | 0.75                       | 0.70                                 | 0.70   | 0.70              | 0.65           |
| Positive factored moment          | 0.63                       | 0.57                                 | 0.52   | 0.50              | 0.35           |
| Exterior negative factored moment | 0                          | 0.16                                 | 0.26   | 0.30              | 0.65           |

**R13.6.3.3** — The moment coefficients for an end span are based on the equivalent column stiffness expressions from References 13.18, 13.19, and 13.20. The coefficients for an unrestrained edge would be used, for example, if the slab were simply supported on a masonry or concrete wall. Those for a fully restrained edge would apply if the slab were constructed integrally with a concrete wall having a flexural stiffness so large compared to that of the slab that little rotation occurs at the slab-to-wall connection.

For other than unrestrained or fully restrained edges, coefficients in the table were selected to be near the upper bound of the range for positive moments and interior negative moments. As a result, exterior negative moments were usually closer to a lower bound. The exterior negative moment strength for most slab systems is governed by minimum reinforcement to control cracking. The final coefficients in the table have been adjusted so that the absolute sum of the positive and average moments equal  $M_o$ .

For two-way slab systems with beams between supports on all sides (two-way slabs), moment coefficients of Column (2) of the table apply. For slab systems without beams between interior supports (flat plates and flat slabs), the moment coefficients of Column (3) or (4) apply, without or with an edge (spandrel) beam, respectively.

In the 1977 Code, distribution factors defined as a function of the stiffness ratio of the equivalent exterior support were used for proportioning the total static moment  $M_o$  in an end span. The approach may be used in place of values in 13.6.3.3.

**CODE**

**13.6.3.4** — Negative moment sections shall be designed to resist the larger of the two interior negative factored moments determined for spans framing into a common support unless an analysis is made to distribute the unbalanced moment in accordance with stiffnesses of adjoining elements.

**13.6.3.5** — Edge beams or edges of slab shall be proportioned to resist in torsion their share of exterior negative factored moments.

**13.6.3.6** — The gravity load moment to be transferred between slab and edge column in accordance with 13.5.3.1 shall be  $0.3M_o$ .

**13.6.4 — Factored moments in column strips**

**13.6.4.1** — Column strips shall be proportioned to resist the following portions in percent of interior negative factored moments:

| $\ell_2/\ell_1$                    | 0.5 | 1.0 | 2.0 |
|------------------------------------|-----|-----|-----|
| $(\alpha_1\ell_2/\ell_1) = 0$      | 75  | 75  | 75  |
| $(\alpha_1\ell_2/\ell_1) \geq 1.0$ | 90  | 75  | 45  |

Linear interpolations shall be made between values shown.

**13.6.4.2** — Column strips shall be proportioned to resist the following portions in percent of exterior negative factored moments:

| $\ell_2/\ell_1$                    |                    | 0.5 | 1.0 | 2.0 |
|------------------------------------|--------------------|-----|-----|-----|
| $(\alpha_1\ell_2/\ell_1) = 0$      | $\beta_t = 0$      | 100 | 100 | 100 |
|                                    | $\beta_t \geq 2.5$ | 75  | 75  | 75  |
| $(\alpha_1\ell_2/\ell_1) \geq 1.0$ | $\beta_t = 0$      | 100 | 100 | 100 |
|                                    | $\beta_t \geq 2.5$ | 90  | 75  | 45  |

Linear interpolations shall be made between values shown, where  $\beta_t$  is calculated in Eq. (13-5) and  $C$  is calculated in Eq. (13-6).

$$\beta_t = \frac{E_{cb}C}{2E_{cs}I_s} \quad (13-5)$$

$$C = \sum \left( 1 - 0.63 \frac{x}{y} \right) \frac{x^3 y}{3} \quad (13-6)$$

The constant  $C$  for T- or L-sections shall be permitted to be evaluated by dividing the section into separate rectangular parts, as defined in 13.2.4, and summing the values of  $C$  for each part.

**COMMENTARY**

**R13.6.3.4** — The differences in slab moment on either side of a column or other type of support should be accounted for in the design of the support. If an analysis is made to distribute unbalanced moments, flexural stiffness may be obtained on the basis of the gross concrete section of the members involved.

**R13.6.3.5** — Moments perpendicular to, and at the edge of, the slab structure should be transmitted to the supporting columns or walls. Torsional stresses caused by the moment assigned to the slab should be investigated.

**R13.6.4, R13.6.5, and R13.6.6 — Factored moments in column strips, beams, and middle strips**

The rules given for assigning moments to the column strips, beams, and middle strips are based on studies<sup>13.21</sup> of moments in linearly elastic slabs with different beam stiffness tempered by the moment coefficients that have been used successfully.

For the purpose of establishing moments in the half column strip adjacent to an edge supported by a wall,  $\ell_n$  in Eq. (13-4) may be assumed equal to  $\ell_n$  of the parallel adjacent column to column span, and the wall may be considered as a beam having a moment of inertia  $I_b$  equal to infinity.

**R13.6.4.2** — The effect of the torsional stiffness parameter  $\beta_t$  is to assign all of the exterior negative factored moment to the column strip, and none to the middle strip, unless the beam torsional stiffness is high relative to the flexural stiffness of the supported slab. In the definition of  $\beta_t$ , the shear modulus has been taken as  $E_{cb}/2$ .

Where walls are used as supports along column lines, they can be regarded as very stiff beams with an  $\alpha_1\ell_2/\ell_1$  value greater than 1. Where the exterior support consists of a wall perpendicular to the direction in which moments are being determined,  $\beta_t$  may be taken as zero if the wall is of masonry without torsional resistance, and  $\beta_t$  may be taken as 2.5 for a concrete wall with great torsional resistance that is monolithic with the slab.

CODE

COMMENTARY

13.6.4.3 — Where supports consist of columns or walls extending for a distance equal to or greater than  $(3/4)l_2$  used to compute  $M_o$ , negative moments shall be considered to be uniformly distributed across  $l_2$ .

13.6.4.4 — Column strips shall be proportioned to resist the following portions in percent of positive factored moments:

| $l_2/l_1$                     | 0.5 | 1.0 | 2.0 |
|-------------------------------|-----|-----|-----|
| $(\alpha_1 l_2/l_1) = 0$      | 60  | 60  | 60  |
| $(\alpha_1 l_2/l_1) \geq 1.0$ | 90  | 75  | 45  |

Linear interpolations shall be made between values shown.

13.6.4.5 — For slabs with beams between supports, the slab portion of column strips shall be proportioned to resist that portion of column strip moments not resisted by beams.

13.6.5 — Factored moments in beams

13.6.5.1 — Beams between supports shall be proportioned to resist 85 percent of column strip moments if  $\alpha_1 l_2/l_1$  is equal to or greater than 1.0.

13.6.5.2 — For values of  $\alpha_1 l_2/l_1$  between 1.0 and zero, proportion of column strip moments resisted by beams shall be obtained by linear interpolation between 85 and zero percent.

13.6.5.3 — In addition to moments calculated for uniform loads according to 13.6.2.2, 13.6.5.1, and 13.6.5.2, beams shall be proportioned to resist all moments caused by concentrated or linear loads applied directly to beams, including weight of projecting beam stem above or below the slab.

13.6.6 — Factored moments in middle strips

13.6.6.1 — That portion of negative and positive factored moments not resisted by column strips shall be proportionately assigned to corresponding half middle strips.

13.6.6.2 — Each middle strip shall be proportioned to resist the sum of the moments assigned to its two half middle strips.

13.6.6.3 — A middle strip adjacent to and parallel with a wall-supported edge shall be proportioned to resist twice the moment assigned to the half middle strip corresponding to the first row of interior supports.

R13.6.5 — Factored moments in beams

Loads assigned directly to beams are in addition to the uniform dead load of the slab; uniform superimposed dead loads, such as the ceiling, floor finish, or assumed equivalent partition loads; and uniform live loads. All of these loads are normally included with  $q_u$  in Eq. (13-4). Linear loads applied directly to beams include partition walls over or along beam centerlines and additional dead load of the projecting beam stem. Concentrated loads include posts above or hangers below the beams. For the purpose of assigning directly applied loads, only loads located within the width of the beam stem should be considered as directly applied to the beams. (The effective width of a beam as defined in 13.2.4 is solely for strength and relative stiffness calculations.) Line loads and concentrated loads located on the slab away from the beam stem require consideration to determine their apportionment to slab and beams.


13

738 DESIGN OF CONCRETE STRUCTURES Appendix A

**TABLE A.5a**  
Flexural resistance factor:  $R = \rho f_y \left( 1 - 0.588 \frac{\rho f_y}{f'_c} \right)$  psi

| $\rho$ | $f_y = 40,000$ psi |      |      |      | $f_y = 60,000$ psi |      |      |      |
|--------|--------------------|------|------|------|--------------------|------|------|------|
|        | $f'_c$ , psi       |      |      |      | $f'_c$ , psi       |      |      |      |
|        | 3000               | 4000 | 5000 | 6000 | 3000               | 4000 | 5000 | 6000 |
| 0.0005 | 20                 | 20   | 20   | 20   | 30                 | 30   | 30   | 30   |
| 0.0010 | 40                 | 40   | 40   | 40   | 59                 | 59   | 60   | 60   |
| 0.0015 | 59                 | 59   | 60   | 60   | 88                 | 89   | 89   | 89   |
| 0.0020 | 79                 | 79   | 79   | 79   | 117                | 118  | 118  | 119  |
| 0.0025 | 98                 | 99   | 99   | 99   | 146                | 147  | 147  | 148  |
| 0.0030 | 117                | 118  | 118  | 119  | 174                | 175  | 176  | 177  |
| 0.0035 | 136                | 137  | 138  | 138  | 201                | 204  | 205  | 206  |
| 0.0040 | 155                | 156  | 157  | 157  | 229                | 232  | 233  | 234  |
| 0.0045 | 174                | 175  | 176  | 177  | 256                | 259  | 261  | 263  |
| 0.0050 | 192                | 194  | 195  | 196  | 282                | 287  | 288  | 291  |
| 0.0055 | 211                | 213  | 214  | 215  | 309                | 314  | 317  | 319  |
| 0.0060 | 229                | 232  | 233  | 234  | 335                | 341  | 345  | 347  |
| 0.0065 | 247                | 250  | 252  | 253  | 360                | 368  | 372  | 375  |
| 0.0070 | 265                | 268  | 271  | 272  | 385                | 394  | 399  | 403  |
| 0.0075 | 282                | 287  | 289  | 291  | 410                | 420  | 426  | 430  |
| 0.0080 | 300                | 305  | 308  | 310  | 435                | 446  | 453  | 457  |
| 0.0085 | 317                | 323  | 326  | 329  | 459                | 472  | 479  | 485  |
| 0.0090 | 335                | 341  | 345  | 347  | 483                | 497  | 506  | 511  |
| 0.0095 | 352                | 359  | 363  | 366  | 506                | 522  | 532  | 538  |
| 0.0100 | 369                | 376  | 381  | 384  | 529                | 547  | 558  | 565  |
| 0.0105 | 385                | 394  | 399  | 403  | 552                | 572  | 583  | 591  |
| 0.0110 | 402                | 412  | 417  | 421  | 575                | 596  | 609  | 617  |
| 0.0115 | 419                | 429  | 435  | 439  | 597                | 620  | 634  | 643  |
| 0.0120 | 435                | 446  | 453  | 457  | 618                | 644  | 659  | 669  |
| 0.0125 | 451                | 463  | 471  | 476  | 640                | 667  | 684  | 695  |
| 0.0130 | 467                | 480  | 488  | 494  | 661                | 691  | 708  | 720  |
| 0.0135 | 483                | 497  | 506  | 511  | 681                | 714  | 733  | 746  |
| 0.0140 | 499                | 514  | 523  | 529  | 702                | 736  | 757  | 771  |
| 0.0145 | 514                | 531  | 540  | 547  | 722                | 759  | 781  | 796  |
| 0.0150 | 529                | 547  | 558  | 565  | 741                | 781  | 805  | 821  |
| 0.0155 | 545                | 563  | 575  | 582  | 760                | 803  | 828  | 845  |
| 0.0160 | 560                | 580  | 592  | 600  |                    | 825  | 852  | 870  |
| 0.0165 | 575                | 596  | 609  | 617  |                    | 846  | 875  | 894  |
| 0.0170 | 589                | 612  | 626  | 635  |                    | 867  | 898  | 918  |
| 0.0175 | 604                | 628  | 642  | 652  |                    | 888  | 920  | 942  |
| 0.0180 | 618                | 644  | 659  | 669  |                    | 909  | 943  | 966  |
| 0.0185 | 633                | 660  | 676  | 686  |                    | 929  | 965  | 989  |
| 0.0190 | 647                | 675  | 692  | 703  |                    | 949  | 987  | 1013 |
| 0.0195 | 661                | 691  | 708  | 720  |                    | 969  | 1009 | 1036 |
| 0.0200 | 675                | 706  | 725  | 737  |                    | 988  | 1031 | 1059 |





ASSUMPTIONS

- 20" x 20" COLUMNS
- LIVE LOAD = 40 psf TABLE 4-1  
ASCE 7-05
- DEAD = 137.5
- # 6 BARS

THICKNESS OF SLAB - ACI 318 Building Code Chpt 9 9.5(c) 2008

W/O DROP PANEL  
W/O EDGE BEAMS  
60 KSI STEEL

$$= l_n/33$$

\* TO BE CONSERVATIVE, PICK LARGEST

$$BAY \therefore = 30'$$

$$= \frac{30 \times 12}{33} = 10.9'' = 11''$$

FIND MOMENT

FRAME A  $M_o = \frac{1}{8} W_u l_2 l_n^2$   $W_u = 1.2D + 1.6L$   $l_2 = 26'$   $l_n = 27.5 - 1.67 = 25.83'$

$$= \frac{1}{8} (0.202)(26)(25.83)^2 = 1.2 \left(\frac{11}{12} \times 150\right) + 1.6(40) = 137.5 + 64 = 202 \text{ psf} = 0.202 \text{ KSF}$$

FRAME B  $M_o = \frac{1}{8} (0.202)(27.5)(24.33)^2$   $W_u = 0.202 \text{ KSF}$   $l_2 = 27.5$   $l_n = 26 - 1.67 = 24.33'$

$$= 411 \text{ K-ft}$$

CHART 13.6.3.2

NEG FACTORED MOMENT = 0.65

$$\alpha = \frac{\text{Beam}}{\text{Column}} = \frac{0.12}{0.1} = 0$$

POS FACTORED MOMENT = 0.35

$$\beta = \frac{E_c}{2EI} = 0 \quad \text{TORSION CONSTANT OF TRANSVERSE BEAM}$$

FRAME A  $l_2/l_1 \Rightarrow 26/27.5 = 0.945$

13.6.4.1

$\therefore$  75% IN COLUMN STRIP  
25% IN MIDDLE STRIP

MOMENT

$\therefore$  60% IN COLUMN STRIP  
40% IN MIDDLE STRIP

MOMENT

13.6.4.4

FRAME B  $l_2/l_1 \Rightarrow 27.5/26 = 1.06$

13.6.4.1

$\therefore$  75% IN COLUMN STRIP  
25% IN MIDDLE STRIP

MOMENT

$\therefore$  60% IN COLUMN STRIP  
40% IN MIDDLE STRIP

MOMENT



- MOMENT = TOP BAR  
+ MOMENT = BOTTOM BAR

FRAME A - MOMENT :  $(M_o \times 0.65)$  + MOMENT :  $(M_o \times 0.35)$   
 $(438 \times 0.65) = 284.7$   $(438 \times 0.35) = 153.3$   
 $(284.7 \times 0.75) = M_n$   $(284.7 \times 0.75) = M_n$   $(153.3 \times 0.60) = M_n$   $(153.3 \times 0.40) = M_n$   
 $M_n = 214 \text{ ft-k (CS)}$   $M_n = 72 \text{ ft-k (MS)}$   $M_n = 92 \text{ ft-k (CS)}$   $M_n = 62 \text{ ft-k (MS)}$

FRAME B - MOMENT :  $(M_o \times 0.65)$  + MOMENT :  $(M_o \times 0.35)$   
 $(411 \times 0.65) = 268$   $(411 \times 0.35) = 144$   
 $(268 \times 0.75) = M_n$   $(268 \times 0.25) = M_n$   $(144 \times 0.60) = M_n$   $(144 \times 0.40) = M_n$   
 $M_n = 201 \text{ ft-k (CS)}$   $M_n = 67 \text{ ft-k (MS)}$   $M_n = 87 \text{ ft-k (CS)}$   $M_n = 58 \text{ ft-k (MS)}$

|              | + Moment | - Moment |
|--------------|----------|----------|
| COLUMN STRIP | 92 ft-k  | 214 ft-k |
| MIDDLE STRIP | 62 ft-k  | 72 ft-k  |

FRAME A

|              | + MOMENT | - MOMENT |
|--------------|----------|----------|
| COLUMN STRIP | 87 ft-k  | 201 ft-k |
| MIDDLE STRIP | 58 ft-k  | 67 ft-k  |

FRAME B

COLUMN STRIP - FRAME B

| ITEM | DESCRIPTION                          | -M     | +M     |                            |
|------|--------------------------------------|--------|--------|----------------------------|
| 1    | MOMENT ( $M_n$ )                     | 201    | 87     |                            |
| 2    | CS- SLAB WIDTH ( $b$ (in))           | 165    | 165    | $\frac{27.5 \times 12}{2}$ |
| 3    | EFFECTIVE DEPTH ( $d$ (in))          | 9      | 9      |                            |
| 4    | $M_u = M_n / 0.9$                    | 223    | 97     |                            |
| 5    | $M_n \times 12 / b$                  | 14.62  | 6.33   |                            |
| 6    | $R = \frac{M_n \times 12000}{b d^2}$ | 200    | 87     |                            |
| 7    | $\rho =$ FROM A.5a                   | 0.0034 | 0.0015 |                            |
| 8    | $\rho_s = \rho b d$                  | 5.05   | 2.23   |                            |
| 9    | $A_s = 0.0018 b t$                   | 3.27   | 3.27   |                            |
| 10   | LARGER 8 OR 9 / 0.44                 | 12     | 8      |                            |
| 11   | $N_{min} = \#2 / 2t$                 | 8      | 8      |                            |
| F    | LARGER 10 OR 11                      | 12     | 8      |                            |

MIDDLE STRIP - FRAME B

| ITEM | DESCRIPTION                          | -M     | +M    |
|------|--------------------------------------|--------|-------|
| 1    | MOMENT ( $M_n$ )                     | 67     | 58    |
| 2    | CS- SLAB WIDTH ( $b$ (in))           | 165    | 165   |
| 3    | EFFECTIVE DEPTH ( $d$ (in))          | 9      | 9     |
| 4    | $M_u = M_n / 0.9$                    | 74.44  | 64.44 |
| 5    | $M_n \times 12 / b$                  | 4.87   | 4.22  |
| 6    | $R = \frac{M_n \times 12000}{b d^2}$ | 67     | 58    |
| 7    | $\rho =$ FROM A.5a                   | 0.0011 | 0.001 |
| 8    | $\rho_s = \rho b d$                  | 1.634  | 1.485 |
| 9    | $A_s = 0.0018 b t$                   | 3.27   | 3.27  |
| 10   | LARGER 8 OR 9 / 0.44                 | 8      | 8     |
| 11   | $N_{min} = \#2 / 2t$                 | 8      | 8     |
| F    | LARGER 10 OR 11                      | 8      | 8     |

CHECK

ONE WAY SHEAR

FRAME A  $V_u = W_u (l_1) \left( l_2 - \frac{\text{column}/12}{} - \frac{d}{12} \right)$   
 $= 0.202 (1) \left( 27.5 - \frac{20/12}{} - \frac{9/12}{} \right)$   
 $= 5.24$

$\phi V_c = \frac{0.75 (2) \sqrt{5000} (12) d}{1000}$   
 $= 11.46$

$V_u < \phi V_c \therefore \text{OK} \checkmark$

FRAME B  $V_u = 0.202 (1) \left( 26 - \frac{20/12}{} - \frac{9/12}{} \right)$   
 $= 4.93$

$\phi V_c = 11.46$

$V_u < \phi V_c \therefore \text{OK} \checkmark$

PUNCHING SHEAR

$V_c = 4 \sqrt{f'_c} b_o d$

$\alpha_s = 40$

$f_c = 1$  b/c square column

$V_c = (2 + \frac{\alpha_s}{b_o/d}) \sqrt{f'_c} b_o d$

$b_o = \text{perimeter of column (in)}$

$V_c = (0.85/b_o/d + 2) \sqrt{f'_c} b_o d$

$d = \text{Eqn}$

$V_c = 4 (\sqrt{5000}) (26 \times 9) (9) = 295 \text{ K}$

$b_o = (20 + 4.5 + 4.5) = 29$

$V_c = 6 \sqrt{5000} (26 \times 9) (9) = 443 \text{ K}$

$V_c = 5.1 (\sqrt{5000}) (26 \times 9) (9) = 377 \text{ K}$

$295 \times 0.75$  (SAFETY FACTOR)  
 $= 221 \text{ K}$

$V_u = (\text{AREA OF SLAB} \times W_u) - \frac{\text{column}^2}{144}$   
 $= (26 \times 27.5 \times 0.202) - \frac{20^2}{144/2}$   
 $= 143 \text{ K}$


$V_c > V_u \therefore \text{OK} \checkmark$












## **Appendix D**

### **Structural System Schedule and Cost Estimates**

#### Contents:

- Post Tension Concrete Schedule vs. Reinforced Concrete System
- Reinforced Concrete Option 1 (Removing One Story) Takeoff Notes & Cost Analysis
- Reinforced Concrete Option 2 (Story Height Adjustment) Takeoff Notes & Cost Analysis
- Comparing Cost of 3 Concrete Systems



|  |  |   |   |  |   |  |
|--|--|---|---|--|---|--|
| Turnberry Tower Arlington<br>Post Tension vs. Reinforced | Task      | Milestone  | Rolled Up Task       | Rolled Up Progress  | External Tasks   | Group By Summary  |
|  | Progress  | Summary    | Rolled Up Milestone  | Split               | Project Summary  | Deadline          |

**Reinforced Concrete Option 1 (Removing One Story) Takeoff Notes & Cost Analysis**

| <b>Concrete Slabs (Reinforced Concrete)</b>     |                         |                |             |              |
|---|-------------------------|----------------|-------------|--------------|
| Level   | Area (Ft <sup>2</sup> ) | Thickness (Ft) | Volume (CF) | Volume (CY)  |
| P-6   | 40,000                  | 0.67           | 26800       | 993          |
| P-5   | 40,000                  | 0.67           | 26800       | 993          |
| P-4   | 40,000                  | 0.67           | 26800       | 993          |
| P-3   | 40,000                  | 0.67           | 26800       | 993          |
| P-2   | 40,000                  | 0.67           | 26800       | 993          |
| P-1   | 40,000                  | 0.67           | 26800       | 993          |
| L   | 25,000                  | 1              | 25000       | 926          |
| 2   | 20,100                  | 0.917          | 18425       | 682          |
| 3   | 20,100                  | 0.917          | 18425       | 682          |
| 4   | 20,100                  | 0.917          | 18425       | 682          |
| 5   | 20,100                  | 0.917          | 18425       | 682          |
| 6   | 20,100                  | 0.917          | 18425       | 682          |
| 7   | 20,100                  | 0.917          | 18425       | 682          |
| 8   | 20,100                  | 0.917          | 18425       | 682          |
| 9   | 20,100                  | 0.917          | 18425       | 682          |
| 10  | 20,100                  | 0.917          | 18425       | 682          |
| 11  | 20,100                  | 0.917          | 18425       | 682          |
| 12  | 20,100                  | 0.917          | 18425       | 682          |
| 14  | 20,100                  | 0.917          | 18425       | 682          |
| 15  | 20,100                  | 0.917          | 18425       | 682          |
| 16  | 20,100                  | 0.917          | 18425       | 682          |
| 17  | 20,100                  | 0.917          | 18425       | 682          |
| 19  | 20,100                  | 0.917          | 18425       | 682          |
| 20  | 20,100                  | 0.917          | 18425       | 682          |
| 21  | 20,100                  | 0.917          | 18425       | 682          |
| 22  | 20,100                  | 0.917          | 18425       | 682          |
| 23  | 20,100                  | 0.917          | 18425       | 682          |
| 24  | 20,100                  | 0.917          | 18425       | 682          |
| 25  | 20,100                  | 0.917          | 18425       | 682          |
| 26  | 20,100                  | 0.917          | 18425       | 682          |
| MPH   | 20,100                  | 0.917          | 18425       | 682          |
| Total (CY)                                      |                         |                |             | 23259        |
| Waste Factor (5%)                               |                         |                |             | 1.05         |
| <b>TOTAL CONCRETE FOR REINFORCED SLABS (CY)</b> |                         |                |             | <b>24422</b> |

| Concrete               |               |             |                    |
|------------------------|---------------|-------------|--------------------|
| Area                   | Amount (CY)   | Cost per CY | Total Cost         |
| Footings (Columns)     | 296           | \$125       | \$37,000           |
| Footings (Shear Walls) | 1,075         | \$125       | \$134,375          |
| Columns                | 2,192         | \$125       | \$274,038          |
| Slab On Grade          | 1,043         | \$125       | \$130,331          |
| Mud Slab               | 85            | \$125       | \$10,625           |
| Floor Slabs            | 23,380        | \$125       | \$2,922,500        |
| Beams                  | 5,878         | \$125       | \$734,750          |
| Shear Walls            | 8,491         | \$125       | \$1,061,375        |
| Curbs, Pads, Toppings  | 915           | \$125       | \$114,375          |
| <b>TOTAL</b>           | <b>43,355</b> |             | <b>\$5,419,369</b> |

| Reinforcing Steel |              |              |                    |
|-------------------|--------------|--------------|--------------------|
| Area              | Amount (Ton) | Cost per Ton | Total Cost         |
| Columns           | 354          | \$1,000      | \$354,200          |
| Shear Walls       | 1944         | \$1,000      | \$1,944,000        |
| Slabs             | 1065         | \$1,000      | \$1,065,000        |
| <b>TOTAL</b>      | <b>3363</b>  |              | <b>\$3,363,200</b> |

| Miscellaneous Items |           |               |                    |
|---------------------|-----------|---------------|--------------------|
| Item                | Amount    | Cost per      | Total Cost         |
| WWF 6x6 W1.4/W1.4   | 19,312 SF | \$18.05 / CSF | \$348,582          |
| WWF 6x6 W2.1/W2.1   | 53,001 SF | \$26.50 / CSF | \$1,404,527        |
| <b>TOTAL</b>        |           |               | <b>\$1,753,108</b> |

| Total Material Cost |           |                     |
|---------------------|-----------|---------------------|
| Item                | Amount    | Total Cost          |
| Concrete            | 43355 CY  | \$5,419,369         |
| Reinforcing Steel   | 3363 Tons | \$3,363,200         |
| Miscellaneous Items |           | \$1,753,108         |
| <b>TOTAL</b>        |           | <b>\$10,535,677</b> |
| <b>TOTAL PER CY</b> |           | <b>\$243.01</b>     |

| Concrete Total Cost           |                     |               |           |          |         |           |                    |
|-------------------------------|---------------------|---------------|-----------|----------|---------|-----------|--------------------|
| Description                   | Method of Placement | Qty           | Unit      | Material | Labor   | Equipment | Total Cost         |
| Spread Footings (Columns)     | Crane and Bucket    | 296           | CY        | \$125.00 | \$24.50 | \$11.95   | \$47,789           |
| Spread Footings (Shear Walls) | Crane and Bucket    | 1,075         | CY        | \$125.00 | \$24.50 | \$11.95   | \$173,559          |
| Columns                       | Pumped              | 2,192         | CY        | \$125.00 | \$24.00 | \$8.80    | \$345,898          |
| Slab on Grade                 | Crane and Bucket    | 1,043         | CY        | \$125.00 | \$17.00 | \$8.25    | \$156,711          |
| Mud Slab                      | Crane and Bucket    | 85            | CY        | \$125.00 | \$17.00 | \$8.25    | \$12,771           |
| Floor Slabs                   | Pumped              | 23,380        | CY        | \$125.00 | \$13.55 | \$4.94    | \$3,354,796        |
| Beams                         | Pumped              | 5,878         | CY        | \$125.00 | \$24.00 | \$8.80    | \$927,548          |
| Shear Walls                   | Pumped              | 8,491         | CY        | \$125.00 | \$19.75 | \$7.20    | \$1,290,207        |
| Curbs, Pads, Toppings         | Hauled              | 915           | CY        | \$125.00 | \$20.58 | \$9.33    | \$141,743          |
| <b>TOTAL</b>                  |                     | <b>43,355</b> | <b>CY</b> |          |         |           | <b>\$6,451,022</b> |

| Average Labor and Equipment |                 |                |           |
|-----------------------------|-----------------|----------------|-----------|
| Description                 | Labor           | Equipment      | Unit      |
| Footings                    | \$54.50         | \$0.33         | CY        |
| Columns                     | \$435.00        | \$42.50        | CY        |
| Slab on Grade               | \$55.00         | \$0.41         | CY        |
| Slabs                       | \$207.00        | \$19.60        | CY        |
| Beams                       | \$490.00        | \$48.50        | CY        |
| Shear Walls                 | \$430.00        | \$42.50        | CY        |
| Curbs, Pads, Toppings       | \$129.00        | \$1.78         | CY        |
| <b>Average per CY</b>       | <b>\$257.21</b> | <b>\$22.23</b> | <b>CY</b> |

| Construction Cost of Concrete System for Turnberry Tower Arlington   |       |      |          |              |                |               |
|--|-------|------|----------|--------------|----------------|---------------|
| Description  | Qty   | Unit | Material | Labor        | Equipment      | Total Cost    |
| Cast In Place Concrete including placing and stripping formwork, placing rebar, placing concrete, and finishing concrete | 43355 | CY   | \$243.01 | \$257.21     | \$22.23        | \$22,651,046  |
|  |       |      |          | <b>TOTAL</b> | <b>\$30.20</b> | <b>per SF</b> |



**Reinforced Concrete Option 2 (Story Height Adjustment) Takeoff Notes & Cost Analysis**

| <b>Concrete Slabs (Reinforced Concrete)</b>     |                         |                |             |              |
|---|-------------------------|----------------|-------------|--------------|
| Level   | Area (Ft <sup>2</sup> ) | Thickness (Ft) | Volume (CF) | Volume (CY)  |
| P-6   | 40,000                  | 0.67           | 26800       | 993          |
| P-5   | 40,000                  | 0.67           | 26800       | 993          |
| P-4   | 40,000                  | 0.67           | 26800       | 993          |
| P-3   | 40,000                  | 0.67           | 26800       | 993          |
| P-2   | 40,000                  | 0.67           | 26800       | 993          |
| P-1   | 40,000                  | 0.67           | 26800       | 993          |
| L   | 25,000                  | 1              | 25000       | 926          |
| 2   | 20,100                  | 0.917          | 18425       | 682          |
| 3   | 20,100                  | 0.917          | 18425       | 682          |
| 4   | 20,100                  | 0.917          | 18425       | 682          |
| 5   | 20,100                  | 0.917          | 18425       | 682          |
| 6   | 20,100                  | 0.917          | 18425       | 682          |
| 7   | 20,100                  | 0.917          | 18425       | 682          |
| 8   | 20,100                  | 0.917          | 18425       | 682          |
| 9   | 20,100                  | 0.917          | 18425       | 682          |
| 10  | 20,100                  | 0.917          | 18425       | 682          |
| 11  | 20,100                  | 0.917          | 18425       | 682          |
| 12  | 20,100                  | 0.917          | 18425       | 682          |
| 14  | 20,100                  | 0.917          | 18425       | 682          |
| 15  | 20,100                  | 0.917          | 18425       | 682          |
| 16  | 20,100                  | 0.917          | 18425       | 682          |
| 17  | 20,100                  | 0.917          | 18425       | 682          |
| 18  | 20,100                  | 0.917          | 18425       | 682          |
| 19  | 20,100                  | 0.917          | 18425       | 682          |
| 20  | 20,100                  | 0.917          | 18425       | 682          |
| 21  | 20,100                  | 0.917          | 18425       | 682          |
| 22  | 20,100                  | 0.917          | 18425       | 682          |
| 23  | 20,100                  | 0.917          | 18425       | 682          |
| 24  | 20,100                  | 0.917          | 18425       | 682          |
| 25  | 20,100                  | 0.917          | 18425       | 682          |
| 26  | 20,100                  | 0.917          | 18425       | 682          |
| MPH   | 20,100                  | 0.917          | 18425       | 682          |
| Total (CY)                                      |                         |                |             | 23942        |
| Waste Factor (5%)                               |                         |                |             | 1.05         |
| <b>TOTAL CONCRETE FOR REINFORCED SLABS (CY)</b> |                         |                |             | <b>25139</b> |

| Concrete               |               |             |                    |
|------------------------|---------------|-------------|--------------------|
| Area                   | Amount (CY)   | Cost per CY | Total Cost         |
| Footings (Columns)     | 296           | \$125       | \$37,000           |
| Footings (Shear Walls) | 1,075         | \$125       | \$134,375          |
| Columns                | 2,192         | \$125       | \$274,038          |
| Slab On Grade          | 1,043         | \$125       | \$130,331          |
| Mud Slab               | 85            | \$125       | \$10,625           |
| Floor Slabs            | 24,097        | \$125       | \$3,012,125        |
| Beams                  | 5,878         | \$125       | \$734,750          |
| Shear Walls            | 8,491         | \$125       | \$1,061,375        |
| Curbs, Pads, Toppings  | 915           | \$125       | \$114,375          |
| <b>TOTAL</b>           | <b>44,072</b> |             | <b>\$5,508,994</b> |

| Reinforcing Steel |              |              |                    |
|-------------------|--------------|--------------|--------------------|
| Area              | Amount (Ton) | Cost per Ton | Total Cost         |
| Columns           | 354          | \$1,000      | \$354,200          |
| Shear Walls       | 1944         | \$1,000      | \$1,944,000        |
| Slabs             | 1100         | \$1,000      | \$1,100,000        |
| <b>TOTAL</b>      | <b>3398</b>  |              | <b>\$3,398,200</b> |

| Miscellaneous Items |           |               |                    |
|---------------------|-----------|---------------|--------------------|
| Item                | Amount    | Cost per      | Total Cost         |
| WWF 6x6 W1.4/W1.4   | 19,312 SF | \$18.05 / CSF | \$348,582          |
| WWF 6x6 W2.1/W2.1   | 53,001 SF | \$26.50 / CSF | \$1,404,527        |
| <b>TOTAL</b>        |           |               | <b>\$1,753,108</b> |

| Total Material Cost |           |                     |
|---------------------|-----------|---------------------|
| Item                | Amount    | Total Cost          |
| Concrete            | 44072 CY  | \$5,508,994         |
| Reinforcing Steel   | 3983 Tons | \$3,398,200         |
| Miscellaneous Items |           | \$1,753,108         |
| <b>TOTAL</b>        |           | <b>\$10,660,302</b> |
| <b>TOTAL PER CY</b> |           | <b>\$241.88</b>     |

| Concrete Total Cost           |                     |               |           |          |         |           |                    |
|-------------------------------|---------------------|---------------|-----------|----------|---------|-----------|--------------------|
| Description                   | Method of Placement | Qty           | Unit      | Material | Labor   | Equipment | Total Cost         |
| Spread Footings (Columns)     | Crane and Bucket    | 296           | CY        | \$125.00 | \$24.50 | \$11.95   | \$47,789           |
| Spread Footings (Shear Walls) | Crane and Bucket    | 1,075         | CY        | \$125.00 | \$24.50 | \$11.95   | \$173,559          |
| Columns                       | Pumped              | 2,192         | CY        | \$125.00 | \$24.00 | \$8.80    | \$345,898          |
| Slab on Grade                 | Crane and Bucket    | 1,043         | CY        | \$125.00 | \$17.00 | \$8.25    | \$156,711          |
| Mud Slab                      | Crane and Bucket    | 85            | CY        | \$125.00 | \$17.00 | \$8.25    | \$12,771           |
| Floor Slabs                   | Pumped              | 24,097        | CY        | \$125.00 | \$13.55 | \$4.94    | \$3,457,679        |
| Beams                         | Pumped              | 5,878         | CY        | \$125.00 | \$24.00 | \$8.80    | \$927,548          |
| Shear Walls                   | Pumped              | 8,491         | CY        | \$125.00 | \$19.75 | \$7.20    | \$1,290,207        |
| Curbs, Pads, Toppings         | Hauled              | 915           | CY        | \$125.00 | \$20.58 | \$9.33    | \$141,743          |
| <b>TOTAL</b>                  |                     | <b>44,072</b> | <b>CY</b> |          |         |           | <b>\$6,553,905</b> |

| Average Labor and Equipment |                 |                |           |
|-----------------------------|-----------------|----------------|-----------|
| Description                 | Labor           | Equipment      | Unit      |
| Footings                    | \$54.50         | \$0.33         | CY        |
| Columns                     | \$435.00        | \$42.50        | CY        |
| Slab on Grade               | \$55.00         | \$0.41         | CY        |
| Slabs                       | \$207.00        | \$19.60        | CY        |
| Beams                       | \$490.00        | \$48.50        | CY        |
| Shear Walls                 | \$430.00        | \$42.50        | CY        |
| Curbs, Pads, Toppings       | \$129.00        | \$1.78         | CY        |
| <b>Average per CY</b>       | <b>\$257.21</b> | <b>\$22.23</b> | <b>CY</b> |

| Construction Cost of Concrete System for Turnberry Tower Arlington   |           |      |          |              |                |               |
|--|-----------|------|----------|--------------|----------------|---------------|
| Description  | Qty       | Unit | Material | Labor        | Equipment      | Total Cost    |
| Cast In Place Concrete including placing and stripping formwork, placing rebar, placing concrete, and finishing concrete | 4407<br>2 | CY   | \$241.88 | \$257.21     | \$22.23        | \$22,975,867  |
|  |           |      |          | <b>TOTAL</b> | <b>\$30.63</b> | <b>per SF</b> |

**Comparing Cost of 3 Concrete Systems**

| <b>Structural Systems Cost Comparison for Turnberry Tower Arlington</b> |                   |                       |             |
|---|-------------------|-----------------------|-------------|
| Structural System   | Residential Units | Total Structural Cost | Cost per SF |
| Post Tension Concrete   | 247               | \$20,658,837          | \$27.55     |
| Reinforced Concrete (Removing 1 Story)                                  | 235               | \$22,651,046          | \$30.20     |
| Reinforced Concrete (Adjusting Story Height)                            | 247               | \$22,975,867          | \$30.63     |

## **Appendix E**

### Supply Water System Takeoff Notes and Estimates

#### Contents:

- Propress System Takeoff Notes and Estimate (Typical Unit)
- Comparing Cost of Propress System vs. CPVC System

| Propress System Takeoff Notes (Typical Unit) |                 |            |         |                   |               |            |                |                |
|--|-----------------|------------|---------|-------------------|---------------|------------|----------------|----------------|
| Pipe (Copper - Type L - PP)                  |                 |            |         |                   |               |            |                |                |
| Item   | Size            | Quantity   | Price   | Mat. Cost         | Unit Labor Hr | Total Hrs. | Labor Cost     | Total Cost     |
| Hard Tube                                    | 1/2             | 280        | \$1.96  | \$437.93          | 0.02          | 6          | \$391          | \$829          |
|  | 3/4             | 94         | \$3.12  | \$234.05          | 0.02          | 2          | \$131          | \$365          |
|  | 1               | 76         | \$4.69  | \$284.45          | 0.03          | 2          | \$126          | \$410          |
| <b>Totals</b>                                |                 | <b>450</b> |         | <b>\$956.42</b>   |               | <b>10</b>  | <b>\$648</b>   | <b>\$1,604</b> |
| Fittings (Copper - Propress - PP)            |                 |            |         |                   |               |            |                |                |
| Item   | Size            | Quantity   | Price   | Mat. Cost         | Unit Labor Hr | Total Hrs. | Labor Cost     | Total Cost     |
| 45 Degree Elbow                              | 1/2             | 12         | \$3.30  | \$75.77           | 0.41          | 5          | \$329          | \$405          |
|  | 3/4             | 3          | \$4.05  | \$23.25           | 0.41          | 1          | \$82           | \$105          |
| 90 Degree Elbow                              | 1/2             | 27         | \$2.84  | \$146.71          | 0.41          | 11         | \$740          | \$887          |
|  | 3/4             | 18         | \$4.80  | \$165.29          | 0.41          | 7          | \$493          | \$658          |
|  | 1               | 17         | \$9.62  | \$312.86          | 0.09          | 2          | \$104          | \$417          |
| Coupling                                     | 1/2             | 13         | \$2.55  | \$63.42           | 0             | 0          | \$0            | \$63           |
|  | 3/4             | 7          | \$3.87  | \$51.83           | 0             | 0          | \$0            | \$52           |
|  | 1               | 5          | \$7.82  | \$74.80           | 0             | 0          | \$0            | \$75           |
| Reducer                                      | 3/4 x 1/2       | 17         | \$11.60 | \$377.27          | 0.21          | 4          | \$233          | \$610          |
|  | 1 x 3/4         | 10         | \$13.30 | \$254.44          | 0.25          | 2          | \$164          | \$418          |
| Tee  | 3/4             | 8          | \$7.64  | \$116.93          | 0.62          | 5          | \$329          | \$446          |
|  | 1               | 7          | \$13.76 | \$184.28          | 0.14          | 1          | \$64           | \$248          |
| Tee Reducing                                 | 3/4 x 3/4 x 1/2 | 6          | \$6.42  | \$73.69           | 0.31          | 2          | \$123          | \$197          |
|  | 1 x 1 x 1/2     | 2          | \$15.75 | \$60.27           | 0.37          | 1          | \$49           | \$109          |
|  | 1 x 1 x 3/4     | 1          | \$15.75 | \$30.14           | 0.37          | 0          | \$25           | \$55           |
| <b>Totals</b>                                |                 | <b>153</b> |         | <b>\$2,010.92</b> |               | <b>41</b>  | <b>\$2,735</b> | <b>\$4,746</b> |
| Hanger Components                            |                 |            |         |                   |               |            |                |                |
| Item   | Size            | Quantity   | Price   | Mat. Cost         | Unit Labor Hr | Total Hrs. | Labor Cost     | Total Cost     |
| Fig 65 Clevis                                | 1-1/2           | 56         | \$5.14  | \$138.16          | 0.46          | 26         | \$1,720        | \$1,858        |
|  | 2               | 30         | \$5.50  | \$79.20           | 0.27          | 8          | \$541          | \$620          |
| Allthread-Galv. Wedge                        | 3/8             | 344        | \$3.86  | \$132.78          | 0             | 0          | \$0            | \$133          |
| Anchor                                       | 3/8             | 86         | \$1.35  | \$55.73           | 0             | 0          | \$0            | \$56           |
| <b>Totals</b>                                |                 | <b>516</b> |         | <b>\$405.87</b>   |               | <b>34</b>  | <b>\$2,261</b> | <b>\$2,667</b> |

| Misc. Components                |      |            |       |                  |               |                   |                   |                   |
|---------------------------------|------|------------|-------|------------------|---------------|-------------------|-------------------|-------------------|
| Item                            | Size | Quantity   | Price | Mat. Cost        | Unit Labor Hr | Total Hrs.        | Labor Cost        | Total Cost        |
| Washers - Galv.                 | 3/8  | 258        | 0.39  | \$10.06          | 0             | 0                 | \$0               | \$10              |
| Nuts - Galv.                    | 3/8  | 258        | 0.25  | \$44.51          | 0             | 0                 | \$0               | \$45              |
| <b>Totals</b>                   |      | <b>516</b> |       | <b>\$54.57</b>   |               | <b>0</b>          | <b>\$0</b>        | <b>\$55</b>       |
| <b>PROPRESS SYSTEM</b>          |      |            |       | <u>Mat. Cost</u> |               | <u>Total Hrs.</u> | <u>Labor Cost</u> | <u>Total Cost</u> |
| <b>GRAND TOTALS (TYP. UNIT)</b> |      |            |       | <b>\$3,428</b>   |               | <b>85</b>         | <b>\$5,644</b>    | <b>\$9,072</b>    |

| Comparing CPVC vs. Propress Supply Water Systems (Per Typical Unit) |                |            |                |                |                        |                |            |                |                |
|---|----------------|------------|----------------|----------------|------------------------|----------------|------------|----------------|----------------|
| CPVC System   |                |            |                |                | Propress System (2006) |                |            |                |                |
| Item  | Mat. Cost      | Total Hrs. | Labor Cost     | Total Cost     | Item                   | Mat. Cost      | Total Hrs. | Labor Cost     | Total Cost     |
| Pipe  | \$856.48       | 10         | \$649          | \$1,505        | Pipe                   | \$956.42       | 10         | \$648          | \$1,604        |
| Fittings  | \$350.26       | 58         | \$3,844        | \$4,194        | Fittings               | \$2,010.92     | 41         | \$2,735        | \$4,746        |
| Hanger Components   | \$405.87       | 34         | \$2,261        | \$2,667        | Hanger Components      | \$405.87       | 34         | \$2,261        | \$2,667        |
| Misc. Components  | \$56.90        | 0          | \$0            | \$57           | Misc. Components       | \$54.57        | 0          | \$0            | \$55           |
| <b>Total</b>  | <b>\$1,670</b> | <b>102</b> | <b>\$6,754</b> | <b>\$8,424</b> | <b>Total</b>           | <b>\$3,428</b> | <b>85</b>  | <b>\$5,644</b> | <b>\$9,072</b> |

| Cost of Supply Water System to Units in Turnberry Tower Arlington |                          |                    |                           |                        |                          |                    |                           |
|---|--------------------------|--------------------|---------------------------|------------------------|--------------------------|--------------------|---------------------------|
| CPVC System   |                          |                    |                           | Propress System (2006) |                          |                    |                           |
| Cost Per Unit   | Total Cost for 247 Units | Man Hours per Unit | Total Hours for 247 Units | Cost Per Unit          | Total Cost for 247 Units | Man Hours per Unit | Total Hours for 247 Units |
| \$8,424   | \$2,080,728              | 102                | 25,194                    | \$9,072                | \$2,240,784              | 85                 | 20,995                    |
| Time Savings Using Propress System over CPVC System (Man Hours)   |                          |                    |                           |                        |                          |                    | 4,199                     |
| Cost Savings Using Propress System over CPVC System (\$)          |                          |                    |                           |                        |                          |                    | (\$160,056)               |

Note: This comparison is using prices from 2006

## **Appendix F**


### Site Logistics Plan for Material Delivery

#### Contents:

- Original Site Logistics Plan
- Modified Site Logistics Plan
- Flow of drywall through level 2 of the building




Turnberry Tower Arlington  
Site Plan - Tower Erection



Revisions

| Date | No. | Description |
|------|-----|-------------|
|      |     |             |
|      |     |             |
|      |     |             |
|      |     |             |
|      |     |             |
|      |     |             |
|      |     |             |
|      |     |             |
|      |     |             |
|      |     |             |
|      |     |             |




- Legend**
- Site Boundary
  - Building Boundary
  - Site Chain Link Fence

- Concrete Pump & Truck
- Toilet
- Relocated Traffic Light
- Fire Hydrant


- Rebar Laydown Area
- 30 Yard Dumpster
- Concrete Dumpster
- Temp. Electric Shed

- Trash Chute
- Equipment Laydown
- Material Hoist



Drawn by: Larry Warner  
Date: 10/24/2008  
Sheet Number  
96 OF 99

**Turnberry Tower Arlington  
Site Plan - Tower Erection**



Revisions

| Date | No. | Description |
|------|-----|-------------|
|      |     |             |
|      |     |             |
|      |     |             |
|      |     |             |
|      |     |             |
|      |     |             |
|      |     |             |
|      |     |             |
|      |     |             |
|      |     |             |

Seal

Drawn by: Larry Warner

- Legend**
- Site Boundary
  - Building Boundary
  - Site Chain Link Fence
  - Concrete Pump & Truck
  - Toilet
  - Relocated Traffic Light
  - Fire Hydrant
  - Rebar Laydown Area
  - 30 Yard Dumpster
  - Concrete Dumpster
  - Temp. Electric Shed
  - Trash Chute
  - Equipment Laydown
  - Material Hoist

**Direction**

N

### 2<sup>nd</sup> Floor Deliveries

