Pearland Recreation Center and Natatorium Pearland, Texas



Final Report

Prepared By: Matt Smiddy

Faculty Consultant: Jim Faust

Submitted: April 7, 2010

Pearland Recreation Center and Natatorium

Pearland, Texas



Project Overview:

Use: Community Recreation Center Size: 105,000 SF of Floor Space

Height: 2 Stories

Construction Dates: May 2009 - June 2010

Construction Cost: ~\$17 Million Delivery Method: Design-Bid Build Competitive Bid Lump Sum



Mechanical:

- Three (3) 2000-5000 CFM Outside AHUs
- Eight (8) 3000-19000 CFM Inside AHUs.
- Two (2) 1,063,000 BTUH Natrual Gas Bollers
- Two (2) 1,699,000 BTUH Natural Gas Bollers
- Two (2) 138 Ton Chillers
- Seven (7) 100-340 GPM Pumpa

Electrical:

- One (1) 600A Surface Mounted Distribution Panel
- One (1) 400 KW Back-Up Generator
- 3000A Building Power Supply

Project Team:

Owner: City of Peerland Texas

Pearland Independent School District

CM: EMJ Corporation Architect: PBK

Structural Engineer: Conti, Jumper, Gerdner, & Assoc.

MEP Engineer: PBK - MEP Group Pool Consultant Aquatic Excellence

Architecture:

Natatorium:

- One (1) 50 Meter X 25 Yard Indoor Competition Pool
- One (1) Four (4) Lane X 25 Yard Therapy Pool with
- Handloap Access Ramp
- Meeting/Training Room

Recreation Center:

- Competition Gym with Four (4) Lane Track
- Weight Room
- Men's/Women's Locker Rooms
- Offices
- Multi-Purpose Rooms

Structural:

Natatorium:

- Concrete Plens
- Glulem Structural Framing
- Conorete State on Grade

Recreation Center:

- Concrete Plens
- Structural Steel Framing
- Concrete State on Grade and on Elevated Steel Decking

Matt Smiddy Construction Option

http://www.engr.psu.edu/ae/thesis/portfolios/2010/mds5055/



Table of Contents:

Section	Page #:
Table of Figures and Tables	iv
Acknowledgements	V
Section 1 - Executive Summary	1
Section 2 - Introduction	2
Section 3 - Project Overview	3
3-1 Client Information	
3-2 Project Delivery System	
3-3 Organizational Chart	
3-4 Project Team Contacts	
3-5 CM Staffing Plan	
Section 4 - Design and Construction Overview	7
4-1 Architecture and Enclosure	
4-2 Building Systems	
4-3 Local Conditions	
4-4 Site Layout Planning	
Section 5 - Project Logistics	20
5-1 Milestone Schedule	
5-2 Detailed Project Schedule	
5-3 Construction Cost Estimate	
Section 6 - Analysis #1 – Concrete Columns with Steel Trusses Vs.	30
Glulam Structural System (Structural – Breadth Topic #1)	
6-1 Background Carle	
• 6-2 Goals	
6-3 Analysis Method A December 2	
6-4 Resources Congrete Steel and Olylege	
6-5 Durability of Concrete, Steel, and Glulam Concrete Report R	
6-6 Structural System Re-Design 7 Cost Apply size	
6-7 Cost Analysis Cost Analysis	
6-8 Schedule Analysis Constructed tiltu Analysis	
6-9 Constructability Analysis Can alysis and Bornaria	
6-10 Conclusions and Remarks Continue 7 Analysis #2 AC Chiller Way Continue Toward Analysis #2 Ac Chiller Way Continue Toward The Continue Toward T	22
Section 7 - Analysis #2 – AC Chillers Vs. WC Chiller With Cooling Tower	33
(Mechanical – Breadth Topic #2) • 7-1 Background	
• 7-1 Background • 7-2 Goals	
• 7-3 Analysis Method	
• 7-4 Resources	
• 7-5 System Selection:	
7-6 Cost Analysis 7-7 Schodulo/Constructability Analysis	
7-7 Schedule/Constructability Analysis 7.8 Energy Analysis	
7-8 Energy Analysis 7-9 Conclusions and Remarks	
7-9 Conclusions and Remarks Section 9 Analysis #3 Adversarial Project Team Polationships on	37
Section 8 - Analysis #3 – Adversarial Project Team Relationships on Design-Bid-Build Projects and other Delivery Methods for Public Projects	31
8-1 Background	
• 0-1 Dackyrounu	

•	8-2 Goals	
•	8-3 Analysis Method	
•	8-4 Resources	
•	8-5 Project Team Analysis	
•	8-6 Analysis of Other Delivery Methods on Public Projects	
•	8-7 Applications of MAE Concepts	
•	8-8 Conclusions and Remarks	
Section 9 - Ar	nalysis #4 – Bolted Vs. Welded Glulam Arch Connection	40
•	9-1 Background	
•	9-2 Goals	
•	9-3 Analysis Method	
•	9-4 Resources	
•	9-5 Feasibility and Constructability Analysis	
•	9-6 Design Analysis	
•	9-7 Cost Analysis	
•	9-8 Schedule Analysis	
•	9-9 Conclusions and Remarks	
Section 10 - S	Summary and Conclusions	43
Section 11 - V	Vorks Cited	44
Appendix 3 –	Project Overview References	46
Appendix 5 –	Project Logistics References	51
Appendix 6 –	Analysis #1 (Natatorium Structure) References	67
Appendix 7 –	Analysis #2 (Mechanical System) References	79
Appendix 8 –	Analysis #3 (Delivery Methods) References	86

Table of Figures and Tables:

Table 3-1.1 Project Funding Distribution
Table 3-2.1 - Design Contract Payment Distribution
Figure 3-2.2 - Project Team Organizational Chart
Figure 3-4.1 - CM Organizational Chart
Figure 4-1.1 - First Floor Plan
Figure 4-1.2 – Second Floor Plan
Figure 4-1.3 - South Exterior Elevation
Figure 4-1.4 - North Exterior Elevation
Figure 4-1.5 - East Exterior Elevation
Figure 4-1.6 - West Exterior Elevation
Figure 4-2.1 - Rec Center 1st Floor Mechanical Room
Figure 4-2.2 - Rec Center 2nd Floor Mechanical Room Locations
Figure 4-2.3 - Natatorium 1st Floor Mechanical Room Location
Figure 4-2.4 - Natatorium 2nd Floor Mechanical Room Location
Table 4-2.5 – Mechanical Room Equipment
Figure 4-2.6 - Construction photo of roof trusses at recreation center
Figure 4-4.1 – Excavation Phase Site Plan
Figure 4-4.2 – Foundations Phase Site Plan
Figure 4-4.3 – Structural Framing Erection Phase Site Plan
Figure 4-4.4 – Enclosure Phase Site Plan
Table 5-2.1 – Milestone Date Comparison
Figure 5-2.2 - Structural and Enclosure Trade Construction Sequence
Figure 5-2.3 - Interior Trades Construction Sequence
Figure 5-2.4 – Recreation Center Construction Phase Locations
Figure 5-2.5 – Swimming Pool Construction Sequence
Table 5-3.1 – Cost Estimate Comparison
Table 5-3.2 – Detailed Structural System Estimate Summary
Figure 5-3.3 – Location of Typical Bay Used for Estimate
Figure 6-1.1 - Natatorium with steel structural system
Figure 6-1.2 - Gymnasium with glulam structural system.
Table 6-1.3 - 2003 IBC Structural Loads
Figure 7-1.1 - Cooling Tower
Figure 7-1.2 - Chillers
Table 7-1.3 – Mechanical System Cost Estimate
Table 7-1.4 - Energy Cost Savings
Figure 9-1.1 - Glulam Arches
Table 9-1.1 - Connection Performance Specification
Table 9-1.2 – Items Added and Removed per Connection

Acknowledgements:

A special thanks to the following people for their contribution to this research project:

Jamie Knise - Facchina Construction of Florida LLC

Scott Stoltz – EMJ Corporation

Matt Luna – EMJ Corporation

Phillip Crissman – EMJ Corporation

Kevin Huff – EMJ Corporation

Van Franks – PBK

Andrea Brinkley - City of Pearland

Skipper - City of Pearland

Mike Parks – RM Rogers

Ashley Rohrscheib - Apel Steel Corporation

John Bechtel - Penn State OPP

Chris Musser - Penn State OPP

Carlo Colella – UMD Department of Capital Projects

Martin Powers – Johnson Controls

Tim Robinson – Carrier

Joe Mulligan - Boland-Trane

Nathan Patrick - Southland Industries

Jim Faust – Penn State AE Department

Chris Magent – Penn State AE Department

Moses Ling - Penn State AE Department

Kevin Parfitt - Penn State AE Department

Robert Holland – Penn State AE Department

Pete Medford – Fort Bend Mechanical

Section 1 - Executive Summary

This report focuses on four construction related analyses of the Pearland Recreation Center and Natatorium building in Pearland, Texas, a Houston, Texas suburb. Two of these four construction related research topics also include a structural analysis and a mechanical analysis. In addition to these analyses this report also contains an overview of the project, including a summary of the project team, the building systems, construction cost, construction schedule, and construction logistics.

Analysis #1 considers replacing the glulam structural system in the natatorium with a concrete column and steel joist structural system. This analysis included a feasibility study as well as a structural analysis to design the structural members. Results from this analysis reflect a construction cost savings of over \$600,000 by using the proposed concrete and steel system. Additionally, there are no changes in the construction schedule.

The next analysis looks at replacing the as designed air-cooled chiller mechanical system with a water-cooled chiller and cooling tower mechanical system. This study also includes a mechanical analysis. This study reveals a \$48,500 construction cost savings and a \$248,000 yearly energy cost savings by using the proposed water-cooled chiller and cooling tower system. Again, this modification has no construction schedule implications.

Next the project team's interaction is analyzed, primarily focusing on the effects of the delivery method. Design-bid-build, the delivery method being used on the project, appears to have resulted in a successful project with no adversarial relationships developing. This project is compared with another project being constructed by the same owner but using the design-build delivery method. It is determined that design-bid-build is the preferred delivery method for public projects, particularly when they are complex such as the Pearland Recreation Center and Natatorium project.

Finally an investigation of the glulam column connection with the concrete footers in the natatorium is conducted. Constructability of the as-designed bolted connection is quite difficult during column erection, as precisely aligning the columns with the bolts is challenging. This analysis considers modifying the connection to a welded connection. Using a welded connection results in no additional construction costs and has no effect on the construction schedule. However, a welded connection would have been much easier to construct.

Section 2 - Introduction

The Pearland Recreation Center and Natatorium project is located at 4141 Bailey Road in Pearland, Texas; a suburb 15 miles south of Houston, Texas. It is being developed through a joint venture between the City of Pearland and the Pearland Independent School District to serve the Pearland community.

The \$17 million, 41,817 square foot project began design in March 2007 and construction is scheduled for completion in May 2010. The project, designed by PBK and constructed by EMJ Corporation, is using a design-bid-build delivery method.

The 63,300 square foot recreation center houses a competition gym, indoor running track, racquetball courts, weight room, aerobics room, dance room, locker rooms, administrative offices, and other multi-purpose rooms.

The 41,000 square foot natatorium features a state of the art 25-yard X 50-meter competition pool with two (2) 1-meter and two (2) 3-meter diving boards. There is also a 4-lane 25-yard therapeutic pool with a handicap access ramp.

Section 3 - Project Overview:

3 - 1 Client Information

Pearland Recreation Center and Natatorium is being built to promote recreation and economic activity in Pearland, Texas. The project is being funded by the City of Pearland, Pearland Independent School District, and the Pearland Economic Development Organization as shown below in **Table 3-1.1 - Project Funding Distribution**:

Table 3-1.1 - Project Funding Distribution

Party	Amount Contributed	Source of Funding
City of Pearland, Texas	\$13 Million	Tax Revenue
Pearland Independent School District	\$3.5 Million and 7-acre building site	School Bond
Pearland Economic Development Organization	\$1.5 Million	Tax Revenue

The City of Pearland identified a recreation center and natatorium as 'high' priority in their 2005 master plan. At the same time, Pearland Independent School District recognized a need for a natatorium for their school. The two parties decided to come together to build a joint project. The Pearland Economic Development Organization also recognized the potential economic impacts this project could have on local businesses through additional visitors to the Pearland area. A similar facility nearby, University of Houston's Recreation Center, currently has to turn away requests for facility use due to overbooking, so this new facility could have a significant economical impact on the community.

The master plan called for a project that would serve the community for many years. To meet this goal, the project was flexibly designed to meet any potential changes in regulations. For example the competition pool was designed to be 55 meters long with (2) 2.5 meter wide bulkheads so should regulation pool length change, the facility could easily be modified to meet this new requirement.

The only project deadline is to have the natatorium completed before the start of school in Fall 2010. At this time the project should be completed in June 2010, so this will not be an issue. Currently the project does not have a phased completion and there are no intentions to implement one at this time.

3 - 2 Project Delivery System

A design-bid-build delivery system is being used on the Pearland Recreation Center and Natatorium project. The City of Pearland, Pearland Independent School District, and Pearland Economic Development Organization are building the project as a joint-venture. However, all contracts for the project are held by the City of Pearland. The City of Pearland has hired PBK as the architect and EMJ Corporation as the construction manager for the project.

PBK has selected sub consultants to assist in designing the project. The primary consultants are shown in **Figure 3-2.2 - Project Team Organizational Chart**. The only designer contract held with the City of Pearland is a lump sum Professional Design contract, with payments distributed as shown in the **Table 3-2.1 - Design Contract Payment Distribution**.

Table 3-2.1 - Design Contract Payment Distribution

Deliverable	% of Lump Sum
Schematic Design	15%
Complete Design	15%
Construction Documents	20%
Contractor Procurement	25%
Construction Service	25%

EMJ was selected as general contractor through a 'Best Value' selection method. The City of Pearland considered items such as cost, schedule history, references, and proposed specialty contractors during this selection process. EMJ contracted specialty contractors to perform all the work on site. They hold lump sum contracts with all their subs as shown in **Figure 3-2.2 - Project Team Organizational Chart**. A complete list of specialty contractors on the project is available in **Appendix 3**.

The project design was essentially completed prior to contractor selection, so the design-bid-build delivery method with a lump sum contract is appropriate for this project.




Figure 3-2.2 - Project Team Organizational Chart

The City of Pearland required the following insurance to be held by the contractors and design professionals on the project:

- -Worker's Compensation as per Texas State Requirements
- -Commercial General Liability Insurance:
 - -\$1,000,000 for each occurrence
 - -\$2,000,000 general aggregate limit
 - -\$2,000,000 product-completed operations aggregate limit
 - -\$1,000,000 personal and advertising injury limit
- -Auto liability insurance coverage of \$1,000,000
- -Employer's liability insurance coverage of \$1,000,000 per accident or disease
- -Umbrella liability insurance coverage of \$5,000,000
- -Professional liability insurance coverage of \$1,000,000.
- -Builder's risk insurance in equivalence to total repair and replacement charges of every incident.

3 - 3 Project Team Contacts

City of Pearland – Andrea Brinkley – Project Manager

EMJ Corporation - Scott Stoltz - Project Manager

EMJ Corporation – Kevin Huff – Project Engineer

EMJ Corporation - Phillip Crissman - Project Superintendent

PBK - Van Franks - Principle

3 - 4 CM Staffing Plan

The CM (EMJ Corp) project team for the Pearland Recreation Center and Natatorium project consists of a Vice-President in Charge, a Project Manager, a Project Engineer, a Superintendent, and an Assistant Superintendent.

The Vice-President in Charge, Project Manager, and Project Engineer work from the EMJ home office in Dallas, TX and visit the project site about twice a month. The Superintendent and Assistant Superintendent are on-site in Pearland, TX at all times.

The Project Engineer, Superintendent, and Assistant Superintendent work full time on the project while the Project Manager and Vice-President in Charge are both part time on the project and oversee other projects as well. **Figure 3-4.1 - CM Organizational Chart** shows the organization of the staff on this project.




Figure 3-4.1 - CM Organizational Chart

Section 4 - Design and Construction Overview

4 - 1 Building Architecture/Enclosure

The Pearland Recreation Center and Natatorium houses a recreation center and natatorium as shown in **Figures 4-1.1 – First Floor Plan** and **4-1.2 – Second Floor Plan**. The building spans 638'-1" and is 230'-1" wide. The natatorium is located on the eastern half of the building and is connected to the recreation center on the opposite half of the building.




Figure 4-1.1 - First floor plan

B C C D

Recreation Center Figure 4-1.2: Second floor plan

Natatorium

The 2-story recreation portion of the building contains a double height competitive gym seating 588 spectators and a raised 4-lane running track around the perimeter. There is also a dance room, aerobics room, weight room, 2 racquetball courts, locker rooms, offices, and other multipurpose rooms.

The double height natatorium contains an 8-lane 50 meter competition pool and a 4-lane 25 yard instructional pool with a handicap ramp. The competition pool includes a moveable bulkhead, (2) 1-meter diving boards, and (2) 3-meter diving boards. There is seating for 694 spectators in bleachers surrounding the competition pool. There are also equipment rooms and training rooms in this portion of the building.

Building Codes

2003 International Building Code

2003 International Plumbing Code

2003 International Mechanical Code

2003 International Electrical Code

2003 International Energy Code

2003 International Fire Code

2003 International Gas Code

1994 Texas Accessibility Standards

1992 Americans with Disabilities Act

Zoning

Zoning District – 'GB' (General Business)

	Requirements	Actual
Minimum Lot Size	22,500 Square Feet	330,090 Square Feet
Minimum Lot Width	150'-0"	727'-7" (Frontage on Bailey Road)
Minimum Lot Depth	125'-0"	453'-8"
Building Setback: Front	25'-0" Minimum	212'-6"
Building Setback: Rear	25'-0" Minimum	32'-9"
Building Setback: Side	10'-0" Minimum	34'-6"
Height Restriction	45'-0" Maximum Height	44'-11"

Historical Requirements

There are no historical requirements on this project.

Building Facades

The facades are primarily face brick on horizontally reinforced 8" CMU with rigid insulation and damp proofing between. The facades by the recreation center and natatorium entrances are calcium silicate masonry units on horizontally reinforced 8" CMU with rigid insulation and damp proofing between. All the glazing is ¼" Tinted Tempered Float Glass.

The south façade, facing Bailey Road is 25% glazing as shown in **Figure 4-1.3 - South Exterior Elevation**.




Figure 4-1.3 - South Exterior Elevation

The north façade has 10 windows as shown in Figure 4-1.4 - North Exterior Elevation.




Figure 4-1.4 - North Exterior Elevation

The east façade has a series of strip windows along the recreation center entrance as shown in **Figure 4-1.5 - East Exterior Elevation**.




Figure 4-1.5 - East Exterior Elevation

The west façade has 10 windows plus a strip window at the recreation entrance as shown in **Figure 4-1.6 - West Exterior Elevation.**




Figure 4-1.6 - West Exterior Elevation

4 - 2 Building Systems

Demolition

No demolition was required.

Excavation

The site is at an elevation of 14' above sea level. It was necessary to excavate to about 14' for the foundations. For this reason it was necessary to dewater the site. This was done using well points throughout the site. Excavation was done with a 1:1 layback so no temporary support was needed.

Structural Framing System

The Recreation center has a structural steel frame. The columns are all tube steel while the beams are W-sections with K-series joists supporting 18ga galvanized 1-1/2" deep non-composite floor decking and 22ga galvanized 1-1/2" deep Type "B" steel non-composite roof decking. All connections between W-sections are bolted and the connections to the tube steel are welded connections. The steel was erected using a 50-Ton and 80-Ton Truck Crane.

The Natatorium has glulam columns supporting glulam purlins which support a 3" wood deck. The glulam system was erected using a 100-Ton and 75-Ton Truck Crane.

Cast-In Place Concrete

The only cast-in-place concrete in this project was the slabs and foundations. The foundation consisted of spread footings on drilled piers. The footings used stick-built forms and were poured with a pump truck. There is a 5" thick reinforced concrete slab-on-grade with a vapor barrier that extends throughout the entire building foundation. There is also a 3" thick concrete slab on WWF on the elevated slabs. The slab-on-grade was placed using a pump truck in 4 different pours. The elevated slabs at the second level and the roof were each poured in 3 pours.

Precast Concrete

There is no precast concrete on this project.

Mechanical System

The recreation center is serviced by five (5) mechanical rooms located as shown below in Figures 4-2.1 - Rec Center 1st Floor Mechanical Room Locations and 4-2.2 - Rec Center 2nd Floor Mechanical Room Locations:




Figure 4-2.1 - Rec Center 1st Floor Mechanical Room Locations





Figure 4-2.2 - Rec Center 2nd Floor Mechanical Room Locations

The Natatorium is serviced by two (2) mechanical rooms as shown below in **Figures 4-2.3** - **Natatorium 1st Floor Mechanical Room Location** and **4-2.4** - **Natatorium 2nd Floor Mechanical Room Location**:



The mechanical rooms contain mechanical equipment as shown in **Table 4-2.5 – Mechanical Room Equipment**.

Table 4-2.5 – Mechanical Room Equipment

Location	Item
RM1a	Two (2) Air Cooled Chillers
RM1b	Four (4) End Suction Pumps
RM2a	Two (2) Air Handling Units, Two (2) Boilers, and One (1) End Suction
	Pump
RM2b	Three (3) Air Handling Units
RM2c	Four (4) Air Handling Units
NM1	One (1) Air Handling Unit and One (1) Condenser
NM2	Two (2) Air Handling Units

Air is distributed throughout the building using rectangular and flex duct. These ducts then connect to Constant Air Volume Terminals in each room.

Fire Suppression System

The building has a Wet Pipe Pre-Action Fire Sprinkler System that is to be installed to a performance spec of:

Public Spaces, Classrooms, and Offices: 0.10 GPM/SF over the most remote 1,500 SF.

Mechanical Rooms, Storage Areas, and Service Areas: 0.15 GPM/SF over 1,500 SF.

Electrical System

The electrical system for the Pearland Recreation Center and Natatorium has a 3000A building supply with a 600A Surface Mounted Distribution Panel. There is also a 400 KW emergency back-up generator for the building.

Masonry

The entire building has an 8" horizontally reinforced non-load bearing CMU enclosure. There is reinforcing at 16" on-center. There is also a bond beam every 8' (12-courses of block).

Attached to the CMU is a face brick veneer connected by masonry ties every 4-courses of CMU. Between the CMU and face brick there is 1 ½ inch rigid insulation and an air space. Additionally, the CMU has a damp proofing applied to it.

Roofing

The roof in the recreation center is a steel truss system (shown in **Figure 4-2.6 - Construction photo of roof trusses at recreation center**) while the roof in the natatorium is a glulam truss system. The roofing system throughout the recreation center and natatorium consists of a standing seam metal roof on a fully adhered waterproof membrane. The roofing system over the main entrance to the building on the south side, a small strip between the recreation area and natatorium, and a small portion of the north side of the natatorium is modified bitumen.



Figure 4-2.6 - Construction photo of roof trusses at recreation center

Curtain Wall

There are no curtain walls in this building.

Sustainable Features

This building has no sustainable features.

4 - 3 Local Conditions

Labor

The project site is located in a suburb of Houston, TX; the 4th largest city in the US. This location enables easy access to a diversely skilled labor force. For this reason labor availability will not be a problem.

Weather

Houston, TX has a warm and mild climate. While winter weather will not be an issue, there is the potential for tropical weather to affect the project during the fall months. Additionally, since the project is located in a region that is prone to tropical weather, there will be more stringent building codes and inspections.

Geography

The project is located on a 7-acre plot of land in an unpopulated portion of the suburb of Houston, Texas. There is ample area for construction lay down and parking.

The project site is at a very low elevation (+14'). Because of the low site elevation, ground water will be a serious consideration during excavation. It will be necessary to de-water the site during all excavation activities.

Sustainability

Sustainable construction practices are not predominant in the Houston area. It is uncommon for construction projects to apply sustainable practices such as construction material recycling, etc.

Tipping Fees:

It is common practice in the Houston area to not recycle construction material. For this reason, all construction waste is placed in the same dumpster on site. Removal of this waste costs \$316 per 40 cubic yard dump. This is \$7.9 per cubic yard of waste.

4 - 4 Site Layout Planning

Site layout for the Pearland Recreation Center and Natatorium is greatly simplified due to a large site. Consistent across all phases of the project are the dumpsters in the northeast corner of the site with a dedicated entrance off of Bailey road for access to empty them, porta-potties in the northeast corner of the parking lot, the construction offices on the east side of the site, the temporary transformer in the southeast corner of the building, temporary utilities running to the southeast corner of the building from Bailey Rd, contractor parking on the south side of the site, and the site entrance off of Bailey road on the south side of the site.

Site layout for the excavation phase of construction is shown in **Figure 4-4.1 – Excavation Phase Site Plan**. Excavation will begin from the northwest corner of the building and proceed towards the southeast corner of the building as shown. Dump trucks will arrive and circulate through the site to remove soil as shown.




Figure 4-4.1 – Excavation Phase Site Plan

Figure 4-4.2 – Foundations Phase Site Plan shows the site layout for the foundations phase of construction. Foundations work will again progress from the northwest corner to the southeast corner of the building. A rebar yard, with access provided for flatbed rebar truck deliveries, is provided in the southwest corner of the site. The pump truck and concrete trucks will circulate as shown. They will only be present on site during concrete pours. The location of the pump truck will move eastward on the site as work progresses. A contractor material storage area is also provided in the southeast corner of the site.




Figure 4-4.2 – Foundations Phase Site Plan

The project site begins to become more congested as the structural framing erection phase of construction begins. Site layout for this phase is shown in **Figure 4-4.3 – Structural Framing Erection Phase Site Plan**. Erection of the steel and glulam will proceed from the west end of the building to the east end. Steel and glulam members will be delivered and unloaded in the shake-out area in the southwest corner of the site. Two cranes will be erecting the steel and glulam on site, one on the north side and one on the south side of the building as shown. Steel joists will be delivered to this shake-out area as well, but will then be moved to the joist shake-out area on the north side of the site to be prepared for final erection. There will be an access point for stocking material to the building located at the southwest corner of the building. This will be done using front loaders.





Figure 4-4.3 – Structural Framing Erection Phase Site Plan

Enclosures is the final phase of construction. Work in this phase will progress in a clockwise direction, first around the recreation center than proceeding to go around the natatorium. There will be a contractor material staging area in the southwest corner of the site. This area will be used by contractors to unload materials from trucks as shown. There are also material storage areas on the north side and in the southeast corner of the site. Materials will again be stocked to the building through the access point at the southwest corner of the building using front loaders. **Figure 4-4.4 – Enclosure Phase Site Plan** shows the site layout for this phase of construction.



Section 5 - Project Logistics

The project schedule for the Pearland Recreation Center and Natatorium begins with commencement of design on March 1, 2007 and ends with substantial completion on May 12, 2010.

5 – 1 Milestone Schedule

After site work is completed, the recreation center will be constructed separately from the natatorium. While they are one building, the structural systems and building features of the two portions are completely different so separate construction of the two building sections seems most efficient. Through each phase of construction, the recreation center will generally precede construction of the natatorium.

Site Work

The site work activity contains all work done for site preparation as well as for the parking lot, which will be constructed at the beginning of the project to allow for a cleaner construction site.

Foundations

The foundations in the natatorium will commence once the excavation has been completed for the swimming pools. This excavation will be performed while the foundations are being constructed on the recreation center.

Structural

The structural system in the recreation center is very simple and does not have anything important to note. The natatorium has 14 large glulam beams that will span the swimming pools. The structural system in the natatorium will begin after the recreation center's structural system has been completed and will be constructed by a separate contractor due to the glulam material.

Finishes

The finishes in the recreation center again don't have anything unique to note, however the natatorium must have the interior finishes completed prior to beginning the swimming pool finishes (tiles, etc.) in order to avoid damage to the expensive work that will be put in place in the swimming pool.

The project schedule for this project is relatively simple. The key item to notice when viewing the schedule is the separation in construction of the two (recreation center and natatorium) portions of the building. See **Appendix 5** for the complete project summary schedule.

5 - 2 Detailed Project Schedule

Construction of the Pearland Recreation Center and Natatorium will begin with the Notice to Proceed on April 20, 2009 and conclude with Substantial Completion on May 12, 2010. The complete detailed schedule is available in **Appendix 5**. To create the construction schedule for the project the building was split into two portions: recreation center and natatorium. This was done because these two portions of the building are very different and will be constructed in a different manner due to the swimming pool and glulam structural system in the natatorium. **Table 5-2.1 – Milestone Date Comparison** compares some key construction milestone dates in the recreation center versus the natatorium.

Table 5-2.1 – Milestone Date Comparison

Milestone	Recreation Center	Natatorium
Notice to Proceed	4/20/2009	4/20/2009
Top Out	8/7/2009	8/30/2009
Dry-In	10/23/2009	12/9/2009
Substantial Completion	5/12/2010	4/28/2010

Structure and Enclosure

Construction of the building's structural system and enclosure is sequenced as shown in **Figure 5-2.2 - Structural and Enclosure Trade Construction Sequence**




Figure 5-2.2 – Structural and Enclosure Trade Construction Sequence

Interiors

Following 'Dry-In,' a 'parade of trades' construction sequence is applied; that is only one trade works in each space at a time and each trade follows the previous. **Figure 5-2.3 - Interior Trades Construction Sequence** shows the order of the interior 'parade of trades'.




Figure 5-2.3 - Interior Trades Construction Sequence

Following the interior 'parade of trades' a number of specialty items are installed, such as casework, gym flooring, and gym equipment. See the detailed schedule in **Appendix 5** for all activities.

Recreation Center

Construction of the recreation center progresses counterclockwise through the building in three phases. **Figure 5-2.4 – Recreation Center Construction Phase Locations** shows the locations of these three phases.




Figure 5-2.4 – Recreation Center Construction Phase Locations

Second floor activities only have two phases since the gym is double height and the small portion of phase three that has a second level is combined with phase 2 for the second floor.

Natatorium

There is no phasing of construction in the natatorium as there was in the recreation center. Construction sequencing in the natatorium will revolve around the swimming pool construction. See **Figure 5-2.5 – Swimming Pool Construction Sequence** for the sequence of swimming pool construction activities.




Figure 5-2.5 – Swimming Pool Construction Sequence

Construction of other portions of the natatorium will be occurring throughout the pool construction; however it is critical that the finishing and tiles in the swimming pool are the last activity to occur in the swimming pool area in order to protect the work. Immediately after this is completed, the pool will be filled with water and testing and chemical balancing will begin.

5 - 3 Construction Cost Estimate

Actual Cost

Total Actual Building Construction Cost: \$15,137,233

Actual Building Construction Cost/SF: \$144.00/SF

Total Project Cost: \$16,901,509

Project Cost/SF: \$160.79

By System

System	Total Cost (\$)	Cost/SF (\$)
Structural Steel (Erection Included)	\$1,054,385	\$5.8
Cast-In Place Concrete	\$1,166,021	\$11.09
Masonry	\$1,223,500	\$11.64
HVAC	\$1,907,000	\$18.14
Electrical	\$41,936	\$0.40
Plumbing	\$499,027	\$4.75
Fire Protection	\$195,450	\$1.86
Elevators	\$41,936	\$0.40
Roofing	\$609,900	\$5.81

NOTE: For confidentiality purposes the actual estimate has not been posted.

Estimated Construction Cost

The estimated cost for the project was created using D4Profiler and RS Means SF Cost Data. D4Profiler takes real cost data from similar past projects and modifies it to meet the specified building requirements.

D4Profiler had a very similar project, a recreation center with a large natatorium, just outside of Cincinnati, Ohio. This project was almost the exact same size as well the Pearland project as well. The cost was within 1% of the actual cost. This cost was the total project cost, not just the construction cost. This total project cost estimate is included in **Appendix 5**.

Obtaining an RS Means estimate was more difficult. A separate cost estimate was obtained for the recreation center (using the 'Gymnasium' building type in RS Means) and the natatorium (using the 'Swimming Pool, Enclosed' building type in RS Means). A problem that arose was that the cost data provided in RS Means was for projects much smaller than the Pearland project. To account for this it was necessary to extrapolate the table values. The cost estimates for these two portions were then combined to obtain a total building cost. This price was again within 1% of the actual cost. This estimate is only for construction costs and is included in **Appendix 5** with all the calculations that were performed.

These estimates are shown in the **Table 5-3.1 - Cost Estimate Comparison** below.

Table 5-3.1 – Cost Estimate Comparison

Method	Total Cost (\$)	Cost/SF (\$)	Price Includes:
D4Cost	\$16,786,542	\$159.87	Total Project Cost
RS Means SF	\$15,043,887	\$143.28	Construction Cost
Data			

Detailed Structural Cost Estimate

In addition to the Parametric Cost Estimate from D4Profiler and the SF Cost Estimate from RS Means, a detailed structural system construction cost estimate was also performed. A detailed structural system construction cost estimate for the Pearland Recreation Center and Natatorium project yielded just over \$4,425,000, or about \$42/SF. This cost includes all labor, equipment, and material required for construction of the caissons, concrete, structural steel, steel decking, joists, trusses, wood decking, and glulam structural framing. A break-down of the cost estimate is shown in **Table 5-3.2 – Detailed Structural System Estimate Summary**. The complete estimate as well as the calculations are available in **Appendix 5**.

Table 5-3.2 – Detailed Structural System Estimate Summary

Cost Breakdown Summary

Dev.	Item	Total Cost
02465	Caissons	\$526,841.25
03220	Rebar	\$60,681.51
03221	WWF	\$18,041.18
03310	3000 psi concrete	\$145,747.62
03311	3500 psi concrete	\$36,687.77
03312	Concrete Finishing	\$15,161.58
03313	Concrete Forming	\$471,115.84
03314	Vapor Barrier	\$123,562.53
03315	5" Concrete Edge Form	\$2,729.14
03316	3" Pour Stop	\$821.42
03500	Roof Deck	\$626,272.50
05100	Structural Steel	\$702,167.12
05200	Steel Floor Joists	\$390,755.16
05300	Metal Deck	\$66,784.03
06100	Wood Trusses	\$170,000.00
06110	Glulam (Decking, Purlins, and Columns)	\$1,070,000.00
	Total Cost	\$4,427,368.67

Pricing for the estimate was obtained using RS Means 2009 Building Construction Cost Data and contractor information. RM Rodgers provided the glulam pricing and Tectum Inc. provided pricing for the Tectum E roof decking system over the recreation center. All other pricing information came from RS Means.

The estimate was created by doing a detailed take-off of a typical bay of the building and extrapolating. **Figure 5-3.3 – Location of Typical Bay Used for Estimate** shows the 2520 SF (both levels) area, between gridlines G-J and 1-2, which was used.




Figure 5-3.3 – Location of Typical Bay Used for Estimate

Recreation Center

Using the total cost estimate obtained from this bay, a cost/SF value was calculated and multiplied by the square footage of the recreation center. This cost/SF did not include the Tectum 'E' roof decking or roof trusses. The cost of these two items was estimated for the entire recreation center then added to the extrapolated cost estimate. See **Appendix 5** for the complete detailed cost estimate.

Natatorium

Modifications had to be made to the cost/SF value to estimate the natatorium's structural system cost since the structural system is glulam instead of steel, like the recreation center. Additionally, there are no elevated slabs in the natatorium. To account for these differences the structural steel and elevated deck costs were subtracted from the recreation center's cost/SF. This new cost/SF was then multiplied by the total square footage of the natatorium. This extrapolated value was added to the glulam columns, purlins, and decking value provided by

RM Rodgers for the total natatorium structural system construction cost. See **Appendix 5** for the complete detailed cost estimate.

General Conditions Estimate

A detailed general conditions cost estimate was also calculated. A general conditions cost of just over under \$2 million was estimated for the Pearland Recreation Center and Natatorium project. This estimate was obtained using pricing from RS Means and EMJ Corporation. See **Appendix 5** for the complete estimate.

The general conditions estimate contains 5 portions: project management, temporary facilities, temporary utilities, cleaning, and miscellaneous. Project management and insurance, bond, and O&P are the primary costs in the general conditions, totaling almost \$1.9 million. Temporary facilities include items such as job office trailers, temporary sanitary facilities, and barricades. All material hoisting (lifts, cranes etc.) and heavy equipment are to be provided by the contractors so it was not necessary to include these items. Temporary utilities consist of costs for temporary electric, water, and telephone during construction. The cleaning section will pay for weekly site clean-up and final building clean-up. A miscellaneous section with items such as hand tools, safety, and blue prints is also included. A 2% bond, 3% insurance, and 10% overhead and profit are also included in the estimate. These percentages are of the total project cost (\$16,786,542 as per Tech #1 estimate).

Section 6: Analysis #1 – Concrete Columns with Steel Trusses Vs. Glulam Structural System (Structural – Breadth Topic #1)

6 – 1 **Problem**:

Unlike the steel structural system in the recreation center, the natatorium has been designed using a glulam structural system. It is unusual for a natatorium to use a glulam structural system.

Additionally, glulam is significantly more expensive than concrete and steel and presents unique challenges during construction. The designer insists that structural steel, even with special coatings, corrodes and deteriorates in the humid environment of natatoriums.

6 - 2 Goal:

Determine the structural and economic feasibility of using a steel structural system in place of the currently designed glulam system in the natatorium, including identifying the durability of steel and glulam in a natatorium's humid environment.

6 – 3 Analysis Method:

 Determine the durability of concrete, steel and glulam structural systems in a natatorium environment, including all maintenance issues and costs.



Figure 6-1.1 - Natatorium with steel structural system. Courtesy of Penn State



Figure 6-1.2 - Gymnasium with glulam structural system. Courtesy of Structure Mag

- 2) Design a structural concrete and steel system to replace the glulam system.
- 3) Calculate the cost savings associated with using a structural concrete and steel system
- 4) Analyze the schedule impacts of using a structural concrete and steel system
- 5) Consider the constructability effects of using structural concrete and steel

6 – 4 Resources:

- 1) Penn State OPP Chris Musser
- 2) University of Virginia Capital Projects
- 3) University of Maryland Capital Projects
- 4) University of Houston Capital Projects
- 5) RS Means 2009 Cost Data
- 6) R.M. Rodgers Miles Parks
- 7) Designers with experience in glulam and concrete and steel structural systems in natatoriums.
- 8) MS Project
- 9) Pearland Recreation Center and Natatorium project team.

6 – 5 Durability of Concrete, Steel and Glulam:

Initially the objective of this analysis was to design a completely steel structural system in the natatorium. As research of the steel structural system progressed, it was suggested by structural engineers at a number of university's capital projects groups that a structural system consisting of concrete columns and steel girders/joists be used instead. Paint on steel chips very easily and when exposed to water (like the bases of columns would be) the steel would begin to rust. Alternatively, if concrete was used the only concern would be water penetrating the concrete and rusting the rebar. Since the bases of the columns will not be saturated with water this scenario can be ignored. Similarly, since the steel joists and girders would be located up in the ceiling, the chance of paint being chipped on them would be very low. Additionally, the only water concern would be humidity which should not cause the steel to rust, especially if the paint on the steel is not chipped.

6 – 6 Structural System Re-Design:

After a concrete and steel structural system was decided upon it was necessary to design the system. The system was designed using the 2003 International Building Codes shown in **Table 6-1.3 – 2003 IBC Structural Loads**. The roof slope was set at 3:12.

Table 6-1.3 -2003 IBC Structural Loads

Type of Load	Design Load
Roof	20 lb/SF
Dead Weight	20 lb/SF
Wind	120 mph for 30 sec gust – exposure C – importance factor of 1.15

The resulting design consisted of (468) 25' 14k1 joists at 4' o.c. These joists rest on (14) 140' 104SLH22 girders at 25' o.c. The steel system rests on (28) 10" X 10" square concrete columns with 4-#5's. The design calculations as well as the Steel Joist Institute and Concrete Reinforcing Steel Institute sizing sheets that were used are attached in **Appendix 6.** It is important to note that throughout this system redesign it was assumed that the CMU walls in the natatorium would support the structure laterally.

6 – 7 Cost Analysis:

Once a new structural system was designed it was necessary to determine the cost implications of this design modification. To do this RS Means 2009 Cost Data was used. Using this cost data, a total system cost of \$469,738 was obtained. This was a \$600,262 savings over the \$1,070,000 glulam structural system (supplied by R.M. Rodgers, glulam contractor on project) that it replaced. An additional \$30,000 was incorporated into the steel system to cover extra connection costs (plates for column-beam connection, etc.) Cost calculations as well as RS Means cut sheets are included in **Appendix 6**.

6 – 8 Schedule Analysis:

A schedule analysis was performed to analyze the effects of this new system on the construction schedule. It was discovered that there was no effect on the schedule. As shown in the modified schedule (shows only the portion of the schedule that included this modification) in **Appendix 6**, the concrete columns are poured while steel is being erected on the Recreation Center and when steel erection is completed on the Recreation Center, the erectors simply continue work on the building with erection in the Natatorium. Prior to the system modification, the steel erectors would have been done once the Recreation Center was complete and the glulam erectors would begin their structural system erection by erecting the glulam members. The only difference with the modified system is that instead of the glulam erectors working on the Natatorium following completion of the Recreation Center's steel, there would be steel erectors erecting steel in the Natatorium.

6 – 9 Constructability Analysis:

Modification of the structural system makes it more easily constructible. The 100 Ton truck crane that was used to erect steel in the Recreation Center would already be on site and would be able to lift all the steel members in the natatorium so no additional cranes would be needed. Additionally, a constructability challenge with the glulam system was the erection of the arches, particularly aligning the bolted connection to the footer. By using the concrete columns this concern could be neglected. Another benefit of this new system is that it would eliminate the need for a glulam subcontractor and would therefore result in one less subcontractor that needs to be on site and managed.

6 – 10 Conclusions and Remarks:

Modification of the natatorium structural system from glulam to steel and concrete resulted in a cost savings, no schedule change, and a more easily constructible building. The objective of this analysis was successful in identifying a preferable alternative to the as-designed natatorium structural system.

Section 7: Analysis #2 – AC Chillers Vs. WC Chiller With Cooling Tower (Mechanical – Breadth Topic #2)

7 – 1 *Problem:*

During the design phase of construction the owners of the Pearland Recreation Center and Natatorium insisted on using a cooling tower system to cool the water for the building's mechanical system. PBK, the project architect and MEP engineer, convinced them that using a cooling tower system with a water cooled (WC) chiller would be unreasonable since the building was only 105,000 SF. Instead they suggested using an air cooled (AC) chiller system, which would be a more economical choice given the size of the building.

7 – 2 Goal:

The goal of this research topic is to compare the cost of a cooling tower and WC chiller and AC chiller system in order to determine the more economical option. Cost data is already available for the AC chiller system; however it will be necessary to size and develop a construction cost estimate for a WC chiller and cooling tower system.



Figure 7-1.1 - Cooling Tower (Courtesy of Zetacorp)



Figure 7-1.2 - Chillers (Courtesy of Tatro Plumbing)

7 – 3 Analysis Method:

- 1) Determine the cooling loads on the Pearland Recreation Center and Natatorium
- Select a cooling tower and WC chiller system that would satisfy the required cooling loads for the building.
- Obtain construction cost information for the selected WC chiller and cooling tower system.
- 4) Compare the cost of the WC chiller and cooling tower system to the as designed AC chiller system to determine the more economical option.
- Consider constructability factors that may make either option more feasible.
- 6) Consider life-cycle cost and maintenance factors for each option.

7 – 4 Resources:

- 1) Professor James Freihaut and AE 310 HVAC Fundamentals course materials
- 2) Pearland Recreation Center and Natatorium project MEP engineer PBK MEP
- 3) Fort Bend Mechanical
- 4) EMJ Corporation
- 5) Southland Industries Nathan Patrick
- 6) Chesapeake Systems David Jaworski
- 7) Boland-Trane Joe Mulligan

7 – 5 System Selection:

The first step in analyzing the modification of the mechanical system was to design and select a suitable system. As previously mentioned, the current AC chiller would need to be replaced with a WC chiller as well as a Cooling Tower. The 2 as-designed AC chillers each had a capacity of 138 Tons, an entering water temperature of 56d F, a leaving water temperature of 42dF, and a flow rate of 240 GPM. Using these previous design specs and the fact that the project was located in Houston, TX it was determined that the new WC Chiller/Cooling Tower system be designed with a DB temperature of 92dF, a WB temperature of 77dF, a capacity of 276 tons and a 85dF condenser water temperature. Using these parameters it was discovered that the 2 AC chillers could be replaced with only 1 WC chiller. Similarly, the Cooling Tower was sized using an 85dF entering water temperature, a 95dF leaving water temperature and a 828 GPM (3 GPM/ton) flow rate. Product cut sheets for the WC chiller and Cooling Tower supplied by Boland-Trane and Chesapeake Systems are available in **Appendix 7**.

7 – 6 Cost Analysis:

Once the new mechanical system was designed it was then necessary to estimate the cost of the new system and compare it to the previous system. To do this, quotes were obtained from Chesapeake Systems and Trane-Boland for the cooling tower and WC chiller respectively. Labor costs for the installation of this equipment and additional pumps and piping required for the cooling tower were obtained from RS Means 2008 Cost Data. Cost information for the asdesigned system was obtained from Fort Bend Mechanical, the mechanical contractor on the project. The new mechanical system offered a \$48,523 savings over the previous system.

Table 7-1.3 – Mechanical System Cost Estimate contains a summary of this comparison and the complete cost estimate calculations are contained in Appendix 7.

Table 7-1.3 – Mechanical System Cost Estimate

Item	Cost	Source
Cooling Tower		
Material	\$30,171	Chesapeake Systems
Labor	\$2,650	RS Means 2008 Cost Data, Pg. 374
Additional Pumps & Piping		·
Labor & Material	\$26,082	RS Means 2008 Cost Data, Pg. 374
Water Cooled Chiller		·
Material	\$93,840	Boland-Trane
Labor	\$11,700	RS Means 2008 Cost Data, Pg. 373
Additional Structural Support for Cooling Towers		·
Labor & Material	\$15,557	Fort Bend Mechanical
Total Cost for New System	\$180,000	
Total Cost for Old System	\$228,523	
Initial Cost Savings with New System	\$48,523	

7 – 7 Schedule/Constructability Analysis:

There are three potential constructability issues that would need to be considered with the new WC Chiller/Cooling Tower system that were not present with the old system:

- The Cooling Tower would require additional structural support in the concrete slab that it would be placed on. This issue should not pose a problem, given the concrete slab is properly reinforced when it is constructed.
- 2) The Cooling Tower would require a crane for placement. It would be important to properly plan for this and ensure that adequate access is left to the mechanical courtyard on the north side of the building where it would be placed.
- 3) Previously, the AC chiller had been placed outside in the mechanical courtyard. With the new system, the cooling tower would be placed here and the water cooled chiller would need to be placed inside. There would be room for this equipment in the mechanical room on the northwest corner of the building. However it is important to consider access to this room for chiller installation.

While none of these issues should be a problem, it would be important to give them careful consideration while planning construction to ensure that adequate measures would be taken to account for them. This system modification should have no effect on the schedule since the only additional activities will be cooling tower placement and some extra pumps and piping which could be included in the current mechanical system construction duration.

7 – 8 Energy Cost Analysis:

An energy cost comparison between the two systems was also performed. The old air-cooled chiller system consumed 1.3 KW/Ton for each chiller, or a total of 718 KW. Using a water-cooled chiller and cooling tower the total energy usage would be only 427 KW. Energy information for the water-cooled chiller came from Boland-Trane and for the cooling tower a COP of 4 was assumed and the KW/ton value was calculated from that. Assuming energy costs of 10 cents per KWh in Houston, TX the total energy cost savings using the new system are shown in **Table 7-1.4 - Energy Cost Savings**. All the calculations for this cost comparison can be found in **Appendix 7**.

Table 7-1.4 - Energy Cost Savings

	<u> </u>
Time Period	Cost Savings
Daily	\$698
Monthly	\$20,707
Yearly	\$248,488

7 – 9 Conclusions and Remarks:

Modification of the mechanical system from an air cooled chiller system to a water cooled chiller with a cooling tower system presents a savings of almost \$50,000 in construction costs, almost \$250,000 a year in energy costs, and no change in construction schedule duration.

While the new system is preferred economically, there are some additional factors that would need to be taken into consideration during construction such as additional structural reinforcing and construction logistics in mechanical equipment placement. Similarly, a cooling tower will require additional consideration throughout its life-time to ensure that the water in the cooling tower is controlled. Considering the building contains two swimming pools, this water maintenance should not be an issue for the owner as they should already have water control systems in place for the swimming pools and the monitoring of the cooling tower water could just be folded into these duties. In conclusion, a water cooled chiller and cooling tower system could be beneficial for the Pearland Recreation Center and Natatorium project.

Section 8: Analysis #3 – Adversarial Project Team Relationships on Design-Bid-Build Projects and other Delivery Methods for Public Projects (MAE Focus Topic)

8 – 1 Problem:

Projects utilizing the traditional Design-Bid-Build delivery method tend to result in adversarial relationships between project team members. As Pearland Recreation Center and Natatorium approaches completion, it seems that the project is unique in that the project team is still working together effectively and the project is setup for an on-schedule, on-budget completion. It appears that this is a great opportunity to analyze some attributes of a successful project team using this delivery method. Design and construction of the project has been seamless. Throughout the design phase there was beneficial owner-designer interaction that resulted in many features of the building being modified to more effectively meet the owner's needs. During construction there were few problems encountered and the project is currently scheduled to be completed well ahead of schedule.

8 – 2 Goal:

The goal of this research is to determine the factors that contributed to the project's apparent success, including factors such as project team selection and contracting method. Conclusions obtained from this research will be targeted at helping owners select successful teams for their upcoming projects. Additionally, this research will potentially identify an ideal delivery method for public projects.

8 – 3 Analysis Method:

- 1) Issue questionnaires to project team members to collect their opinions of why the project was successful, as well as to determine if there were any aspects of the project that could have been improved.
- 2) Compare questionnaire responses to identify commonalities.
- 3) Interview select project team members to identify specific attributes that have contributed to the project's success.
- 4) Study the contract documents in order to locate language that contributed to the project's success.
- 5) Identify aspects of the project team selection process that led to the successful outcome.
- 6) Interview other public project teams using various delivery methods to potentially identify an ideal project delivery method for public projects.

8 – 4 Resources:

- 1) Project team surveys
- 2) Project team interviews
- 3) Project contract documents
- 4) Project team selection method
- 5) Case studies Other Public Projects
- 6) AE 572 Project Development and Delivery Planning course materials

8 - 5 Project Team Analysis:

Analyzing the Pearland Recreation Center and Natatorium's project team began by sending out a survey to the general contractor, EMJ Corporation; owner, City of Pearland; and architect, PBK. Responses were obtained from the general contractor and owner, however after numerous attempts an answer was never received from the architect. These surveys are attached in **Appendix 8**. Upon receipt of the survey responses it became apparent that the project team was working very well together and that all members had a cordial relationship. Additionally, the traditional design-bid-build delivery method was working very well. The City of Pearland was very satisfied with EMJ's work. They were impressed with the management of the company and their effort to achieve a successful project.

After digesting the results from the surveys, phone interviews were executed with the general contractor and architect. These phone interviews developed the concept of 'the ideal delivery method for public projects' - the final result of this research topic. During the phone interviews both the general contractor and owner were strong advocates for the design-bid-build delivery method for public projects such as this. The City of Pearland said they use this delivery method on almost all their projects. This delivery method allocates the risk away from the owner to the other project team members. As a steward of the tax payers, they prefer to do whatever it takes to ensure the community receives a quality project. Consequently on their projects the City prioritizes stewardship of taxpayer funds by valuing quality over an earlier completion schedule

8 – 6 Analysis of Other Delivery Methods on Public Projects:

The City of Pearland is currently also constructing a public service building that will house the police department and other city services. This project is using a design-build delivery method, one of the city's first projects to take this route. City council constrained the project to use this delivery method. The project manager expressed extreme dissatisfaction with the delivery method, citing a lack of checks and balances that normally occur between the general contractor and designer. Since these parties are from the same firm, the owner is no longer the connecting link between these parties and there is much less transparency in the project team's actions.

Another problem that the project manager identified on the project was that there were still design omissions - one of the problems the design-build delivery method is claimed to eliminate. Additionally, construction tends to catch-up to the design and at times has to be put on hold, resulting in schedule extensions and additional costs.

8 – 7 Applications of MAE Concepts:

Analyzing the design-bid-build and design-build delivery methods applied concepts that were learned in a number of graduate level engineering courses, namely AE 572 – Project Development and Delivery Planning, AE 597I – CII Best Practice, and CE 531 – Legal Aspects of Engineering and Construction.

Project Development and Delivery Planning provided knowledge that was critical to understanding how design-bid-build and design-build delivery methods work. Understanding the benefits and drawbacks of these delivery methods allowed for a more effective analysis of the ideal delivery method given the circumstances faced in a public project.

Understanding the legal aspects of construction and engineering was paramount to identifying an ideal delivery method for a public project. Shifting the liability of a public works project away from the owner is a critical legal strategy to consider when selecting the appropriate delivery method.

The Construction Industry Institute's Best Practices course offered an overview of pre-project planning, change management, and equitable risk allocation. These topics enhanced a better understanding of the issues that needed to be considered when selecting a delivery method. Pre-project planning is one of the most important phases of a project as it lays the framework for how a project will be run. This phase can vary greatly based on the delivery method. Change management is also a very important topic, as the number of changes required on a project can have large cost implications. Understanding how a delivery method would affect these changes is important to understand. Again, allocation of risk is a primary concern, particularly for an owner on a public project so it is important to understand how to efficiently shift this risk away from the owner.

8 – 8 Conclusions and Remarks:

Projects using the design-bid-build delivery method are notorious for ending with adversarial relationships between project team members. Pearland Recreation Center and Natatorium has been an exception. Project team members have, in fact, attributed the success of their project to the design-bid-build delivery method. A reason for the project's success using the design-bid-build delivery method has been the City of Pearland's project goal: "Build a quality project on budget". They are not as concerned with completing the project by a specific deadline as they are with controlling costs and producing a project that will serve the community for many years to come.

For complex public projects such as this one, the owner is better served using a design-bid-build delivery method over a design-build delivery method because it effectively allocates liability away from the owner and maintains the beneficial checks and balances between the designer and general contractor.

Section 9: Analysis #4 - Bolted Vs. Welded Glulam Arch Connection

9 - 1 Problem:

In the natatorium of the Pearland Recreation Center and Natatorium a glulam structural system is used, including 14 glulam arches. These glulam arches are connected to the concrete footers using bolts. The bolted connections of these arches were difficult due to the small tolerances of the glulam arches. In hind sight, the contractor suggested that a welded connection would have been more constructible.



Figure 9-1.1 - Glulam Arches (Courtesy of Structural Mag)

9 - 2 Goal:

The goal of this research is to identify the feasibility of using welded connections instead of the as-built bolted connections for the 28 connections (2 per arch) of the 14 glulam arches to the concrete footers.

9 – 3 Analysis Method:

- 1) Determine the cost of using a welded connection.
- 2) Identify the time required to construct a welded connection.
- 3) Compare the cost and time duration for a welded connection with that of a bolted connection.
- 4) Consider the durability of a welded connection versus a bolted connection.
- 5) Research the availability of qualified welders in the geographic area.

9 - 4 Resources:

- 1) Welding contractors
- 2) Pearland Recreation Center and Natatorium project team.
- 3) Glulam contractors
- 4) RS Means Cost Data
- 5) MS Project

9 - 5 Feasibility/Constructability Analysis:

A welded connection would be easier to construct. The greater Houston area has ample availability of qualified welders. However, connecting dissimilar materials might create problems with the weld.

9 - 6 Design Analysis:

As designed, each connection had (12) 1" diameter stainless steel anchor bolts. This is the equivalent of 12 X 3.14 x $(0.5")^2 = 9.42 \text{ in}^2$ of steel connection. To create a weld of equivalent strength, it would be necessary to have 75.36 $(9.42 \text{in}^2/(1/8 \text{in}))$ linear inches of 1/8" weld. This would require about 38 inches of 1/8" weld on each side of the connection.

9 – 7 Cost Analysis:

To analyze the costs associated with this connection, it is necessary to identify what would be removed and added. **Table 9-1.2 – Items Added and Removed per Connection** lists these items.

Table 9-1.2 – Items Added and Removed per Connection

Added	Removed
75" of1/8" weld	(12) 1" Anchor Bolts
Metal plate embedded in concrete footer	(12) holes for bolts
	Careful alignment of columns during erection.
	Extra labor to align anchor bolts with holes during erection.

It can be assumed that the material costs associated with the removal of the 12 bolts and the addition of the plate that would be casted into the concrete footer would cancel each other out and could be ignored. Similarly, the labor costs required to insert the plate in the concrete would likely be less and certainly wouldn't be more than the cost to place and brace the anchor bolts during the concrete pour. It is very difficult to properly brace anchor bolts while pouring concrete.

It can also be assumed that the costs associated with field welding the steel plates would be equivalent to the costs of cutting the bolt holes in the steel and the additional labor that would be required to align the anchor bolts with the holes in the steel plate on the base of the glulam column.

9 – 8 Schedule Analysis:

Analyzing the schedule implications of this connection modification is also important. Assuming a 60" long 1/8" weld could be done in 1 hour, .8 connections could be done per hour. The total of 28 connections would only add 35 man hours. Therefore, the schedule implications of this change could be ignored since it would be no more than the time required to set the anchor bolts prior to pouring concrete and aligning the columns with the bolts during glulam erection.

9 – 9 Conclusions and Remarks:

As designed, the bolted connection between the glulam columns and the concrete footer is very difficult to construct. Modifying to a welded connection would eliminate the tedious process of aligning the baseplate of the glulam column with the anchor bolts without increasing the schedule or cost of construction; in fact, it could possibly result in a cost reduction.

Section 10 - Summary and Conclusions:

After performing design, cost, and schedule analysis on the construction of the Pearland Recreation Center and Natatorium the following conclusions have been reached:

- 1) The structural system in the natatorium should be changed from glulam to structural steel. This change would save over \$600,000 in construction costs and have no effect on the construction schedule, durability and life-cycle costs of the building.
- 2) A water-cooled chiller with a cooling tower mechanical system should replace the air-cooled chiller. This modification would save almost \$50,000 in construction costs, almost \$250,000 in yearly energy costs, and would have no implications to the construction schedule. A downside to this change would be that the cooling tower would require additional maintenance to control the water in the cooling tower, however since the building contains a swimming pool there should already be qualified maintenance staff on site that could also easily oversee the maintenance of the cooling tower.
- 3) For complex public buildings such as the Pearland Recreation Center and Natatorium, a design-bid-build delivery method is preferred over design-build. Design-bid-build allocates financial risk away from the owner and includes the all important checks and balances between team members such as the architect and general contractor. These checks and balances are lost in a design-build delivery method because the architect and general contractor are part of the same firm and the owner is no longer included in the interaction between these parties.
- 4) At the connection between the glulam column and the concrete footers in the natatorium, a welded connection should replace the current, bolted connection. Construction of the bolted connection is difficult as the holes in the column baseplate need to be precisely aligned with the anchor bolts in the footer. A welded connection eliminates this complexity. A welded connection should replace the current bolted connection between the glulam column and the concrete footers in the natatorium.

Making the above modifications to the Pearland Recreation Center and Natatorium would save about \$650,000 in construction costs, significantly reduce yearly energy costs, maintain the construction schedule, produce a higher quality product, and create a more constructible building.

Section 11 - Works Cited

General – All Sections:

Dubler, Craig. Class Lecture. AE-473 Building Construction Management and Control. The Pennsylvania State University, University Park, PA. Fall 2009.

Horman, Michael. Class Lecture. AE 476 Building Construction Engineering - 2. The Pennsylvania State University, University Park, PA. Spring 2009.

Magent, Christopher. Class Lecture. AE 472 Building Construction Planning and Management. The Pennsylvania State University, University Park, PA. Spring 2009.

Analysis #1 - Structural system modification:

<u>2009 RS Means Building Construction Cost Data</u>. Kingston, MA: Construction Publishers and Consultants, 2008.

Concrete Reinforcing Steel Institute, <u>Concrete Reinforcing Steel Institue design handbook, 2008</u>. Schaumburg, IL: Concrete Reinforcing Steel Institue, 2008.

Steel Joist Institute., <u>Standard specifications</u>, <u>load tables and weight tables for steel joists and joists girders: metric and U.S. customary units / Steel Joist Institute.</u> Myrtle Beach, SC: Steel Joist Institute, 1994.

Atamturktur, Sezer. Class Lecture. AE 309 Introduction to Structural Analysis. The Pennsylvania State University, University Park, PA. Fall 2007.

Hanagan, Linda Morley. Class Lecture. AE 404 Building Structural Systems. The Pennsylvania State University, University Park, PA. Fall 2008.

Analysis #2 – Mechanical system modification:

<u>2008 RS Means Mechanical Cost Data</u>. Kingston, MA: Construction Publishers and Consultants, 2007.

McQuiston, Parker, Spitler, <u>Heating, Ventilating, and Air Conditioning</u>. Hoboken, NJ: John Wiley & Sons, Inc., 2005.

Freihaut, James. Class Lecture. AE 310 HVAC Fundamentals. The Pennsylvania State University, University Park, PA. Fall 2007.

Analysis #3 – Project Delivery Systems for Public Projects:

Sweet, Schneier, <u>Legal Aspects of Architecture</u>, <u>Engineering</u>, and the <u>Construction Process</u>. Stamford, CT: Cengage Laerning, 2009.

Thomas, Ellis, <u>Interpreting Construction Contracts</u>. Reston, VA: American Society of Civil Engineers, 2007.

Anumba, Chimay. Class Lecture.AE 597I CII Best Practices. The Pennsylvania State University, University Park, PA. Fall 2009.

Thomas, Randolph. Class Lecture. CE 531 Legal Aspects of Engineering and Construction. The Pennsylvania State University, University Park, PA. Fall 2009.

Horman, Michael. Class Lecture. AE 572 Project Development and Delivery Planning. The Pennsylvania State University, University Park, PA. Spring 2009.

Analysis #4 – Glulam-Footing Connection Detail:

American Welding Society, <u>Structural welding code</u>. Miami, FL: American Welding Society, 2002.

Parks, Mike. Personal interview. March 2010.

Stoltz, Scott. Personal interview. February 2010.

Appendix 3 – Project Overview References

Specialty Contractor List

SUBCONTRACTORS AND SUPPLIERS RECREATION CENTER & NATATORIUM PEARLAND, TX #5085

PROJ. EST.: LOU ARRIETA JUNE 30, 2009

PROJ. MGR.: SCOTT STOLTZ
PROJ. ASST.: MATT LUNA
SUPERINT.: PHILLIP CRISSMAN

SUBCTR	CO NAME	CO ADDRESS	CITY STATE ZIP	CONT F NAME	CONT L NAME	PHONE	FAX	SUBCD
0000-1 OWNER	City of Pearland							0000-1
0000-2 ARCHITECT	PBK Architects							0000-2
0000-3 STRUCTURAL ENGINEER								0000-3
0000-4 MEP ENGINEER								0000-4
0000-5 JOBSITE	EMJ Corporation	4141 Bailey Road	Pearland, TX 77584	Phillip	Crissman			0000-5
5085-0107-030100-00 CONCRETE	MCM Commercial Concrete, Inc.	9518 Grant Road	Houston, TX 77070	Matt	Mabry	713-466-7670	713-466-7683	030100-00
5085-0116-034713-00 CONCRETE DECK	G.L. Nettles, Inc.	41229 Park 290 Drive	Waller, TX 77484	Bryan	Batchman	936-372-9020	936-372-9032	034713-00
5085-0124-042000-00 MASONRY	Easthaven Incorporated	8723 Easthaven Dr.	Houston, TX 77075	Tommy	Grantland	713-944-5361	713-944-2815	042000-00
5085-0101-050000-00 STRUCTURAL STEEL	Apel Steel Corporation	2345 Second Avenue N.W.	Cullman, AL 35058	Hank	Apel	256-739-6280	256-739-6304	050000-00
5085-0105-061800-00 WOOD ROOF DECKING	R.M. Rodgers, Inc.	6352 Akder Drive	Houston, TX 77081-4404	Max	Rodgers	713-666-2229	713-666-2516	061800-00
5085-0144-062200-00 MILLWORK	Victoria Cabinetworks, a subsidiary of Roth Construction, Inc.	2002 Delmar Drive	Victoria, TX 77901	Casey	Roth	361-578-0263	361-578-1271	062200-00
5085-0122-072450-00 LATH & PLASTER	Kenyon Plastering of Texas, Inc.	3401 West 11 th Street	Houston, TX 77008	Patrick	Troy	832-673-6404	832-673-0406	072450-00
5085-0125-075000-00 ROOFING	Admiral Roofing and Sheet Metal, LLC	14521 Old Katy Rd. #224	Houston, TX 77079	E. Eugene	Lauver	281-372-1250	281-372-1252	075000-00
5085-0152-075000-01 ROOFING	Threadgill Sheet Metal Works, Inc.	17515A Huffmeister	Cypress, TX 77429	Wayne	Threadgill	281-373-0016	281-373-0010	075000-01

SUBCONTRACTORS AND SUPPLIERS RECREATION CENTER & NATATORIUM PEARLAND, TX #5085

PROJ. EST.: LOU ARRIETA JUNE 30, 2009

PROJ. EST.: LOU ARRIETA
PROJ. MGR.: SCOTT STOLTZ
PROJ. ASST.: MATT LUNA
SUPERINT.: PHILLIP CRISSMAN

5085-0150-078100-00	Alpha Insulation &	787 Bradfield Rd.	Houston, TX	David	Wright	281-999-7000	281-999-7005	078100-00
FIREPROOFING	Waterproofing, Inc.		77060					
5085-0147-079200-00	Century Roofing	4411 Airline	Houston, TX	Mike	Martin	713-697-8288	713-697-8299	079200-00
WATERPROOFING/	L.L.C.	1	77022					
SEALANTS								
5085-0111-081100-00	Piper-Weatherford	165 Tecon Cove	Buda, TX 78610	Tom	Buyers	512-420-0726	512-420-9367	081100-00
HOLLOW METAL	Co. Distributor –	1						
DOORS/WOOD	Architectural	1						
DOORS/FINISH	Specialties	1						
HARDWARE								
5085-0134-083323-00	ABC Steel	5100 South Willow	Houston, TX	Bob	Casson	713-729-9700	713-729-8611	083323-00
OVERHEAD DOORS	Products Co., Inc.	1	77035					
	dba ABC Doors	1						
5085-0126-084000-00	Ranger Specialized	19031 Aldine	Houston, TX	Omar	Maalouf	281-821-3777	281-821-3785	084000-00
STOREFRONT	Glass, Inc.	Westfield	77073					
5085-0142-090600-00	PC Unlimited, Inc.	211-E Randon Dyer	Rosenberg, TX	Josef	Poncik	281-344-1900	281-344-1922	090600-00
DRYWALL/		Road	77471					
CARPENTRY		1						
5085-0123-093000-00	ASA Carlton, Inc.	5224 Palmero Court.	Buford, GA	Scott	Hester	770-945-2195	770-945-5640	093000-00
CERAMIC TILE		Suite 200	30518					
5085-0118-096433-00	Jellison Inc., dba	1109 Regal Row	Austin, TX 78748	Don	Jellison	800-366-8306	512-282-4070	096433-00
GYM FLOOR/	Jelco	Troo regariton	7.050.1, 174.161.16	20	00		0.2.202 .0.0	000.000
RAQUETBALL		1						
COURT/		1						
SCOREBOARD		1						
SYSTEM		1						
5085-0148-096433-01	Polymer Systems,	17320 E. State Hwv	Buchanan Dam,	Carl	Taylor	512-793-6575	512-793-2779	096433-00
EPOXY FLOOR	Inc.	29	TX 78609	-	· c.y.c.	0.2700 00.0	0.2.700 2.70	200.00
5085-0146-096500-00	Marek Brothers	2115 Judiway	Houston, TX	Mike	Holland	713-681-2626	713-681-6540	096500-00
TILE/BASE/CARPET	Systems, Inc.	2110 oddinay	77018	MIKE	rioliariu	710-001-2020	710-001-0010	000000-00
5085-0143-099113-00	Zaxon Commercial	2116 Kyle Circle	Heath, TX 75032	Bryan	Jobe	214-538-2911	214-206-1146	099113-00
PAINTING	Painting, LLC	2110 Tyle Olide	ricum, rix rodoz	Diyan	0000	211000 2011	2112001110	000110-00
5085-0149-100610-13	Atlas Sign	6411 Airline Drive	Houston, TX	Michael	Johnson	713-699-1121	713-699-2211	100610-13
SIGN WORK	Services, Inc.	OTT THE DIVE	77076	- Inchide	JOHN SOIT	110 030-1121	110 000-2211	100010-10
5085-0112-101100-00	Klinger Specialties	2611 Couch	Houston, TX	Benny	Castro	713-861-4213	713-861-4471	101100-00
BULLETIN BOARDS,	Direct. Inc.	2011 COUCH	77008	Denity	Castro	713-001-4213	/13-001-44/1	101100-00
ACCORDIAN	Direct, inc.		77000				1	
ACCORDIAN			1	1	1		1	I

SUBCONTRACTORS AND SUPPLIERS RECREATION CENTER & NATATORIUM PEARLAND, TX #5085

PROJ. EST.: LOU ARRIETA PROJ. MGR.: SCOTT STOLTZ PROJ. ASST.: MATT LUNA SUPERINT.: PHILLIP CRISSMAN

JUNE 30, 2009

DOORS, POSTER								
CASE, SWINSUIT								
DRYER								
5085-0119-102113-00	Victoria Builder	5301 N. John	Victoria, TX	Dan	Gorfido	361-572-8929	361-572-8992	102113-00
TOILET/DRESSING/	Supply Company,	Stockbauer	77904					
SHOWER	Inc.							
COMPARTMENTS								
5085-0127-102813-00	Tri-Tech Building	4301 Founder's Way	Chattanooga, TN	Ted	Wilkes, Jr.	423-892-7307	423-622-4736	102813-00
TOILET	Products LLC	Drive, Suite C	37416					
ACCESSORIES								
5085-0138-105100-00	Silicon Valley	18522 Bridoon	Cypress, TX	Michael	Lacey	281-550-9975	281-550-9980	105100-00
BENCHES/	Shelving &		77433		_			
LOCKERS/	Equipment Co., Inc.							
SHELVING								
5085-0117-107313-00	Assoc. Bldrs	7106 Mapleridge	Houston, TX	Jeff	Gifford-	713-661-9222	713-661-7022	107313-00
FLAGPOLES	Specialties, Inc.		77081		Weaver			
1	Dba Kronberg's							
1	Flags & Flagpoles							
5085-0133-107310-00	Luebe-Jones, Inc.	9201 Winkler	Houston, TX	Will	Sims	713-944-0988	713-944-5815	107313-00
ALUMINUM	dba Avadek		77017					
CANOPIES								
5085-0132-107313-01	Sign and Awning	4711 Vermont	Fort Worth, TX	Todd	Price	817-926-7270	817-926-7311	107313-01
ALUMINUM SUN	Services, Inc.		76115					
SCREENS								
5085-0141-114000-00	Classic Stainless,	4330 Bronze Way	Dallas, TX 75237	Gus	Macias	214-467-8700	214-467-8705	114000-00
STAINLESS STEEL	Inc.							
5085-0136-114000-01	Manna Distributors,	8708 West Park	Houston, TX	Alan	Nahman	713-977-3318	713-789-7513	114000-01
RESIDENTIAL	Inc.		77063					
EQUIPMENT								
5085-0140-114000-02	Alliance Food	2225 E. Beltline Rd.	Carrollton, TX	Al	Berger	972-820-8352	972-820-6021	114000-02
KITCHEN	Equipment Corp.		75006		-			
EQUIPMENT								
5085-0113-115213-00	Game Court	10901 Circle Drive	Austin, TX 78736	David	Henderson	512-394-0461	512-394-0480	115213-00
GYMNASIUM	Services, Inc.							
EQUIPMENT								
5085-0121-115213-00	Daersed	3645 Fredricksburg	San Antonio, TX	G'Anna	Parkey	210-732-9327	210-732-9347	115213-00
PROJECTOR	Enterprises dba	Rd.	78201		_			

SUBCONTRACTORS AND SUPPLIERS RECREATION CENTER & NATATORIUM PEARLAND, TX #5085

PROJ. EST.: LOU ARRIETA JUNE 30, 2009

PROJ. EST.: LOU ARRIETA
PROJ. MGR.: SCOTT STOLTZ
PROJ. ASST.: MATT LUNA
SUPERINT.: PHILLIP CRISSMAN

SCREENS	Southwest Décor							
5085-0120-122000-00 HORIZONTAL BLINDS	Longhorn Blinds of Austin, LLC	4201 S. Congress Ave., #312	Austin, TX 78745	Ron	Newhouse	512-447-5496	512-707-7315	122000-00
5085-0115-131100-00 SWIMMING POOL	Progressive Commercial Aquatics, Inc.	2510 Farrell Road	Houston, TX 77073	Tim	Phelps	281-982-0212	281-443-1524	131100-00
5085-0137-133416-00 ALUMINUM BLEACHERS	Southern Bleacher Company, Inc.	801 Fifth Street	Graham, TX 76450	Jim	McCain	800-433-0912	940-549-1365	133416-00
5085-0106-142000-00 ELEVATOR	ThyssenKrupp Elevator Corporation	14820 Tomball Pkwy., Suite 190	Houston, TX 77086	Adam	Meyer	713-289-0289	713-896-4660	142000-00
5085-0109-211300-00 FIRE PROTECTION	Firecheck of Texas, Inc.	11500 N. 10 th Street	McAllen, TX 78504-0222	Hal	Wychopen	956-383-3473	956-380-3473	211300-00
5085-0139-212000-00 FIRE EXTINGUISHERS/ CABINETS	PBJ Specialties	7800 Bissonnet Street, Suite 350	Houston, TX 77074	Scott	Harmon	713-774-5701	713-774-5717	212000-00
5085-0110-221000-00 PLUMBING	Johnston Commercial Plumbing, LLC	800 Wilcrest Dr., Suite 150	Houston, TX 77042	Michael	Johnston	713-532-4202	713-532-9906	221000-00
5085-0108-230000-00 HVAC	Fort Bend Mechanical, LTD	13625 Stafford Road	Stafford, TX 77477	Pete	Medford	281-403-4822	281-403-4823	230000-00
5085-0104-260000-00 SITE/BUILDING ELECTRIC	Quinco Electrical of Dallas, Inc.	3016 W. Story Rd.	Irving, TX 75038	Richard	Cavazos	972-258-9105	972-258-9107	260000-00
5085-0129-272000-00 ALARM/ VIDEO/ SECURITY CAMERA	NetVersant Solutions, LLC	9750 W. Sam Houston Parkway N., Suite 100	Houston, TX 77064	Steven	Davis	832-487-1973	832-487-1901	272000-00
5085-0131-280000-00 SOUND SYSTEM	FireTron, Inc.	10101A Stafford Centre Dr.	Stafford, TX 77477	Richard	Phillips	281-499-1500	281-499-3711	280000-00
5085-0130-283100-00 FIRE ALARM/ TELEPHONE	Wilson Fire Equipment & Service Company, Inc.	7303 Empire Central Drive	Houston, TX 77040	Waylan	Gandy	832-310-2469	832-310-2569	283100-00
5085-0102-310600-00	W.T. Byler Co.,	15203 Lillja Road	Houston, TX	Jeremy	Perkins	281-445-2070	281-445-4356	310600-00

SUBCONTRACTORS AND SUPPLIERS RECREATION CENTER & NATATORIUM PEARLAND, TX #5085


PROJ. EST.: LOU ARRIETA JUNE 30, 2009


PROJ. EST.: LOU ARRIETA
PROJ. MGR.: SCOTT STOLTZ
PROJ. ASST.: MATT LUNA
SUPERINT.: PHILLIP CRISSMAN


EARTHWORK/ ASPHALT PAVING	L.P.		77060-5299					
5085-0145-313116-00 SOIL POISONING	Aroco Pest Management, L.L.C.	4321 Pepperbush	Fort Worth, TX 76137	Ron	Muse	817-920-5950	817-847-5754	313116-00
5085-0135-321723-00 PAVEMENT MARKINGS	Arkansas Line Marking, Inc.	10524 Dreher Road	Little Rock, AR 72206	Michael	Griffin	501-888-5052	501-888-1080	321723-00
5085-0151-323100-00 FENCING	Foster Fence LTD	16700 Old Hwy 90 East	Houston, TX 77049	Daniel	Greak	281-456-7273	281-456-0221	323100-00
5085-0114-329000-00 LANDSCAPE & IRRIGATION	Site Landscape Development LLC	762 E. Business 121	Lewisville, TX 75057	Kirk	Boyd	972-221-2205	972-221-2208	329000-00
5085-0103-334000-00 WATER/SEWER	Joslin Construction Company, Inc.	21518 West Wallis	Porter, TX 77365	Ray	Joslin	281-354-5840	281-354-5840	334000-00

Appendix 5 – Project Logistics References


Detailed Project Schedule











Parametric Cost Estimate – D4Profiler


Wednesday, September 16, 2009

Statement of Probable Cost

Page 1

			Pearland Natatorium - Au	ug 2009 - 1X - Houston			
	Prepared By:		Prepared For:				
	,	Moody/Nolan, Ltd. + HOK 1776 East Broad Street					
		Columbus, OH 43203 Fax:		Fax:			
	Building Sq. Size: Bid Date:		Site Sq. Size:	418176			
			Building use:	Recreational			
	No. of floors:		Foundation:				
	No. of buildings:	1_	Exterior Walls:				
	Project Height:	52	Interior Walls:	GYP			
	1st Floor Height: 1st Floor Size:	90000	Roof Type: Floor Type:	MET TER			
	let i looi Size.	30000	Project Type:				
vision				Percent	Sq. Cost	Amount	
	Bidding Requiren	nents		2.48 2.48	2.58 2.58	389,439	
	Bidding Requ	liements				389,439	
	Concrete			5.10	5.30	800,197	
	Concrete			5.10	5.30	800,197	
	Masonry			17.25	17.95	2,709,962	
	Masonry			17.25	17.95	2,709,962	
5	Metals			15.96	16.60	2,506,241	
	Metals			15.96	16.60	2,506,241	
	Wood & Plastics			0.60	0.62	93,806	
	Wood & Plast	itos		0.60	0.62	93,806	
,	Thermal & Moistu	ire Protection		8.21	8.54	1,288,653	
	Thermal & Mo	oisture Protection		8.21	8.54	1,288,653	
	Doors & Windows	8		3.03	3.15	475,665	
	Doors & Wind			3.03	3.15	475,665	
	Finishes			7.29	7.59	1,145,575	
	Finishes			7.29	7.59	1,145,575	
)	Specialties			0.82	0.85	128,865	
	Specialties			0.82	0.85	128,865	
	Equipment			0.36	0.38	56,852	
	Equipment			0.36	0.38	56,852	
,	Furnishings			0.39	0.41	61.590	
	Furnishings			0.39	0.41	61,590	
	Special Construc	tion		12.39	12.89	1,945,298	
	• •						
	Special Cons	struction		12.39	12.89	1,945,298	
ı	Conveying Syste	ms .		0.36	0.37	55,905	
	Elevators			0.36	0.37	55,905	
5	Mechanical			16.54	17.21	2,598,132	
	Mechanical			16.54	17.21	2,598,132	
	Electrical			9.23	9.60	1,449,261	
	Electrical			9.23	9.60	1,449,261	
otal Bull	iding Costs			100.00	104.05	15,705,442	
2	Site Work			100.00	2.59	1,081,100	
	Site Work			100.00	2.59	1,081,100	
otal Non	n-Building Costs			100.00	2.59	1,081,100	
							_
tal Droi	Ject Costs					16,786,542	

RS Means Data for Natatorium



RS Means Data for Recreation Center

COMMERCIAL/IN	IDUSTR	IAL/	M.	310	G	ymane	ısivn	1			
						3	150	98K	1.683	22.8	6
-								1		63,	300
Casts per square ioo	DESCRIPTION OF THE PARTY.	CONTROL	12000	16000	20000	25000	30000	35000	100000	(45000	50000
Exterior Wall	S.F. Area		440	520	600	700	708	780	841	910	979
	L.E. Perine	a reporter		147.75	43.35	40 šč	\$5.00	132	1575	31.45	102,30
Relationate Countrie Book	Lam Wasd		54,90	157.75	155,73	50.35	45.0	141.95	Ve2 35	41.25	140,40
1.5en/dc 560s	FI, I, SWMT		94.60		0.000	:0.40	152.55	149,95	- Air	15.75	12850
max decir with	-w-Word		26.75	2,36	(0.15	70.22	leZot	129.75	dea	(135.55	134.70
Tunner de deck fazikus	€gd Sea 1	- SSE 187	162.7	66.46	174.95	Discholar.	III - Day Soul	E 40	80,70	125.17	11201
charieties (1	tea Sea		\$3.59	5422	10.4	Q2.00	SHEW.	<.10	1998	85.65	135.26
10/4	chpc.985	2.62	18,500	15/05	91.90	39	350 NO.	1,10	- Control		
Ponger (42), April Turini	2:100.7		0,50	1.40	325	1 8	230	3.40	25	1.05	1.15
Avening the seed of Crease	3e 1 %		553	6.60	9.82	820	10	5,63	0.55	0.50	356
	1.4		ke	ment-No	App tocals						
The Line of Congression control of the finishing the finishing the control of the Congression of the Congres	Repentes con pla	illet See See See See See See	\$ Gast 15-16 215-20 240-30 25-20 11-00	pro Panada 1 1	Description when, the Lader Sound San Appin	d. single tite. 2 ten, 50° o 5 ten, course bedeauth of see eq. 250 wide	67 ct 72' -72' lord -ctar; 	31,	- 1	Und Transp Transp Transp Lh Bods Ead	\$ Set 12: -319 107: IA) 63: E3,30 21 -53,30 2,00
Oyan Mari Enclosely incominal English		3.E 3.E 3.E 3.E	5,82 6,85 9,65 6,65		americans Lead b	e, chiling or w To mper tighting, 25 v ettery oppinson		Celaica		Ead fort fact body	303 232 365
Fig. 72° well profit I' wiest net nets		3.6	Die.		15003						

Data for Estimate Location Adjustment

STATE/ZIP	CITY	Residential	Commercial	STATE/2IP	CITY	Residential	Commen
NORTH BAKOTA (556 557 558	CONTO) Devision Mi of Velision	% #1 %	84 87 86	PENNSYLVANIA (C 190191 193 194 195196	OMTO: Prisidatina West-frestor Norratow Reading	1.46 1.40 5.09 5.57	1 07 1 00 1 00
OHIO 430 433 434 434 436 437-438	Calumbus Marion Taletto Zanesville	.90 .89 1,00 88	% #4 46 29	PUENTO RICO (02) RHODE ISLAND	Sin Jun	,3g	8.
435 440 441 44-44	States with Lords General Astro	.93 .98 L.C1	90 96 - 86	DA DA SOUMI CAPOLINA	Newport Providence	1.06 1,06	1.00
444.44* 440.447 145.448 150.457 451.457 453.457 453.457 453.457	Yu.ngstowa Dearn Warshed Hamilton Carinari Dearn Sping still Chitethe	.88 .56 .63 .63 .62 .72 .72	96 84 22 92 1 92 1 92 1 92 1 92 1 92 1 92 1	293-292 293 291 295 295 297 297 298 299	Columba Spatianoung Charlestor Florence Greenville Roos Hi Akan Beaufort	.64 .68 .67 .80 .53 .52	80 50 50 50 50 50 50 50 50 50 50 50 50 50
457 453 DKLAYCMX	Atrens Line	ð	.28 .52	SCUTH DAKOTA 870671 574	Socia Falls Waterbow	72	.83. 08.
730 733 73° 735 736 737	Calabora Gy Actinos Gueta Gueta Gueta	.79 .78 .90 .76 .76	23 23 23	879 874 878 878 578 577	Wichell Aberdoor Pierre Woorlege Rapid City	79 76 77 77 77 75 78	.80 .87 .81 .70
7.88 7.89 7.40 74. 7.45 4.44 4.86 4.7. 4.9. 4.9. 4.9.	Poddwst Starte Tuto Nam Natioges Natiog Natiog Natiog Natiog Natio	88 75 75 75 87 77 87 77 87	09 190 190 191 191 190 191 191 191 191 1	10 TESSEE	Surviville Chamanooga Vernodis Longon Lify Sone alle Mathematic Bistomatic Comments	84 281 70 70 70 70 70	.80 .96 .80 .90
000 F.CK 9,475,27 9,73 17,7 17,7 9,75 9,75 9,75 9,75 9,75 9,75	enthra fact inject Mringe Obrach the Le d Locatean	35 35 35 36 36 37	LTL LTC LTC LTC LTC 27	TEXA3 100 101 101 102 103 103 103 103 103 103 103 103 103 103	Mik nev won bear Delen Geerwie Tetarsten Lingerw Tyle Prestne	25 26 36 5 5 5 7 7 7 8 8 8 8 8 8 8 8 8 8 8 8 8 8	76 25 73 78 74 30
PENNSYLVANIA 100-02 103 104 105 106 107 108 108 109	Filtrough Westmolth Hoother Fedfred Geensturg Indias Unios	95 95 90 87 45 91 84 89	95 36 95 95 96 96 97	756 750 751 753 754 754 755 755 755 755	Early For War, h Der kon Wei, Ja Falls Eastered Tomole Week Brownwood San Chipso	Al Al た り た の た の の の の の の の の の の の の の の の	26 27 28 27 27 27 27 27 27 27 27 27 27 27 27 27
69 61 62 62 63 64 67 67 67 77 77 77 77 77 77 77 77 77 77	Johnstown Outer Phay Desire Run Desire Run Desire Run Ing Of Siry Ete Runfund State College Welson Understand Run	**************************************	#5555 #5255 #5555 #5 # # # # # # # # # #	770772 770 774 776 776 778 779 780 761 763 763 764 765 763 764 765 767 768 767 768 769 769 769 769 769 769 769 769	Hoseway Marcha Marcha Gaveston Broan Victors Lanco Sar Antono Corpus Classi NoAlen Acido Del Ro Underso Labord Amenic Crisco Amenic Acido Acido Amenic Acido	85 89 83 83 77 77 80 75 75 80 86 84 74 74 75 73	382 312 312 312 312 312 313 314 315 315 315 315 315 315 315 315 315 315
186 186	front use Dovestown	30 25	105	940941 947 44 943	Set Laber City Ogden Logar	3: 78 79	8: 8: 8:

Detailed Structural System Cost Estimate Hand Take-Offs

5ir	
	Recreation Center 1054
	Strudural System Hand Talke-Off
	From Gridlines G-5/1-4
1)	Caissons: (2) @ 48"dia, (2) @ 42"dia and (2) @ 30"dia. All 12 length
	Concrete: 2x5.58 CYD
	2x5.58 CYD 2x4.27 CYD 2x2.18 CYD Total Concrete: 24.06 CYD - 3000ps;
Reins.	Steel & HI 6: 8-#10
,	6x8x12'=576lft of #10
	Ties: 2- #3@18" => 8 ties (15)
	(2) - 12.56' = 7(2)(8)(12.56) = 201'
	(7) - 10.99' = 7(7)(8)(10.99) = 176'
	(2) - 7.85' = 7(2)(8)(7.85') = 126'
	So: #3: 0.37657 #10: 4.303451
	503'x0.376 1/st _ 0.1 Ton
	576' x 4,303'9/5> = 1.24 Ton Zaco'b/ton = 1.34 Ton of Rebac

	284
2)	Factings: (5) 2'x2'x2' FJ6s
	Concrete: 40 = 1.48 CYDs -3000psi
	Farming: 16 SFCA X5= 805FCA
	Steel: 2-#7 T+B
	5x(4)(2) = 40-lst 05#7
	#7° 20044 1/2
1	40x2,04420.04Ton
3)	Grade Beam:
	Total Length: 73.5'
	Concrete: 2'x 1.1' x 73.5' = 161.7 CF
	Forming: 4'x 73.5'= 294 SFCA
	Steel: 2-#7 T+B
	#3 Stillups @10" ac = 29457 8#7
	6.2' × 88 = 546' of #3 0.376×546+294×2.044 = 0.403Tons
	2000

	3054
4) Slab-on Grade: Area = 27.25 x 46.25'=	1260 SF
Concrete: 1260 SF x 5/12 = 525 = 10	7.44 CYD
Vapor Barrier: 1260 SF	-3000psi
5" Edge Form: 27.251	
Steel: #3 @ 14" O.C. EW L71.17'	ar
27.25 + 46.25 = 24 +40 = 64lft of	F#3
0.376×64 = 0.01 Ton	
Finishing: 1260 SF	
5) Elevated Slab: 1260 SF	
Concrete: 1260 ×3/12= 11.67 CYD-	350psi
9/16" Deck: 1260 SF	,
3" Paux Stop: 27,2515	
Finishing: 1260SF	
Reinforcing: 1260SFOF 6×6 WW	γÞ

	*Note: These are for entire bldg. (Rec Center)
*6)	Roof Deck: 319×181=57,739 SFx1032-59,645SF 74" Tectum E Roof Deck: 59,645SF
*7)	Wood Trusses: 68 LHSP@ 5'o.c
8)	Steel:
C 6	Columns: (4) TS 10×10×36" - 27' Beams: (2) W 27×84 - 27.25' (1) W 16×26 - 45.5' (1) W 30×90 - 27.25'
	Floor Joists: (11) 78 LH 12 - 45.5'

Detailed Structural System Estimate

Item	Units	Quantity	Labor (\$/unit)	Material (\$/unit)	Equipment (\$/unit)	Total (\$/unit)	Labor	Material	Equipment	Total	RS Means
					Caissons						
9 Bell diameter, 48" shaft	EA	5.00	\$975.00	\$450.00		\$1,430.00	\$4,875.00	\$2,250.00	\$5,500.00	\$12,625.0	Page 592
					Footings						
Concrete - 3000 psi	CYD	1.48	\$33.50	\$101.00			\$49.58	\$149.48			2 Page 64, 65
Concrete Forming	SFCA	80.00	\$2.93	\$0.70			\$234.40	\$56.00			
Reinforcing Steel	TON	0.04	\$680.00	\$1,475.00		\$2,280.15	\$27.20	\$59.00	\$5.01	\$91.2	1 Page 59
					Frade Beams	A CONTRACTOR OF THE PARTY OF TH	-		and the second	1500000	and the same
Concrete - 3000 psi	CYD	6.00	\$12.05	\$101.00			\$72.30	\$606.00		\$704.6	4 Page 64, 65
Concrete Forming	SFCA	294.00	\$2.93	\$0.70			\$861.42	\$205.80			2 Page 46
Reinforcing Steel	TON	0.40	\$890.00	\$2,440.00	\$0.00	\$3,330.00	\$358.67	\$983.32	\$0.00	\$1,341.9	Page 58
		- 0		S	lab-On-Grade						
Concrete - 3000 psi	CYD	19.44	\$16,70	\$101.00			\$324.65	\$1,963.44	\$118.58	\$2,406.6	7 Page 64, 65
Concrete Finishing	SF	1260.00	\$0.18	\$0.00			\$226.80	\$0.00			Page 66
5" Concrete Edge Form	LF	27.25	\$2.02	\$0.38	\$0.00	\$2.40	\$55.05	\$10.36	\$0.00	\$65.4	Page 47
Vapor Barrier	SF	1260.00	\$1.15	\$1.20	\$0.00	\$2.35	\$1,449.00	\$1,512.00	\$0.00	\$2,961.0	Page 192
Reinforcing Steel	TON	0.01	\$620.00	\$1,475.00	\$0.00	\$2,095.00	\$6.20	\$14.75	\$0.00	\$20.9	5 Page 59
				(Salestanie)	levated Slab	100000000			200		
Concrete - 3500 psi	CYD	11.67	\$15.50	\$104.00			\$180.89	\$1,213.68	\$65.94	\$1,460.5	Page 64
Concrete Finishing	CYD	1260.00	\$0.18	\$0.00			\$226.80	\$0.00			Page 66
3" Pour Stop	SF	6.81	\$3.33	\$1.47	\$0.00	\$4.80	\$22.69	\$10.01	\$0.00	\$32.7	Page 44
6 X 6 WWF Reinforcing	CSF	12.60	\$24.50	\$32.50			\$308.70	\$409.50		\$718.2	Page 60
9/16* Metal Decking	SF	1260.00	\$0.36	\$1.72		\$2.11	\$453.60	\$2,167.20	\$37.80	\$2,658.6	Page 124
					teel Columns						
TS 10x10x3/8"x16"	LF	6.75	\$51.00	\$1,625.00			\$344.25	\$10,968.75			B Page 110
TS 8x8x3/8"x14"	LF	1.93	\$49.00	\$880.00		\$964.00	\$94.50	\$1,697.14	\$67.50	\$1,859.14	4 Page 110
					Steel Beams						
W 27x84	LF	54.50	\$2.96	\$139.00	\$1.58	\$143.54	\$161.32	\$7,575.50	\$86.11	\$7,822.9	3 Page 114
N 16x26	LF	45.50	\$2.44	\$43.00	\$1.74		\$111.02	\$1,956.50		\$2,146.6	9 Page 114
W 30x90	LF	27.25	\$2.94	\$163.00		\$167.50	\$80.12	\$4,441.75	\$42.51	\$4,564.3	8 Page 114
		177.000			Floor Joists	i waxaa					
28LH12	LF	500.50	\$1.96	\$28.00	\$1.12	31.08	980.98	14,014.00	560.56	\$15,555.54	4 Page 121
***************************************			Tot	al Structural System	Cost":					\$80,719.45	
				Total Cost/SF*:						\$32.03	-

				enter Structural System	Except Roof Deck a	ind Trusses)		
Structural System	SF	63300	\$32.03					\$2,027,499.00 NA
		///	COLUMN	Roof De	ck			
7 1/4" Tectum E Roof Deck	SF	59645.00	\$3.50	\$7.00	\$0.00	\$10.50 \$208,757.50 \$417,515.00	\$0.00	\$626,272.50 NA
	200000		- Chillord	Wood Tru	2582			
130' LHSP Wood Joist Trusses	EA	68	\$500.00	\$1,500.00	\$500.00	\$2,500.00 \$34,000.00 \$102,000.00	\$34,000.00	\$170,000.00 NA
			Total Recreation	Center Structural System	n Cost:			\$2,823,771,50

'Note: This cost does not include the Roof Deck and Wood Trusses

tem	Units	Quantity	Labor (\$/unit)	Material (\$/unit)	Equipment (\$/unit)	Total (\$/unit)	Labor	Material	Equipment	Total	RS Means
10111	Office	addining	Educit (# drint)	material (# dint)	Caissons	Trocal (4:arm)	Edoor	material	Equipment	Total	Into mount
7 Bell diameter, 48* shaft	EA	5.00	\$975.00	\$450.00		\$1,430.00	\$4,875.00	\$2,250.00	\$5,500.00	\$12,625.00	Dage 502
Deli diameter, 45 shart	EA	0.00	\$975.00	3450.00	Footings	\$1,430.00	34,010.00	\$2,250.00	30,000.00	\$12,020.00	rage 332
	-										
Concrete - 3000 psi	CYD	1.48	\$33.50				\$49.58				Page 64, 65
Concrete Forming	SFCA	80.00	\$2.93				\$234.40	\$56.00			
Reinforcing Steel	TON	0.04	\$680.00	\$1,475.00	\$125.15	\$2,280.15	\$27.20	\$59.00	\$5.01	\$91.21	Page 59
					3rade Beams						
Concrete - 3000 psi	CYD	6.00	\$12.05	\$101.00	\$4.39	\$117.44	\$72.30	\$606.00	\$26.34		Page 64, 65
Concrete Forming	SFCA	294.00	\$2.93	\$0.70	\$0.00	\$3.63	\$861.42	\$205.80	\$0.00	\$1,067.22	Page 46
Reinforcing Steel	TON	0.40	\$890.00	\$2,440.00	\$0.00	\$3,330.00	\$358.67	\$983.32	\$0.00	\$1,341,99	Page 58
				S	lab-On-Grade						
Concrete - 3000 psi	CYD	19,44	\$16,70	\$101.00	\$6.10	\$123.80	\$324.65	\$1,963.44	\$118,58	\$2,406.67	Page 64, 65
Concrete Finishing	SF	1260.00	\$0.18	\$0.00	\$0.00	\$0.18	\$226.80	\$0.00	\$0.00	\$226.80	Page 66
5* Concrete Edge Form	LF	27.25	\$2.02	\$0.38	\$0.00	\$2.40	\$55.05	\$10.36	\$0.00	\$65.40	Page 47
/apor Barrier	SF	1260.00	\$1.15	\$1.20	\$0.00	\$2.35	\$1,449.00	\$1,512.00	\$0.00	\$2,961.00	Page 192
Reinforcing Steel	TON	0.01	\$620.00	\$1,475.00	\$0.00	\$2,095.00	\$6.20				Page 59
			Tol	tal Structural System	Cost*:					\$32,114.60	
				Total Cost/SF1:						\$12.74	

Natatorium Structural Costs (Except Glulam Materials											
Structural System SF 41817 \$12.74								\$532,911.20	NA .		
A HEALTH STORY	Glulam										
Glulam Framing	SF	41230.00	\$7.34	\$15.90	\$0.00	625 QE	9202 405 00	\$655,725.00	\$0.00	\$1,070,000,00	NA
Wood Deck	SF	41230.00	41.41	\$2.71	\$0.00	\$20.90	\$302,405.00	\$111,790.00	\$0.00	41,410,000.00	NA
	Trial Material Property Control Contro										

'Note: This cost does not include Glulam Product

General Conditions Estimate

General Conditions Estimate

General Conditions Estimate										
Item	Unit	Unit Cost	Quantity	Total Cost						
General Contractor Personnel (RS N	leans Page 10)									
Admin/Secretary	MTH	\$3,200.00	5	\$2,555.00						
Assistant Superintendant	MTH	\$7,600.00	13	\$98,800.00						
Superintendant	MTH	\$8,227.00	13	\$106,951.00						
Project Engineer	MTH	\$7,145.00	13	\$92,885.00						
Project Manager	MTH	\$8,346.00	6.5	\$54,249.00						
Senior Project Manager	MTH	\$8,660.00	1.5	\$12,990.00						
Temporary Facilities (EMJ Corporat										
Jobsite Office	MTH	\$486.67	15	\$7,300.00						
Temporary Toilets	MTH	\$513.33	15	\$7,700.00						
Barricades	MTH	\$66.67	15	\$1,000.00						
Construction Signs	MTH	\$60.00	15	\$900.00						
Dumpsters	MTH	\$133.33	15	\$2,000.00						
Temporary Utilities (EMJ Corporatio	n)									
Temporary Electric	MTH	\$1,000.00	15	\$15,000.00						
Temporary Water	MTH	\$46.67	15	\$700.00						
Temporary Telephone	MTH	\$646.67	15	\$9,700.00						
Cleaning (EMJ Corporation)										
Misc. Clean-up	MTH	\$233.33	15	\$3,500.00						
Site Clean-up	LS	\$2,500.00	1	\$2,500.00						
Final Building Clean-up	LS	\$37,000.00	1	\$37,000.00						
Miscellaneous (EMJ Corporation)										
Trash Removal	MTH	\$966.67	15	\$14,500.00						
Blueprints	LS	\$3,500.00	1	\$3,500.00						
Safety (Drug Testing, Equipment, etc.)	LS	\$1,500.00	1	\$1,500.00						
Hand Tools	LS	\$6,000.00	1	\$6,000.00						
Engineering and Layout	LS	\$2,000.00	1	\$2,000.00						
Incidentals	LS	\$4,000.00	1	\$4,000.00						
Insurance	% of Contract	\$16,786,542.00	3%	\$503,596.26						
Bonds	% of Contract			\$335,730.84						
0&P	% of Contract	\$16,786,542.00	4%	\$671,461.68						
Total	1			\$1,998,018.78						

Pearland Recreation Center and Natatorium – Final Report
Appendix 6 – Analysis #1 (Natatorium Structure) References

Natatorium Structural System Design Calculations Natatorium Structural System Lalus -Wind: 120mph for 30 sec gust, exp. c, Imp. Factor of 1.15 Roof Slope = 3:12 Sample Boy J1 4016/SFx4=160 => Use a 14K1 which can support up to 180 & 25'spans We will need 36 of theseper bay=Total of these per bay=Total of the per b B1 | Treat joist loads as uniform load:

160 1/4 x 75' = 4000 1b/4' = 1000 # => Use a 1045LH 22 which we will need atotal of 14 of these. (our span is only 140')

Concrete Columns:

Axial Load:

401b/sf x 70'x 25'= 70,000 column.

This would use a 10"x10" square concrete column with 4-45's.

We would need 28 of these columns

STANDARD ASD LOAD TABLE

OPEN WEB STEEL JOISTS, K-SERIES

Based on a 50 ksi Maximum Yield Strength Adopted by the Steel Joist Institute November 4, 1985 Revised to November 10, 2003 - Effective March 01, 2005

The black figures in the following table give the TOTAL safe uniformly distributed load-carrying capacities, in pounds par linear toot, of ASD K-Series Steel Joists. The weight of DEAD loads, including the joists, must be deducted to determine the LIVE load-carrying capacities of the joists. Sloped parallal-chord joists shall use span as defined by the length along the slope.

The figures shown in RED in this load table are the nominal LIVE loads per thear foot of joist which will produce an approximate deflection of 1/380 of the span. LIVE loads which will produce a deflection of 1/240 of the span may be obtained by muniplying the figures in RED by 1.5. In no case shall the TOTAL load capacity of the joists be exceeded.

The approximate joist weights per linear loct shown in these tables do not include accessories.

The approximate moment of inertia of the joist, in inches^a is; $I = 26.767(W_{\rm H})(L^2)(10^{-3})$, where $W_{\rm H} = {\bf RED}$ figure in the Load Table and $L = ({\rm Span} - 0.35)$ in feet.

For the proper handling of concentrated and/or varying loads, see Section 6.1 in the Code of Standard Practice for Steel Joists and Joist Girders.

Where the joist span exceeds the unshaded area of the Load Table, the row of bridging nearest the mid span shall be diagonal bridging with botted connections at the chords and intersections.

ASD

Joint		Koks	_	-	-	Vield St	0.500	700.00	100000	12200	20000	1000	2000	10.00	1947	16809
Designation Depth (n.)	6		12K1	12K3	1245	1481	14K8	14K4	1485	16403	1643	1684	16K5	16K5	184.7	16 16
Approx. V/s	7.7		- /	-			1			100	110000	37.55		2.5	7.5	
(list./ft.)	5.1	W	5.0	5.7	7.1	155	8.0	87	7.7	5.5	6.3	7.0	7.5	8.1	a.e	10.0
Epan (fl.)						4										
	550															
9	660															
10	550	550									-				-	
11	480	550		-	-		-	-	-			-	_	-		
12	377	542 650	650	565	860	-1-					_	1			_	-
	286	470	550	560	550			1505		-						
13	225	358	550 510	510	510											
14	394 178	412 208	500 425	550 460	350 463	5 00	550	550	550							
15	281 145	358	284	543 428	650 434	61	550 907	560 507	560 507							
16	246	313	380	476	350	448	550 467	550 467	550 467	550	550	550	560	650	950	550
17	1100	277	335	420	650	336	495	560	650	512	550 550	550	200.0	550 550	550	550
18		108 248	234	374	306	329	441	530	550	468 456	528 500	528	550	538 650	550	560
19	_	134 221	269	335	454	216	365	475	4001 650	408	455	547	490 550	490	490 550	490 550
20		199	241	907 302	268 450	284	267	428	525	347	386	452	455 550	455 550	560	455 560
21		97	142 218	277	230	197	248	287	847	207	330	308	426	426	425	429
		1000	123	150	186	170	322	895	476 298	333 255	285	333	508 279	548	560 406	580 405
22			189	S49 130	837 172	234	293	353 215	432 250	903 222	247	406	450	498	560	560
23			181	227	308	121	265 160	300	395	977 190	216	571 580	418	455 307	907 389	560
84			166	808	282	159/	245	206	852	254 170	283	340	384	410	465	560
25			CONT.	- 10	-	180	225	272	334	234	260	221	358	384	290 425	514
25					-/	100	124 209	851	326	210	240	290	219 328	355	283	474
27		-		-		154	198	238	288	200	148	178 288	194	329	366	439
25						.70	98	216	139	119	132	155 240	177	185	208	246
				200		145	00	100	126	185	207	138	281 155	308 165	1990 1990	408 220
89										1/3 35	193	232	261	285	317	380
30										161	180	216	126	268 197	151	255
31							-			151	185	800	229	249	277	332
32				-						142	198	101	214	293	137	311



VULCRAFT LOAD TABLE SUPER LONGSPAN STEEL JOISTS, SLH-SERIES

Based on a 50 ksi Maximum Yield Strength

ASD

Jost Descusion	Approx Wt. In Lts. per Linear Ft. (Josts Only)	Depth In Inchas	Safe Load In Libs. Between						Q.	CAR SE	en in	EET*	1						
			96-128	129	132	135	138	141	144	147	150	155	160	165	170	175	180	185	19
9681.417	52	96	70,000	540	517	495	474	456	438	421	405	380	357	235	316	296	281	206	200
		3555		389	363	339	318	296	280	263	247	224	204	188	170	158	143	132	12
96SL-118	59	.96	78,800	608	583	553	535	513	493	475	457	430	406	261	360	240	322	305	28
				443	413	385	352	340	319	300	282	256	232	212	194	178	168	150	13
96SL 118	66	98	94,200	727	697	667	639	611	585	561	539	505	474	445	419	396	373	353	33
			1	502	469	438	410	385	361	340	320	290	264	241	220	202	186	171	15
96SLH20	74	08	105,000	834	789	784	722	691	662	635	810	571	536	504	175	448	423	400	37
	1000			569	531	495	485	436	409	386	362	329	299	272	249	229	210	193	17
98SLH21	93	36	133,000	1027	892	940	900	664	829	797	786	719	675	635	598	564	533	504	47
				698	652	613	571	535	503	478	445	404	867	386	306	281	258	238	22
9651,422	102	96	149,000	1150	1108	1087	1029	991	957	921	998	832	782	738	894	658	620	587	55
2028-XC1	7675	405-23		811	757	708	683	622	584	548	517	489	426	389	355	326	300	276	25
			104-137	138	m_2	144	147	150	155	160	165	170	1/5	180	185	190	195	200	20
1045LH18	59	104	76,800	664	932	512	499	472	144	418	396	374	354	335	318	302	287	273	26
	22.50		- and the	426	400	375	353	332	301	274	250	229	209	192	177	164	152	140	13
1043_H19	67	104	93,400	674	647	622	599	574	538	507	479	452	427	404	383	364	346	325	31
	View			484	450	628	401	377	342	811	284	290	238	218	201	186	172	160	14
1045_H20	75	104	105,000	764	732	714	688	661	621	583	548	516	467	460	435	413	391	371	35
				548	510	483	453	427	387	852	321	293	269	247	228	210	196	181	16
104S_H21	90	104	132,000	966	917/	881	847	613	763	718	677	539	604	571	541	514	488	464	44
7	1	25.00	mulia	678	5	593	558	525	476	433	395	361	331	301	230	269	240	222	20
104S_H22	104	100	148,000	1023	1034	988	956	984	883	830	793	738	698	660	626	594	564	536	51
_	1636	1000		783	734	689	649	610	553	508	459	420	385	353	326	301	278	258	24
104S_H23	109	104	163,000	1181	1141	1096	1052	1009	945	287	834	785	741	700	662	628	595	565	53
				619	768	721	679	636	5/8	526	490	439	403	370	341	315	291	2/0	20
1121.51-119	67	443	112-146	147	150	155	160	165	170	175	180	185	190 362	196	200 345	205	210	215	22
112LSM19	6/	112	91,900	623	600	584	530	500	472	446	424	102	225			329	214	300	28
112SUH20	78	112	104,000	466 710	439 688	398 649	352 610	575	302 543	276 514	255 488	234 483	216 440	200 417	186 398	172 379	160 381	149 345	14
11230120		31.5	109/3000	528	497	450	410	374	342	313	288	266	246	227	210	195	181	169	15
112SLH21	91	112	131,000	891	858	805	757	713	673	637	603	572	543	516	491	488	446	126	40
Tractificati	91	218	tations	050	612	000	034	400	421	386	355	327	301	2/9	256	240	224	208	19
112ELF22	104	112	147.000	000	967	913	871	824	778	736	637	661	628	596	588	541	516	492	47
	1,		141.000	756	721	644	586	535	489	449	412	380	350	324	301	279	260	242	22
112ELH23	110	112	162,000	1102	1067	1012	939	901	848	800	756	716	679	644	612	582	554	528	50
	5005	1000		790	744	674	613	560	512	469	431	397	367	340	315	292	272	253	23
112SLH24	iai	112	192,000	1304	263	1199	1139	1074	1014	359	909	862	810	778	741	706	673	642	61
	100		1000	957	901	817	743	678	620	569	523	481	444	411	381	354	329	307	28
K	L		102-164	165	170	175	180	185	190	195	200	205	210	215	220	230	235	240	
120SLH20	77	120	98,900	597	564	532	505	479	456	434	414	395	376	359	344	329	315	302	29
William X	750	250.00	The sales	430	393	361	332	306	282	261	242	225	209	195	182	170	159	49	14
120SU-121	92	120	123,000	748	706	667	682	500	570	542	516	400	459	449	428	410	392	376	26
			1000	530	485	444	409	376	347	321	298	277	259	243	224	203	195	184	17
120SU 22	104	120	141,000	856	8.9	770	729	692	658	6226	506	568	542	517	495	473	453	434	41
-0000000000	2000	Steve	100 m	818	564	516	475	438	404	374	347	322	300	279	261	244	228	214	20
120SLJ 23	111	120	156,000	943	986	848	804	768	725	690	Fci7	626	596	563	545	519	496	475	45
X1500 250.00	15.60	15,100	-	844	590	541	497	458	428	391	363	338	313	282	272	255	238	224	21
120SLF24	-32	120	185,000	1117	1062	1003	960	902	968	816	777	741	706	675	645	617	591	566	54
	200		1	781	715	655	603	555	512	474	440	408	330	351	330	303	289	271	25
120SUF25	- 52	120	212,000	1284	1218	1162 768	1092	1036	984	996	691	860	811	775	741	703	678	650	82
				915	837										387	362			29



200	T	.0	**********	121	500 500		ttt	i ki	ŽŽ	133	i i i	eşt.	- - - - -	- 5		18
here symmetries in 4 faces	- R		AHHA	251	552		ত ইবাও	1. 10 V 12 KS 60	grand State	286	151	Table 1	288485	- 2		September of the continue of the Continue of the September of the Continue of
rica m	Mak	N.	발생품인입	13 (N) (E)	3 12		888	424	847·	93±	18.0	209	226444	R)		5 N L
4 fuent	Max Cap	97,	daesa	XXX	41 1813		(88 8	23%	882	\$1.5 P	ŧŧ.	988	RHEGGE	23		
1.4	2	dit.	ed@#¥	i di di	625	501	228	87.3	228	S 888	WE.	6 2 61	94F6E8	ā		House of the terror of the Colonia of the Section Sec
	45	Ħ	#252Z	205	1100	SQUARE .	ann Mar	enk	888 888		188	SAE	885828	U:		H 1
	25%	4.7	RESEW	268	225	TIED	102	400	283	TED C	ā.	ARE:	ggalle	5		E 6 1
	5.	3	esser.	335	交额等	COLUMNS	E	200	egs	01	188	385	SEKETS	5		0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
	00%A	gir.	u u u u u	205	245		323	īr.	522		15 15 15 15 15 15 15 15 15 15 15 15 15 1	388	gagagá	9		an sales su
	34	gt.	295.1	222	585	12" × 1	463	r Tran	Død	14 × 1	132	838	SERBEE	21		AS C SAC
M. in	7.0	giv,	48088	354	388	NI.	8d¥	g sig	8#3	# ### ### ### ########################	1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1	<u> </u>	2245 25	27. 4.		Serial Serial
M, in inchkips	7 N/00.	1 85	22232	a : 2	ಕ್ಷಣ್ಣ		:88 :	មឧត្ត	ಪತ್ರಕ	ভাগদ	72	ndag:	ikanes	£.		an the
80	20,00	phi,	92693	# 33	823	r in	883	888	888	- 325	ź;	ğuğı	250055	21		200
sque o	81=0 (IB)	186	5-5±2	ಅವನ	824 824		1700	int	_ # #	हे देत <u>.</u> के	88	- 2 % i	E 1,858 E 1	ž		RME
i per	Axial	dist.	EEGEV	288	988		198	4aa	200	585	űá.	HOUR	185623	5 E		187
3	-			_											-	
Short a	3. 2. 2. 2. 2. 3. 3. 4. 3. 4. 4. 4. 4. 4. 4. 4. 4. 4. 4. 4. 4. 4.		1144	55	£255									a ama	555 555 555 555 555 555 555 555 555 55	914.6
18 8					5649	ti n	10 to	ŧ		10000	45	2410	110 110 110 110 110 110 110 110 110 110	2222 2484 255 255 255 255 255 255 255 255 255 25	7-5	8
100	3		1283	100	sene Segg	909			146 146 146 146 146 146 146 146 146 146	ioss Ilbas	You	2410 4.70	48 22 481 22 48 481 22 481 22	######################################	# # # # # # # # # # # # # # # # # # #	300
natricul in a	0000	Ø.d₁	100 H	243		āli	12. 7	19	A.		55	120		2.00 m 20.00 kg 10.	Start S	- 6%
Short adoptes no sidesysa Bers Symmatrical in 4 hoses	Mar Cap			920	8865	16 20	70° HS	120 1246	255	ZESES	58 55	578 578	42240	SARRERE	673	98
nins no sidesway natriculin 4 lanser	Su den serv	منفي رافق رابند	2325	250 SEC. 250	2545 2942	ini6	10 10 10 10 10 10 10 10 10 10 10 10 10 1	125 126 61	255 045	ZKSES SSQGG	10 E	410 4.70 1545 1621 211 5.78 1825 1734	22 1973 4 1973 2 1973 2 1973 2 1973	8488666 4888986	181 181 211 211 215	5,002 22230
natricul in 4 leases	OBC 36PU	side sign sign sign	28 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8	577 775 777 1580 577 775 777 1580	8845 3845 3845		10: 10: 10: 20: 20: 20: 20: 20: 20: 20: 20: 20: 2	125 126 61	\$155 50 50 50 50 50 50 50 50 50 50 50 50 5	24555 37055 38666	100 1429 540 207 156 1581 113 2940	410 4.00 1545 1621 411 5.78 1625 1734	00 1675 025 27 1745 827 36 1745 871 226 1973 872 400 2200 1175	8555555 \$255555 \$255555	181 211 115 438 211 288 675 245 902	SDC 5225 30CS
nons no sidesway natricul in 4 lenses	YSO OSCINEN	only one one one	200 SEE SEE SEE SEE SEE SEE SEE SEE SEE S	5.00 CH	8265 2382 2382 2382	100 100 100 100 100 100 100 100 100 100	100 100 100 100 100 100 100 100 100 100	12: 12: 6:1 7:2 W Z'U	191 HB 634 HB 153 HB 15	14555 88955 80078 30005	120 143 540 287 76 158 158 113 286 85	410 4.70 1545 1621 211 5.78 1825 1734	00 1673 025 2233 27 1734 087 2387 34 1745 087 2387 225 1973 972 2331 4 00 2551 175 3815	842565 8858386 8855888 483585	121 211 116 316 468 211 328 317 475 922 424	2015 9755, 9757 70°S
natricat in 4 leaser	Su den serv	side sign sign sign		500 044 777 1500 301 2700 677 975 304 3412 601 2911	3344 3344 3353 3353 3353	100 100 100 100 100 100 100 100 100 100	10" 11" 30 202 30 203 50 110 40 250 00 247	12: 12: 6:1 7:2 W Z'U	42 12 12 12 12 12 12 12 12 12 12 12 12 12	26555 87556 86678 86685 86885	100 1429 540 287 756 2885 1581 1533 2340 854 3468	#10 474 1945 1971 298 620 SMJ #11 578 1975 1974 295 578 3957 SOUARE HED GO	.00 1672 025 2230 73 27 1735 087 2987 751 94 1745 087 2987 751 225 197 972 2431 670 4400 2500 1775 3816 538	20 160 88 250 78 160 78	1341 2181 1155 3150 556 4346 2181 1288 3181 1004 675 2415 672 4754 1168	5.00 2220 '345 315V 1060
natricul in 4 leases	<mark>И</mark> вт Сар — US-Д — 25%	only one one one	201 12 12 12 12 12 12 12 12 12 12 12 12 12	577 775 Feb 342 687 2911 548		5 15 15 15 15 15 15 15 15 15 15 15 15 15	101 110 110 202 200 2041 005	SQUARE TED COLUMNS	150 105 175 175 175 175 175 175 175 175 175 17		101 1429 540 207 756 2584 855 156 1561 153 2940 855 3681 897	#10 474 1945 1971 298 620 SMJ #11 578 1975 1974 295 578 3957 SOUARE HED GO	00 1670 025 225 73 274 27 1745 087 287 75 250 96 1745 087 287 75 250 225 99 97 277 281 640 557 400 250 175 3816 236 468	\$42552 ####256 \$45584 483235 ###################################	131 201 115 315 56 2947 436 211 28 317 104 429 677 245 622 474 1166 527	300 2215 315 3150 100 4614
	Max Cap U.S.I. 25% f,	ملك في فلا في فلا فلا في	100 44 145 140 140 140 140 140 140 140 140 140 140	577 975 50 3412 60 2911 548 328	15 15 15 15 15 15 15 15 15 15 15 15 15 1	1.00 CH 520 159 500 200 497 2300 1.00 CH 520 1551 605 2207 612 2500	10° 11° 120 222 30 203 45 308 -	SQUARE TED COLUMNS	190 1915 1715 2216 122 2438 4435 1416 443 2133 1715 272 573 1417 1629 1644 1375 797 5734 645		105 1439 540 2877 756 2086 875 5281 156 1571 153 2840 855 5268 897 3543	#10 4.74 1945 1921 2556 220 3144 891 1848 #11 572 1975 1774 2175 178 3787 172 3856 SONABLE HIGH COLLIMANS IN	2 1 1 1 2 1 1 1 2 1 1 1 1 1 1 1 1 1 1 1	\$625824 1888285 693586 6933885 8888783 8888783 8888783	131 2021 115 3150 556 2647 731 432 2.11 228 3157 1014 4521 3158 677 2415 672 4754 1168 5577 931	5.00 2235 7375 3238 1080 4674 483 556
	Max Cap U.S.J. 25% J. 50% J.	خاط فالله فالله فالله فالله فالله الله فالله الله	100 100 100 100 100 100 100 100 100 100	5.00 CM 777 1588 501 2199 439 2430 172 5.70 725 504 5412 601 2911 446 2884 419		1.00 10.01 250 1000 300 2000 407 2300 405 1.00 10.51 635 2227 612 2550 405	100 110 100 202 70 200 005 100 407	157 DAY (15 PLZ MR 97) 150 151 151 151 151 151 151 151 151 151	190 1010 755 2150 1021 2031 435 2778 222 1435 425 2150 1031 2021 550 3780 3780 2031 2031 2031 435 2778		100 1439 540 207 756 2000 655 5201 525 157 157 153 200 55 3568 697 5543 535	21	2 1 1 1 2 1 1 1 2 1 1 1 1 1 1 1 1 1 1 1	\$62582 1888286 603588 603386 1888783 1888783 1888783 18888783 18888783 18888783 18888783 18888783 18888783 18888783 18888783 18888783	1341 2011 1155 3150 156 2640 771 445 436 2141 1285 817 1104 4591 315 4600 675 2415 552 456 1166 527) 931 802	5.00 2235 7375 3238 1080 4674 483 556
	186 186 186 288 5 808	only on the for day the day des	201 25 100 25 10	5.07 17.05 17.0 18.00 367 27.05 439 5.030 372 2703 6.77 17.05 17.0 14.12 687 29.11 548 22.05 419 38.23	15	1.65 CH 320 155 605 2207 612 2554 405 2550	10" 115" 120 202 20 201 203 05 108 40 40 355 58 115 31 250 00 247 635 278 42 335	SOUARE TED COLUMNS (#5 218 617 100 100 100 100 100 100 100 100 100 1	199 1015 755 1116 132 263 455 276 459 127 1415 425 2155 578 250 550 510 459 159 1015 1015 1016 278 450 450 450		145 145 540 297 76 288 85 128 55 340 156 157 173 240 55 368 87 353 55 476	10 4.0 193 101 225 231 244 661 158 031 251 251 251 251 251 251 251 251 251 25	22 20 20 20 20 20 20 20 20 20 20 20 20 2	####2## ####2## ####2## ###### ###### ######	331 321 115 315 55 55 77 71 45 47 43 44 45 47 44 45 47 47 47 47 47 47 47 47 47 47 47 47 47	5.04 2225 '925 928' 1089 4634 483 196 687
φ [®] , in indi-kips	Mac Cap USA, 25% (, 50% (, 10.% (,	علاء على علاء على علاء على على على	FIG. 2022 MI. SOF, 1974 SSP, 1975 SS	\$50 744 717 1500 667 2769 439 2640 172 2750 280 677 775 676 4812 667 2811 646 3205 419 3525 106	15	- 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	70" 11" 20 202 70 203 05 308 47 355 101 56 10" 51 206 00 247 65 202 42 935 29	SOUVABLE LED COTTINUES 188, 258, 258, 258, 258, 258, 258, 258, 2	191 OLD 173 LLD 182 SAN 855 JAN 845 SAN 855 SA		145 145 140 207 156 200 85 155 158 455 1510 207 155 156 156 156 156 156 156 156 156 156	210 470 1930 1931 2250 230 240 691 1250 601 1250	100 CO	######################################	231 201 115 315 266 267 741 448 87 527 432 231 228 317 101 429 873 400 883 510 575 7415 572 494 1168 527 831 6022 735 738	5.02 22.16 37.5 37.87 1058 4674 815 156 657 659
Short odennis in o sidesway $t_i' = 4,000 \mathrm{ps} \cdot t_i = 60,000 \mathrm{ps}$ Use's symmetrical in 4 house $\Phi_{i,i}^{\mathrm{tr}}$ is kips	Max Cap U.S.J. 25% J. 50% J.	علام فالله فالله فالله فالله فالله فالله فالله فالله	March 1920 - 454 1920	\$57 174 777 1888 991 278 439 2430 172 2780 240 1960 577 1755 1674 1412 997 2911 448 2008 419 1823 166 4754	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	- 107 107 108 108 208 407 208 301 228 220 1172 1178 405 273 714 1178	70° 11° 120 20° 20° 20° 20° 20° 20° 20° 40° 40° 40° 40° 40° 40° 40° 40° 40° 4	90.0 20.0 30.0 50.0 50.0 50.0 50.0 50.0 50.0 5	191 1015 175 1276 1272 2881 2825 1778 413 5081 2826 1778 413 5081 2826 1778 413 5081 2826 183 5081 4826 183 5081 2826 183 5081 4826 4826 4826 4826 4826 4826 4826 4826		240 1439 440 2377 756 2886 875 288 455 3310 287 4482 156 1671 153 2340 555 368 887 1543 555 476 286 387	210 4.76 1835 1731 2255 230 5444 651 1539 651 4715 230 541 571 4715 230 571 471 571 571 571 571 571 571 571 571 571 5		######################################	231 231 115 215 25 26 264 731 445 27 527 32 432 231 238 331 116 459 373 400 38 510 32 575 545 552 454 116 527 91 602 73 730 730 28	5.00 22.05 73.05 31.00 10.00 46.04 46.05 19.05 66.07 64.01 38.4

Natatorium Structural System Costs Structural System Costs Columns: 101/x10"=7 Use 12"x12"cost Need: 10"x10"x 20 x 28 = 388-89 5)3 = 14.4 CYD of concrete (Agri) CYD (Min. Beins) Beams 1 1045LH: 140'x14=1960957 Cost: \$84.59 1st ×1960=\$ 165,630 Soists 14K1: 25'x468= 11,700 lft Cost: \$12.30/18+ * 11,700/81= \$143,910 Decking 226a. - Over 500 squares: #2.58/sr= (pg.124) [ost: 41,817 sfx #2.58/sf = #107,888] +30kin plate misc. hadu Total New System Cost: \$489,738 Old System Cost: \$1,070,000 Savings : \$60,767

	1105 - Prestressing Tendons	THE RESIDENCE OF THE PARTY OF T	A 7 19 18 18		CALCONIC	CARL COLOR	The second second			
03.2	3 05.50 Prestressing Steel		Grea		labor- Hours	0.0	Harri		cre Costs	
1050	47 kip	G	63	4200	0.5	Urit	Moterial 1,12	Liting 62	Ecupirent .07	
1200	Binground strand, 50° var., 100 km	G	C.c	1275	625	13	.67	1.13	99	
1750	500 cp	G	1	1475	.322	7	.62	73	02	California de la companya della companya de la companya della comp
1406	700° spon, 100 kip	G		1500	.21		.52	.96	.07	
453	300 kg 2001 quai 100 kg	G		1550	.019		.62	.57	30	1.5
1890	300 kp	G	11	1300	.02		.02	26	62	1.50
1820	lingautal urs, 50° spor, 42 kg	G G	1		.019	41	42	.35	02	
1850	14340	G	11	1400	123	1 :	76	1.03	.32	Mark Williams Color To 1997
2000	75' span, 42 kg	G		100000	.017		72	. 95		1
2000	*3k3	G	17	#I-nca0000	.015	77	78	. 36	.02	
2220	Unground single shoot, 100° slab, 25 km	តី		1200			.28 .67	.65	.)*	.45
2250	35 liu	[G]	1	100000000000000000000000000000000000000	.0-2	11	62	1.20	.62	AU 12020
			-		-	4		-76	Air	1.62
03	24 Fibrous Reinforci	ina	7					70.0		
1.3	105 - Reinforcing Fibers	Service Control	*	50503	THE STATE	002-6			No. 17	S SALL
03 24	05.30 Synthetic Fibers	S0.20.50.0000000000000000000000000000000	and the	C. 4.	C. C. C.	SERVE.	AL TELEVISION	10000	WE TO	March Co.
	SYNTHETIC FIBERS	atac of the tenton of the	1	-		SHIP		VIII IN THE PERSON	2011	T 100 11 10
0.00	Synthetic Bluss, use to concrete			205	52.5	. 1		11.24		
01.10	1-1/2 b. per C t.			100	1	16 (C% 1	5.43 ° 5.85			4.43
03 24	05.70 Steel Fibers	-			4.1	S. D.	2.00			4.65
0.000	STEEL FIBERS	49 EARLY T				100	ALP V		TECHO.	
9150	Scalitars, act himmon	G				12.	70	7 11		
1155	25 is m (.*)	G				CY.	7.50		Selver 1	17.38
			A 2 2 4 7 1	SHOW HERE	11/15			- 1 C - C - 4	200	17.26
0.000	Villa, per C.f.	G				11.				26"
0.60 0170	75 lepar CT	G		200	P		35 54			36
				200			35		25.5	24 24 70
0120 0189	75 h. per C.). 100 H. per C.S.	G G	83	Zin.			35 54		25.6/	24
0130	30 Cast-In-Place Con	icrete					35 54			24
03	30 Cast-In-Place Con	icrete	2				35 54			24
03	30 Cast-In-Place Con 30 Cast-In-Place Con 33 Cast-In-Place Con 33 Concrete in Place	icrete					35 54			24
0176 0180 03 03 30 1	30 Cast-In-Place Con 30 Concrete in Place ONCRETE IN PLACE	G G ICTETE lace Concret					35 54			24
03	75 h. per 17. 100 f. per 05. 30 Cast-In-Place Con 253 — Muscellaheous Cast-fri-Pl 53.40 Concrete in Place ONCRETE IN PLACE Industry forms 16 hoses, maintening tree, mounts, observer	G G ICrete Iace Concret					35 54			24
0170 0180 03 03 30 9 0000 0	75 h. per 17, 100 lb. par 08. 30 Cast-In-Place Con 25 - Miscellaneous Cast-Pri-Place Oncrete in Place Oncrete in Place Industry the Place Industry time 19 to 19	G G ICrete lace Concret (80830-94)					35 54 70			24
0176 0180 03 03 30 9 0000 0	75 h. part 1. 100 ft. part 2. 100 ft. part 2. 30 Cast-in-Place Con 25 — Miscellaheous Cast-fri-Pl 253.40 Concrete in Place ONCRETE IN PLACE Industry forms 15 uses (, nairboding steel, owners, closener and final forms 15 uses (, nairboding steel, owners, closener and final forms 15 uses (, nairboding steel, owners, closener and final forms 15 uses (, nairboding steel, owners, closener and final forms 15 uses (, nairboding steel, owners, closener	G G ICrete lace Concret (80830-94)	2144 1	5.62 12	304 C		35 54 70	515	49	24
0170 0180 03 03 30 9 0010 0 0020 0050	75 h. par 17. 100 lb. par 18. 30 Cast-In-Place Con 153 - Miscelliaheous Cast-Pr-Pl 53.40 Concrete in Place ONCRETE IN PLACE Industry from Wisself, minimizing tree, concrete character from places of the violance or character of the violance of the violan	G G ICTETE IACE Concreti	7144 1	5 35 10.3	304 C		35 54 70 400 430	430	41	24 73 944 901
0176 1189 03 30 9 0072 0096 1300 650 650 670	75 h. part 1. 100 ft. part 2. 100 ft. part 2. 30 Cast-in-Place Con 25 — Miscellaheous Cast-fri-Pl 253.40 Concrete in Place ONCRETE IN PLACE Industry forms 15 uses (, nairboding steel, owners, closener and final forms 15 uses (, nairboding steel, owners, closener and final forms 15 uses (, nairboding steel, owners, closener and final forms 15 uses (, nairboding steel, owners, closener and final forms 15 uses (, nairboding steel, owners, closener	G G ICTETE IACE Concreti	2144 (1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	5.55 10.5 2.22 3.4	804 (702) 75		35 54 70 400 430 155	450 133	41 ,83	24 73 73 944 901 795,83
03 30 9 000 000 000 000 000 000 000 000	75 h. part 1. 100 ft. part 2. 100 ft. part 2. 30 Cast-In-Place Con 25 - Miscelfaheous Cast-Pri-Pl 53.40 Concrete in Place 0NCRETE in Place Industry forms 16 uses, marketing tree, concrete chosener are final injuries orbandes introduce 25 capat there executates, industry, marketing	G G IGTETE lace Concret (80889847	2144 (2144 (2145 (2146 (21	6 35 10.3 2.22 3.4 3.7 4.7	804 C 7021 73		35 54 70 400 433 155 223	(50 133 81	.83 .89	24 73 944 901 795.80 255.37
0176 0189 03 30 9 0022 0056 0300 0350 600 670 703	75 to part 1. 100 to be CS. 30 Cast-In-Place Con 20 Concrete in Place 53.40 Concrete in Place ONCRETE IN PLACE Indian tens (Aussel, naineing see, annote, closener are this injuries orbands introfes thans, Ske ser (F., 10 sech 35 year those yearstless, interes, mainer Moint in Charles states, 12 year returnmentations 20 year Charles states, 12 year returnmentations 20 years returning	G G IGTETE Jace Concreti	2144 1 1 445 2 446 1	5 35 10.3 2.22 3.4 8.7 4.7 1.96 16 3	704 C 7021 74		35 54 70 400 433 155 203 400	(5) 133 01 574	41 ,80 ,89 84	24 70 94 901 775,80 134
0170 0180 03 30 9 0010 0 0020 0050 0300 0550 600 570 700 700	75 h. part 1. 100 lb. part 2. 100 lb. part 2. 30 Cast-In-Place Con 20 Concrete in Place 553.40 Concrete in Place ONCRETE IN PLACE Industry braces obtained greet, another observer and history order of branks industry from the control as a location maintain thomes control as a location maintain thomes control as a location maintain thomes store 17 2 12 minimum analysis Joseph contents Joseph cont	G G IGTETE lace Concret (80889847	2144 1 2 1 445 2 2 44 1	6 35 10.3 2.22 8.4 8.7 4.7 1.96 16.3 1.37 19.3	304 C 7021 74 24		35 54 70 400 430 155 202 400 720	750 133 01 874 750	41 .80 .89 .84 .75 56 1	24 70 844 901 795.60 255.37 1, 34 1, 34
033 30 9 1022 1022 1022 1022 1022 1022 1022 1	75 h. per 17. 100 b. per 05. 30 Cast-In-Place Con 20 Cast-In-Place Con 20 Cast-In-Place 53.40 Concrete in Place ONCRETE IN PLACE Industry times (Austel), neighbody seet, annotes observed are this injuries observed in these years and the observed from 5 times. Skepper 18. 10 seen. 20 per Oncrete in Place Industry constitutes, industrial methods Soon in Characteristics, industrial methods Stories (B. 10 years) Made unconstitutes Made unconstitutes Made unconstitutes Made unconstitutes Made unconstitutes	G G IGTETE Jace Concreti	7144 (1444 (5 35 10.3 2.22 3.4 8.7 4.7 1.96 16 3	904 (702) 74 24 79 48		35 54 70 400 430 155 203 400 720 150	750 133 81 870 750 890	41 - 80 - 89 - 84 - 75 90 1 - 94:50	944 70 944 901 775,80 915,37 1,35 1,35 1,74,50
033 30 : 000 000 000 000 000 000 000 000	75 h. per 17. 100 b. per 05. 30 Cast-In-Place Con 200 Cast-In-Place Con 200 Cast-In-Place 53.40 Concrete in Place ONCRETE IN PLACE Industry times (Austel), neighbody seet, annotes observed see this injuries observed industry though Skoper (F. 10 seen 25 par though story (F. 10 seen Maintan strowing 10" a. B", communications 30 sequentiating 30 sequentiating 30 sequentiating 30 sequentiating 30 sequentiating 30 sequentiating	G G IGTETE Jace Concreti	2144 1 - 1 -145 2 - 44 1	6.35 (10.3 2.22 (3.4 3.7 (4.7 1.96 (6.4 1.3 (19.7 1.3 (72.)	804 C 702 74 72 73 44 48 30		400 400 430 155 252 400 729 1,150 315	450 133 01 874 750 890 495	41 80 89 84 75 96 9 94:50 47	24 73 944 901 795,83 1,34 1,585,30 2,124,50 357
033 30 : 000 000 000 000 000 000 000 000	75 h. per 17. 100 ft. per 17. 100 ft. per 17. 30 Cast-In-Place Con 20 Cast-In-Place Con 20 Cast-In-Place 53.40 Concrete in Place ONCRETE IN PLACE Industry forms (Aussel, nairbody see, consists closener aschission order otherwise industry Assume the second second mariner Assume the second second mariner Assume the second second mariner Assume the second	G G IGTETE Jace Concreti	2144 1 2144 1 2144 2 244 1 1	5 35 103 2.22 3.4 3.7 4.7 1.96 163 1.3 193 1.22 12.3	304 (C 702) 74 24 27 43 43 20		35 54 70 600 430 155 202 000 725 1350 315 425	450 133 01 670 750 890 495	41 - 83 - 89 - 84 - 75 96 - 84-50 - 67 - 61	944 70 944 901 795,80 15,32 1,385,50 2,124,50 257 1,526
0176 0189 01	30 Cast-In-Place Con Subscellate our Cast-In-Place Con Subscellate our Cast-In-Place Subscellate our Cast-In-Place Subscellate our Cast-In-Place Subscellate our Cast-In-Place ONCRETE IN PLACE Industry forms (Susse), nairlicing see, on rate, closener are this injuries otherwise industed from Subscellate (Income Subscellate) Charles contains, industrie, maintain architecture, success, 187 x 187 maintain architecture, success, su	G G IGTETE Jace Concreti	2144 1 2144 1 2145 2 246 1 1	5 35 10.3 2.22 3.4 3.7 4.7 1.96 16.7 1.3 17.7 1.03 72.1 1.22 12.3 2.57 15.9	804 C 7027 74 724 731 448 20 1 1 1 1 1 1 2		400 400 430 155 252 400 729 1,150 315	450 133 01 874 750 890 495	30 89 84 75 50 8450 47 81 74 50	944 70 944 901 775,80 15,32 1,34 1,585,50 257 1,526 1,826 1,875,50
0176 0189 01	30 Cast-In-Place Con Source light exist Cast-In-Place Source light exist Cast-In-Place Source light exist Cast-In-Place Oncrete in Place Industry forms (Susse), miniming see, counts, closeners are his violantes otherwise indicated seen, on rate, closeners are his violantes otherwise indicated from expensions, indicated miniming When the control of the contro	G G IGTETE Jace Concreti	2144 1 2144 1 2145 2 2 444 1 1 1 1 1 1 1 1	5 35 103 2.22 3.4 87 4.7 1.36 163 1.3 173 1.03 173 1.22 172 2.57 15.9 175 15.5	804 C 7027 74 72- 727 74 830 1 1 12		400 400 430 155 202 400 720 1315 425 025	450 133 80 870 790 890 495 640 730	41 - 83 - 89 - 84 - 75 96 - 84-50 - 67 - 61	944 70 901 775,80 11,04 1,585,50 2,124,50 287,50 (47,5) (47,5)
0176 0189 01	30 Cast-In-Place Con Sauce Make Cast-In-Place Con Sauce Make Cast-In-Place Salad Concrete in Place Oncrete in Place Inducing forms 16 uses (mainledgraws, concrete closeness and final operations) of the second sections of the sections of the second sections of the second sections of the sections of the second sectio	G G IGTETE Jace Concreti	144, 174, 184, 184, 184, 184, 184, 184, 184, 18	5 35 10.3 2.22 3.4 3.7 4.7 1.96 16.3 1.3 19.3 1.22 2.8 2.57 15.9 1.56 6.2 1.5 16.2	804 C 702! 75 24 20 1 1 1 1 2 1 1 1 2 1 1 1 2 1 1 1 2 1 1 2 1 1 2 1 1 2 1 1 2 1 1 2 1 1 2 1 1 2 1 1 2 1 1 2 1 1 1 2 1 1 1 2 1 1 1 2 1 1 1 1 2 1		400 400 430 166 203 400 725 156 425 025 770	495 640 730 730 730 730 730 540	41 .63 .67 .69 .64 .75.50 .94.50 .67 .61 .74.56 .12.50	944 70 944 901 775,80 15,32 1,34 1,585,50 257 1,526 1,826 1,875,50
033 33 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	30 Cast-In-Place Con Source light exist Cast-In-Place Source light exist Cast-In-Place Source light exist Cast-In-Place Oncrete in Place Industry forms (Susse), miniming see, counts, closeners are his violantes otherwise indicated seen, on rate, closeners are his violantes otherwise indicated from expensions, indicated miniming When the control of the contro	G G IGTETE Jace Concreti	10 144 1	5 35 10.0 2.22 3.4 3.7 4.7 1.96 16.3 1.3 17.7 0.3 17.7 0.22 12.9 0.25 13.5 1.66 6.7 1.2	300 4 C 772 724 727 724 727 727 728 728 728 728 728 728 728 728		400 400 430 166 203 (156 203 (156) 275 (25) (25) (25) (27) (27) (27)	650 133 91 670 790 890 495 640 730 840 455	41 .20 .57 .54 .75.56 .94.50 .67 .61 .74.56 .12.50 .18	944 70 944 901 755,80 1135 1,585 50 2,174,50 287 1,325 1,325 1,325 1,326 1,328 1,328 1,328 1,328

205 2	21 Steel Joist 16 Longspan Joists 28H-63, 78 D/F 28H-11, 25 D/F 32H-63, 76 D/F 32H-63, 76 D/F 32H-63, 76 D/F 32H-63, 76 D/F	il foist Framing		(rev Curput	laitor-			2005 la			
2325 2345 2345 2385 2400 2440 2440 2440	6.50 Longspan Joists 288-66, 6-6-7-7 288-11, 25-6-7-7 328-68, 7-15-7-7 228-12, 30-15-7-7			(rev Curput				2000 5-	- fact		
2325 2345 2345 2385 2400 2440 2440 2440	28H06, 16 IS/F 28H11, 25 IS/F 32H08, 17 IS/F 32H13, 30 IS/F	[5.3	Material	rpo.	Equipment	Talai	lra
1341 756. 1381 7401 7401 7440 7440 7440	288-11, 25 b/d 328-08, 17 b/d 328-13, 30 b/d	[-	F-7 1800	Cec .	.ni	Moterioi 15.05	.96	1.171	21.19;	
756. 2380 7400 2490 7440 2440 7440	320-08, 17 to/JF 320-13, 30 to/U		G	1 300	046	1	25	.96	1.12	31.08	
2380 2400 2400 2440 2440 2440	320H13, 30 tb/L1		G	1300	Cat		15.20	1.96	17	22.25	
7400. 2420. 2440. 2440. 2480.			G	1500	044		34	96	1.12	37.38	
2420 2440 2440 2450	301 1.9. 2 14/15		C	1 1800		20/22	25.50	1.96	612	26.58	100
2440 2440 7480			G	1500	Contract of		43.30	196	ALCOHOL: N. A. C. C.	13.58	
2440 7480	56H 4, 36 l1/IF		G	2700	038		23.50.0	1.58	.91	36.91	
7480	4CUT C, 20 G/B		G	2200	386		40.30	150		13.01	
500000000000000000000000000000000000000	ACLAS , 26 H2F		G	2200	.336		25	1.60	.51	27.51	-
276 (1.3	44U11, 22 U/O		6	2200	.036		47.50	1.50	51	50.01	
	44(1)4, 47 H/IF		G	2200	.056	19	25	1.40	51	27.51	
2520	48(H)1, 22 LL/LF		G	2200	.056		47.50	1.50	51	50.01	
2540	450H5, 42 U/M	557813-007251-203-90525-41T	Teb	EIGHPH!	3900	11.70	RESERVE	S(9,823)	(RESERVE)	1000	
7630	For esynthem 40 compatibles For 30 to 39 tons, cetal		14.5	Mile:		100	68	Charle			S.
2630			34		10		50.8	2.71	Taran S	41.75-0	
2504	20 to 29 ons, mal 4.0 n 19 mrs, mod		14		1000	- Delay	5CK		101	125-12	3
2506	5 to 9 tale, use	NAMES OF TAXABLE PARTY.		40.00	PC-250	10000	98	25%	CHARLE STATE	200ghc.2000#03	
2507	5 12 5 10 B, 311 1 to 4 10 B, 202						75%	90%			
2603 2603	lass from Lion, non		1	1			100%	100%			
4000	For webselvines enliging cold		1		1		1000	50%			
0019 0020 0050	Made for a grader meterols Coenes, 40 for lote, toxic hidging, stra Average		G	12	5,523 6,667	[0)	1,525 2,950)35 294	184 167	, 2154 ₂ 2,511	2
3050	Wasimum		G	1 9	8,859	7	2,450	3/0	225	3,083	3
3.30	801, 5.1 Jb/JF		6	1 1200	100000	LE.	5,20	2.94	1.57	9.6	
0.40	1001, 3.0 ±/41		G	1200	4.53500		£.10 ;	2.34	1.34	9.49	
0.00	12%, 3.7 M/F		G	1500 1500		22 9	5.80	2.35	1,341	9.79	*
0.87	14%, 5.0 b/J		G	1860			5 40	95	1.12	9.48	
0203	16G, \$31b/\$		G	1301			8.25	1.95	1.17	1.33	經
0223	1666, 3.1 lb/JF		G	200	100		7,65	1,75	16	10.61	B 5-40
0343.} 0343	1885,77 tb/45 889, 10.2 tb/45		4	2000	W. C	n arm	3.40	1.76		3.16	
(4.)	Spen 80" to 50", minimum		G	17	4,706		1,775	205	115	2,101	2
6440	Sparce to to , mention Vegeta		G	1 17	4,706		2,000	708	113	2,325	1
0650	'Atamum	CIF.	G	10	5		9,125	355	23	2,681	:
0500	2001, 8.2 U/JF		G		.082	Li	8.20	- 1.78	T	12.76	
3570	23K5 10.8 E/4F	15 V (2 3 15 15 15 15 15 15 15 15 15 15 15 15 15	G		1,020		(.80	1.76	la.	18:36	
0540	2285, 8.8 Je/F	da a series de la companya del companya del companya de la company	G G	2000			5.00	./8		11.58	
3560	29K9, 11.5 LL/LF		G		.040	4	17,30	1.75		1409	
1660	24%, 9.7 lb/ F		G	2200			5.70	.60	.31	12.20	
0500	78 (10, 13.3 ts/AF		G	2200	1 .036		15.0	.60		19.63	
0520	2666, 10.6 lb/ F		G	2200			10.60	.63		3.11	
0546	>4f10, 12.8 d / F		(4)	2701	136		13.50 (.òJ		4.31	
0160	2863, 12 / 16/19		G	240			12.70	47		5.01	
058)	28K12, 27.3 E/JF		G	2400	.030		2.16	1.47.		7.41	
0705	3083, 13.2 (6/8)		G				3.20	147			
	3.K.9, 17.6 by F		G	4 243	.033	7	7.80	1.47	.34	19.97	
0720	For less than 40 ron of libro										

Admition	200	1113 - Deep Longspan Steel Joist				Linu	12.27	SOUTH	2009 30		020910	101
ABOUND STEEL	2			(nev	Cultur	Hours	Uil	Noterio	10001	Fantussi	latel	ind Cap
September Sept	30			1-7			11			1		
Section Sect	0.0									1		
Second Color Seco	3 0											
Sect of Line Color	30		G							(35.5)		
Company Comp	150		G									
20	320		<u>G</u>	-00								
Totals function (1988) Total function (1988) Tot	20											1000
22 Sept 20 15 tem, old 105	20	내내스 시민들은 기업을 가는 이번 이번 이번 경험을 받았다. 이번 시간	<u>G</u>	*	220.0	.Jea	¥		,na	21 174 (174)	55.31	76
20 20 22 no. off C. 10 15 no. off C. 10	010		127		1965	Hers.		100				112
1.00 1.00	22			13		300	2.5	The second second second				THE REAL PROPERTY.
1					8							
1	0.0				£			7,010,000	0.00	. 3		
	7.7					1				8 8	0.00	
Sulf sizes, Normalians, Charles striggs, document Gill F7 16 5 lot 2,001 291 166 2,287 7289 2499	10	Participant and the Control of the Control of the San State of the San Sta	mee conceed	rmens	500,00	error.	terror.	See Street was a	4.4	ON HORSE	CONTRACT	Non-the
Specific 2011 Altimate in Service 6, alternate Gill F7 16 5 16 2,700 291 266 2287 2289	9.0	[1] 사람들은 2011 (1) [2] 경우를 하는 경우를 하는 것이 되었다. 그 사람들은 사람들은 사람들은 사람들이 되었다.	a part		133		10	13,0	nir.	4.70		1100
10	nc	[2] - 10, [2] - 10 [2] - 11 [2] - 11 [2] - 12 [2] - 12 [2] - 12 [2] - 12 [2] - 13 [Jan 1					× 2000	7.031	197	2.247	* nto
Machina Col. 1, 7,275 1, 3,50 320 83 3,452 3,375 32 10,555 5,575 5,677 Col. 100 555 11 40,555 2,555 1,544 52,157 60 100 555 11 40,555 2,555 1,544 52,157 60 100 555 12,555 2,555 1,544 52,157 60 100 555 100 525 12,555 1,544 1,521 60 100 555 100 1,555 1,544 1,521 1,60 1,50 1,555 1,555 1,545 1,555	let,			17	A 100 PM	4. 55-130	RI	ACCOUNT OF THE PARTY OF THE PAR	MEDICAL PROPERTY.	Committee of the Commit		
Company Comp	HC.	The state of the s			\$100 may 200 miles	Section 1975	100	E-4-Car and recognitive to	0.0000000000000000000000000000000000000	Walter Street Street	Service Control of the service of th	
Section Sect	EC.		5. British			10000	*			18 SEC. 1	PO-50 VC 000	
1					40.0000	Sept. 10. 15. 15. 16.	11	30.00			33330000	
Section Sect					1 55.55	1	100	0.000			577.00	
Section Sect		Contract the second of the sec		bobo	10000	1.150.5	400		the state of the	Secretary and the second	Aller a region of the second	
Colors C					100 100	A PERSONAL PROPERTY.	80	ACCRECATE TO A STATE OF THE PARTY OF THE PAR		Control of the Control		A STATE OF THE STA
1				13	T-10 (4.0)	ALC: NO		and the second of the law	4.00.000.000.000.00	A ROSE WITH	AND RESERVE	178 865
1 1 1 1 1 1 1 1 1 1		The state of the s	THE RESERVE AND ADDRESS OF THE PERSON NAMED IN		- Table 1	CONTRACTOR OF		P. P. Land Co., Str. Berry B.		CONTRACTOR AND	and the second second	SECTION N
1 1 1 1 1 1 1 1 1 1	_	The state of the s	COLUMN TO SELECT	1	Service States			the second section in the second section	The State of Local Division in which the	the second second	100000	
1		AND COMPANY OF A COMPANY				The second	13	 ************************************			137555	750000
1263 1273 127 127 127 128 110 1344 135 1.95 1.12 35.08 111 1275		to continue to the	1000000			C 55	16	0.0000000				100 00000
1635 1635				1	1.000	30.75.50.00	1					100000
Table Tabl		from the contract of the contr	The second second second	Late:	and the same	and the same	9223			35,335.52		
Page	100	PROBLEMS A TROUBLES CONTRACTOR AND A SECOND		100	100			0.000	20.00		4000	14.4
200 200		(1) (2) (2) (4) (4) (4) (5) (4) (4) (4) (4) (4) (4) (4) (4) (4) (4			100			ne		1000	ASSES.	100
10 to 19 to 15 to 3 to 10 to 10 to 15 to 3 to 10 to				-		400	3 640	Market Control				No.
10 1 10 1 10 10 10 10	100,000	(4) 整定的社会区域设备设备等等的组织中间中部的现代的表现的对应。	Mary San	earless.	all all	and the same	war.	CATHER STATE OF COLUMN				2,51,000
1 1 1 1 1 1 1 1 1 1				į.				505	25%			
100% 100%		FILE PRINCIPAL P						75%	509	5		
Company Comp								100%	100%			
Color Congspan Joists Color			100000	6 1-6	4440	1	45.0	05007-10	\$2500 A	est thy	122.10	No.
Congspan Johns Cong			100000000000000000000000000000000000000	00000	4.74	C COL	and the same		Special Control	A DE BAR	17.114	-/
Output Continue	_		SUPPLIES OF	Sec.	Sept.	ESTA	Sec. 1	00000000	F-10 15	LEADER W	20224-0	DECEMBER OF THE PARTY OF THE PA
					356		700		Astron		2.00	
Section Sect					3157					1	200	a control
Autops G			त्व	6.7	16		93	2000	221	106	7 497	270
Modeline G		Parameter and the second of th		200			T. Sec.			Programme and the control		1 25
18,000, 12,01,715 G		T. 1 000000 T. C.										
20 181805, 1718/AF G 1700 0.957 21.50 7.52 1.44 25.46 22.50 4 25.00 0.957 12.55 2.52 1.844 1.7.51 21 25 25 25 25 25 25 25 25 25 25 25 25 25		En Company Control Control	[6]	1 1			100			D. O. S.		
6 1000 057 12 15/01 2 1000 057 12 55 2.52 1,44 1,7.51 2 50 50 1000 1000 1000 1000 1000 1000							11			20,200		
50 SCHOP, 1911/919 G 1490 397 21.50 2.52 1.44 25.66 22.90 50 24.005, 1512/91 G 1700 357 1470 2.52 3.343 10.56 2		have been also as the contract of the second contract of the property of the contract of the second contract of th	(A) (S) (S)	lesson.			contra la			Acres of the State	A STATE OF THE REAL PROPERTY.	Comp. 2 0-2863
9 74H05, 131E/JF [G] 1/00 357 14/0 7/52 1344 10.56 22	141	[유리] [[[[[[[[[[[[[[[[[[[[6]	1								A RESPONDED THE VIEW
A 1 Company of the co	90		G				274					
	90 100	24LHOS, 13 LE/AF 24LHOS, 23 DE/AF	G		1400	35/		25	Z1Z	144	20.10	

05	31 Steel Decking							0.99				022
No.	173 + Steel Roof Decking	\$100 PM	880 P.P.	210	Dal-	leber	CON.	-	2009 3c	re (ret:		(org
05.31	23.50 Roof Decking		1	Ger	20.00	Harr	0m	Namer of	IATEL	teupneti	Tetel	irc 02"
2500	90-560 sames	CN	G	-4	149 T	.057	11		- 3	- 32	2.33	2.10
ALL	De SO store		G		2000	600		1.85	.25	.03	2.17	2.5
2630	20 gains, most Silestions		G		:85:	.008		3,83	.37	:0.	: 43	40
7655	5.4500 squares		G	1	4:70	£115		2.A2	35	.U.	2.80	5.3
2700	Cyer 5.00 ap tr ⊕		G		4800	.007		2, 8	34	.03	255	3.0
2900	18 graps, under 50 stures		G	, 13	3500	.308		3.3	38	.04	3.5	4.1
2950	50 500 saucns	1.5	G	183	+100	.008	90	3,13	. Si	.00	2.17	3.7
3000	Ower SINC squeres		<u>G</u>		4300	.007		2.82	.54 .35	184	1.60	6.5
3050	15 grage, order 50 squaes		G		3/00	005		5.25	36	.03	4.60	5.3
000	5550 since		G		1000	Libo		4.21 3.79	34	.03	4.9	4.3
317	Over 500 squares		<u>IG</u>	*	4200	.003		.04	7-		.04	7.0
3150	From many state of the sead of wide ris, ce	t.h	G		1			79			.79	
2160	or no must restend of wife the odd	ent Victoria	G.	and Marie	WHAT !	Sept. 10.00	*	70 March 1	15,000	PASSING.	A A STATE OF	7/1/2
853	1 33 - Steel Form Decking	198	NAME OF STREET	48.0	No. of	100	370	STATE OF STREET	135		13.6	
05 31	33.50 Form Decking				-		power.	NO. ESTATE		-4977	100000000000000000000000000000000000000	ni draini
9010	FORM DECKING	103	EPSES-	15	1	1.0	10%		4.15			
000	Mace from 1937 of marenos	Service of			1	200		132	36	.03	2.11	25
\$100	Sections, steel, 23 gauge, 9/15" deep, unposted		<u>G</u>		A STATE OF THE STATE OF	45/20000	5	137	36	TO SHARE WATER OF	1.97	2.3
63200	- GIALIFES		<u> </u>		3400 3400	.008		1.57	37	16	2.27	2.7
5220	24 grape, 1" deat, propoled		G		3500			2.20	.37	100	1.63	3.1
5240	Bohorizeri		G		3800	March 1995	1 10	05	.35		2.41	23
5300	94 garge, 1-5/1-61 Josep, elementati		6		3830	+		2.34	.38	V (1000)	2.76	3.2
:400	Sept-technic	discreption	G		8/00	A comment	100	2 50 s		of the later with the	2.93	34
ASCC :	Ze groups: 67 67 feet, asserber	100.25	ĪĠ		5700	10000		2.55	30	THE TOTAL W. L. L. L. L.	2.48	35
6000	Sd saries		[G	100	3000	Property of	10	3.98	±0	SOURCE OF YORK	3.72	4.2
6700	Zi quip. I' dan morel		G		5500	WITH SECUL	1	3.22	30		3.65	43
(000)	Grander Sheet metric using skeare form. "2" whose with 2 be	ent rela	CONTRACTOR	444	2,64,00	7		1	and a second	V		
7000 7100	10 graps	Man jen	G	1 250	350	.022	18	5.30	.04	.37	5.71	1 1
770.1	0 3.10°	19	G		1 350	.072		7.20	1.04	- 3:	5.41	10.1
1.11.1	10 2, agr	-			-				and Sur		ALC: NO COLUMN	Was November
A.F.	35 Raceway Deck	ring	Accom	1	60			9.74				12.3
UD	33 Raceway Deci	31115	433VII	44					BANK BANK		district of	Mark to
05	5 12 - Steel Cellular Deck	ang				-24	and of	1 20 1	22.7	STATISTICS.	SESTEMBED.	218
Maria de la compansa	13.50 Cellular Decking	A 15/2		200		- 100	_	THE PROPERTY.	-	TALS:	PROFESSION OF THE PROPERTY OF THE PROFESSION OF	STREET, ST
05 35	CELLULAR DECKING											1-00
	CELLULAK DECKING	4.41.13	305 - 3 Year				arrive to	3000	11 150	- 4	30.00	TA
	Mento gram riscycled moderick	COMPANY NO. OF P.	25/56 DESIDE	100	5.465	THE PARTY	0.00	CONTRACTOR OF THE PARTY OF THE			4).28	
:001C	Martin Control of the	gune:	<u> [c</u>		CONTRACTOR	200	0000	至.20	. 95		4 6 4 4 7 7 7 7	
8010 9013 8230	Mento gram riscycled moderick	o more:	· · · · · · · · · · · · · · · · · · ·		1427	.023		17:60			STATE OF THE PARTY.	1.14
0015	Made nom rich ded modernis. Gelalar uris, galo 21 deep. 2020 groups, der 1.	i gjarës	· · · · · · · · · · · · · · · · · · ·		147	023 023	5.5	11.60 11.95	e de la companya de l		13.09	15
0010 0013 0230 0250	Menterom ricydad molenes Galaki cris, gala 21 deep, 2020 gruge, Ser 1. 18 20 grupa	i more	· · · · · · · · · · · · · · · · · · ·		147) 139) 36	023 0 .023 0 .024		11.95 14.20	1.02 1.07 1.50		13.09 15.36	15 JA 15 7.
0010 0015 0230 0250 0300	Mento rom riccyddd molent 8 Galafer Cris, gelt, 22 Eesp, 2020 gauga, dae'i 1 48 20 gasgo 18-8 garge	i aports			139 36 133	0 .023 0 .023 0 .024 0 .024		11.95 14.20 15.85	1.00 1.00 1.00 1.00	09 10 10 10	13.09 15.36 7.04	14. 15. 7. 19.
0010 0013 0230 0250 0300 0320	Mente commiscycled moterick Gelulor unis, gold 27 deep, 2002 grupp, 2001 l. 18 20 grupp 18 18 grupp 18 18 grupp 18 16 grupp 27 deep, geluntered, 2002 grupp	i mures			36 36 133 137	0 023 0 023 0 024 0 024 6 025		11.95 14.20 15.85 1.25	1.04 1.04 1.50 1.50 1.50	10 10 10 10	13.09 15.36 17.04 12.40	15. 15. 7. 19.
0010 0015 0230 0250 0303 0320 0340	Mente rom riecyddd noberth Galder cyfn, gelt 27 deg, 2020 gaugs, dan 1. 18 20 gasgo 18-8 garge 18-18 gauge 18-16 gauge	i m ines ([6] 2 2 2 (6)		39 36 133 137 135	0 .023 0 .023 0 .024 0 .024 5 .025 0 .024		11.95 14.20 15.85 1.25 1.25	1.00 1.00 1.00 1.00 1.00 1.00	10 10 10 10 10	13.09 15.36 7.04 12.40 14.27	16 18 7, 19 14.
0010 0013 0200 0250 0300 0320 0340 0400	Mente rominiscy ded motients Gelulor units, gabt 27 deep, 2020 groups, deer 1. 18 20 groups 19 8 groups 19 8 groups 16 6 groups 27 deep, gaboritest, 2020 groups 18 18 groups 18 18 groups 18 18 groups	i aj urės	्ड <u>८</u> ८ ८ ८ ८		1470 36 133 137 135 129	0 023 0 023 0 024 0 024 6 025 0 024 0 225		11.95 14.20 15.85 17.5 33.90 53.53	1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00	0 00 10 10 10 10 10 10 10	13.09 15.36 7.04 12.40 14.77	16 15 7, 14 16 16
0010 0013 0230 0250 0300 0320 0340 0400 0500	Mente commiscycled moterick Gelulor upin, golo 27 desp. 2020 grups, per 1. 18 20 grups 18 18 grups 18 18 grups 18 16 grups 27 desp. griboritest, 2020 grups 18 18 grups	i spine:	[6] [2] [2] [3] [4] [6]		1490 1391 36. 133. 1371 1351 1291 133	0 .023 0 .023 0 .024 0 .024 6 .025 0 .026 0 .026		11.95 14.20 15.85 15.6 15.6 13.60 13.5 15.25	1.50 1.50 1.53 1.53 1.50 1.50 1.15	2 09 10 10 10 10 10 10 10 10 10 10 10 10	13.09 15.36 7.34 12.43 14.73 14.73	14. 16. 15. 7. 14. 16. 16. 17.
0010 0013 0230 0250 0300 0340 0400 0500 0500	Mente commiscycled moterick Gelulor upin, golo 27 deep, 2020 grups, deer 1. 18 20 grups 19 8 grups 19 8 grups 16 6 grups 27 deep, geluntered, 2020 grups 18 20 grups 18 20 grups 18 20 grups 18 16 grups 16 18 grups 16 18 grups	i mines	[0 0 0 0 0 0 0 0 0 0 0		1470 36. 133. 137. 135. 129. 123.	0 .023 0 .023 0 .024 0 .024 0 .025 0 .025 0 .026 0 .026		11.95 11.95 14.20 15.85 1.75 13.60 13.53 16.25	1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00	2 09 10 10 10 10 10 10 10 10 10 10 10 10 10	13.09 15.36 7.34 12.40 14.73 14.73 16.54	16. 18. 7. 14. 16. 10. 15.
0010 0013 0200 0250 0300 0340 0400 0900 0900 0900	Meno com recycled moterics Colubrative, gob. 27 Seep. 2020 groups, dec 1. 18 20 groups 18 10 groups 18 10 groups 18 10 groups 18 20 groups 18 21 groups 18 21 groups 18 21 groups 18 22 groups 4 27 Seep. grbanton, 20 415 groups	5 ajunts			1470 36- 133 137- 135- 129- 133 115- 117-	0 .023 0 .023 0 .024 0 .024 6 .025 0 .024 0 .026 0 .026 1 .020		11.95 14.20 15.85 1.25 13.80 13.55 16.25 16.65 15.70	1.07 1.07 1.25 1.25 1.25 1.25 1.25 2.26 1.3	2 09 10 10 10 10 10 10 10 10 10 10 10 10 10	13.09 15.36 7.34 12.40 14.77 14.77 16.54 18.03	16. 16. 16. 16. 16. 16. 16. 16. 16. 16.
9010 0015 0730 0250 0300 0340 0400 0500 0500 0700 0800 1000 1100	Mente commiscycled moterics Calular units, galo 27 deep, 2020 groups, deer 1. 18 20 groups 4- 8 groups 3- 8 groups 3- 6 groups 18 50 groups 18 50 groups 18 16 groups 16 16 groups 10 16 groups 10 16 groups	s gjunte	C		1450 364 1333 1377 1355 1299 1433 1135 1130	0 .023 0 .023 0 .024 0 .024 6 .024 0 .024 0 .026 1 .026 1 .029		11.95 14.20 15.85 1.25 38.60 33.55 16.25 16.65 15.70 15.60	1,00 1,00 1,00 1,00 1,00 1,00 1,00 1,00	2 09 10 10 10 10 10 10 10 10 10 10 10 10 10	13.09 15.38 7.34 12.43 14.73 14.73 16.54 18.03	16. 16. 16. 16. 16. 16. 16. 16. 16. 16.
9010 0015 0230 0250 0300 0340 0400 0900 0900 0700 0800 1000	Meno com recycled moterics Colubrative, gob. 27 Seep. 2020 groups, dec 1. 18 20 groups 18 10 groups 18 10 groups 18 10 groups 18 20 groups 18 21 groups 18 21 groups 18 21 groups 18 22 groups 4 27 Seep. grbanton, 20 415 groups	i gjurë.	C		1470 36- 133 137- 135- 129- 133 115- 117-	0 .023 0 .023 0 .024 0 .024 0 .024 0 .025 0 .025 0 .026 0 .033 0 .033 0 .033		11.95 14.20 15.85 1.25 13.80 13.55 16.25 16.65 15.70	1,09 1,09 1,29 1,29 1,00 1,10 1,10 1,10 1,10 1,10 1,10 1,1	2 09 10 10 10 10 10 10 10 2 15 10 2 15 11 12 10 10	13.09 15.38 7.34 12.43 14.73 14.73 16.54 18.03 17.13 17.13	16. 15. 19. 14. 16. 16. 17. 18. 18. 18. 18. 19. 18. 19. 19. 19. 19. 19. 19. 19. 19. 19. 19

Modified Schedule - Without Glulam in Natatorium

	Natatorium - Pool Floor Steel Placement	5 days	Mon 6/15/09	Fri 6/19/09	114	Pool	Pool	
	Natatorium - Pool Floor Concrete Placement	1 day?	Mon 6/22/09	Mon 6/22/09	115	Pool	Pool	
	Natatorium - Pool Walls Rough-In	10 days	Tue 6/23/09	Mon 7/6/09	116	Pool	pool	
	Natatorium - Pool Walls Steel Placement	15 days	Tue 7/7/09	Mon 7/27/09	117	Pool	Pool	
3	Natatorium - Pool Walls Concrete Placement	2 days	Thu 7/30/09	Fri 7/31/09	118	Pool	į Pool	
-	Natatorium - Drill Piers	10 days	Tue 6/2/09	Mon 6/15/09	15	Concrete	Concrete	
	Natatorium - Form and Reinforce Spread Footings	11 days	Mon 8/3/09	Mon 8/17/09	119	Concrete	Concrete	
	Natatorium - MEP Underground	10 days	Mon 8/3/09	Fri 8/14/09	119	MEP		
	Natatorium - Pour Slab-On Grade	2 days	Tue 8/18/09	Wed 8/19/09	122,121	Concrete	Concrete	
	Natatorium - Form, Reinforce, and Pour Columns	5 days	Thu 8/20/09	Wed 8/26/09	123	Concrete	Concrete	
	Natatorium - Steel Erection	20 days	Thu 8/20/09	Wed 9/16/09	23,123	Concrete	Concrete	
	Natatorium - Top Out	0 days	Wed 9/16/09	Wed 9/16/09	125,124	All	♦ 9/16	
	Natatorium - CMU North Wall	5 days	Thu 9/17/09	Wed 9/23/09	126	Masonry	Masonry	
	Natatorium - CMU East Wall	5 days	Thu 9/24/09	VVed 9/30/09	127	Masonry	Masonry	
	Natatorium - CMU South Wall	5 days	Thu 10/1/09	Wed 10/7/09	128	Masonry	Masonry	
	Natatorium - Face North Wall	5 days	Thu 10/8/09	Wed 10/14/09	129	Masonry	🍵 Masonry	
	Natatorium - Brick East Wall	5 days	Thu 10/15/09	Wed 10/21/09	130	Masonry	a Masonry	
	Natatorium - Brick South Wall	5 days	Thu 10/22/09	Wed 10/28/09	131	Masonry	@ Masonry	
	Natatorium - Roof Decking	15 days	Mon 4/20/09	Fri 5/8/09		Steel	Steel Steel	
	Natatorium - Windows	20 days	Thu 10/29/09	Wed 11/25/09	132	Windows	Windows	
	Natatorium - Dry-In	0 days	Wed 11/25/09	Wed 11/25/09	134	All	♠ 11/25	
	Natatorium - Pool Gutter System	20 days	Mon 5/11/09	Fri 6/5/09	133	Pool	Pool Pool	
	Natatorium - Standing Seam Roofing System	20 days	Mon 5/11/09	Fri 6/5/09	133	Roofing	Roofing	
	Natatorium - Overhead Rough-in	10 days	Thu 11/26/09	Wed 12/9/09	135	MEP	■ MEP	
	Natatorium - Interior Framing	10 days	Thu 12/10/09	Wed 12/23/09	138	Drywall	prywa	all

Pearland Recreation Center and Natatorium – Final Report
Appendix 7 – Analysis #2 (Mechanical System) References
Appendix 7 – Analysis #2 (Mechanical System) References
Appendix 7 – Analysis #2 (Mechanical System) References
Appendix 7 – Analysis #2 (Mechanical System) References
Appendix 7 – Analysis #2 (Mechanical System) References
Appendix 7 – Analysis #2 (Mechanical System) References
Appendix 7 – Analysis #2 (Mechanical System) References
Appendix 7 – Analysis #2 (Mechanical System) References
Appendix 7 – Analysis #2 (Mechanical System) References
Appendix 7 – Analysis #2 (Mechanical System) References
Appendix 7 – Analysis #2 (Mechanical System) References
Appendix 7 – Analysis #2 (Mechanical System) References
Appendix 7 – Analysis #2 (Mechanical System) References
Appendix 7 – Analysis #2 (Mechanical System) References

Mechanical System Cost Calculations Mechanical System Pricing Cooling Towers Material: \$30,171 (supplier's price) Labor: \$ 7,650 (RS Means 2008, war pg. 374) Additional Pumps + Piping: Labor + Material . \$94.59/Ton X 276 Tons = \$76,082 (BS Means 2008, pg. 374) Chiller (WC): Material: 276 Toro X \$340/Ton = \$93,840 (Supplier's Price) Labor: \$11,700 (BS Means 2008, pg. 373) Add'I Structural Support For Cooling Towers: Labor + Material: #15,557 (estimate from 140) Total Cost for New Design: \$180,000 Previous Mechanian System Cost: \$ 228,523 (from Mechanical Initial Savings of: \$48,523 Contractor

	64 26 - Rotary-Screw Water Chillers	2000	Orio	trba			2008 Ears Coss		To
23 6	4 26.10 Rotary-Screw Type Water Chillers	Craw				//meral	laner Equipment	Total	lo:
1140	320 ran	(67	.12	273	Er.	163,500	2,400	175,900	19
(2)0	Puckeyot unit, water oppied, not indutower						The same		
0210	80 to:	0.7	.15		lt.	38,500	0,000	48,500	
(620)	160 ron \		1.4		101	45,200	0.300	55,550	6
0230	150ton		3	3000		84,500	10;926	/5,300	5
(640	200 rcn	11.1	'3		11	/2,503	11,500	33,800	3
(2:0]	253 mn	×	12			81,000	11,7001	72,700	10
(276	300 km		12			95,000	12,000	07.000	12
(270	350 km	*	12	274	7	134,500	12,400	146,500	é
1458	White socied, towar set included		6				S. A. S. S. S.		
1520	135 ten cooling, straw compressors	0/	14	235	31	55,000	16,600	65,600	
15E0	SC to cooling, snow compressors		13	240	1. 7	63,500	10,800	/4,300	
1520	200 by soding x ewonitions in		.11	750		87,500	1.200	95,700	H
150	291 on onling stew or tresses	A STATE OF THE STA	.12	250	*	51,500	(1/0)	108,200	11
23	64 33 - Direct Expansion Water Chillers	100	0.11	-	100	1 2		The state of the s	1
93 6	4 33.10 Direct Expansion Type Water Chillers							33377	
0010	DIRECT EXPANSION TYPE WATER CHILLERS, With surror corbus		4110	Be Si	AUG.	200	4年世纪1	100	1
3000	Diece expansion, shall and tube type, for culting systems								14
2020	i de la collega	95	2	8	176	5,975	340	6,315	234
8330	5 to	production of	1.90	0.42	Lat.	5,900.	355	10,255	. 1
640	10 mi		140	9,417	11	13,300	400	2,783	1
8250	A0 ma		1.50	10.557		14,000	450	14,450	ı
	30 mm		1 1	16	9 90	17,900	480	18,580	
E160	22 TH		10.4	16	9E JOS	11,700	007	15,203	2
£160 £170	50 tu		90	17,778	1	25,700	753	29,455	
	9 m (Ctrans) 2 m 1 m 1 m	05				E CONTRACTOR	000000000000000000000000000000000000000	3.070.000	3
920 925 925	65 Cooling Towers	0.5		17,778		28,700	755	29,455	2: 3: 5:
9270 928 928 93 6	65 Cooling Towers 5 13 - Farced-Draft Cooling Towers 5 13.10 Forced-Draft Type Cooling Towers			17,778		28,700	755	29,455	3
925 925 93 6 00()	65 Cooling Towers 65 13:- Forced-Draft Cooling Towers 6 13.10 Forced-Draft Type Cooling Towers FORCED-DRÁFT TYPE COOLING TOWERS, Préviged unts 193000			17,778		28,700	755	29,455	3
923 6000 0000 0000 00000 00000 00000 00000 0000	65 Cooling Towers 65 13: Forced-Draft Cooling Towers 5 13:10 Forced-Draft Type Cooling Towers FORCED-DRÁFT TYPE COOLING TOWERS, Priorged Links 63 venesal steel			17,778		28,700	755	29,455	3
925 925 925 93 6: 00(1) 1071 108)	65 Cooling Towers 65 13:— Farced-Draft Cooling Towers 6 13.10 Forced-Draft Type Cooling Towers FORCED-BRÁFT TYPE COOLING TOWERS, Houged units 6 a venicular and present the cooling towers Freeze coling towers	-310	90	17,778 25,567		25,000 50,000	755 1:175	27,455 52,175 52,175	3: 5:
9270 928 928 93 6 0010 0091 0091 0091	65 Cooling Towers 65 Cooling Towers 513:— Forced-Draft Cooling Towers 513:10 Forced-Draft Type Cooling Towers FORCED-DRÁFT TYPE COOLING TOWERS, Prologed unto 193000 Gaveniss steel Freez call, asseltant Verted, but take, 61 min.		90	17,778 29,567		25,000 50,000 W	755 1.175 - ;	29,455 52,175 107.75	3 5
925 925 925 923 60 900 (000) 900 (000) 9100 (100)	65 Cooling Towers 65 Cooling Towers 65 13:— Forced-Draft Cooling Towers 5 13:10 Forced-Draft Type Cooling Towers FORCED-BRÁFT TYPE COOLING TOWERS, height dutb Gaveness one Frees call, asseltan Verted, set talls, 61 mm. 100 for	-310	90 100	17,778 26,567 26,567 267 ,263		25,000 57,000 W 74	755 1.175 - : - : - : - : - : - : - : - : - : -	29,455 52,175 107,75 06,35	3 5
23 60 000 000 000 000 000 000 000 000 000	65 Cooling Towers 65 Cooling Towers 65 13:— Forced-Draft Cooling Towers 5 13:10 Forced-Draft Type Cooling Towers FORCED-DRÁFT TYPE COOLING TOWERS, heliogid unto Governess see France only asselted Verical set of the filter 170 for	-310	90 90 100 105	17,778 25,567 26,567 267 240 220		25,700 57,000 Wi 74 74	755 1.175 1.175 1.75 1.65 9.70	29,455 52,175 107,75 06,35 81,70	3 5
928 928 93 66 9010 9070 9080 9180 9280 9280	65 Cooling Towers 55.13.4- Forced-Draft Cooling Towers 5.13.10 Forced-Draft Type Cooling Towers FORCED-DRÁFT TYPE COOLING TOWERS, heighted in to Graven and the state of the towers of the tower of	-310 -34	90 105 105 125	17,778 25,567 26,567 267 267 269 279 200		25,000 50,000 We 74 74 65,50	755 1.175 1.175 1.75 1.75 10.55 9.70 8.80	29,455 52,175 107,75 96,35 81,70 74,30	3 5
93 6: 000 000 000 000 000 000 000 000 000 0	65 Cooling Towers 55.13.44 Forced-Draft Cooling Towers 5.13.10 Forced-Draft Type Cooling Towers FORCED-DRÁFT TYPE COOLING TOWERS, Présuged unts Grantes and Vericle satisfies à l'imm 100 cr 115 to 151 tor 152 tor	-310	90 90 100 105	17,778 25,567 26,567 267 240 220		25,700 57,000 Wi 74 74	755 1.175 1.175 1.75 1.65 9.70	29,455 52,175 107,75 06,35 81,70	3 5
93 67 000 000 000 000 000 000 000 000 000 0	65 Cooling Towers 55.13:44 Forced-Draft Cooling Towers 5.13:10 Forced-Draft Type Cooling Towers FORCED-DRÁFT TYPE COOLING TOWERS, Préviged units Grantest steel Future couli, asselban Vertical set may all min 100 tor 115 to 151 tor 162 tor for interroporities, no multicles	-310 -34	90 105 105 125	17,778 25,567 26,567 267 267 269 279 200		25,000 50,000 We 74 74 65,50	755 1.175 1.175 1.75 1.75 10.55 9.70 8.80	29,455 52,175 107,75 96,35 81,70 74,30	3 5
923 923 93 6: 00(2) 0092 0093 0109 0290 0290 0290 0300 0300 0300 0300 03	65 Cooling Towers 55 13:44 Forced-Draft Cooling Towers 5 13:10 Forced-Draft Type Cooling Towers FORCED-DRÁFT TYPE COOLING TOWERS, Prolonged units Graveness see Fraces cooling acceptive Vertical and these, of time 10 force 115 for 150 for interroporties, we multiples noticed on discretible	-310 J	90 90 105 105 125 92	2556 2556 267 267 240 270 200 352	Treef	26,000 50,000 90 76 74 66,50 55	755 1.175 1.75 1.75 10.55 9.70 8.80 8	29,455 52,175 107,75 96,25 81,70 74,30 61	3 5
923 923 93 6 0010 0091 0091 0091 0091 0091 0190 0290 1100 1500 1500 1500	65 Cooling Towers 55 13:44 Forced-Draft Cooling Towers 5 13:10 Forced-Draft Type Cooling Towers FORCED-DRÁFT TYPE COOLING TOWERS, hedged onto 03000 Governed and overall and one Forced and overall and one Forced towers Forced - Draft Type Cooling Towers Forced - Draft Type Cooling Towers	-310 -34	90 90 105 105 125 92	267 267 267 267 267 270 270 270 270		26,000 50,000 90 76 74 66,50 55	755 1.175 1.75 10.55 9.70 8.80 8.42	27,455 52,175 52,175 107,75 96,35 86,73 74,33 61	3 5 5
\$270 \$280 \$280 \$23 67 \$000 \$200 \$200 \$200 \$200 \$200 \$200 \$20	65 Cooling Towers 55 13:4- Farced-Draft Cooling Towers 5 13:10 Forced-Draft Type Cooling Towers FORCED-DRÁFT TYPE COOLING TOWERS, Prolonged units Gaveness staw Future cooling as allow Verical set of the Allow 10 for 115 for 151 for 152 for for fateer experities, see markels natured of dear effew Verifies, get drive, 167 for 197 for	-310 J	90 90 100 100 120 32 24 25	267 267 267 267 267 270 270 270 152	Treef	25,000 50,000 90	755 1.175 1.75 10.55 9.70 8.80 8.42 8.42 8.42	27,455 52,175 52,175 107,75 96,35 86,73 74,33 61 110,40 81,20	3 5
923 923 93 6 0010 0091 0091 0091 0091 0091 0190 0290 1100 1500 1500 1500	65 Cooling Towers 55 13:44 Forced-Draft Cooling Towers 5 13:10 Forced-Draft Type Cooling Towers FORCED-DRÁFT TYPE COOLING TOWERS, thouged units 03050 Governed steel Frace colin acsolium Verical self-the, follows 100 ter 115 to 150 ter 152 ter for tigner operius, see maticles naued of date effow Verical, quardine, 167 for 197 ter 582 ter 582 ter	-310 J	90 90 100 105 120 120 22 23 32	26560 26560 267 267 267 270 270 270 270 270 270 270 270 270 27	Treef	25,000 50,000 9% 76 74 65,50 55	755 1.175 1.75 10.55 9.70 8.80 8.42 9.20 8	29,455 52,175 107,75 96,35 83,73 74,33 61 116,49 81,20 62,50	33 34 34 34 34 34 34 34 34 34 34 34 34 3
\$270 \$280 \$280 \$280 \$28 60 \$000 \$200 \$200 \$200 \$200 \$200 \$200 \$2	65 Cooling Towers 55 13:— Forced-Draft Cooling Towers 5 13:10 Forced-Draft Type Cooling Towers FORCED-BRÁFT TYPE COOLING TOWERS, Prological units Governess steel Freeze colli, acsolium Verical, sel table, follows 100 ter 115 ter 125 ter 125 ter 125 ter 125 ter 126 ter 127 ter 128 ter 129 ter	-310 J	90 100 100 120 120 120 120 120 120 120 12	25.50 25.50 26.70 26.70 26.70 27.70	Treef	25,000 50,000 90 74 74 65,50 55	755 1.175 1.175 10.55 9.70 8.80 8	29,455 52,175 107,75 96,35 83,73 74,33 61 110,49 81,20 56,50 56,95	3. St
5270 5250 925 923 65 0010 0071 0081 1290 1290 1290 1290 1290 1290 1290 129	65 Cooling Towers 55 13:— Forced-Draft Cooling Towers 5 13:10 Forced-Draft Type Cooling Towers FORCED-DRÁFT TYPE COOLING TOWERS, Prologed unto 193000 Governest steel Fraces craft, asselfant Vertical tell table, foll tree 100 ter 115 to 151 ter 152 ter 15 ter 152 ter 15 terlines capatitis, see marticles mared at deace than Vertical tell table, for too 197 terlines capatitis, terlines 152 terlines capatitis, terlines 152 terlines capatitis, terlines 153 terlines capatitis, terlines 154 terlines 155 terli	-310 J	90 90 100 105 120 120 22 23 32	26560 26560 267 267 267 270 270 270 270 270 270 270 270 270 27	Treef	25,000 50,000 9% 76 74 65,50 55	755 1.175 1.75 10.55 9.70 8.80 8.42 9.20 8	29,455 52,175 107,75 96,35 83,73 74,33 61 116,49 81,20 62,50	33 34 34 34 34 34 34 34 34 34 34 34 34 3
5270 5250 925 6 923 6 900 900 900 920 120 120 120 120 120 120 120 120 120 1	65 Cooling Towers 55.13:— Forced-Draft Cooling Towers 5.13.10 Forced-Draft Type Cooling Towers FORCED-BRÁFT TYPE COOLING TOWERS, heliogid unto 1990ec Governess one Frees colli, asseltan Verticl, selfate, follows 100 for 115 to 151 tor 152 tor 161 for operation, les maticles matical at date flave Verticl, again dive, 167 for 197 for 198 on 1018 var Play through, confragaloge	-310 26 96	90 100 100 100 120 120 120 120 120 120 12	267 240 270 270 270 270 270 270 270 270 270 27	Truel	25,000 50,000 WW 74 74 75,50 55	755 1,175 1,175 10,55 9,70 8,80 8 8,40 8,20 8 7,45 7,45 7,05	29,455 52,175 52,175 107,75 96,35 83,70 74,30 60 110,40 51,20 58,95 64,95	33 55 55 55 55 55 55 55 55 55 55 55 55 5
\$270 \$280 23.6 23.6 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0 20.0	65 Cooling Towers 55.13:— Forced-Draft Cooling Towers 5.13.10 Forced-Draft Type Cooling Towers FORCED-BRÁFT TYPE COOLING TOWERS, height unto 1990en Governest one Frence colling assiltant Verticle at larte, follows 1970en 115 to 153 tor 155 to 151 tor 152 tor 164 their operation, less maticles matical of date flow Verticle and the 157 ton 1977 ton 1977 ton 1978	-310 J	90 105 105 125 125 127 128 129 129 120 120 120	267 240 270 270 270 270 270 270 270 270 270 27	True!	25,000 50,000 Windows 76 74 65,50 55 102 73 60,50 97,00 97,00	755 1,175 1,175 10,55 9,70 8,80 8 8,40 8,20 8 7,45 7,05	29,455 52,175 52,175 107,75 96,35 81,70 74,30 61 110,40 81,20 52,50 54,95 10,845	3 5
5270 5280 23 66 0007 0000 0000 2000 2200 2200 2200 2000	65 Cooling Towers 55.13:— Forced-Draft Cooling Towers 5.13.10 Forced-Draft Type Cooling Towers FORCED-BRÁFT TYPE COOLING TOWERS, heliogid unto 1990ec Governest one Freest colli, asseltani Freest colli, asseltani 100 for 115 to 151 tor 152 tor 161 fore opubits, ass maticles neced at date than Ventical particles, 167 for 1977 tor 1987 tor 1988 on 1018 var Play magnitic minigal type 50 tor 75 tor	-310 346 96 96 96 96 96 96 96	90 100 100 100 120 120 120 120 120 150 150	267 225.667 267 267 270 270 270 270 182 190 182 190 165 165 165 165 165 165 165 165 165 165	Tree!	25,000 50,000 Windows 76 74 65,50 55 102 73 60,50 970 970 10,400 13,500	755 1,175 1,175 10,55 9,70 8,80 8 8,40 8,20 8 7,45 7,05	29,455 52,175 52,175 107,75 96,35 81,70 74,30 51 20 51,20 52,50 56,93 54,95 10,845 14,195	2.30
\$270 \$280 \$23 60 \$000 \$000 \$200 \$200 \$200 \$200 \$200 \$2	65 Cooling Towers 55.13:— Forced-Draft Cooling Towers 5.13.10 Forced-Draft Type Cooling Towers FORCED-BRÁFT TYPE COOLING TOWERS, height unto 1990en Governest one Frence colling assiltant Verticle at larte, follows 1970en 115 to 153 tor 155 to 151 tor 152 tor 164 their operation, less maticles matical of date flow Verticle and the 157 ton 1977 ton 1977 ton 1978	-310 26 96	90 90 100 100 120 120 120 120 120 120 120 12	267 240 270 270 270 270 270 270 270 270 270 27	Total factor for the	25,000 50,000 Windows 76 74 65,50 55 102 73 60,50 97,00 97,00	755 1,175 1,175 10,55 9,70 8,80 8 8,40 8,20 8 7,45 7,05	29,455 52,175 52,175 107,75 96,35 81,70 74,30 61 110,40 81,20 52,50 54,95 10,845	3 5

	65 Cooling Towers		241475			Sizina	100			
00.45	5 13 - Farced Draft Cooling Towers		Drify		Desi	Barrel .		ne Costs	Task	Īn
2536	13.10 Forced-Draft Type Cooling Towers	Gren C-7	.6:	Hours 49.23	Unit Sa.	Harer of 29,000	2,200	Equipment	31.200	ind (§) 85,300
2540	300 50			59.759	-	35,400	2,650		36,050	40,701
7544	350 ton	1		58.065		37,700	5,050		40.750	45,100
2548	400 00	and the		78,049	30.4	39,380	3,500	273	-42,800	+3,500
2552	-460 m	1	36	88.154	10.00	47,200	2,950		\$1,250	
2556	500 ron		37	100		53580	4,50		55,000	
2590	550 m		.30	107	31	54,500	4,825		59,325	67,000
2564	ror C03		.27	117		5/,000	5,2%		62,275	20,500
2568	60 m	11	.25	127		43,500	5,725	Î	69,275	78,000
25/2	700 in		.25	137	1	74,500	6,175		80,675	90,000
2575	750 mi		.22	145		79,500	6,600		dá,100	97,500
2590	600 to		21	-157	23	86,500	4,850	200 cm	73,350	
2584	\$50 00 100 100 100 100 100 100 100 100 10	TALK.	. 20	155	0.5	91 500	. 7,690	5-13-2	98,550	111,500
258:	900 to 1		.20	10:	11	47,000	7,290		64,250	117,500
2592	\$504m	12 3 14	119	10	35	002500	1,250	S C A		124,000
2596	°C00°m	+	.15	(0)	÷	105.500	1, 125		113,625	123,000
2700	Adel for, insuces draft									
2/10	50 to	0-6		1C.526	E.	7.000	165	1	9,465	10,600
2720	75 tar		Auto Carlotte	12,785		10.500	695		77,295	17,700
2724	COm			15,673	N.	1,200	465		72,055	13,600
2726	250	767	THE COURT	24.427		3.500	1:100		34,930	16,500
2737	200 to	100000000000000000000000000000000000000		(35,21)	200	73.400 · .	AL67		25,150	
2736	Well in		The second lives of	185,237	31.1	74.4Cff	-	1000	97,630	
2740	300 to			55,255		30,900)	88,450	37,500>
274(330 to:		F-200	65,085		33,000	3,50		38,090	40,500
2748	400 (5*		-11	78,045		37,900	2,500		4 ,300	46,000
2752	450 to	no nanov hadao	36	88.154	4000	42,000	3,550	COLUMN TO THE REAL PROPERTY.	45,950	52,000
2756	5000	1 4 Fe	37	00		44,600	4,500		45,100	55,000
2760	\$50 to		30	107	33	49,800	-2.525		The Control of Control	47,500
2764	600 to		27	27		52.500 57.500	5,175			65,000
2765 1 2772	700 br		23	37	130	65,500	6,175	1010124	and the second second second	87,500
2776	750 to		22	45		58,000	6,500		74,600	84,500
2780	500 to		21	57		71,000	6,550		77,890	83,500
2784	550 to-		20	155		71.500	7,550		78,550	
2705	500 to	sergrand at a	29	61	color!	74,000	1,152	Septiment of the second	5 7 51,250	92/201
2792	750 to		18.19	70	0.3	78,000	1,157		85,650	97,000
2796	C00.rm		18	180		32,500	f, 125		30,675	
3000	For righer caprothes, use multiples		100		920			OTTO STATE		
3532	For points and a ping, and	0.6	36	637	anti.	48	25		76	549
4000	brdiagóa gslars, ött		1	-	v	79:	75%			-
4100	Greing ween charmon treater	0.5	3	5,333	Ez.	292	225	1	518	662
5000	Rosiglass	J-2"						1		0.000
5010	Cowfro	Tory A		105.0		Section 1				7
5100	(Char	Gń.	1,50	16		3,450	705	7	4,155	4,85
5120	25 to	14	.99	24.242	220	7,050	1,075	100	8,125	
5140	300 ton		.43	55,814	47.75.044	76,500	2,450	Start 4	18,950	2 ,353
5163	500 (a)		27	137		29.600	4,600			39,817
5180	1000 mm	+	.15	160	+	51.000	7,025		58,025	65,1.2
6000	Starless stee							1		
6010	Induced draft, courselyse, huriscorted, but if we			i						
6100	57 kg	06	1:50		E.	9.575	705		10,390	1.75
6120	Fi kit	4	.99	24.242	1	3.500	1,575	A CONTRACTOR	14,975	16,917

Water Cooled Chiller Spec Sheet

Page 1 of 2

Southland - Houston Chiller Study RTHD-1			
General	KIHD-I		
Capacity:	Compressor configuration:		
276.00 tons	C2		
Efficiency:	IPLV:		
0.667 kW/ton NPLV:	0.512 kW/ton		
0.549 kW/ton	Evaporator		
Evap configuration:	Evap pressure drop:		
D3	5.50 ft H2O		
Evap leaving temp:	Evap fouling factor:		
42.00 F Evap flow rate:	0.00010 hr-sq ft-deg F/Btu Evap fluid concentration:		
470.90 gpm	0.00 %		
Minimum evap flow rate:	Evap fluid freeze point:		
324.00 gpm	32.00 F		
Evap entering temp:	Evap fluid type: Water		
56.00 F Number of evep passes:	water		
3 Pass	Condenser		
Cond configuration:	Cond fouling factor:		
E3	0.00025 hr-sq ft-deg F/Btu		
Cond entering temp:	Cond fluid concentration:		
85.00 F Cond flow rate:	0.00 % Cond tube type:		
792.80 gpm	Enhanced Fin - Copper		
Cond leaving temp:	Cond water side pressure:		
95.00 F	150psi/10.5Bar Condenser Water		
Number of cond passes:	Pressure Cond fluid type:		
2 Pass Cond pressure drop:	Water		
11.10 ft H2O			
<u>Electrical</u>			
Unit voltage:	Max overcurrent protection:		
460/60/3	600.00 A		
Starter type: Wye-delta	Starter expected inrush: 469.00 A		
Unit power:	Motor locked rotor amps:		
184.00 kW	1453.00 A		
Run load amps:	Max RLA (for starter sizing):		
266.50 A Min circuit ampacity:	364		
333.10 A	Miscellaneous		
Full load sound pressure (ARI Condition):	Shipping weight		
83 dBA	14002.0 lb		
Refrigerant charge (HFC-134a):	ARI certification:		
490.0 lb	ARI certified Rated capacity (ARI):		
Without Oil Cooler	307.30 tons		
ARI certified selection:	Distribution channel:		
Yes	United States		
Operating weight: 15044.0 lb	Pressure vessel code:		
13044.0 ID	ASME Pressure Vessel Code		
Test			
Performance test options:	Factory tolerance test:		
No Performance Test	No performance test		

file://C:\Documents and Settings\tswsh120\Local Settings\Temporary Internet Files\OLK1... 2/21/2010

Cooling Tower Spec Sheet



7400 Coca-Cola Drive Hanover, MD 21076

Phone:-443-561-1600 Fax:-443-561-1601 Web Address: www.chesapeakesys.com Offer of Sale

Reference No. 13643

To: Matt Smiddy

Attn:

Date: 2/19/2010

Business Fax:

Job Name: Penn State Project

Job Engineer:

Thank you for requesting a quotation on the following equipment:

Danfoss Variable Frequency Drive(s)

Evapco Cooling Tower(s)

We are pleased to submit our offer based on the conditions indicated.

[CT-1] Quantity (1) Evapco Cooling Tower(s), Model AT-19-99

276 Ton Induced Draft Counterflow Cooling Tower. CTI Certified to Cool 828 GPM of Water from 95 F to 85 F @ 77 F Entering Wet Bulb Temperature - Qty (1) 20 HP Fan (460/3/60)

Base Price Includes:

- "EVAPCOAT" G-235 Galvanized Construction (Casing & Panels & Basin)
- Stainless Steel Strainers
- PVC EVAPAK Fill & Drift Eliminators (Drift Rate Not To Exceed 0.001% of Recirculation Flow)
- "Sight Tight" PVC Air Inlet Louvers & Screen Design (Prevents Light From Entering the Basin)
- 100% Corrosion Free Water Distribution System
- Solid Backed/Multi-Grooved "Power Band" Belt Drive
- Pillow Block Bearings With a Minimum L-10 Life of 75,000 Hours
- Cast Aluminum Drive Sheaves
- External Motor/Belt Drive Adjustment
- Extended Lubrication Lines
- Internal Working Platform for Service of Water Distribution System and Fan/Motor Drive System
- EVAPCO Thermal Performance Guarantee
- CTI Certified
- IBC Compliant
- 5-Year Motor & Drive Parts Warranty

Note: Motors are Shipped Loose for Field Mounting by Others on 8.5 Wide Units Note: Unless Noted Otherwise All Accessories Ship Loose for Field Installation

Reference No. 13643

Page 1

2/19/2010

Energy Cost Calculations

Cooling Tower/Chiller Energy Cost W-C Chiller: C.667 KW x 276 Ton = 184 KW Cooling Tower: Assume COP 084=> KW/ - 12 -12 -12 = 0871 0.879 KW X 276 Ton = 243 KW Total Energy Usage of New System: 427 KW Total Energy Usage of Old System: 2. Al Chillers @ 1.3 km = 2.6 km x276 Ins = 718/LW Energy Costs: ~100/kw.h in Houston, Tx So each day, 29/724x0.1= \$698/Day Savings Month: \$20,707 Year: \$248,488

Response from General Contractor's Survey

The purpose of this survey is to investigate the interaction of the Pearland Recreation Center and Natatorium project team. This survey has been designed to capture the general contractor's viewpoint.

- 1) If you were to redo the project, would you change the delivery method? If so, what would you change it to and why? If not, what were the advantages of the Design-Bid-Build delivery method chosen? A: The architect & I have spoken often that this should have been a CM @ Risk type contract. That is because of the difficult design features, there have been many small changes to the contract that would be easier to resole if the CM @ Risk method had been used. Typically the CMR anticipates these challenges and has allowances to care for that.
- 2) How frequently did you interact with the designers? A: We meet a minimum of once a week with the architect, and he often visits the site once or twice more during the week to consult with the superintendents.
- 3) How frequently did you interact with the owners? *A: We meet every other week at a progress meeting.*
- 4) What was the most common method of communication with designers? *A: Telephone conversations, with email a close second.*
- 5) What was the most common method of communication with the owners? A: Telephone.
- 6) What are the *main* criteria that were used to select the subcontractors and suppliers? Would you modify any of these criteria if you were to do it over again? *A:* As a hard bid, the primary selection criteria were price, with ability to perform the project second. It is hard to modify this criterion when the project is a hard bid. Selection of a better qualified sub, but at a higher cost might make our bid higher, and thus we would not be the low bidder.

7) What types of contracts were held between the subcontractors/suppliers and general contractor? <i>A: I have attached a sample contract.</i>
8) What language would you add/remove/change in these contracts if you were to do it over again? <i>A: We re content with our current contract.</i>
9) What language was specifically effective? A: We find the duration language, and that the days allowed for various work to run concurrent helps the superintendent to push the project.
10) How frequently were Owner-Architect-Contractor meetings held? Was this frequency adequate? <i>A: Meetings are held every other week. This is adequate.</i>
11) How often would the architect and/or owner representative visit the construction site? A: Owner at least once every other week, and sometimes once a week. The architect is on site a minimum of once a week, and the architect has a construction representative on site every day for at least ½ day.

Response from Owner's Survey

The purpose of this survey is to investigate the interaction of the Pearland Recreation. Center and Natatorium project team. This survey has been designed to capture the owner's viewboint. 1) Why was the Design-Bid-Build delivery method chosen? This is the typical Milland Chasen by the City for
This is the typical Milliard Citisen by the City for Complex projects such as this. 2) If you were to rado the project, would you change the delivery method? If so, why? If not, what were the advantages of the Design-Bid-Build delivery method chosen? No, this method is the best CMAR & DB would not have seved the CAR well for this type a project. Simply big box stores and affice wilding might land flooriselves to other Alexandra See prof #2 3) What main criteria were used to select the designer? - Familiarity with they fonding stakeholder quiet See projects - The estanding of concept of projects working in municipal pojects 4) What would you change in these write tail I you were to ski it over again? None
5) What main criterie were used to school the general contractor? Lough this ended proposal criteria, as attached, future. The The Wildus to Biddl's (pg 1-3) 6) What would you change in these criteria if you were to do it over again? Nove.
7) Did the contract with the contractor and designer contain any specific language requiring interaction between the two parties? It'so, what? There is no can tract between about all the first one of the tractor of designer. The contract is with the owner of specified containation with the owner on contract is with the owner of specified contraction, see attached sec occos what language would you with other agencies, see attached sec occos what language would you without any in the contract if you were to do it over again? Allae
9) How frequently were Owner-Architect-Contractor meetings held? Was this frequency adequate? Meeting one and Birty 2 wasted, or more. frequently if certain & Ciduatina required
10) How often would the architect and/or owner representative visit the construction site? Occurris 19 13 on Site decling, no specified in the con 8v. I tant continued (architect also populate construction manage ment one-signar)

#2 The DBB method allows the designe # owner to review all aspects of the proposed facility before construction starts. The user group of state holder have more time to provide input at all stogges of design.

#-5 Pg/ Instructions to bidders

CITY OF PEARLAND

13. Opening of Bin Proposals

Bid Proposals will be opened and (unless obviously non-responsive) read aloud publicly. An abstract of the amounts of the base Bid Proposals and major alumnates (if any) will be made available to Bidders after the opening of Bid Proposals. Bid Proposals, in their entirety, shall be open for public inspection after the contract is awarded, with the exception of any trade accrets or confidential information contained therein, provided Bidder has expressly identified any specific information contained therein as being trade secrets or confidential information.

14. Bid Proposals to Remain Subject to Acceptance

All Bid Proposals will remain subject to acceptance for sixty (60) days after the day of the Bid Proposal opening, but Owner may, in its sole discretion, release any Bid Proposal and return the bid security prior to that date.

Award of Contract

Owner reserves the right to reject any and all Birt Proposals, to waive any and all informalities not involving price, time or changes in the Worlt and to negotiate confract terms with the Successful Ridder. Owner may reject a bid as non-responsive if: 1) Bidder fails to provide required Bid Security: 2) Bidder improperly or illegibly completes or fails to complete all information required by the Bidding Documents; A) Bidder fails to sign the Bid Proposal or improperly signs the Bid Proposal; 4) Bidder qualifies its Bid Proposal; 5) Bidder tardily or otherwise impreparly submits its Bid Proposal; 6) Bidder fails to submit the Qualifications of Bulder as required under section 3 of these Instructions to Bicileus, or 7) Bid Proposal is officivisc non-responsive. In determining the best value for the Owner, and in determining to whom to award a contract, Owner may consider: 1) purchase price; 2) reputation of the Bidder and Bidder's goods or services; 3) quality of Bidder's gnode or services; 4) extent to which the goods or services meet the Owner's needs, 5) Bidder's past relationship with the Owner, 6) impact on the ability of Owner to comply with laws and rules relating to contracting with historically underetifized businesses. and nonprofit organizations employing persons with disabilities; 7) total longform cost to Owner to acquire Bidder's goods or services; 8) the Qualifications of Bidder; and 9) any other relevant exteria specifically listed in the Bidding Documents. Discrepancies in the multiplication of units of Work and unit prices will be resolved in favor of the unit prices. This reparates between the indicated sum of any column of figures and the correct sum thereof will be resolved in favor of the correct same

15.1.1 For exact Selection Criteria, Refer to "Exhibit A", Sheet 00200-Exhibit A

15.2 In evaluating Bid Proposals, Owner will consider the Qualifications of the Bidders, whether or not the Bid Proposa's comply with the prescribed requirements, and such alternates, unit prices and other data, as may be requested in the Bid Proposal form or prior to the Notice of Award.

01/2009

00200 - 6 of 7

992

Exhibit "A"

SELECTION CRITERIA

DETERMINATION OF SUCCESSIBL RESPONDENT AND AWARD OF CONTRACT

A. In determining the Saleohed Offeron, the Owner will evaluate the information distinct from the Otterer's (Contractor's) Qualification Statement required havein, the information salarified on the Proposal Form, and other selection witerin including, but not be limited to the full afflowing:

	Cutterfa	Source	Souring Procedure	Score	Fector	Total
7.	6636 Proposal	<i>Ггорозаі</i> Риги	Confractor to submit their Competitive Sealed Proposals in the forms included in the Specification Manual, Alternates proposed and Mark-up for Changes, Low Price – 45 pts. For Subsequent Proposeds, the low Proposeds of the shall be divided by the Subrequent Proposeds pureously proposed for the form of the form of the form to get the form.		1	4 5
2	Contractor's Reputation	AIA 305	References in Hounton Area are asked to rate the contractor. 2. Reference responses from Project Owners and A/E's on similar projects. 3. Reference questions on hodget, schedule, reportingly estimation and responsiveness. 4. Record of Chalms incldences and fletgation experiences over the past five years. 5. Record of Chalms incldences and elegation experiences over the past five years. 6. Reputation of Chalms Orders. 8. Neguness an accred as follows: Excellence 10 pts; Very Good = 5 pts; Average = 5 pts; For = 2 pts; Per = 4 pts. 9. Points from include colorances are averaged.	10	1	10
3.	Experience	AIA 305 (type and size)	Gotted number of similar projects in the Houston that fall within a 1/- 25% range of the project hudget. 2. Past aspecience to projects of similar scope, scale, Complexity and type. 3. References in the Houston area if contractor brings appropriate resources (personnel & equipment) to against project completion by contract target end deter Contractor can are point for each parent. 4. On the simulation of 10 points.	<i>10</i>	í	10
4.	Maintananca of Schedule	References	References in Housian Area are assisted whether or not the achieval was met in their penjant. Responses and council as follows: Complete a test of satisfactive overcoming proportionable of complete a few of satisfactive overcoming proportionable of 4 pts. Completed few should be 4 pts. Completed few should be 5 pts. Completed from two weeks behind actionable 4 pts. Completed inner than two weeks behind actionable 4 pts.	5	1	5

00200 + Pxh(bit A)

						P33
5.	Project Yeam	Propose! Information (resumen)	Resumes for Project Manager and Superintendent will cook be assumed and points given to the team for the following: Time in business (for each individual): 10+ ms = 4 c/s; 8 9 yrs = 3 pro; 5-7 yrs = 2 pro; 2-4 yrs = 1 or, and less than 2 yrs = 0 pro. Number of similar projects completed (for each individual): 4 = 4 pro; 3 3 pro; 2 - 2 pro; = 2 pro; 0 = 0 c/s. Time with the Computer (for each individual) 5 = ms = 5 plo; 4 yrs = 4 pro; 3 yrs = 3 pro; 2 yrs = 2 pro; 1 yr = 1 pro and less than 1 yrs = 0 pro. Number of projects completed as a team of the project = 0 pro.	36	0.2778	10
G.	Аррговск	Proposal Information	The Project Plan or Approach proposet. L. Quality and charty of proposet's workplan heduding echedule, logistics/plassing plans, understanding of the work and considivity to oppoling operations in the Community. Responses are scient as follows: Breellent = S pto Very Good = 4 pts; Average = 4 pts; Far = 2 pts; Poor = 6 pts.	5	1	6
7.	Proposed Suncontractors	Proposal Information	The Mejor Subcontractors proposed by Contractor. Oustry of Major Subcontractors listed. By Enriched Major Subcontractors with Projects of Similar cope and style. References in Dension if Sobrontractors bidging appropriate remarker (personnel and equipment) to use the project completion by contract farget and dates. Responses are sourced as follows: Decellent 15 pts; Very Good 14 pts; Average 13 pts; Pair 12 pts; Proj 0 pts. Points from multiple references are averaged.	5	1	5
đ.	Safety Railing	AIA 305	Contractors to provide the Owner with their Experience Modifier Race (RMR). Experience Oxford RMR of 0.30 0.39 = 3 pts; EMR of 0.51 = 0.85 = 5 pts; EMR of 0.52 = 0.39 = 3 pts; Experience Oxford RMR. Experience Oxford RMR.	5	r ·	5
9.	Warcanty	References	References in Houston Area are asked to rate the conteaches, Responses ere social as follows: Exaction: = 5 pts; Very Good: - 4 pts; Area age = 3 pts; Eain = 2 pts; Poen = 0 pts Poents them multiple references are averaged	6	J	.

Total Possible Secre

100

00200 + Exhibit A

		#7
COLY OF PEARLAND	 SPECIAL CONDITIONS OF A	GREEMENT

Section 00800

SPECIAL CONDITIONS OF AGREEMENT

The following Special Conditions modify the General Conditions, Droumont 00700. Where a postion of the General Conditions is mudified or detected by these Special Conditions, the unakened portions of the General Conditions shall remain in effect.

1.01 Add the following paragraph to the end of Article 1.01:

The OWNBRS representative on the project is: Andrea Brinkley, 3501 E. Orange, Phone 281 632-1797.

- 4.23 Add the following Notes at the end of Article 4.23;
 - Contractor shall note that any work in the madways (Sailey Road and Veterans Drive)
 is limited to the bours between 9:00 AM and 2:00 FM.
 - Contractor shall content and contribute work in the readways with the School Hours and Dus times with the Pearland Independent School District.
 - Contractor shall notify BDD #4 (Brazaria Dazinage District) prior to any draining work to be performed in either Springfield Ditch to the North of the property and Cowarts Creek to the south of the property.
 - Contractor shall contact the City of Pearland prior to any work on the new Sanitary Sewer line along Votorana Drive and for any storm sewer outfalls or tie-ins to existing drainage.

09/2007 00800-1ef1

ACADEMIC VITA of Matt Smiddy

Matt Smiddy 137 H. Alley Apt. 201 State College, PA 16801 msmiddy5055@gmail.com

Education: Bachelor of Architectural Engineering, Penn State University, Spring 2010

Bachelor of Arts in Economics, Penn State University, Spring 2010

Honors in Architectural Engineering

Thesis Title: Pearland Recreation Center and Natatorium

Thesis Supervisor: James A. Faust

Related Experience:

Intern, ExxonMobil Development Company (Houston, TX)

05/09 - 08/09

- Re-wrote the Construction Coordination Procedure Pro-Forma for use in all project contracts.
- Assisted in expediting first oil on the Banyu Urip (\$2 B) project in Indonesia
- Created an outline for a Temporary Facilities Global Practice

Intern, The Alexander Building Company (State College, PA)

12/08-5/09

- Led the implementation of Building Information modeling into the company.
- Used a 3-story office building as a prototype

Intern, Facchina-McGaughan LLC. (Miami, FL)

05/07 - 08/07, 05/08 - 08/08

- Assisted in management of construction of concert hall designed by Frank Gehry \$100M
- Assisted in management of construction of 43-Story Condominium project \$130M

Intern, The Whiting-Turner Contracting Company (Miami, FL)

05/06 - 08/06

- Assisted in management of construction of 33-Story Condominium project \$90M
- Bid out 4 scope of works
- Oversaw the project's quality control program, submitting 10 QC reports/week

Research Assistant, Pennsylvania Transportation Institute

03/08 - 12/08

- Assisted in testing bearing capacities of asphalt cores for PENDOT

Teaching Assistant, Penn State University

09/08 - Present

 Coordinated exam and homework grading for 75 students in Environmental Economics and 75 students in Material Science for Civil Engineers courses

BIM Execution Guide Project

09/08 - 12/08

- Created a publicly available guide for using BIM for cost estimating.
- Performed a BIM case study on the New World Symphony Concert Hall

Awards:

Engineer-In-Training Golden Key International Honour Society Schreyer Honors College Scholar 2009 Hettema Leadership Award Recipient Tau Beta Pi Engineering Honor Society Phi Kappa Phi Honor Society Member Phi Alpha Epsilon Honor Society Member

Presentations/Activities:

President and Web Master, Student Chapter of Partnership for Achieving Construction Excellence

Member, 2005-2006 Penn State Men's Varsity Swim Team Member and Web Master, Penn State Water Polo Team President and Web Master, Penn State Club Swim Team

Family Member Chair, Robert J. Smiddy Memorial Scholarship Award Committee

Volunteer, Special Olympics

Envoy, Penn State Engineering Coop & Internship Program