

STEM Building

Science Technology Engineering Mathematics

Hagerstown Community College

Hagerstown, MD



Final Report

Craig Owsiany

Construction Management

Adviser: Robert M. Leicht

April 7, 2011



STEM Building

Science Technology Engineering Mathematics

Hagerstown Community College

Hagerstown, MD 21742

Building Statistics

- Building Cost: \$15.6 M
- Size: 62, 840 sq. ft.
- Time of Construction: 6/4/10-11/30/10
- Delivery Method: Design-Bid- Build

Building Envelope

- Glazed Aluminum Curtain Wall System
- Insulated Glass
- Brick Veneer
- Metal Panels
- Anodized Aluminum Storefront

Mechanical

- One Mechanical Room
- One Custom AHU Provides 37,000 CFMs of Outdoor Air
- Cabinet Unit Heaters and Propeller Unit Heaters
- Chilled Water

Electrical

- 1000 KVA Pad Mount Transformer
- 250 KVA, 277/480V, 3 Phase Generator
- 5 Interior Transformers

Architecture

- Laboratories
- Classrooms
- Faculty Offices
- Computer Rooms



Structural

- CIP Concrete Footings
- Structural Steel Framing System w/ Shear Connections
- Three Concrete Towers for Lateral Bracing

Lighting

- Skylite 2x2, Skylite 2x4
- Verve III
- Skydome
- Avenue 6
- Zylinder Glass



Executive Summary

This report will cover two breadth studies in the structural and mechanical option. They will also investigate areas of critical industry issue research, value engineering analysis, constructability review and schedule acceleration.

These analyses include:

1. Mat Slab Redesign (Lower Mat Slab and Extend Foundation Walls)
2. Green Roof Redesign (Extensive to Intensive)
3. Curtain Wall Redesign (Stick Built to Unitized)

The first analysis will meet the structural breadth and investigate into value engineering and constructability review. This analysis was chosen when it was discovered that competent rock was found at a lower elevation than planned. An alternative method of lowering the footing will be explored in this analysis.

The second analysis will meet the mechanical breadth and research critical industry issues and value engineering. Redesigning the green roof will lead to lower heating and cooling loads which can provide long term saving for the STEM Building. The long term savings and overall load reduction from installing the green roof will be investigated in this analysis. PV panels and green roof as an educational tool will also be analyzed, specifically how information will be relayed to students.

The third analysis of converting the stick built curtain wall system to a unitized curtain wall system will help cover the constructability review and schedule acceleration requirements. A unitized curtain wall system offers a quicker on site construction time and higher quality product.

Table of Contents

Analysis I: Mat Slab Redesign (Lower Mat Slab and Extend Foundation Walls).....	5
A. Background.....	5
B. Goal.....	8
C. Proposed Solution/Mat Slab Redesign.....	11
D. Schedule/Sequence/Coordination.....	14
E. Estimating.....	15
Analysis II: Green Roof Redesign (Extensive to Intensive).....	16
A. Background.....	16
B. Goal.....	16
C. Takeoffs.....	17
D. Proposed Green Roof Design.....	17
E. Schedule/Sequence/Coordination.....	22
F. Roof System Structural Integrity Verification.....	22
G. Estimating.....	23
H. Heating/Cooling Load Reduction.....	24
I. Educational Tool.....	30
Analysis III: Curtain Wall Redesign (Stick Built to Unitized).....	34
A. Background.....	35
B. Goal.....	36
C. Takeoffs.....	36
D. Schedule (Acceleration).....	37
E. Sequencing.....	40
F. Constructability.....	41
G. Coordination.....	42
H. Estimating.....	43

List of Appendices

Appendix A: Stair Shaft 1 Cost Calculations.....44

Appendix B: Live and Dead Load Calculations.....50

Appendix C: ASCE Chapter 2: Combination of Loads, p. 5.....54

Appendix D: Design Information Material Properties.....57

Appendix E: University of Central Florida Green Roof Case Study.....59

Appendix F: Curtain Wall Takeoffs.....63

Appendix G: Crane Locations for Curtain Wall Installation.....66

Appendix H: Accelerated Schedule.....73

Appendix I: Accelerated Schedule Critical Path.....85

I. Footing Redesign (Structural Breadth)

A. Background

Prior to the structural design of the STEM Building, a geotechnical report was performed by Triad Engineering, the contracted geotechnical engineer. A total of “eleven (11) structure test borings and three (3) storm water management test borings” were performed to complete their investigation. It was determined that the subsurface of the proposed site was comprised of mainly limestone bedrock. Triad concluded that all foundations were to sit on competent rock and be designed for a bearing pressure of 8000 psf. See note C.1 taken from structural drawing S001 for reference in Figure 1 below.

C. FOUNDATIONS

1. Foundations shall be bearing on competent limestone bedrock and are designed for a bearing pressure of 8000 psf based on a subsurface exploration program conducted by Triad Engineering and described in report dated June 29, 2009. Contractor shall notify the Geotechnical Engineer before placing any footings.

Figure 1: Structural Drawing S001 Note 1

The boring tests also helped determine the expected elevations of competent rock upon which foundations will bear. The depth of auger refusal was used as the approximation factor to identify such elevation.

Throughout the excavation process, competent rock was discovered at a depth significantly lower than expected in one area in particular; the southwest corner of the building where Stair 1 is located. Below in Figure 2, Stair Shaft 1 is highlighted in blue. See Figure 3 (below Figure 2) for a close up of Stair 1.




Figure 2: Stair Shaft 1 (Blue)




Figure 3: Stair Shaft 1




Figure 4: Stair Shaft 1 Structural Section

Stair shaft 1 was designed to bear on a 4' mat slab at an elevation of 549' (top of slab) above sea level which would place competent rock at 545' ($549' - 4' = 545'$). During the excavation process, non-competent rock was detected at 545', forcing further excavation. Competent rock was finally established at 540'. This circumstance brings forth the question of how to compensate for the over excavation.




Figure 5: Mat Slab (Red)

B. Goal

The overall goal of this analysis is to determine the best means of ratifying the situation at hand, which is over excavation. Items of higher concern are to keep the cost as low as possible and minimize negative impacts on the schedule. A total of three solutions were devised to rectify the problem of over excavation. The next few paragraphs will outline each of the solutions, as well as their pros and cons.

Triad Engineering has recommended the contractor fill over excavated areas back to the design elevation with lean concrete. See Figure 6 below for reference.




Figure 6: Triad Solution

In small areas this would be acceptable, but in this event, the amount of lean concrete needed would be excessive. While this will be the easiest of all three solutions because it requires little to no labor and no formwork, it will concurrently be the most expensive due to the considerable amount of lean concrete necessary. Below are takeoffs performed to show the cost and time of such work in this instance. Implementing this solution would require 38 truckloads of concrete to complete. A further breakdown of the time and materials is provided in Appendix A

	Triad Solution
Time (hrs)	12.5
Material	\$ 23,948.15

Figure 7: Triad Solution Takeoffs

The general contractor has decided to form and place the concrete back to design elevation in order to save on materials. See Figure 7 below for reference.




Figure 8: GC Solution

There are noticeable savings from decreasing materials but there is added formwork and labor that accompanies this solution. This solution would require 27 truckloads to complete. Overall it is cheaper than Triad’s solution but the gain is minimal. See Figure 8 below for the quantity takeoffs performs for materials, labor and time.

	GC Solution
Time (hrs)	8.7
Material	\$ 17,840.25

Figure 9: GC Solution Takeoffs

The third proposed solution is to place a small amount of lean concrete for leveling purposes, and lower the mat slab and foundation to the over excavated elevation. See Figure 9 below for reference.




Figure 10: Proposed Solution

Significant savings will be seen on lean concrete while labor costs will be similar to the GC's solution. On the other hand, normal weight reinforced concrete will be increased but the savings from lean concrete will greatly exceed this addition. Only 2 truck loads will be needed for lean concrete and 6 truck loads for normal weight concrete. Formwork will also be similar to the GC solution. Below are the quantity takeoffs shown for this proposed solution.

	Proposed Solution
Time (hrs)	16.9
Material	\$ 5,609.17

Figure 11: Proposed Solution Takeoffs

C. Proposed Solution/Mat Slab Redesign

After performing preliminary takeoffs for all three solutions, it is clear that the proposed solution is the most cost efficient and yields comparable impact on the schedule. In order to implement the proposed solution, the structural integrity must be checked for the added foundation wall loads. In order to confirm the structural integrity, the current loads bearing on the mat slab must be calculated and added to the extra loads provided by the extended foundation walls. This total load must be compared against the design load. If the actual load is less than the designed load, no further redesign of the mat slab is necessary. If the actual load is greater than the design load, further redesign of the mat slab will take place. It is predicted that the actual load will be less than the design loads. The mat slab currently supports 5 floors and a penthouse; extending the foundation walls 5' will be a minimal load increase compared to the existing loads.

The total load bearing on the footing is divided in dead loads and live loads. The chart below shows a further break down of the items contained in each load division.

Dead Loads	Live Loads
Compacted Soil	Classroom
Concrete (NW & LW)	Corridors at 3 rd Floor & Below
Rebar	Corridors Above 3 rd Floor
Steel Beams	Stairs
Stairs	
Curtain Wall & Metal Panels	
Brick Veneer	
Green Roof	
Ceiling	
Partitions	
Elevator	
HVAC & Plumbing	
Cistern	

The dead loads and live loads were summed using the ASCE (American Society of Civil Engineers) Standard, Chapter 2: Minimum Design Loads for Buildings and Other Structures was specifically used. The mat slab was designed using Section 2.4: Combining Nominal Loads Using Allowable Stress Design because the initial allowing bearing pressure was determined by the geotechnical engineer and the structural engineer is to design to that pressure.

Moving forward, loads were summed floor by floor. In general, the criteria for totaling the loads remained similar. Differences arose in dead loads mainly from the enclosure materials of the building: brick veneer, metal panels and curtain wall. The live loads slightly altered floor by floor as determined by the use of the space and the tributary width of which the stair shaft supported. Total live and dead loads are displayed in Figure 12 below.

Dead Loads	
	Total (lbs)
Compacted Soil (4')	496,100
Concrete-Normal Weight (5")	20,834
Concrete-Normal Weight (10")	728,625
Concrete-Normal Weight (12")	498,075
Concrete-Normal Weight (18")	56,306
Concrete-Normal Weight (20")	34,531
Concrete-Light Weight (4 1/4")	251,828
Beams	30,525
Stairs (20")	305,723
Curtain Wall & Metal Panels	23,460
Brick Veneer	92,576
Green Roof	132,688
Ceiling	28,604
Partitions	56,038
HVAC & Plumbing	57,208
Cistern	31,000
Total	2,844,119

Live Loads	
	Total (lbs)
Corridors 3rd Floor & Below	80,990
Corridors Above 3rd Floor	97,188
Classrooms	105,240
Stairs	122,289
Total	405,706

Figure 12: Stair Shaft 1 Live and Dead Loads

Overall the dead and live loads of the stair shaft come to 2,884,199 pounds and 405,706 pound respectively. The loads from the extended foundation walls will need to be added to these totals and are shown in Figure 13 below.

Dead Loads Total	2,844,119
Live Loads Total	405,706
Extended Foundation Wall Loads	139,750
Dead+Live	3,249,826
Dead +Live+Extended	3,389,576
Percentage Increase	4.12%

Figure 13

As the table shows, the total load on the mat slab increases by 4.12%. To establish if this increase in load would necessitate any redesign, the total load was divided by the area of the mat slab. The results can be seen in Figure 14 below.

Total Load (P)	3,389,576
Area (A)	1,128
P/A (lbs/sf)	3,006

Figure 14

The bearing pressure comes to $3,006 \frac{\text{lbs}}{\text{sf}}$. This is only 38% of the $8000 \frac{\text{lbs}}{\text{sf}}$ design which confirms that the current mat slab design is adequate. The resulting bearing pressure does seem rather low. It is important to note that when designing structural systems, additional load factors exist: earthquake, snow, wind, rain and snow. These factors will add to this bearing pressure but have been neglected from this analysis.

A meeting was set with the structural engineer to verify the results of this analysis. After the goal of the analysis and its results were explained, the structural engineer confirmed that the current mat slab design would support the increased load. He described that a general rule of thumb for determining if redesigning a structural system such as a stair shaft would begin at about 10-15% load increase. He went on further to explain that structural engineers would not design a structural system within 4.12% of its actual load. Therefore the load increase in this analysis was almost negligible so the current mat slab will suffice.

D. Schedule/Sequence/Coordination

In terms of schedule duration, sequencing and coordination, the three solutions are very similar. Durations for each solution may include just concrete pouring time, concrete/formwork time, or concrete/formwork/rebar time but the difference between the three is less than a day. The same sequencing and coordination applies to all three solutions with respect to other trade work.

E. Estimating

The cost of each of the options will have a noticeable difference. Triad’s Solution will be presented first (Figure 15), followed by the GC Solution (Figure 16) and the Proposed Solution (Figure 17). Due to the small size of the spreadsheets, Figure 18 was generated to help view the costs.

Triad Solution Cost									
Materials	LF	\$/LF	Sq. Ft.	\$/Sq. Ft.	CY	\$/CY	Duration	\$/Crew	Total
Concrete					299.3	80			\$ 23,944.00
Total									\$ 23,944.00

Figure 15

GC Solution									
Materials	LF	\$/LF	Sq. Ft.	\$/Sq. Ft.	CY	\$/CY	Duration	\$/Crew	Total
Formwork-Lumber	240	0.3							\$ 72.00
Formwork-Plywood			755	1.41					\$ 1,064.55
Lean Concrete					208.8	80			\$ 16,704.00
Backfill									\$ -
Crew							1	960	\$ 960.00
Total									\$ 18,800.55

Figure 16

Proposed Solution									
Materials	LF	\$/LF	Sq. Ft.	\$/Sq. Ft.	CY	\$/CY	Duration	\$/Crew	Total
Formwork-Lumber	480	0.3							\$ 144.00
Formwork-Plywood			426	1.41					\$ 600.66
Lean Concrete					20.9	80			\$ 1,672.00
Normal Weight Concrete					34.3	92			\$ 3,155.60
Backfill									\$ -
Crew							2	960	\$ 1,920.00
Total									\$ 7,492.26

Figure 17

Totals	
Solution	Cost
Triad	\$ 23,944.00
GC	\$ 18,800.55
Proposed	\$ 7,492.26

Figure 18

As you can see, both the Triad Solution and GC Solution have rather high costs compared to the Proposed Solution. The cost of the proposed solution is far less than that of its competitors at \$7,492, making it the easy choice. A savings of \$16,451 or \$11,308 can be seen by implementing the Proposed Solution.

II. Green Roof Redesign

A. Background

A green roof is being installed on the fifth level of the STEM Building. The area was originally designed to be an aesthetically pleasing area, accessible to students, combining wood panel pavers, concrete tile pavers, stone aggregate and indigenous vegetation. Upon further investigation and a meeting with the owner, it came to light that the area would not be an accessible area for insurance reasons and the school policy/safety plan. In this instance, the current design of the green roof is unjustified.

B. Goal

The Hagerstown Community College regards itself as an outstanding higher education institution and takes great pride in their facilities. They continually look for ways to enhance the learning experience through any means possible. Taking that into account, analysis two will propose to redesign the current green roof and implement an intensive or high profile green roof. The new design will provide heating load reduction in the winter and cooling load reduction in the summer; as well as act as an educational tool.

The heating and cooling load reduction will be performed using the thermodynamic equation for heat flow:

$$\dot{Q} = \frac{A}{R} * \Delta T$$

Equation 1

In order to successfully complete these calculations, it is important to determine whether the materials are in parallel or series. This will affect the R-Value used for the calculation which could drastically change the outcome/results.

Research will be performed to investigate how the green roof can be used as an educational tool. Currently, the green roof will drain into a cistern located on the third floor of the STEM Building. The cistern as a whole can be seen from the 3rd and 4th floor corridors and will have a window to view water levels on the 3rd floor. Although this is one way of relaying information to the students and faculty, analysis two will explore methods of using sensors and monitors to communicate information throughout the entire building. The same sensors and monitors will be taken advantage of for experiments by students in the Alternate Energy Program and Mechanical Engineering Program.

C. Takeoffs

The current design of the green roof features additional architectural facets including concrete pavers, wood pavers and stone aggregate. Shown below in Figure # is the current design layout of the green roof.




Figure 19

The overall roof area of the STEM Building is 15, 816 ft². The green roof accounts for 2022 ft², or 12.8%, of that total which is a relatively low portion. Breaking down the green roof even further into its architectural units, the actual “green” roof reduces even further. Shown below is a breakdown of the square footages and percentages of the green roof.

Green Roof Takeoffs		
	SF	%
Aggregate/Stone Gravel	308	15.2%
Concrete Tile Pavers	542	26.8%
Wood Panel Pavers	396	19.6%
Indegenous Vegetation	776	38.4%
Total SF	2022	100.0%

Figure 20

As you can see, only 38.4% of the green roof is actually “green.” The other 61.4% is comprised of aggregate, concrete pavers and wood pavers. These materials simply do not provide the same thermal properties as the vegetation and are installed for aesthetic purposes only. Although these facets make the green roof “pretty,” they are unnecessary expenses which also bear no educational value. Furthermore, the design intent of the green roof was to be an accessible area for students to eat, relax, study and do homework. Referencing back to a meeting with Dawn Baker, HCC Facilities Project Coordinator, “The green roof is not meant to be accessible to the general student population.” This reveals that a conflict exists between the architect’s design intent and the owner’s usage of the space.

This acquired information acts as the driving factor for the newly proposed green roof design which will be discussed next.

D. Proposed Green Roof Design

The proposed green roof design involves the elimination of the architectural features of the green roof, and replacing the current 3” conventional green roof with a 6” pre-vegetated module system provided by LiveRoof Inc. The new design will cover the entire 5th floor roof, 2022 ft². See Figure 21 below for reference.




Figure 21

The new design, combined with the modern system, offers benefits in schedule duration (installation time), vegetation time, repair and maintenance cost, thermal values and educational advantages.

Before elaborating on the benefits, an overview of the LiveRoof system is in order. The new system is comprised of pre-vegetated modules which replace conventional green roof underlayment materials such as the drainage channel and filter fabric. Images obtained from a LiveRoof brochure comparing a conventional green roof to the LiveRoof system can be viewed in Figure 22 below.




Figure 22

The first benefit arising from the new system is the shortening of installation time. Once the root barrier is installed, the modules will be delivered to the site in specialized trucks. Stacked trays called “HOPPIT”s can be lifted directly from the truck by crane and set on the roof for quick and easy installation. Figure 23 below shows the three simple steps of installation. Total installation time for the green roof of the STEM Building is estimated to be 2 days. A conventional system needs to have the root barrier, drainage board, filter fabric and edge treatment all installed layer by layer prior to placing soil. Additional time is then required to spread and level soil, as well as plant and cultivate seeds and/or bulbs. Although the installation of the green roof is not on the critical path, and therefore will not decrease the overall schedule, it is a bonus to have the flexibility to install the roof in a shortened period.



Figure 23

Owners are always looking for quick building turnover. This leads into the next benefit of the LiveRoof system.

Immediate results are a great advantage the LiveRoof system offers. Unlike the additional months (stuck with a brown roof) required to grow vegetation needed by the conventional system, the LiveRoof modules are pre-vegetated. This means from the minute the modules are set, the vegetation is already grown which immediately reduces the carbon footprint of the building and provides greater insulation on the roof.




Figure 24: LiveRoof System Day 1



Figure 25: Conventional Green Roof System Day 1

Post installation comes the daunting task of upkeep of the green roof. This is another area of major benefit of the LiveRoof System. Traditional roofs, which require several months to cultivate, suffer from displacement due to wind and animal nuisance. Vegetation and its roots bond to the soil to alleviate the risk of wind displacement. Using the pre-vegetated modules mitigates this risk from day one. The second threat is animal nuisance. Birds feed on the seed used to cultivate the soil of a traditional green roof which consequently necessitates additional seeding. Defecation from birds also holds seeds from other plants and weeds which will grow on the traditional green roof if exposed. The proposed system eliminates the wind displacement effect and greatly reduces the chance of weeds. In the event that weeds or unwanted plants begin to grow, the modules can be lifted from the green roof for maintenance or if need be, a new module can be installed.

E. Schedule/Sequencing/Coordination

In terms of schedule, the proposed green roof system carries similar impacts to the conventional green roof. However, minor changes will be seen in the shortening of the installation process and vegetation period. The lead time for a LiveRoof system is a 16 week minimum, considerably higher than the 2-4 conventional green roof lead time. This will be overcome by proper planning.

Coordination and sequencing changes are unnecessary for this activity. Both systems begin with the installation of the root barrier and end with a finished product (or substantially finished product for the conventional roof). The time in between does not require involvement from other trades.

F. Roof System Structural Integrity Verification

A small concern develops in the load increase of the green roof with regard to the structural integrity of the roof. In a meeting with Chris Johnson, Keast & Hood Structural Engineer, this concern was terminated by the design for the green roof. He had explained that when designing the roof system, 12" compacted soil was used to take into account the green roof. Despite the fact that the original design is for a 3" green roof, he explained that it was safer to over design than under design. Per design, compacted soil weighs 110 pcf (factor also used in analysis one) multiplied by the soil depth (12 inches of soil/12 inches in a foot) produces a design load of 110 psf. The maximum weight (saturated weight) of the 6" LiveRoof system is specified to weigh 40-50 psf. The actual weight is only 45% of the design load, which verifies that the current roof system will support the additional load.

G. Estimating

“How much?” The first question every owner asks when making even the slightest change to their building. The LiveRoof system described above is undoubtedly a comparable product to the conventional system, with half the hassle. Without saying, you pay for convenience in today’s society and there is no exception with green roofs. Switching from a conventional green roof to LiveRoof’s pre-vegetated module green roof doubles the upfront cost. Square footage costs were obtained from CitiRoof Inc., a LiveRoof supplier, and compared to costs designated by a case study performed by the University of Wisconsin. You can visit the website at <http://www.glwi.freshwater.uwm.edu/> to reference case study. With the use of simple geometry, the three different payback periods were calculated. See figure 26 below for reference.

Payback Period			
	\$ Markup	\$ Maintenance Savings	Payback Period (years)
Conventional Low-LiveRoof Low	24264	\$ 1,920.90	12.6
Conventional High-LiveRoof High	34374	\$ 3,639.60	9.4
Conventional Low-LiveRoof High	46506	\$ 1,617.60	28.8

Figure 26

As seen above, the payback period with regards to upfront cost versus maintenance savings from switching from a conventional low profile green roof to the high profile LiveRoof system is 28.8 years. This is substantial time considering the average life cycle of a building is 30 years. The most important component to remember is that this calculation is solely upfront cost versus savings on maintenance. This payback period does not take into account the heat transfer reduction provided by the green roof, where the majority of the savings accumulate. That being said, simply switching from a conventional low profile green roof to the LiveRoof high profile system will pay for itself before the end of the building’s lifecycle in maintenance savings alone. Once thermal properties are taken into account and applied to the equations, significant savings will be seen.

H. Heating/Cooling Load Reduction

A green roof is an incredible building feature that offers numerous environmental benefits including:

- Roof Heat Flow/Transfer Reduction
- Storm Water Management
- Carbon Footprint Reduction

This section of the analysis will concentrate mainly on the green roofs ability to reduce heat flow. The original analysis design was intended to be completed with the use of Green Building Studio, a program developed by Autodesk, to determine the heating/cooling load reduction. Unfortunately technical difficulties were experienced when trying to export the .rvt file to a .gbxml and this approach was abandoned.

Lessons learned in AE310 HVAC Fundamentals and ME201 Thermal Sciences will be used to complete this section of the analysis. In particular, the equation for heat transfer will be applied which is shown below in Equation 1 and Equation 2.

$$\dot{Q} = \frac{A}{R} * \Delta T$$

Equation 2

$$\text{Building Heat Loss} = \frac{\text{Total Surface Area}}{\text{Surface Area R - Value}} \times \text{Change in Temperature}$$

Equation 3

The following units will be used for each term:

- $\text{Building Heat Loss} = \frac{\text{BTUs}}{\text{Hr}}$
- $\text{Total Surface Area} = \text{Sq. Ft.}$
- $\text{R - Value} = \frac{\text{Ft}^2 \cdot \text{F} \cdot \text{Hr}}{\text{BTU}}$
- $\text{Change in Temperature} = \text{°F}$

Only the square footage for the fifth floor green roof will be utilized for this analysis. This decision was made in order to help show the effects of the green roof for a localized area of the building. Since the green roof only covers 12.8% of the total roof area, negligible results would be seen if using the total roof area.

First the R-Values will be determined for the conventional building materials and square footages assigned. The R-Values for a conventional roofing system were determined through the specifications and drawings. They are displayed in Figure 27 below.

Conventional Roof	
Material	R-Value
Modified SBS Cap Sheet	0.70
Modified SBS Base-Ply Sheet	0.70
R-30 Insulation	30.00
Decking/Concrete	0.43
Total (BTU/hr)	31.83

Figure 27

Next the change in temperature will need to be determined. Online weather databases and the drawings will be used for this effort. Citing mechanical drawing, M001, in Figure 28 below shows the building design criteria.

BUILDING DESIGN CRITERIA		
<u>INTERIOR:</u>	SUMMER	75°F
	WINTER	68°F
<u>EXTERIOR:</u>	SUMMER	91°F DBT/74°F WBT
	WINTER	10°F
<u>INTERIOR LOAD:</u>	LIGHTING – 1.5 WATTS/SQ. FT. MISCELLANEOUS – 1.0 WATTS/SQ. FT.	
<u>VENTILATION:</u>	ASHRAE 62.1–2007/IMC 2006	
<u>MAX WALL "U" COEFFICIENT:</u>	0.104 BTU/(HR)(SQ. FT.)(DEG. F)	
<u>MAX ROOF "U" COEFFICIENT:</u>	0.048 BTU/(HR)(SQ. FT.)(DEG. F)	
<u>MAX GLASS TRANSMISSION COEFFICIENT:</u>	0.29 BTU/(HR)(SQ. FT.)(DEG. F)	
<u>MAX GLASS SHADING COEFFICIENT:</u>	0.32	

Figure 28

The difference between the interior design temperatures and the actual average temperature will be used for T . The local Hagerstown weather station provides an online database of weather conditions, <http://i4weather.net/index.html>.

AVERAGE SPRING	52.4 F.
AVERAGE SUMMER	73.4 F.
AVERAGE FALL	55.3 F.
AVERAGE WINTER	33.0 F.

Figure 29

Now that all factors are accounted for, heat loss can be calculated. The heat transfer for a total of four roof scenarios will be calculated. The roof scenarios are as follows:

- Conventional Roof
- 3” Architectural Green Roof (current design)
- 6” All Green Roof (proposed design)
- ½ 6” Green Roof, ½ Conventional Roof (educational design)

The first three scenarios were present in my proposal, with the fourth scenario being discovered as part of my research into green building aspects as educational factors.

The first of four calculations for the conventional roof are shown in Figure 30 below.

Conventional Roof				
Materials	Sq. Ft.	R-Value	Summer: Q=A(To-Ti)/R	Winter: Q=A(Ti-To)/R
Modified SBS Cap Sheet	2022.00	0.70		
Modified SBS Base-Ply Sheet	2022.00	0.70		
R-30 Insulation	2022.00	30.00		
Decking/Concrete	2022.00	0.43		
Conventional Roof Total (BTU/hr)	2022.00	31.83	101.66	2223.72

Figure 30

In the summer months, a solar gain of 101.66 BTUs/hr will be seen while a heat loss of 2223.72 BTUs/hr will be experienced in the winter. The noticeable variation in heat transfer between the two seasons arises from the difference of the design temperature to actual average. ΔT for the summer is only 1.6°F while ΔT for the winter is 33°F.

Next the calculations for the current design of the green roof will be presented.

Current Green Roof							
Materials	Sq. Ft.	Lb./Sq. Ft.	R-Value	Conventional Roof R-Value	Total R-Value	Summer: Q=A(To-Ti)/R	Winter: Q=A(Ti-To)/R
Stone Aggregate	308.00	31.25	0.15	31.83	31.98	15.41	337.14
Wood Pavers	396.00	6.13	2.13	31.83	33.95	18.66	408.25
Concrete Pavers	542.00	23.00	0.65	31.83	32.48	26.70	584.14
3" Conventional Green Roof	776.00	23.44	1.43	31.83	33.25	37.34	816.84
Vegetation							
Soil							
Filter Fabric							
Drainage Channel							
Root Barrier							
Architectural Roof Total						98.12	2146.37

Figure 31

ΔT will remain constant through all calculations. However R-values and roof areas will need to be adjusted accordingly. An R-value of .475 per inch will be defined as the standard for the green roof. An important note when dealing with R-values is to properly delineate whether materials are in parallel or series. All the materials in the conventional roof are in series and therefore R-values need to be summed before applying to the heat transfer equation. In the current green roof design, there is a combination of materials in series and parallel. This is why an R-value and Total R-Value column can be seen in Figure 31 above. The architectural green roof will have 98.12 BTUs/hr of heat gain in the summer and 2146.37 BTUs/hr of heat loss in the winter.

The calculations for the proposed green roof design will be presented next. It is expected that the heat transfer allowed by this design will be the lowest of the scenarios. This prediction is based on the detail that this design possesses the largest green area on the roof; see Figure 32 below.

Proposed Green Roof System						
Materials	Sq. Ft.	R-Value	Conventional Roof R-Value	Total R-Value	Summer: $Q=A(T_o-T_i)/R$	Winter: $Q=A(T_i-T_o)/R$
6" LiveRoof System	2022.00	2.85	31.83	34.68	93.30	2040.95
Prevegetated Modules						
Root Barrier						
All Green Roof Total					93.30	2040.95

Figure 32

Figure 32 above, conveniently shows the lowest heat transfer rates of the scenarios presented thus far. Heat gain in the summer equates to 93.3 BTUs/hr and heat loss comes to 2040.95 BTUs/hr in the winter.

The fourth green roof scenario/design consists of half green roof and half conventional roof. Elaboration on this design and its intent will take place in the next section of this analysis: Educational Tools. Only heat transfer calculations will be presented at this point. See Figure 33 below.

New Green Roof Design							
Materials	Sq. Ft.	Lb./Sq. Ft.	R-Value	Conventional Roof R-Value	Total R-Value	Summer: $Q=A(T_o-T_i)/R$	Winter: $Q=A(T_i-T_o)/R$
1/2-6" LiveRoof System	1011.00	46.88	2.85	31.83	34.68	46.65	1020.48
Prevegetated Modules							
Root Barrier							
1/2-Conventional Roof	1011.00				31.83	50.83	1111.86
Educational Roof Total						97.48	2132.34

Figure 33

The heat transfer outcome is obviously less than the proposed green roof because the vegetation is cut in half. However, the heat transfer is still less than that of the conventional roof and architectural roof.

The heat transfer reduction achieved by the green roof scenarios did not meet expectations based on research of case studies and green roof projects. At a minimum, a 25% reduction in heat transfer was desired which is still rather modest. Currently the maximum heat transfer reduction shown by this analysis is 8.2%.

Due to the undesirable outcome of this analysis, areas of possible discrepancy will be investigated and presented at this time.

After much research, it has been determined that the discrepancy with this analysis occurs with the R-value. An R-value is a means of measuring heat flow resistance, and resistance only. This is only one means of how the green roof reduces heat transfer. The vegetation existing on a green roof is a living entity. It does not just sit there resisting heat flow. The plants literally collect, process, and release energy according to their immediate need the same as humans.

Think of the last sunny day when you were outside and began to sweat. This is your body's way of compensating for overheating. You probably proceeded to get a nice cold drink to cool down and replenish. Plants perform in the same way through a process called evapotranspiration. This is the plants means of "sweating" to cool down. Water is sucked from the soil by the roots and transferred to tiny stomatal openings. These microscopic openings allow the plant to release water to cool itself, just like the pores in our skin. So how do you put an R-value on a living organism? You can't.

Plants compensate for heat through convection, radiation and thermal mass. Mathematically, the equations that describe energy transfer through evapotranspiration, convection, radiation, and thermal mass are far beyond my scope of knowledge. This is a task that should be left for the experts to conquer. Shown below in Figure 34 is an image explaining the relationship between the green roof's layers and the different means of energy control.




Figure 34: Image provided by www.greenroofs.com

As you can see, the long pink line represents the conduction heat factor which is accounted for by the R-value. Overall, the analysis performed fails to include the living benefits of the vegetation and its ability to react to its environment. Once these factors are calculated into the equation, sizeable heat flow reductions will be experienced upon which a faster payback period can be determined. For now, placing an R-value alone on a living organism is a faulty means of calculating heat flow but at the same time will still pay for itself before the end of the buildings life cycle.

I. Educational Tool

Photovoltaic (PV) panels and a green roof exist on the STEM Building to act as educational tools for the Hagerstown Community College. With little knowledge of how the information will be relayed to the student body and used within the classroom, research will be conducted to maximize the learning experience. First the green roof will be addressed, followed by the PV panels.

The green roof is installed primarily for aesthetics; offering minimal thermal benefits and minute educational value. So the task at hand becomes answering how the aesthetic green roof will be altered into an educational green roof. As mentioned in the Heating/Cooling Load Reduction section of this analysis, scenario four is presented as the educational design. This design was discovered through R-value research during which a similar study was performed by the University of Central Florida. Appendix F includes the UCF case study.

The educational design proposed delegates half of the roof to be green and half of the roof to be conventional. The usage space below the roof is two classrooms with mirror images; one located beneath the green roof; one located beneath the conventional roof. Heat sensors will be installed on the ceiling of the classrooms and on the roof (under the green roof). Heat readings will be used by Mechanical Engineering students to calculate the heat transfer through the roof. The use of thermal cameras will be used to visually show the student the temperature difference between the roofs. Below in Figure 35, is an example of thermal imaging. This case study was executed by Cleens, Inc.




Figure 35: Cleens Inc. Case Study Thermal Imaging (Singapore)

This green roof was installed in rows while the STEM Building will demonstrate two separate solid areas of green and conventional roof.

The proposed green roof design also allows these sensors to be installed at a later date with minimal cost impact.

Unlike the green roof which was in the design from the schematic design phase, the PV panels were a late addition. A grant was received from the state to fund higher education for the college's Alternate Energy Program. The college has decided to place the PV panels on the green roof. Figure 36 below displays the PV panel location.



Figure 36



Figure 37



Figure 38

A meeting was held with Tony Valente, HCC Alternate Energy Program professor, to gain some insight on the educational value the PV Panels will offer. During this meeting, Tony stated that sensors and monitors will be used throughout the building to relay information to students. Coincidentally this was also presented in my proposal. However it was still unclear as to the software which would be used to complete this task. Tony provided several examples of larger companies offering renewable energy solutions. The company which stood above the rest was Power-One.

Power-One is a worldwide leader in power conversion and power management solutions. Power-One offers many products but my main focus will be geared to their Fat Spaniel software and its implementation into the STEM Building. Fat Spaniel can both record and calculate the energy produced by the PV panels. The software then uses a web based database to communicate the information.

The photovoltaic panels made up of individual cells convert solar radiation into electricity. When the sun shines on the modules, the cells produce a stream of direct current (DC) electricity and send it to an inverter. The inverter converts the DC electricity from the solar array into alternating current (AC) electricity. Most electrical devices such as lights and computers use AC electricity. The electric meter measures electrical energy produced by the PV panels in kilowatt-hours. Electricity generated by the PV panels, combined with the electricity from the electric utility company is then routed to the building.

A data acquisition system combines electrical generation data from the inverter, usage data from the electric panel, air and cell temperatures from a thermistor, and sunlight from a pyranometer. Once collected, the information is published to the internet. Both the pyranometer and thermistor are used to measure the available sunlight, air and cell temperature. Once on the internet, live performance of the energy system can be viewed remotely on any computer with internet access, using Fat Spaniel monitoring and visualization software.

Monitors will be set throughout the STEM Building to view this information through an interactive format. The Fat Spaniel database has links to demonstration websites; one of which can be viewed in Figure 39 below.

ENGLISH 中文 Español 한국어

Welcome to the Queens Botanical Garden Visitor & Administration Building. This is a green building, which means it was designed and built to protect the environment and people's health.

You can use this display to learn about all the things that make our building green. Touch the "Location" button to see a picture of the building and pick out different parts to explore. Or touch the "Theme" button to find out about the different ideas that go into a green building.

You can also learn about parts of the building you can't usually see, like the rooftop Solar Panels or the Geothermal System. You can even find out how much electricity the Solar Panels are making right now!

To begin exploration, touch a button below:

Queens Botanical Garden
Where people, plants, and cultures meet

- About the Garden
- Programs & Events
- What's in Bloom
- Garden Supporters
- Project Team

Don Edikon has provided leadership support to the energy exhibit.

Explore the site by: LOCATION

Go directly to: Solar Energy System, Geothermal System

Energy Generated by Solar Energy System

RIGHT NOW: 2 kWh

LIFETIME: 56,241 kWh

Figure 39

Touch screen monitors will be installed in the STEM Building to allow occupants the ability to browse through the green information similar to the site above.



Figure 40

The Fat Spaniel software can track and display various features such as temperature, greenhouse gases avoided, wind and total energy generated.

III. Curtain Wall Redesign

A. Background

The enclosure of the STEM Building is comprised of three architectural features: brick veneer, metal panels and curtain wall. Each accounts for approximately 1/3 of the envelope. This can be seen in the rendering shown below in Figure 41.



Figure 41

One aspect of the curtain wall, which sets it apart from the brick veneer and metal panels, is its ability to reduce the schedule. This is based on the information obtained in a meeting with the general contractor where it was stated that the curtain wall (also including windows and storefront) is the last activity performed before the building is deemed water tight. Traditionally waterproofing and blue skin would need to be applied to the substrates of the brick veneer and metal panels to achieve a water tight building; but the STEM Building will utilize spray foam insulation which will also act as the water tight seal.

Achieving an earlier water tight date allows the finish trades to access the building sooner. In the same meeting with the general contractor, stacking rough-in and finish trades was determined to be the greatest area for acceleration. Theoretically, stacking trades should double their output. Unfortunately the working space will be dense with activity and efficiency will suffer. Therefore a time savings factor of 1.5 can be used for everyday the finish trades can access the area ahead of schedule. This leads as the basis of design of the analysis and its goals presented next.

B. Goal

Currently the STEM Building construction is set for 18 months from notice to proceed to substantial completion. The substantial completion date will be used for this analysis because it acts as the start date of owner move-in.

In an effort to accelerate the schedule and provide a higher quality product (VE), an analysis will be completed to show the impact of replacing the originally designed stick built curtain wall system with a unitized (modular) curtain wall system. The advantages of the unitized system derive from the more reliable seals achievable from factory construction and the reduced cost of labor in the factory versus that of field labor. Units can be assembled in a factory while the structural frame of the building is being constructed. Where stick systems require multiple steps to erect and seal the wall, unitized curtain walls arrive on the site completely assembled allowing the floors to be closed in more quickly. Unitized systems also require less space on site for layout thus providing an advantage for sites with space limitations.

C. Takeoffs

Quantity takeoffs were performed for the curtain wall to determine the total number of pieces that will need to be set on the STEM Building. These takeoffs also include the exterior windows/storefront as well. Curtain wall was dissected into pieces by rule of thumb that the maximum size allowable based on the 30' x 12' flatbed trucks used to deliver the walls. Floors of the STEM Building elevate by 14.5 feet which allows the subcontractor to prefabricate curtain walls in 2-story spans. Using Microsoft Excel, the total number of curtain wall pieces were totals; reference Figure 42 below.

Curtain Wall Takeoffs	
	Pieces
North Elevation	4
South Elevation	58
East Elevation	8
West Elevation	13
Total	83

Figure 42

Total piece count comes to 83 for the STEM Building with majority of the curtain wall seen on the south elevation. Shown below in Figure 43 is a south view rendering of the STEM Building.




Figure 43

D. Schedule (Acceleration)

Defining the duration of the proposed unitized curtain wall system will be the next step in this analysis. A standard will need to be set relating total of pieces of curtain wall set per crew per day. A visit to the contracted curtain wall subcontractor’s shop, Accent Metals Inc., was performed to establish general guidelines with regard to durations, lead time, cost estimates, means and methods (how the curtain wall is installed) and size of deliveries.

The original duration allotted for the installation of the stick built curtain wall system was 40 days; running from April 14, 2011 to June 17, 2011. This can be seen in Figure 44 below. The same schedule generated in Technical Assignment 2 will be referenced for this analysis but will be displayed in P3; working remotely provided limited access to Microsoft Project.

ENCLOSURE & SITE FINISHES						
SUMMARY ENCLOSURE						
SUM90100	PERIMETER CMU/STUDS/SHEATHING	25	18MAR11	29APR11	1	
SUM90000	ROOF PARAPETS/BLOCKING/DRAINS	15	25MAR11	19APR11	0	
SUM90300	EXTERIOR BRICK FACADE	15	28MAR11	21APR11	1	
SUM90200	ROOFING FOR DRY-IN	15	04APR11	28APR11	0	
SUM90400	INSTALL WINDOWS	25	05APR11	17MAY11	1	
SUM90500	INSTALL CURTAIN WALLS & STOREFRONTS	40	14APR11	17JUN11	2	

- PERIMETER CMU/STUDS/SHEATHING
- ROOF PARAPETS/BLOCKING/DRAINS
- EXTERIOR BRICK FACADE
- ROOFING FOR DRY-IN
- INSTALL WINDOWS
- INSTALL CURTAIN WALLS & STOREFRONTS

Figure 44

The analysis at hand will propose to cut this duration by 50% and show the impacts on the schedule, sequencing and estimating; but first the curtain wall duration needs to be addressed.

Comparing the installation process of a stick built system versus a unitized system is imperative and will be shown in the table below. For this analysis, it is assumed that exterior wall framing and flashing will be installed before delivery of curtain wall materials.

Table 1

Stick Built System	Unitized System
<ol style="list-style-type: none"> 1. Deliver Materials 2. Shakeout 3. Install Sills and Jambs 4. Install Mullions 5. Glaze 6. Caulk 	<ol style="list-style-type: none"> 1. Deliver Modules 2. Set Module 3. Caulk

As seen by showing the two processes side by side, the unitized system takes advantage of prefabricating curtain wall modules, consolidating steps 2-6 of the stick built installation process down to one. The prefabrication process occurs indoors where temperatures are controlled and the risk of weather days eliminated. The stable working environment also allows for higher quality seals and greater cut precision. Once these modules are set in place, caulking is applied around the perimeter for waterproofing and air barrier purposes; presenting the final product.

The downside of the new design is the lengthy lead time. The table below will define lead times as established by the contracted curtain wall subcontractor for both curtain wall systems.

Table 2: Lead Time

Week	Stick Built System	Unitized System
1-6	Obtain materials	Obtain materials
7	Fabricate/Deliver	Fabricate/Deliver
8	Fabricate/Deliver	Fabricate/Deliver
9-12		Fabricate/Deliver

While both systems take equal time to obtain materials, a project the size of the STEM Building would require 4-6 weeks for fabrication and delivery for a unitized system; compared to the 1-2 week fabrication and delivery period of the stick built system. At first site this is a major deterrent of the unitized system; but with proper planning and a proactive approach, lead time does not enter the design intent equation.

Table 3 below will elaborate on the installation process defined in Table 1 and assign durations. Again, durations are based on a meeting with the curtain wall subcontractor. Durations have been reviewed with the GC project manager to verify accuracy. The overlap between Table 2: Lead Time and Table 3: Installation Time occurs over the delivery period. Delivery is displayed in both tables because both fabrication and installation overlap this activity.

Table 3: Installation Time

Week	Stick Built System	Unitized System
1	Deliver/Frame	Deliver/Install/Caulk
2	Deliver/Frame/Dimension	Deliver/Install/Caulk
3	Deliver/Frame/Dimension	Deliver/Install/Caulk
4	Deliver/Frame/Dimension/Glaze/Caulk	Deliver/Install/Caulk
5	Deliver/Frame/Dimension/Glaze/Caulk	
6	Deliver/Frame/Dimension/Glaze/Caulk	
7	Glaze/Caulk	
8	Glaze/Caulk	

Table 3 clearly exhibits the 50% reduction of installation time achieved by the unitized system. To further back up this statement, the total pieces of curtain wall was divided by 20 days. The result came to setting an average 4.15 pieces per day which is more than achievable.

The downfall of the stick built system is the added steps which need to be completed on site before caulking. The stick built system requires field dimensioning for glazing after frames (sills and jambs) are installed. Once ordered, the glazing has its own 2 week lead time. This results in a minimum 3 week period before the first piece of glazing is set. The lead time also adds 2 weeks to the installation time from the last day frames are set. Overall, a general rule of thumb is that the installation time for a unitized curtain wall system is approximately one half that of its stick built competitor.

The curtain wall system must start being designed much earlier in the design process when acceleration plans are the last thought on an architect's and contractor's minds. Through a meeting with the curtain wall subcontractor, it was determined that the lead time for a project of this size would be approximately 12 weeks. This is a substantial increase compared to the standard 6 week lead time which a stick built system offers.

The simple solution to overcome such a lead time is to be proactive and implement the design early in construction. For the STEM Building project, the activity which offers the greatest risk for schedule delays is excavation. The STEM Building rests upon a limestone land mass which brings great difficulty for excavation and uncertainty when determining durations. Looking back at the detailed schedule produced in Technical Assignment 2, the end of excavation is scheduled 12 weeks prior to the installation of curtain wall. Although still a late change in the construction means and methods, the proposed accelerator is entirely feasible.

Remember that cutting the duration of the curtain wall system is just one step in this acceleration process. The main reason of striving for an earlier water tight date is to allow the finish trades earlier access to the building. Where is the benefit of having a water tight building in which finish trades cannot work? The benefit is now lost; potential days saved are left on the table. The next step in this analysis is to take a deeper look into the schedule and determine the trades and activities in need of re-sequencing. Once identified, the objective is to sequence these trades in a fashion to keep pace with the curtain wall installation and in turn, allow the finish trades to start the day after curtain wall completion (aka water tight date).

Preface to Sequencing: In the event that a schedule acceleration plan is necessary to recover time, there is one crucial point to remember when dealing with subcontractors, “Never call the schedule acceleration plan, a schedule acceleration plan!” The first thought that comes to mind when the word “acceleration” is spoken, is money. Subcontractors mold this word to portray that you are pushing them faster than originally planned and they should be compensated. This becomes the job of the GC to take the word “acceleration” and mold it back. Delivery should be along the lines of:

“We are sequencing trades in a manner to produce the maximum output for all involved.”

For the purpose of this analysis, schedule acceleration will still be used. However, in a real world application it is critical to remember that the plan is only as effective as its execution.

E. Sequencing

The sequencing plan will need to work backwards starting with the reduction in curtain wall duration. Since the goal at hand is to allow earlier access to the finish trades, further analysis will look into its predecessors: MEP Rough Ins.

MEP rough ins are now placed on the critical path due to the reduction in curtain wall installation. To remedy this, MEP rough-in activities will need to be brought on site at an earlier date. By reducing the curtain wall duration to 20 days, the MEP rough ins will need to begin a week ahead of schedule.

MEP trades will begin being stacked on the 3rd, 4th and 5th floor for rough ins and finishes. Although this is an unfavorable condition, this was the means of acceleration stated by the GC and provided in the Schedule Acceleration section of Technical Assignment 3.

Overall the schedule will be reduced by 44 days. See Appendix H for the accelerated schedule and Appendix I for the accelerated schedule critical path.

F. Constructability

The installation of the curtain wall system is straightforward: executed elevation by elevation. Installing curtain wall floor by floor was contemplated at first which would allow finish trades even earlier access to the building. This option was quickly discredited when the thought of multiple crews, multiple cranes or multiple crane moves were considered. The cost increase would not justify the schedule acceleration. Returning to the original sequence of installing curtain wall elevation by elevation was selected as the best option.

Installation will begin on the west elevation of the STEM Building and continue counterclockwise to the south elevation where majority of the curtain exists. See Figure 45 for reference below which was modified from the enclosure site plan generated for Technical Assignment Two.




Figure 45: Curtain Wall Crane Starting Location

Six crane moves will be necessary to complete the installation of the curtain wall. Images displaying these locations can be seen in Appendix E. The question may be asked as to why the installation cannot be completed with only four crane moves. The answer is in the means and methods of installation. A crane will be used with suction cups to lift the modules into place. Therefore, the crane must be on the same side of the building as the installation. In addition, installers will be in a bucket lift at the perimeter of the building for installation. Crane picks over workers is an unfavorable situation and should be avoided if possible for safety measures.

The decision to start on the west elevation was determined by the jobsite entrance location. In order to keep crane moves minimal, it is best to have installation commence at the area of where the crane enters the site. The crane will make a full lap around the building and be able to leave the site in the same fashion; completing the curtain wall installation.

G. Coordination

The coordination involved for installing a unitized system is the same as the stick built system. However attention to detail may shift in some areas. One change arises amongst the allowable tolerances of the two systems and their neighboring enclosure materials. The next is site logistics.

Throughout the STEM Building, curtail wall will be set in CMU openings, concrete openings and cold-formed metal framing (exterior metal framing) openings. These materials have a lower tolerance when installing a unitized system compared to the stick built system. The stick built system offers a little more flexibility since the framing is performed in the field where adjustments can be made. The unitized system requires the concrete, CMU and exterior framing to be installed with high precision since all framing is performed in shop where dimension are off of shop drawings.

Site logistics are of higher concern for the unitized system because of site access. First off, a larger truck will need to be used to deliver the modules. A larger crane will also need to be used due to the weight of the system. Both of these factors need to be accounted for to ensure enough site access and staging is available.

H. Estimating

The unitized system proposed in this analysis does, however, bear a higher upfront cost compared to the stick built system. Typically, a unitized system will cost approximately 10% more than a stick built system. This number was generated using knowledge provided by Hess' estimating department and Greg Ramirez, Hess Senior Project Manager for the STEM Building.

The increase in cost is easily justified by the higher quality of the end product and reductions in schedule. Stick built systems have a much greater chance of leakage than the unitized system. The cost of repair will far exceed that of the 10% increase. The even greater benefit lies in the schedule reduction. Each day reduced from the overall schedule is a substantial cost saving to all involved. Finishing a project ahead of schedule can greatly enhance your chances of performing future work for the same owner. Now that you are tried and tested, the owner will feel comfortable using your services again.

Appendix A

Stair Shaft 1 Cost Calculations

• John Alexander from TBH concrete
L 410-848-9030 ext 231

Concrete Prices

Lean \$80 CY 2000 psi - state tax
Normal Weight \$92 4000psi - state tax

- winter service charge \pm \$3 yard
- non chloride accel. 1% added
L 40s & 50's
- L 2%

\$5 per yard \pm per percent

- retarding admixtures

- adding ice to concrete
to keep below 90°

40lb bag in a yard \$12 per bag
\$.30/lb

1 bag lowers a ³ few degrees

How many CY per lift?

Mat Slab Redesign

- Schedule
- Sequencing
- Coordination
- Estimating - savings on concrete
- Structural Breadth - only .02% increase in weight (minimal) - compared to design load

8000 psf for competent rock

? psf for compacted soil

? psf for stone backfill

Cost of lean concrete - ~~128~~ ^{\$80} / CY 2000 psi
Cost of normal weight concrete - ~~192~~ 4000 psi


$$4 \times 55 \times 20.5 = 4510 \text{ ft}^3$$

$$\hookrightarrow 167 \text{ CY}$$

$$1 \text{ CY} = 27 \text{ ft}^3$$

$$5 \times 55 \times 20.5 = 5637.5$$


$$\hookrightarrow 209 \text{ CY}$$



~~Flow~~

Trial Solution

Materials



5' lower
than expected

$$(55+6) \times (20.5+6) \times 5 = 8082.5 / 27 = 299.3$$

~ 300 CY

~~800~~ 300 CY $\times \frac{1 \text{ truck load}}{8 \text{ CY}} = 37.5 \text{ truck loads}$

how many
lifts?

- add winter fee
- ~~add~~ - cold admixtures
- base cost
- time of travel

$$300 \text{ CY} \times \frac{\$126}{1 \text{ CY}} = \$37800$$

Labor Cost -----

24 pieces of 3' plywood

GC Solution

2 levels

3' overexcavate on each side

Materials

2 levels

20.5

4' mat slab

5' lower

than expected

10 pieces of 3' plywood

55'

2 pieces of 4'-3"

Lean

$$20.5 \times 55 \times 5 = 5637.5 / 27 = 208.8 \sim 209 \text{ CY}$$

$$209 \text{ CY} \times \frac{1 \text{ truck load}}{8 \text{ CY}} = 26.125 \sim 27 \text{ truck loads}$$

$$209 \text{ CY} \times \frac{\$126}{1 \text{ CY}} = \$26,334$$

how many lifts

Formwork

plywood, lumber, nails, ties

$$(20.5 \times 2) + 55$$

$$\text{Plywood} \rightarrow (20.5' \times 5' \times 2) + (55' \times 5' \times 2) = 755 \text{ ft}^2 \text{ plywood}$$



$$\text{Lumber} \rightarrow (24 \times 2 \times 3') + (10 \times 2 \times 3') + (8 \times 4.25') = 238 \text{ ft lumber}$$

$$755 \text{ ft}^2 \times \frac{\$1.41}{\text{ft}^2} = \$1064.55$$

$$238 \text{ ft} \times \frac{\$.30}{\text{ft}} = \$71.4$$

Labor Cost ---

Proposed Solution



~~recalculate~~
length ~~~ 125 ft~~

Lean
formwork


$$1' \times 55' \times 20.5' = 1127.5 \text{ ft}^3 / 27 = 42 \text{ CY} / 8 = 5.25 \sim 6$$

$$(55 \times 2) + (0.5 \times 2) = 111 \text{ ft} \times 5 = 555 \text{ ft}^2$$

6 truck loads

$$42 \text{ CY} \times \frac{\$126}{\text{CY}} = \$5292$$

NW
1'-8" foundation
wall



Form work
 $42.583' \times 2 \times 5' = 426 \text{ ft}^2$

1'-6" foundation
wall

$$44.583' \times 8.667' \times 5' = 372 \text{ ft}^3 \times \frac{150 \text{ lbs}}{\text{ft}^3} = 55800 \text{ lbs}$$

$$\text{length} = 10.833' + .667' + 31.25' + .667' + 10.883' + 8.667' + 11' = 74.017'$$

$$74.017' \times 1.5' \times 5' = 555 \text{ ft}^3 \times \frac{150 \text{ lbs}}{\text{ft}^3} = 83250 \text{ lbs}$$

Appendix B

Stair Shaft 1

Live and Dead Load Calculations

1st Floor

Dead Loads					
	Square Feet	Cubic Feet	Load (psf)	Load (pcf)	Total (lbs)
Compacted Soil (4')	1127.5	4510.0	440.0	110.0	496100.0
Concrete-Normal Weight (5")	333.3	138.9	62.5	150.0	20834.0
Concrete-Normal Weight (10")	64.2	930.4	2175.0	150.0	139562.5
Concrete-Normal Weight (12")	42.5	616.3	2175.0	150.0	92437.5
Concrete-Normal Weight (18")	115.5	375.4	487.5	150.0	56306.3
Concrete-Normal Weight (20")	70.8	230.2	487.5	150.0	34531.3
Stairs (20")	222.3	370.6	250.0	150.0	55585.9
Curtain Wall & Metal Panels	100.0		10.0		1000.0
Brick Veneer	1002.0		22.0		22044.0

Live Loads					
	Square Feet	Cubic Feet	Load (psf)	Load (pcf)	Total (lbs)
Stairs	222.3		100.0		22234.4

2nd Floor

Dead Loads					
	Square Feet	Cubic Feet	Load (psf)	Load (pcf)	Total (lbs)
Concrete-Normal Weight (10")	64.2	930.4	2175.0	150.0	139562.5
Concrete-Normal Weight (12")	42.5	616.3	2175.0	150.0	92437.5
Concrete-Light Weight (4 1/4")	404.9		41.3	110.0	16704.1
Beams	404.9		5.0		2024.7
Stairs (20")	222.3		250.0	150.0	55585.9
Curtain Wall & Metal Panels	100.0		10.0		1000.0
Brick Veneer	1002.0		22.0		22044.0
Ceiling	404.9		5.0		2024.7
Partitions	404.9		15.0		6074.2
HVAC & Plumbing	404.9		10.0		4049.5

Live Loads					
	Square Footage	Cubic Feet	Load (psf)	Load (pcf)	Total (lbs)
Corridors 3rd Floor & Below	404.9		100.0		40494.8
Stairs	222.3		100.0		22234.4

STEM BUILDING

3rd Floor

Dead Loads					
	Square Footage	Cubic Feet	Load (psf)	Load (pcf)	Total (lbs)
Concrete-Normal Weight (10")	51.7	749.2	2175.0	150.0	112375.0
Concrete-Normal Weight (12")	36.0	522.0	2175.0	150.0	78300.0
Concrete-Light Weight (4 1/4")	1609.9		41.3	110.0	66410.4
Beams	1609.9		5.0		8049.7
Stairs (20")	222.3		250.0	150.0	55585.9
Curtain Wall & Metal Panels	435.0		10.0		4350.0
Ceiling	1609.9		5.0		8049.7
Partitions	1609.9		15.0		24149.2
HVAC & Plumbing	1609.9		10.0		16099.5
Cistern		500.0		62.0	31000.0

Live Loads					
	Square Feet	Cubic Feet	Load (psf)	Load (pcf)	Total (lbs)
Corridors 3rd Floor & Below	404.9		100.0		40494.8
Classrooms	1315.5		40.0		52620.0
Stairs	222.3		100.0		22234.4

4th Floor

Dead Loads					
	Square Footage	Cubic Feet	Load (psf)	Load (pcf)	Total (lbs)
Concrete-Normal Weight (10")	51.7	749.2	2175.0	150.0	112375.0
Concrete-Normal Weight (12")	36.0	522.0	2175.0	150.0	78300.0
Concrete-Light Weight (4 1/4")	1720.9		41.3	110.0	70989.1
Beams	1720.9		5.0		8604.7
Stairs (20")	222.3		250.0	150.0	55585.9
Curtain Wall & Metal Panels	435.0		10.0		4350.0
Ceiling	1852.9		5.0		9264.7
Partitions	1720.9		15.0		25814.2
HVAC & Plumbing	1852.9		10.0		18529.5

Live Loads					
	Square Feet	Cubic Feet	Load (psf)	Load (pcf)	Total (lbs)
Corridors Above 3rd Floor	404.9		80.0		32395.9
Classrooms	1315.5		40.0		52620.0
Stairs	222.3		100.0		22234.4

5th Floor

Dead Loads					
	Square Footage	Cubic Feet	Load (psf)	Load (pcf)	Total (lbs)
Concrete-Normal Weight (10")	51.7	749.2	2175.0	150.0	112375.0
Concrete-Normal Weight (12")	36.0	522.0	2175.0	150.0	78300.0
Concrete-Light Weight (4 1/4")	1852.9		41.3	110.0	76434.1
Beams	1852.9		5.0		9264.7
Stairs (20")	222.3		250.0	150.0	55585.9
Curtain Wall & Metal Panels	638.0		10.0		6380.0
Brick Veneer	1102.0		22.0		24244.0
Green Roof	1447.5		91.7	110.0	132687.5
Ceiling	1852.9		5.0		9264.7
Partitions	1852.9		15.0		27794.2
HVAC & Plumbing	1852.9		10.0		18529.5

Live Loads					
	Square Footage	Cubic Feet	Load (psf)	Load (pcf)	Total (lbs)
Corridors Above 3rd Floor	404.9		80.0		32395.9
Stairs	222.3		100.0		22234.4

Roof

Dead Loads					
	Square Footage	Cubic Feet	Load (psf)	Load (pcf)	Total (lbs)
Concrete-Normal Weight (10")	51.7	749.2	2175.0	150.0	112375.0
Concrete-Normal Weight (12")	36.0	522.0	2175.0	150.0	78300.0
Concrete-Light Weight (4 1/4")	516.1		41.3	110.0	21290.0
Beams	516.1		5.0		2580.6
Stairs (20")	111.2		250.0	150.0	27793.0
Curtain Wall & Metal Panels	638.0		10.0		6380.0
Brick Veneer	1102.0		22.0		24244.0

Live Loads					
	Square Footage	Cubic Feet	Load (psf)	Load (pcf)	Total (lbs)
Corridors Above 3rd Floor	404.9		80.0		32395.9
Stairs	111.2		100.0		11117.2

Appendix C

ASCE Minimum Design Loads for Buildings and Other Structure

Chapter 2: Combination of Loads

Page 5

ASCE STANDARD

ASCE/SEI
7-05

Includes Supplement No. 1 and Errata

Minimum Design Loads for Buildings and Other Structures

This document uses both the
International System of Units (SI)
and customary units

Chapter 2 COMBINATIONS OF LOADS

2.1 GENERAL

Buildings and other structures shall be designed using the provisions of either Section 2.3 or 2.4. Either Section 2.3 or 2.4 shall be used exclusively for proportioning elements of a particular construction material throughout the structure.

2.2 SYMBOLS AND NOTATION

D = dead load

D_i = weight of ice

E = earthquake load

F = load due to fluids with well-defined pressures and maximum heights

F_a = flood load

H = load due to lateral earth pressure, ground water pressure, or pressure of bulk materials

L = live load

L_r = roof live load

R = rain load

S = snow load

T = self-straining force

W = wind load

W_i = wind-on-ice determined in accordance with Chapter 10

2.3 COMBINING FACTORED LOADS USING STRENGTH DESIGN

2.3.1 Applicability. The load combinations and load factors given in Section 2.3.2 shall be used only in those cases in which they are specifically authorized by the applicable material design standard.

2.3.2 Basic Combinations. Structures, components, and foundations shall be designed so that their design strength equals or exceeds the effects of the factored loads in the following combinations:

1. $1.4(D + F)$
2. $1.2(D + F + T) + 1.6(L + H) + 0.5(L_r \text{ or } S \text{ or } R)$
3. $1.2D + 1.6(L_r \text{ or } S \text{ or } R) + (L \text{ or } 0.8W)$
4. $1.2D + 1.6W + L + 0.5(L_r \text{ or } S \text{ or } R)$
5. $1.2D + 1.0E + L + 0.2S$
6. $0.9D + 1.6W + 1.6H$
7. $0.9D + 1.0E + 1.6H$

EXCEPTIONS:

1. The load factor on L in combinations (3), (4), and (5) is permitted to equal 0.5 for all occupancies in which L_o in Table 4-1 is less than or equal to 100 psf, with the exception of garages or areas occupied as places of public assembly.
2. The load factor on H shall be set equal to zero in combinations (6) and (7) if the structural action due to H counteracts that due to W or E .

Where lateral earth pressure provides resistance to structural actions from other forces, it shall not be included in H but shall be included in the design resistance.

3. In combinations (2), (4), and (5), the companion load S shall be taken as either the flat roof snow load (p_f) or the sloped roof snow load (p_s).

Each relevant strength limit state shall be investigated. Effects of one or more loads not acting shall be investigated. The most unfavorable effects from both wind and earthquake loads shall be investigated, where appropriate, but they need not be considered to act simultaneously. Refer to Section 12.4 for specific definition of the earthquake load effect E .¹

2.3.3 Load Combinations Including Flood Load. When a structure is located in a flood zone (Section 5.3.1), the following load combinations shall be considered:

1. In V-Zones or Coastal A-Zones, $1.6W$ in combinations (4) and (6) shall be replaced by $1.6W + 2.0F_a$.
2. In noncoastal A-Zones, $1.6W$ in combinations (4) and (6) shall be replaced by $0.8W + 1.0F_a$.

2.3.4 Load Combinations Including Atmospheric Ice Loads. When a structure is subjected to atmospheric ice and wind-on-ice loads, the following load combinations shall be considered:

1. $0.5(L_r \text{ or } S \text{ or } R)$ in combination (2) shall be replaced by $0.2D_i + 0.5S$.
2. $1.6W + 0.5(L_r \text{ or } S \text{ or } R)$ in combination (4) shall be replaced by $D_i + W_i + 0.5S$.
3. $1.6W$ in combination (6) shall be replaced by $D_i + W_i$.

2.4 COMBINING NOMINAL LOADS USING ALLOWABLE STRESS DESIGN

2.4.1 Basic Combinations. Loads listed herein shall be considered to act in the following combinations; whichever produces the most unfavorable effect in the building, foundation, or structural member being considered. Effects of one or more loads not acting shall be considered.

1. $D + F$
2. $D + H + F + L + T$
3. $D + H + F + (L_r \text{ or } S \text{ or } R)$
4. $D + H + F + 0.75(L + T) + 0.75(L_r \text{ or } S \text{ or } R)$
5. $D + H + F + (W \text{ or } 0.7E)$
6. $D + H + F + 0.75(W \text{ or } 0.7E) + 0.75L + 0.75(L_r \text{ or } S \text{ or } R)$
7. $0.6D + W + H$
8. $0.6D + 0.7E + H$

Eq. 2
greater
result
than
Eq. 4

will result in greatest load (neglect live roof)

LRFD → NO!
Load Resistant Factor Design

¹ The same E from Section 12.4 is used for both Sections 2.3.2 and 2.4.1. Refer to the Chapter 11 Commentary for the Seismic Provisions.

Appendix D

Design Information Material Properties

APPENDIX B

Design Information Material Properties

Table B.1 Dead Loads for Masonry Walls

Solid Masonry Units	Weight per inch of wall thickness				
Clay Masonry	10 lb./ft ²				
Concrete Masonry Light Weight Medium Weight Normal Weight	5 lb./ft ² 8 lb./ft ² 10 lb./ft ²				
Hollow Masonry Unit (UngROUTed)*	Weight per ft. ² of wall area				
Thickness	4 in.	6 in.	8 in.	10 in.	12 in.
Clay Masonry	22	27	35	43	52
Concrete Masonry Light Weight Medium Weight Normal Weight	18 22 30	21 26 36	28 34 46	33 41 56	37 47 64
Hollow Masonry Units (Fully Grouted)*	Weight per ft. ² of wall area				
Thickness	4 in.	6 in.	8 in.	10 in.	12 in.
Clay Masonry	42	65	90	112	135
Concrete Masonry Light Weight Medium Weight Normal Weight	26 34 43	46 58 71	66 82 91	82 100 119	96 115 140

* For partially grouted masonry, weight of masonry shall be determined on the basis of linear interpolation between hollow units that are ungrouted and fully grouted based on amount of grouting.

Note: 1 in. = 25.4 mm 1 lb/ft² = 4.88 kg/m²

*Curtain Wall - 16 ft
and Metal Panels - 10 p's f
combined*

*Cistern - 110 psf
x total Volume*

Appendix E

Green Roof Case Study

University of Central Florida



Sustainability



Photo 1 (left): Green roof on April 28, 2005. Photo 2 (right): Green roof on Aug. 18, 2005.

Evaluating Green Roof Energy Performance

Summertime data indicate significantly lower peak roof surface temperatures and higher nighttime surface temperatures for the green roof. The maximum average day temperature seen for the conventional roof surface was 130 °F (54 °C) while the maximum average day green roof surface temperature was 91 °F (33 °C), or 39 °F (22 °C) lower than the conventional roof.

By Jeff Sonne

Green or vegetated roofs are becoming more popular in the United States. High profile examples of U.S. green roofs include the Chicago City Hall and Ford Motor Company Dearborn truck plant that has a total green roof area of more than 10 acres (4 ha). Chicago has begun issuing grants to help residential and small commercial building owners install green roofs.

Green roofs have been in use in Europe for centuries and are a more recent phenomenon in the U.S. Germany has emerged as a leader in modern green roof technology and usage where it's estimated that there are more than 800 green roofs that comprise 10% of all flat roofs.^{1,2}

In addition to rainwater runoff reduction and aesthetic benefits, studies have found that green roofs significantly reduce roof surface temperatures and heat flux rates. A study in Toronto found that two green roofs with minimal vegetation reduced peak summertime roof membrane temperatures of a gymnasium by more than 35°F (1.6°C) and summertime heat flow through the roof by 70% to 90% compared with a conventional roof on the same building³. Simulations also indicate cooling load reductions from green roofs ranging from 1% to 25% depending on building specifics and characteristics of the green roof.^{4,5}

This column evaluates a study of a green roof installed on a two-story building addition completed in June

at the University of Central Florida. This project is led by the University of Central Florida's Stormwater Management Academy through a grant from the Florida Department of Environmental Protection. The department, through a U.S. Department of Energy State Energy Program grant, also is funding the author to compare the energy performance of the green and conventional roofs.

One half of this project's 3,300 ft² (307 m²) roof is a conventional, light colored membrane roof (Photos 1 and 2). The project half has the same membrane with a green roof of grasses and small plants covering the project surface. It consists of 6 in. to 8 in. (0.15 m to 0.2 m) of plant media and a variety of primarily native Florida vegetation up to approximately 2





Figure 1 (left): Roof diagram with sensor locations. Figure 2 (right): Building section diagram.




Figure 3: Comparison of average roof surface temperatures.

ft (0.6 m) in height. The green roof is irrigated twice a week for approximately 15 minutes each time, with collected rainwater when available. Roof surface solar reflectance tests were conducted Aug. 18 for the conventional and green roofs according to ASTM Standard E1918-97 methodology.⁶ The conventional and green roof reflectances were found to be 58% and 12%, respectively.

The energy aspects of this study focus on roof temperature and heat flux comparisons between the conventional, light-colored membrane half of the roof and the green roof. Roof geometry and drainage were designed to allow both the conventional and green roofs to have similar “mirror image” insulation levels and corresponding temperature sensor locations as shown in the roof surface and building section diagrams (Figures 1 and 2).

Temperature measurements include the roof surface, bottom of roof deck, interior air and green roof plant media surface. Meteorological measurements include ambient air temperature, total horizontal solar radiation, rainfall, wind speed and wind direction. All sensors are sampled every 15 seconds and mea-




Figure 4: Comparison of average roof heat fluxes.

surements are averaged or totaled every 15 minutes. Monitoring began in July 2005 and will continue through July 2006.

Summertime data indicate significantly lower peak roof surface temperatures and higher nighttime surface temperatures for the green roof. Figure 3 compares the conventional and green roof surface temperatures for each of the six measurement locations (three conventional roof and three green roof) between July 4 and Sept. 1. The maximum average day temperature seen for the conventional roof surface was 130°F (54°C) while the maximum average day green roof surface temperature was 91°F (33°C), or 39°F (22°C) lower than the conventional roof. A significant shift occurs during peak temperature time periods. Peak surface temperatures for the conventional roof occur around 1 p.m. while the peak green roof surface temperatures occur around 10 p.m.

The minimum average roof surface temperature was 71°F (22°C) for the conventional roof and 84°F (29°C) for the green roof. The conventional roof’s lower nighttime temperatures are due to its surface being directly exposed to the night sky while the green roof surface is covered with plants.

Initial heat flux estimates have also been made for each of the six roof measurement locations for the same period. Heat flux is

Location	Approx. R-Value	Avg. Green Roof Flux, Btu/h · ft ²	Avg. Conventional Roof Flux, Btu/h · ft ²
East	38	0.33	0.36
Middle	17	0.53	0.74
West	38	0.31	0.34

Table 1: Average heat flux estimates for July 4, 2005, through Sept. 1, 2005.

calculated from roof surface and bottom of roof deck temperature measurements and estimated insulation R-values, which because of drainage taper, range from approximately R-15 at the drains to R-60 at the east and west ends of each roof. Figure 4 shows roof heat flux rates for the average day. Heat flux rates for the conventional roof peak in the early afternoon at approximately 2.9 Btu/h · ft² (9.15 W/m²) (at the middle sensor location) while the green roof peaks around midnight at approximately 0.6 Btu/h · ft² (1.89 W/m²) (also at the middle sensor location).

Table 1 shows average heat flux rates over the July 4 through September 1 monitored period. The weighted average heat flux rate over the period for the green roof is 0.39 Btu/h · ft² (1.23 W/m²) or 18.3% less than the conventional roof's average heat flux rate of 0.48 Btu/h · ft² (1.51 W/m²), with the most significant differences occurring near the middle of the roofs at the points of lowest insulation.

Estimating building energy use impacts from green roofs is somewhat involved and dependant on individual building characteristics such as size, use, number of stories and roof/attic design. Side-by-side monitoring studies often are further complicated by submetering issues, since it usually is difficult to separate out HVAC power use for sections of the building under the conventional roof vs. sections under the green roof.

As a rough estimate, assuming all heat gain through the roof must be removed by the AC system, an air-conditioning system efficiency of 10 Btu/h (3 W) per Watt (including fan power and distribution losses) and a total roof area of 3,300 ft² (307 m²), the average energy use to remove the additional heat gain from the conventional roof over the monitored summer period is approximately 700 Watt-hours per day.

Most commercial low slope roofs are darker than the conventional roof used in this study.⁷ Thus, if the conventional roof color were more typical, benefits of the green roof would be greater than those seen here. Over time, the green roof's vegetative canopy will continue to spread and likely reduce heat gains while the conventional roof will darken somewhat and absorb more heat. Another solar reflectance test is planned for next summer to document reflectivity changes of both the conventional and green roofs. Additional temperature and heat flux comparisons will also be made at that time to look at corresponding roof performance changes.

References

1. Wark, C.G. and W. Wark. 2003. "Green roof specifications and standards: Establishing an emerging technology." *The Construction Specifier* 56(8).
2. *The Green Roof Research Program at MSU*. Michigan State University. Oct. 28, 2002. Retrieved Nov. 29, 2005. www.hrt.msu.edu/faculty/Rowe/Green_roof.htm.
3. Liu, K. and B. Bass. 2005. "Performance of green roof systems." *Cool Roofing...Cutting Through the Glare Proceedings*. Atlanta, Ga. May.
4. Wong, et. al. 2003. "The effects of rooftop garden on energy consumption of a commercial building in Singapore." *Energy and Buildings* 35:353–364.
5. Christian, J. and T. Petrie. 1996. "Sustainable roofs with real energy savings." *Proceedings of the Sustainable Low-Slope Roofing Workshop*. Oak Ridge, Tenn.
6. ASTM E1918-97, *Standard Test Method for Measuring Solar Reflectance of Horizontal and Low-Sloped Surfaces in the Field*.
7. Cool Roofs. 2006. Retrieved Jan. 9, 2006. www.epa.gov/heatisland/strategies/coolroofs.html.

Jeff Sonne is senior research engineer with the Florida Solar Energy Center, Buildings Research Division, in Cocoa. ●

Advertisement formerly in this space.

Appendix F
Curtain Wall Takeoffs

STEM BUILDING


Curtain Wall Takeoffs-Pieces								
TYPE	A1/A201 SOUTH PARTIAL	C1/A201 SOUTH PARTIAL	A3/A201 EAST PARTIAL	C3/A201 WEST PARTIAL	A1/A202 NORTH	C1/A202 WEST	C3/A202 EAST	PIECES
W1A						1		1
W1B	2							2
W2	1							1
W3	3							3
W4A	4							4
W4B		6						6
W5A						3		3
W5B	1							1
W6A			6					6
W6B	1							1
W9						2		2
W10					4			4
W11							1	1
W12	2							2
W13	1							1
W13A			6			6		12
W13B			1			1		2
W14		4		2			2	8
W14B							2	2
W15		2		1			1	4
W16		2					1	3
W17		5		1				6
W18							1	1
W19				1				1
W20		2						2
W21		2						2
W22		2						2
Total	15	25	13	5	4	13	8	83

STEM BUILDING

Curtain Wall Takeoffs-SF										
TYPE	SF	A1/A201 SOUTH PARTIAL	C1/A201 SOUTH PARTIAL	A3/A201 EAST PARTIAL	C3/A201 WEST PARTIAL	A1/A202 NORTH	C1/A202 WEST	C3/A202 EAST	TOTAL PIECES	TOTAL SF
W1A	493.2						1		1	493.2
W1B	376.8	1							1	376.8
W2	101.2	1							1	101.2
W3	654.1	1							1	654.1
W4A	602	1							1	602
W4B	1268.5		1						1	1268.5
W5A	616.6						1		1	616.6
W5B	199.3	1							1	199.3
W6A	616.6			1					1	616.6
W6B	199.3	1							1	199.3
W9	440.1						1		1	440.1
W10	888.3					1			1	888.3
W11	186.7							1	1	186.7
W12	215	1							1	215
W13	201.7	1							1	201.7
W13A	5.4			6			6		12	64.8
W13B	5.4			1			1		2	10.8
W14	31.3		4		2			2	8	250.4
W14B	31.3							2	2	62.6
W15	62.5		2		1			1	4	250
W16	93.8		2					1	3	281.4
W17	93.8		5		1				6	562.8
W18	125							1	1	125
W19	125				1				1	125
W20	156.3		1						1	156.3
W21	156.3		1						1	156.3
W22	156.3		1						1	156.3
Total										9261.1


Appendix G

Crane Locations for Curtain Wall Installation



GENERAL NOTES

- TAX MAP BLOCK 516, PARCELS 27-30, 31-34, 35-38, 39-42, 43-46, 47-50, 51-54, 55-58, 59-62, 63-66, 67-70, 71-74, 75-78, 79-82, 83-86, 87-90, 91-94, 95-98, 99-102, 103-106, 107-110, 111-114, 115-118, 119-122, 123-126, 127-130, 131-134, 135-138, 139-142, 143-146, 147-150, 151-154, 155-158, 159-162, 163-166, 167-170, 171-174, 175-178, 179-182, 183-186, 187-190, 191-194, 195-198, 199-202, 203-206, 207-210, 211-214, 215-218, 219-222, 223-226, 227-230, 231-234, 235-238, 239-242, 243-246, 247-250, 251-254, 255-258, 259-262, 263-266, 267-270, 271-274, 275-278, 279-282, 283-286, 287-290, 291-294, 295-298, 299-302, 303-306, 307-310, 311-314, 315-318, 319-322, 323-326, 327-330, 331-334, 335-338, 339-342, 343-346, 347-350, 351-354, 355-358, 359-362, 363-366, 367-370, 371-374, 375-378, 379-382, 383-386, 387-390, 391-394, 395-398, 399-402, 403-406, 407-410, 411-414, 415-418, 419-422, 423-426, 427-430, 431-434, 435-438, 439-442, 443-446, 447-450, 451-454, 455-458, 459-462, 463-466, 467-470, 471-474, 475-478, 479-482, 483-486, 487-490, 491-494, 495-498, 499-502, 503-506, 507-510, 511-514, 515-518, 519-522, 523-526, 527-530, 531-534, 535-538, 539-542, 543-546, 547-550, 551-554, 555-558, 559-562, 563-566, 567-570, 571-574, 575-578, 579-582, 583-586, 587-590, 591-594, 595-598, 599-602, 603-606, 607-610, 611-614, 615-618, 619-622, 623-626, 627-630, 631-634, 635-638, 639-642, 643-646, 647-650, 651-654, 655-658, 659-662, 663-666, 667-670, 671-674, 675-678, 679-682, 683-686, 687-690, 691-694, 695-698, 699-702, 703-706, 707-710, 711-714, 715-718, 719-722, 723-726, 727-730, 731-734, 735-738, 739-742, 743-746, 747-750, 751-754, 755-758, 759-762, 763-766, 767-770, 771-774, 775-778, 779-782, 783-786, 787-790, 791-794, 795-798, 799-802, 803-806, 807-810, 811-814, 815-818, 819-822, 823-826, 827-830, 831-834, 835-838, 839-842, 843-846, 847-850, 851-854, 855-858, 859-862, 863-866, 867-870, 871-874, 875-878, 879-882, 883-886, 887-890, 891-894, 895-898, 899-902, 903-906, 907-910, 911-914, 915-918, 919-922, 923-926, 927-930, 931-934, 935-938, 939-942, 943-946, 947-950, 951-954, 955-958, 959-962, 963-966, 967-970, 971-974, 975-978, 979-982, 983-986, 987-990, 991-994, 995-998, 999-1002, 1003-1006, 1007-1010, 1011-1014, 1015-1018, 1019-1022, 1023-1026, 1027-1030, 1031-1034, 1035-1038, 1039-1042, 1043-1046, 1047-1050, 1051-1054, 1055-1058, 1059-1062, 1063-1066, 1067-1070, 1071-1074, 1075-1078, 1079-1082, 1083-1086, 1087-1090, 1091-1094, 1095-1098, 1099-1102, 1103-1106, 1107-1110, 1111-1114, 1115-1118, 1119-1122, 1123-1126, 1127-1130, 1131-1134, 1135-1138, 1139-1142, 1143-1146, 1147-1150, 1151-1154, 1155-1158, 1159-1162, 1163-1166, 1167-1170, 1171-1174, 1175-1178, 1179-1182, 1183-1186, 1187-1190, 1191-1194, 1195-1198, 1199-1202, 1203-1206, 1207-1210, 1211-1214, 1215-1218, 1219-1222, 1223-1226, 1227-1230, 1231-1234, 1235-1238, 1239-1242, 1243-1246, 1247-1250, 1251-1254, 1255-1258, 1259-1262, 1263-1266, 1267-1270, 1271-1274, 1275-1278, 1279-1282, 1283-1286, 1287-1290, 1291-1294, 1295-1298, 1299-1302, 1303-1306, 1307-1310, 1311-1314, 1315-1318, 1319-1322, 1323-1326, 1327-1330, 1331-1334, 1335-1338, 1339-1342, 1343-1346, 1347-1350, 1351-1354, 1355-1358, 1359-1362, 1363-1366, 1367-1370, 1371-1374, 1375-1378, 1379-1382, 1383-1386, 1387-1390, 1391-1394, 1395-1398, 1399-1402, 1403-1406, 1407-1410, 1411-1414, 1415-1418, 1419-1422, 1423-1426, 1427-1430, 1431-1434, 1435-1438, 1439-1442, 1443-1446, 1447-1450, 1451-1454, 1455-1458, 1459-1462, 1463-1466, 1467-1470, 1471-1474, 1475-1478, 1479-1482, 1483-1486, 1487-1490, 1491-1494, 1495-1498, 1499-1502, 1503-1506, 1507-1510, 1511-1514, 1515-1518, 1519-1522, 1523-1526, 1527-1530, 1531-1534, 1535-1538, 1539-1542, 1543-1546, 1547-1550, 1551-1554, 1555-1558, 1559-1562, 1563-1566, 1567-1570, 1571-1574, 1575-1578, 1579-1582, 1583-1586, 1587-1590, 1591-1594, 1595-1598, 1599-1602, 1603-1606, 1607-1610, 1611-1614, 1615-1618, 1619-1622, 1623-1626, 1627-1630, 1631-1634, 1635-1638, 1639-1642, 1643-1646, 1647-1650, 1651-1654, 1655-1658, 1659-1662, 1663-1666, 1667-1670, 1671-1674, 1675-1678, 1679-1682, 1683-1686, 1687-1690, 1691-1694, 1695-1698, 1699-1702, 1703-1706, 1707-1710, 1711-1714, 1715-1718, 1719-1722, 1723-1726, 1727-1730, 1731-1734, 1735-1738, 1739-1742, 1743-1746, 1747-1750, 1751-1754, 1755-1758, 1759-1762, 1763-1766, 1767-1770, 1771-1774, 1775-1778, 1779-1782, 1783-1786, 1787-1790, 1791-1794, 1795-1798, 1799-1802, 1803-1806, 1807-1810, 1811-1814, 1815-1818, 1819-1822, 1823-1826, 1827-1830, 1831-1834, 1835-1838, 1839-1842, 1843-1846, 1847-1850, 1851-1854, 1855-1858, 1859-1862, 1863-1866, 1867-1870, 1871-1874, 1875-1878, 1879-1882, 1883-1886, 1887-1890, 1891-1894, 1895-1898, 1899-1902, 1903-1906, 1907-1910, 1911-1914, 1915-1918, 1919-1922, 1923-1926, 1927-1930, 1931-1934, 1935-1938, 1939-1942, 1943-1946, 1947-1950, 1951-1954, 1955-1958, 1959-1962, 1963-1966, 1967-1970, 1971-1974, 1975-1978, 1979-1982, 1983-1986, 1987-1990, 1991-1994, 1995-1998, 1999-2002, 2003-2006, 2007-2010, 2011-2014, 2015-2018, 2019-2022, 2023-2026, 2027-2030, 2031-2034, 2035-2038, 2039-2042, 2043-2046, 2047-2050, 2051-2054, 2055-2058, 2059-2062, 2063-2066, 2067-2070, 2071-2074, 2075-2078, 2079-2082, 2083-2086, 2087-2090, 2091-2094, 2095-2098, 2099-2102, 2103-2106, 2107-2110, 2111-2114, 2115-2118, 2119-2122, 2123-2126, 2127-2130, 2131-2134, 2135-2138, 2139-2142, 2143-2146, 2147-2150, 2151-2154, 2155-2158, 2159-2162, 2163-2166, 2167-2170, 2171-2174, 2175-2178, 2179-2182, 2183-2186, 2187-2190, 2191-2194, 2195-2198, 2199-2202, 2203-2206, 2207-2210, 2211-2214, 2215-2218, 2219-2222, 2223-2226, 2227-2230, 2231-2234, 2235-2238, 2239-2242, 2243-2246, 2247-2250, 2251-2254, 2255-2258, 2259-2262, 2263-2266, 2267-2270, 2271-2274, 2275-2278, 2279-2282, 2283-2286, 2287-2290, 2291-2294, 2295-2298, 2299-2302, 2303-2306, 2307-2310, 2311-2314, 2315-2318, 2319-2322, 2323-2326, 2327-2330, 2331-2334, 2335-2338, 2339-2342, 2343-2346, 2347-2350, 2351-2354, 2355-2358, 2359-2362, 2363-2366, 2367-2370, 2371-2374, 2375-2378, 2379-2382, 2383-2386, 2387-2390, 2391-2394, 2395-2398, 2399-2402, 2403-2406, 2407-2410, 2411-2414, 2415-2418, 2419-2422, 2423-2426, 2427-2430, 2431-2434, 2435-2438, 2439-2442, 2443-2446, 2447-2450, 2451-2454, 2455-2458, 2459-2462, 2463-2466, 2467-2470, 2471-2474, 2475-2478, 2479-2482, 2483-2486, 2487-2490, 2491-2494, 2495-2498, 2499-2502, 2503-2506, 2507-2510, 2511-2514, 2515-2518, 2519-2522, 2523-2526, 2527-2530, 2531-2534, 2535-2538, 2539-2542, 2543-2546, 2547-2550, 2551-2554, 2555-2558, 2559-2562, 2563-2566, 2567-2570, 2571-2574, 2575-2578, 2579-2582, 2583-2586, 2587-2590, 2591-2594, 2595-2598, 2599-2602, 2603-2606, 2607-2610, 2611-2614, 2615-2618, 2619-2622, 2623-2626, 2627-2630, 2631-2634, 2635-2638, 2639-2642, 2643-2646, 2647-2650, 2651-2654, 2655-2658, 2659-2662, 2663-2666, 2667-2670, 2671-2674, 2675-2678, 2679-2682, 2683-2686, 2687-2690, 2691-2694, 2695-2698, 2699-2702, 2703-2706, 2707-2710, 2711-2714, 2715-2718, 2719-2722, 2723-2726, 2727-2730, 2731-2734, 2735-2738, 2739-2742, 2743-2746, 2747-2750, 2751-2754, 2755-2758, 2759-2762, 2763-2766, 2767-2770, 2771-2774, 2775-2778, 2779-2782, 2783-2786, 2787-2790, 2791-2794, 2795-2798, 2799-2802, 2803-2806, 2807-2810, 2811-2814, 2815-2818, 2819-2822, 2823-2826, 2827-2830, 2831-2834, 2835-2838, 2839-2842, 2843-2846, 2847-2850, 2851-2854, 2855-2858, 2859-2862, 2863-2866, 2867-2870, 2871-2874, 2875-2878, 2879-2882, 2883-2886, 2887-2890, 2891-2894, 2895-2898, 2899-2902, 2903-2906, 2907-2910, 2911-2914, 2915-2918, 2919-2922, 2923-2926, 2927-2930, 2931-2934, 2935-2938, 2939-2942, 2943-2946, 2947-2950, 2951-2954, 2955-2958, 2959-2962, 2963-2966, 2967-2970, 2971-2974, 2975-2978, 2979-2982, 2983-2986, 2987-2990, 2991-2994, 2995-2998, 2999-3002, 3003-3006, 3007-3010, 3011-3014, 3015-3018, 3019-3022, 3023-3026, 3027-3030, 3031-3034, 3035-3038, 3039-3042, 3043-3046, 3047-3050, 3051-3054, 3055-3058, 3059-3062, 3063-3066, 3067-3070, 3071-3074, 3075-3078, 3079-3082, 3083-3086, 3087-3090, 3091-3094, 3095-3098, 3099-3102, 3103-3106, 3107-3110, 3111-3114, 3115-3118, 3119-3122, 3123-3126, 3127-3130, 3131-3134, 3135-3138, 3139-3142, 3143-3146, 3147-3150, 3151-3154, 3155-3158, 3159-3162, 3163-3166, 3167-3170, 3171-3174, 3175-3178, 3179-3182, 3183-3186, 3187-3190, 3191-3194, 3195-3198, 3199-3202, 3203-3206, 3207-3210, 3211-3214, 3215-3218, 3219-3222, 3223-3226, 3227-3230, 3231-3234, 3235-3238, 3239-3242, 3243-3246, 3247-3250, 3251-3254, 3255-3258, 3259-3262, 3263-3266, 3267-3270, 3271-3274, 3275-3278, 3279-3282, 3283-3286, 3287-3290, 3291-3294, 3295-3298, 3299-3302, 3303-3306, 3307-3310, 3311-3314, 3315-3318, 3319-3322, 3323-3326, 3327-3330, 3331-3334, 3335-3338, 3339-3342, 3343-3346, 3347-3350, 3351-3354, 3355-3358, 3359-3362, 3363-3366, 3367-3370, 3371-3374, 3375-3378, 3379-3382, 3383-3386, 3387-3390, 3391-3394, 3395-3398, 3399-3402, 3403-3406, 3407-3410, 3411-3414, 3415-3418, 3419-3422, 3423-3426, 3427-3430, 3431-3434, 3435-3438, 3439-3442, 3443-3446, 3447-3450, 3451-3454, 3455-3458, 3459-3462, 3463-3466, 3467-3470, 3471-3474, 3475-3478, 3479-3482, 3483-3486, 3487-3490, 3491-3494, 3495-3498, 3499-3502, 3503-3506, 3507-3510, 3511-3514, 3515-3518, 3519-3522, 3523-3526, 3527-3530, 3531-3534, 3535-3538, 3539-3542, 3543-3546, 3547-3550, 3551-3554, 3555-3558, 3559-3562, 3563-3566, 3567-3570, 3571-3574, 3575-3578, 3579-3582, 3583-3586, 3587-3590, 3591-3594, 3595-3598, 3599-3602, 3603-3606, 3607-3610, 3611-3614, 3615-3618, 3619-3622, 3623-3626, 3627-3630, 3631-3634, 3635-3638, 3639-3642, 3643-3646, 3647-3650, 3651-3654, 3655-3658, 3659-3662, 3663-3666, 3667-3670, 3671-3674, 3675-3678, 3679-3682, 3683-3686, 3687-3690, 3691-3694, 3695-3698, 3699-3702, 3703-3706, 3707-3710, 3711-3714, 3715-3718, 3719-3722, 3723-3726, 3727-3730, 3731-3734, 3735-3738, 3739-3742, 3743-3746, 3747-3750, 3751-3754, 3755-3758, 3759-3762, 3763-3766, 3767-3770, 3771-3774, 3775-3778, 3779-3782, 3783-3786, 3787-3790, 3791-3794, 3795-3798, 3799-3802, 3803-3806, 3807-3810, 3811-3814, 3815-3818, 3819-3822, 3823-3826, 3827-3830, 3831-3834, 3835-3838, 3839-3842, 3843-3846, 3847-3850, 3851-3854, 3855-3858, 3859-3862, 3863-3866, 3867-3870, 3871-3874, 3875-3878, 3879-3882, 3883-3886, 3887-3890, 3891-3894, 3895-3898, 3899-3902, 3903-3906, 3907-3910, 3911-3914, 3915-3918, 3919-3922, 3923-3926, 3927-3930, 3931-3934, 3935-3938, 3939-3942, 3943-3946, 3947-3950, 3951-3954, 3955-3958, 3959-3962, 3963-3966, 3967-3970, 3971-3974, 3975-3978, 3979-3982, 3983-3986, 3987-3990, 3991-3994, 3995-3998, 3999-4002, 4003-4006, 4007-4010, 4011-4014, 4015-4018, 4019-4022, 4023-4026, 4027-4030, 4031-4034, 4035-4038, 4039-4042, 4043-4046, 4047-4050, 4051-4054, 4055-4058, 4059-4062, 4063-4066, 4067-4070, 4071-4074, 4075-4078, 4079-4082, 4083-4086, 4087-4090, 4091-4094, 4095-4098, 4099-4102, 4103-4106, 4107-4110, 4111-4114, 4115-4118, 4119-4122, 4123-4126, 4127-4130, 4131-4134, 4135-4138, 4139-4142, 4143-4146, 4147-4150, 4151-4154, 4155-4158, 4159-4162, 4163-4166, 4167-4170, 4171-4174, 4175-4178, 4179-4182, 4183-4186, 4187-4190, 4191-4194, 4195-4198, 4199-4202, 4203-4206, 4207-4210, 4211-4214, 4215-4218, 4219-4222, 4223-4226, 4227-4230, 4231-4234, 4235-4238, 4239-4242, 4243-4246, 4247-4250, 4251-4254, 4255-4258, 4259-4262, 4263-4266, 4267-4270, 4271-4274, 4275-4278, 4279-4282, 4283-4286, 4287-4290, 4291-4294, 4295-4298, 4299-4302, 4303-4306, 4307-4310, 4311-4314, 4315-4318, 4319-4322, 4323-4326, 4327-4330, 4331-4334, 4335-4338, 4339-4342, 4343-4346, 4347-4350, 4351-4354, 4355-4358, 4359-4362, 4363-4366, 4367-4370, 4371-4374, 4375-4378, 4379-4382, 4383-4386, 4387-4390, 4391-4394, 4395-4398, 4399-4402, 4403-4406, 4407-4410, 4411-4414, 4415-4418, 4419-4422, 4423-4426, 4427-4430, 4431-4434, 4435-4438, 4439-4442, 4443-4446, 4447-4450, 4451-4454, 4455-4458, 4459-4462, 4463-4466, 4467-4470, 4471-4474, 4475-4478, 4479-4482, 4483-4486, 4487-4490, 4491-4494, 4495-4498, 4499-4502, 4503-4506, 4507-4510, 4511-4514, 4515-4518, 4519-4522, 4523-4526, 4527-4530, 4531-4534, 4535-4538, 4539-4542, 4543-4546, 4547-4550, 4551-4554, 4555-4558, 4559-4562, 4563-4566, 4567-4570, 4571-4574, 4575-4578, 4579-4582, 4583-4586, 4587-4590, 4591-4594, 4595-4598, 4599-4602, 4603-4606, 4607-4610, 4611-4614, 4615-4618, 4619-4622, 4623-4626, 4627-4630, 4631-



- GENERAL NOTES**
- TAX MAP 98, BLOCK 10, PARCELS 2P
 - SEE REFERENCES AND AREAS
 - PARCELS 2P, 2, 1817 & 18, AND 1, 1853 F.1
 - TOTAL COMMUNITY COLLEGE LANDS = 317,879.9 ACRES
 - ELECTION DISTRICT NO. 10
 - ZONING
 - MAIN CAMPUS BUILDINGS ARE ZONED 'R8' - RESIDENTIAL, SUBURBAN DISTRICT
 - MAIN AREA CONTAINS A RETAIL FEEL, APARTMENTS AND BATHHOUSES IS ZONED 'M' - AGRICULTURAL DISTRICT
 - EXISTING AND PROPOSED USE IS A PUBLIC COLLEGE AND A DAY CARE CENTER, BOTH OF WHICH ARE PERMITTED USES IN THE 'M' AND 'R8' DISTRICTS
 - PROJECT LINES SHOWN HEREON ARE FROM EXISTING TRAIL TO BOUNDARY SURVEY OF THE LANDS OF HAGERSTOWN COMMUNITY COLLEGE PREPARED BY TRIM ENGINEERING, INC. DATED 05-10-07 AND RECORDS AT THE LAND RECORDS OF WASHINGTON COUNTY AS SET FORTH IN PLAT BOOKS 186, 187 AND 188. THIS SURVEY IS REFERENCED TO A FULL SURVEY, SIMPLIFIED PLAN OF SUBDIVISION OF PARCELS, BY JOHN YOUNG, DATED APRIL 3, 1998, AND RECORDED AMONG THE LAND RECORDS OF WASHINGTON COUNTY, BEYLAND 183-187.
 - IMPROVEMENTS AND CONTOURS SHOWN HEREON ARE FROM AERIAL MAPPING PROVIDED BY WINGE AERIAL MAPPING COMPANY, DATED OCTOBER, 1999. VERTICAL DATUM WAS ADJUSTED. BOUNDARY OF THIS PLAN IS FOR CONSTRUCTING A HIGH SCHOOL AND MATHEMATICS BUILDING.
 - MINIMUM SETBACKS FOR SECTIONS 6.1 AND 7.5 OF THE WASHINGTON COUNTY ZONING ORDINANCE.

LOT AREA	LOT WIDTH	FRONT YARD DEPTH	SIDE YARD DEPTH	REAR YARD DEPTH	MAX. BUILDING HEIGHT
15.4C	396'	100'	25'	25'	25' TO 30' OR LESS OR AS SHOWN

PARKING CATEGORY	REQUIREMENT	REQUIREMENT CURRENT
PUBLIC AND FF-STAFF	18	24
EMPLOYEES	1	1
VISITORS	25	24
PERMIT ACCESSIBLE	1	1
TOTAL SPACES	141	151


- ESTIMATED HOURS OF OPERATION
MONDAY - FRIDAY 7 A.M. TO 5 P.M.
SATURDAY 7 A.M. TO 4 P.M.
- PER SECTION 4.12 OF ZONING ORDINANCE
IF AIR POLLUTION OCCURS WILL MEET THE MARYLAND AIR POLLUTION CONTROL STANDARDS
- THERE WILL BE NO NOISE OR GLARE ADVERSELY AFFECTING ADJACENT PROPERTIES
- THERE WILL BE NO VIBRATIONS AFFECTING ADJACENT PROPERTIES
- THE EMISSION OF WASTEWATER WILL COMPLY WITH STATE AND FEDERAL CODES
- NO OUTSIDE SOURCES OF POWER WILL BE USED ON-SITE OTHER THAN PUBLIC UTILITIES
- NO SPECIAL SEWER WASTE WILL BE GENERATED ON-SITE
- THERE WILL BE NO USE STORAGE OF MATERIALS
- TRASH AND RECYCLABLES ARE TO BE COLLECTED BY COLLEGE PERSONNEL
- SITE LIGHTING IS TO BE PROVIDED AS SHOWN ON PLAN. ALL PROPOSED LIGHTING SHALL BE INSTALLED OR SHIELDED IN SUCH A MANNER SO AS TO ELIMINATE GLARE ONTO ADJACENT PROPERTIES AND ROADS
- THERE ARE NO WETLANDS ON THE SITE PER MAPPING BY THE U.S. DEPARTMENT OF THE INTERIOR, FISH AND WILDLIFE SERVICE, HAGERSTOWN, MD, APRIL QUADRANGLE DATED APRIL, 1992
- THERE ARE NO HABITATS OF THREATENED OR ENDANGERED SPECIES IDENTIFIED BY THE U.S. FISH AND WILDLIFE SERVICE PER AS REQUIRED TO BE SHOWN BY SECTION 9.4 OF THE WASHINGTON COUNTY SUBDIVISION ORDINANCE AND SECTION 4.21 OF THE WASHINGTON COUNTY ZONING ORDINANCE
- THERE ARE NO AREAS OF STEEP SLOPES (AS DEFINED IN ARTICLE 28.031 OF THE WASHINGTON COUNTY ZONING ORDINANCE) ON THE LANDS SHOWN HEREON
- NO HYDROLOGIC SITE ANALYSIS IS SHOWN ON THIS SITE FOR SOIL SURVEY MAP BY THE U.S. DEPARTMENT OF AGRICULTURE
- THIS SITE IS NOT WITHIN THE LIMITS OF THE APPALACHIAN TRAIL CORRIDOR OR THE WATER-SHEDS OF THE EDEMONT-SMITHBURG RESERVOIR OR THE UPPER BEAVER CREEK DRAINAGE BASIN
- THIS SITE IS NOT AFFECTED BY THE 10 YEAR FLOOD PLAIN AS SHOWN ON F.E.A. COMMUNITY FLOOD HAZARD ZONING MAP DATED FEBRUARY 1, 1988. SITE IS IN ZONING AREA 28.031 OF THE WASHINGTON COUNTY ZONING ORDINANCE
- THIS PROJECT IS NOT SUBJECT TO REGULATIONS OF THE MARYLAND ACCESSIBILITY ACT FOR THE HANDICAPPED.
- THIS SITE SHALL COMPLY WITH THE REQUIREMENTS OF THE MARYLAND ACCESSIBILITY ACT FOR THE HANDICAPPED.
- SITE COVERAGE 86.4 AC (IMPERVIOUS AREA) 312.36 AC (TOTAL SITE) x 10961+14.6%
- SQUARE FOOTAGE OF BUILDING
FIRST FLOOR = 9,445 SF
SECOND FLOOR = 9,445 SF
THIRD FLOOR = 14,460 SF
FOURTH FLOOR = 14,460 SF
FIFTH FLOOR = 13,275 SF
TOTAL = 50,685 SF

CURRENT WATER AND SEWER ALLOCATION FOR THIS SITE IS 2.650 G.P.D.
PROPOSED ADDITIONAL WATER AND SEWER USAGE IS 0.0 P.D.
ADDITIONAL WATER AND SEWER ALLOCATION 0.0 P.D.

CITY OF HAGERSTOWN WATER AND SEWER DEPARTMENT

THIS APPROVAL IS FOR THE DESIGN AND LAYOUT OF THE PROPOSED WATER SYSTEM IMPROVEMENTS AND SANITARY SEWER SYSTEM IMPROVEMENTS. ALL WATER SYSTEM IMPROVEMENTS AND SANITARY SEWER SYSTEM IMPROVEMENTS SHALL BE CONSTRUCTED TO THE STANDARDS IN EFFECT AT THE TIME OF CONSTRUCTION. THIS APPROVAL DOES NOT GUARANTEE THE ACCURACY OF THE INFORMATION PROVIDED FOR WATER AND SEWER SERVICE. WATER SERVICE AND SANITARY SEWER SERVICE ARE AVAILABLE SUBJECT TO CONFORMANCE WITH ALL LOCAL AND FEDERAL REGULATIONS RELATIVE TO THE APPLICATION FOR SERVICE. PAYMENT OF FEES AND APPROVAL OF THE WATER SERVICE APPLICATION AND SANITARY SEWER SERVICE APPLICATION. THIS APPROVAL IS VALID FOR A PERIOD OF (1) YEAR.

CITY OF HAGERSTOWN
WATER & SEWER DEPARTMENT



LEGEND

- NEW CONCRETE SIDEWALK
- NEW PAVES
- NEW ASPHALT PAVING
- NEW LANDSCAPE WALL/CURB
- NEW S/M QUALITY STRUCTURE

APPROVED FOR CONSTRUCTION:


HAGERSTOWN COUNTY, DIVISION OF PUBLIC WORKS
LAND DEVELOPMENT ENGINEERING

DATE

THE STORMWATER MANAGEMENT PLAN SHOWN HEREON IS APPROVED.

WASHINGTON COUNTY, DIVISION OF PUBLIC WORKS
LAND DEVELOPMENT ENGINEERING

DATE



OWNER/DEVELOPER
HAGERSTOWN COMMUNITY COLLEGE
ATTN: DR. GUY ALBERTI
1748 ROBINWOOD DRIVE
HAGERSTOWN, MD 21742
PHONE: 301-790-9300

Craig Owsiany

Curtain Wall Crane Plan

- █ Yellow Curtain Wall Crane
- █ Green Contractor Staging
- █ Brown Temp. Sanitary Facilities
- █ Dark Green Loading Dock
- █ Blue Building Stone Access
- █ Yellow Temp. Power
- █ Blue Parking
- █ Red Crane Stone Access
- █ Orange Dumpster

ARCHITECTS
C/O BERN HOSBACK & ASSOCIATES
101 N. CHARLES STREET
14TH FLOOR
BALTIMORE, MD 21201
410-578-0443

CIVIL ENGINEER
TRIM ENGINEERING, INC.
1075 D. SHERMAN AVENUE
HAGERSTOWN, MD 21740
301-791-6400

LANDSCAPE ARCHITECT
MANAN RYVEL ASSOCIATES, INC.
801 STYAN PARK DRIVE
BALTIMORE, MD 21211
410-235-6001

STRUCTURAL ENGINEER
HUNT & HUNTS
1800 M STREET NW
SUITE 470
WASHINGTON, DC 20036
800-225-7861

MECHANICAL/PLUMB ENGINEER
JAMES POSEY ASSOCIATES, INC.
3115 CROW MILK CREEK DRIVE
MIDDLEBURG, VA 22114
410-268-8410

ACOUSTIC ENGINEER
SHEIN WELFARE
3070 S D
ARLINGTON, VA 22201
703-243-8301

LAB PLANNERS
SET PLANNERS
500 MILBURN BOULEVARD
ARLINGTON, VA 22209
703-680-6767



PROJECT NAME:
HAGERSTOWN COMMUNITY COLLEGE
ARTS AND SCIENCE COMPLEX - STEM BUILDING


11400 ROBINWOOD DR
HAGERSTOWN, MD 21742

CONSTRUCTION DOCUMENTS

CONSULTANT PROJECT NO. 2009
S/MC ARCHITECT APPROVAL

NAME	DATE
TITLE	DEPARTMENT OF GENERAL SERVICES APPROVAL
PROJECT MANAGER	DATE
CHEF-PROJ. MGT. & DESIGN	DATE
CHECKED BY:	DATE
DRAWN BY:	DATE
CHECKED BY:	DATE
DATE PROJECT NUMBER:	CG-08-MOD-8
DATE:	10-28-2015
DATE:	10-28-2015
DATE:	10-28-2015
DATE:	10-28-2015
DATE:	10-28-2015

Site Plan
C 300
SHEET ____ OF ____



ARCHITECTS
 C/O BERN HOSBACK & ASSOCIATES
 101 N. CHARLES STREET
 14TH FLOOR
 BALTIMORE, MD 21201
 410-578-0443

CIVIL ENGINEER
 TRING ENGINEERING, INC.
 1075 D. BISHMAN AVENUE
 HAGERSTOWN, MD 21740
 301-787-6400

LANDSCAPE ARCHITECT
 MANAN RYVEL ASSOCIATES, INC.
 801 SYMAN PARK DRIVE
 BALTIMORE, MD 21211
 410-225-8001

STRUCTURAL ENGINEER
 HEART & HOOD CO.
 1800 M STREET NW
 SUITE 105
 WASHINGTON, DC 20036
 800-225-7961

MECHANICAL/PLUMB ENGINEER
 JAMES POSEY ASSOCIATES, INC.
 3115 CROW MILKING DRIVE
 BALTIMORE, MD 21244
 410-684-8150

ACOUSTIC ENGINEER
 BERRY WILFAX ASSOCIATES
 SUITE 202
 WILMINGTON, VA 23391
 703-243-8205

LAB PLANNERS
 SET PLANNERS
 1501 WILSON BOULEVARD
 ANNAPOLIS, MD 20709
 410-293-8787



PROJECT NAME:
 HAGERSTOWN COMMUNITY COLLEGE
 ARTS AND SCIENCE COMPLEX -
 STEM BUILDING

**11400 ROBINWOOD DR
 HAGERSTOWN, MD 21742**

CONSTRUCTION DOCUMENTS

CONSULTANT PROJECT NO. 2022
 DESIGN ARCHITECT APPROVAL

NAME: _____ **DATE:** _____

TITLE: DEPARTMENT OF GENERAL SERVICES
APPROVAL: _____

PROJECT MANAGER: _____ **DATE:** _____

CHEF-PROJ. MGT. & DESIGN: _____ **DATE:** _____

MARK: _____ **DESCRIPTION:** _____

DWG FILE: 2440-003-0200

DRAWN BY: STAFF

CHECKED BY: JTB


JOB PROJECT NUMBER: CO-18-MOD-8

DATE: 10-28-2025

Site Plan

C 300

SHEET: _____ **OF:** _____



GENERAL NOTES

- 1) TAX MAP 98, BLOCK 10, PARCELS 2P
- 2) SEE REFERENCES AND AREA
- 3) PARCELS 2P, 2, 1817 & 18 AND 1, 1853 & 11
- 4) TOTAL COMMUNITY COLLEGE LANDS = 317.8759 ACRES
- 5) ELECTION DISTRICT NO. 10
- 6) ZONING
- 7) MAIN CAMPUS BUILDINGS ARE ZONED "R6" - RESIDENTIAL, SUBURBAN DISTRICT
- 8) MAIN AREA CONTAINS A RETAIL FEELS, APARTMENTS AND BATHHOUSES IS ZONED "M" - AGRICULTURAL DISTRICT
- 9) EXISTING AND PROPOSED USE IS A PUBLIC COLLEGE AND A DAY CARE CENTER, BOTH OF WHICH ARE PERMITTED USES IN THE "M" AND "R6" DISTRICTS
- 10) PROJECT LINES SHOWN HEREON ARE FROM A ZONING SURVEY OF BOUNDARY SURVEY OF THE LANDS OF HAGERSTOWN COMMUNITY COLLEGE PREPARED BY TRING ENGINEERING, INC. DATED 06-10-2019 AND RECORDED AMONG THE LAND RECORDS OF WASHINGTON COUNTY AS SET FORTH IN PLAT BOOKS 2410, 2411 AND 2412
- 11) ALL PLAT BOOKS CITED IN THIS HEREBY REFERENCED TO A FULL ENTITLED "SIMPLIFIED PLAN OF SUBDIVISION OF PARCELS 2P FOR JOHN YOUNG'S DATED APRIL 2, 1998 AND RECORDED AMONG THE LAND RECORDS OF WASHINGTON COUNTY, MARYLAND AS PLAT NUMBER 1887
- 12) IMPROVEMENTS AND CONTOURS SHOWN HEREON ARE FROM AERIAL MAPPING PROVIDED BY WINGE AERIAL MAPPING COMPANY, DATED OCTOBER, 1999. VERTICAL DATUM WAS ASSUMED: BENCHMARK OF THIS PLAN IS FOR CONSTRUCTING A HIGH SCHOOL AND MATHEMATICS BUILDING
- 13) MINIMUM REQUIREMENTS FOR SECTIONS 6.1 AND 7.5 OF THE WASHINGTON COUNTY ZONING ORDINANCE

LOT AREA	LOT WIDTH	FRONT YARD DEPTH	REAR YARD DEPTH	REAR YARD SETBACK	MAX. BUILDING HEIGHT
15.4C	596'	100'	100'	210 FEET OR LESS	35'

- 10) THE COLLEGE IS SERVED BY PUBLIC SEWER AND WATER PROVIDED BY THE CITY OF HAGERSTOWN
- 11) A NEW WALL MOUNTED SIGN IS PROPOSED AS SHOWN ON PLAN. ALL SIGNAGE SHALL COMPLY WITH SECTION 22.28 OF THE WASHINGTON COUNTY ZONING ORDINANCE
- 12) EXISTING PARKING IS AS SHOWN

PARKING CATEGORY	REQUIREMENT	REQUIREMENT CURRENT
P.F.A.C. AND P.F. STAFF	1.00	2.00
SUBTOTAL	1.00	2.00
VEHICLE SPACES	1.00	1.00
BIKE SPACES	0.00	0.00
BIKE ACCESSIBLE	0.00	0.00
TOTAL SPACES	1.00	3.00

- 13) ESTIMATED HOURS OF OPERATION: MONDAY - FRIDAY 7 A.M. TO 9 P.M. SATURDAY 7 A.M. TO 4 P.M.
- 14) PER SECTION 4.12 OF ZONING ORDINANCE: IF AIR POLLUTION OCCURS WILL MEET THE MARYLAND AIR POLLUTION CONTROL STANDARDS
- 15) THERE WILL BE NO HEAT OR GLARE ADVERSELY AFFECTING ADJOINING PROPERTIES
- 16) THERE WILL BE NO VIBRATIONS AFFECTING ADJOINING PROPERTIES
- 17) THE EMISSION OF RADIOACTIVE WAVELENGTHS WILL COMPLY WITH STATE AND FEDERAL CODES
- 18) NO OUTSIDE SOURCES OF POWER WILL BE USED ON SITE OTHER THAN PUBLIC UTILITIES
- 19) NO HAZARDOUS SEWER WASTE WILL BE GENERATED ON SITE
- 20) THERE WILL BE NO USE STORAGE OF MATERIALS
- 21) TRASH AND RECYCLABLES ARE TO BE COLLECTED BY COLLEGE PERSONNEL
- 22) SITE LIGHTING IS AS SHOWN ON PLAN. ALL PROPOSED LIGHTING SHALL BE RETAILED OR SHIELDED IN SUCH A MANNER SO AS TO ELIMINATE GLARE ONTO ADJOINING PROPERTIES AND ROADS
- 23) THERE ARE NO WETLANDS ON THE SITE PER MAPPING BY THE U.S. DEPARTMENT OF THE INTERIOR, FISH AND WILDLIFE SERVICE, HAGERSTOWN, MD. PA. QUADRANGLE DATED APRIL, 1982
- 24) THERE ARE NO HABITATS OF THREATENED OR ENDANGERED SPECIES IDENTIFIED BY THE U.S. FISH AND WILDLIFE SERVICE PER RECORDS REQUIRED TO BE SHOWN BY SECTION 9.4 OF THE WASHINGTON COUNTY SUBDIVISION ORDINANCE AND SECTION 4.21 OF THE WASHINGTON COUNTY ZONING ORDINANCE
- 25) THERE ARE NO AREAS OF STEEP SLOPES AS DEFINED IN ARTICLE 28.831 OF THE WASHINGTON COUNTY ZONING ORDINANCE ON THE LANDS SHOWN HEREON
- 26) NOT AFFECTED BY 21.26 AS SHOWN ON THIS SITE FOR SOIL SURVEY MAP BY JOHN EMMERTER, 8/12/2008 OTHER THAN AS SHOWN ON THIS SITE FOR SOIL SURVEY MAP BY PREPARED BY THE U.S.D.A. N.R.C.S.
- 27) THIS SITE IS NOT WITHIN THE LIMITS OF THE ANNEAPOLIS TIAL ZONING OR THE WATER SHEDS OF THE EDOMONT-SMITHSBURG RESERVOIR OR THE UPPER BEAVER CREEK DRAINAGE BASIN
- 28) THIS SITE IS NOT AFFECTED BY THE 10 YEAR FLOOD PLAIN AS SHOWN ON F.E.A. COMMUNITY PANEL NO. 2000E (WATER YEAR 1982) AND 1988 SITE 5 IN ZONING 1
- 29) THIS PROJECT IS NOT SUBJECT TO THE FEDERAL REGISTER OF THE NATIONAL ANTIDISCRIMINATION ACT FOR THE PURPOSES OF THE HCC PROPERTY
- 30) THIS SITE SHALL COMPLY WITH THE REQUIREMENTS OF THE MARYLAND ACCESSIBILITY CODE FOR THE HANDICAPPED
- 31) SITE COVERAGE: 88.4 AC (IMPERVIOUS AREA) 32.26 AC (TOTAL SITE) x 100% = 114.4%
- 32) SQUARE FOOTAGE OF BUILDING: 8,445 SF
- 33) FIRST FLOOR: 8,445 SF
- 34) SECOND FLOOR: 14,460 SF
- 35) THIRD FLOOR: 14,460 SF
- 36) FOURTH FLOOR: 14,460 SF
- 37) FIFTH FLOOR: 13,275 SF
- 38) TOTAL: 63,100 SF

CURRENT WATER AND SEWER ALLOCATION FOR THIS SITE IS: 2.6 MG, 0 P.D.
PROPOSED ADDITIONAL WATER AND SEWER USAGE IS: 3.0 P.D.
ADDITIONAL WATER AND SEWER ALLOCATION: 0.4 P.D.

CITY OF HAGERSTOWN WATER AND SEWER DEPARTMENT


THIS APPROVAL IS FOR THE DESIGN AND LAYOUT OF THE PROPOSED WATER SYSTEM IMPROVEMENTS AND SANITARY SEWER SYSTEM IMPROVEMENTS. ALL WATER SYSTEM IMPROVEMENTS AND SANITARY SEWER SYSTEM IMPROVEMENTS SHALL BE CONSTRUCTED TO THE STANDARDS IN EFFECT AT THE TIME OF CONSTRUCTION. THIS APPROVAL DOES NOT GUARANTEE THE ACCURACY OF THE INFORMATION OR SANITARY SEWER SERVICE, WATER SERVICE AND SANITARY SEWER SERVICE ARE AVAILABLE. SUBJECT TO COMPLIANCE WITH ALL LOCAL AND FEDERAL REGULATIONS RELATIVE TO THE APPLICATION FOR SERVICE, PAYMENT OF FEES AND APPROVAL OF THE WATER SERVICE APPLICATION AND SANITARY SEWER SERVICE APPLICATION. THIS APPROVAL IS VALID FOR A PERIOD OF (1) YEAR.

CITY OF HAGERSTOWN: _____ **DATE:** _____
WATER & SEWER DEPARTMENT: _____

Craig Owsiany

Curtain Wall Crane Plan

Curtain Wall Crane	Contractor Staging	Temp. Sanitary Facilities
Loading Dock	Building Stone Access	Temp. Power
Parking	Crane Stone Access	Dumpster



- GENERAL NOTES**
- 1) TAX MAP 66, BLOCK 101, PARCELS 2P
 - 2) SEE REFERENCES AND AREA
 - 3) PARCELS 2P, 2, 1817 & 1818, 1853 P.11
 - 4) TOTAL COMMUNITY COLLEGE LANDS = 317,879 ACRES
 - 5) ELECTION DISTRICT NO. 10
 - 6) ZONING
 - 7) MAIN CAMPUS BUILDINGS ARE ZONED "R" - RESIDENTIAL, SUBURBAN DISTRICT
 - 8) MAIN AREA CONTAINS A RETAIL FEEL, APARTMENTS AND BATHROOMS IS ZONED "M" - AGRICULTURAL DISTRICT
 - 9) EXISTING AND PROPOSED USE IS A PUBLIC COLLEGE AND A DAY CARE CENTER, BOTH OF WHICH ARE PERMITTED USES IN THE "M" AND "R" DISTRICTS
 - 10) PROJECT LINES SHOWN HEREON ARE FROM A ZONING AND BOUNDARY SURVEY OF THE LANDS OF HAGERSTOWN COMMUNITY COLLEGE PREPARED BY TRISK ENGINEERING, INC. DATED 05-10-07 AND RECORDED AMONG THE LAND RECORDS OF WASHINGTON COUNTY AS SET FORTH IN PLAT BOOKS 100, 101 AND 102 HEREBY REFERENCED TO A FULL ENTITLED "SIMPLIFIED PLAN OF SUBDIVISION OF PARCELS 2P, 2, JOHN YOUNG'S, DATED APRIL 2, 1998, AND RECORDED AMONG THE LAND RECORDS OF WASHINGTON COUNTY, MARYLAND AS PLAT NUMBER 1867
 - 11) IMPROVEMENTS AND CONTOURS SHOWN HEREON ARE FROM AERIAL MAPPING PROVIDED BY WINGS AERIAL MAPPING COMPANY, DATED OCTOBER, 1999. VERTICAL DATUM WAS ADJUSTED.
 - 12) PORTION OF THIS PLAN IS FOR CONSTRUCTING A HIGH SCHOOL AND MATHEMATICS BUILDING.
 - 13) NUMBER OF REQUIREMENTS FOR SECTIONS 6.1 AND 7.5 OF THE WASHINGTON COUNTY ZONING ORDINANCE

LOT AREA	LOT WIDTH	FRONT YARD DEPTH	SIDE YARD DEPTH	REAR YARD DEPTH	MAX. BUILDING HEIGHT
15.4C	306'	100'	21'	21'	35' FOR 100' OR LESS OF OR 35'

- 14) THE COLLEGE IS SERVED BY PUBLIC SEWER AND WATER PROVIDED BY THE CITY OF WASHINGTON
 - 15) A NEW WALL MOUNTED SIGN IS PROPOSED AS SHOWN ON PLAN. ALL SIGNAGE SHALL COMPLY WITH SECTION 22.28 OF THE WASHINGTON COUNTY ZONING ORDINANCE
 - 16) EXISTING PARKING IS AS SHOWN
- | PARKING CATEGORY | NO. OF SPACES | REQUIREMENT | NO. OF SPACES | REQUIREMENT |
|---------------------|---------------|-------------|---------------|-------------|
| PUBLIC AND FF-STAFF | 18 | 18 | 24 | 24 |
| EMERGENCY | 1 | 1 | 1 | 1 |
| VEHICLE | 25 | 25 | 25 | 25 |
| BIKE | 1 | 1 | 1 | 1 |
| BIKE | 1 | 1 | 1 | 1 |
| BIKE | 1 | 1 | 1 | 1 |
- 17) ESTIMATED HOURS OF OPERATION: MONDAY - FRIDAY 7 A.M. TO 9 P.M. SATURDAY 9 A.M. TO 4 P.M.
 - 18) PER SECTION 4.12 OF ZONING ORDINANCE: IF AN AIR POLLUTION CONTROL WILL MEET THE MARYLAND AIR POLLUTION CONTROL STANDARDS:
 - a) THERE SHALL BE NO HEAT OR GLARE ADVERSELY AFFECTING ADJOINING PROPERTIES
 - b) THERE SHALL BE NO VIBRATIONS AFFECTING ADJOINING PROPERTIES
 - c) THE EMISSION OF WASTEWATER SHALL COMPLY WITH STATE AND FEDERAL CODES
 - d) NO OTHER SOURCE OF POLLUTION WILL BE USED UNLESS OTHER THAN PUBLIC UTILITIES
 - e) NO SPECIAL SEWER WASTE WILL BE GENERATED ON SITE
 - f) THERE SHALL BE NO NOISE SOURCE OF MATERIALS
 - 19) TRASH AND RECYCLABLES ARE TO BE COLLECTED BY COLLEGE PERSONNEL
 - 20) SITE LIGHTING IS AS SHOWN ON PLAN. ALL PROPOSED LIGHTING SHALL BE RETAILED OR SHIELDED IN SUCH A MANNER SO AS TO ELIMINATE GLARE ONTO ADJOINING PROPERTIES AND PROXIMITY
 - 21) THERE ARE NO WETLANDS ON THE SITE PER MAPPING BY THE U.S. DEPARTMENT OF THE INTERIOR, FISH AND WILDLIFE SERVICE, WASHINGTON, MD. PA., QUADRANGLE DATED APRIL, 1999
 - 22) THERE ARE NO HABITATS OF THREATENED OR ENDANGERED SPECIES IDENTIFIED BY THE U.S. FISH AND WILDLIFE SERVICE PER RECORDS REQUIRED TO BE SHOWN BY SECTION 9.4 OF THE WASHINGTON COUNTY SUBDIVISION ORDINANCE AND SECTION 4.21 OF THE WASHINGTON COUNTY ZONING ORDINANCE
 - 23) THERE ARE NO AREAS OF STEEP SLOPES AS DEFINED IN ARTICLE 28.031 OF THE WASHINGTON COUNTY ZONING ORDINANCE ON THE LANDS SHOWN HEREON
 - 24) NO. 100 FERTILIZER IS SHOWN AS SHOWN ON THIS SITE FOR SOIL SURVEY MAP 51 PREPARED BY THE U.S. A.N.R.C.S.
 - 25) THIS SITE IS NOT WITHIN THE LIMITS OF THE ANNEAQUAN TRAIL CORRIDOR OR THE WATER-SHEDS OF THE EDOMONT-SMITHSBURG RESERVOIR OR THE UPPER BEAVER CREEK DRAINAGE BASIN
 - 26) THIS SITE IS NOT AFFECTED BY THE 10 YEAR FLOOD PLAIN AS SHOWN ON F.E.A. COMPANY PANEL NO. 20000, WASHINGTON COUNTY, MARYLAND, DATED APRIL 2, 1998, SITE 512 ZONING DISTRICT
 - 27) THIS PROJECT IS NOT SUBJECT TO THE APPLICATION OF THE MARYLAND ACCESSIBILITY ACT OR THE ADA ACT FOR THIS PROJECT
 - 28) THIS SITE SHALL COMPLY WITH THE REQUIREMENTS OF THE MARYLAND ACCESSIBILITY ACT FOR THE WINDICATED
 - 29) SITE COVERAGE: 81.4 AC (IMPERVIOUS AREA) 312.36 AC (TOTAL SITE) x 100% = 114.4%
 - 30) SQUARE FOOTAGE OF BUILDING:

BASE FLOOR	= 8,445 SF
SECOND FLOOR	= 9,238 SF
THIRD FLOOR	= 14,460 SF
FOURTH FLOOR	= 11,278 SF
FIFTH FLOOR	= 13,275 SF
TOTAL	= 56,706 SF

CURRENT WATER AND SEWER ALLOCATION FOR THIS SITE IS 2.650 G.P.D.
 PROPOSED ADDITIONAL WATER AND SEWER USAGE IS 3.0 P.P.D.
 ADDITIONAL WATER AND SEWER ALLOCATION 5.650 G.P.D.

CITY OF HAGERSTOWN WATER AND SEWER DEPARTMENT

THIS APPROVAL IS FOR THE DESIGN AND LAYOUT OF THE PROPOSED WATER SYSTEM IMPROVEMENTS AND SANITARY SEWER SYSTEM IMPROVEMENTS. ALL WATER SYSTEM IMPROVEMENTS AND SANITARY SEWER SYSTEM IMPROVEMENTS SHALL BE CONSTRUCTED TO THE STANDARDS IN EFFECT AT THE TIME OF CONSTRUCTION. THIS APPROVAL DOES NOT GUARANTEE THE ACCURACY OF THE INFORMATION OR ANY OTHER WATER SERVICE, WATER SERVICE AND SANITARY SEWER SERVICE. THE USER SHALL BE RESPONSIBLE FOR ALL UTILITIES AND CONDITIONS IN THE FIELD OF THE APPLICATION FOR SERVICE. PAYMENT OF FEES AND APPROVAL OF THE WATER SERVICE APPLICATION AND SANITARY SEWER SERVICE APPLICATION. THIS APPROVAL IS VALID FROM A PERIOD OF 12 MONTHS.

CITY OF HAGERSTOWN WATER & SEWER DEPARTMENT

LEGEND

- NEW CONCRETE SIDEWALK
- NEW PAVES
- NEW ASPHALT PAVING
- NEW LANDSCAPE WALL/CURB
- NEW S/M QUALITY STRUCTURE

APPROVED FOR CONSTRUCTION:

WASHINGTON COUNTY, DIVISION OF PUBLIC WORKS
 LAND DEVELOPMENT ENGINEERING

DATE

THE STORMWATER MANAGEMENT PLAN SHOWN HEREON IS APPROVED.

WASHINGTON COUNTY, DIVISION OF PUBLIC WORKS
 LAND DEVELOPMENT ENGINEERING

DATE

OWNER/DEVELOPER
 HAGERSTOWN COMMUNITY COLLEGE
 ATTN: DR. GUY ALBERTI
 1740 ROBINWOOD DRIVE
 HAGERSTOWN, MD 21742
 PHONE: 301-791-3000

- Curtain Wall Crane
- Contractor Staging
- Temp. Sanitary Facilities
- Loading Dock
- Building Stone Access
- Temp. Power
- Parking
- Crane Stone Access
- Dumpster

Craig Owsiany

Curtain Wall Crane Plan

- ARCHITECTS**
 C/O BERN HOSBACK & ASSOCIATES
 101 N. CHARLES STREET
 14TH FLOOR
 BALTIMORE, MD 21201
 410-578-0443
- CIVIL ENGINEER**
 TRISK ENGINEERING, INC.
 1075 D. SHERMAN AVENUE
 HAGERSTOWN, MD 21740
 301-791-6400
- LANDSCAPE ARCHITECT**
 MANAN RYVEL ASSOCIATES, INC.
 801 STRAWN PARK DRIVE
 BALTIMORE, MD 21211
 410-225-6001
- STRUCTURAL ENGINEER**
 HENRI WILFAX INC.
 1800 M STREET NW
 SUITE 475
 WASHINGTON, DC 20008
 800-225-1961
- MECHANICAL/PLUMB ENGINEER**
 JAMES POSEY ASSOCIATES, INC.
 3115 LOREY BALDWIN DRIVE
 BALTIMORE, MD 21244
 410-268-8100
- ACOUSTIC ENGINEER**
 HENRI WILFAX INC.
 1800 M STREET NW
 SUITE 475
 WASHINGTON, DC 20008
 800-225-1961
- LAB PLANNERS**
 SET PLANNERS
 1501 WILSON BOULEVARD
 ANNAPOLIS, MD 20708
 410-293-6767





PROJECT NAME
 HAGERSTOWN COMMUNITY COLLEGE
 ARTS AND SCIENCE COMPLEX - STEM BUILDING

11400 ROBINWOOD DR
 HAGERSTOWN, MD 21742

CONSTRUCTION DOCUMENTS
 CONSULTANT PROJECT NO. 2009
 OWNER AGENCY APPROVAL

NAME	DATE
TITLE	DEPARTMENT OF GENERAL SERVICES APPROVAL
PROJECT MANAGER	DATE
CHEF-PROJ. MGT. & DESIGN	DATE
MARK	DATE
DESCRIPTION	
DWG FILE	2440-003-000
DRAWN BY	STAFF
CHECKED BY	STAFF
USER PROJECT NUMBER	CG-08-MOD8
DATE	10-28-2015
Site Plan	
C 300	
SHEET	OF



- GENERAL NOTES**
- 1) TYP MAP 66 BLOCK 4 VIL. PARCELS 2P
 - 2) SEE REFERENCES AND AREA
 - 3) PARCELS 2P, 2, 187 F 18 AND 1, 188 F 111
 - 4) TOTAL COMMUNITY COLLEGE LANDS = 317.8789 ACRES
 - 5) ELECTION DISTRICT NO. 10
 - 6) ZONING
 - 7) MAIN CAMPUS BUILDINGS ARE ZONED "R-1" RESIDENTIAL SUBURBAN DISTRICT
 - 8) MAIN CAMPUS AREAS ARE ZONED "R-2" RESIDENTIAL SUBURBAN DISTRICT
 - 9) PROJECT LINES SHOWN HEREON ARE FROM A ZONING AND BOUNDARY SURVEY OF THE LANDS OF HAGERSTOWN COMMUNITY COLLEGE PREPARED BY TRISK ENGINEERING, INC. DATED 06/07 AND RECORDED AMONG THE LAND RECORDS OF WASHINGTON COUNTY AS SAID DATE. PLANNING SURVEILANCE DATA IS HEREBY REFERENCED TO A FULL ENTITLED, SIMPLIFIED PLAN OF SUBDIVISION OF PARCELS 2P, FOR JOHN YOUNG'S DATED APRIL 8, 1998, AND RECORDED AMONG THE LAND RECORDS OF WASHINGTON COUNTY, BEYLAND 489-1847.
 - 10) IMPROVEMENTS AND CONTOURS SHOWN HEREON ARE FROM AERIAL MAPPING PROVIDED BY WINGED AERIAL MAPPING COMPANY, DATED OCTOBER, 1999. VERTICAL DATUM WAS ADJUSTED.
 - 11) PORTION OF THIS PLAN IS FOR CONSTRUCTING A HIGH SCIENCE AND MATHEMATICS BUILDING.
 - 12) MINIMUM REQUIREMENTS PER SECTIONS 6.1 AND 7.5 OF THE WASHINGTON COUNTY ZONING ORDINANCE.

LOT AREA	LOT WIDTH	FRONT YARD DEPTH	REAR YARD DEPTH	REAR YARD SETBACK	MAX. BUILDING HEIGHT
15.4C	596'	100'	100'	21' 0" (FORCES) OR 3'	35'

PARKING CATEGORY	REQUIREMENT	REQUIREMENT CURRENT
P.F.A.C. AND P.F. STAFF	18	24
EMERGENCY	1	1
VEHICLE	25	24
BIKE	1	1
ACCESSIBLE	1	1
TOTAL	47	51

- 13) ESTIMATED HOURS OF OPERATION: MONDAY - FRIDAY 7 A.M. TO 9 P.M. SATURDAY 7 A.M. TO 4 P.M.
- 14) PER SECTION 4.12 OF ZONING ORDINANCE: IF AIR POLLUTION OCCURS WILL MEET THE MARYLAND AIR POLLUTION CONTROL STANDARDS.
- 15) THERE WILL BE NO HEAT OR GLARE ADVERSELY AFFECTING ADJOINING PROPERTIES.
- 16) THERE WILL BE NO VIBRATIONS AFFECTING ADJOINING PROPERTIES.
- 17) THE EMISSION OF RADIONUCLIDES WILL COMPLY WITH STATE AND FEDERAL CODES.
- 18) NO OUTSIDE SOURCES OF POWER WILL BE USED ON SITE OTHER THAN PUBLIC UTILITY.
- 19) NO SPECIAL SEWER WASTE WILL BE GENERATED ON SITE.
- 20) THERE WILL BE NO USE STORAGE OF MATERIALS.
- 21) TRASH AND RECYCLABLES ARE TO BE COLLECTED BY COLLEGE PERSONNEL.
- 22) SITE LIGHTING LIGHTS ARE PROPOSED AS SHOWN ON PLAN. ALL PROPOSED LIGHTING SHALL BE RETAILED OR SHIELDED IN SUCH A MANNER SO AS TO ELIMINATE GLARE ONTO ADJOINING PROPERTIES AND PROXIMITY.
- 23) THERE ARE NO WETLANDS ON THE SITE PER MAPPING BY THE U.S. DEPARTMENT OF THE INTERIOR, FISH AND WILDLIFE SERVICE, HAGERSTOWN, MD. PA. QUADRANGLE DATED APRIL, 1989.
- 24) THERE ARE NO HABITATS OF THREATENED OR ENDANGERED SPECIES IDENTIFIED BY THE U.S. FISH AND WILDLIFE SERVICE PER RECORDS REQUIRED TO BE SHOWN BY SECTION 9.4 OF THE WASHINGTON COUNTY SUBDIVISION ORDINANCE AND SECTION 4.21 OF THE WASHINGTON COUNTY ZONING ORDINANCE.
- 25) THERE ARE NO AREAS OF STEEP SLOPES AS DEFINED IN ARTICLE 28.831 OF THE WASHINGTON COUNTY ZONING ORDINANCE ON THE LANDS SHOWN HEREON.
- 26) NOT AFFECTED BY 21.16 AS SHOWN ON THIS SITE FOR SOIL SURVEY MAP 51, PREPARED BY THE U.S.D.A. N.R.C.S.
- 27) THIS SITE IS NOT WITHIN THE LIMITS OF THE ANNEAQUAN TRAIL CORRIDOR OR THE WATER SHEDS OF THE EDOMONT-SMITHSBURG RESERVOIR OR THE UPPER BEAVER CREEK DRAINAGE BASIN.
- 28) THIS SITE IS NOT AFFECTED BY THE 10 YEAR FLOOD PLAIN AS SHOWN ON F.E.A. COMMUNITY PANEL NO. 2000E, WASHINGTON COUNTY, 1998. THIS SITE IS ZONED R-1.
- 29) THIS PROJECT IS NOT SUBJECT TO THE REGULATIONS OF THE MARYLAND ACCESSIBILITY ACT FOR THE HANDICAPPED.
- 30) THIS SITE SHALL COMPLY WITH THE REQUIREMENTS OF THE MARYLAND ACCESSIBILITY ACT FOR THE HANDICAPPED.
- 31) SITE COVERAGE: 84.4 AC (IMPERVIOUS AREA) 312.36 AC (TOTAL SITE) x 109% = 114.4%
- 32) SQUARE FOOTAGE OF BUILDING: 8,445 SF
- 33) FIRST FLOOR: 8,445 SF
- 34) SECOND FLOOR: + 14,460 SF
- 35) THIRD FLOOR: + 14,460 SF
- 36) FOURTH FLOOR: + 13,275 SF
- 37) FIFTH FLOOR: + 13,275 SF
- 38) TOTAL: 53,915 SF

CURRENT WATER AND SEWER ALLOCATION FOR THIS SITE IS 2.680 G.P.D.
 PROPOSED ADDITIONAL WATER AND SEWER USAGE IS 3.0 P.D.
 ADDITIONAL WATER AND SEWER ALLOCATION 5.680 G.P.D.

CITY OF HAGERSTOWN WATER AND SEWER DEPARTMENT

THIS APPROVAL IS FOR THE DESIGN AND LAYOUT OF THE PROPOSED WATER SYSTEM IMPROVEMENTS AND SANITARY SEWER SYSTEM IMPROVEMENTS. ALL WATER SYSTEM IMPROVEMENTS AND SANITARY SEWER SYSTEM IMPROVEMENTS SHALL BE CONSTRUCTED TO THE STANDARDS IN EFFECT AT THE TIME OF CONSTRUCTION. THIS APPROVAL DOES NOT GUARANTEE THE ACCURACY OF THE INFORMATION OR ANY OTHER WATER SERVICE, WATER SERVICE AND SANITARY SEWER SERVICE. THE USER SHALL BE RESPONSIBLE TO OBTAIN ALL NECESSARY PERMITS FROM THE CITY OF HAGERSTOWN WATER AND SEWER DEPARTMENT FOR SERVICE, PAYMENT OF FEES AND APPROVAL OF THE WATER SERVICE APPLICATION AND SANITARY SEWER SERVICE APPLICATION. THIS APPROVAL IS VALID FOR A PERIOD OF (1) YEAR.

CITY OF HAGERSTOWN WATER & SEWER DEPARTMENT

Craig Owsiany

Curtain Wall Crane Plan

Curtain Wall Crane	Contractor Staging	Temp. Sanitary Facilities
Loading Dock	Building Stone Access	Temp. Power
Parking	Crane Stone Access	Dumpster

- ARCHITECTS**
 C/O BERN HOSBACK & ASSOCIATES
 101 N. CHARLES STREET
 14TH FLOOR
 BALTIMORE, MD 21201
 410-578-0443
- CIVIL ENGINEER**
 TRISK ENGINEERING, INC.
 1075 D. SHERMAN AVENUE
 HAGERSTOWN, MD 21740
 301-781-6400
- LANDSCAPE ARCHITECT**
 MANAN RYVEL ASSOCIATES, INC.
 801 STRYKER PARK DRIVE
 BALTIMORE, MD 21211
 410-225-8001
- STRUCTURAL ENGINEER**
 HENRY HANCOCK CO.
 1800 M STREET NW
 SUITE 470
 WASHINGTON, DC 20036
 800-222-7861
- MECHANICAL/PLUMB ENGINEER**
 JAMES POSEY ASSOCIATES, INC.
 3115 CROW HALL CIRCLE DRIVE
 BALTIMORE, MD 21244
 410-268-8150
- ACOUSTIC ENGINEER**
 SHEN HUI FAN FAY DRIVE
 SUITE 202
 ARLINGTON, VA 22201
 703-243-8202
- LAB PLANNERS**
 SET PLANNERS
 1501 WILSON BOULEVARD
 ARLINGTON, VA 22209
 800-222-8167



PROJECT NAME:
 HAGERSTOWN COMMUNITY COLLEGE ARTS AND SCIENCE COMPLEX - STEM BUILDING

11400 ROBINWOOD DR
 HAGERSTOWN, MD 21742

CONSTRUCTION DOCUMENTS
 CONSULTANT PROJECT NO. 2009
 05/06 ARCHIT. APPROVAL

NAME	DATE
TITLE	DEPARTMENT OF GENERAL SERVICES APPROVAL
PROJECT MANAGER	DATE
CHEF-PROJ. MGT. & DESIGN	DATE


MARK	DATE	DESCRIPTION
DRWG FILE	2440-003-000	
DRAWN BY	STAFF	
CHECKED BY	STAFF	
DATE	10-28-2015	

DATE 10-28-2015
 USER PROJECT NUMBER: CG-18-MOCHA
Site Plan
 C 300
 SHEET ___ OF ___



- GENERAL NOTES**
- 1) TAX MAP 98 BLOCK 016 PARCELS 2P
 - 2) SEE REFERENCES AND AREA
 - 3) PARCELS 2P, 1, 1817 8 AND 1, 1853 F 11
 - 4) TOTAL COMMUNITY COLLEGE LANDS = 317,878 ACRES
 - 5) ELECTION DISTRICT NO. 10
 - 6) ZONING
 - 7) MAIN CAMPUS BUILDINGS ARE ZONED "R" - RESIDENTIAL, SUBURBAN DISTRICT
 - 8) MAIN AREA CONTAINS A RETAIL FEELS, APARTMENTS AND BATHROOMS IS ZONED "A" - AGRICULTURAL DISTRICT
 - 9) EXISTING AND PROPOSED USE IS A PUBLIC COLLEGE AND A DAY CARE CENTER, BOTH OF WHICH ARE PERMITTED USES IN THE "A" AND "R" DISTRICTS
 - 10) PROJECT LINES SHOWN HEREON ARE FROM A ZONING TITLE BOUNDARY SURVEY OF THE LANDS OF HAGERSTOWN COMMUNITY COLLEGE PREPARED BY TRIM ENGINEERING, INC. DATED 05-07-2009 AND RECORDS AT THE LAND RECORDS OF WASHINGTON COUNTY AS SAID DATE. PLANNING SURVEILANCE DATA IS HEREBY REFERENCED TO A FULL ENTITLED, SIMPLIFIED PLAN OF SUBDIVISION OF PARCELS, BY JOHN YOUNG, DATED APRIL 8, 1998, AND RECORDED AMONG THE LAND RECORDS OF WASHINGTON COUNTY, BEYOND AND BEYOND.
 - 11) IMPROVEMENTS AND CONTOURS SHOWN HEREON ARE FROM AERIAL MAPPING PROVIDED BY WINGS AERIAL MAPPING COMPANY, DATED OCTOBER, 1999. VERTICAL DATUM WAS ADJUSTED. PURPOSE OF THIS PLAN IS FOR CONSTRUCTING A MAIN SCIENCE AND MATHEMATICS BUILDING.
 - 12) ALL REQUIREMENTS PER SECTIONS 6.1 AND 7.5 OF THE WASHINGTON COUNTY ZONING ORDINANCE.
- | LOT AREA | LOT WIDTH | FRONT YARD DEPTH | REAR YARD DEPTH | REAR YARD SETBACK | MAX. BUILDING HEIGHT |
|----------|-----------|------------------|-----------------|-------------------|----------------------|
| 15.4C | 396' | 100' | 100' | 21.5 FEET OR 50' | 35' |
- 13) THE COLLEGE IS SERVED BY PUBLIC SEWER AND WATER PROVIDED BY THE CITY OF HAGERSTOWN.
 - 14) A NEW WALL MOUNTED SIGN IS PROPOSED AS SHOWN ON PLAN. ALL SIGNAGE SHALL COMPLY WITH SECTION 22.38 OF THE WASHINGTON COUNTY ZONING ORDINANCE.
 - 15) EXISTING PARKING IS ACTUAL COURSE.
- | PARKING CATEGORY | REQUIREMENT | REQUIREMENT CURRENT |
|---------------------|-------------|---------------------|
| PUBLIC AND FF-STAFF | 18 | 24 |
| EMERGENCY | 1 | 1 |
| VEHICLE | 25 | 24 |
| BIKE | 1 | 1 |
| BIKE | 1 | 1 |
| BIKE | 1 | 1 |
- 16) ESTIMATED HOURS OF OPERATION: MONDAY - FRIDAY 7 AM TO 9 PM SATURDAY 9 AM TO 4 PM
 - 17) PER SECTION 4.12 OF ZONING ORDINANCE: IF AN AIR POLLUTION CONTROL WILL MEET THE MARYLAND AIR POLLUTION CONTROL STANDARDS:
 - 1) THERE WILL BE NO HEAT OR GLARE ADVERSELY AFFECTING ADJOINING PROPERTIES.
 - 2) THERE WILL BE NO VIBRATIONS AFFECTING ADJOINING PROPERTIES.
 - 3) THE EMISSION OF WASTEWATER SHALL COMPLY WITH STATE AND FEDERAL CODES.
 - 4) NO OUTSIDE SOURCES OF POWER WILL BE USED UNLESS OTHER THAN PUBLIC UTILITIES.
 - 5) NO SPECIAL SEWER WASTE WILL BE GENERATED ON SITE.
 - 6) THERE WILL BE NO USE STORAGE OF MATERIALS.
 - 7) TRASH AND RECYCLABLES ARE / SHALL BE COLLECTED BY COLLEGE PERSONNEL.
 - 8) SITE LIGHTING IS PROPOSED AS SHOWN ON PLAN. ALL PROPOSED LIGHTING SHALL BE RETAILED OR SHIELDED IN SUCH A MANNER SO AS TO ELIMINATE GLARE ONTO ADJOINING PROPERTIES AND PROXIMITY.
 - 9) THERE ARE NO WETLANDS ON THE SITE PER MAPPING BY THE U.S. DEPARTMENT OF THE INTERIOR, FISH AND WILDLIFE SERVICE, HAGERSTOWN, MD. PA., QUADRANGLE DATED APRIL, 1999.
 - 10) THERE ARE NO HABITATS OF THREATENED OR ENDANGERED SPECIES IDENTIFIED BY THE U.S. FISH AND WILDLIFE SERVICE PER RECORDS REQUIRED TO BE SHOWN BY SECTION 9.14 OF THE WASHINGTON COUNTY SUBDIVISION ORDINANCE AND SECTION 4.21 OF THE WASHINGTON COUNTY ZONING ORDINANCE.
 - 11) THERE ARE NO AREAS OF STEEP SLOPES AS DEFINED IN ARTICLE 28.831 OF THE WASHINGTON COUNTY ZONING ORDINANCE ON THE LANDS SHOWN HEREON.
 - 12) NO UNDESIRABLE ST. 12.16.01 IS SHOWN ON THIS SITE PER SOIL SURVEY MAP BY PREPARED BY THE U.S.D.A. N.R.C.S.
 - 13) THIS SITE IS NOT WITHIN THE LIMITS OF THE ANNEAQUAN TRAIL CORRIDOR OR THE WATER SHEDS OF THE EDOMONT-SMITHSBURG RESERVOIR OR THE UPPER BEAVER CREEK DRAINAGE BASIN.
 - 14) THIS SITE IS NOT AFFECTED BY THE 10 YEAR FLOOD PLAIN AS SHOWN ON F.E.A. COMMUNITY PANEL NO. 20090, WASHINGTON COUNTY, MARYLAND, DATED APRIL 1, 1998. SITE IS ZONED "A".
 - 15) THE PROJECT IS NOT SUBJECT TO THE APPLICATION OF THE MARYLAND ACCESSIBILITY ACT AREA PROVIDED FOR THE PARCEL OF THE HCC PROPERTY.
 - 16) THIS SITE SHALL COMPLY WITH THE REQUIREMENTS OF THE MARYLAND ACCESSIBILITY ACT FOR THE WANDPACED.
 - 17) SITE COVERAGE: 81.4 AC (IMPERVIOUS AREA) 312.36 AC (TOTAL SITE) x 109% = 14.4%
 - 18) SQUARE FOOTAGE OF BUILDING:

FIRST FLOOR	= 8,443 SF
SECOND FLOOR	= 9,243 SF
THIRD FLOOR	= 14,462 SF
FOURTH FLOOR	= 14,238 SF
FIFTH FLOOR	= 13,275 SF
TOTAL	= 59,661 SF



LEGEND


[Symbol]	NEW CONCRETE SIDEWALK
[Symbol]	NEW PAVES
[Symbol]	NEW ASPHALT PAVING
[Symbol]	NEW LANDSCAPE WALL/CURB
[Symbol]	NEW SLM QUALITY STRUCTURE

CURRENT WATER AND SEWER ALLOCATION FOR THIS SITE IS 2.650 G.P.D.
 PROPOSED ADDITIONAL WATER AND SEWER USAGE IS 3.0 P.P.D.
 ADDITIONAL WATER AND SEWER ALLOCATION 0.350 P.P.D.

CITY OF HAGERSTOWN WATER AND SEWER DEPARTMENT

THIS APPROVAL IS FOR THE DESIGN AND LAYOUT OF THE PROPOSED WATER SYSTEM IMPROVEMENTS AND SANITARY SEWER SYSTEM IMPROVEMENTS. ALL WATER SYSTEM IMPROVEMENTS AND SANITARY SEWER SYSTEM IMPROVEMENTS SHALL BE CONSTRUCTED TO THE STANDARDS IN EFFECT AT THE TIME OF CONSTRUCTION. THIS APPROVAL DOES NOT GUARANTEE THE ACCURACY OF THE INFORMATION OR ANY OTHER WATER SERVICE, WATER SERVICE AND SANITARY SEWER SERVICE. THE USER SHALL BE RESPONSIBLE TO THE USER FOR THE ACCURACY OF THE INFORMATION AND THE USER SHALL BE RESPONSIBLE FOR THE APPLICATION FOR SERVICE, PAYMENT OF FEES AND APPROVAL OF THE WATER SERVICE APPLICATION AND SANITARY SEWER SERVICE APPLICATION. THIS APPROVAL IS VALID FROM A PERIOD OF 12 MONTHS.

CITY OF HAGERSTOWN _____ DATE _____
 WATER & SEWER DEPARTMENT



OWNER/DEVELOPER
 HAGERSTOWN COMMUNITY COLLEGE
 ATTN: DR. GUY ALBRI
 1740 ROBINWOOD DRIVE
 HAGERSTOWN, MD 21742
 PHONE: 301-791-3000

APPROVED FOR CONSTRUCTION

WASHINGTON COUNTY, DIVISION OF PUBLIC WORKS _____ DATE _____
 LAND DEVELOPMENT ENGINEERING

THE STORMWATER MANAGEMENT PLAN SHOWN HEREON IS APPROVED.

WASHINGTON COUNTY, DIVISION OF PUBLIC WORKS _____ DATE _____
 LAND DEVELOPMENT ENGINEERING

Craig Owsiany

Curtain Wall Crane Plan

- Curtain Wall Crane
- Contractor Staging
- Temp. Sanitary Facilities
- Loading Dock
- Building Stone Access
- Temp. Power
- Parking
- Crane Stone Access
- Dumpster

- ARCHITECTS**
 C/O BERN HOSBACK & ASSOCIATES
 101 N. CHARLES STREET
 14TH FLOOR
 BALTIMORE, MD 21201
 410-578-0443
- CIVIL ENGINEER**
 TRIM ENGINEERING, INC.
 1075 D. SHERMAN AVENUE
 HAGERSTOWN, MD 21740
 301-791-6400
- LANDSCAPE ARCHITECT**
 MANAN RYVEL ASSOCIATES, INC.
 801 STRYDOM PARK DRIVE
 BALTIMORE, MD 21211
 410-225-6001
- STRUCTURAL ENGINEER**
 HENRY HANCOCK
 1800 M STREET NW
 SUITE 475
 WASHINGTON, DC 20036
 800-222-7861
- MECHANICAL/PLUMB ENGINEER**
 JAMES POSEY ASSOCIATES, INC.
 3115 LORRY HALL DRIVE
 BALTIMORE, MD 21244
 410-684-8150
- ACOUSTIC ENGINEER**
 3800 WILFAX AVENUE
 SUITE 202
 ARLINGTON, VA 22201
 703-243-8201
- LAB PLANNERS**
 SET PLANNERS
 1501 WILSON BOULEVARD
 ARLINGTON, VA 22209
 703-908-6767



PROJECT NAME
 HAGERSTOWN COMMUNITY COLLEGE
 ARTS AND SCIENCE COMPLEX - STEM BUILDING

11400 ROBINWOOD DR
 HAGERSTOWN, MD 21742

CONSTRUCTION DOCUMENTS

CONSULTANT PROJECT NO. 2009
 SCIENCE RESEARCH APPROVAL

NAME	DATE
TITLE	DEPARTMENT OF GENERAL SERVICES APPROVAL
PROJECT MANAGER	DATE
CHEF-PROJ. MGT. & DESIGN	DATE
MARK	DATE
DESCRIPTION	
DWG FILE	2440-003-000
DRAWN BY	STAFF
CHECKED BY	STAFF
USER PROJECT NUMBER	CG-08-MOD8
DATE	10-28-2015
Site Plan	
C 300	
SHEET	___ OF ___

Appendix H
Accelerated Schedule

Activity ID	Activity Description	OD	ES	EF	TF	2010							2011							2012							
						J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M

SLAB ON DECK PLACEMENTS

LEVEL 2 & 3 SLAB ON DECK PLACEMENTS

8000	CL 1-9: 2ND FLR MECH/PLB DECK PREP	2	04FEB11	07FEB11	10
8010	CL 1-9: 2ND FLR ELEC DECK PREP	2	04FEB11	07FEB11	10
8020	CL 1-9: 2ND FLR CONCRETE DECK PREP	2	09FEB11	11FEB11	10
8100	CL 1-9: 3RD FLR MECH/PLB DECK PREP	2	11FEB11	14FEB11	9
8110	CL 1-9: 3RD FLR ELEC DECK PREP	2	11FEB11	14FEB11	9
8030	CL 1-9: 2ND FLR STEEL INSPECTION	1	14FEB11	14FEB11	11
8040	CL 1-9: 2ND FLR POUR SLAB ON DECK	1	15FEB11	15FEB11	11
8120	CL 1-9: 3RD FLR CONCRETE DECK PREP	2	15FEB11	17FEB11	9
8130	CL 1-9: 3RD FLR STEEL INSPECTION	1	18FEB11	18FEB11	9
8140	CL 1-9: 3RD FLR POUR SLAB ON DECK	1	21FEB11	21FEB11	9

█ ICL 1-9: 2ND FLR MECH/PLB DECK PREP
█ ICL 1-9: 2ND FLR ELEC DECK PREP
█ ICL 1-9: 2ND FLR CONCRETE DECK PREP
█ ICL 1-9: 3RD FLR MECH/PLB DECK PREP
█ ICL 1-9: 3RD FLR ELEC DECK PREP
█ ICL 1-9: 2ND FLR STEEL INSPECTION
█ ICL 1-9: 2ND FLR POUR SLAB ON DECK
█ ICL 1-9: 3RD FLR CONCRETE DECK PREP
█ ICL 1-9: 3RD FLR STEEL INSPECTION
█ ICL 1-9: 3RD FLR POUR SLAB ON DECK

WEST LEVEL 4 & 5 SLAB ON DECK PLACEMENTS

8200	CL 1-7: 4TH FLR MECH/PLB DECK PREP	3	28FEB11	03MAR11	10
8210	CL 1-7: 4TH FLR ELEC DECK PREP	3	28FEB11	03MAR11	10
8220	CL 1-7: 4TH FLR CONCRETE DECK PREP	2	04MAR11	07MAR11	11
8230	CL 1-7: 4TH FLR STEEL INSPECTION	1	08MAR11	08MAR11	12
8240	CL 1-7: 4TH FLR POUR SLAB ON DECK	1	10MAR11	10MAR11	12
8300	CL 1-7: 5TH FLR MECH/PLB DECK PREP	3	10MAR11	14MAR11	7
8310	CL 1-7: 5TH FLR ELEC DECK PREP	3	10MAR11	14MAR11	7
8320	CL 1-7: 5TH FLR CONCRETE DECK PREP	2	15MAR11	17MAR11	7
8330	CL 1-7: 5TH FLR STEEL INSPECTION	1	18MAR11	18MAR11	7
8340	CL 1-7: 5TH FLR POUR SLAB ON DECK	1	21MAR11	21MAR11	7

█ ICL 1-7: 4TH FLR MECH/PLB DECK PREP
█ ICL 1-7: 4TH FLR ELEC DECK PREP
█ ICL 1-7: 4TH FLR CONCRETE DECK PREP
█ ICL 1-7: 4TH FLR STEEL INSPECTION
█ ICL 1-7: 4TH FLR POUR SLAB ON DECK
█ ICL 1-7: 5TH FLR MECH/PLB DECK PREP
█ ICL 1-7: 5TH FLR ELEC DECK PREP
█ ICL 1-7: 5TH FLR CONCRETE DECK PREP
█ ICL 1-7: 5TH FLR STEEL INSPECTION
█ ICL 1-7: 5TH FLR POUR SLAB ON DECK

EAST LEVEL 4 & LEVEL 5 SLAB ON DECK PLACEMENTS

8400	CL 11.1-7: 4TH FLR MECH/PLB DECK PREP	3	15MAR11	18MAR11	3
8410	CL 11.1-7: 4TH FLR ELEC DECK PREP	3	15MAR11	18MAR11	3
8420	CL 11.1-7: 4TH FLR CONCRETE DECK PREP	2	21MAR11	22MAR11	3
8430	CL 11.1-7: 4TH FLR STEEL INSPECTION	1	24MAR11	24MAR11	4
8450	CL 11.1-7: 4TH FLR POUR SLAB ON DECK	1	25MAR11	25MAR11	4
8500	CL 11.1-7: 5TH FLR MECH/PLB DECK PREP	2	25MAR11	28MAR11	0
8510	CL 11.1-7: 5TH FLR ELEC DECK PREP	2	25MAR11	28MAR11	0
8520	CL 11.1-7: 5TH FLR CONCRETE DECK PREP	2	29MAR11	31MAR11	0
8530	CL 11.1-7: 5TH FLR STEEL INSPECTION	1	01APR11	01APR11	0
8550	CL 11.1-7: 5TH FLR POUR SLAB ON DECK	1	04APR11	04APR11	0

█ ICL 11.1-7: 4TH FLR MECH/PLB DECK PREP
█ ICL 11.1-7: 4TH FLR ELEC DECK PREP
█ ICL 11.1-7: 4TH FLR CONCRETE DECK PREP
█ ICL 11.1-7: 4TH FLR STEEL INSPECTION
█ ICL 11.1-7: 4TH FLR POUR SLAB ON DECK
█ ICL 11.1-7: 5TH FLR MECH/PLB DECK PREP
█ ICL 11.1-7: 5TH FLR ELEC DECK PREP
█ ICL 11.1-7: 5TH FLR CONCRETE DECK PREP
█ ICL 11.1-7: 5TH FLR STEEL INSPECTION
█ ICL 11.1-7: 5TH FLR POUR SLAB ON DECK




ENCLOSURE & SITE FINISHES

SUMMARY ENCLOSURE

SUM90100	PERIMETER CMU/STUDS/SHEATHING	25	18MAR11	29APR11	0
SUM90000	ROOF PARAPETS/BLOCKING/DRAINS	15	25MAR11	19APR11	5
SUM90300	EXTERIOR BRICK FACADE	15	28MAR11	21APR11	1

█ PERIMETER CMU/STUDS/SHEATHING
█ ROOF PARAPETS/BLOCKING/DRAINS
█ EXTERIOR BRICK FACADE

Start Date	03MAY10
Finish Date	17AUG12
Data Date	04JUN10
Run Date	04APR11 08:55

 Early Bar
 Progress Bar
 Critical Activity

STEM
HESS CONSTRUCTION + ENGINEERING SERV
ARTS + SCIENCE COMPLEX
PRELIMINARY
AREA EARLY DATES

Date	Revision	Checked	Approved

Activity ID	Activity Description	OD	ES	EF	TF	2010												2011												2012																																																																																							
						J				J				A				S				O				N				D				J				F				M				A				M				J				J				A				S				O				N				D				J				F				M				A				M				J				J				A				S			
SUMMARY ENCLOSURE																																																																																																																					
SUM90200	ROOFING FOR DRY-IN	15	04APR11	28APR11	5	■ ROOFING FOR DRY-IN																																																																																																															
SUM90400	INSTALL WINDOWS	20	05APR11	09MAY11	1	■ INSTALL WINDOWS																																																																																																															
SUM90500	INSTALL CURTAIN WALLS & STOREFRONTS	20	14APR11	17MAY11	0	■ INSTALL CURTAIN WALLS & STOREFRONTS																																																																																																															
SITE FINISHES																																																																																																																					
SUM91000	METAL PANELS & SOFFITS	40	14APR11	17JUN11	0	■ METAL PANELS & SOFFITS																																																																																																															
SUM91100	SITE HARDSCAPE	30	20JUN11	05AUG11	0	■ SITE HARDSCAPE																																																																																																															
SUM91200	SITE LANDSCAPING	20	08AUG11	05SEP11	0	■ SITE LANDSCAPING																																																																																																															
SUM91300	SITE WORK TO COMPLETE LIST	10	06SEP11	20SEP11	0	■ SITE WORK TO COMPLETE LIST																																																																																																															
MAIN MECHANICAL & ELECTRICAL ROOMS																																																																																																																					
LV2 MAIN ELECTRICAL ROOM																																																																																																																					
SUM5000	LV2 ELEC ROOM (FRP EQPT PADS)	2	18MAR11	21MAR11	38	■ LV2 ELEC ROOM (FRP EQPT PADS)																																																																																																															
SUM5005	LV2 ELEC ROOM (CONSTRUCT ELEC ROOM)	5	02MAY11	06MAY11	9	■ LV2 ELEC ROOM (CONSTRUCT ELEC ROOM)																																																																																																															
SUM5010	LV2 ELEC ROOM (SET MAIN ELEC GEAR)	3	09MAY11	11MAY11	9	■ LV2 ELEC ROOM (SET MAIN ELEC GEAR)																																																																																																															
SUM5030	LV2 ELEC ROOM (CONDUIT R/I & CONN'S TO GEAR)	20	12MAY11	09JUN11	9	■ LV2 ELEC ROOM (CONDUIT R/I & CONN'S TO GEAR)																																																																																																															
SUM5050	LV2 ELEC ROOM (TEST GEAR)	3	10JUN11	14JUN11	16	■ LV2 ELEC ROOM (TEST GEAR)																																																																																																															
SUM5080	LV2 ELEC ROOM (PULL/TERM PRIMARY POWER)	10	10JUN11	23JUN11	9	■ LV2 ELEC ROOM (PULL/TERM PRIMARY POWER)																																																																																																															
SUM5090	LV2 ELEC ROOM (ENERGIZE MAIN ELECTRICAL GEAR)	0		23JUN11	9	◆ LV2 ELEC ROOM (ENERGIZE MAIN ELECTRICAL GEAR)																																																																																																															
LV2 MECHANICAL ROOM																																																																																																																					
SUM5500	LV2 MECH RM (SET MAJOR MECHANICAL EQPT)	10	12APR11	25APR11	6	■ LV2 MECH RM (SET MAJOR MECHANICAL EQPT)																																																																																																															
SUM5520	LV2 MECH RM (MECH PIPE TO EQPT)	25	26APR11	31MAY11	6	■ LV2 MECH RM (MECH PIPE TO EQPT)																																																																																																															
SUM5560	LV2 MECH RM (ELEC ROUGH-IN & CONN'S TO EQPT)	15	24MAY11	14JUN11	6	■ LV2 MECH RM (ELEC ROUGH-IN & CONN'S TO EQPT)																																																																																																															
SUM5540	LV2 MECH RM (INSULATION TO EQPT)	15	01JUN11	21JUN11	11	■ LV2 MECH RM (INSULATION TO EQPT)																																																																																																															
SUM5570	LV2 MECH RM (CONTROL ROUGH-IN & CONN'S TO EQPT)	15	08JUN11	28JUN11	6	■ LV2 MECH RM (CONTROL ROUGH-IN & CONN'S TO EQPT)																																																																																																															
SUM5580	LV2 MECH RM (CHECK/TEST/START-UP HVAC PUMPS)	5	29JUN11	06JUL11	6	■ LV2 MECH RM (CHECK/TEST/START-UP HVAC PUMPS)																																																																																																															
PENTHOUSE																																																																																																																					
SUM6000	PH (SET & ASSEMBLE AHU)	10	29APR11	12MAY11	8	■ PH (SET & ASSEMBLE AHU)																																																																																																															
SUM6520	PH (MECH PIPE & DUCT TO AHU'S)	25	06MAY11	10JUN11	8	■ PH (MECH PIPE & DUCT TO AHU'S)																																																																																																															
SUM6570	PH (CONTROL ROUGH-IN & CONN'S TO AHU)	15	18MAY11	08JUN11	25	■ PH (CONTROL ROUGH-IN & CONN'S TO AHU)																																																																																																															
SUM6560	PH (ELEC ROUGH-IN & CONN'S TO AHU)	15	06JUN11	24JUN11	292	■ PH (ELEC ROUGH-IN & CONN'S TO AHU)																																																																																																															
SUM6540	PH (INSULATION TO PIPE & DUCT)	15	13JUN11	01JUL11	8	■ PH (INSULATION TO PIPE & DUCT)																																																																																																															
SUM6580	PH (CHECK/TEST/START-UP AHU)	5	07JUL11	13JUL11	6	■ PH (CHECK/TEST/START-UP AHU)																																																																																																															
INTERIOR ROUGH-INS & FINISHES																																																																																																																					
LEVEL 1 ROUGH-INS & FINISHES																																																																																																																					
SUM10000	L1 (LAYOUT INTERIOR WALLS)	2	22FEB11	23FEB11	12	■ L1 (LAYOUT INTERIOR WALLS)																																																																																																															
SUM10050	L1 (FRAME FIRE & CORRIDOR WALLS, TOP 4' DW)	5	24FEB11	02MAR11	12	■ L1 (FRAME FIRE & CORRIDOR WALLS, TOP 4' DW)																																																																																																															
SUM10100	L1 (DUCTWORK/MECH PIPE MAINS)	10	25FEB11	10MAR11	12	■ L1 (DUCTWORK/MECH PIPE MAINS)																																																																																																															
SUM10150	L1 (DUCTWORK/MECH PIPE BRANCHES)	10	28FEB11	11MAR11	17	■ L1 (DUCTWORK/MECH PIPE BRANCHES)																																																																																																															
SUM10200	L1 (PLB MAINS FOR DOM/GAS/AIR/VAC)	8	03MAR11	14MAR11	12	■ L1 (PLB MAINS FOR DOM/GAS/AIR/VAC)																																																																																																															

Start Date 03MAY10
Finish Date 17AUG12
Data Date 04JUN10
Run Date 04APR11 08:55

■ Early Bar
■ Progress Bar
■ Critical Activity




STEM
HESS CONSTRUCTION + ENGINEERING SERV
ARTS + SCIENCE COMPLEX
PRELIMINARY
AREA EARLY DATES

Date	Revision	Checked	Approved

Activity ID	Activity Description	OD	ES	EF	TF	2010												2011												2012											
						J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S								

LEVEL 2 ROUGH-INS & FINISHES																																									
SUM20420	L2 (CEILING BRANCH CONDUIT)	8	19APR11	28APR11	296	■ L2 (CEILING BRANCH CONDUIT)																																			
SUM20500	L2 (FRAME INTERIOR PARTITIONS)	6	22APR11	29APR11	292	■ L2 (FRAME INTERIOR PARTITIONS)																																			
SUM20510	L2 (PLUMBING WALL ROUGH-INS)	8	27APR11	06MAY11	306	■ L2 (PLUMBING WALL ROUGH-INS)																																			
SUM20540	L2 (ELEC POWER/LIGHTING WALL ROUGH-IN)	10	27APR11	10MAY11	309	■ L2 (ELEC POWER/LIGHTING WALL ROUGH-IN)																																			
SUM20220	L2 (MECH/PLB INSULATION)	10	29APR11	12MAY11	26	■ L2 (MECH/PLB INSULATION)																																			
SUM20580	L2 (HANG DRYWALL PARTITIONS)	8	06MAY11	17MAY11	12	■ L2 (HANG DRYWALL PARTITIONS)																																			
SUM20520	L2 (TEST PLUMBING WALL ROUGH-INS)	2	09MAY11	10MAY11	315	■ L2 (TEST PLUMBING WALL ROUGH-INS)																																			
SUM20530	L2 (INSULATE PLUMBING WALL ROUGH-INS)	4	11MAY11	16MAY11	315	■ L2 (INSULATE PLUMBING WALL ROUGH-INS)																																			
SUM20550	L2 (MEP WALL CLOSE-IN INSPECTIONS)	5	17MAY11	23MAY11	315	■ L2 (MEP WALL CLOSE-IN INSPECTIONS)																																			
SUM20800	L2 (CEILING GRID/LIGHTS/GRD'S/SPRK ADJUSTMENTS)	12	18MAY11	03JUN11	26	■ L2 (CEILING GRID/LIGHTS/GRD'S/SPRK ADJUSTMENTS)																																			
SUM20600	L2 (TAPE & FINISH PARTITIONS)	10	24MAY11	07JUN11	2	■ L2 (TAPE & FINISH PARTITIONS)																																			
SUM20700	L2 (PRIME & 1ST COAT PAINT)	8	08JUN11	17JUN11	8	■ L2 (PRIME & 1ST COAT PAINT)																																			
SUM20730	L2 (PULL BRANCH WIRE)	8	08JUN11	17JUN11	10	■ L2 (PULL BRANCH WIRE)																																			
SUM20750	L2 (INSTALL VAV'S & CONNECTIONS)	8	10JUN11	21JUN11	10	■ L2 (INSTALL VAV'S & CONNECTIONS)																																			
SUM20860	L2 (SERVICE CARRIERS & DROPS TO CASEWORK)	8	20JUN11	29JUN11	8	■ L2 (SERVICE CARRIERS & DROPS TO CASEWORK)																																			
SUM20880	L2 (ABOVE GRID INSPECTION)	3	30JUN11	05JUL11	8	■ L2 (ABOVE GRID INSPECTION)																																			
SUM20900	L2 (FLOORING)	10	06JUL11	19JUL11	8	■ L2 (FLOORING)																																			
SUM20820	L2 (CHECK/TEST/START-UP VAV'S)	3	19JUL11	21JUL11	6	■ L2 (CHECK/TEST/START-UP VAV'S)																																			
SUM20840	L2 (MILESTONE CONDITIONED AIR AVAILABLE)	0		21JUL11	6	◆ L2 (MILESTONE CONDITIONED AIR AVAILABLE)																																			
SUM20910	L2 (SET CASEWORK & MEP FIXT'S/CONN'S)	15	22JUL11	11AUG11	6	■ L2 (SET CASEWORK & MEP FIXT'S/CONN'S)																																			
SUM20920	L2 (FINAL PAINT WALLS & CEILING)	8	26JUL11	04AUG11	13	■ L2 (FINAL PAINT WALLS & CEILING)																																			
SUM20930	L2 (CASEWORK COUNTERTOPS & SURFACE RACEWAYS)	10	12AUG11	25AUG11	6	■ L2 (CASEWORK COUNTERTOPS & SURFACE RACEWAYS)																																			
SUM20940	L2 (DROP CEILING TILE/DOORS/TRIMOUT)	8	16AUG11	25AUG11	6	■ L2 (DROP CEILING TILE/DOORS/TRIMOUT)																																			
SUM20990	L2 (WORK TO COMPLETE LIST)	5	26AUG11	01SEP11	32	■ L2 (WORK TO COMPLETE LIST)																																			

LEVEL 3 ROUGH-INS & FINISHES																																									
SUM30000	L3 (LAYOUT INTERIOR WALLS)	3	14MAR11	16MAR11	24	■ L3 (LAYOUT INTERIOR WALLS)																																			
SUM30050	L3 (FRAME FIRE & CORRIDOR WALLS, TOP 4' DW)	6	17MAR11	24MAR11	24	■ L3 (FRAME FIRE & CORRIDOR WALLS, TOP 4' DW)																																			
SUM30100	L3 (DUCTWORK/MECH PIPE MAINS)	15	21MAR11	08APR11	24	■ L3 (DUCTWORK/MECH PIPE MAINS)																																			
SUM30150	L3 (DUCTWORK/MECH PIPE BRANCHES)	15	23MAR11	12APR11	31	■ L3 (DUCTWORK/MECH PIPE BRANCHES)																																			
SUM30200	L3 (PLB MAINS FOR DOM/GAS/AIR/VAC)	10	18APR11	29APR11	12	■ L3 (PLB MAINS FOR DOM/GAS/AIR/VAC)																																			
SUM30300	L3 (FIRE PROTECTION MAINS)	6	02MAY11	09MAY11	283	■ L3 (FIRE PROTECTION MAINS)																																			
SUM30500	L3 (FRAME INTERIOR PARTITIONS)	8	02MAY11	11MAY11	292	■ L3 (FRAME INTERIOR PARTITIONS)																																			
SUM30210	L3 (PLB BRANCHES FOR DOM/GAS/AIR/VAC)	10	02MAY11	13MAY11	12	■ L3 (PLB BRANCHES FOR DOM/GAS/AIR/VAC)																																			
SUM30580	L3 (HANG DRYWALL PARTITIONS)	10	04MAY11	17MAY11	24	■ L3 (HANG DRYWALL PARTITIONS)																																			
SUM30510	L3 (PLUMBING WALL ROUGH-INS)	10	09MAY11	20MAY11	306	■ L3 (PLUMBING WALL ROUGH-INS)																																			
SUM30320	L3 (FIRE PROTECTION BRANCHES)	6	10MAY11	17MAY11	283	■ L3 (FIRE PROTECTION BRANCHES)																																			
SUM30540	L3 (ELEC POWER/LIGHTING WALL ROUGH-IN)	10	11MAY11	24MAY11	309	■ L3 (ELEC POWER/LIGHTING WALL ROUGH-IN)																																			
SUM30400	L3 (ELEC FEEDER CONDUITS)	8	12MAY11	23MAY11	283	■ L3 (ELEC FEEDER CONDUITS)																																			

Start Date	03MAY10	 Early Bar
Finish Date	17AUG12	 Progress Bar
Data Date	04JUN10	
Run Date	04APR11 08:55	 Critical Activity

STEM Sheet 7 of 11

HESS CONSTRUCTION + ENGINEERING SERV
ARTS + SCIENCE COMPLEX
PRELIMINARY
AREA EARLY DATES

Date	Revision	Checked	Approved

Activity ID	Activity Description	OD	ES	EF	TF	2010												2011												2012																																																																																			
						J				A				S				O				N				D				J				F				M				A				M				J				J				A				S				O				N				D				J				F				M				A				M				J				J				A				S			
LEVEL 5 ROUGH-INS & FINISHES																																																																																																																	
SUM50750	L5 (INSTALL VAV'S & CONNECTIONS)	10	28JUL11	10AUG11	5	■ L5 (INSTALL VAV'S & CONNECTIONS)																																																																																																											
SUM50800	L5 (CEILING GRID/LIGHTS/GRD'S/SPRK ADJUSTMENTS)	12	04AUG11	19AUG11	2	■ L5 (CEILING GRID/LIGHTS/GRD'S/SPRK ADJUSTMENTS)																																																																																																											
SUM50860	L5 (SERVICE CARRIERS & DROPS TO CASEWORK)	8	08AUG11	17AUG11	4	■ L5 (SERVICE CARRIERS & DROPS TO CASEWORK)																																																																																																											
SUM50820	L5 (CHECK/TEST/START-UP VAV'S)	3	11AUG11	15AUG11	5	■ L5 (CHECK/TEST/START-UP VAV'S)																																																																																																											
SUM50840	L5 (MILESTONE CONDITIONED AIR AVAILABLE)	0		15AUG11	12	◆ L5 (MILESTONE CONDITIONED AIR AVAILABLE)																																																																																																											
SUM50880	L5 (ABOVE GRID INSPECTION)	3	22AUG11	24AUG11	2	■ L5 (ABOVE GRID INSPECTION)																																																																																																											
SUM50900	L5 (FLOORING)	10	25AUG11	08SEP11	2	■ L5 (FLOORING)																																																																																																											
SUM50910	L5 (SET CASEWORK & MEP FIXT'S/CONN'S)	20	30AUG11	27SEP11	2	■ L5 (SET CASEWORK & MEP FIXT'S/CONN'S)																																																																																																											
SUM50920	L5 (FINAL PAINT WALLS & CEILING)	8	01SEP11	13SEP11	11	■ L5 (FINAL PAINT WALLS & CEILING)																																																																																																											
SUM50990	L5 (WORK TO COMPLETE LIST)	5	02SEP11	09SEP11	11	■ L5 (WORK TO COMPLETE LIST)																																																																																																											
SUM50930	L5 (CASEWORK COUNTERTOPS & SURFACE RACEWAYS)	12	28SEP11	13OCT11	2	■ L5 (CASEWORK COUNTERTOPS & SURFACE RACEWAYS)																																																																																																											
SUM50940	L5 (DROP CEILING TILE/DOORS/TRIMOUT)	10	30SEP11	13OCT11	2	■ L5 (DROP CEILING TILE/DOORS/TRIMOUT)																																																																																																											
PHASE 1 FINAL CLOSE-OUT																																																																																																																	
PHASE 1 FINAL CLOSE-OUT																																																																																																																	
SUM60000	PRE-FUNCTIONAL TESTING	25	09AUG11	13SEP11	5	■ PRE-FUNCTIONAL TESTING																																																																																																											
SUM60100	FINAL BUILDING LIFE SAFETY INSPECTIONS	20	21SEP11	18OCT11	0	■ FINAL BUILDING LIFE SAFETY INSPECTIONS																																																																																																											
SUM60050	HVAC BALANCING	20	19SEP11	14OCT11	2	■ HVAC BALANCING																																																																																																											
SUM60200	11-30-11 SUBSTANTIAL COMPLETION	0		18OCT11	0	◆ 11-30-11 SUBSTANTIAL COMPLETION																																																																																																											
SUM60300	PUNCLIST PERFORMANCE PERIOD	28	19OCT11	29NOV11	0	■ PUNCLIST PERFORMANCE PERIOD																																																																																																											
SUM60400	OWNER MOVE-IN	28	19OCT11	29NOV11	0	■ OWNER MOVE-IN																																																																																																											
SUM60500	PHASE 1 FINAL COMPLETION	0		29NOV11	0	◆ PHASE 1 FINAL COMPLETION																																																																																																											
SUM60510	1-12-12 START CLASSES	0	30NOV11		0	◆ 1-12-12 START CLASSES																																																																																																											
PHASE 3 RENOVATIONS																																																																																																																	
PHASE 3 START RENOVATIONS																																																																																																																	
SUM70000	1-12-12 START PHASE 3	0	30NOV11		0	◆ 1-12-12 START PHASE 3																																																																																																											
PHASE 3 LEARNING CENTER RENOVATIONS																																																																																																																	
SUM71000	LC (SELECTIVE ARCH/MEP DEMO)	20	30NOV11	28DEC11	0	■ LC (SELECTIVE ARCH/MEP DEMO)																																																																																																											
SUM71010	LC (STRUCTURAL & ENCLOSURE MODIFICATIONS)	25	29DEC11	02FEB12	5	■ LC (STRUCTURAL & ENCLOSURE MODIFICATIONS)																																																																																																											
SUM71020	LC (UNDERGROUND MEP & SLAB INFILLS)	15	20JAN12	09FEB12	31	■ LC (UNDERGROUND MEP & SLAB INFILLS)																																																																																																											
SUM72000	LC (LAYOUT INTERIOR WALLS)	3	10FEB12	14FEB12	31	■ LC (LAYOUT INTERIOR WALLS)																																																																																																											
SUM72020	LC (INTERIOR ROUGH-INS)	30	15FEB12	27MAR12	31	■ LC (INTERIOR ROUGH-INS)																																																																																																											
SUM72030	LC (INTERIOR FINISHES)	40	28MAR12	22MAY12	31	■ LC (INTERIOR FINISHES)																																																																																																											
SUM72640	LC (WORK TO COMPLETE LIST)	8	23MAY12	04JUN12	33	■ LC (WORK TO COMPLETE LIST)																																																																																																											
SUM72700	LC (HVAC BALANCING)	10	23MAY12	06JUN12	31	■ LC (HVAC BALANCING)																																																																																																											
SUM72750	LC (FINAL BUILDING LIFE SAFETY INSPECTIONS)	10	23MAY12	06JUN12	31	■ LC (FINAL BUILDING LIFE SAFETY INSPECTIONS)																																																																																																											
SUM72800	LC (SUBSTANTIAL COMPLETION)	0		06JUN12	31	◆ LC (SUBSTANTIAL COMPLETION)																																																																																																											
SUM72850	LC (PUNCLIST PERFORMANCE PERIOD)	15	07JUN12	27JUN12	31	■ LC (PUNCLIST PERFORMANCE PERIOD)																																																																																																											
SUM72900	LC (OWNER MOVE-IN)	15	07JUN12	27JUN12	31	■ LC (OWNER MOVE-IN)																																																																																																											

Start Date	03MAY10	■ Early Bar
Finish Date	17AUG12	■ Progress Bar
Data Date	04JUN10	■ Critical Activity
Run Date	04APR11 08:55	

STEM
HESS CONSTRUCTION + ENGINEERING SERV
ARTS + SCIENCE COMPLEX
PRELIMINARY
AREA EARLY DATES


Date	Revision	Checked	Approved

Appendix I

Accelerated Schedule Critical Path

Activity ID	Cal ID	Activity Description	OD	Start	Finish	Total Float	2010												2011												2012											
							J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	E								
INITIAL SITE MTGS/PERMITS/CRITICAL PROCUREMENT																																										
NTP/INITIAL SITE MEETINGS/PERMITS																																										
1	1	6-4-10 NOTICE TO PROCEED	0	04JUN10*		1																							6-4-10 NOTICE TO PROCEED													
10	1	INITIAL PLANNING & SCHEDULING	15	04JUN10	24JUN10	1																							INITIAL PLANNING & SCHEDULING													
20	1	MOBILIZE SITE CONTRACTOR	7	25JUN10	06JUL10	1																							MOBILIZE SITE CONTRACTOR													
INITIAL SITEWORK																																										
INITIAL SITE DEMO & SED/ER CONTROL																																										
4000	1	DEMO FOR SED/ER, CONST ENTRANCE, & SILT FENCE	4	07JUL10	12JUL10	1																							DEMO FOR SED/ER, CONST ENTRANCE, & SILT FENCE													
4010	1	DISCONNECT & REMOVE LIGHT FIXTURES	2	13JUL10	14JUL10	1																							DISCONNECT & REMOVE LIGHT FIXTURES													
4030	1	STRIP TOP SOIL	1	15JUL10	15JUL10	1																							STRIP TOP SOIL													
4020	1	SELECTIVE SITE DEMO	6	15JUL10	22JUL10	1																							SELECTIVE SITE DEMO													
4035	1	BLASTING OPERATIONS FOR PONDS & UTILITIES	10	16JUL10	29JUL10	1																							BLASTING OPERATIONS FOR PONDS & UTILITIES													
4040	1	CONSTRUCT BIO RET AREA 1 & 2	4	30JUL10	04AUG10	1																							CONSTRUCT BIO RET AREA 1 & 2													
POWER RELOCATION @ NEW BUILDING PAD																																										
4200	3	EXCV DB OLD SCE XFORMER TO NEW MH	5	05AUG10	12AUG10	1																							EXCV DB OLD SCE XFORMER TO NEW MH													
4250	3	EXCV DB NEW MH TO NEW XFORMER PAD	4	13AUG10	18AUG10	1																							EXCV DB NEW MH TO NEW XFORMER PAD													
4300	3	EXCV DB NEW XFORMER PAD TO EX CR BLDG MH	7	19AUG10	30AUG10	1																							EXCV DB NEW XFORMER PAD TO EX CR BLDG MH													
4310	3	CONDUIT & MH DB NEW XFORMER PAD TO EX CR BLDG MH	4	31AUG10	03SEP10	1																							CONDUIT & MH DB NEW XFORMER PAD TO EX CR BLDG MH													
4320	3	INSPECT DB NEW XFORMER PAD TO EX CR BLDG MH	1	07SEP10	07SEP10	1																							INSPECT DB NEW XFORMER PAD TO EX CR BLDG MH													
4330	3	CONCRETE NEW XFORMER PAD TO EX CR BLDG MH	1	08SEP10	08SEP10	1																							CONCRETE NEW XFORMER PAD TO EX CR BLDG MH													
4350	1	PULL & TERM WIRE DB OLD SCE TO EX CR	5	09SEP10	15SEP10	1																							PULL & TERM WIRE DB OLD SCE TO EX CR													
BUILDING PAD EXCAVATION																																										
5100	3	EXCV BLDG TO SUBGRADE FOR LV1 FND'S	15	08SEP10	30SEP10	0																							EXCV BLDG TO SUBGRADE FOR LV1 FND'S													
5120	3	EXCV BLDG TO SUBGRADE FOR LV3 FND'S	5	01OCT10	08OCT10	0																							EXCV BLDG TO SUBGRADE FOR LV3 FND'S													
SUBSTRUCTURE																																										
CL 9-7 LV1 SUBSTRUCTURE																																										
6010	3	CL 9-7: FRP PERIMETER FOOTING	3	11OCT10	14OCT10	0																							CL 9-7: FRP PERIMETER FOOTING													
6020	3	CL 9-7: FRP FOUNDATION WALLS	12	15OCT10	02NOV10	0																							CL 9-7: FRP FOUNDATION WALLS													
6040	3	CL 9-7: FRP STAIR 3 & SHAFT WALL TO LV 3	8	04NOV10	16NOV10	0																							CL 9-7: FRP STAIR 3 & SHAFT WALL TO LV 3													
6050	2	CL 9-7: CURE STAIR 3 & SHAFT WALL TO LV 3	7	17NOV10	23NOV10	0																							CL 9-7: CURE STAIR 3 & SHAFT WALL TO LV 3													
9-7 WALL BRACING/WP/BACKFILL FOUNDATION WALLS																																										
6620	3	CL 9-7: WATERPROOF WALLS FOR LV2 FND'S	3	24NOV10	30NOV10	0																							CL 9-7: WATERPROOF WALLS FOR LV2 FND'S													
6630	3	CL 9-7: DRAIN TILE @ WALLS FOR LV2 FND'S	2	02DEC10	03DEC10	0																							CL 9-7: DRAIN TILE @ WALLS FOR LV2 FND'S													
6640	3	CL 9-7: BACKFILL WALLS FOR LV2 FND'S	4	06DEC10	10DEC10	0																							CL 9-7: BACKFILL WALLS FOR LV2 FND'S													

Start Date 03MAY10
Finish Date 17AUG12
Data Date 04JUN10
Run Date 04APR11 09:01

 Early Bar
 Progress Bar
 Critical Activity

HESS CONSTRUCTION +
ENGINEERING SERVICES

Preliminary CPM Schedule

Sheet 1 of 4

Date	Revision	Checked	Approved

Activity ID	Cal ID	Activity Description	OD	Start	Finish	Total Float	2010												2011												2012											
							J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	E								

CL 9.2-11.5: LV3 SUBSTRUCTURE						
6700	3	CL 9.2-11.5: DRILL/INSTALL ROCK ANCHORS	3	13DEC10	16DEC10	0
6710	3	CL 9.2-11.5: TEST & INSPECT ROCK ANCHORS	3	17DEC10	21DEC10	0
6720	3	CL 9.2-11.5: FRP PERIMETER FOOTING	4	23DEC10	30DEC10	0
6730	3	CL 9.2-11.5: FRP FOUNDATION WALL	8	03JAN11	14JAN11	0
6740	3	CL 9.2-11.5: FRP STAIR #2 SHAFT WALL TO ROOF	12	10JAN11	28JAN11	0

- CL 9.2-11.5: DRILL/INSTALL ROCK ANCHORS
- CL 9.2-11.5: TEST & INSPECT ROCK ANCHORS
- CL 9.2-11.5: FRP PERIMETER FOOTING
- CL 9.2-11.5: FRP FOUNDATION WALL
- CL 9.2-11.5: FRP STAIR #2 SHAFT WALL TO ROOF

7-9 LV2 SLAB ON GRADE						
6800	3	CL 9-7: INTERIOR BACKFILL TO GRADE FOR LV2	2	17JAN11	18JAN11	0
6820	3	CL 9-7: UNDERGROUND PLB ROUGH IN FOR LV2 SOG	3	20JAN11	24JAN11	0
6840	3	CL 9-7: UNDERGROUND ELEC ROUGH IN FOR LV2 SOG	1	25JAN11	25JAN11	0
6850	3	CL 9-7: STONE FILL/SLAB PREP FOR LV2 SOG	2	27JAN11	28JAN11	0
6860	3	CL 9-7: IN-STONE ELECTRICAL ROUGH IN FOR LV2 SOG	2	31JAN11	01FEB11	0
6880	3	CL 9-7: LV2 POUR SLAB ON GRADE	1	03FEB11	03FEB11	0

- CL 9-7: INTERIOR BACKFILL TO GRADE FOR LV2
- CL 9-7: UNDERGROUND PLB ROUGH IN FOR LV2 SOG
- CL 9-7: UNDERGROUND ELEC ROUGH IN FOR LV2 SOG
- CL 9-7: STONE FILL/SLAB PREP FOR LV2 SOG
- CL 9-7: IN-STONE ELECTRICAL ROUGH IN FOR LV2 SOG
- CL 9-7: LV2 POUR SLAB ON GRADE

CL 9.2-11.5: LV3 SLAB ON GRADE						
6910	3	CL 9.2-11.5: INTERIOR BACKFILL TO GRADE FOR LV3	3	31JAN11	03FEB11	0
6920	3	CL 9.2-11.5 UNDERGROUND PLB ROUGH IN FOR LV3 SOG	3	04FEB11	09FEB11	0
6940	3	CL 9.2-11: UNDERGROUND ELEC ROUGH IN FOR LV3 SOG	1	11FEB11	11FEB11	0
6950	3	CL 9.2-11.5: STONE FILL/SLAB PREP FOR LV3 SOG	2	14FEB11	15FEB11	0
6960	3	CL 9.2-11.5: IN-STONE ELEC ROUGH IN FOR LV3 SOG	2	17FEB11	18FEB11	0
6980	3	CL 9.2-11.5: LV3 POUR SLAB ON GRADE	1	21FEB11	21FEB11	0

- CL 9.2-11.5: INTERIOR BACKFILL TO GRADE FOR LV3
- CL 9.2-11.5 UNDERGROUND PLB ROUGH IN FOR LV3 SOG
- CL 9.2-11: UNDERGROUND ELEC ROUGH IN FOR LV3 SOG
- CL 9.2-11.5: STONE FILL/SLAB PREP FOR LV3 SOG
- CL 9.2-11.5: IN-STONE ELEC ROUGH IN FOR LV3 SOG
- CL 9.2-11.5: LV3 POUR SLAB ON GRADE

SUPERSTRUCTURE STEEL




STEEL WEST SIDE LV3 TO ROOF						
7100	3	CL 1-7: ERECT COL & BEAMS 3RD TO ROOF	5	04FEB11	14FEB11	0
7110	3	CL 1-7: METAL DECK 4TH, 5TH & ROOF	4	15FEB11	21FEB11	0
7120	3	CL 1-7: DETAIL STEEL 4TH FLOOR	3	22FEB11	25FEB11	0
7130	3	CL 1-7: DETAIL STEEL 5TH FLOOR	3	28FEB11	03MAR11	0
7140	3	CL 1-7: DETAIL STEEL ROOF	3	04MAR11	08MAR11	0

- CL 1-7: ERECT COL & BEAMS 3RD TO ROOF
- CL 1-7: METAL DECK 4TH, 5TH & ROOF
- CL 1-7: DETAIL STEEL 4TH FLOOR
- CL 1-7: DETAIL STEEL 5TH FLOOR
- CL 1-7: DETAIL STEEL ROOF

STEEL EAST SIDE LV 3 TO ROOF						
7200	3	CL 7-11.1: ERECT COL & BEAMS 3RD TO ROOF	5	22FEB11	01MAR11	0
7210	3	CL 7-11.1: METAL DECK 4TH, 5TH & ROOF	4	03MAR11	08MAR11	0
7220	3	CL 7-11.1: DETAIL STEEL 4TH FLOOR	3	10MAR11	14MAR11	0
7230	3	CL 7-11.1: DETAIL STEEL 5TH FLOOR	3	15MAR11	18MAR11	0
7240	3	CL 7-11.1: DETAIL STEEL ROOF	3	21MAR11	24MAR11	0

- CL 7-11.1: ERECT COL & BEAMS 3RD TO ROOF
- CL 7-11.1: METAL DECK 4TH, 5TH & ROOF
- CL 7-11.1: DETAIL STEEL 4TH FLOOR
- CL 7-11.1: DETAIL STEEL 5TH FLOOR
- CL 7-11.1: DETAIL STEEL ROOF

Start Date 03MAY10
 Finish Date 17AUG12
 Data Date 04JUN10
 Run Date 04APR11 09:01

 Early Bar
 Progress Bar
 Critical Activity

HESS CONSTRUCTION +
 ENGINEERING SERVICES

 Preliminary CPM Schedule

Sheet 2 of 4

Date	Revision	Checked	Approved

Activity ID	Cal ID	Activity Description	OD	Start	Finish	Total Float	2010					2011					2012										
							J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F

SLAB ON DECK PLACEMENTS

EAST LEVEL 4 & LEVEL 5 SLAB ON DECK PLACEMENTS

8500	3	CL 11.1-7: 5TH FLR MECH/PLB DECK PREP	2	25MAR11	28MAR11	0
8510	3	CL 11.1-7: 5TH FLR ELEC DECK PREP	2	25MAR11	28MAR11	0
8520	3	CL 11.1-7: 5TH FLR CONCRETE DECK PREP	2	29MAR11	31MAR11	0
8530	3	CL 11.1-7: 5TH FLR STEEL INSPECTION	1	01APR11	01APR11	0
8550	3	CL 11.1-7: 5TH FLR POUR SLAB ON DECK	1	04APR11	04APR11	0

■ CL 11.1-7: 5TH FLR MECH/PLB DECK PREP
 ■ CL 11.1-7: 5TH FLR ELEC DECK PREP
 ■ CL 11.1-7: 5TH FLR CONCRETE DECK PREP
 ■ CL 11.1-7: 5TH FLR STEEL INSPECTION
 ■ CL 11.1-7: 5TH FLR POUR SLAB ON DECK

ENCLOSURE & SITE FINISHES

SUMMARY ENCLOSURE

SUM90100	3	PERIMETER CMU/STUDS/SHEATHING	25	18MAR11	29APR11	0
SUM90500	3	INSTALL CURTAIN WALLS & STOREFRONTS	20	14APR11	17MAY11	0

■ PERIMETER CMU/STUDS/SHEATHING
 ■ INSTALL CURTAIN WALLS & STOREFRONTS

SITE FINISHES

SUM91000	3	METAL PANELS & SOFFITS	40	14APR11	17JUN11	0
SUM91100	3	SITE HARDSCAPE	30	20JUN11	05AUG11	0
SUM91200	3	SITE LANDSCAPING	20	08AUG11	05SEP11	0
SUM91300	3	SITE WORK TO COMPLETE LIST	10	06SEP11	20SEP11	0

■ METAL PANELS & SOFFITS
 ■ SITE HARDSCAPE
 ■ SITE LANDSCAPING
 ■ SITE WORK TO COMPLETE LIST

PHASE 1 FINAL CLOSE-OUT

PHASE 1 FINAL CLOSE-OUT

SUM60100	1	FINAL BUILDING LIFE SAFETY INSPECTIONS	20	21SEP11	18OCT11	0
SUM60200	1	11-30-11 SUBSTANTIAL COMPLETION	0		18OCT11	0
SUM60300	1	PUNCHLIST PERFORMANCE PERIOD	28	19OCT11	29NOV11	0
SUM60400	1	OWNER MOVE-IN	28	19OCT11	29NOV11	0
SUM60500	1	PHASE 1 FINAL COMPLETION	0		29NOV11	0
SUM60510	1	1-12-12 START CLASSES	0	30NOV11		0

FINAL BUILDING LIFE SAFETY INSPECTIONS ■
 11-30-11 SUBSTANTIAL COMPLETION ◆
 PUNCHLIST PERFORMANCE PERIOD ■
 ■ OWNER MOVE-IN
 ◆ PHASE 1 FINAL COMPLETION
 ◆ 1-12-12 START CLASSES

PHASE 3 RENOVATIONS

PHASE 3 START RENOVATIONS

SUM70000	1	1-12-12 START PHASE 3	0	30NOV11		0
----------	---	-----------------------	---	---------	--	---

◆ 1-12-12 START PHASE 3

PHASE 3 LEARNING CENTER RENOVATIONS

SUM71000	1	LC (SELECTIVE ARCH/MEP DEMO)	20	30NOV11	28DEC11	0
----------	---	------------------------------	----	---------	---------	---




LC (SELECTIVE ARCH/MEP DEMO) ■

PHASE 3 CLASSROOM BUILDING

SUM81000	1	CR (SELECTIVE ARCH/MEP DEMO)	25	14DEC11	19JAN12	0
SUM81010	1	CR (STRUCTURAL & ENCLOSURE MODIFICATIONS)	35	20JAN12	08MAR12	0
SUM81020	1	CR (UNDERGROUND MEP & SLAB INFILLS)	15	24FEB12	15MAR12	0
SUM82000	1	CR (LAYOUT INTERIOR WALLS)	5	16MAR12	22MAR12	0
SUM82020	1	CR (INTERIOR ROUGH-INS)	50	23MAR12	01JUN12	0

CR (SELECTIVE ARCH/MEP DEMO) ■
 CR (STRUCTURAL & ENCLOSURE MODIFICATIONS) ■
 CR (UNDERGROUND MEP & SLAB INFILLS) ■
 CR (LAYOUT INTERIOR WALLS) ■
 CR (INTERIOR ROUGH-INS) ■

Start Date 03MAY10
 Finish Date 17AUG12
 Data Date 04JUN10
 Run Date 04APR11 09:01









 Early Bar
 Progress Bar
 Critical Activity

HESS CONSTRUCTION +
 ENGINEERING SERVICES




 Preliminary CPM Schedule

Sheet 3 of 4

Date	Revision	Checked	Approved

Activity ID	Cal ID	Activity Description	OD	Start	Finish	Total Float	2010												2011												2012											
							J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	E								
PHASE 3 CLASSROOM BUILDING																																										
SUM82030	1	CR (INTERIOR FINISHES)	60	23APR12	17JUL12	0																							CR (INTERIOR FINISHES) 													
SUM82640	1	CR (WORK TO COMPLETE LIST)	8	18JUL12	27JUL12	0																							CR (WORK TO COMPLETE LIST) 													
SUM82700	1	CR (HVAC BALANCING)	8	18JUL12	27JUL12	0																							CR (HVAC BALANCING) 													
SUM82750	1	CR (FINAL BUILDING LIFE SAFETY INSPECTIONS)	8	18JUL12	27JUL12	0																							CR (FINAL BUILDING LIFE SAFETY INSPECTIONS) 													
SUM82800	1	CR (SUBSTANTIAL COMPLETION)	0		27JUL12	0																							CR (SUBSTANTIAL COMPLETION) 													
SUM82850	1	CR (PUNCHLIST PERFORMANCE PERIOD)	15	30JUL12	17AUG12	0																							CR (PUNCHLIST PERFORMANCE PERIOD) 													
SUM82900	1	CR (OWNER MOVE-IN)	15	30JUL12	17AUG12	0																							CR (OWNER MOVE-IN) 													
SUM82950	1	CR (PHASE 3 FINAL COMPLETION) 9-28-12	0		17AUG12	0																							CR (PHASE 3 FINAL COMPLETION) 9-28-12 													

Start Date 03MAY10
Finish Date 17AUG12
Data Date 04JUN10
Run Date 04APR11 09:01

 Early Bar
 Progress Bar
 Critical Activity

HESS CONSTRUCTION +
ENGINEERING SERVICES

Preliminary CPM Schedule

Date	Revision	Checked	Approved