WESTINGHOUSE BUILDING 4 TECHNICAL ASSIGNMENT 2

2010

Æ



Jonathan M Fisher Robert Leicht 10/27/2010



Table of Contents

Executive Summary3
Detailed Project Schedule4
Site Layout Planning5
Detailed Structural System Estimate6-7
General Conditions Estimate8
Critical Industry Issues9-11
Appendix A12-16
Appendix B17-18
Appendix C19-25
Appendix D26-28

Technical Assignment Two

Jonathan Fisher – CM

Robert Leicht

Executive Summary

Technical Assignment Two is intended to expand upon some of the logistic and project planning aspects of the Westinghouse Building 4 project. A detailed project schedule for the site will look into and explain this projects individual phases and processes. A site plan laying out the logistics of the excavation phase of the project will be explored in detail along with a thorough investigation into the costs of the structural system of the building. Finally, a general conditions estimate that is unique to this particular project will be produced and explained.

A key finding in the project schedule is that it is laid out in such a way that the subcontractors can start working on new sections of the building while another part of their team finishes the last part. This schedule feature allows the project to progress faster and keeps work going in different parts of the building simultaneously. This method of scheduling also leaves room subcontractor delays. If a portion of the building is delayed the full subcontractor team can continue working on the current part of the building and then move on all together when the next portion is ready. The site layout plan for Building 4 is very simple and generic. The building is being building built in a very rural part of Pennsylvania so it has few site logistics abnormalities. One key feature of this site plan is its openness. Having a large parking lot at their disposal at all times makes it very easy for Turner Construction to run a wellorganized site during all phases. The detailed structural estimate revealed that there are 2,772 cubic yards of concrete and 443 tons of structural steel supporting the new building. A cost analysis revealed very similar findings between the structural costs found while conducting the RS Means square footage estimate and conducting and RS Means Costs works analysis. The general conditions estimate was just a little lower than most building coming in at 7.3% of the overall cost of the project. This is due to the low cost of the personal needed on site at any one time because of the small project size. It was also found in this section that the insurance and bonds portion of the project was abnormally high in terms of its overall percentage of the estimate.

Detailed Project Schedule

*See Appendix A for the detailed project schedule

Turner Construction employed a unique construction schedule technique when constructing the Westinghouse Building 4 project. The building schedule is broken down into several sections that break out the schedule by both floor and discipline. This method of breaking down the schedule made it very easy to identify where in the building contractors would be spending their time considering the unique method of phasing that was employed. Since the building is only three floors, the construction team was able to use a method of phasing that allowed them to be working on multiple floors simultaneously. For example, while the electrical work is being finished up on the 2nd floor the electrical contractor is scheduled to begin the 3rd floor wiring. This was an effective method of phasing on this project because it allowed work to move forward at a quicker pace.

Sequencing the structure of the building was a simple and straightforward process. The steel and metal decking were constructed at the same time and less than a month later the interior metal framing began. Again, the building height and simplicity made this possible because the whole steel erection process only lasted 3 weeks. During these three weeks while the steel was still being erected, the first concrete of the slab on grade was poured. The pouring of the slabs on deck started the same day that the last of the steel decking was placed. The rush on the slab on grade was necessary so that the workers would have a solid ground floor to walk around on and a place to store equipment and materials.

The electrical system of the building is an excellent example of how the MEP systems were broken down into the rough-in, distribution, and finishing stages. The electrical rough-in process started just 3 days before the first wiring was placed in the building. Once the wiring was completed, a three month electrical break occurred before the lighting was connected. This 3 month period is meant to give the other mechanical contractors time to finish their above ceiling work before the suspended ceiling tile was installed and the ceilings were ready for the lights. Balancing the system is the final step of the MEP process. There is a grace period of several months left before this stage to ensure that all building construction is completed and ready for a fair evaluation. Looking at the other mechanical systems reveals a similar timing and delivery method as was used for the electrical system.

There were no real timing constraints on the project that added difficulty to the schedule. The building does not block the flow of traffic on any major roads nor did it have any specific events that it had to be ready for. However, keeping top this schedule was very important to the customer who is renting office space in other buildings until this one is completed. Westinghouse building 4 was completed on time and actually received its certificate of occupancy 3 months ahead of schedule.

Site Layout Planning

*See Appendix B for site layout plan

When analyzing the site layout planning for this project there are several key elements that should be pointed out. Westinghouse Building 4 has a unique and valuable site for this project. Being a smaller project in a non-congested area, the building's workers were able to utilize the surrounding parking lots and space directly adjacent to the building. Shown on the site plan as the only major building sharing the site, Westinghouse Building 3 is owned by the same company and is thus more than happy to help out the project team and be accommodating in any way they can. Contractors on the job are allowed to park and store extra building materials outside the actual project property line which allows for less on site congestion.

The site plan shown was developed for the excavation and early steel erection phases of the project. A sloped cutback at the west side of the site allows for excavators and large equipment to enter the building footprint during excavation. Being the this excavation is only extending an average of 6 feet down this sloped cutback is all that is required and no additional equipment ramps are required. The 200 ton crawler crane that will be on site has an entire side of the building to itself to move back and forth along the building throughout construction. Any deliveries to the site will utilize the back entrance on the west side of the site and circle around the south of the building to drop their loads. This feature allows the north road of the site to be used only for dump trucks and concrete trucks to minimize traffic congestion around the site. Also, the site dumpsters and wood chipping area sit right next to the road to minimize the amount of site dump trucks have to traverse during trash removal.

All of the trailers and temporary toilet facilities sit onside the construction fence in the neighboring Westinghouse parking lot. This site features allows for enough space so that workers do not have to yell over the sounds of construction during meetings and close enough that walking to and from the bathroom is not a problem.

The temporary site power is a unique feature to the Westinghouse Building 4 project. Having just completed the first 3 buildings, Westinghouse was already planning for the fourth building to begin construction. The power supply shed on the site that feeds the main 3 buildings was constructed with the power hook ups for the fourth building. This made it very easy for the construction team to tap into the grid power to quickly set up the temporary power supply. This feature was also handy in the later stages of construction when the temporary power lines on the site were just simply converted to permanent ones.

Detailed Structural Systems Estimate

*See Appendix C for detailed structural systems take off and cost

Westinghouse Building 4 utilizes a simple concrete spread footing substructure with a steel frame superstructure. Sixty footings total distribute the load from the floors above to the ground below. Table 1 below shows the total amount of material with the building. These quantities along with, which entity they came from allowed for the detailed structural systems cost to be done using RS Means Cost Works. To obtain these numbers a waste factor of 5% was used for the concrete and a waste factor of 10% was used for the formwork. All of the structural steel pieces would be cut via the shop drawings and no waste factor was applied.

Material	Material Totals										
System	Units	Total									
CIP	CY	2772									
Structural Steel	tons	442.812									
Rebar	tons	30									
Formwork	LF	9209									

Table 1: shows the total amount of the various structural materials required for Westinghouse Building 4

Table 2 shows the comparison between the estimated structure costs using the RS Means square footage estimate conducted in tech report 1 and the system costs using the RS Means Cost Works program. When looking at the results it is easy to see that the CIP estimate differs greatly. This anomaly occurs because the RS Means Square Footage Estimate only accounts for the concrete in the slab on grade. This leaves out a significant amount of concrete that lies in the building's footing, piers, and foundation walls. Had this extra concrete been accounted for it would be expected that the estimates would be much closer. The Structural Steel estimate however, is extremely similar in the two cases, only differing by 3 cents per square foot.

Structural System Cost											
RS Means SF Estimate (Tech 1) Values Cost Works Estimate											
System	Total	\$/SF	Total	\$/SF							
CIP	\$755,540.00	\$6.24	\$1,345,477.00	\$11.12							
Structural Steel	\$1,686,787.00	\$13.94	\$1,682,598.00	\$13.91							

Table 2: shows a comparison between the structural system estimate conducted for tech report 1 and the estimate using RS Means Cost Works.

The structural steel in Building 4 is laid out in 7 different patterns. The system is very simple in general because this system is the same in is the same in all floor systems. Figure 1 shows the layout of the bays in a single floors and shows how the bays repeat themselves quite frequently. This repetition of bay and floor structural systems is a common feature of office buildings and buildings with congruent space uses on each floor. The building itself is symmetrical about its axis so it only make sense that its structural system would follow suite. It should be noted that the number 7 bays house the elevators and the number 5 bays house the vertical stairwells and mechanical runs.

1	2	2	2	2	2	2	2	2	2	2	2	1
3	4	5	6	4	7	4	7	4	6	5	4	3
1	2	2	2	2	2	2	2	2	2	2	2	1

Figure 1: Shows the labeling of the bays within Westinghouse Building 4. Repeating numbers represent identical bays.

When conducting the structural systems estimate using RS Means Cost Works the program assumes a value for equipment and Labor. This program also automatically assigns an appropriate value for the amount and size of rebar in each concrete quantity depending on its thickness and strength. Time and location factors are also automatically applied by selecting a start time of the project and project location. One assumption that was made during the concrete square footage was that the vertical shafts that run through the building were not subtracted from the square footage of the floors. This would only really come into play in the second and third floor because the roof and the slab on grade have fewer penetrations.

General Conditions Estimate

*See Appendix D for General Conditions Estimate

The general conditions estimate for Westinghouse Building 4 was conducted using two different resources. By using a combination of RS Means and knowledge provided by the project manager on site a fairly accurate estimate was compiled without releasing any proprietary information. Table 3 below shows a breakdown of the total results from the four areas of the general conditions estimate. The total general conditions costs of this project is about 7.3% of the total building cost. The general conditions

costs on an average construction project is between 8% and 10% of the project value with a larger difference between the personal costs and the insurance and bonds costs. Westinghouse Building 4 is a unique project because it has a smaller on site project team and thus less personal costs throughout the project. This feature brings down the total

personal cost of the project which in turn yields a lower overall cost estimate for the general conditions.

General Conditions	Summary
Personal	\$530,400.00
Temporary Facilities, Utilites,	\$250,450,00
and Equipment	3230,430.00
Miscellaneous	\$59,400.00
Insurance and Bonds	\$448,052.98
Total GC Cost	\$1,288,302.98

Table 3: shows a comparison between the 4 categories of the general conditions estimate.

Figure 2 shows how the \$1.2 million is distributed on the project. The personal cost accounts for 41% of the total and includes all people directly involved in this project. It should be noted that this personal cost does include the cost of the estimator's time to come up with a detailed project estimate. The amount of time each person on the project team actually spends on this project is estimated. Complications and unexpected change orders may require more time from certain people and thus change this amount. The second largest cost is the insurance and bonds cost. This category encompasses all of the expenses associated with insuring the site and its occupants along with all the costs of permits and bonds on the project. The temporary facilities, utilities, and project equipment total accounts for 10% of the overall project. This category includes costs such as: trailer costs, crane



costs, dumpster costs, and temporary power, water, and electric costs. Each one of these entities must be accounted for to ensure that all necessary subjects arrive to the site when they are supposed to and removed on time to avoid pointless spending. The last category is the miscellaneous costs, which are relatively small individually, but can add up to large sums of money in the end.

Figure 2: shows the breakdown of the general conditions estimate.

Critical Industry Issues

This year the 19th annual PACE Roundtable was held at The Pennsylvania State University. The purpose of the meeting is to create opportunity for industry leaders, professors, and students to interact and discuss pertinent industry issues that are currently plaguing the construction industry. In addition to a large meeting environment there were also several smaller breakout session that gave an opportunity for more face to face interaction between individuals. One of these breakout sessions discussed Integrated Project Delivery, or IPD. Another was a very informative session that discussed the future of electricity monitoring and metering called Smart Grid. These sessions were very informative and valuable to take part in because they discuss some of the issues that are currently plaguing our industry because of either lack of participation amongst industry members or lack of knowledge of the technology.

IPD, or Integrated Project Delivery, was hosted by Robert Leicht and discussed some of the issues that cause the construction industry to be less productive than it could be. Integrated Project Delivery is a delivery method that is meant to ease the delivery of a project and speed up the procurement time, but there are major barriers that industry members must first overcome before this method can work. This system of delivery is always a Design-Build delivery method because all subcontractors must be brought on board early in the design phase of the project. Also, in this new type of delivery there is no individual entity to blame for hold ups or bad estimates. However, IPD also has some real advantages over traditional delivery methods. IPD encourages collaboration and shares responsibility on a jobsite, which leads to more innovative projects and can lead to a speedier construction time.

Industry barriers that discourage IPD from becoming common place in construction are vast and complicated. Working together and sharing information is not traditionally held as a high priority on a job site amongst the different trades and managers, but it is of the utmost importance on an IPD site. Subcontractors are usually chosen on a lowest bid basis and only want to accomplish the minimum amount they have to then move on to their next job. In IPD however, the mechanical contractor for example has just as much at stake in the project as say the bricklayer. All trades must work together and help each other in order for the job to get done correctly and on budget. Also, deciding who is at fault for certain schedule delays or extra cost on a project is of utmost importance to all entities on the jobsite because people's lively hoods and wages are at risk when expensive mistakes or miscalculations occur.

Another barrier that IPD must overcome is minimizing the initial job target cost. Because there is no GMP initial contract agreements and pricing must be agreed upon by all entities up front. Usually if a project goes over budget the owner is stuck footing the bill so it is very important to get them on board and understanding their responsibilities before the project gets under way. Traditional design-bid-build construction is also usually cheaper because the lowest bid of all of the subcontracts is chosen so that the overall building cost is minimized. In IPD however this minimizing cost technique cannot be

utilized because all parts of the project team are brought on so early so other cost cutting techniques must be investigated. With high collaboration and cooperation on site value engineering is an easy way to cut costs on an IPD job. Another barrier for IPD to overcome, especially in today's economy, is that it cannot be used on state or federal projects because they require that competitive bidding take place on the projects.

IPD, along with its challenges, also carries with it many positive aspects. Since there is more collaboration and cooperation on IPD sites the jobs usually turn out to be more innovative than traditional jobs. Trades are encouraged to share ideas and find solutions instead of determine blame and create excuses. Another positive is that subcontractors are often given more authority on IPD projects and are allowed to make their own educated decisions on the spot in the field to solve a problem. This decreases the amount of time that is wasted while subs wait to hear back for the architect or other authoritative figure on design changes. The positives of IPD definitely outweigh the negatives, but the culture of the construction industry is very difficult to change because it has been the same way for so long. Hopefully with the integration of BIM and 4D modeling closer collaboration will take place on sites and one day Integrated Project Delivery construction will be a viable option for owners to pursue on their projects.

The breakout session pertaining to Smart Grad technology was more of an information session than a discussion. The session was very valuable and informative and brought to light some concepts that could help address the energy crisis going on around the world right now. Dr. Riley headed this session and used a very interesting example to describe Smart Grid technology. He described how the electricity company offered Penn State a large sum of money to show that they could drop their electricity consumption suddenly my several megawatts. Being that my building is being built for a power company I can relate closely to this concept. When power companies have to buy electricity from other companies the costs are very high and the company does not make any profit. For this reason Smart Grid could be used to reduce consumption while, say a power plant is being serviced.

Other aspects of Smart Grid Technology include advanced metering, small quantity power generation, and cyber security over the system. The concept of advanced metering involves installing meters on buildings and even homes that measure not only the quantity of electricity being used but the time of day that energy is being used. This technology may encourage building owners to install battery banks in their buildings that charge at night when power is cheaper and then discharge them during the day. Small quantity power generation involves the generation of small amounts in large amounts of locations to balance grids. This idea could include anything from smaller power plants to putting solar panels on the roofs of buildings. These ideas should be at the forefront of the industry because indications are already apparent that power companies will not be able to keep up with demand in the future. A risk of using Smart Technology is that computer hackers could break into your meter online and determine when you are home during the day. If burglars knew when you were not home it would be an excellent opportunity for them to break in and rob your house.

Both of these breakout sessions presented ideas that could be directly applied to my project. It would be interesting to investigate how IPD could have been used on the Westinghouse Building 4

project to create a more innovative project. Being that the project is a privately owned project IPD could have been a valuable delivery method that showed how it successfully delivers projects both on time and on budget. Westinghouse advertises them self as a green company because they design nuclear power plants that do not generate green house gasses. Smart Grid Technology could be installed in their new building to show another way that they are trying to help the global energy crisis. In every new technology there must be genie pigs and I plan to investigate both of these industry ideas for my thesis building.

Both during the main meeting and the breakout sessions the industry leaders were excited to share their knowledge and experience from the field. Some of this information could not be learned in a classroom, which made this event very valuable to both students and industry members of other trades. Later down the road in this project I think it would be valuable to contact Robert Grottenthaler from Barton Malow about IPD. In the breakout session Bob shared multiple experiences working with this delivery method and seemed like he could definitely share more knowledge on the subject. Shawn Cingle from Southland Industries attended both of the breakout sessions that I attended. He would be another person I would contact on both subjects, but especially the Smart Grid Technology. Being that he works for an electrical subcontractor I think he would be an excellent contact from the industry.

Appendix A – Detailed Project Schedule

ID	0	Task Mode	Task Name	Duration	n Start	Finish	November	December	January	February Feb	March Mar	April	May May	June
1		*	First Level Schedule	191 day	/s Tue 12/1/09	Tue 8/24/10			5411	1.60	Inter	7,01	inay	Jan
2	_	*	2336 Poke-Thru RI	4 days	Tue 12/1/09	Fri 12/4/09								
3		*	1001 Slab on Grade 1	2 days	Mon 12/14/0	Tue 12/15/09		Π						
4	_	*	1002 Slab on Grade 2	2 days	Fri 12/18/09	Sat 12/19/09		Π						
5	_	*	1003 Slab on Grade 3	2 days	Tue 12/22/09	Wed 12/23/09		I						
6	_	*	1004 Slab on Grade 4	2 days	Wed 12/30/0	Thu 12/31/09			1					
7		*	1005 Slab on Grade 5	, 2 days	Thu 1/7/10	Fri 1/8/10			D					
8	_	*	1006 Slab on Grade 6	, 2 days	Fri 1/15/10	Sat 1/16/10			T					
9	_	*	2251 Electrical OH RI	, 10 days	Mon 2/22/10	Fri 3/5/10								
10		*	1061 SOFP 1st Floor	2 days	Tue 2/23/10	Wed 2/24/10				I				
11		*	2101 Mechanical OH RI	, 13 days	Wed 2/24/10	Fri 3/12/10								
12	_	*	1062 SOFP 1st FLoor	2 days	Fri 2/26/10	Mon 3/1/10								
13	_	*	2102 Mechanical OH RI	, 15 davs	Fri 2/26/10	Thu 3/18/10								
14		*	1181 Sprinkler Mains and Branch	nes 24 days	Mon 3/1/10	Thu 4/1/10					C			
15	_	*	1740 Interior Framing	, 11 days	Tue 3/9/10	Tue 3/23/10								
16	_	*	2325 Electrical In-Wall RI	, 28 davs	Wed 3/10/10	Fri 4/16/10					C			
17		*	1741 Interior Framing	, 24 davs	Thu 3/11/10	Tue 4/13/10					C			
18	_	*	1142 Plumbing OH RI	25 days	Fri 3/12/10	Thu 4/15/10					C			
19	_	*	1750 Interior Framing	, 3 davs	Tue 3/16/10	 Thu 3/18/10	-							
20	_	*	2127 Duct Insulation	, 7 davs	Wed 4/14/10	 Thu 4/22/10								
21		*	2432 Drywall T & F	, 39 days	Fri 4/16/10	Wed 6/9/10								
22	_	*	1200 Switchgear Installation	, 5 davs	Mon 5/24/10	Fri 5/28/10								
23	_	*	2342 Finish Walker-Duct- 1	, 5 days	Wed 6/9/10	Tue 6/15/10								
24	_	*	2730 Tile Floors and Walls 1st Fl	8 days	Thu 6/10/10	Mon 6/21/10								
25	_	*	2431 Drywall T & F (exterior wall	l) 10 days	Tue 7/6/10	Mon 7/19/10								
26	_	*	2530 Painting 1st Fl	7 days	Wed 7/21/10	Thu 7/29/10								
27	_	*	2630 Ceilings 1st Fl	8 days	Wed 7/21/10	Fri 7/30/10								
28		*	2930 Sprinkler Heads 1st Fl	6 days	Wed 7/21/10	Wed 7/28/10								
29	_	*	3030 Diffuser Installation 1st Fl	6 days	Fri 7/23/10	Fri 7/30/10								
30		*	2830 Finish Power 1st Fl	5 days	Mon 7/26/10	Fri 7/30/10								
31		*	3130 Lighting 1st Fl	7 days	Wed 7/28/10	Thu 8/5/10								
32		*	3560 Set Doors and Hardware 1s	st Fl 5 days	Fri 7/30/10	Thu 8/5/10								
33		*	3330 Flooring 1	12 days	Tue 8/3/10	Wed 8/18/10								
34		*	4060 Casework	10 days	Wed 8/11/10	Tue 8/24/10								
35		*	11430 Punchlist 1st Fl	10 days	Wed 8/11/10	Tue 8/24/10								
36		*	Second Floor Schedule	137 day	/s Thu 2/4/10	Fri 8/13/10								
37		*	1011 Slab on Deck 2	2 days	Thu 2/4/10	Fri 2/5/10]							
38		*	1012 Slab on Deck 2	2 days	Thu 2/11/10	Fri 2/12/10				I				
39		*	1013 Slab on Deck 2	2 days	Tue 2/16/10	Wed 2/17/10				I				
40		*	1014 Slab on Deck 2	2 days	Wed 2/17/10	Thu 2/18/10				I				
41		*	1063 SOFP 2nd Floor	3 days	Mon 3/1/10	Wed 3/3/10								
			Task		Project Summary		lr	nactive Milesto	ne 💠		Manual S	Summary Rollu	ıp	D
Projec	t. Eull c	Schedule	Split		External Tasks		lr	nactive Summa	ry 🖵		Manual S	Summary		Pr
Date:	Mon 10)/25/10	Milestone	•	External Milestone	۵	N	Aanual Task	, 		Start-only	, v	С	
		-	Cummon	•		▼		uration call	10100			7 	-	
			Summary		inactive Task			vuration-only			Finish-on	пу	-	
								Page 1						

ıy	June	July	August	September	October
May	Jun	Jul	Aug	Sep	Oct
	Dead	line ress	÷		

ID	_	Task	Task Name	Duration	Start	Finish	November	December	January	February	March	April	May	June	July	August	September October
42	0	Mode	2102 Machanical OU DI	21 days	Mar 2/9/10	Nam 4/5/10	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep Oct
42			2103 Mechanical OH RI	21 days	Wion 3/8/10	Wion 4/5/10					<u> </u>						
45			2254 Electrical OU BL	17 days	Thu 3/25/10	Fri 4/16/10					1						
44			1142 Diumbing Old Di	10 days	1110 3/25/10	Wed 4/7/10	_				I						
43				10 Udys	Wod 2/21/10	100014/19/10	_										
40		×.	2334 POKE-I II'U KI	6 days	Wed 3/31/10) Wed 4/7/10											
47		×.	2328 Electrical In-Wall Ri	IU days	1 nu 4/1/10	Wed 4/14/10											
40		×.	1760 Interior Framing	7 days	Wed 4/7/10	1nu 4/15/10											
49 E0			2135 Duct Insulation	11 days	Thu 4/20/10	Vveu 4/21/10							P				
50	_	× 	2428 Drywall T & F - Duct Shalls	27 days	Thu 4/29/10	F(10/4/10)							L				
51			2434 Drywall T & F (exterior wall)	14 udys	Tue 6/22/10	FII 7/9/10	_							-			
52	_	×	2520 Palliting 2nd Fl	7 uays	Mon 7/12/10) Tue $7/20/10$	_										
54		×	2720 Tile Fleers and Walls and Fl	o uays	Mon 7/12/10	$\sqrt{100}$ Wed $7/21/10$	-										
55	_	×	2720 The Floors and Walls 210 Fl	o uays	Mon 7/12/10	$\sqrt{10}$ Weu $7/21/10$	-										
56		 - ♪	2020 Splitticer Installation 2nd El	6 days	Wed 7/14/10	$W_{ed} 7/21/10$											
57		 - ♪	2120 Lighting 2nd El	0 days	Mon 7/19/10	$T_{\rm U0} = \frac{7}{27} \frac{10}{10}$	_										
58			2550 Set Doors and Hardware and E	7 uays	Wod 7/21/10	Tue $7/27/10$											
59		- <u>-</u>	2220 Elooring 2	6 days	Eri 7/22/10	$r_{10} = 7/20/10$									r -		
60		-	2340 Poke-Thru Install	5 days	Mon 8/2/10	Fri 8/6/10	_								-	-	
61		-	3321 Elooring 2	6 days	Mon 8/2/10	Mon 8/9/10											
62		-	A040 Casework	11 days	Mon 8/2/10	Mon 8/16/10											
63		-	11/20 Punchlist 2nd El	10 days	Mon 8/2/10	Fri 8/13/10	_										
64	_		Third Floor Schedule	10 ddys	s Fri 2/19/10	Thu 7/29/10											
65	_		1015 Slab on Deck 3	2 days	Eri 2/19/10	Sat 2/20/10				Π						-	
66		-	016 Slab on Deck 3	2 days	Tue 2/23/10	Wed 2/24/10				-							
67		*	1017 Slab on Deck 3	2 days	Wed 2/24/10) Thu $2/25/10$				-							
68		*	1018 Slab on Deck 3	2 days	Fri 2/26/10	Sat 2/27/10				_	1						
69	_	*	1065 SOFP 3rd Floor	4 days	Mon 3/15/10) Thu 3/18/10											
70		*	2105 Mechanical OH RI	21 davs	Wed 3/24/10) Wed 4/21/10	-]					
71	_	*	1145 Plumbing OH RI	21 davs	Mon 3/29/10) Mon 4/26/10	-										
72	_	*	2332 Poke-Thru RI	8 days	Wed 3/31/10) Fri 4/9/10	-										
73		*	2255 Electrical OH RI	13 days	Tue 4/6/10	Thu 4/22/10											
74		*	1146 Plumbing OH RI	, 15 days	Wed 4/7/10	Tue 4/27/10											
75		*	1790 Interior Framing	10 days	Fri 4/9/10	Thu 4/22/10											
76		*	1186 Sprinkler Mains and Branches	11 days	Wed 4/14/10) Wed 4/28/10							3				
77		*	2330 Electrical In-Wall RI	5 days	Mon 4/19/10) Fri 4/23/10	_										
78		*	2136 Duct Insulation	5 days	Thu 4/22/10	Wed 4/28/10	-										
79		*	2429 Drywall T & F - Duct Shafts	8 days	Wed 5/5/10	Fri 5/14/10											
80		*	2452 Drywall T & F - Interior	20 days	Tue 5/18/10	Mon 6/14/10							C				
81		*	2436 Drywall T & F Exterior Wall	11 days	Mon 6/7/10	Mon 6/21/10											
82		*	2610 Ceilings 3rd Fl	20 days	Tue 6/8/10	Mon 7/5/10								C			
			Task		Project Summary		lna	active Milestor	ne 🔷		Manual	Summary Rollu	up qu	Dea	dline	₽	
Proie	ect: Full :	Schedule	Split		External Tasks		lna	active Summar	y 🖵		Manual :	Summary	—	Pro:	gress		
Date	e: Mon 1	0/25/10	Milestone 🔶		External Milestone	•	M	anual Task	C		Start-on	ly	C				
			Summary		Inactive Task		Dı.	iration-only			Finish-or	nly	3				
								Рада 2				,					
								I USC Z									

ID		Task	Task Name	Duration	Start	Finish	Novembe	r December	January	February	March	April	May
83	•		2910 Sprinkler Heads 3rd Fl	6 days	Wed 6/9/10	Wed 6/16/10	NOV	Dec	Jdfi	Feb	IVIdí	Арг	IVIdy
84	-	- 🐊	2/137 Drywall T & E Exterior Wall	10 days	Mon 6/14/10	Fri 6/25/10	_						
85		- 🐊	2510 Painting 3rd Floor	10 days	Mon 6/28/10	Thu 7/1/10	_						
86		- 🐊	2710 Tile Floors and Walls 3rd Fl	8 days	Mon 6/28/10	$W_{ed} 7/7/10$	_						
87		- 🐊	2210 Finish Power and Fl	5 days	Mon 6/28/10	Ved 7/7/10	_						
88		- 🐊	2010 Diffusor Installation 3rd El	5 days	Tue 6/20/10	Tuo 7/6/10	_						
89		- 🐊	2110 Lighting 2rd El	7 days	Fri 7/2/10	$M_{00} = 7/12/10$							
90		- 🐊	3310 Elgenning 3	6 days	Thu 7/8/10	Thu 7/15/10	_						
91		- 🐊	2820 Einish Power 2nd El	5 days	Thu 7/15/10	Wed 7/21/10	_						
92		- 🐊	2320 Philiph Tower 2nd Th	5 days	Eri 7/16/10	Thu 7/22/10							
93		- 🐊	2311 Elooring	6 days	Eri 7/16/10	Fri 7/22/10	_						
94	-			10 days	Eri 7/16/10	Thi 7/23/10	_						
94		- 🐊	11410 Runchlist 2rd El	10 days	$r_{11} / 10 / 10$	Thu 7/29/10	_						
96	-	-	Exterior Activities	EQ days	Tuo 2/0/10	Fri 6/11/10							
97		- 🐊	1030 Lintels	15 days	Tue 3/9/10	Mop 2/29/10						1	
97				1 days	rue 3/3/10	Wod $2/17/10$	_						
00		- 	1920 Exterior Framing w/ Darapot	4 udys	FIT 5/12/10	$V = \frac{3}{17} \frac{3}{10}$	-					٦	
100		- 	1020 Exterior Framing W/ Parapet	25 uays	Mon 2/20/10	F(14/10/10)	-						
100	-	- 	1071 Boofing at Darapat	17 days	Tuo 2/20/10	Wod $4/21/10$	_						_
101	-	- 	1071 Rooming at Parapet		Tue 5/50/10	Wed 4/21/10	-						
102		×	1850 Exterior Framing W/ Parapet	5 uays	Mon 5/2/10	Wed 4/21/10	-						r
103		×	1112 Glass & Glazing	27 uays	Non 5/3/10	Tue 6/8/10	_						
104			1121 Parapet Metal Parles	22 udys	Non 5/10/10	Tue 6/8/10	_						
105			1126 Metal Panels 3rd Floor	3 days	Wod C/0/10	Wed 5/12/10	_						-
100		×.	1135 Metal Panels - 3rd Floor	2 days	Wed 6/9/10	Thu 6/10/10							_
107	-	×.		22 days	Thu 5/13/10	Fri 6/11/10							
108		×.	Site Activities	88 days	Wed 4/7/10	Fri 8/6/10							
109		×.	6000 Curbing	59 days	Wed 4/7/10	Sat 6/26/10						2	
110		×.	8000 Site Lighting	46 days	Wed 4/7/10	Wed 6/9/10	_					_	
111	-	×.	5020 Curbing - Phase 3		Tue 5/4/10	Tue 5/18/10	_						
112		×.	7000 Landscaping	67 days	Tue 5/4/10	Wed 8/4/10	_						_
113		×.	9010 Exterior Sidewalks - Phase 1	11 days	Fri 5/28/10	Fri 6/11/10							
114			10000 Sub-Base & Pavement	49 days	Tue 6/1/10	Fri 8/6/10	_						
115			2270 Generator	15 days	Wed 6/9/10	Tue 6/29/10	_						
110			9030 Exterior Sidewalks - Phase 2	5 days	Mon 6/14/10	Fri 6/18/10	_						
11/			9040 Exterior Sidewalks - Phase 3	5 days	Wion 6/21/10	Fri 6/25/10	_						
118			7040 Landscaping- Phase 5	12 days	Fri //2/10	Mon 7/19/10	_						
119		*	6030 Curbing - Phase 4	8 days	Mon 7/5/10	Wed //14/10							
120				106 day	rs Fri 1/15/10	Fri 6/11/10							
121			1080 Roof Curbs (RTUS and Mechanical)	33 days	Fri 1/15/10	Tue 3/2/10	_						
122			1020 Roof Penetrations	2 days	Wed 2/24/10	Thu 2/25/10	_			<u>u</u>	-		
123		X	1070 Roofing	14 days	Tue 3/2/10	Fri 3/19/10							
			Task		Project Summary			Inactive Milestor	ne 🔶		Manual Su	ummary Rollu	ρ
Projec	t: Full	Schedule	Split		External Tasks			Inactive Summar	y 🖓		Manual St	ummary	
Date:	Mon 1	10/25/10	Milestone 🔶		External Milestone	\$	I	Manual Task			Start-only		C
			Summary		Inactive Task			Duration-only			Finish-onl	У	3
								Page 3					



D	0	Task Mode	Task Name	Duration	Start	Finish	November Nov	December Dec	January Jan	February Feb	March Mar	April	May May
24	_	*	1179 RTU Installation	3 days	Thu 4/1/10	Mon 4/5/10			5411	100			
125		*	2118 Set Condensing Units 1, 2,	3, 26 days	Mon 3/1/10	Mon 4/5/10					[
126		*	2122 Set Condensing Units 4, 5	3 days	Thu 4/1/10	Mon 4/5/10							
127		*	1125 Screen Wall	19 days	Tue 5/18/10	Fri 6/11/10							
128		*	2110 Kitchen Exhaust	13 days	Tue 5/18/10	Thu 6/3/10							
129		*	1147 Plumbing RTU Hook-Up	5 days	Mon 5/24/10	Fri 5/28/10							
130		*	Concrete Work	111 days	6 Mon 12/14/0	Mon 5/17/10							
131		*	1000 Slab on Grade	25 days	Mon 12/14/0	9 Fri 1/15/10							
132		*	1009 Slab on Deck	17 days	Thu 2/4/10	Fri 2/26/10]		
133		*	1100 Masonry	36 days	Mon 3/29/10	Mon 5/17/10						C	
134		*	Steel	110 days	Wed 1/6/10	Tue 6/8/10			_				
135		*	1007 Steel Erection	14 days	Wed 1/6/10	Mon 1/25/10							
136		*	1008 Metal Deck	18 days	Tue 1/12/10	Thu 2/4/10							
137		*	1450 Interior Metal Framing	40 days	Fri 2/26/10	Thu 4/22/10				[C		
138		*	1120 Metal Panels	, 22 days	Mon 5/10/10	Tue 6/8/10							
139		*	HVAC, Fire Protection, Plumbing	111 days	Wed 2/24/10	Wed 7/28/10							
140		*	2100 Ductwork	19 davs	Wed 2/24/10	Mon 3/22/10]		
141		*	1180 Sprinkler Mains and Branch	nes 43 days	Mon 3/1/10	Wed 4/28/10					[
142		*	1130 Sprinkler Standpipes	, 10 davs	Mon 3/8/10	Fri 3/19/10							
143		*	1140 Plumbing Rough-In	, 33 davs	Mon 3/15/10	Wed 4/28/10							
144		*	1178 Plumbing Risers	22 days	Tue 3/23/10	Wed 4/21/10							
145		*	2117 Mechanical Piping	, 6 davs	Mon 3/29/10	Mon 4/5/10							
146		*	2107 Duct Risers	, 16 davs	Mon 4/5/10	Mon 4/26/10							
147		*	2900 Sprinkler Heads	36 davs	Wed 6/9/10	Wed 7/28/10							
148		3	Electrical	136 days	5 Fri 3/12/10	Fri 9/17/10					—		
149		*	2300 Electrical Building Rough-In	31 days	Fri 3/12/10	Fri 4/23/10]	I
150		*	2200 Electrical Service Distribution	on 26 davs	Mon 3/15/10	Mon 4/19/10							
151		*	3100 Lighting	, 25 days	Fri 7/2/10	Thu 8/5/10							
152		*	3500 Balancing	15 days	Mon 8/30/10	Fri 9/17/10							
153		-	General	121 days	5 Fri 3/12/10	Fri 8/27/10					— —		
154		*	1021 Remove Weather Protection	on 10 days	Fri 3/12/10	Thu 3/25/10							
155		*	2400 Drywall Tape & Finish	, 70 days	Mon 3/22/10	Fri 6/25/10							
156		*	1110 Glass & Glazing	, 30 davs	Mon 5/3/10	Fri 6/11/10							
157		*	2600 Ceilings	, 39 days	Tue 6/8/10	Fri 7/30/10							
158		*	3200 Toilet Fixture Installation	, 3 days	Wed 6/16/10	Fri 6/18/10							
159		*	2500 Painting	, 24 days	Mon 6/28/10	Thu 7/29/10							
160		*	3300 Flooring	, 24 davs	Thu 7/8/10	Tue 8/10/10							
161		*	4010 Casework	, 28 davs	Fri 7/16/10	Tue 8/24/10							
162		*	11400 Punchlist	, 28 days	Fri 7/16/10	Tue 8/24/10							
163		*	4000 Startup and Testing	, 20 davs	Mon 8/2/10	Fri 8/27/10							
164		*	11440 Owner Training	10 days	Mon 8/2/10	Fri 8/13/10							
			Task		Project Summary		Ina	active Milesto	ne 🔶		Manual	Summary Roll	lup
rniect	·· Full S	Schedule	Split		External Tasks		Ina	active Summa	ry 🖵	(Manual	Summary	_
)ate: N	Mon 10	0/25/10	Milestone	•	External Milestone		Ma	anual Task	-		Start-on	, ly	C
			Summary		Inactive Task		Du	uration-only			Finish-or	าไง	



Appendix B – Site Layout Plan



Appendix C – Detailed Structural System Estimate

|--|

				F	ootings (3	8000psi)				
Length (ft.)	Width (ft.)	Depth (ft.)	Rebar Type	Rebar Qty.	LF of Rebar	Weight (lb/LF)	No. of Columns	Total Concrete (CY)	Total Rebar (tons)	
4.5	4.5	1.5	6	7	63	1.502	4.50	0.19		
6	6	2	6	11	132	1.502	16	42.67	1.59	
6.5	6.5	2	6	14	182	1.502	8	25.04	1.09	
4	4	1.33	6	5	40	1.502	4	3.15	0.12	
7.5	7.5	2.33	8	11	165	2.67	24	116.50	5.29	
5.5	5.5	1.75	6	9	99	1.502	4	7.84	0.30	
						Total	200	9		
5% waste for Concrete 10										
Grand Total 210 9										

Piers (3000 psi)									
Length (ft.)	Width (ft.)	Depth (ft.)	Rebar Type	Rebar Qty.	LF of Rebar	Weight (Ib/LF)	No. of Piers	Total Concrete (CY)	Total Rebar (tons)
2	2	2	8	8	24	2.67	38	11	1
						Total		11	1
					5% v	vaste for Co	ncrete	1	
						Grand Tota	I	12	1

Slab On Grade (4000 psi)								
Length (ft.)	Width (ft.)	Depth (in.)	WW Fabric Type	W-Number	Fabric Qty. (sqft)	Weight (Ib/100 sqft)	Total Concrete (CY)	Total Rebar (tons)
312	132	5	6 x 6	W2.1 x W2.1	41184	30	636	6
					Total		636	6
5% waste for Concrete 32								
					Grand Total		668	6

	Slabs On Deck (4000 psi)								
Length	Width	Depth	WW	W-Number	Fabric	Weight	No. of	Total	Total
(ft.)	(ft.)	(in.)	Fabric		Qty.	(lb/100	Slabs	Concrete	Rebar
			Туре		(sqft)	sqft)		(CY)	(tons)
312	132	4.5	6 x 6	W2.1 x	82368	30	3	1716	12
				VVZ.1		- · ·		1740	4.0
						lotal		1/16	12
5% waste for Concrete							86		
						Grand Total		1802	12

	Foundation Walls (3000 psi)								
Length (ft.)	Width (ft.)	Depth (ft.)	Slope	Rebar Type	Rebar Qty.	LF of Rebar	Weight (Ib/LF)	Total Concrete (CY)	Total Rebar (tons)
888	1.5	2.33	2	4	3	2664	0.668	77	1
		Founda	ation Wall	Dowels					
Length (ft.)	DWL Spacing (in.)	Bent Dowel Size	No. of Dowels	LF of Rebar	Weight (Ib/LF)	Total Rebar (tons)			
5.5	16	4	667	3668.5	0.668	1			
						Total		77	2
					5% w	aste for Co	ncrete	4	
						Grand Tota	d -	80	2

Formwork						
Name	Formwork Req. (sq ft)					
Footings	2880					
Piers	608					
Foundation Walls	4440					
Slab on Grade	444					
Total	8372					
10% waste	837					
Grand Total	9209					

Steel Quantities

					Beams			
Bay	Size	lb/lft	Length	Qty./Bay	No. of Bays/Floor	No. of Vert.	Total Linear	Total Tons
						Bays	Feet	
1	W18x35	35	24	1	4	2	192	3.36
1	W24x55	55	24	2	4	2	384	10.56
1	W24x62	62	24	1	4	2	192	5.952
1	W21x44	44	48	2	4	2	768	16.896
2	W24x55	55	48	1	22	2	2112	58.08
2	W24x55	55	24	1	22	2	1056	29.04
2	W24x62	62	24	1	22	2	1056	32.736
2	W21x44	44	48	2	22	2	4224	92.928
3	W21x44	44	30	1	2	2	120	2.64
3	W18x35	35	30	2	2	2	240	4.2
4	W24x55	55	30	1	5	2	300	8.25
4	W18x35	35	30	2	5	2	600	10.5
5	W24x62	62	30	1	2	2	120	3.72
5	W10x19	19	8	2	2	2	64	0.608
5	W10x17	17	11	1	2	2	44	0.374
5	W18x35	35	24	2	2	2	192	3.36
5	W10x15	15	8	10	2	2	320	2.4
5	W12x19	19	11	1	2	2	44	0.418
6	W24x62	62	30	1	2	2	120	3.72
6	W18x35	35	30	2	2	2	240	4.2
7	W24x55	55	30	1	2	2	120	3.3
7	W21x44	44	16.5	1	2	2	66	1.452
7	W10x19	19	16.5	1	2	2	66	0.627
7	W10x15	15	2	2	2	2	16	0.12
7	W12x22	22	11.5	2	2	2	92	1.012
7	W10x15	15	10	2	2	2	80	0.6
						Тс	otal	301.053

	Metal Decking (type B-Deck)					
	Туре	Total (sq ft)				
Roof Decking	1.5" Type B	41184				
Floor Decking	1.5" Type B	82368				

Columns								
Size	lb/lft	Length	Qt.	Total Length	Total Tons			
W14x90	90	22	12	264	11.88			
W14x109	109	20	24	480	26.16			
W14x120	120	22	24	528	31.68			
W14x68	68	28	8	224	7.616			
W14x90	90	28	48	1344	60.48			
W14x61	61	28	4	112	3.416			
				Total	141.232			

Unit Detail Report



Cranberry, PA, 16066 Year 2009 Quarter 4

Date: 26-Oct-10

Structural System	Estimate
-------------------	----------

Prepared By: Jonathan Fisher Penn State

LineNumber	Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
Division 03 Concrete					
031113053950	C.I.P. concrete forms, wood, exterior plyform, buy, 3/4", includes material only	9,209.00	S.F.	\$0.98	\$9,024.82
033053400920	Structural concrete, in place, column, square, avg reinforcing, 24" x 24", includes forms(4 uses), reinforcing steel, and finishing	12.00	C.Y.	\$1,286.56	\$15,438.72
033053401900	Structural concrete, in place, elevated slab, flat slab with drop panels, 125 psf superimposed load, 20' span, includes forms(4 uses), reinforcing steel, and finishing	1,802.00	C.Y.	\$638.42	\$1,150,432.84
033053404700	Structural concrete, in place, slab on grade, 6" thick, includes forms(4 uses) and reinforcing steel	668.00	C.Y.	\$171.92	\$114,842.56
033105701950	Structural concrete, placing, continuous footing, shallow, pumped, includes vibrating, excludes material	80.00	C.Y.	\$28.47	\$2,277.60
033105702450	Structural concrete, placing, spread footing, pumped, under 1 C.Y., includes vibrating, excludes material	210.00	C.Y.	\$65.89	\$13,836.90
033529300100	Concrete finishing, floors, manual screed, bull float	123,552.00	S.F.	\$0.32	\$39,536.64
033913500400	Curing, curing blankets, buy, minimum, 1" to 2" thick	300.00	S.F.	\$0.29	\$87.00
Division 03 Subtotal					\$1,345,477.08
Division 05 Metals					
051223750620	Structural steel member, 100-ton project, 1 to 2 story building, W10x15, A992 steel, shop fabricated, incl shop primer, bolted connections	416.00	L.F.	\$31.45	\$13,083.20
051223750700	Structural steel member, 100-ton project, 1 to 2 story building, W10x22, A992 steel, shop fabricated, incl shop primer, bolted connections	174.00	L.F.	\$40.99	\$7,132.26
051223751300	Structural steel member, 100-ton project, 1 to 2 story building, W12x22, A992 steel, shop fabricated, incl shop primer, bolted connections	136.00	L.F.	\$37.30	\$5,072.80
051223753300	Structural steel member, 100-ton project, 1 to 2 story building, W18x35, A992 steel, shop fabricated, incl shop primer, bolted connections	1,464.00	L.F.	\$56.40	\$82,569.60
051223754100	Structural steel member, 100-ton project, 1 to 2 story building, W21x44, A992 steel, shop fabricated, incl shop primer, bolted connections	5,178.00	L.F.	\$67.58	\$349,929.24
051223754900	Structural steel member, 100-ton project, 1 to 2 story building, W24x55, A992 steel, shop fabricated, incl shop primer, bolted connections	3,972.00	L.F.	\$81.88	\$325,227.36

LineNumber	Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
051223755100	Structural steel member, 100-ton project, 1 to 2 story building, W24x62, A992 steel, shop fabricated, incl shop primer, bolted connections	1,488.00	L.F.	\$91.42	\$136,032.96
053113503900	Metal decking, steel, open type, long span, galvanized, over 50 Sq, 4-1/2" D, 16 ga	123,552.00	S.F.	\$6.18	\$763,551.36
Division 05 Subtotal	-				\$1,682,598.78

Appendix D – General Conditions Estimate

Personal									
	Qty. Cost per Week Weeks								
Vice President	1	2200	12	\$26,400.00					
Project Executive	1	\$2,150.00	30	\$64,500.00					
Project Manager	1	\$2,800.00	45	\$126,000.00					
Project Engineer	1	\$1,800.00	45	\$81,000.00					
Project Superintendent	1	\$2,400.00	45	\$108,000.00					
Assistant Superintendent	1	\$2,200.00	45	\$99,000.00					
Project Safety Manager	1	\$300.00	45	\$13,500.00					
Estimating Cost	1	\$4,000.00	3	\$12,000.00					
	Total Cost								

Temporary Facilities, Utilities and Equipment					
	Qty.	Units	Cost per Unit	Months	Total
Office Trailer Start Up	1	each	\$1,800.00	once	\$1,800.00
Office Trailer Rent	1	months	\$1,000.00	11	\$11,000.00
Office Trailer Removal	1	each	\$2,000.00	once	\$2,000.00
Office Supplies/Equipment	1	months	\$200.00	11	\$2,200.00
Storage Trailers	3	months	\$150.00	11	\$4,950.00
Crawler Crane	1	months	\$24,000.00	6	\$144,000.00
Portable Toilets	2	months	\$175.00	11	\$3 <i>,</i> 850.00
Hand Tools/Small Equipment	1	months	\$500.00	11	\$5 <i>,</i> 500.00
Fire Extinguishers	10	each	\$75.00	once	\$750.00
Office Computer Equipment	3	months	\$400.00	11	\$13,200.00
Dumpsters	3	months	\$175.00	12	\$6,300.00
Personal Mobile Phones	3	months	\$100.00	11	\$3,300.00
Temporary Power Hook Up	1	each	\$2,000.00	once	\$2,000.00
Temporary Power	1	months	\$5,000.00	7	\$35,000.00
Temporary Water Hook Up	1	each	\$1,000.00	once	\$1,000.00
Temporary Water	1	months	\$1,200.00	7	\$8,400.00
Temporary Lighting	1	months	\$1,000.00	7	\$7,000.00
			Total Co	st	\$250 <i>,</i> 450.00

Miscellaneous Costs							
	Qty.	Units	Cost per Unit	Months	Total		
Signage	50	each	\$10.00	once	\$500.00		
Site Clean Up	1	months	\$1,200.00	12	\$14,400.00		
Field Expenses	1	months	\$1,000.00	12	\$12,000.00		
Fencing	2500	LF	\$0.75	12	\$22,500.00		
Temporary Road Ways	1	each	\$10,000.00	once	\$10,000.00		
			Total Cost		\$59,400.00		

Insurance and Bonds						
	% of Contract	RS Means Building Cost Estimate	Cost			
Bonds	1.00%	\$17,570,705.00	\$175,707.05			
Permits	1.00%	\$17,570,705.00	\$175,707.05			
Insurance	0.55%	\$17,570,705.00	\$96,638.88			
		Total Cost	\$448,052.98			