

# LUKE GRAY CONSTRUCTION MANAGEMENT PROJECT X NEW YORK

#### MECHANICAL, ELECTRICAL, LIGHTING

MECHANICAL-AHU'S RANGING FROM 8650-6300CFM ON EACH FLOOR, SUPPLEMENTARY HYDRONIC FIN TUBE BASEBOARD RADIATION ALONG THE PERIMETER

ELECTRICAL-POWER IS DISTRIBUTED WITH 208/120V, 3-PHASE , 4 WIRE PANELS ON EACH FLOOR; DRY TYPE TRANSFORMER

LIGHTING-THERE ARE MANY TYPES LAMPS USED WITHIN THE BUILDING INCLUDING FLUORESCENT, INCANDESCENT, METAL HALIDE, H.I.D. FIXTURES. THE EMERGENCY LIGHTING FOR THE BUILDING IS SUPPLIED BY FLUORESCENT FIXTURES WITH A 90 MINUTE EMERGENCY BATTERY PACK.

#### **ARCHITECTURAL & STRUCTURAL**

FOUNDATION-REINFORCED MAT SLAB 10" DEEP TWO-WAY FLOOR SLAB COLUMN LAYOUT 24' X 24' THE EXTERIOR WALLS NATURAL BRICK WITH THREE CURTAIN WALL SLOTS TO BREAK UP THE BRICK FACADE THAT BLENDS SEAMLESSLY INTO THE SURROUNDING HISTORICALLY RICH TOWN-HOUSES THERE ARE THREE LEVELS OF 12" INTENSIVE GREEN ROOFS

CM-SKANSKA ARCHITECT-MA ARCHITECTS STRUCTURAL-ROBERT SILMAN MECHANICAL-FMC ASSOCIATES LIGHTING-RS LIGHTING DESIGN DURATION-AUGUST 2008-JULY 2010 SIZE-54,640SF BUILDING USE-OFFICES & THEATRE

HTTP://WWW.ENGR.PSU.EDU/AE/THESIS/PORTFOLIOS/2011/LAG290/INDEX.HTML

#### **Executive Summary**

Technical report 3 addresses areas in regards to Project X that are good candidates for research, alternative methods, value engineering, and schedule compression. A site interview was conducted with the Project Manager of Project X, John Gunning, to discuss these topics. The report ends with an observation of problem identification and technical analysis methods. The first constructability challenge was monitoring movement of adjacent buildings and excavation support systems during construction. Extensive measures had been taken to monitor the vibration, lateral, and vertical displacements by the geotechnical and structural engineers. The second constructability challenge was preserving the playhouse walls. The third constructability challenge was that there was no material laydown area. This required the project team to close down one of the lanes of traffic during construction. Other constructability challenges included cold weather concrete substructure placement, collisions of lagging and tiebacks with chilled water lines.

The biggest risk was the client not being able to move in June 25, 2010, because the owner had to terminate their lease. The primary acceleration method was working overtime and second shift. This was done by the interior finish crews, interior fit out crews, concrete subcontractors.

Value Engineering (VE) ideas that have been implemented on Project X include: corrugated metal paneling on penthouse, traditional 4" red brick used on the façade. VE ideas not implemented despite cost implications are a green roof terrace and aluminum roof railing.

Problems that arose during construction were dealing with public opinion of the project, five year estimating and value engineering sessions, low value of BIM due to the small size of the building, and scheduling.

The areas of technical analysis are Utilizing BIM for estimates, design, and owner validation; Implementing BIM in the field; Identify and recommend potential areas that owners can utilize BIM after construction; Small projects uses of BIM advantages and disadvantages; and Identify current design limitations of BIM technology.

## **Table of Contents**

Executive Summary	3
Constructability Challenges	5
Schedule Acceleration Scenarios	10
Value Engineering Topics	12
Problem Identification	14
Technical Analysis Methods	16

## **Constructability Challenges**

The first constructability challenge was monitoring movement of adjacent buildings and excavation support systems during construction. Monitoring of excavation system was done by installing reference points at 25-ft on-center around the entire perimeter of the excavation to properly monitor the ground movements behind the excavation support system and to properly monitor building movements. As the excavation proceeded, points were installed on soldier piles to measure potential lateral deflection. Points were installed at the top, the mid-point, and at the base of the excavation. These locations were subject to review by the Owner's structural and Geotechnical Engineers. First, this task was achieved by monitoring points had to be established by the Contractor employing a Professional Land Surveyor licensed in the State of New York, and referenced to a fixed off-site benchmark. A building across the street from the construction was used for a reference. Second, monitoring of the excavation support system was performed on a semiweekly basis during any sheeting, bracing, underpinning and excavation work. Readings were being taken to nearest 0.005 ft. Written reports summarizing the monitoring results were submitted within 24 hours of a reading by the Contractor's Professional Engineer and/or Surveyor to the Construction Manager for review by the Owner's Structural and Geotechnical Engineers.

Monitoring of adjacent buildings the Owner's Geotechnical Engineer conducted movement and cracks monitoring of the adjacent buildings. Vibration monitoring was implemented for all adjacent buildings. The contractor received monitoring reports on a weekly basis and was notified within 24 hours of a reading when a threshold is exceeded. The threshold limit was defined as the maximum allowable vertical or lateral movement is 3/8 inches and the maximum allowable particle wave velocity is 0.5 inch per second. The engineer devised a plan if the above thresholds approach exceeding limit. First, the Contractor will immediately stop work if movement reaches <sup>1</sup>/<sub>4</sub>-in and/or vibration level reaches 0.3 inch per second. Then, the contractor would inspect the building for potential damage. Inspections would be made by the Contractor, his engineer, the Owner's Engineers, and the adjacent building's engineer. Next, the contractor would develop alternate methods and procedures, subject to the review and approval of the Owner's Engineers and the adjacent building's engineer to stabilize the building, stop movements and/or lower vibration levels. The contractor would have to resume work using the agreed upon alternative method. Lastly, the Contractor would have to restore, to the satisfaction of the Property Owner, by repair or otherwise, the portions of buildings, or their contents, altered by the Contractor in furtherance of his sheeting, bracing, and underpinning work.

adjacent building. The adjacent buildings were extensively braced on the south side due to the preservation of the existing playhouse's walls. The existing adjacent structure required additional c-channel to reinforce the north neighboring structure by tying into the floor wood trusses of the neighboring structure; because the wall was not load bearing wall it was only two courses thick. Also a great deal of underpinning concrete was used to uphold the adjacent structures.



Figure 1: Shows the C-Channel used to reinforce north side of adjacent structure

The second constructability challenge was preserving the existing playhouse's walls. A protective sidewalk bridge was used to permit pedestrians flow during non-working hours. The demolition of the existing 33,000SF building consists of four separate townhouses that were merged together during the 1940's. The existing building is compiled of brick and mortar, which has been primarily demolished by excavators. The playhouse was demolished by hand. The building has historical and cultural significance. It houses a 4,400SF playhouse on the ground and basement levels that is scheduled to remain. As part of the project, the interior walls of the theater will be demolished and rebuilt. The playhouse portion of the building is located at the southern end of the site's 8,430 SF footprint. Four walls of the original theatre that is located on the basement and ground floor level will remain throughout construction.

The project team has done the following to preserve the historical significance of the theater: The owner has preserved the exact volume and footprint of the playhouse theater. The owner has preserved and restored the 1940's playhouse façade. The owner has integrated relevant historical features and pieces of the existing theater. The owner has built a smaller building than allowed by zoning. New construction is low-scale, contextual, brick building for law faculty and student research.

These four walls, which were mortared together with a variety of stones and bricks, will be temporarily preserved by shoring the walls with steel beam structural system. This is a very challenging task because there is a dentist office on the south side. In addition there are restaurants adjacent to the building that lends to daily delivery. Also there are apartments on the north and west side and a small one-way street on the east side. The playhouse portion of the building is located in the southern end of the site.

A temporary steel frame was used to preserve the existing theatre walls and the adjacent building. This made construction activity very difficult due to the structural bracing. The steel bracing was anchored to the adjacent building's masonry wall. Double l-angle steel wielded together was used for vertical members and round hollow structural sections (hss) steel tubing was used for the lateral members shown in Figures 2 and Figure 3. One lane of traffic was closed during construction to allow for a crawler crane to be used.



Figure 2: Shows Temporary Structural Steel Bracing



Figure 3: Shows an Up-close View of the Structural Steel Bracing

## Gray

The third constructability challenge was that there was no material layout area. All of the material deliveries had to be just in time deliveries. There was no room on the site for material storage. All of the long lead items had to be ordered prematurely to ensure a timely delivery when needed. The cast-in-place concrete system congested the site with formwork and shoring. In order to allow space for the delivery trucks and crane one of the lanes traffic to be closed for a two week period. Also the entire road had to be closed in order to install new service off the existing water main, which runs approximately center and parallel to MacDougal Street. MacDougal Street (from West 4th to West 3rd Street) was closed beginning no earlier than October 26, 2009, 8:00 AM to 4:00 PM, Monday to Saturday. Sidewalk access on the east side of street will be maintained at all times. No impact to the water service to the adjacent neighbors is anticipated. Neighbors directly south of 133-139 MacDougal Street will be able to back up their cars to the front of their property. At the end of each work day - after 4:00 PM - steel plates will be placed over the pit to allow street access.



Figure 4: Illustrates the Very Limited Storage Area



Figure 5: Shows limited material handling due to the space required for shoring and formwork

## **Schedule Acceleration Scenarios**

#### **Risk to Completion Date:**

The biggest risk was the client not being able to move in on June 25, 2010. After the client terminated their current lease; they saved about 400k and therefore that money was spent on overtime and insuring the work was complete. As part of the law school's master plan, Project X moves the admissions office from the distant leased building, which allowed the school to save the cost of leasing office space and brought key departments back to campus. The main contributing factor to completing the project on time was weather delays. Not getting the building enclosed would prevent the sheetrock & subsequent finishes from starting. Also design changes requiring fabrication could impact installation sequences and delay follow-on work. Since, the concrete superstructure is in the critical path, the concrete pours were schedule for one week per pour this activity is highly dependent upon the weather conditions. This required the concrete subcontractors to work one day a week for approximately 10 weeks, weather permitting. The contractor worked between 8:00PM and 12:00AM to trowel newly poured concrete. This one day per week will coincide with the day of the concrete pour of each slab level. When the pour is complete and while the concrete is still wet, a gas powered trowel machine will be used to make the slab smooth and level before the concrete has begun the curing process. The completion time of the concrete finishing was temperature driven. Warmer weather would allow for an earlier completion time. In colder temperatures, it would take longer. Temporary heating units were used when the temperature dropped to expedite the work.

#### **Areas of Potential Acceleration:**

All areas were accelerated drywall, electric trim, taping and paint. Carpet and furniture install were done on second shift to make time. Increase Manpower and working overtime were the two techniques utilized to complete the project on time. Interior fit-out and MEP rough-in trades can accelerate by working more floors simultaneously, finish trades can work overtime or double shifts. The primary cost of schedule acceleration was the cost of overtime premium and second shift premium.

#### **Critical Path:**

The first activity was to erect structure to get building roofed to allowed the lobby lift to proceed, which the allowed the sheetrock and finishes to proceed up the building. Once the  $2^{nd}$  floor was completed, the furniture installation continued through the  $5^{th}$  floor. Note:  $6^{th}$  floor was smaller than the  $5^{th}$  floor so it didn't take as long. See Figure 6 critical activities report. The timing of moving out of occupants leaving existing building and move-in of occupants is essential. The critical path is show in Figure 6 below.

#### Gray

12.12         Rev/Algory Startis Cons Superstructure         10 </th <th>Activity ID</th> <th>Activity Description</th> <th>Orig Dur</th> <th>Rem Dur</th> <th>Early Start</th> <th>Early Finish</th> <th>2009 2010 Jul aug sep oct nov dec jan feb mar apr may jun jul au</th>	Activity ID	Activity Description	Orig Dur	Rem Dur	Early Start	Early Finish	2009 2010 Jul aug sep oct nov dec jan feb mar apr may jun jul au
12.112         Fundamin Carbon Constructure         60         10         10	3P03.211	Prep/Sbmt Sbmtis Conc Superstructure	25	10	02FEBD94	15,000	Prep/Sbmt Sbmtls Conc Superstructure
Dist Die Undergemein         Bie Der Dersegnent         Bie Der Dersegnent           Die Undergemein         Sie Die Dersegnent         Sie Die Dersegnent         Sie Die Dersegnent           Die Undergemein         Sie Die Dersegnent         Sie Die Dersegnent         Sie Die Dersegnent           Die Die Dersegnent         Sie Die Dersegnent         Sie Die Dersegnent         Sie Die Dersegnent         Sie Die Dersegnent           Die Dersegnent         Sie Die Der	P03.211		-				
01.100         Orderprint(10:10)         20         10         2,200,000         Point Review         3         3         10,000         10,00	MGR.107						
06110         040 <sup>3</sup> mouth to Owner         1         0         0410 <sup>4</sup> <t< td=""><td>NDN. 180</td><td></td><td>2.55</td><td></td><td></td><td></td><td></td></t<>	NDN. 180		2.55				
061.00         081-00-00000000000000000000000000000000	/GR.108						
100.100         100.100 <t< td=""><td>AGR.109</td><td></td><td></td><td></td><td></td><td></td><td></td></t<>	AGR.109						
D1100         Outcogning Pig Figures North Wall         7	IGR.106						
08.174         Modelize Dewatering         1         1         1         27.12         Bodelize Dewatering         Part All Devatering System         1         1         27.12         Stabula         Other all Dewatering System         1 <t< td=""><td>DN. 190</td><td></td><td></td><td></td><td></td><td></td><td></td></t<>	DN. 190						
Dir. 10.         Install Descenting System         6         5         28.200.00         Install Descenting System         0         0           Dir. 20.         RED/W-V cost Sparthultum Return         6         0 <td>08.174</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>	08.174						
10.213         FabCub- Conc. Superstructure Retur         4/3         4/4         3/0.000         10/0.000         10/0.000         10/0.000         10/0.000         10/0.000         10/0.000         10/0.000         10/0.000         10/0.000         10/0.000         10/0.000         10/0.000         10/0.000         10/0.0000         10/0.0000         10/0.0000         10/0.	IDN. 185	the second s	5		and a series in the second second	and the second se	
Div 10         Div Method         10         DAU0000         HAU0000           VAL         Multiper Watherproof, Rain & Foruz Head         10         DAU000         BAU000           DIV 20         Mate Form, Waterproof, Rain & Foruz Head         10         DAU000         BAU000           DIV 20         Mate Form, Waterproof, Rain & Foruz Head         10         DAU000         BAU000           DIV 20         Mate Form, Waterproof, Rain & Foruz Head         20         20         DAU000         BAU000           DIV 20         Mate Form, Waterproof, Rain & Foruz Head         20         20         DAU000         BAU000         BAU0000         BAU000         BAU0000         BAU0000         BAU0000         BAU00000	03.213		45			01OCT09	Fab/Dely Conc Superstructure Rebar
Div Die Verbanza die Elevator Pfin         10         10         Deuzone         10 <td>DN.103</td> <td>Install U/G Plumbing</td> <td>10</td> <td>10</td> <td>03AUG09</td> <td>14AUG09</td> <td>Install U/G Plumbing</td>	DN.103	Install U/G Plumbing	10	10	03AUG09	14AUG09	Install U/G Plumbing
D1020         Mar Form, Waterpoor, Reis A Four, Water (19)         Mar Form, Waterpoor, Reis A Four, Water (19)         Mar Form, Waterpoor, Reis A Four East (19)         Mar Form, Mar Four, Mar Fo	DN.195		10	10	03AUG09	14AUG09	Pour Mechanical & Elevator Pits
D1020         ML4 Form. Waterpoor. Reis A Forur Weis         0	07.434	Mobilize Fdn Waterproofing	1	1	05AUG09	05AUG09	Mobilize Fdn Waterproofing
D1210         Mar Form, Watergroot, Rebur & Pour East         10         10         10         200050700           D2025         Firsh Physius Escandino, Scored & 200         200050700         200050700         Enviration Valia         200         200050700         Enviration Physics Escandino, Scored Wals,         Enviration Physics Escandino, Scored Wals,           D1220         Baskin Corea Speriturbure         6         6         COCT00         Education Scored Physics Escandino, Scored Wals,           D1220         Baskin Corea Pay House         6         COCT00         Education Scored Physics Escandino, Scored Physics           D1220         Baskin Corea Pay House         6         COCT00         Education Scored Physics           D1220         Baskin Corea Pay House         6         COCT00         Education Scored Physics           D1200         PRP caller Columns         5         SOCT00         SOCT00         Physics Physics         Physics Physics           D110         PRP caller Columns / 14 Pr Stab         6         SOCT00         Physics Physics Physics         SOCT00         SOCT00         SOCT00         SOCT00         SOCT00         SOCT00         SOCT00	DN.200		10			19AUG09	
Dit 200         Print Pay House Excession & Concrete Weix           Dit 215         Fundation Walls         Concrete Weix           Dit 215         Fundation Walls         Concrete Weix           Dit 215         Fundation Walls         Concrete Weix           Dit 225         Backfit Clean Up         6         Concrete Weix           Dit 225         Backfit Clean Up         6         Concrete Weix           Dit 225         Backfit Clean Up         Concrete Weix         Dit 200           Dit 225         Backfit Clean Up         Concrete Weix         Dit 200           Dit 200         Concrete Weix         Dit 200         Concrete Weix           Dit 200         Concrete Weix         Dit 200         Dit 200           Dit 200         Dit 200         Concrete Weix         Dit 200           Dit 200         Dit 200         Concrete Weix         Dit 200           Dit 200         Dit 200         Dit 200         Dit 200         Dit 200         Dit 200           Dit 200         Dit 200         Dit 200         Dit 200         Dit 200         Dit 200         Dit 200         Dit 200         Dit 200         Dit 200         Dit 200         Dit 200         Dit 200         Dit 200         Dit 200         Dit 200         <	DN.210						
DN216         Fundation Valia         20         20         D05EPP0         P1000000           D3214         Mabiles Cons Superstructure         6         G200000         G000000           D3214         Mabiles Cons Superstructure         6         G200000         G000000           D1226         Sils on Grade Play House         5         G200000         G0000000           D1205         Sils on Grade Play House         5         G200000         G0000000           D1100         PBP Cell Columns         5         G200000         G0000000           D1100         PBP Cell Columns         5         G200000         G0000000           D1100         PBP Cell Columns / 14F Pl Sab         5         G200000         G0000000         FPE Play FL Columns / 41h Pl Sab         5         G200000         G000000         FPE Play FL Columns / 41h Pl Sab         5         G200000         G000000         FPE Play FL Columns / 41h Pl Sab         5         G2000000         G000000         FPE Play FL Columns / 41h Pl Sab         5         G2000000         G2000000         G2000000         G2000000         FFEP fair FL Columns / 41h Pl Sab         FFEP fair FL Columns / 41h Pl Sab         G20000000         G20000000         G20000000         G20000000         G2000000000000000000000000000000000000	DN.205						
03.214         Malilies Core Superstructure         6         6         03.02179         Malotics Core Superstructure           D12.20         Badritt Clean Up         5         63.002709         60.00709         Badritt Clean Up           D12.20         Badritt Clean Up         5         63.002709         60.00709         Badritt Clean Up         Badritt Clean U	DN.215		-			01OCT09	
D1202         Backfill Clear Ug         6         6         2002/19         600/19	03.214						
DN225         Sab on Caske Pray House         6         6         SOCCT09         Bit Sab on Caske Pay House         7           STN 004         Begin Superstructure         0 </td <td>DN.220</td> <td></td> <td>-</td> <td></td> <td></td> <td></td> <td></td>	DN.220		-				
TH. 004         Bight Superstructures         0         0         00         00000000           RU. 105         PAP Cellar Columns         6         5         60000000         15000000           RU. 105         PAP Cellar Columns         7.6         6.6         5         60000000         15000000           RU. 107         PF PT Eff PS mC Columns / 1st FF Sab         5         5         5         5         5         7.6	DN 225						
Ru.100         P#P Celar Celumes         9         9         90000000         90000000         90000000         9000000000000000000000000000000000000	STN 004						
Ru.15a         Pur.V Stab on Deck Basement         6         6         60000000         20000000         PPR Bmt Columns / 1mt Pi Stab         6         6         2000000         PPR Bmt Columns / 1mt Pi Stab         6         6         2000000         PPR Bmt Columns / 1mt Pi Stab         6         6         20000000         PPR Dmt Columns / 1mt Pi Stab         6         5         20000000         PPR Dmt Pi Columns / 2mt Pi Stab         6         5         2000000         PPR Dmt Pi Columns / 2mt Pi Stab         6         5         2000000         PPR Dmt Pi Columns / 2mt Pi Stab         6         5         2000000         PPR Dmt Pi Columns / 2mt Pi Stab         6         5         2000000         PPR Dmt Pi Columns / 2mt Pi Stab         7         2000000         2000000         PPR Dmt Pi Columns / 2mt Pi Columns / 2mt Pi Stab         2mt Pi Columns / 2mt Pi Column	RU.100					150CT09	
RU.102         RP Bart Columns / Is FP Slab         6         6         200709         SU0709         SU07070         SU0709 <thsu0709< th=""></thsu0709<>					and shall be a set of the second s	and the second second second	
RU.103         FRP 1st FIr Columns / 2nd Fir Stab         6         5         000/0709           RU.104         FRP 2nd Fir Columns / 2nd Fir Stab         5         000/0709           RU.105         FRP 2nd Fir Columns / 2nd Fir Stab         5         000/0709           RU.106         FRP 2nd Fir Columns / 2nd Fir Stab         5         5         000/0709           RU.106         FRP 2nd Fir Columns / 2nd Fir Stab         5         5         000/0709           RU.105         FRP 2nd Fir Columns / 2nd Fir Stab         5         5         000/0709           RU.106         FRP 2nd Fir Columns / 2nd Fir Stab         5         5         000/0709           RU.106         FRP 2nd Fir Columns / 2nd Fir Stab         5         000/0709           RU.106         FRP 2nd Fir Columns / 2nd Fir Stab         5         000/0709           RU.106         FRP 2nd Fir Columns / 2nd Fir Stab         5         000/0709           RU.106         FRP 2nd Fir Columns / 2nd Fir Stab         5         000/0709           RU.106         FRP 2nd Fir Columns / 2nd Fir Stab         5         000/0709           RU.106         FRP 2nd Fir Columns / 2nd Fir Stab         5         000/070           RU.106         FRP 2nd Fir Columns / 2nd Fir Columa / 2nd Fir Columa / 2nd Fir Columa / 2nd Fir Colu			_				
RU.104         FRP 2nd Fir Columns / 3nd Fir Slab         S         S         OBNOV09         TANUTO         FRP 2nd Fir Columns / 3nd Fir Slab         FRP 2nd Fir Columns / 3nd Fir Slab           RU.105         FRP 3nd Fir Columns / 3nd Fir Slab         S         S         SNOV09         SNOV09           RU.105         FRP 3nd Fir Columns / 3nd Fir Slab         S         S         SNOV09         SNOV09           RU.105         Degin Celar Interior Flout         O         O         SNOV09         SNOV09           RU.106         Dutwork Mansfiranches         S         S         2400/000         OHDECON         SNOV09         SNOV09           RU.106         Dutwork Mansfiranches         10         10         ODECON         SNOV09         SNOV09         SNOV09         SNOV09           RU.106         Nutwork Mansfiranches         10         10         ODAN10         100         SNOV09							
Rul 100         FRP 3rd Fir Columns / 4th Fir Slab         S         S         INNOV00           N3314         Mobilize Metal Ductwork         S         S         INNOV00           N3314         Mobilize Metal Ductwork         S         S         INNOV00           CL 100         Temporary Power & Lighting         2         2         20N0V00         Segin Cellar Interior Filout           CL 100         Ductwork Mainsfiltranches         S         2         20N0V00         SNOV00           CL 100         Ductwork Mainsfiltranches         10         10         20EC00         10EC00           0.1104         Ductwork Mainsfiltranches         10         10         20EC00         SUMNITO         SUMNITO           0.1104         Ductwork Mainsfiltranches         10         10         20EC00         GALANITO         SUMNITO         SUMNITO           0.1104         Ductwork Mainsfiltranches         10         10         20AANITO         1NARITO         Summiter Pajning Mains & Branches         Summiter Pajning Mains         Summiter Pajning Mains         Summiter			-	-			
H3.314       Mobilize Metal Ductwork       6       6       7XVO00       23NOV00         0.0500       Begin Celar Interior Floud       0       0       02NOV00       4Begin Celar Interior Floud       0       0         0.100       Temporary Power & Lighting       2       20NOV00       4Begin Celar Interior Floud       0       0         0.101       Ductwork Mains/Branches       10       10       07DEC00       18DEC09       18DEC09       18DEC09       18DEC09       18DEC09       18DEC09       18DEC09       18DEc040K Mains/Branches       10       10       02MAN10       12DEC006 (5AN10       18DEC09       18DEC09       18DEC09       18DEC09       18DEc040K Mains/Branches       10       10       02MAN10       12DEC09 (5AN10       18DEC09       18DEc040K Mains/Branches       10       10       10DEC040K Mains/Branches       10       10       10DEC040K Mains/Branches       10       10       10DEC040K Mains/Branches       10       10       10DEC040K Mains/Branches       10DEC040K Mains/Branches       10DEC040K Mains/Branches       10DEC040K Mains/Branches       10DEC040K Mains/Branches       10DEC040K Mains/Branches       10DEC040K			-				
D0.500         Begin Celar Interior Flout         0         0         201/00         201/07/00         201							
CL 100         Temporary Power & Lighting         2         2         20N0V00         23N0V00         23N0V00         23N0V00         23N0V00         24N0V00		and the second se				23INOVU9	
CL 106         Dudwork MainsBranches         8         8         2 4V0V00         04DEC09           BS 104         Dudwork MainsBranches         10         10         070C909         16DEC09           D104         Dudwork MainsBranches         10         10         070EC09         16DEC09           D104         Dudwork MainsBranches         10         10         06JAN10         19JAN10           D2106         Sprinkler Piping Mains & Branches         10         10         06JAN10         19JAN10           D2101         Sprinkler Piping Mains & Branches         10         10         02JEEB10         04JANR10           D2106         Beltrichal Conduit         10         10         19FEB10         04JANR10           D2106         Beltrichal Conduit         10         10         19FEB10         04JANR10           D2106         Beltrichal Conduit         10         10         16MAR10         20AMR10           D2108         Celling Rich & 1d Coat         8         0         SOMAR10         04AMR10         20AMR10         04AMR10         20AMR10         04AMR10         04AMR10         02AMR10         04AMR10         02AMR10         02AMR10         02AMR10         02AMR10         02AMR10         02AMR10						226101/20	
BS.104         Ductwork Mains/Branches         10         10         07DC009         18DEC09         05UAN10         Ductwork Mains/Branches         0         0           0.000         Outwork Mains/Branches         10         10         21DC00         05UAN10							
D1.14         Dutwork Mains/Branches         10         10         2010200         05.JAN 10         Image: Dutwork Mains/Branches         Distance           02.106         Dutwork Mains/Branches         10         10         00.ANN 10         15.JAN 10         Image: Dutwork Mains/Branches         Dutwork Mai			-				
Dutwork MainsBranches         10         10         06JAN10         IBJAN10							
Sprinkler Piping Mains & Branches         10         10         20/04/10         Q2/EB10         Sprinkler Piping Mains & Branches         Sprinkler Piping Mains & Branches           02.100         Install HVAC Piping Mains         12         12         02/07/EB10         16/EB10         16/EB100         16/EB1000         16/EB1000         16/EB1000         16/EB1000         16/EB1000         16/EB100							
Natall HVAC Piping Mains         12         12         12         03         03         15         15         15         15         15         16         1		e a de la resta				and the second second second	
Display         Rough-In Electrical Conduit         10         10         19FEB10         OHMAR10           02.110         Rough-In Electrical Conduit         10         10         19FEB10         OHMAR10         IMAR10           02.106         Beetrical Rough-In Electrical Notation         2         2         OMAR10         IMAR10         OMAR10         IMAR10		and a construction of the state	_		and the second second second		
D2.140         Rough-In Electric In Walls         S         S         0 SMAR10         11MAR10           D2.140         Rough-In Electric In Walls         2         1 ZMAR10         15MAR10         Electrical Rough-In Inspection         2         2         72MAR10         15MAR10         Electrical Rough-In Inspection         Electrical Rough-In Inspection         2         1 ZMAR10         15MAR10         Drywall/T&S Cree & Corr Walls 2nd Side & Cellg's Electric In Walls         Electrical Rough-In Inspection           02.172         Drywall/T&S Cree & Corr Walls 2nd Side & Cellg's Electrical Rough-In Inspection         0         0         Drywall/T&S Cree & Corr Walls 2nd Side & Cellg's Electric In Walls         Electrical Rough-In Inspection           02.178         Prime Paint & 1st Coat         8         8         06APR10         05APR10         OFAPR10         Electrical Rough-In Inspection           02.216         Celling Grid         5         5         06APR10         25APR10         OBAPR10         Electrical Rough-In Inspection         Electrical Rough-In Inspection           02.216         Flooring & Base         5         5         07MAY10         05MAY10         Install Furniture & Workstations         Electrical Rough-In Inspection           02.226         Install Furniture & Workstations         5         5         07MAY10         05MAY10			-				
Base         Standard         Standard <thstandard< th="">         Standard         <ths< td=""><td></td><td></td><td>-</td><td></td><td></td><td></td><td></td></ths<></thstandard<>			-				
Opywal/T&S Core & Corr Walls 2nd Side &         10         10         16 MAR10         25MAR10         Opywal/T&S Core & Corr Walls 2nd Side & Celig status         Image: Corr Walls 2nd Side & Celig Time         Image: Corr Walls 2nd Side & Celig Time         Image: Corr Walls 2nd Side & Celig Time         Image: Corr Walls 2nd Side & Celig Time </td <td></td> <td>-</td> <td></td> <td></td> <td></td> <td></td> <td></td>		-					
D2.178         Prime Paint & 1st Coat         8         8         30MAR10         0BAPR10           D2.178         Prime Paint & 1st Coat         5         0 JAPR10         07APR10         07APR10         07APR10         07APR10         0140							
Ocaling Grid         S         S         0 GARRO         S         S         0 GARRO         O GARRO         G GARRO	210 m h h h			1000			
No.         No. <td></td> <td></td> <td></td> <td>12.5</td> <td></td> <td></td> <td></td>				12.5			
Constraint         Constra					and the second se	and the second se	
Q2 210         Above Celling Inspection         Q 2         23APR10         28APR10         28APR10 <td>02.196</td> <td></td> <td>-</td> <td></td> <td></td> <td></td> <td></td>	02.196		-				
02.214         Celling Tiles         5         5         27APR10         03MAY10           02.216         Flooring & Base         5         5         30APR10         66MAY10           02.226         Install Furniture & Workstations         5         5         30APR10         13MAY10           02.226         Install Furniture & Workstations         5         5         30APR10         13MAY10           02.226         Install Furniture & Workstations         5         5         14MAY10         20MAY10           02.226         Install Furniture & Workstations         5         5         14MAY10         20MAY10           05.226         Install Furniture & Workstations         5         5         21MAY10         20MAY10           05.226         Install Furniture & Workstations         4         31MAY10         03JUN10         Install Furniture & Workstations           05.227         Terminate Electric @ Workstations         3         3         01JUN10         03JUN10         Install Furniture & Workstations           05.232         Terminate Electric @ Workstations         3         3         01JUN10         03JUN10         TeleData Terminations @ Workstations         5           05.240         Final Inspection         7         7	02 206		-				
Q2.216     Flooring & Base     5     5     30APR10     06MAY10       Q2.226     Install Furniture & Workstations     5     5     07MAY10     13MAY10       Q2.226     Install Furniture & Workstations     5     5     07MAY10     13MAY10       Q2.226     Install Furniture & Workstations     5     5     21MAY10     03JJN10       Q4.226     Install Furniture & Workstations     4     4     31MAY10     03JJN10       Q5.220     Install Furniture & Workstations     4     4     31MAY10     03JJN10       Q5.227     Install Furniture & Workstations     4     3     3     01JJN10       Q5.230     Install Furniture & Workstations     3     3     01JJN10     03JJN10       Q5.247     Telrobata Terminations @ Workstations     3     3     01JJN10     03JJN10       Q5.240     5 H F. Substantially Complete     0     0     02JJN10       Q5.241     Telrobata Terminations @ Workstations     3     3     01JJN10       Q5.241     Substantially Complete     0     0     02JN10       Q5.242     Substantially Complete     0     0     0       Q5.244     Substantially Complete     0     0     0       Q5.241     Tell Inspections     7	.02.210					a starter and a starter at the	
Q2 228         Install Furniture & Workstations         5         5         07/MAY10         13MAY10           G3 226         Install Furniture & Workstations         5         5         14MAY10         20MAY10         Install Furniture & Workstations           G4 226         Install Furniture & Workstations         5         5         14MAY10         20MAY10         Install Furniture & Workstations           G5 226         Install Furniture & Workstations         4         4         31MAY10         03JUN10           G5 226         Install Furniture & Workstations         4         4         31MAY10         03JUN10           G5 226         Install Furniture & Workstations         3         0         0         Install Furniture & Workstations           G5 227         Install Furniture & Workstations         3         3         0.1JUN10         03JUN10           G5 237         Telnbata Technically Oxorpieto         0         0         02JUN10         02JUN10         TeleData Terminations @ Workstations         3           G5 240         Sth FI. Substantially Complete         0         0         0         0         0           D5 240         Sth FI. Substantially Complete         7         7         03JUN10         1JJJUN10         Sth FI. Substantially Complete	.02.214						
Constant	.02.216				and the second		
OLD:0         Install Fumiture & Workstations         0         0         Install Fumiture & Workstations         0         0         Install Fumiture & Workstations         0         Install Fumiture & Workstations         0	.02.228		5				
Observed         Install Furniture & Workstations         4         4         3 MAY10         03 JUN10           05220         Install Furniture & Workstations         2         2         0 JUN10         02JUN10         Install AV Jacks & Equipment         Install AV Jacks & Equipment           05230         Install Furniture & Workstations         3         3         0 JUN10         02JUN10         Install AV Jacks & Equipment           05232         Terminate Electric @ Workstations         3         3         0 JUN10         02JUN10         Terminate Electric @ Workstations           05240         56h Fl. Substantially Complete         0         0         02JUN10         TeleData Termination @ Workstations           1PL 113         Final Inspections         7         7         03JUN10         1JJUN10         TeleData Termination @ Workstations           1PL 114         Issue NYC TCO'         5         6         7JUN10         1JJUN10         TeleData Terminate Supervise To'           051007         Receive TCO         0         0         11JUN10         TeleData Terminate Supervise To'         TeleData Terminate Supervise To'           051007         Move-In         0         0         11JUN10         TeleData Terminate Supervise To'         TeleData Terminate Supervise To'	.03.226	Install Furniture & Workstations	5			and the second second	
D6 230         Install AV Jacks & Equipment         2         2         0 JUN10         02JUN10         Install AV Jacks & Equipment         Install AV Jacks & Equipment           05 230         Terminate Electric @ Workstations         3         3         0 JUN10         03JUN10         03JUN10         Terminate Electric @ Workstations         Terminations @ Workstations	.04.226	Install Furniture & Workstations	5				
Obs 232         Terminate Electric @ Workstations         3         3         0 1/UN10         03/UN10         Terminate Electric @ Workstations         1         0	.05.226	Install Furniture & Workstations	-				
Observed         TeleData Terminations @ Workstations         3         3         0 JUN10         0 JUN10         TeleData Terminations @ Workstations           05.240         5th Fl. Substantially Complete         0         0         0.2UN10         25th Fl. Substantially Complete         5th Fl. Substantially Complete         5th Fl. Substantially Complete         6th Fl. Substa	.05.230	Install AV Jacks & Equipment	2	2	01JUN10	02JUN 10	
D6 240         Sth Fl. Substantially Complete         0         0         02.UN10           HPL 113         Final Inspections         7         7         03.UN10         11.UN10           HPL 114         Issue NYC TCO'         6         5         07.UN10         11.UN10           N1007         Receive TCO         0         0         11.UN100           Sth Pl. Substantially Complete         €         6         07.UN10         11.UN100           Sth Pl. Substantially Complete         0         0         11.UN100         Bisue NYC TCO'           Sth Pl. Substantially Complete         0         0         11.UN100         ●           Sth Pl. Substantially Complete         0         0         11.UN100         ●           Sth Pl. Substantially Complete         0         0         0         ●	05.232	Terminate Electric @ Workstations	3	3	01JUN10	03JUN10	
05 240         Sth Fl. Substantially Complete         0         0         0.2,U/H1           HPL 113         Final hspections         7         7         03,U/H1         11,U/H10           HPL 114         Issue NYC TCO'         5         5         07,U/H11         11,U/H10           N1007         Receive TCO         0         0         11,U/H10           STN.010         Move-In         0         0         14,U/H10	05.234	-					TeleData Terminations  Workstations
IPL 113         Final Inspections         7         7         03JUN10         11JUN10           IPL 114         Issue NYC TCO'         5         5 07JUN10         11JUN10         Ilissue NYC TCO           STN 007         Receive TCO         0         0         11JUN10         Ilissue NYC TCO           Nto 10         Move-in         0         0         14JUN10         Move-in	05.240				-	02JUN10	5th Fl. Substantially Complete
IPL 114         Issue NYC TCO'         5         5         07JUN10         11JUN10           STN.007         Roceive TCO         0         0         11JUN10           STN.010         Move-in         0         0         14JUN10	APL 113		-		03JUN10	11JUN10	Final Inspection
STN 007         Receive TCO         0         0         11JUN10           STN.010         Move-In         0         0         14JUN10	APL 114					and the balance of the second	
5TN.010 Move-In 0 0 14JUN10							
						and and include and streaments	
						and the state of t	
	Date h Date Date Date	16AJG10 01.JU.09 08.JU.09.08.54		retis Bar al Activi	×		SKANSKA
© Primavera Systems, Inc.	s Date Date Date	01JU.09 08JU.09 08 54			×		SKANSKA

Figure 6: Shows the Critical Path Schedule

## **Value Engineering Topics**

#### Value Engineering Ideas Implemented

#### Metal panel system vs. brick

The owner went with a metal panel system instead of brick on the 6<sup>th</sup> floor. The cost of the metal paneling system \$131,360, while the brick would have cost \$287,350 a total cost saving of \$155,990.



Figure 7: Shows the Adjacent Height Restrictions and the Metal façade Used on the Roof Level.

The client decided to have an extra floor but do the sunken first floor, because they had a height restriction of aligning with the existing surrounding building. This cost the owner less by not having to construct façade and windows on the 1<sup>st</sup> floor. Also, this allowed the owner to meet the goal of adding square footage while maintaining the buildings low profile. The cost of heating and cooling the underground portion will also be less for the owner. The owner originally wanted a taller building to add 3 floors to the original building and renovate the existing building. Though the existing structure could not support additional floors and the existing pressure on the bearing wall footings was not adequate for additional load required. Therefore the owner decided to sink two of the floors into the ground in order to satisfy the square footage requirements.

#### Traditional brick vs. green brick

A red masonry façade elon 70/30 (4" Brick) was used on the project in lieu of the specified "green" brick for the exterior wall. It saved approximately \$65,000 for the owner. Although, the owner wanted the "green" brick as a selling feature of the building however economics won out.

## Value Engineering Ideas Considered But Not Implemented

## Green roof vs. traditional roofing methods

Traditional roofing methods were suggested by Skanska however a green roof was still used despite cost implications. Adding green roofing cost the owner approximately \$300,000 more than traditional methods. The green roof was a part of the owner's requirements to implement practices and procedures to meet the project's environmental performance goals, which include achieving LEED Platinum Certification.



Figure 8: Shows Green Roof and Aluminum Railing

#### Not using aluminum roof railing

Skanska suggested not using aluminum roofing. Since, the aluminum roof railing did not require maintenance the owner decided to use the aluminum roof railing. Aluminum roof railings were added in lieu of painted steel railings, even though this would cost approximately \$50,000 more. The owner's goal for the aluminum roof railing was to allow for occupants on the green roof terraces.

Project X went thru an exhaustive 5 year estimating and value engineering sessions until the owner had a design they liked and could afford. Skanska vetted everything extensively. Project X went thru an exhaustive 5 year estimating and value engineering sessions until the owner had a design they liked and could afford. Skanska vetted everything extensively.

## **Problem Identification**

#### **Dealing with Public opinion of project**

The school and the greater university have trumpeted the building as a positive addition to the neighborhood. With the Project X, the university attempted to foster a dialogue with the community to avoid increasingly negative perception of the university. The university went to great lengths to build a contextual building and to preserve the walls of the Playhouse and develop an enhanced performance space for this historic theater. Maintaining the existing walls of the Playhouse was a main point of contention between community leaders and the university, and when structural instability in one of the walls was discovered during construction last summer, some of it was demolished without public announcement, angering community officials. Although, the owner has preserved everything possible the community was still generally angered by the construction.

NYU has recently discussed with local community groups about a construction project on the site that would provide space for legal research centers for the NYU School of Law. Before construction an office and apartment building which houses the Playhouse, occupies an important cultural spot in the history of the American theatre. However, the actual building that previously existed on the site today looks nothing like the building occupied by the playhouse theater, most famous for launching the career of Eugene O'Neill among many others of his contemporary writers, actors and artists. The existing building is the result of a major renovation in the 1940s when four separate houses were converted into one apartment building. This conversion included the complete renovation of the interiors of the buildings and the construction of a single façade that you see today. Figure 9 shows the Pre-1940s renovation on the left and the new building on the right.



Figure 9: Shows the Pre-1940's Renovation on the Left and the New Project X Building on the Right.

#### Reduce the rework time and cost in estimating

The contractors, the designers, and the owner had to constantly be updating new drawing during the five year estimating and value engineering sessions. Could the team have benefitted from converting the project into a paperless project?

#### Low value of BIM due to the small size of the building

The project was a small size, therefore the owner and contractors decided not to implement BIM on the project. BIM modeling could have possibly been used to persuade the public opinion of the project. Also, the BIM model could potentially bring time savings cost savings to the project.

#### Schedule

Schedule acceleration had to revert to working overtime and second shifts in order to complete the project on time. Is there an alternate schedule acceleration method that could have been used? Possibly, implementing Vela systems on the project could have saved the project team money in by expediting the schedule.

## **Technical Analysis Methods**

#### Utilizing BIM for estimates, design, and owner validation

Identify specific areas of Project X design which were extensively analyzed by the owner, redesign by the designer, and estimated by the contractor. Analyze time savings that could have been achieved by sharing information in the preconstruction stage.

Develop a strategy for the owner to use on future projects to use for a more streamlined and integrated information exchange between the owner, contractor, and designers by developing a BIM project plan using The BIM Project Execution Plan. This can be used by the owner as an example for future building development. The BIM Project Execution Plan, which was created to provide a practical manual that, can be used by the project teams for designing their BIM strategy and developing a BIM Project Plan.

#### **Implementing BIM in the field**

The second topic of interest is carrying BIM to the field- new responsibilities, roles, & competencies. How can the trades utilize the BIM to decrease the amount of time in spent construction? How can the construction managers' verify the construction in the field more efficiently? As more people see the potential for BIM in construction, they realize that it can be used in all phases of the construction process from planning, bidding and designing to building and management and be taken out to the field.

Analysis multiple case studies to identify potential areas BIM can be used in the field. BIM implementation varies from project to project, so it would be beneficial to have a source of successful project tools that could be used on different projects. The analysis will consist of the case studies listed in Table 1 and five construction company interviews. In the end, develop a list of technics that could be implemented on Project X. There many companies in the industry researching this subject. The goal of this portion is to bring a greater awareness of BIM in the field. BIMtofield.com Website by Trimble will be used for reference.

An interesting initiative spearheaded by Trimble is "BIM to Field" that will focus on helping building owners, contractors, and engineers better understand the potential of solutions that allow the transfer of BIM data to field level systems. While the BIMtoField.com Website is a major step forward in creating awareness about the transfer of BIM data to the field, the initiative's activities will extend further to include hosting annual seminars, Webinar series, as well as product and solution level certifications, according to King. For now the Website will be a resource for case studies, videos, white papers, and best practices learned from the industry. The initiative is comprised of industry leading solution providers including Accubid, Micro Application Packages LTD (MAP), QuickPen, Tekla, Trimble, Technical Sales International (TSI) and Vela Systems. Each of these partners has developed unique products and solutions that provide an aspect of delivering BIM data to the field. BIM to field was discussed by Jurrud Krug, marketing manager for Building Construction Division of Trimble at Trimble Dimensions 2010 Conference held in Las Vegas, Nevada. (AEC Weekly November 22, 2010 by Susan Smith)

#### Gray

Utilizing Vela systems Customer Case Studies								
CM	Concept	Benefts	Project Type					
Barton Malow	Connecting BIM to Commissioning, Handover and Operations	Solution Reduces Costs of Handover and Operations for Owner and Improves Contractor Efficiency.	Hospital (Maryland General Hospital, Baltimore, Maryland) - Addition and Penovation					
Turner	Managing QA/ QC from an Enterprise Perspective - Verifying Conformance and Driving Performance	Technology Improves Enterprise-level Quality Assurance and Fisk Management.	Condominium (Fittenhouse Square, PA), Military Housing Unit (Hampton Poads Naval Housing, VA) and others					
DPR	BiM-enabled Real-Time Supply Chain Management at DPRConstruction, Inc. with Tekla Structures and Vela Systems	Tekla-Vela integrated system accelerates schedule 20%, eliminates unnecessary reorders, improves coordination and crew allocation.	Education (UCSC Porter B College, Santa Cruz, California)					
Robins & Morton	Robins & Morton Gains ⊟ficiency and Accelerates Healthcare Project Delivery Using Vela Systems Field Software	Improved quality control processes towards a goal of zero punch. Accelerated project delivery without jeopardizing quality and dient service.	Hospital, Central Energy Plant, Medical Office Beilding (Florida Hospital Memorial Medical Center, Ormond Beach, Florida)					
Clabro	Clanbro Achieves Paperless Jobsite at Destiny USA: Integrated solution from Vela Systems and Autodesk automates electronic plan delivery and filed activities on Tablet POs	Achieved paperless jobsite, cut issue processing time from 5 days to 8 minutes.	Green Construction: Commercial Mall (Destiny USA, Syracuse, New York)					
Hensel Phelps	Hensel Phelps Uses Vela Systems Field Software to Deliver Prototype of New Aircraft Launch System for the U.S. Navy	Saved Headcount by Automating Quality Inspection Processes and Using Bectronic Documents in the Field.	Heavy-Military (BMALSFacility, Naval Air Engineering Station, Lakehurst, New Jersey)					
Skanska	Skanska Uses Field BIM Solution to Save \$1 Million on the New Meadowlands Stadium	Saved \$1 Million in Project Costs.	Stadium (New Meadowlands Stadium, New Jersey)					
BEFFRY	Industry Safety Leader William A. Berry & Son Uses Vela Systems to Improve Safety Verification and Subcontractor Accountability	Reduced Safety Inspection Time By 50%	Hospital (Brigham and Women's Hospital new Cardiovascular Center, Boston, Mass)					
SUFFOLK	Driving Efficiencies in the Construction Industry with Motion Tablet POs	Suffolk Outs Contractor Worklist Time By 50%	Hospitality (Liberty Hotel, Boston, Mass)					
Charleville Development Corp	Charleville Development Accelerates Project Delivery and Improves Quality with Vela Systems for The Blue at Doral Project	Gained 30 Days on Schedule.	Condominium and Hotel (The Blue at Doral, Miami, Ra)					
Arquitectonica	Arquitectonica Launches Next Generation Construction Administration Services with Vela Systems	construction administration processes, saves time on each project due to field automation.	Commercial and Mixed Use (Wilkie D. Ferguson, Jr. United States Courthouse in Miami, Fla)					
амс	OMCGroup Accelerates Grovenor House Project with Vela Systems Software	Finished 3 Months Ahead of Schedule.	High-rise Condominium (Grovenor House, Miami, Fla)					

Table 1: Shows the Case Studies that Will Be Utilized for Finding More Information About Field Implementation of BIM This table was provided by Vela systems.

Identify and recommend potential areas that owners can utilize BIM after construction Currently, owners don't know the how the BIM can be used after construction. In most cases, it is archived and long-term value of the model is lost. Also, there is not a Building Management System that is integrated into the BIM. The goal is to developing models to meet the client's needs. "Building information modeling is certainly the most talked about technology. In fact, market research indicates that more than 50% of the building and construction industry is now using BIM in some form." (ENR November 22, 2010) Despite these numbers, many owners don't know what to do with the BIM after construction. How can owners utilize the BIM for facility maintenance and operations? The solution begins by investigating the end uses of the model before the construction begins. On most projects the data owners need for facility maintenance, certification, and inspection data is not included in the model, because the owners don't put these requests in the specifications. Thus this information must become apparent in order to include them in the BIM execution plan, so the contractors and designers don't include too much information and too little information. Ideally the contractor would have recommendations from the owner; however owners don't necessarily know all the choses. Thus the goal of this analysis would be to contribute this data to The Pennsylvania State University's **BIM** Execution Plan.

The following is goals I am looking to accomplish in shadowing The Pennsylvania State University's OPP Area services.

Identify how the current practices of commissioning for project closeout and continuous commissioning.

Identify viable information that can be uploaded into the BIM model.

Identify which maps and O&M are used by the universities maintenance department.

Identify ways the owners can store design intent and O&M in the BIM.

Development a strategy for universities maintenance department to organize data within the BIM model.

Identify which energy management system, BMS, cafum, MMS, CMMS, or ARTRA is being used by The Pennsylvania State University and University X.

Identify common renovation changes that can be updated simultaneously in the BMS and BIM.

This will be accomplished by shadowing The Pennsylvania State University's OPP and University X's OPP. At The Pennsylvania State University Andy Ellenberger Supervisor, Area Serves has granted me permission to shadow maintenance personal for a full week starting December 15, 2010 to December 25, 2010. In addition, research will require shadowing Project X's OPP maintenance worker for a day Area service personal's responsibilities include: electrical work, emergency repairs, environmental systems, everyday maintenance, plumbing and piping, preventative maintenance, refrigeration. It is very important for area services to identify the location and O&M required for maintenance in the least amount of time possible. Also, interviews will be conducted with the university's director of operations Kenny Lee and John Betchel to validate the conclusions.

#### Small projects uses of BIM advantages and disadvantages

COBIE is a standard used by the industry to monitor the dollar value of BIM use in construction. Use COBIE Calculator for a case study of Project X and four other buildings of The Pennsylvania State University's buildings and University X.

Assist in cultivating a data base of case studies that could be used by the industry.

Develop recommendations for COBIE.

Identify predictions for feasibility studies relative to Contract types, conditions, uses, long term uses, and life cycle costs.

Determine time savings that can be achieved by the owner while using BIM technology.

## Identify current design limitations of BIM technology Structural

Design the concrete structural system with Revit Structures program. Design the concrete structural system with Tekla Structures program. Determine the benefits of a detailed structural model from the start of design. Compare the disadvantages and advantages. Find the current limitations of the software Analyze time savings that could be saved in the shop drawing and detailing process. **Electrical** Design the electrical with Revit MEP systems. Determine the benefits of a detailed electrical from the start of design.

Analyze time savings in the detailing process.

Determine the benefits of a detailed electrical model from the start of design.

Identify how 3D models assist in prefabrication of work for electrical contractors.

Identify how the 3D model can be helpful when complicated conduit bends are required.

Identify the benefits of representing the contractors' access and maintenance clearances in their models.

Identify the current areas that are lacking of product information.

Analyze time savings in the detailing process.

#### Conclusions

Modeling the building using current technology will clarify the current limitations of the software.

Identify the possibilities of model-based fabrication.

Compare the disadvantages and advantages Revit and Quickpen. Tekla, Trimble, Accubid. Interviewing the designers of Project X to learn what software they used. Find out the limitations of BIM in design application.

## **Research Interviews**

Interview with Thornton Tomasetti discovered Tekla Software can detail concrete reinforcement. Typically this is only done for clarification purposes in the field of complex details, such as MEP penetrations, column splices, and foundation walls. This is a very simple to do (research the procedure for this.

Interview with Barton Associates to discover BIM's capabilities for electrical and HVAC design.

Interview with Dr. Lepage discover Tekla Software capabilities with concrete structures

Interview with Dr.Geschwindner to find out the applications of Steel construction in BIM technology