NEW REGIONAL MEDICAL CENTER

EAST NORRITON, PA



Senior Thesis Final Report

Implementing VDC tactics to add value in design, preconstruction, construction, and document turnover

Brian J. Nahas The Pennsylvania State University Department of Architectural Engineering Construction Management Option

Faculty Advisor: Dr. Robert Leicht AE 482 | Spring 2012



EAST NORRITON, PA

NEW REGIONAL MEDICAL CENTER

Gilbane Building Company

Einstein MEDICAL CENTER MONTGOME

ARCHITECTURAL FEATURES

- 96 medical & surgical | 22 ICU | 20 obstetrical | 8 neonatal beds
- 5 story glass atrium with smoke management system
- Curtain wall composition: precast concrete panels & glazing
- LEED Certified Rating

MECHANICAL SYSTEM

- 10,800 square foot Central Utility Plant
- 9 AHU's | 3 water chillers (two 825 ton, one 450 ton) | three boilers (two 500 HP, one 400 HP)
- Variable air volume systems located in each patient room to provide personalized heating and cooling needs
- Double Interlocked Deluge Preaction Sprinkler System

ELECTRICAL SYSTEM

- 500A, 480/277V, 3 phase, 4 wire feed supplies the building through two redundant 3750 KVA 408/277V transformers
- Seventy-nine 480/277V | Ninety-six 120/208V panel boards feeding the building systems
- Two 100KW, 1250KVA generators

PROJECT OVERVIEW

Owner: Construction Manager: Architect: Structural Engineer: Civil Engineer: MEPF Engineer: Project Cost: Size & Height: Duration:

New Regional Medical Center, Inc. Gilbane Building Company Perkins + Will, Inc. O'Donnell & Naccarato Bohler Engineering, Inc. PWI Engineering \$147 million 366,780 SF | 5 Stories July 6, 2010 - August 31, 2012

CONSTRUCTION

- 84-acre Greenfield Property | 30-acre preserved
- CM at Risk contract | Guaranteed Maximum Price
- Foundations phased North to South | Steel phased West to East | Finishes phased top-down, bottom-up meeting on 1st Floor
- Hospital staff training scheduled August 8 October 15, 2012

STRUCTURAL SYSTEM

- Cast-in-place concrete column footings & foundation walls
- Structural steel frame | 30' x 30' grid
- W12 & W14 column with splices at 1st & 3rd Floors
- W24 girders & W14 beams with flexible moment connections at column connections
- All slabs consist of metal decking, shear studs, WWF & composite concrete

BRIAN J. NAHAS | CONSTRUCTION MANAGEMENT http://www.engr.psu.edu/ae/thesis/portfolios/2012/bjn5029/index.html



Senior Thesis Final Report Brian J. Nahas Construction Management Option

EXECUTIVE SUMMARY

This Senior Thesis Final Report includes the process development and outcomes derived through the analysis of the New Regional Medical Center. This facility is a new construction, 5 floors, 366,780 square foot hospital in East Norriton, Pennsylvania, and is associated with the Einstein Healthcare Network.

Through the four areas of technical analysis, investigation and applications have identified construction efficiency through information exchange. BIM utilization will streamline the construction estimating and planning processes on this project. An effective curtain wall modularization and architectural redesign of the atrium, in addition to a structural redesign of the concrete pour strips, will provide a strong comparison of the benefits in early designer and builder communication. Finally, the development of a facility management interface for building operation will identify innovative solutions and provide substantial benefits of a project-based document interface.

BIM IN PRECONSTRUCTION:

Model-based estimating is a growing VDC concept within construction firms. Over the past few years, industry leaders have begun developing internal processes in order to identify and understand the capabilities of this method. This analysis investigated the implementation of this strategy for estimating the structural bid packages -- identifying strengths, weaknesses, and industry growth. The structural steel Revit-based estimate produced a cost of \$7,710,326, which is 0.50% above the schedule of values logged for this system. The cast-in-place concrete estimate was not as successful, resulting in a 10.70% deviation for the schedule of. It has been recommended that implementation of 5D estimating for a structural steel system is effective.

As VDC gains speed within the industry in traditional applications, developments were made to identify a logical workflow, extracting data from the structural steel model to identify the most cost effective erection process. It was recognized that the workflow of the structural erection of the New Regional Medical Center contained an oversize crane for 77% of the duration. Through this visual analysis of Revit-based data, it was recognized that construction by sector is a more efficient process. This analysis identified a new VDC method in order to highlight trending data within a structural steel model, and resulted in a savings of two weeks on the construction schedule, in addition to \$315,727 of the project cost.

REDESIGN OF ATRIUM ENCLOSURE PROCESS

Prefabrication and unitization of glazing systems have been recognized for developing higher quality, faster installation, and a safer working environment. This analysis investigates the consideration of unitization of the atrium's curtain wall and a related architectural redesign to improve construction logistics and enhance the utilization of open space in the facility. At \$123,455, the architectural redesign included the addition of floor levels and corridor access along the curtain wall at the 1st and 3rd levels. The cost savings are minor for the unitization of the curtain wall; however, it would provide a safer work environment, higher quality, and a tighter work schedule.

This analysis created an aesthetically pleasing space to improve constructability and eliminate a high-risk construction process on the site, while also providing a space for patient and visitors to enjoy the greenfield



landscape surrounding the hospital. It was recognized that the unitization of the curtain wall system would reduce field assembly duration; however, require a 20-week lead-time to procure and assemble the units. Unitization would have only been logical if the glazing subcontractor was brought into the project earlier to assist with design development.

REDESIGN OF STRUCTURAL POUR STRIP

Constructability issues versus design decisions are consistently reviewed in order to understand the implication of a chosen system. This analysis preforms a cost comparison of the expansion system of the facility to identify if the selected system is the best option for the owner. It has been identified that the building's pour strip system is a more cost effective design decision. The choice to utilize the pour strips over expansion joints saved the project approximately \$57,800. The analysis also clarified that the building's pour strip system is a more aesthetically pleasing system and is preferred by the Owner.

It is recommended that other design teams and Owners investigate the implications of a pour strip within their facility in lieu of an expansion joint. Although the expansion joint provides a simpler construction method, the aesthetic results and additional costs may not be worthwhile. Through the utilization of design alternative in Autodesk Revit, the design team or construction management firm can quickly analyze the cost benefits and cross-reference these outcomes with the intentions and goals of the Owner and facility user group.

DOCUMENT MANAGEMENT FOR THE OWNER

This analysis focused on the research into the development of an accessible, easy to use, and updatable, document management system for the facility management team after the construction of the building. Through industry discussion, interface development, and continued feedback from the user group, it was identified that this system is critical to streamlining the workflow of a facility management team.

This analysis confirms the capabilities of new approaches to document controls and turnover packages for an owner. Although a digital turnover interface is not included with the original package of the New Regional Medical Center, with development, the concepts shared through this research will permit the Owner to incorporate the ideas into their new healthcare campus in East Norriton, PA. By providing new methods such as an FM Dashboard and FM Interact to host BIM packages and construction documents in a simple interface, the user group can easily sort through great quantities of documents to find applicable items.

It is recommended that Owners, notably from Universities and Healthcare Systems, need to develop their internal goals of document management. Although construction companies will be capable of developing a web based interface and document controls for turnover, larger Owners should outline their own method in order to streamline and combine all of this facilities into a common system.





ACADEMIC ACKNOWLEDGEMENTS

The Architectural Engineering Faculty

Dr. Robert Leicht (Advisor)


INDUSTRY ACKNOWLEDGEMENTS



Gilbane Building Company







Special Thanks

Andrew Packer, Jerry Shaheen, & Gilbane's Project Team

Richard Montalbano & the Facility Management Staff at Albert Einstein Healthcare Network

Gene Hodge, Jason Brown, Nicholas Kantor, & Michal Wojtak at Mortenson Construction

Dr. Craig Dubler & the Facility Management Staff at Penn State's Office of Physical Plant

PACE Industry Members

My Family & Friends



Table of Contents

Abstract	1
Executive Summary	2
Acknowledgements	4
Building Introduction	
Project Team Directory	
Client Information	
Project Delivery System	
Engineering Systems	
Building Construction Cost	
Detailed Project Schedule	
Analysis Weight Matrix	
Analysis 1 BIM in Preconstruction	
Part A: BIM for Quantity Takeoff & Estimating	
Methodology	
Outcome	
Reflection	
Part B: Crane Planning & Logistics	
Methodology	41
Alternate Process	45
Reflection	50
Analysis 2 Redesign of Atrium Enclosure Process	
Methodology	
Outcome	63
Reflection	
Analysis 3 Redesign of Structural Pour Strip	65
Methodology	
Outcome	
Reflection	
Analysis 4 Document Management for the Owner	
State of the Industry	77
Concept A: FM Dashboard Development	86
Concept B: FM Interact Development	
Senior Thesis Final Report April 4, 2012	Page 5



Outcome
Reflection
Recommendations & Conclusions
Analysis 1 BIM in Preconstruction103
Analysis 2 Redesign of Atrium Enclosure Process104
Analysis 3 Redesign of Structural Pour Strip104
Analysis 4 Document Management for the Owner105
Resources & References
Appendix A Organizational Chart
Appendix B Staff Organizational Chart109
Appendix C General Conditions Plan
Appendix D Structure & Enclosure Plan
Appendix E Project Schedule
Appendix F 5D Estimate Process Map
Appendix G 5D Estimate Values
Appendix H Crane Sequence Trending Charts
Appendix I Crane Load Chart
Appendix J Critical Path Schedule
Appendix K Pour Stop QTO & Estimate152
Appendix L Expansion Joint Structural Analysis
Appendix M Expansion Joint QTO & Estimate
Appendix N Nystrom Expansion Joint Product Guide



FIGURES REFERENCES IN REPORT

FIGURE 1: REGIONAL MAP BING.COM	10
FIGURE 2: BIRDS-EYE VIEW (LOOKING NORTH) BING.COM	10
FIGURE 3: FACADE SYSTEM GILBANE BUILDING CO	11
FIGURE 4: PATIENT ROOM MOCKUP GILBANE BUILDING CO.	14
FIGURE 5: NEW REGIONAL MEDICAL CENTER'S VISION GILBANE BUILDING CO	14
FIGURE 6: STRUCTURAL STEEL ERECTION SOUTH ELEVATION	18
FIGURE 7: STRUCTURAL STEEL ERECTION WEST ELEVATION	18
FIGURE 8: GENERAL CONDITION RATIOS	23
FIGURE 9: BUILDING QUADRANTS SHEET A-200A PERKINS & WILL	26
FIGURE 10: STEP 2 – SELECT CATEGORY < MULTI-CATEGORY >	32
FIGURE 11: SELECT NECESSARY FIELD REFERENCES PER MODELED COMPONENT	32
FIGURE 12: STEP 4 - SELECT NECESSARY GROUPING STRATEGIES	33
FIGURE 13: STEP 5 - SCHEDULE REVIEW	
FIGURE 14: ESTIMATING SPREADSHEET	34
FIGURE 15: RESEARCH RESULT TREND VS. SYSTEM IN 5D ESTIMATING	39
FIGURE 16: DWF MODEL OF CRANE ANALYSIS COLOR ATTRIBUTING	42
FIGURE 17: PIVOTTABLE FIELD CONFIGURATION	45
FIGURE 18: CRITICAL PICK WORKFLOW - TRENDING BY ELEVATION [SEE APPENDIX H FOR FULL SCALE]	46
FIGURE 19: CRITICAL PICK WORKFLOW - TRENDING BY SECTOR [SEE APPENDIX H FOR FULL SCALE]	47
FIGURE 20: CRANE LOGISTICS – BLUE: GROVE TMS9000E, RED: 2250 MANITOWOC	50
FIGURE 21: CURTAIN WALL GLAZING WORKFLOW	55
FIGURE 22: CURTAIN WALL CONSTRUCTION [TAKEN ON 10/4/2011 BY AL BATTEN, R.A. KENNEDY & SONS INC.]	56
FIGURE 23: INTERIOR MODEL IMAGE AT 2ND FLOOR ATRIUM	58
FIGURE 24: RENDERED 3D INTERIOR SECTION AT ATRIUM	59
FIGURE 25: RENDERED 3D EXTERIOR SECTION AT ATRIUM	60
FIGURE 26: SOUTH FACADE DELIVERY SEQUENCE	61
FIGURE 27: EAST ELEVATION DELIVERY SEQUENCE	61
FIGURE 28: FIELD JOINTED UNITS [SHOWN IN BLACK OUTLINE]	62
FIGURE 29: SCHEMATIC LIFT SEQUENCE	62
FIGURE 30: SECOND FLOOR OVERALL FRAMING PLAN [SHEET S-120 PERKINS & WILL]	65
FIGURE 31: ENLARGED POUR STRIP [S-220B PERKINS & WILL]	66
FIGURE 32: SECTOR B ROOF POUR STRIP [TAKEN ON 6/13/2011 BY GILBANE BUILDING CO.]	67
FIGURE 33: ALLOWABLE BUILDING LENGTH PER CALCULATED DESIGN TEMPERATURE	71
FIGURE 34: JOINT RENDERING	72
FIGURE 35: JOINT DETAIL	72
FIGURE 36: POUR STRIP STRUCTURAL FRAME SYSTEM	73
FIGURE 37: EXPANSION JOINT STRUCTURAL FRAME SYSTEM	74
FIGURE 38: CLOSE-UP POUR STRIP SLAB & STRUCTURE CONFIGURATION	75
FIGURE 39: CLOSE-UP EXPANSION JOINT SLAB & STRUCTURE CONFIGURATION	75
FIGURE 40: SURVEY RESPONDENT FIRM TYPES	81
Figure 41: Dashboard Components	88
FIGURE 42: WEB-INTERFACE LOGIN SCRIPT	89



Figure 43: Portal Homepage	89
FIGURE 44: PROJECT HOMEPAGE	90
Figure 45: File Structure	
FIGURE 46: ROOM LOG DATABASE WEBPAGE	92
Figure 47: Room Log [Enlarged]	92
FIGURE 48: AS-BUILT DRAWINGS WEBPAGE	
FIGURE 49: AS-BUILT MODELS WEBPAGE	94
Figure 50: O&M Data Webpage	94
FIGURE 51: SUBMITTAL WEBPAGE	
FIGURE 52: TRADE DIRECTORY WEBPAGE	96
FIGURE 53: PIVOTVIEWER NETFLIX APPLICATION	98
FIGURE 54:DEEPZOOM CONCEPT	98
Figure 55: Custom Filter Parameters	99
FIGURE 56: CUSTOM DATA ENTRY & DOCUMENT RELATIONSHIPS	



TABLE REFERENCES IN REPORT

TABLE 1: TYPICAL PATIENT ROOM FIXTURE SCHEDULE	19
TABLE 2: GENERAL CONDITION SUMMARY	23
TABLE 3: DETAILED SCHEDULE PHASE SUMMARY	25
TABLE 4: WEIGHT MATRIX OF DISTRIBUTION IN INVESTIGATION AREAS	29
TABLE 5: 5D ESTIMATING COMPARISONS	36
TABLE 6: PROPOSED SCHEDULE WITH TWO CRANES (VALUES PROVIDED THROUGH GILBANE SCHEDULING)	49
TABLE 7: CURTAIN WALL COST SUMMARY	
TABLE 8: PROPOSED SCHEDULE FOR ATRIUM ENCLOSURE ACTIVITIES	
TABLE 9: UPDATED SCHEDULE FOR ATRIUM ENCLOSURE ACTIVITIES	54
TABLE 10: ARCHITECTURAL REDESIGN COSTS	63
TABLE 11: POUR STRIP COST SUMMARY	66
TABLE 12: DESIGN LOAD SCHEDULE [S-001 PERKINS & WILL]	70
TABLE 13: SNOW DESIGN LOAD SCHEDULE [S-001 PERKINS & WILL]	70
TABLE 14: EXPANSION JOINT COST SUMMARY	72
TABLE 15: COST COMPARISON	76
TABLE 16: WHAT READERS LIKE ABOUT THEIR INFORMATION TECHNOLOGY TODAY	81
TABLE 17: WHAT READERS SAY ABOUT THEIR FUTURE INFORMATION TECHNOLOGY NEEDS	
TABLE 18: PIVOTVIEWER FOR FACILITY DOCUMENT MANAGEMENT	101



The New Regional Medical Center

OWNER: THE NEW REGIONAL MEDICAL CENTER, INC.

BUILDING INTRODUCTION

SITE OVERVIEW

The New Regional Medical Center is located at 559 West Germantown Pike in East Norriton, Pennsylvania (Figure 1). The selected site is an 84-acre greenfield property, which was previously occupied by an 18-hole golf course, miniature golf course, and auxiliary buildings; this site provides a very accessible and open plan for development. It is located directly off of a main arterial road (Germantown Pike) which bisected half of Montgomery County, and provides access to major roadway systems of





neighboring counties. The site design shall preserve over one-third of the property as open green space for patients, visitors, and public walking trails. Along Germantown Pike, on the Southwest and Southeast corners of the property, there are existing establishments that range from restaurants, drugstores, and retail services, as shown in Figure 2.

ARCHITECTURAL DESIGN

The facility's architectural design includes 146 beds: 96bed medical/surgical, 22-bed intensive care unit, 20bed obstetrical unit, and an 8-bed neonatal intensive care unit. It also includes a state-of-the-art 24-hour emergency department, advanced cancer care, advanced cardiac services, in addition to cutting-edge catheterization and electro-physiology laboratories (Wooley, 2010). Future campus development plans



FIGURE 2: BIRDS-EYE VIEW (LOOKING NORTH) | BING.COM

include direct on-site access to primary care at the adjacent medical office building. The main architectural feature of the project is the five-story central patient tower atrium. This atrium serves as the location of the main entrance, and the vertical conveyance systems for the hospital. It also provides a sun-filled space, in which each floor's balcony steps back from the curtain wall to provide an open, large, panoramic view of the surrounding green space and across Germantown Pike onto the preserved lands of the Norristown Farm Park.

ARCHITECTURAL MATERIALS

The primary building enclosure is a curtain wall system that incorporates precast panels and glazing units, as shown in Figure 3. The architectural precast concrete panels are located on the North, South, and East façade of the patient tower, and feature linear windows of consistent size. In order to create aesthetic variation and



texture across the surfaces, sandblasting of varying degree was requested. In addition to this, split-faced concrete masonry units are located on the building at the West, North, and East sections of exterior wall at the Emergency Department and the Central Utility Plant. Metal panel components are located on the building at the West facade of the patient tower in addition to the screen wall surrounding the rooftop mechanical systems for the low roof.

SUSTAINABILITY

The New Regional Medical Center is dedicated to implementation of sustainability features within design, construction, and lifecycle of the facility. With consideration for the patients, the community, and the environment, countless steps have been taken by the Einstein-Montgomery Partnership and project team to achieve their goal of a LEED Certified rating for the medical campus. Sustainability features include a land preservation and waste management program, management of solar gain through architectural design and building placement, and design development for



implementation of future sustainable technologies.

FIGURE 3: FACADE SYSTEM | GILBANE BUILDING CO.

CONSTRUCTION PROGRAMMING

The New Regional Medical Center includes 4 stories above grade, with a partial sub-grade ground floor. It will stand at 90'-8" tall, and have a gross building area of approximately 360,000 square feet. The project is being delivered through a construction management at risk contract, under an approximate construction cost of \$147 million using a guaranteed maximum price contract.

Construction began on July 6, 2010 and is scheduled to be completed on August 31, 2012.



PROJECT TEAM DIRECTORY Einstein OWNER: NEW REGIONAL MEDICAL CENTER, INC. [THE PARTNERSHIP OF ALBERT EINSTEIN **HEALTHCARE NETWORK & MONTGOMERY** HEALTHCARE SYSTEM] nane C GILBANE BUILDING COMPANY **CONSTRUCTION MANAGER:** Gilbane Building Company ARCHITECT: **PERKINS + WILL STRUCTURAL ENIGNEERS:** O'DONNELL & NACCARATO **BOHLER CIVIL ENGINEER: BOHLER ENGINEERING** пщі MEP & FIRE PROTECTION ENGINEERS: PWI ENGINEERING **TRAFFIC ENGINEERS:** TRAFFIC PLANNING & DESIGN, INC LANDSCAPE ARCHITECT: wells**appel** WELLS APPEL



CLIENT INFORMATION

The Owner of the New Regional Medical Center consists of the collaboration and partnership of the Albert Einstein Healthcare Network (AEHN) and the Montgomery Hospital Medical Center (MHMC). The Einstein-Montgomery Partnership is referred to as the New Regional Medical Center, Inc. for the purposes of this report.

Individually, AEHN and MHMC have strong, rich histories regarding healing, healthcare, and service to the Philadelphia region. In 1865, AEHN was founded, and is now regarded as one of the most comprehensive healthcare providers in the region. MHMC has been proving medical care to the region since 1894, in addition to representing the market share in Central Montgomery County community. The partnership is based off common mission statements, focusing on serving the community and hosting excellence in clinical care. It was carried out through AEHN's long-term strategic growth initiative (Partnership Vision).

DRIVER FOR HEALTHCARE DEVELOPMENT

Within the past decade, there has not been a new medical center built in southeastern Pennsylvania (Wooley, 2010). The only previous healthcare work during this period consisted of facility renovations and interior upgrades. Currently residents of the Central Montgomery County region must travel to neighboring regions or into the City of Philadelphia to receive care. In order to permit residents to remain in this area and have accessible services, the New Regional Medical Center, Inc. realized that the southeastern Pennsylvania was lacking a modern, technologically advanced, healthcare campus capable of providing comprehensive care. In addition to meeting the facility needs, through this programming Einstein is able to harness their internal teaching experience in order to provide the latest clinical treatments and a highly skilled staff of physicians in the most advanced hospital in the region.

FACILITY EXPECTATIONS

In order to meet the void in healthcare services for this region, the New Regional Medical Center will feature the leading-edge clinical services and programs. This facility will operate as a full-service, acute care hospital. The program includes a 24-hour emergency care and trauma response, an advanced cancer center, cardiac surgery services, general surgery, and medical offices for primary care and specialist. The New Regional Medical Center is associated with Phase 1 of the medical campus. Additional installations, such as the medical office building will supplement the hospital's services, and provide convenient, on-site access to primary practices and specialists.

The campus is designed as a suburban hospital campus. By working with design professionals and local residents, the site design preserves one-third of the 84 acre property, providing a vast green space setting, complementing the Norristown Farm Park across the street. Through consideration of setting within the architectural design, 75% of hospital rooms will overlook the park.

Due to the high expectations for the facility's performance, the construction's quality and safety are two of the Owner's most valued aspect of the project. Through a GMP contract, any cost risks or concerns have been alleviated. In order to keep the project on schedule and uphold the delivery date of the project, strict liquidated damages have been incorporated to help emphasize the importance of a timely delivery; however,



necessary time extensions may be negotiated in order to deliver a high-quality facility under safe working conditions. Due to the greenfield site, very few sequencing concerns are present for the project, permitting a very accurate work flow, in addition to timely building turnover. The facility will undergo a single occupancy phase in addition to an Owner and staff-training period. In order to provide complete transparency between the Owner, construction manager, and site activities, the Owner has representatives on site to monitor and assist in the daily activities and approvals required for the project.

OWNER'S EXPECTATIONS

Perkins + Will, Inc. and Gilbane Building Company, were selected by the New Regional Medical Center, Inc. for their design and construction services due to their previous success in the health care market. Perkins + Will is a commercial architecture firm which specializes in health care projects. Gilbane is currently ranked seventh on *Modern Healthcare's* list of top Construction Management companies. With a very strong team in place, various programs and processes were incorporated into the project in order to meet the expectations of the Owner, end-users,



FIGURE 4: PATIENT ROOM MOCKUP | GILBANE BUILDING CO.

and the community. Assembly and room mockups are heavily utilized on the project in order to ensure the facility and systems meet the needs of the staff, in addition to proper workspace for the latest hospital equipment to be installed. Figure 4 provides an example of a mockup emergency patient room and a mockup of a general patient room. Three-dimensional modeling and coordination efforts were incorporated through the utilization of Building Information Modeling (BIM) in order to design and coordinate the mechanical, electrical, plumbing, and fire protection systems. These processes, in addition to strong Owner, A/E, and CM communication, will lead to a successful project and deliver the state-of-the-art New Regional Medical Center in accordance with the vision the Einstein-Montgomery Partnership set out to achieve (Figure 5).



-FIGURE 5: NEW REGIONAL MEDICAL CENTER'S VISION | GILBANE BUILDING CO.



PROJECT DELIVERY SYSTEM

CONSTRUCTION CONTRACT

The New Regional Medical Center project will be constructed under a single prime contract with Gilbane Building Company. The facility will compromise Phase 1 of the healthcare campus constructed on the 84-acre property. The Owner selected the construction manager through a Request for Proposal process resulting in a GMP selection. Gilbane Building Company was awarded the project and is delivering the project through a CM at Risk contract. The contract consists of a GMP of \$146,741,834.00 for the construction dates of July 6, 2010 to August 31, 2012. The project is listed as tax exempt. Liquidated damage language includes a fee of \$13,607 per day, applied to a late delivery after August 31, 2012. After sixty days late, liquidated damages increase to \$50,000 per day. Per the contract, one-hundred percent of cost savings is returned to the Owner. In addition to this, ten percent of Gilbane's fee is retained throughout the project's duration. If the project requires a time extension for unforeseen conditions or at Owner's request, time will be granted for delay to critical path items. Compensation on general condition expenses for durations of requested extensions will be considered on a case-by-case basis.

Appendix A contains graphical representation of the project's contractual agreements.

This project delivery and contract method is appropriate for the New Regional Medical Center because the project funding has been acquired through the sale of Federal Housing Administration Insurance Bonds in the amount of \$310,000,000. In addition to this, in August of 2010, the U.S. Department of Housing and Urban Development agreed to insure the bonds through FHA's Section 242 Hospital Mortgage Insurance Program (Wooley, 2010). Through utilization of private funding through bond sale, the guaranteed maximum bid process would permit the Owner to properly manage funding and meet the financial goals of the project without hidden or unknown construction costs.

Change orders and contract values are separately screened in order to ensure a tight project budget. Gilbane Building Company's experience with healthcare facilities of this size and delivery system produced a strong project team, innovate value engineering methods, and high standards on project safety, in addition to a competitive bid value. These elements assisted in the awarding of the contract.

Additional Contracts

Perkins + Will will prepare contract documents, with consultation from a team of design professionals. As shown in **Appendix A**, Perkins + Will operate by a lump sum and is in contract with their associates. In addition to the Architect, Program Manager, and Construction Manager working under contract of the Owner, three additional consultants are in direct contract with the Owner regarding specialty services.

The contract with Gilbane Building Company excludes the following concurrent construction operations at the project site: (1) Geotechnical & Testing Work, (2) Independent Testing, (3) Furniture, (4) Medical Equipment, (5) Communication Equipment, and (6) Nursing Stations.

The Owner will award separate contracts for these program-specific activities.



SUBCONTRACT DEVELOPMENT

The subcontract award process is as follows:

- (1) Gilbane prequalifies subcontractors for predetermined bid packages
- (2) Subcontractors are invited to place a bid by a predetermined time and date
- (3) The lowest qualified bidder is awarded the subcontract
- (4) Gilbane releases the bid results with recommendation to the Owner for selection and Owner's approval

Note: Each subcontract is a lump sum contract per the bid package's scope of work.

Once selected, the subcontractor is notified and agreement documents are procured. Ten percent of each trade contractor's payment is retained until substantial completion of scope of work. The Owner reserved the right to reduce retainage at fifty percent completion to five percent. The trade contractors are required to agree and pay for a 100% Performance and a 100% Payment bond, in addition to enrolling in Gilbane CCIP Program.

The Owner will provide Builder's Risk Insurance with a deductible of no more than \$50,000. However, Gilbane Building Company is required to maintain a CCIP Insurance Program. This program requires subcontractors to complete and submit the appropriate paperwork to qualify under their insurance. In addition to this coverage, per the subcontracts, trades must carry workers compensation and employer's liability, commercial general liability, business automobile liability, an umbrella liability, professional liability insurance, and finally contractor's pollution liability.



STAFFING PLAN

PROJECT MANAGEMENT

The project management system for the New Regional Medical Center is conducted through a full-time field staff, with supplementary support from the regional office. Gilbane Building Company's Delaware Valley Regional Office (DVRO) is overseeing the New Regional Medical Center. DVRO is based in Center City Philadelphia, Pennsylvania, and approximately 23 miles away from the project site, permitting strong support from the regional office.

As shown in **Appendix B**, the project organization chart represents the interrelationship between the Field Office and Regional Office operations. The Project Executive, Kevin Kriebel, is stationed at the job site to serve as a direct line of communication between the site activities and the Project Principle, Stephen O'Connor. Beneath Kevin is a team of six members who coordinate the various facets of the project. Their selection for their particular role is based on various measures, including previous job roles and experience in healthcare projects of this scale. Their responsibilities cover the major elements of a construction project from preconstruction through closeout, including administration, accounting, safety, quality, and engineering. As mentioned, the close proximity of the site to the regional office permits strong site support. For example, the MEP and BIM Coordinators for this project work out of the regional office; however, they host weekly on-site coordination meetings and building walkthroughs. These meetings included the modeler and/or supervisor for the following trades: (1) Sheetmetal, (2) Plumbing/HVAC Piping, (3) Fire Protection, (4) Electrical, (5) Drywall/Ceilings, and (6) Pneumatic Tube, in which constructability conflicts are resolved and work-in-place is reviewed.

Project Superintendent and Project Engineer, Brian Baird and Joseph McCammit respectively, oversee the daily site activities regarding Gilbane's project management. During the lifecycle of the construction process, slight variations of the staffing plan occurred to expedite deliverables and adapt to project conditions; however, the overall structure methodology has remained unchanged from the initial system proposed with the GMP.



ENGINEERING SYSTEMS

CONSTRUCTION MEANS & METHODS

In Montgomery County, Pennsylvania, it is typical for a hospital complex to be constructed with a steel framing system and curtain wall facade. Due to this building being the first medical center for the region in ten years, it is challenging to locate similar projects in the immediate area for a means and methods comparison. With the recent development in healthcare technology and building technology, the existing facilities in southeastern PA will not provide an efficient design and construction processes comparison.

Understanding the current state of healthcare construction, and Perkins + Will's expertise, the building methods utilized on the project reflect the current trends in construction within the Philadelphia region.

The foundation systems utilized on the New Regional Medical Center consist of foundation walls and spread footings. The work process for the foundation systems began with the north concrete spread footings and moved south. Foundation work was sequenced directly behind the excavation process, starting with the spread footings to the north, then placement of the wall footings and retaining wall, followed by the spread footings to the south.

The sequence plans (Figure 6 & Figure 7) for the structural steel of the New Regional Medical Center begins in the south-west corner of the structure and progress east, covering ground level to the second floor of the West Tower (shown in red). Once this section is complete, the remainder of the building's steel is placed to the same elevation. This phase is represented in orange. The crane returns to the south-west corner after looping the building, and continues to place the final two levels of the West Tower (shown in blue). From here, it travels along the south facade, placing the atrium and high-roof steel (shown in purple), the beginning of the East Tower (shown in green) and concludes with the remainder of the East Tower (shown in brown).




FIGURE 6: STRUCTURAL STEEL ERECTION SOUTH ELEVATION




FIGURE 7: STRUCTURAL STEEL ERECTION WEST ELEVATION



Finish sequencing is planned for a top-down, bottom-up approach. This method permits the trades to work their way out of the building, and depart the medical center on the first floor. Doing so also permits the completed sections of the facility to be locked out and begin closeout review. The programming of the facility has placed the Emergency Department and Operating Rooms on the ground floor and first floor, respectively, of the north sector of the medical center. These two areas involve the greatest focus regarding interior systems and finishes. By working down the East and West Towers, the tower crews will complete three floors (Fourth, Third, Second); in the same amount of time scheduled for the ground crews have to complete the ground floor. The goal is for the crews to merge on the first floor and work their way north, finishing the operating room support areas and waiting area last.

ELECTRICAL SYSTEM

The building will have electrical and tele-data components such as backup generators, critical circuitry to help ensure minimal power interruption, nurse call systems for effective communication and code blue systems throughout the campus. The supply power enters the site from the south-west corner, and follows the maintenance road up to the loading dock area of the medical center. This area hosts the backup generators and all utility connection for the facility. This facility has two emergency generators, with the capabilities for a third. These generators are 100KW, 1250KVA each and tie directly into the main power system.

The power enters the electrical control room through a 5000A Bus Duct that comes off of a 3750 KVA, 480/277V transformer. The medical center features a redundant supply system in parallel, permitting uninterrupted power supply. Once entering the electrical control room, the 500A, 480/277, 3 phase, 4 wire feed the building systems. The building system is also wired with for critical power, emergency power, and emergency power life safety services directly from the backup generators.

The medical center is serviced by seventy-nine 480/277V and ninety-six 120/208V panel boards which distribute power throughout the building to meet the services need of hospital equipment, staff, and patients.

LIGHTING SYSTEM

Due to the design efforts to create an effective balance of light quality with energy efficiency, the majority of lighting fixtures in the building incorporate energy efficient compact fluorescent lights (CFL). Additionally, metal halide (MH), fluorescent (FL), light emitting diode (LED), and either electronic or magnetic low voltage (ELV or MLV). A majority of the fixtures are recessed ceiling-mounted and require 277 volts, with wattage dependent on the lighting application.

TABLE 1: TYPICAL PATIENT ROOM FIXTURE SCHEDULE

Fixture Location	Туре	Quantity	Lamp Type	Wattage
Ceiling Mounted (Interior Side)	Recessed	2	CFL	32W/Fixture
Ceiling Mounted (Exterior Side)	Recessed	2	LED	20W/Fixture
Ceiling Mounted (Above Headwall)	Wall Wash Down	1	FL	28W/Fixture
Wall Mounted (Above Headwall)	Wall Wash Up	1	FL	14W/Linear Foot
Above Patient Bed	Recessed	1	CFL	160W/Fixture



MECHANICAL SYSTEM

The building's mechanical systems are made up of several main components including boilers, custom air handlers, cooling towers, chillers and variable air volume boxes. The central utility plant (CUP) houses all of the major mechanical equipment that is not installed rooftop. The CUP is located at in the north-west corner of the facility and was designed at a lower elevation to permit proper pipe and utility clearances above the equipment. There are four major vertical shafts (150 - 200SF each) that service the East and West wings of the patient tower. In the central core, there are two vertical shafts for MEP distribution for the Atrium and high roof services.

The New Regional Medical Center's HVAC system is serviced by seven custom outdoor air-handling units and two indoor air handling units. The outdoor AHU's are located as rooftop units, and the two indoor units are located in the CUP. They operate as a VAV mixed air system. There are three water chillers (825Ton, 825Ton, 450Ton) which service these AHU's cooling conditions, while the building's heating system is serviced by two 500 HP boilers and one 400 HP boiler which also located in the CUP. Ductwork is utilized to transport the air to each space, and all patient rooms contain VAV boxes for individual controls. Hydronic piping transports the chilled and hot water to each AHU. The Operating Rooms have a dedicated AHU system that features a blow-through arrangement and requires a minimum of 50,300 CFM of outside air in comparison to its 45,000 CFM supply air.

STRUCTURAL SYSTEM

The New Regional Medical Center features a structural steel frame, which is arranged on a grid pattern of 30 feet by 30 feet. The column system includes splices that are placed four feet about first floor, and four feet above the third floor. This permits ease of connection and assembly. The columns are comprised of W12 and W14, which range from 49 lbs/lf to 170 lbs/lf. The maximum load for the interior columns of the building are estimated to be 800 kips, and the maximum load for the exterior columns of the building are estimated to be 605 kips. This project features eight different braced frame configurations, which are oriented perpendicular to the south facade in the East and West Towers. The framing plan is generally comprised of W24 girders with W14 beams. All girders have flexible moment connections designed for lateral loads on the structure.

The slab configurations various throughout the structure, and utilize different assembly configurations. All slabs are comprised of composite metal decking, shear studs, and welded-wire-fabric.



ENGINEERING SUPPORT SYSTEMS

FIRE PROTECTION

The fire suppression system within the medical center includes a Double Interlocked Deluge Preaction Sprinkler System. This system corresponds to the facility usage since accidental discharge would be damaging to medical equipment and finishes. Water pressure is supplied by a 1000-gpm, 100-psi boot, diesel engine fire pump and networked though a combined wet standpipe and automatic wet pipe. The passive suppression system description is withheld at request.

TRANSPORTATION & CONVEYANCE

The New Regional Medical Center contains three stair towers, in addition to a monument staircase within the atrium, servicing the ground to first floors. All three of the major stair towers service the four medical floors, with the west conveyance servicing the high roof, and the central conveyance servicing the low roof. These shafts meet U.L. Design No. U467, and contain a two hour fire-rating shaft wall, in addition to two finished sides. The stair construction consists of shop fabricated steel sections. With two stringer beams, and a welded sheet metal tread pans, site filled with concrete. Due to high traffic during construction, tread pans were filled with wood blocking initially.

The elevator systems present in the medical system consist of four trauma (patient) elevators, in addition to three public service elevators. The elevator core is located at the rear of the atrium and provides a centralized vertical service to the facility. All elevator shafts are designed to the same life-safety standards as the previously mentioned for the stair shafts. The New Regional Medical Center contains three-machine room-less elevators for public service, which service 58'-8" of travel at 200 FPM for a 3000lb capacity. The four trauma elevators are a traction system that also covers 58'-8" of travel, but performs at 100 FPM for a 6000lb capacity.



PROJECT COST EVALUATION

BUILDING CONSTRUCTION COST

Building Construction Cost: \$127,653,895.80

Total Area: 366,780 SF

Building Construction Square Foot Cost: \$348.00/SF

TOTAL PROJECT COST

Total Cost: **\$146,741,834.00**

Square Foot Cost: \$400.10/SF



GENERAL CONDITIONS SUMMARY


The general conditions (GC) estimate for this project is based off of the 33 month construction schedule. It is comprised of personnel costs, construction management reimbursements and facility, temporary utilities, and miscellaneous costs, including bonding and insurances. Excluded items from Gilbane's general condition costs are also included in this section; however, they are also excluded from the table below. Table 2 and Figure 8 include summary information regarding the major components of general condition costs. This estimate was developed by using data provided by Gilbane Building Company, with supplement from RSMeans.

The New Regional Medical Center's general conditions estimate is \$18,222,285, with a monthly cost of \$560,094. Notable factors in the estimate are the personnel costs, in addition to the miscellaneous, bonds, and insurances on the project. Personnel costs account for 45.5% of the total GC cost, and miscellaneous, bonds, and insurances account for 52%.

Cost concerns for the general condition revolve around scheduling and billing overruns since any minor delay on the project schedule risks extending the large expense of personnel in addition to miscellaneous, bonding, and insurance beyond the scope of the GMP. In order to mitigate this, close monitoring must be made regarding construction progress, and personnel billing. The project team must monitor the construction schedule daily, and ensure their personnel costs are within the budget. Although miscellaneous, bonds, and insurances costs constitute the highest percentage of the New Regional Medical Center's general conditions, the project team can control few of these internally.

GENERAL CONDITIONS SUMMARY				
	Cost/Unit	Units	Total Cost	
Personnel	\$251,661	Month	\$8,304,803	
CM Reimbursable	\$11,102	Month	\$336,375	
		Single Expense	\$369,175	
Temporary Utilities	\$10,087	Month	\$332,874	
Misc., Bonds, Insurance	\$287,244	Month	\$9,479,058	
Monthly Total:	\$560,094	Project Total:	\$18,222,285	

TABLE 2: GENERAL CONDITION SUMMARY



GENERAL CONDITIONS RATIOS

FIGURE 8: GENERAL CONDITION RATIOS



SITE PLANS

EXISTING CONDITIONS PLAN

The site is located at the former location of *Wood's Golf Center* at 559 West Germantown Pike, in East Norriton Township. The site comprises 89 acres, and is bordered to the south by West Germantown Pike, and commercial and residential properties border the remaining sides. The terrain and topography of the site is typical of a standard golf course, and the site features multiple existing buildings and structures associated with the facility.

See **Appendix C** for the existing conditions plan for the New Regional Medical Center.

STRUCTURE & ENCLOSURE PLAN

This phase begins with the move of the field staff out to their project trailers. In addition to this, this phase includes the availability of onsite parking for all project workers. The tool trailers are added as more trades begin arriving to the site, and a secondary site entrance is established for emergency or after-hours use only. With the additional space in the newly built parking fields to the north, material storage for long lead items and recent project deliveries is available. The crane path is established along the south elevation of the medical center. Through the logistical planning and sequencing, this project can be completed per the schedule with one 300 Ton Manitowoc crane.

See **Appendix D** for the Steel Structure & Enclosure Phase Plan for the New Regional Medical Center.



DETAILED PROJECT SCHEDULE

PRIMAVERA SCHEDULE

The project detailed schedule includes approximately 270 activities and milestones associated within the phases of (1) design and preconstruction services, (2) construction activities, and (3) final closeout. The level of detail distinguishes sequencing, rough-in, finishes, and commissioning for trade activity. In addition to this, major phasing activities have been grouped in order to develop summary information concerning this work. Table 3 includes the major components of the Primavera schedule, and provides a summary of the phasing relations.

See **Appendix E** for the New Regional Medical Center's project schedule.

TABLE 3: DETAILED SCHEDULE PHASE SUMMARY

Primavera Schedule					
Phase	Start	Finish	Duration (days)		
Design & Preconstruction	01-Oct-07	11-May-10	681		
Construction	01-Jul-10	31-Aug-12	553		
Structure	29-Nov-10	18-Apr-11	99		
Enclosure	22-Mar-11	01-Sep-11	116		
Ground Level	11-Mar-11	25-May-12	310		
Level 1	08-Apr-11	28-Feb-12	227		
Level 2	22-Apr-11	28-Feb-12	217		
Level 3	04-May-11	28-Feb-12	209		
Level 4	11-May-11	28-Feb-12	204		
Project Closeout	09-Apr-12	15-Oct-12	133		

DESIGN & PRECONSTRUCTION

The design and preconstruction phase consists of 681 days and includes activities from preliminary site investigation / geotechnical testing through the Owner awarding the project to the construction management team. In review of the design and preconstruction sequencing, there are two major activity lapses on the project schedule between the (1) Preliminary Geotechnical Investigation and Supplemental Geotechnical Investigation, and (2) Supplemental Geotechnical Investigation and Civil Design. These lapses occurred due to timely decisions regarding finding a suitable site, and subgrade environment for the intended medical program. Additional influences on this gap can be attributed to coordination of the land purchase and development of project funding. However, once design began on the project, this phase progressed under suitable timing.

CONSTRUCTION

Construction of the New Regional Medical Center consists of 553 days from Notice to Proceed (NTP) to Substantial Completion. This phase includes all major construction activities (outlined in Table 3), in addition to site clearing, driveway and parking lot establishment, and landscape installation around the facility. The construction phase is identified through 10 internal sequences that are additionally detailed within the schedule provided in **Appendix E**.



STRUCTURE


The structural phase of the construction schedule includes a combination of steel erection, and slab on deck placement. This process is dictated by an overall sequence layout, staged by bays. The sequence essentially flows from A to D to C & B as noted in Figure 9. In addition to this typical sequence, concrete work for the footings and retaining wall, and the slab-on-grade (SOG) are also included. Items that are not included due to level-of-detail constraints include activities such as in-slab electrical and plumbing rough-in, in addition to steel staging and delivery milestones.

The layout sequences were identified in such a way to permit concurrent activities between steel erection and slab-on-deck (SOD) preparation and placement. Typically each sequence requires 10 - 18 days of work, while each SOD needs 5 - 10 days for placement. In order to efficiently plan work through these spaces, the SOD began construction approximately three sequences behind, permitting a safe working area for the concrete and decking crews, while also keeping an accelerated structural schedule. A key item to note is that the SOG is held until approximately 50% of the structure is in place, in addition to a portion of the slab on deck underway. This strategy is required in order to permit the appropriate electrical and plumbing services within the slab to be roughed-in prior to pouring. Due to the location of the cafeteria on ground level in Section A, this sequencing was essential to keeping this area of the facility on schedule.

ENCLOSURE

Building enclosure for the medical center is scheduled over 116 days, and includes major activities regarding façade and roof enclosure. Due to the various exterior materials on this project, and the internal phasing required to meet the constructability requirements of the curtain wall, this phase includes major activities surrounding the exterior walls, curtain wall pre-cast, and atrium curtain wall.

The exterior walls are located surrounding the ground level at the emergency room entrance (Section C), and the loading dock area





(Section D). This activity was sequenced first due to the longer duration of 95 days to complete. Following this, the curtain wall assembly was developed through the building sector layout. In this work flow, the medical center consists of 4 quadrants in which the trades are sequenced, as shown in Figure 9. Similarly, the roofs are phased by the quadrant method, in addition to designation of "low" or "high".

Enclosure begins with curtain wall pre-cast placement in section C and D, and progresses into section A and B. The building roof system is phased in a similar pattern, approximately one section behind the curtain wall. In order to minimize crane and worker overlap, the metal panel installation travels in the same sequence overlapping roof activities. They begin to the north, over sections D and C, and continue counterclockwise into the west façade. Due to constraints along the south façade (activity: curtain wall atrium), the metal panel work flow passes by the frontage of A and B, and continues work on the east façade before returning to fill-in



around the atrium curtain wall. The curtain wall atrium activity is the most critical of the enclosure sequencing due to its large size, challenging construction method, and its reliance on progress in both section A and B for tolerance controls.

GROUND LEVEL THROUGH LEVEL 4

Construction on the ground level through level 4 consists of a systematic workflow that is repeating at each level. The only major difference between these five sequences is the overall duration. The ground level consists of 310 working days, while level 4 consists of only 204 days. The floors between these two decrease in duration with the rise in level. The range in variation is due to the overlying fact that the ground floor and level 1 are the two largest floors with the core medical systems, while level 2, 3, and 4 consist of the patient tower with repetitive elements, and a more efficient work flow.

The sequencing on this aspect of the New Regional Medical Center consists of approximately 32 activities that include the major MEP and finishes trades. It details aspects regarding rough-in, distribution, and finishes, in addition to detailing the scheduling differences regarding overhead and in-wall activities. Specialty systems of the medical center, such as the medical gas system and the pneumatic tube system, are also included in the detailed schedule. It is recognized that duration increases with floor size and system complexity. In addition to this, activity items also increase in detail; however, these additional items were excluded from the detailed estimate due to detail constraints.

The following sequence reflects the flow of work through the New Regional Medical Center:

Finish sequencing is planned for a top-down approach. This method permits the trades to work their way out of the building, and depart the medical center on the first floor. Doing so also permits the completed sections of the facility to be locked out and begin closeout review. However, the programming of the facility, places the Emergency Department and Operating Rooms on the ground floor and first floor, respectively, of the north sector of the medical center. These two areas involve the greatest focus regarding interior systems and finishes; therefore, a second crew will be dedicated to this space. By working down the East and West Towers, the crews will complete three floors (Fourth, Third, Second); in the same amount of time scheduled for the second crew to complete the ground floor. The goal is for the crews to merge on the first floor and work their way north, finishing the operating room support areas and waiting area last (*Packer, Field Engineering | Gilbane Building Co., 2011*).

Note however, that the activities in the schedule do not convey the same message. Within **Appendix E**, and detailed in Table 3, work began on the ground level first, and additional levels were added approximately every two weeks, working up the structure. All floors are schedule to conclude on February 28th, except for the ground level which will not be completed for another 3 months. This discrepancy is due to a reevaluation of the MEP coordination and workflow process through the building. The included detail schedule reflects initial plans of the trade sequence. After discussion with the subcontractors, and revision of coordination model sequencing, it was recognized that this process is most efficient and meets the schedule and workflow progression outlined in the initial GMP.



PROJECT CLOSEOUT

The project closeout has been included in the detailed project schedule located in **Appendix E**. Project closeout takes 133 days for the New Regional Medical Center and includes activities such as Owner move-in, Department of Health (DOH) inspections, and Owner training. Workflow for move-in, inspections, and punch list items, will be conducted from the top down – following the trades out of each area, permitting each area to be signed-off and delivered in time for Owner and medical staff training.



ANALYSIS WEIGHT MATRIX

A weight matrix, shown in Table 4, was developed in order to appropriately allocate effort between the four core areas of investigation. The percentages within the matrix signify the actual level of time and effort dedicated to each of the four analysis areas, including the two breadths associated with the Atrium Enclosure Analysis and Pour Stop Analysis.

TABLE 4: WEIGHT MATRIX OF DISTRIBUTION IN INVESTIGATION AREAS

Analysis Description	Industry Research	Value Engineering	Constructability Review	Schedule Reduction/Acceleration	Total
BIM in Preconstruction	5%	5%	10%	10%	30%
Atrium Enclosure & Breadth	-	-	15%	-	15%
Pour Stop Analysis & Breadth	-	15%	10%	-	25%
Document Management	25%	-	5%	-	30%
Total	30%	20%	40%	10%	100%



ANALYSIS 1 | BIM IN PRECONSTRUCTION PART A: BIM FOR QUANTITY TAKEOFF & ESTIMATING PROBLEM IDENTIFICATION

Gilbane utilized various processes and software platforms to quantify and estimate the New Regional Medical Center at various levels of design development. Additionally, they utilized on-screen takeoff to finalize their estimate for their bid proposal. Their process consisted of the traditional methods of plan-document review and cross reference to a cost database of past projects with similar components. Although utilizing a technology platform to develop the QTO, all quantities had to be manually counted and measured within each PDF sheet. Once completed, this data was exported into excel, and cost information was embedded per line item to reach their cost estimate. Although logical and accurate, this process can be refined by taking advantage of the capabilities of the 3D models built to produce the 2D plan construction drawings.

The Building Information Modeling (BIM) implementation on the pre-construction and construction of this project was minimal; however, the model created by the design teams was sufficient for various uses during structural estimating. This analysis will study the usability in the level of detail (LOD) and information embedment within the components modeled in the structural design. A 3D QTO and database-referenced estimate will be performed, and the results of material costs and time duration to perform the analysis will be recorded. These results will be compared with Gilbane's process, and the schedule of values recorded to construct the system. Additionally, a comparison will be made to previous thesis investigations on BIM estimating to reflect any industry growth or process development over the past four years.

BACKGROUND INFORMATION

In 2009, construction management student Ralph Kreider proposed the concept of BIM in Estimating during his final report. The analysis within this report focused on the comparison of three methods of construction estimating for an interior wall assembly: (1) Manual/Traditional Methods, (2) Revit-Based Methods, and (3) Autodesk Quantity Takeoff. The results provided recommendation that the Revit-Based Method for material scheduling and quantity takeoff is the most efficient, reducing the duration to perform the exercise by 20 percent, and resulting within 1.5 percent of quantities and cost from the actual manual takeoff methods. Outcomes resulted in the directive that "construction firm[s] should begin to invest time and money into the gained efficiency of automated takeoff" (Kreider, 2009).

Later that month, Engineering News-Record released an article regarding the transformation of BIM Pilot programs during the preceding 4 years. The goal of these programs were to "improve multidisciplinary drawing coordination, [and] streamline estimating," in addition to others processes. A discussion point of the article address the concern impacting the estimating workflow, with the contractors estimating the work, disjointed from outlining the level of detail necessary in the model components to accurately estimate the work (Post, 2009).

In 2010, construction management student Ronza Abousaid also implemented the concept of Revit-Based estimating within his final report. The analysis within this report focused on both industry insight and the comparison of two methods of construction estimating for an exterior curtain wall assembly: (1) Manual/Traditional Methods, and (2) Revit-Based Methods. The results of the research also recommend that Revit-Based Methods eliminate calculation errors during quantification of areas and lengths. Although



computer software such as Autodesk Quantity Takeoff or Acrobat Professional can scale drawing and make measurement, Revit-Based Methods also reduce counting errors. Implementation concluded that Revit-Based Methods reduced the duration to perform the exercise by 89 percent; however, the results produced a cost, which was below the manual takeoff by 24 percent. Outcomes resulted in the directive to continue to pursue the development and understanding of the capabilities and limitations of 5D modeling. The analysis concluded with a caveat, stating "to benefit from the time savings of model-based cost estimating, it is important for an Owner to clearly state the intent of releasing the 3D modeling [as the basis for estimating] in a contractual format with the designers" (Abousaid, 2010).

The 20th Annual PACE Roundtable took place on November 9, 2011, and brought students and industry members to discuss this year's theme of "Building Innovation into Practice: Keeping what Works." Using student-based research goals after a recap of implementation of BIM tools and technology over the past year, the following was determined a key takeaway from the program.

- Continue to compare the use of BIM tools (or technology) to traditional methods of project estimate development. Focus on concepts such as: system appropriateness, process execution, time savings, and cost accuracy, relative to traditional methods.
- Study the positive and negative effects of implementation and the added (or lost) value of its use.

On March 12, 2012, *Engineering News-Record* released industry responses to a survey they developed regarding the current state and outlook of technology implementations. The second most common statement focused on data integration with BIM, notably regarding estimating and schedule from the model. This response trailed the number one response, shortfalls in current software products. Notable concepts in which it beat out revolved around collaboration (3rd), cloud storage (5th), tablet PCs (10th), and BIM training (13th).

"THE CONSTRUCTION INDUSTRY SHOULD FOCUS LESS ON PERCEIVED NEEDS FOR NEW TECHNOLOGY AND MORE ON HOW TO WORK WITH WHAT IT HAS." *Ray Chen, Faith Technologies*

ANALYSIS INFLUENCES

- Development of details and parameters included in modeled components.
- The accuracy of the cost database referenced.
- Ability to interpret modeled data and adjust for gaps of inadequate information.



METHODOLOGY

- (1) Open structural model in Revit and view the model in a 3D template.
- (2) Create a material takeoff using the "Schedules & Quantities" feature.

Category:		Name:
CMulti-Category> Areas (Gross Building) Areas (Rentable) Assemblies Casework	* III	Multi-Category Schedule Schedule building components Schedule keys
Ceilings Curtain Panels Curtain Systems Curtain Wall Mullions		Key name: Phase: Future
Bectrical Equipment Bectrical Fixtures Floors	Ŧ	
Show categories from all dis	ciplines	

FIGURE 10: STEP 2 - SELECT CATEGORY < MULTI-CATEGORY>

(3) Apply the appropriate fields to the data.

Note: Ensure the cost database pricing relation is compatible with the requested data from the element.

Fields	Filter	Sorting/Grouping	Formatting	Appearance		
Availa	ble fields				Scheduled fields (in order):	
Asse Calc. Com Cont Cost End End End End End End		cription m Reinforcing Dead Live - Total - Dead - Live	Ad	Add> < Remove d Parameter	Category Family and Type Level Count Thickness Material: Volume Material: Area Base Plate WtperFt Pier Size & Material Top of Footing Pier Reinforcing	
	Edit	Delete			Edit De	elete
Selec	t availabl	e fields from:				_
Multi	ple Categ	jories	•		Move Up Move	e Down
		ments in linked files				

FIGURE 11: SELECT NECESSARY FIELD REFERENCES PER MODELED COMPONENT

(4) Apply the appropriate grouping elements to the data.

Fields Filter So	ting/Grouping Formatting Appearance
Sort by:	Category
Header	Footer:
Then by:	Family and Type
Header	✓ Footer: Title, count, and totals ✓ Blank line
Then by:	Level
Header	Footer:
Then by:	(none)
Header	Footer: Blank line
Grand totals:	Title, count, and totals
🔽 Itemize every in	stance

FIGURE 12: STEP 4 - SELECT NECESSARY GROUPING STRATEGIES

(5) Review the schedule for formatting updates.

Category	Family and Type	Level	Count	Thickness	Material: Volume	Material: Area	Base Plate	WtperFt	Pier Size & Material	To
Floors	Floor: 1 1/2" 22 Ga. Metal Roof Deck	CANOPY	1		187.48 CF	1500 SF				
Floors	Floor: 1 1/2" 22 Ga. Metal Roof Deck	CUP MEZZANINE	1		50.56 CF	405 SF				
Floors	Floor: 1 1/2" 22 Ga. Metal Roof Deck	Penthouse	1		1553.01 CF	12424 SF				1
loors	Floor: 1 1/2" 22 Ga. Metal Roof Deck	Penthouse	1		591.25 CF	4730 SF				1
loors	Floor: 1 1/2" 22 Ga. Metal Roof Deck	Penthouse	1		2291.16 CF	18329 SF				
loors	Floor: 1 1/2" 22 Ga. Metal Roof Deck	ROOF	1		334.82 CF	2679 SF				
loors	Floor: 1 1/2" 22 Ga. Metal Roof Deck	ROOF	1		261.23 CF	2090 SF				1
loors	Floor: 1 1/2" 22 Ga. Metal Roof Deck	ROOF	1		32.30 CF	258 SF				1
loor: 1 1/2" 22 Ga.		32	·	12353.56 CF	98828 SF					
loors	Floor: 1 1/4"x3/16" GRATING	1st Floor	1		10.93 CF	105 SF		1		T
loors	Floor: 1 1/4"x3/16" GRATING	3rd Floor	1		3.80 CF	37 SF				1
loors	Floor: 1 1/4"x3/16" GRATING	CANOPY	1		12.33 CF	118 SF				1
loors	Floor: 1 1/4"x3/16" GRATING	CANOPY	1		12.33 CF	118 SF				1
loors	Floor: 1 1/4"x3/16" GRATING	CANOPY	1		4.59 CF	44 SF				-
loors	Floor: 1 1/4"x3/16" GRATING	CANOPY	1		3.05 CF	29 SF				-
loors	Floor: 1 1/4"x3/16" GRATING	CANOPY	1		32.66 CF	314 SF				1
loors	Floor: 1 1/4"x3/16" GRATING	CUP MEZZANINE	1		12.26 CF	118 SF				-
loors	Floor: 1 1/4"x3/16" GRATING	GROUND FLOOR	1		87.27 CF	838 SF				-
loors	Floor: 1 1/4"x3/16" GRATING	Low CUP	1		8.86 CF	85 SF				-
loor: 1 1/4"x3/16" (GRATING: 10		10		188.08 CF	1806 SF				-
loors	Floor: 2 1/2" NW Concrete on 1 1/2" Composite Metal Deck	1st Floor	1	1	0.00 CF	320 SF		1		1
loors	Floor: 2 1/2" NW Concrete on 1 1/2" Composite Metal Deck		1		106.70 CF	320 SF				
loors	Floor: 2 1/2" NW Concrete on 1 1/2" Composite Metal Deck	1st Floor	1		0.00 CF	184 SF				-
loors	Floor: 2 1/2" NW Concrete on 1 1/2" Composite Metal Deck	1st Floor	1		61.26 CF	184 SF				-
loor: 2 1/2" NW Cor	crete on 1 1/2" Composite Metal Deck: 4		4		167.96 CF	1008 SF				-
loors	Floor: 3 1/4" LW Concrete on 3" Composite Metal Deck	1st Floor	1		0.00 CF	23638 SF		1		-
loors	Floor: 3 1/4" LW Concrete on 3" Composite Metal Deck	1st Floor	1		12311.69 CF	23638 SF				1
loors	Floor: 3 1/4" LW Concrete on 3" Composite Metal Deck	1st Floor	1		0.00 CF	13365 SF				
loors	Eloor: 3 1/4" I W Concrete on 3" Composite Metal Deck	1st Floor	1		6960 93 CE	13365 SE				

FIGURE 13: STEP 5 - SCHEDULE REVIEW

- (6) Export Schedule in Delimited Text (*.txt) format.
- (7) Open File via Microsoft Excel.



- (8) Format the appearance & break apart the schedule as desired. [Family, Discipline, etc.]
- (9) Simplify & Summarize groupings and families as desired.

Note: Formatting of the table must be considered before and after export. It is best practice to use decimals and remove units within all number-based parameters in order to simplify calculation processes within Excel.

(10) Create Columns for Material, Labor, Equipment, and Total equivalent costs.

SI Number Family : Quantity	Measured Units	Total Units	Weight (Tons)	Material	Labor	Equipment	Total	Material Cost	Labor Cost	Equipment Cost	Total Cost
05 12 23.40 Lightweight Framing											
C10x25: 64	837'- 4 9/16"	20925	10.46727								
600 Channel framing, 8" and larger	25 lb/lf	LBS		0.64	8 2.36	50.	22 3.26	\$ 14,229.00	\$ 49,383.0	0 \$ 4,603.50	\$ 68,215.5
C12x30: 6	76'7 11/16"	2299.172	1.149586								
600 Channel framing, 8" and larger	30 lb/lf	LBS		0.68	8 2.30	50.	22 3.26	\$ 1,563.44	\$ 5,426.0	5 \$ 505.82	\$ 7,495.3
ž3x3x3/8: 29	131'-0 15/16"	131	0.471885								
476 Angle 3"x3"x3/8"		LF		4.8	5 20.5	51.	.91 27.27	\$ 636.66	\$ 2,685.5	0 \$ 250.21	\$ 3,572.3
ž3x3x5/16: 2	7'-0 7/8"	7	0.021213								
476 Angle 3"x3"x3/8"		LF		4.8	6 20.5	51.	.91 27.27	\$ 34.02	\$ 143.5	0 \$ 13.37	\$ 190.8
ž4x4x3/8: 21	188'- 6 9/16"	1828.888	0.914444	1							
400 Angle Framing, 4" and larger	9.7 lbs/lf	LBS		0.65	5 2.65	э 0.	25 3.59	\$ 1,188.78	\$ 4,919.7	1 \$ 457.22	\$ 6,565.7
ž6x4x5/16: 2	8' - 9 1/2"	90.538	0.045269								
400 Angle Framing, 4" and larger	10.3 lbs/lf	LBS		0.65	5 2.69) 0.	25 3.59	\$ 58.85	\$ 243.5	5 \$ 22.63	\$ 325.0
MC12x31: 10	249' - 1 7/8"	7722	3.861886								
600 Channel framing, 8" and larger	31 lb/lf	LBS		0.6	8 2.36	5 0.	22 3.26	\$ 5,250.96	\$ 18,223.9	2 \$ 1,698.84	\$ 25,173.7
05 12 23.40 Lightweight Framing								\$ 22,961.70	\$ 81,025.22	2 \$ 7,551.59	\$ 111,538.52
03 31 05.70 Placing Concrete											
GB 30"x32": 1	4.16 CY	4.16	NA								
150 3000 psi		CY		99	9		99	\$ 411.84	\$ -	\$.	\$ 411.8
3200 Grade Beam, direct chute		CY			11.4	5 0.	31 11.76	\$ -	\$ 47.6	3 \$ 1.29	\$ 48.9
03 31 05.70 Placing Concrete								\$ 411.84	\$ 47.6	3\$ 1.29	\$ 460.7
03 21 10.70 Glass Fiber Reinfornced Polyn	ner Bars			•							
Round Bar 1": 53	1531'-9 9/16"	1532	c)							

FIGURE 14: ESTIMATING SPREADSHEET

(11) Total by Family, CSI Family, and report findings for comparison.

See **Appendix F** for a process map for the execution of 5D Estimating in this analysis.

OUTCOME

Using the BIM model developed through the design, fabrication, and installation of the structural system in the medical center, an accurate structural estimate was procured for the entire structure. With a single pass through the model, multiple material schedules were developed and exported into Excel for data management and cost incorporation from *RSMeans Facility Construction Cost Data 2011*.

According to discussion with Gilbane's estimating team, the structural system estimate on the New Regional Medical Center took a team of four members approximately 20 hours each, to complete the estimate. The acquired estimate value by Gilbane totaled to \$19,890,000. Once construction was completed on the structure, the schedule of values resulted in a cost of \$5,642,000 for the concrete system, and \$7,672,000 for the metals system, totaling to \$13,314,000

The original detailed estimate, through the utilization of modeled components, resulted in a cost of \$9,155,687. Once the location factor¹ was applied, a more appropriate estimate of \$10,190,280 was achieved.

¹ Location factor #194 is applied to the RSMeans data in order to produce a more accurate estimate to the geographic location of the project. Within the appendix of the RSMean catalog, location factors by city and state are listed. The value



This value is 23.46 percent short of the actual project cost, as identified through the schedule of values released for the work. This process took 10 hours to complete, including the formatting, research, and input of the RSMeans data into the quantity takeoff tables which consisted of over 5,000 components.

Reflecting on the results of the current state of the analysis, a 23.46 percent short is unacceptable to suggest further research and development of this BIM tool. After reviewing scheduled quantities, and RSMeans data for accuracy, it was confirmed that a "blind" release of modeled component into a cost database matrix to gather an estimate is impractical. With further investigation and application of the information gathered from (1) the original estimating process, (2) bid packages development, and (3) the components included and excluded from the related scopes of work, a hybrid estimating process was implemented.

CONSIDERATIONS FOR REEVALUATION

In light of inaccuracies in comparison to the original estimate values and the schedule of values produced during construction for the New Regional Medical Center, modifications to the derived values are outlined in the following section. The bases for modifications include elements which were not included in the model, or are unable to be attributed or entered as a modeled parameter. These values were derived off of the schedule of values in order to accurately incorporate the material, equipment, labor costs into the bid package's scope of work, permitting compatible comparisons. It is recognized below that implementation of a hybrid estimating program which incorporates both model-based data and on-screen (or by-hand) takeoffs still produces variable results, depending on the building system.

Table 5 includes the breakdown of the outcomes of this analysis. Note that due to the adjustments made within the hybrid estimate concept, (1) means and methods, (2) non-modeled elements, (3) inaccurate modeled elements, (4) overhead and services, and (5) design-alternate can be incorporated into the final number, producing a much more accurate and usable result.

CONCRETE HYBRID ESTIMATE

Original: CIP Concrete [\$2,466,807]

Adjust 5D estimate to reflect the following additions/subtractions as noted:

- Stone Sub Base for SOG: +\$109,559
- Vapor Barrier: +\$25,851
- Concrete Curbs: +\$37,538
- Concrete In-Fill Stairs: +\$12,000
- Site Retaining Walls: +\$634,998
- Concrete Sealer: +\$5,460
- Housekeeping Pads: +\$112,500
- Surveying/Layout: +\$200,000
- General/Daily Cleanup: +\$142,000
- Reinforcing Steel: +\$523,998

obtain for Norristown, PA is 111.3, and is the multiplier for the total cost and cost per square foot. This value is then divided by 100 per RSMeans directions in order to adjust the costs back to the baseline factor of 100/100. Original Values: Concrete [\$2,466,807], Metals [\$6,688,880].



Modified: CIP Concrete [\$4,270,711] Location Factor: [\$4,270,711] * [111.3/100] = \$4,753,301 Sales Tax: 6% = \$285,198

TOTAL: CIP Concrete [\$5,038,499]

STEEL HYBRID ESTIMATE

Original: Structural Steel [\$6,688,880]

Adjust 5D estimate to reflect the following additions/subtractions as noted:

- Mobilize: +\$60,000
- Scaffold Stair System: +\$72,500
- Reinforcing Steel: -\$523,998
- Precast Connections: +\$164,000
- Surveying/Layout: +\$25,000
- General/Daily Cleanup: +\$49,000

Modified: Structural Steel [\$6,535,393] Location Factor: [\$6,535,393] * [111.3/100] = \$7,273,892 Sales Tax: 6% = \$436,434

TOTAL: Structural Steel [\$7,710,326]

TABLE 5: 5D ESTIMATING COMPARISONS

	Compari	son Table 5D Estimatin	g	
Bid Package	Component	Component Cost		Difference from SOV
	System Estima	ate Costs (Provided by Gi	lbane)	
03A	CIP Concrete	\$5,959,569	\$16.25	+5.63%
05A	Structural System	\$8,345,697	\$22.75	+8.78%
		\$14,305,266	\$39.00	+7.45%
	Modified	Estimate from 5D Proce	SS	
03A	CIP Concrete	\$5,038,499	\$13.74	-10.70%
05A	Structural System	ctural System \$7,710,326		+0.50%
		\$12,748,825	\$34.76	-4.25%
	Schedule of	Values (Provided by Gilb	ane)	
03A	CIP Concrete	\$5,642,000	\$15.38	
05A	Structural System	\$7,672,000	\$20.92	
		\$13,314,000	\$36.30	

See **Appendix G** for the summation of each modeled element family associated with the structural estimate.



CONCRETE MODEL-BASED DISCREPANCIES

REINFORCEMENT QUANTIFICATION

Concrete reinforcement metadata within the modeled concrete elements do not output a quantity into the material schedule created through the 3D export process. The output of this information is merely the tag embedded as a parameter depending on how the element was created during design. The resulting data only forecasts bar quantities and sizes, and does not include relevant lengths. Due to this, most of the resulted data concerning reinforcing is handled exactly the same as if it is performed as a traditional-estimate takeoff. In lieu of this, the accuracy of reliance on the model to produce quantities becomes invalid.

Gilbane's Estimate for Reinforcing Steel: \$523,998 5D Estimate for Reinforcing Steel: \$354,956

Discrepancy: \$169,042 [-32.26%]

The reinforcing component estimated values have been supplemented with information provided by Gilbane, due to significant discrepancy and inconsistencies in model output. At this time, there is not a process to extract accurate reinforcing elements based off of the methods the information was embedded within the structural model for the New Regional Medical Center.

VOLUMETRIC CALCULATIONS

Concrete volumes and square footages did no calculate on some components. Although located and reviewed within the model, it is unknown why the information did not translate. The instances did transfer into the quantity schedule. Recognition of this permitted the errors to be quantified through the traditional method; however, these values remain excluded from the model-specific estimate to validate 3D Estimate capabilities.

Due to this occurrence, these components are not included in the model-specific estimate, and have been omitted from the estimate tables and QTOs included within this report.

FORMWORK SQUARE FOOTAGE CALCULATIONS

Concrete formwork and square footage values are not associated within the parameter values of the modeled elements; therefore, an estimate for these components is excluded from the concrete CIP total. It is unknown if it is possible to attribute related formwork systems into different component types through parametric properties with Revit.

Due to this occurrence, these components are not included in the model-specific estimate, and have been omitted from the estimate tables and QTOs included within this report. It is believed that exclusion accounts for a majority of the 10.70% discrepancy.

POTENTIAL FOR PERSONNEL COST SAVINGS

It is recognized that a 3D QTO process, with cross reference to a database for the estimating process has the potential to create more efficient QTO's for counted or calculated elements. Concurrently, this efficiency can be applied against personnel rates to demonstrate cost savings against the pre-construction budget for Gilbane.



Estimating Personnel: \$127 / HR Estimating Team: 4 members Traditional Estimating Timeframe: 4 team member, 20 Hours each [\$10,160] 5D Estimating Timeframe: 1 team member, 16 Hours [\$2,032]

Potential Cost Savings: \$8,128 [64 Hours] Potential Cost Savings per 10,000 Square Feet: \$2.21 [0.17 Hours]

This savings can directly be applied to reduce the budget for the pre-construction activities, or application towards time and estimating efforts for more complex and detailed systems within the facility.

Reflection

It is believed that this analysis will expose new opportunities for model information usage for the structural system of the New Regional Medical Center and upcoming projects for Gilbane and other firms. This analysis identifies the current state, growth, and continued potential of leveraging BIM within preconstruction and construction estimating.

Although there is deviation from the actual value, the amount of time saved in utilizing a model for takeoffs permits a greater level of attention to the details and the constructability of the project. In addition to this, cost savings due to a more efficient estimate process can assist in development of cost estimation modeling training, or funding of Autodesk program licenses to access and perform the task. Through performance of traditional method estimating, while concurrently producing a 5D estimate on available model components, a comparison log permits a stronger understanding of the correlation of model detail and component parameters, with an accurate estimate. Additionally, a firm can also develop cross-referencing strategies to supplement traditional method estimating for systems that are more complicated.

Moving forward, this analysis, along with previously developed reports, continues to demonstrate the capabilities and risks of 5D modeling. Additionally, they feature both the shortcomings and growth of the process since its initiation, as shown in Figure 15. It is recommend that firms begin using 5D estimating for the basis of structural steel bid packages (Nahas, 2012) and interior partition bid packages (Kreider, 2009), and supplement this process, with traditional methods in order to align modeled components with the scope of work, or account for details not included with the model. Additionally, it is recommended that companies continue internal research in Revit-Based Methods concurrent to traditional estimating practices on more complicated modeled systems, such as concrete (Nahas, 2012), and curtain wall systems (Abousaid, 2010). Through implementation and continued development, construction firms can provide input and monitor design firms' evolution towards transferrable parameters and modeled features into an estimating matrix.






FIGURE 15: RESEARCH RESULT TREND VS. SYSTEM IN 5D ESTIMATING



PART B: CRANE PLANNING & LOGISTICS

PROBLEM IDENTIFICATION

Gilbane utilized a traditional process and minimal software platforms to identify and select the appropriate steel erection logic for the New Regional Medical. Their process consisted of the review of the structural engineer's plan-documents and cross reference to a database of past projects. Although utilizing of the traditional method produces an accurate crane size, and correctly locates crane pick logistics, there is no basis to identify any trending data for the location and frequency of the critical picks for the structural steel frame. It has been recognized that for the duration of the project, the crane on site was oversized; however, due to the erection sequence determined for the project, there was no ability to downsize the crane for cost savings.

This analysis will investigate the usability in the information embedded within the components modeled in the structural design to visualize erection workflow options. A structural steel erection workflow analysis will be performed, and the results of the recommended workflows relative to crane size optimization will be recorded. These results will be compared with Gilbane's process, and the crane rental expenses of the processes. Additionally, an overview of different program approaches and limitations will be developed, reflecting industry challenges and barriers to this investigation.

BACKGROUND INFORMATION

This analysis will research and develop the process to retrieve embedded information to develop a structural steel estimate, identify the location of critical-pick steel members, and develop a logistics plan for the structural steel erection phase of construction at the New Regional Medical Center.

The second technology break-out session of *The 20th Annual Pace Roundtable*, titled "Strategies and Opportunities for Taking BIM into the Field" focused on the benefits of BIM in the field and developing field logistics. Overall, comments reflected on technology training and generation gaps typically found within the industry, and the challenges to overcome 2D versus 3D communication. Although many industry member comments were in full support of implementation strategies, risks associated with legal concerns, file exchanges, and document standards on BIM models were voiced. Notable issues arose with discussion around model Ownership and model sharing. Sharing models and information tools have developed to permit levels of access from owning, editing, viewing, to excluding. With hopes to mitigate and manage document controls, a higher level of confidence is instilled.

At the conclusion of the session, multiple recommendations were made by industry professional concerning potential research ideas. 3D and 4D crane logistics workflows were proposed during the break-out session, and developed through discussion after the conclusion of the PACE Roundtable. The following section outline the methodology designed though research and industry discussion.

ANALYSIS INFLUENCES

- Locating details and parameters included in modeled components.
- The interoperability of project data into various software platforms.
- Ability to interpret modeled data within the software and create a visual representation.



- Alternative methods to visualize outcomes if document data exchange method is not supported.

Methodology

ACCESSING EMBEDDED STEEL PARAMETERS

- (1) Create Structural Column Schedule
 - a. Fields Required: Family, Type, Column Location Mark, Top Level, Wt/ft, Length
- (2) Access Schedule Properties
 - a. Add Calculated Value (weight-Tons), Formula: WtperFt*Length/1'/2000, add to Fields
 - b. Select the Sorting/Grouping Tab, and sort by weight (tons) descending.
- (3) Repeat Step 1 & 2 for Structural Framing Schedule

UPDATING THE 3D MODEL TO RENDER COLORS RELATIVE TO STEEL MEMBER'S TOTAL WEIGHT

- (4) Open the {3D} View
 - a. Highlight all, Override graphics in view to White, Solid.
 - b. Leave non-structural elements in the model.
 - i. These elements are boundaries to crane placement, however, hide the floors.
- (5) Open One of the newly created schedules
 - a. Locate Structural members over 10 Tons,
 - i. Highlight rows in Schedule, and click "Highlight in Model".
 - ii. Once in Model, right click and select override graphics in view by element
 - 1. change surface pattern:
 - a. Over 10 Tons to RED, Solid.
 - b. 5 10 Tons to ORANGE, Solid.
 - c. 3 5 Tons to YELLOW, Solid.
 - d. 1-3 Tons to CYAN, Solid.
 - e. 0.5 1 Ton to GREEN, Solid.
 - f. Below 0.5 Tons, Ignore and leave as white elements.
 - b. Repeat Step 10a for the other schedule.

EXPORTING THE VIEW

- (6) Duplicate 3D View with Detailing
 - a. Open {3D} Highlight All, Override Graphics, NONE
 - b. Rename Copy of {3D} to "Structural Member Weight (Ton) Analysis.
- (7) Export to SKP
 - a. Revit Export>Options>Setups DWG/DFX
 - i. Layers (Export all BYLAYER, and create new override)
 - ii. Colors (Index Color)
 - iii. Solids (ACIS Solids)
 - b. Export.CAD Formats>DWG, Next... Save.

Note: at this point in the methodology, Sketchup, nor other software platforms, were not able to load the overridden colors applied to the view in Step 5. The only export file which was readable with the overridden



colors was (.DWF). Unfortunately, this file format prevents the elements from being edited or manipulated in any other way, and is considered a "Read-Only" format. Figure 16 is a visual demonstrating the export format.




FIGURE 16: DWF MODEL OF CRANE ANALYSIS COLOR ATTRIBUTING

IMPORTING INTO SKETCH UP

- (8) Sketchup Pro>Import>Select File...
- (9) Group modeled components per the Erection Plan Phases
 - a. Assign each group to a Layer, identifying phase sequence within the name
- (10) Logically walk though each erection phase by turning on each layer
 - a. Within each phase, recognize the heaviest member based on the color scale.
 - b. Locate possible crane placement paths, and measure linear distance between
 - c. Identify shortest logical location & make mark
 - d. From radius (linear distance), sketch necessary lines to identify crane sizing parameters
 - e. Reference crane load chart and select crane size
- (11) Repeat for each progressive phase



- a. Note that it is appropriate to assume the same crane size as a starting point in identifying location of crane; however, keep in mind, a smaller crane option may be available for the phase at hand.
- (12) Review crane selection outcomes and optimize logistics to meet safety, financial, and schedule requirements of the project. Insert appropriate crane model if utilizing 4D model.
- (13) Export out of Sketchup via IFC File type, if utilizing 4D model.

IMPORTING INTO SYNCHRO

- (1) Import the IFC File into Synchro
- (2) Sequence the model to the schedule via the provided erection zones, or appropriate subsets.
- (3) Have active timeline color remain in the gradient color scheme, and override old phases to be shown as grey elements.

-Alternate process if 4D model already exists-

(4) Load process or Crane Models from Sketch Up into existing 4D model to verify workflow logic with rest of site activities.

INTEROPERABILITY ISSUES

In the March 2012 issues of Modern Steel Construction, an in-depth review covered the steel industry's migration to IFC file structure. The goal of this conversion is to increase interoperability of steel models as open-source files which permits translations across multiple software platforms used within the industry.

"SIMPLISTICALLY THE IDEA WAS THAT IF TWO SOFTWARE PRODUCTS FULLY ADOPTED THE SCHEMA, THEN THE END USER COULD SIMPLY PRESS A BUTTON TO EXCHANGE DATA AND IT WOULD BE 100% CORRECT." CHRIS MOOR, AISC DIRECTOR OF INDUSTRY INITIATIVES

The article, titled "Interoperability for Construction" proceeds to talk about the limitations and barriers to open standards and proprietary data within software vendors. It has been recognized that due to need to maintain a competitive edge in the market, the software will never exchange data as easily as the users would prefer. However, it was noted that as long as limitations and the elements of propriety data are known, solutions can be found.

"AT EACH EXCHANGE POINT A THOROUGH UNDERSTANDING IS NEEDED OF WHO IS INVOLVED, WHAT SOFTWARE IS INVOLVED, AND WHAT DATA NEEDS TO BE EXCHANGED (OR CAN BE EXCHANGED) AND WHAT THE DATA WILL BE USED FOR." Luke Faulkner, AISC Director of Information Technology Initiatives

Currently, new workflows and processes need to be recognized, along with the shortfall of information exchange, in order to appropriately realign modeling and software standards and interoperability. This analysis is a perfect example which details "the reality [...] that the broader construction industry has become



BIM-hungry and as its capacity to utilize BIM has grown, so too have the expectations of what data it expects to be able to access" (Moor & Faulkner, March 2012).

"IN THE END, OUR GOAL IS TO PROVIDE A SERVICE TO THE INDUSTRY SUCH THAT USERS CAN ENTER A FEW PIECES OF INFORMATION ABOUT THEIR ROLE, SOFTWARE AND THE DATA THEY WISH TO EXCHANGE AND IN RESPONSE WILL OBTAIN A RECOMMENDATION FOR HOW BEST TO ACHIEVE THE EXCHANGE." *AISC Initiatives*

In light of growing interoperability concerns identified by software providers and end users, an Open BIM Program has been developed as of March, 13, 2012. This program was established through a joint effort of leading software vendors in order to launch a "global program to help promote Open BIM collaboration workflows throughout the AEC industry" (buildingSMART International Ltd., 2012).

"OPEN BIM PROGRAMME IS A MARKETING CAMPAIGN INITIATED BY GRAPHISOFT®, TEKLA® AND OTHER MEMBERS OF BUILDINGSMART® TO URGE AND FACILITATE GLOBALLY COORDINATED PROMOTION OF THE OPEN BIM CONCEPT THROUGHOUT THE AEC INDUSTRY, WITH ALIGNED COMMUNICATION AND COMMON BRANDING AVAILABLE TO PROGRAMME PARTICIPANTS." BUILDINGSMART

Although in its inception, this concept further presses the importance of identifying intended workflows, BIM processes, and the expectations of data exchange through software platforms. Although this analysis has identified limitations in software exchange, it has assisted in bringing to light the current state of the industry's efforts of create solutions and developing more efficient processes. In response to buildingSMART press release, Michal Wojtak, Integrated Construction Manager at Mortenson Construction agreed, stating "I believe this is one of the most important standards to tackle, considering how many challenges we currently encounter in data exchange just between the Autodesk products." He continued, "Unfortunately, the original partnership of Open BIM does not include Autodesk, but hopefully this strategy creates competitions to make the products and processes better, and not continue to isolate data exchanges processes by software providers" (Wojtak, Integrated Construction Manager | Mortenson Construction, 2012).

PivotTable Field List

V Family

V Type

Level
Elevation

WtperFt

Length
Weight (Tons)

Sector

Family

Туре

Level

Elevation

Sector

Choose fields to add to report:

Column Location Mark

***** ×

G •

ALTERNATE PROCESS

In lieu of the current state of the document exchange regarding the efforts of this analysis, an alternative method of structural steel workflow planning for the New Regional Medical Center's site logistics and crane selection process has been developed. This alternative process takes advantage of readily available and exportable data from the 3D structural BIM model, and organizes the information is a way for visual analysis and interpretation of construction workflow based off of trends in structural steel tonnage by member.

METHODOLOGY

ACCESSING EMBEDDED STEEL PARAMETERS

- (1) Create Structural Column Schedule
 - a. Fields Required: Family, Type, Column Location Mark, Top Level, Wt/ft, Length
- (2) Access Schedule Properties
 - a. Add Calculated Value (weight-Tons), Formula: WtperFt*Length/1'/2000, add to Fields
 - b. Select the Sorting/Grouping Tab, and sort by weight (tons) descending.
- (3) Repeat Step 1 & 2 for Structural Framing Schedule

EMBEDDING STEEL LOCATION AND PROJECT SECTOR

- (1) Open one of the 3D Model views
 - a. Duplicate with detailing and update the Visual Graphics to only display Structural Steel members (including Beam and Columns).
- (2) Change the view point to a plan view of the 3D Model, utilizing the ViewCube
- (3) Highlight the elements based off of the building Key (or Sector) Map provided with the drawings.
 - a. In the properties window, select one of the element categories.
 - i. In the "Comment" field, enter the Sector number or letter.
 - ii. Repeat for other element categories which were highlighted.
 - b. Repeat this process for all of the building sectors.

DEVELOPING THE MATERIAL TAKEOFF SCHEDULE

- (1) Follow the guidelines provided in Analysis 1: Part A Methodology to create the schedule for all of the structural steel components within the model.
- (2) In addition to the fields provided, also include the "Comments" field, as this will provide directive for the sector or region the member is located within.
- (3) Export the Schedule.

DEVELOPING THE PIVOT CHART

(1) Import the data into Microsoft Excel, and place the related tables CONFIG

FIGURE 17: PIVOTTABLE FIELD CONFIGURATION

Drag fields between areas below:

Ŧ

Axis Fields (Ca... Σ Values

Ŧ

Legend Fields .

Max of Weigh... 🔻



within their own worksheet.

- (2) Create three additional sheet, labeled "Pivot Chart," "Pivot Table," "Merged Data."
 - a. If the "Reference Level" line item of the exported schedule provided specific labels for "First Floor," "Second Floor," etc. Create a fourth sheet, permitted a VLOOKUP command, which will update the data extracted from the model and replace the values with the proper elevations. This method provides a stronger understanding of the height of steel.
- (3) Update the Data for Reference
 - a. In the "Merged Data" table, copy and paste the data from the exported model schedule.
 - b. Add an additional column to provide the VLOOKUP function to reference elevation heights.
 - c. Format the data using "Format as Table."
 - d. If interested, apply "Conditional Formatting" to particular columns of interest.
- (4) Create the Pivot Chart
 - a. Select a cell within the "Merged Data" table
 - b. Select "Insert" "Pivot Table" "Pivot Chart"
 - i. Place this chart within a new sheet.
- (5) Apply the Filter Parameters
 - a. Reference Figure 17 to identify the placement and logic of the PivotTable fields.
- (6) Update the Summation Field to identify the "Maximum" steel weights per filter parameter.
 - a. Right click on the Field, and select "Vale Field Settings"
 - b. Change the "Summarize value field by" to "Max"
- (7) Revise the graphical representation, colors, and chart setting to provide a stronger visual.

INTERPRETING THE PIVOT CHART

(1) When visualizing the initial data per the Field Table Field List provided in the previous section, the following image depicts the outcome.




FIGURE 18: CRITICAL PICK WORKFLOW - TRENDING BY ELEVATION [SEE APPENDIX H FOR FULL SCALE]



(2) Reversing the order of the "Axis Fields" within the Field Table Field List provides an alternative visual.




FIGURE 19: CRITICAL PICK WORKFLOW - TRENDING BY SECTOR [SEE APPENDIX H FOR FULL SCALE]

Ουτсоме

Figure 18 and Figure 19 display the two-workflow options available at the New Regional Medical Center. As this site is a greenfield project, with an open landscape surrounding the steel erection process for the facility, this interpretation process is beneficial to identify structural steel tonnage trends in order to properly sequence the erection process in order to optimize the crane capacity present on site, and minimize costs.

Figure 18 represents the workflow conducted by Gilbane at the New Regional Medical Center. This figure represents the structural steel erection workflow moving vertically, erecting the facility by sector, but only up until the column splice. Once each column splice was reach, the remaining sectors were also built to that elevation. This figure represents the requirement to keep a larger crane on site, as multiple lifts consists of steel over 17.5 tons at both the first floor and the third floor, which occur in different column lift sequences. Figure 18 highlights the efficiency of having a single crane on site, through analysis of a horizontal trend line. This efficiency focuses on having a single high-tonnage rig on site during the entire erection program minimizing the overhead costs of setup and breakdown, in addition to the delivery of multiple crane systems. However, this chart also displays the fact that there were only 7 instances out of 30 where a non-typical lift occurred, and the crane was sized to these cases. Due to this, the crane was oversize 77% of the project, and applying much higher rental expenses into the project's budget.

Figure 19 represents an alternative workflow for the project. This chart represents the structural steel erection workflow moving by sector, and completing the entire elevation's structural frame, moving onto the next sector. This figure represents the requirement to keep a larger crane on site, as multiple lifts consists of steel over 17.5 tons at both the first floor and the third floor, which occur in different column lift sequences. Figure 19 highlights the efficiency of having cranes sized to a particular erection sequence, however with a non-



horizontal trend line; it also identifies the risks of having additional expenses for each crane's setup and mobilization. This efficiency focuses on having the highest-tonnage rig on site during only the erection program it is required. With 6 out of 7 non-typical lifts occurring within Sector A, it is sensible to bring in a specific crane for this instance, and remove it from the site after the members are erected. This workflow permits a more cost-effective strategy in the erection process.

COST SAVINGS

CONSTRUCTION BY ELEVATION (LEVEL)

A 300 ton 2250 Manitowoc crane will be placing the critical structural steel members. This truck crane travels around the perimeter of the building per the sequencing narration and the site logistics plans. The complete crane arrived on site via approximately 15 trucks, and is schedule to perform all major lifts for the duration of the project. This 2250 model features a 500 HP engine, a 140 foot boom (6 inserts), and a 60 foot fixed jib attached.

Mobilization & Demobilization Costs: \$9,000 x 2 = \$18,000 Rental Costs: \$20,000 x 18 weeks = \$360,000 **TOTAL: \$378,000**

Concurrently, a 300 ton 2250 Manitowoc crawler will be placing the balance of the structure in addition to the precast facade. This model included a 140 foot boom in addition to a 110 foot luffing jib. As this crane would be present in both workflow cases for a common duration, it has been assumed that any cost savings with a redistribution of the critical pick workflow would be negligible.

CONSTRUCTION BY SECTOR (BAY)

The same crane configuration for the 300 ton 2250 Manitowoc truck crane would be utilized. However, the crane would be required on site for a shorter duration, only required for Sector A and Sector C, and a smaller capacity crane, sized below, will replace it for Sector B and D.

Crane Selection²

The crane selection process consists of two main determinants. These focus on the required lifting capacity of the crane for the heaviest pick at a particular distance and height. Once the crane type and configuration conditions are identified, reference is made to a load chart for the particular model to identify capabilities and final selection. Additional influences to consider include the workflow, base configuration of the crane, the quadrant the lift is occurring within, and the site conditions and necessary preparations for the crane to operate.

Selection for the size-reduced crane will parallel many of the parameters in which the crane selected by Gilbane comparing the alternative workflow derived through this analysis.

² Lecture *Crane Selection* in AE475 [Building Construction Engineering I] on October 7, 2010



(1) Determinants

- a. Workflow: Sector A & B (300 ton), Sector C & D (TBD)
- b. Critical Lifting Weight: 2.3 tons at 29'-4" or 2.5 tons at 14'-8" Elevation
- c. Critical Lifting Reach: 140' Radius in Sector D
- d. Base Configuration: Outriggers of a Mobile Truck Crane
- e. Boom Configuration: Boom and Extension
- f. Quadrant: 360 degrees
- (2) Sizing
 - a. Crane Selection: Grove TMS9000E
 - b. Boom Selection: 110 Feet + 33 Feet Extension with 40' Insert
 - c. Crane Specifications: See Appendix I
- (3) Outcome
 - a. 140' Radius: 5620 tons (less 2 x 1609 lbs for block and tackle) = 2402 lbs
 - b. Require a 142.3 foot boom with 33 foot luffing jib at 5-20 degrees offset

Resultant Costs

Mobilization & Demobilization Costs: \$9,000 x 2 + \$3,400 x 2 = \$24,800 Rental Costs: \$20,000 x 15 weeks + \$5,840 x 3 weeks = \$317,520 **TOTAL: \$342,320**

WORKFLOW REQUIREMENTS

- It is essential to erect the Central Utility Plant first (Located in Sector D)
- Sector A must begin next, as this is the largest quadrant and includes the Atrium

Taking advantage of the greenfield site, a revision to the crane workflow was possible, as there were limited site constraints, in addition to the ability to meet the workflow requirements outlined above. With the ability to visualize structural steel trends, the PivotChart provided an opportunity to develop a more efficient erection program for the New Regional Medical Center. If this site was more restricted, the PivotChart could still be utilized, however the results would have to be evaluated in order to reflect the workflow requirements and limitation of the site.

POTENTIAL FOR SCHEDULE ACCELERATION

In addition to cost savings associated with reducing the crane size, there is potential to sequence the crane logistics and erection schedule to reduce time for erection using two cranes instead of one crane. Figure 20 includes an overview of the two-crane workflow process in correspondence to the updated workflow developed earlier in this analysis.

TABLE 6: PROPOSED SCHEDULE WITH TWO CRANES (VALUES PROVIDED THROUGH GILBANE SCHEDULING)

Sector A	Sector B Sector C		Sector D
2250 Manitowoc	2250 Manitowoc	Grove TMS9000E	Grove TMS9000E
38 Days	34 Day	6 Days	7 Days
15 W	/eeks	3 We	eeks




FIGURE 20: CRANE LOGISTICS - BLUE: GROVE TMS9000E, RED: 2250 MANITOWOC

Following the proposed erection schedule, the governing duration is 15 weeks, which accounts for the combined durations for Sector A and Sector B. The original project schedule following the elevation, lift-based erection plan results in duration of 85 days, or 17 weeks. This revised approach reduces the erection schedule and the total project schedule by 2 weeks, as structural steel erection resides on the critical path of the construction schedule. This results in a cost savings of \$280,047 based on the month general conditions cost outlined previously in this report.

REFLECTION

Due to limitations in software interoperability and data exchange, the key component to identify steel size does not transfer out of Autodesk Revit. At this time, this method is not feasible for crane site logistics as view filters are not transferrable between Autodesk-based formats, nor are they compatible with open source formats. With further development and insight into similar industry initiatives, workflows can be evaluated and revised to meet the developing standards of data exchange between software products.

In lieu of the current state of the document exchange regarding the efforts of the original analysis, the alternative method still provided a strong visualization of the location, height, and weight of the critical picks. Additionally, through the development of this process, trending information that would have been overlooked in the 3D modeled approach were readily present and provided suggesting and inquiries towards optimization of the erection workflow. It was recognized that the workflow process of the structural erection of the New Regional Medical Center contained an oversize crane for 77% of the duration. Through a visual analysis of the data stored within the structural model, a more comprehensive understanding in addition to alternative



workflows are presented, optimizing the logistics, and expenses of cranes during the structural steel erection process. Additionally, a schedule acceleration opportunity was recognized and provided additional costs savings of \$280,047 in general condition costs, in addition to a savings of \$35,680 on crane rental. In total, this analysis identified a new VDC method in order to highlight trending data within a structural steel model, and resulted in a savings of two weeks on the construction schedule, in addition to \$315,727 of the project cost.



ANALYSIS 2 | REDESIGN OF ATRIUM ENCLOSURE PROCESS

PROBLEM IDENTIFICATION

The atrium glazing enclosure is an extremely challenging scope of work at the New Regional Medical Center, as the assembly is entirely stick-built in situ. Additionally, the interior finishes of the atrium are located on the critical path of the project. If any delay were to occur during the assembly of this curtain wall system, potential impacts to temporary heating, interior finishes, and the status of the remaining schedule items would be affected. Due to the potential for delay during the construction process of this system, an alternative system will be designed, permitting prefabrication of the atrium's enclosure components, and a more efficient construction process for the New Regional Medical Center.

Breadth

This analysis will constitute the architectural breadth component of this report, and will involve redesigning the New Regional Medical Center to include elements to improve the constructability of the atrium's curtain wall glazing system, in addition to the inclusion of public space, which looks out onto the surrounding property and into the neighboring Norristown Farm Park. Associated with this architectural redesign, the unitization of the curtain wall glazing components will be addressed. These efforts will include the modularization and prefabrication of the glazing units in order to reduce costs and project schedule. Additionally, the goal of the breadth is verify the benefits of the redesign in comparison to the existing design of this space regarding quality, safety, and construction logistics.

BACKGROUND INFORMATION

The New Regional Medical Center's critical path consists of 83 activities over 500 working days and began on October 29, 2010, and concludes per the schedule on October 15, 2012. This path revolves primarily around non-accessible drywall finishes in the patient tower, in addition to heavy rough-in in the operating and surgical cores of the medical center, primarily in sector 1C. However, the critical path concludes with the finish elements of the atrium of the facility. This area is the key focus for the final 7 months of the project, as Owner furnished equipment begins to be installed in other areas of the hospital.

See Appendix H for the New Regional Medical Center's critical path schedule.

Focused items on the critical path include the sequence: (1) Frame Non-Accessible Walls, (2) Drywall Non-Accessible Walls, and (3) Sheet Metal Overhead Rough-In. This sequence occurs in 11 phases and walks from the 4th floor down to 2nd floor, moving from sector A into B (as shown in Figure 9, Page 26). Once sector 2B is completed, these trades skip over the 1st floor and proceed to the ground level. Ground level critical path activities only include sector A and C. Sector A includes the medical center's cafeteria and kitchen, and sector C includes elements of the emergency room.

Once these three activities are completed on the ground level, they return to the 1st floor and work from A to B to C, and tie into completed areas of D, in addition to future critical path items associated with the operating and surgical rooms. Critical activities in this sector include overhead and in-wall rough-in for plumbing, electrical, medical gas, security, and pneumatic tubing. This area is finalized with partition and ceiling drywalls. Due to drywall's placement on the critical path of sector C, the atrium progress is also added to the critical path of the hospital.



With the large size of the atrium, scaffolding is required in order to install and finish many of the features located within the ceilings and high walls of this space. All finish elements of the atrium, from scaffolding installation to removal, is a critical activity.

Finally, in order to deliver a completed project, final walk thru, sign-offs, and inspections conclude the critical path for the New Regional Medical Center.

RISKS TO COMPLETION DATE

The largest risk to completion date is missing the enclosure deadline of September 1, 2011. If missed, the critical path described above is impacted beginning with 1st floor sector C activities, resulting in delay of the atrium, and potentially substantial and final completion. Additionally, depending on the delay, other activities such as pouring the concrete pour stops in each wing of the facility may be held due to cold weather conditions within the building, as delay will progress into the winter season. Failure to pour these slab sections on time will create delays on interior flooring of the patient towers, and potentially impact finishes and equipment installation in these areas.

Based off the project schedule included in **Appendix E**, with comparison to the critical path schedule included in **Appendix J**, the atrium enclosure assembly is to be completed on August 1, 2011, which permits a float of one month before the enclosure deadline, permitting additional time to complete the complex assembly if required.

EXISTING PARAMETERS

COST INFORMATION

The atrium's curtain wall system was part of Bid Package # 8.C – Curtain Wall & Aluminum Windows, and was awarded to R.A. Kennedy & Sons Inc.

The bid constituted a lump sum of \$5,571,410 and included 17,664 hours of labor for the following systems:

- (1) Glazed Curtain Wall System
- (2) Aluminum Windows
- (3) Automatic Entrances
- (4) ICU/CCU Entrances
- (5) Interior Glazing
- (6) Glass Handrail
- (7) Glass Partitions
- (8) Aluminum Storefront
- (9) System Caulking & Sealants
- (10) Reveal Break Metals

Focusing into the Glazed Curtain Wall System components alone, Table 7 details the cost breakdown per the award bid amount provided by R.A. Kennedy & Sons Inc.



TABLE 7: CURTAIN WALL COST SUMMARY

Glazed Curtain Wall System Breakdown							
Quantity	41,000 SF						
Man-hours	10,173 Hours						
Crew Size	23						
Material	\$2,132,000						
Installation	\$1,023,342						
Caulking & Sealants	\$100,000						
Cleanup	\$35,328						
System Total	\$3,326,670						

SCHEDULE INFORMATION

PROPOSED SCHEDULE

The proposed schedule accounted for 8 weeks for the system to be completed, with an approximate schedule of 2 weeks to construction the framing system, 4 weeks to insert the gaskets and glazing panes, and finally another 2 weeks to caulk and seal the system.

TABLE 8: PROPOSED SCHEDULE FOR ATRIUM ENCLOSURE ACTIVITIES

Activity	Start Date	End Date	Duration	
Curtain Wall Atrium	June 6, 2011	August 1, 2011	40	
Overall Enclosure Schedule	March 22, 2011	September 1, 2011	116	

Due to challenges and complexities in constructing this system, it was recognized that the scope of the curtain wall system would take longer than the 8 weeks initially planned. An updated activity status placed the completion at the middle of October, with an ultimate delay to the enclosure schedule of approximately one and a half months, or 32 working days.

ACTUAL SCHEDULE

The frame and glass was installed beginning on August 1st and concluding on October 15th, and required an extra six weeks for the silicone seals and trim to be completed. This process began construction already delayed from the original baseline schedule, and continued to be affected by an aggressive assembly timeline. The system took three additional weeks to assemble over the original estimate. R.A. Kennedy & Sons utilized a crew of 23 members to install the curtain wall system. Due to the challenges of the leaning wall configuration, the installation required a larger crew size and additional equipment when compared to a traditional system.

TABLE 9: UPDATED SCHEDULE FOR ATRIUM ENCLOSURE ACTIVITIES

Activity	Start Date	End Date	Duration
Curtain Wall Atrium	August 1, 2011	October 15, 2011	54
Overall Enclosure Schedule	March 22, 2011	October 15, 2011	148



CONSTRUCTION PROCESS

The curtain wall construction consists of a stick built process, which involved the complete assembly of the system on site and in place on the exterior of the structural framing.

Due to the restrictions of height and site logistics, the workflow could not be overlapped or sequenced due to safety concerns, and accessibility of the working surface. The work path consisted of working by level up the face, then proceeding to the next assembly to the west (left), and finally concluding the enclosure at roof level, as shown in Figure 21.

The entire system was assembled using multiple pieces of equipment, which were orchestrated to provide a safe working platform and material delivery to the work surface. The aluminum framing was set using a crane for lifting the frames, and a hi-reach lift for guiding the frame into place, due the inverted application. The glass was set using a crane with a power cup attachment, for lifting the glass, and two hi-reach lifts, one to guide the top of the glass and the other the bottom. Additionally, since the parapet of the atrium curtain wall is inverted in the opposite direction, it required two HEK towers so the very




FIGURE 21: CURTAIN WALL GLAZING WORKFLOW

top of the reverse lean could be installed. A photo of the system during the construction process can be seen, in Figure 22.

ANALYSIS INFLUENCES

SUBCONTRACTOR INTERVIEW³

On March 22, 2012, an interview was conducted with Al Batten, who is Project Manager for R.S. Kennedy & Sons, Inc., and is overseeing the design, construction, and operations of Bid Package # 8.C – Curtain Wall & Aluminum Windows at the New Regional Medical Center.

SYSTEM CHALLENGES

The inverted application caused some challenges during construction. One item that required much focus was the perimeter panels and the panel steel support structure. These components are often overlooked during the design process, as typically they do not appear to be difficult. Unfortunately, R.A. Kennedy & Sons were not provided any structure to attach the perimeter panels; therefore, they have to fabricate support steel to attach to the structural columns, in order to affix the panels. They were only provided the steel column layout for the atrium, and there was no thought on how to support the curtain wall by the design team. This fell onto the subcontractor and required them to design and build out steel structure to support the curtain wall designed by Perkins & Will.

³ Al Batten – Project Manager, R.A. Kennedy & Sons, Inc.



A second challenge regarded the steel reinforcing which was required within the frame. This specification, along with a temperature-based expansion/contraction for a plus or minus temperature range of 180 degrees made the construction especially complex. It required the subcontractor to design the system "horizontally," allowing the bottom of each frame to "float," with only the top of each frame anchored to the structure. The design team outlined these specifications in order to minimize the number of custom extrusion needed for the system.

SYSTEM RECOMMENDATIONS

Due to the bidding process and the outlined construction schedule, R.A. Kennedy & Sons, Inc. was not permitted to provide any recommendations, alterations, or options for the system design. They were only provided with a structural steel grid in which they had to design how to attach their own system.

It is recommended that prefabrication of unitized panels for the atrium's curtain wall system would have been a better alternative. However, more time would need to be allocated to the design and system constraints, in addition to a final design decision occurring sooner. During R.A. Kennedy & Son's shop drawing submittal process, crucial design items were still being determined. Additionally, interior working platforms or decking would make construction easier, permitting a team to align and affix the base of the panel from the interior.

Prefabrication (unitizing) closes a building in quickly, but all of the design work needs to be done well in advance. Stick building, which was the process for this assembly, allows for time in the schedule to work out sizes and design issues in the field. Additionally, if a unitized system were to be used, all new extrusions would have to have been used and there was not enough time. In this facility, R.A. Kennedy & Sons prefabricated every other glazing system, except for the atrium's enclosure. Looking back onto how this system played out, they would have preferred to have this system unitized, with prefabricated frames, and preinstalled glazing units. With this option, the field assembly would have been more efficient, cost-effective, and safer.



FIGURE 22: CURTAIN WALL CONSTRUCTION [TAKEN ON 10/4/2011 BY AL BATTEN, R.A. KENNEDY & SONS INC.]
Senior Thesis Final Report | April 4, 2012 Pag



METHODOLOGY

The redesign of this system will be performed through the reference of "The International Building Code 2006" prepared by the International Code Council, with additional compliance coordination from "ADA Accessibility Guidelines for Buildings and Facilities" prepared by the U.S. Architectural and Transportation Barriers Compliance Board. In order to aesthetically transition the additions into to the space, a majority of the interior finishes will remain typical of the space, and refer to existing components of the facility. The goal of the analysis is to design a permanent working platform at the first and third floor to assist in construction logistics of the inverted curtain wall system. Additionally, this platform will be finished as public space and designated as a public lounge area for patients and visitors. Finally, this area will provide additional workspace necessary for maintenance and cleaning of the glazing system.

EXISTING PARAMETERS & GUIDELINES

The following factors will be examined and taken into account during this analysis:

- (1) Dimensions and configurations of the building
- (2) Aesthetic finishes of the atrium space
- (3) Provision for constructability and usable finished space
- (4) Adherence to relevant life safety codes
- (5) Adherence to relevant building codes, such as ADA compliance

The following assumptions will form the basis of this analysis, unless otherwise noted:

- (1) Member layout to remain typical to the existing design
- (2) Joist type and spacing to remain typical to the existing design
- (3) LRFD design analysis process will be utilized
- (4) The expansion joints will be located in the same place as the concrete pour strips, if applicable.

The following notes from LS-001 Code Compliance Data are of particular importance to this analysis:

- (1) International Building Code (IBC) Section 308: Occupancy Classification: Assembly [Group A-2]
- (2) IBC Section 404: Atriums
 - a. Automatic Fire Protection and Smoke Control
 - b. Interior Finishes shall be a minimum of Class B without reduction for automatic sprinklers
 - i. Flame Spread Index: 26 75
 - ii. Smoke Developed Index: 0 450
 - c. Travel distance to means of egress shall not exceed 200 feet
- (3) IBC Section 602.2: Type 1 Construction
- (4) Egress Requirements
 - a. Capacity of Egress: 15 net Square feet per Occupant Assembly Unconcentrated
 - b. Egress Width: 0.15 inches per occupant
 - c. Travel distance from exit of egress travel shall not exceed 250 feet

The following notes regarding ADA accessibility are of particular importance to this analysis:

- (1) 4.2 Space Allowance and Reach Ranges
 - a. 60 inches minimum for wheelchair passing width and turning space
 - b. Handrails must be continuous in the space and terminate parallel to the floor level if angled



The following notes from S-001 Schedule & General Notes are of particular importance to this analysis:

- (1) Floors have been designed as composite beam and composite deck.
- (2) All concrete shall be ready-mix and have a minimum compressive strength at 28 days of:
 - a. Concrete Slab on Metal Deck: 3,500 SPI
- (3) All concrete shall have a minimum of 500 lbs of cement per cubic yard.
- (4) All structural steel shall be fabricated and erected in accordance with the latest AISC Code. All connections, including at HSS sections, shall be designed and detailed in accordance with the latest AISC Code. All wide flange shapes shall be ASTM A992.
- (5) Design Load Requirements
 - a. Typical Floor: Dead Load-65 pounds per square feet, Live Load-100 pounds per square feet
 - b. Atrium Roof: Dead Load-75 pounds per square feet, Live Load-100 pounds per square feet
- (6) Utilize a 3 ¼" Lightweight Concrete on 3" Metal Deck

ARCHITECTURAL ANALYSIS PROCESS

Architectural redesign will take place using Autodesk Revit Architecture and Structure in order to modify and add to the existing model furnished by Perkins & Will. The redesign will include the development of two working interior platforms, which are to be utilized by the trades for construction of the curtain wall-glazing units, in addition to the interior finishes. These working platforms will be designed in order to meet building codes applicable to the space, and permit them to double as and interior corridor and lounge that will be cantilevered off the structural steel at the face of the curtain wall-glazing units.

The concept will create a lounge that will be accessible from both the east and west patient towers at level one and level three. This space will include furnishing and side tables to provide a comfortable and flexible environment for the patients and their visitors. This space will overlook the front façade of the medical center and provide a panorama view of the Norristown Farm Park.

The existing parameters and guidelines referenced above have been taken into account, and the following renderings highlight the redesign space.




FIGURE 23: INTERIOR MODEL IMAGE AT 2ND FLOOR ATRIUM





FIGURE 24: RENDERED 3D INTERIOR SECTION AT ATRIUM







FIGURE 25: RENDERED 3D EXTERIOR SECTION AT ATRIUM

UNITIZED CURTAIN WALL SYSTEM

Analysis is to be performed to calculate the optimum assembly dimensions for the unitized system. The new assembly will consist of panels in which span each floor level. Additionally, due to delivery restrictions, the overall dimension of the length will be limited to what R.A. Kennedy & Son's is capable of hauling. Figure 26 and Figure 27 display the delivery sequence and truckload distribution for the curtain wall units. Additionally, due to height restrictions on delivery, the front façade panels require a field assembly to stack two panels to reach the full height, corresponding with the work platforms, allowing a safe working plane to affix the panels to the structural system, as shown in Figure 28.














FIGURE 28: FIELD JOINTED UNITS [SHOWN IN BLACK OUTLINE]

In order to coordinate the lifts with the inverted façade, a crane will pick the assembled 22'-0" tall unit towards the building, and hang the unit from the engineered support structure. Once hanging in place, a crew standing on the new working levels inside of the structural frame will pull the bottom edge back to the face of the steel and affix the base of the unit, as shown in Figure 29.




FIGURE 29: SCHEMATIC LIFT SEQUENCE



OUTCOME

ARCHITECTURAL REDESIGN COST

Square foot estimate costs are applied against the additional architectural and structural elements required to include this redesign into the project costs. Below is a table of the additional costs and outcome.

TABLE 10: ARCHITECTURAL REDESIGN COSTS

System	Cost
Floor System	\$8,450
Structural Steel	\$24,338
GWB	\$3,280
Finishes	\$87,387
Redesign Total	\$123,455

Redesign costs for the unitization of the curtain wall assembly is comparable in costs to a stick built system. The major changes with the costs are that the in-filed construction costs for equipment and labor are reduced, while the fabrication and assembly costs are increased, in addition to transportation costs. In talking with R.A. Kennedy & Son, they justified that there would be very little cost differential in the two system approaches. In this case, a lead-time of 20 weeks would be required to allow for procurement of materials and fabrication. The major benefit of the unitized system would permit a quicker building enclosure and a reduction in high-risk construction activities on site. Overall, unitization for this project would not create a schedule acceleration situation. Due to the lead-time relative to when R.A. Kennedy & Sons were brought into the project, the unitized system would arrive on site in just enough time to complete the enclosure on schedule. Unitization would only prevent the delay in which occurred with the original stick-built system.

CONSTRUCTABILITY SAVINGS

Due to the architectural configuration of the existing system, notably the incline and reverse incline of the atrium's glazing curtain wall, great efforts, financially, were made in order to engineer a safe manner to construct the original design. In addition to the need of multiple cranes and lifts, a crew double in size to typical installations, was required to complete this façade. With the implementation of a unitized system, the need for multiple cranes, lifts, and an oversized crew is eliminated. If planned properly, the entire system can be constructed with a typical crew size and only one crane in operation. This will reduce substantial equipment and labor expenses for the system, in addition to reducing the level of risk for the workers. With the inclusion of the architectural redesign, the workers are placed at a safe working height and can maneuver the flying panels into place with more control. Additionally, future trades who are responsible for encasing the steel columns in gypsum wall board and painting, will have a safer working platform, eliminating the need to cantilever scaffolding out to the inside of the enclosure.

AESTHETICS, SPACE, AND USABILITY

In development of the architectural redesign, the goal was to provide a more efficient construction process, while in turn, developing a permanent space for facility use. It has been recognized through analysis that multiple public space features were removed from the original design due to cost overruns. Keeping this in mind, an aesthetically pleasing space was designed in order to improve constructability and eliminate a high-risk construction process on the site, while also providing a space for patient and visitors to enjoy the



greenfield landscape surrounding the hospital. Additionally, a more accessible access point is created for interior glazing cleaning. Overall, this redesign and unitization process meets the Owner's expectations by providing high construction quality in a safe environment, while enhancing the patient's experience.

Reflection

It is believed that this analysis confirms that stronger focus should have been provided during design development of the atrium's curtain wall enclosure. With this component being one of the most time critical events during construction, a stronger outline and interface with a glazing subcontractor should have been performed. Doing so would have permitted constructability input, design development, and transparency behind achieving the design intent in the most economical process. Although early subcontractor involvement would have resulted in the unitization and design reviews of the atrium enclosure, the delivery method for this project created a barrier for input. The New Regional Medical Center would have benefitted from a modular system, in addition to an architectural revision to include catwalk lounges along the atrium exterior wall.

From this analysis it is recommended that design teams review their curtain wall systems with a stronger focus. Additionally, obtaining a glazing subcontractor for consultation would also assist in design development in order to ensure that the expected product meets the schedule, cost, and quality level that the owner and construction team expects to produce. With the assistance of a prefabricated glazing system, the construction site requires fewer trades working in high-risk locations, in addition to less equipment on site. Finally, the key to this system being implemented is open communications and consultation during design development and design revisions.



ANALYSIS 3 | REDESIGN OF STRUCTURAL POUR STRIP

PROBLEM IDENTIFICATION


The New Regional Medical Center was faced with constructability issues surrounding the schedule and access to the pour strip regions of the facility. Due to the reliance of an on-time completion of the pour strip, in order to continue to install the interior components on schedule, the design decisions of this element will be analyzed. A design alternative would include a traditional building expansion joint. Typically, expansion joints create ease in construction methods and do not rely on the building enclosure activities. With the risk of an enclosure delay on this project, this analysis will analyze the project costs, schedule, and aesthetics of an expansion joint, identifying if this would have been a better option given the complexities in the atrium enclosure activities and the uncertainty of its schedule.

BREADTH

This analysis will constitute the structural breadth component of this report, and will include redesigning the concrete pour stop as a typical building expansion. Structural calculations will be performed to compare this system to a building expansion joint system. Additional costs, schedule impacts, and constructability reviews will be considered as a substantial part of the redesign, notably focusing on foundation changes, and steel frame revisions. With review, acknowledgement of which system would have performed best in this case and in combination with the schedule derived from Architectural Breadth previously discussed. Reflection on the outcomes will discuss design decision logic from a construction point of view.

BACKGROUND INFORMATION

The New Regional Medical Center is roughly 556 feet in length and has two concrete pour stops, per floor, located within each patient tower, which are each offset 125 feet from the east and west exterior walls (Figure 30). Although the main structure is steel with metal decking, the structural design detailed pour stops in lieu of building expansion joints. This connection detail requires the entire building to be enclosed and climate controlled prior to pouring the final connection. Once the structural steel and concrete decking reach typical interior temperature conditions, and transition through temperature expansion and contraction, this strip will be in-filled (Figure 31). This concept creates a rigid frame for the facility, providing both a structurally sound facility in addition to an architecturally pleasing interior without visible joints.



Unfortunately, per Analysis 2, the building enclosure date was missed on the project, which induced schedule



delays for a conditioned facility. Without a neutralized temperature in the space, and adequate time for the materials to expand and contract, the pour strip could not be placed. Ultimately, this delay affects interior finishes, such as flooring, as the pour strip areas still contain exposed metal decking and reinforcing for the floor slab.

In order to overcome this issue, and return the project back to the intended schedule, temporary enclosures were made at the connection of the patient tower and the atrium, as the atrium glazing was still being installed. Once temporary enclosure was complete, the towers were conditioned to the heat requirements for the pour strips.

In lieu of these challenges, this analysis will compare the existing pour strip system to an expansion joint system, and identify the more applicable design to this case. It will address if the pour stop was the best choice, in addition to review cost, schedule, and aesthetics concerning structural joints and pour strips.




FIGURE 31: ENLARGED POUR STRIP [S-220B | PERKINS & WILL]

EXISTING PARAMETERS

COST INFORMATION

Due to the complexities of the components associated with the pour strip being located within multiple Bid Packages, the cost information provided will be derived through quantity takeoff and *RS Means* cost information.

The estimate constituted a sum of \$239,772. Table 11 details the cost breakdown per the calculated values. **Appendix K** includes resultant values per detailed quantity takeoff.

Pour Strip Assembly							
Foundation System	\$59,512						
Structural Columns	\$61,217						
Structural Beams	\$101,826						
Slab on Grade	\$684						
Slab on Metal Deck	\$9,230						
Reinforcing	\$7,303						
Total:	\$239,772						

TABLE 11: POUR STRIP COST SUMMARY



SCHEDULE INFORMATION

Although discussion in the previous section detailed the delay of building enclosure, and the impact it created on conditioning the space and properly placing the building's pour strip system, the winter weather in which this system was being completed within was extremely mild. Due to this, the project did not have any longterm schedule impacts, and the initial delay recovered within reasonable time.

Although this is fortunate for the construction schedule and process needed for the pour strips, it must be recognized that grave delay entering the winter months, could have negatively affected the outcome of the project. Identifying this system as a critical assembly within the building, these circumstances and constructability requirements must be reviewed during the design process. Alternative designs should not only be considered for cost savings, constructability, or aesthetic purposes, they should also be reviewed against ability to recover from unforeseen delay.

CONSTRUCTION PROCESS

The entire system was assembled during the steel erection process, and did not require extra effort to arrange the component per the design details. This assembly required that a 2'-6" gap be left within the slab on metal deck. Once the building was conditioned, this gap was in-filled with concrete via a wheelbarrow, and the welded-wire fabric within the gap was overlapped from the bordering slab edges. The critical construction influence this system has is the fact that there is a 2'-6" break in the slab on deck, with two instances on every floor above grade. This can be seen below, in Figure 32. With not only the development of a tripping hazard, coordination of the interior finishes must be orchestrated properly to ensure that this system is completed, and the temporary floor plate cover is removed, before the floor systems and wall board are installed.



FIGURE 32: SECTOR B ROOF POUR STRIP [TAKEN ON 6/13/2011 BY GILBANE BUILDING CO.]



INFLUENCES

OWNER INTERVIEW⁴

In order to properly understand the design decision of selecting a pour strip system over a typical building expansion joint, an interview with Richard Montalbano, who is the Vice President and Project Executive for Albert Einstein Healthcare Network, was conducted on January 31, 2012. Below are the results of the discussion.

Q: Why was the pour strip system selected for the New Regional Medical Center?

A: The New Regional Medical Center has an elegant, sleek, architectural aesthetic on both the interior and exterior of the facility. Although the expansion joint could be hidden behind the precast enclosure panels, the interior finishes would not support the look of an expansion joint cover.

Q: Does the Albert Einstein Healthcare Network have negative experience with expansion joints?

A: Yes, we have a number of facilities that contain expansion joints, and this system creates a maintenance nightmare. It may be specific to healthcare and hospitals, but our expansion joints see extensive wear and tear due to the loading crossing the threshold. This is mainly due to the hospital beds and other equipment movement.

Q: How has maintenance affected your design decision?

A: Maintenance is the critical reasoning why the expansion joint system was not utilized on this facility. Although there may be new products on the market, the direction of interior finishes selected for the hallways do no support a gap within the building. Typically, the expansion joint cover plates are carpeted-over in our other facilities. However, we cannot utilize carpet within the hallways of this hospital. If vinyl tile were placed over the gap, the tiles would warp and crack. Unless a product is available in which the floor finish can be in-laid in the system, an expansion joint is not practical.

Q: It is recognized that the construction process for a pour strip becomes much more complicated, especially as the finishing requires building enclosure. How do you feel if this system creates a delay on the project?

A: Many of the design decision made within this facility revolved around building comfort, aesthetics, and the lifecycle of the facility. It is understood that this design decision may create construction issues, and areas for delay. Although this decision does not simplify the AEC's project approach, it eases the maintenance and lifecycle control of the space. If I can make maintenance that much easier for my facilities, the decision is justified.

Q: If a product is located which is capable of embedding the architectural finishes within the joint cover, in addition to providing structural support, would you consider the system as a feasible design alternate?

A: Yes, I think this would be a reasonable design alternate to consider. I would be most concerned with the cost difference. It is understood that the construction team would be able to perform either system without considerable schedule alterations. Focus on costs and aesthetics.

⁴ Richard Montalbano - Vice President & Project Executive, Albert Einstein Healthcare Network



METHODOLOGY

The redesign of this system will be performed through the reference of "Expansion Joints in Buildings – Technical Report No. 65" prepared by the Standing Committee on Structural Engineering of the Federal Construction Council. Additional references will include material used in AE 404 and AE 308, notably "Fundamentals of Structural Analysis, Third Edition" by Kenneth M. Leet. Finally, structural calculation for foundation redesign will follow the guidelines presented in CE 397A, and "Principles of Foundation Engineering" by Braja Das.

EXISTING PARAMETERS & GUIDELINES

The following factors will be examined and taken into account during this analysis:

- (6) Dimensions and configurations of the building
- (7) Design temperature change
- (8) Provision for temperature control
- (9) Type of frame, connection to the foundation, and symmetry of stiffness against lateral displacement
- (10) Material of construction

The following assumptions will form the basis of this analysis, unless otherwise noted in calculations:

- (5) Floor construction assemblies to remain typical to the existing design
- (6) Member layout to remain typical to the existing design
- (7) Joist type and spacing to remain typical to the existing design
- (8) LRFD design analysis process will be utilized
- (9) The expansion joints will be located in the same place as the concrete pour strips, if applicable.

The following notes from S-001 Schedule & General Notes are of particular importance to this analysis:

- (7) Floors have been designed as composite beam and composite deck. Beam/deck shoring is not required unless noted otherwise on drawings.
- (8) Bottom of footings shall bear on undisturbed virgin soil capable of safely supporting 4,000 PSF.
- (9) Reinforcing steel shall have a minimum clear cover as follows:
 - a. Concrete poured against earth: 3"
- (10) All concrete shall be ready-mix and have a minimum compressive strength at 28 days of:
 - a. Spread footings: 4,000 PSI
 - b. Slab-on-Grade: 3,500 PSI
 - c. Concrete Slab on Metal Deck: 3,500 SPI
- (11) All concrete shall have a minimum of 500 lbs of cement per cubic yard.
- (12) All structural steel shall be fabricated and erected in accordance with the latest AISC Code. All connections, including at HSS sections, shall be designed and detailed in accordance with the latest AISC Code. All wide flange shapes shall be ASTM A992.



The following tables from S-001 Schedule & General Notes are of particular importance to this analysis:

DESIGN LOAD SCHEDULE (ALL LOADS SHOWN ARE IN POUNDS PER SQ. FT.)												
AREA	SLAB ON GRADE	SLAB ON GRADE	SLAB ON GRADE	TYPICAL FLOOR	SURGERY FLOOR	BED TOWER PATIENT BATHROOMS	MECHANICAL PENTHOUSE	ROOF w/ CONCRETE	MECHANICAL PENTHOUSE ROOF	TYPICAL ROOF	3rd FLOOR LOW ROOF	Ы
COMPONENT	4' 5I	6 ¹ 5I	8' SI	TΥΡ	surg	BED BATI	PENT	ROOF	PENT	TΥΡ	Brd F	ATRIUM
CONCRETE SLAB	50	75	100									
3 1/4" L.W. CONC. ON 3" DECK				48								
3 1/4" N.W. CONC. ON 3" DECK												58
5" N.W. CONC. ON 3" DECK					81		81					
3 1/4" L.W. CONC. ON 2" DECK						43						
ROOF & INSULATION									8	8	8	
STEEL				8	10	8	10	10	10	7	7	8
CEILING				2	2	2	2	2		2	2	2
M.E.P.				4	4	4	4	4	15	4	4	4
COLLATERAL				3	3	3	3	4	12	4	4	з
CONCRETE OVERPOUR						10						
BALLAST											10	
8" CONCRETE PAD								100				
TOTAL DEAD LOAD	50	75	100	65	100	70	100	120	45	25	35	75
TOTAL LIVE LOAD	100	200	250	100	100	100	150	100	30	30	30	100
TOTAL LOAD	150	275	350	165	200	170	250	220	75	55	65	175

TABLE 12: DESIGN LOAD SCHEDULE [S-001 PERKINS & WILL]

TABLE 13: SNOW DESIGN LOAD SCHEDULE [S-001 PERKINS & WILL]

SNOW DESIGN LOAD SCHEDULE							
ITEM	SYMBOL	VALUE	REFERENCE				
GROUND SNOW LOAD	Pg	30 psf	FIGURE 1608.2				
SNOW EXPOSURE FACTOR	C.	1.0	TABLE 7-2				
SNOW LOAD IMPORTANCE FACTOR	I,	1.2	TABLE 7-4				
THERMAL FACTOR	Ct	1.0	TABLE 7-3				
FLAT-ROOF SNOW LOAD	Pf	26 psf	SECTION 7.3				






FIGURE 33: ALLOWABLE BUILDING LENGTH PER CALCULATED DESIGN TEMPERATURE

STRUCTURAL ANALYSIS PROCESS

- (1) Analysis is to be performed to calculate the necessary gap required for the building expansion joint.⁵
 - a. Calculate design temperature
 - b. Identify allowable building length
 - c. Calculate upper bound for joint closure
 - d. Apply construction tolerances
 - e. Select gap dimension & appropriate cover products
- (2) Analysis is to be performed to design each column, and is to result with an economically designed column per gird intersections (4 per wing) from the foundation to the roof. Splices will occur at elevations previously present in the building's structural design.⁶
 - a. Tributary Areas Calculations
 - b. Live Load Reductions (as needed)
 - c. Locate Splices
 - d. Design Column
- (3) Analysis is to be performed to design the necessary footing per column system case.⁷
 - a. Calculate design temperature
 - b. Identify allowable building length
 - c. Calculate upper bound for joint closure

⁵ Analysis process formed on standards included within (Standing Committee on Structural Engineering of the Federal Construction Council, 1974) with reference to (Stein, Reynolds, Grondzik, & Kwok, 2006).

⁶ Analysis process formed based on AE 404 and AE 308 with reference to (Leet, Uang, & Gilbert, 2008).

⁷ Analysis process formed based on CE 397A with reference to (Das, 2011).



- d. Apply construction tolerances
- e. Select gap dimension & appropriate cover products

See **Appendix L** for the calculations for the expansion joint system for the New Regional Medical Center.

STRUCTURAL ANALYSIS OUTCOME

In order to provide a comparable result, the cost information provided to quantify the value of the building expansion joint system will also be derived through quantity takeoff and *RS Means* cost information. Through modeling an alternative system within the structural Revit model, BIM and virtual construction is leveraged to quickly review and quantify the system changes.

The estimate constituted a sum of \$297,570. Table 14 details the cost breakdown per the calculated values. **Appendix M** includes resultant values per detailed quantity takeoff.


Expansion Joint Assembly		
Foundation System	\$32,758	
Structural Columns	\$60,671	
Structural Beams	\$101,826	
Slab on Grade	\$684	
Slab on Metal Deck	\$8,552	
Reinforcing	\$8,613	
Expansion Joint Covers	\$40,289	
Misc. Steel Angle	\$44,177	
Total:	\$297,570	

TABLE 14: EXPANSION JOINT COST SUMMARY

The selected interior finish of the expansion joint includes Nystrom expansion cover system that permits the inclusion of the finished floor and wall materials. The components include the following components:

EJ-TMM-200-W EJ-TMM-200w-W EJ-RJS-200

Appendix N includes the Nystrom product guide for the selected components of the system.








FIGURE 36: POUR STRIP STRUCTURAL FRAME SYSTEM





FIGURE 37: EXPANSION JOINT STRUCTURAL FRAME SYSTEM






FIGURE 38: CLOSE-UP POUR STRIP SLAB & STRUCTURE CONFIGURATION




FIGURE 39: CLOSE-UP EXPANSION JOINT SLAB & STRUCTURE CONFIGURATION



OUTCOME

STRUCTURAL ASSEMBLY COST COMPARISON

This analysis identified that the building's pour strip system is a more cost effective design decision. The choice to utilize the pour strips over expansion joints saved the project approximately \$57,800. Although the expansion joint system permitted a decrease in the size of the foundation system, and slight decrease in the concrete slab and metal deck, these reductions did not offset the increase in other system costs. The expansion joint system requires an added cost for the miscellaneous steel angles for the slab edge at the joint, in addition to the finishing cover strips for the floors, walls, and roof.

TABLE 15: COST COMPARISON

Pour Strip vs. Expansion Joint Assembly	% Change
Foundation System	-44.95%
Structural Columns	-0.89%
Structural Beams	0%
Slab on Grade	0%
Slab on Metal Deck	-7.35%
Reinforcing	+17.94%
Expansion Joint Covers	+100%
Misc. Steel Angle	+100%
Total:	+24.11%

AESTHETICS' SYSTEM COMPARISON

This analysis clarified that the building's pour strip system is a more aesthetically pleasing system and is preferred by the Owner. Although consideration were made to locate and include a system which met the maintenance and aesthetic interior requirements of the Owner, it is understood that the more cost effective system also included the least disturbance to the finishes and aesthetics of the space.

REFLECTION

It is believed that this analysis confirmed the design decision made in correspondence with the Owner and the design team. Although it is believe that an expansion joint system creates efficiency and cost savings in construction, it is clear that in the application at the New Regional Medical Center this is not the case. Due to the high expectations of the Owner regarding patient experience, finish quality, and maintenance.

From this analysis, it is recommended that other design teams and Owners investigate the implications of a pour strip within their facility in lieu of an expansion joint. Although the expansion joint provides a simpler construction method, the aesthetic results and additional costs may not be worthwhile. It has become commonplace that an expansion joint is more efficient; however, it is recommended that the design team or construction management firm use the design alternate process within Autodesk Revit to quickly analyze the cost benefits of a building pour strip, and cross-reference these outcomes with the intentions and goals of the Owner and facility user group.



ANALYSIS 4 | DOCUMENT MANAGEMENT FOR THE OWNER

PROBLEM IDENTIFICATION

As discussed earlier in 'Analysis 1 | BIM in Preconstruction,' this project underutilized recent industry growth and implementation of Building Information Modeling. Although not requested by the Owner, recent developments in collaborative tools and data integration, has created interest in research into development of a facility management document dashboard for the New Regional Medical Center. As the first building for this new medical campus, this facility is the perfect opportunity to develop and test out a new technology platform, and demonstrate the capabilities of new collaboration methods and information management, which have been of growing interest over the past two years.

STATE OF THE INDUSTRY

The 20th Annual PACE Roundtable took place on November 9, 2011, and brought students and industry members to discuss this year's theme of "Building Innovation into Practice: Keeping what Works." The breakout session titled "BIM Services for the Owner", focused on many of the difficulties and challenges of conveying BIM services through the life cycle of a project, and into a usable form for the Owner's facility management staff. It was understood that many Owners are confused on BIM requirements and interfacing elements necessary to capture usable information. It was also recognized that different types of Owners dictate different level of BIM services within project development. The two main distinctions were between an Owner and a developer. As an Owner, BIM services are more influential because they retain the facility for operation. However, focusing on developers and their consistent building turnover, BIM services were less likely to be requested from the Owner, as the resale value of BIM models and facility databases are not readily defined to date.

Consensus was reach that the BIM for Owners drivers revolve around cost reduction, notably through change order reduction and a more transparent construction information exchange process. However, risk was acknowledged that BIM should be developed through particular metrics that are focused on the delivery process outlined by the Owner. Due to legal constraints, information exchange and collaboration should be highly detailed and compliant with various BIM contracts, such as AIA E202, AGC Census Documents, and BIM Addendum.

It was recognized that additional drivers of information exchange has to come from the fabrication facilities, and not necessarily the Owner. Software developments must be made in order to take usable data from a designer's model into fabrication facilities, and back out to an Owner. Although the Owner's facility management staff may require a system restructuring or redevelopment of their asset databases, it is understood that this direction is easier to perform over retooling fabrication facilities.

The construction industry was identified as a difficult industry to develop design and component standards, in order to minimize new, unique details within each project. Although project uniqueness creates great strides in technology and progresses typical means-and-methods, unique and specialty construction on every new project, creates high risks for both the designer and the contractor. BIM level of detail is being challenged consistently with document quality falling due to insurance risks, high profile projects, and complex details.



With current developments of Owner resources and reflections on BIM strategies, hopes are high for a stronger, more developed, Owner understanding on BIM services in the future.

At the conclusion of the session, multiple recommendations were made by industry professional concerning potential research ideas. The key point agreed upon by the industry professional present was to utilize the technology and software platforms available on the market. The importance was stressed to take advantage of the skills and training the current workforce already has, and to make information access easier and more streamlined.

Finally, it was acknowledged that with the upcoming *BIM Planning Education Session* workshop on April 17, 2012, much of the workflows, interfacing, and development of a facility management database should be focused on the understanding and integration of medium developed through the construction process, and not redefining the BIM process. Additionally, the upcoming release of "Owner Execution Planning" by the Computer Integrated Construction Research Program, at Penn State University's Department of Architectural Engineering (see Research & Collaboration), will ground may of the recent efforts.

RELATED ARTICLES

As companies begin to complete their BIM pilot projects, much recognition was made to the need to reevaluate and change their workflows and company organization. This influenced the design team the most, changing from design assignment "sheet-type based" workflow, into a "model-element" process, as the sheets automatically update when components are added and modified. In addition to this, many companies began to reach the limits of their hardware, regularly having system crash, or freeze. Moving forward, firms recognized their limits, and began modifying their capabilities in order to continue to press BIM's development. At this point, "progress became decentralized and organic;" however, "BIM is not a silver bullet and is not going to resolve issues on its own, though it may help clarify [...] choices that may not have been previously evident" (Post, 2009). Reflecting back on the progression of BIM and restructuring of organizations, rarely do firms address the need to update documentation organization. For the most part, document structure has been overlooked in the transition of BIM enabled project. As facility-management databases are developed out of construction BIM, there is a risk that a format will not be developed until the project is underway, forcing a divided workflow.

"A DIVIDED WORKFLOW [...] MEANT PROJECT KNOWLEDGE WAS BEING DEPOSITED IN TWO SEPARATE DATABASES, DEFEATING ONE OF THE POTENTIAL EFFICIENCIES OF BIM. EACH DATABASE NEEDED CONSTANT MANUAL UPDATING TO STAY COORDINATED AND USEFUL." *Nadine Post, Engineering News-Record*

Over the past few years, as BIM has developed into a tangible benefit for Owners and the building's user groups, additional interest and collaboration has produce solutions and recognizable benefits of the value in capturing information. The driver behind this effort includes efficiency, accessibility, and differentiation in the industry. It has been recognized that many of the existing methods of a facility management document transitions includes a data handoff that includes the file structure relevant to construction. As projects convert into a digital environment, much of the data is being embedded into the models, and organizational methods are adapting to "construction-to-FM model handover standards and systems". This process requires the



project team to gather and store equipment and material information in a logical way as the project proceeds, and eliminates the inefficiencies of manually collecting and organizing handover data at the end of the project. The key to delivering data from construction into the life-cycle operation includes the "introduction of relatively easy-to-use tools and process adjustments" which not only produces a better product for the Owner, but has also improved construction awareness (Sawyer, Data for the Life Cycle, 2011).

"THE OWNERS ALL ARE AFTER THE SAME THING: TO IMPROVE THE QUALITY OF CONSTRUCTION AND MAKE THE DATA HANDED OVER TO FACILITIES TRULY USEFUL, RATHER THAN BEING EITHER A PAPER OR DIGITAL LANDFILL AS IN THE PAST" *Tom Sawyer, Engineering News-Record*

As companies begin differentiating themselves through a long-list of client deliverables, it is common for an Owner or a construction firm to 'add-on' new items during the construction process, namely those focused on BIM and Facility Management turnovers. Although challenging to upgrade an active project or modify documents on a completed project, it has been recognized that simple processes can replace the need to start BIM modeling process from the beginning. Facility users do not necessarily need an intelligent model to perform their job, or make their tasks more efficient. What they do need is an intelligent system that assists in accessing the original documents, and allows them to utilize BIM on newer facilities. With the ability to utilize simple document exchanges, "information [can] be loaded into the system from scratch." Seeing the advantages of incorporating "intelligent" document control for existing facilities, with "intelligent" model development permits a single source deliverable that can be tailored to the situation (Ross, 2011).

"YOU DON'T HAVE TO DESIGN THE STRUCTURE IN THE FIRST PLACE USING BIM SOFTWARE, ALTHOUGH THAT WOULD BE NICE. AND YOUR CLIENTS DOES NOT NEED SUPER-SOPHISTICATED SOFTWARE TO TAKE ADVANTAGE OF THE DELIVERABLE." Steven Ross, Engineering News-Record

Based out of Vancouver, British Columbia, a company called *Multivista* produces project photography using high-end cameras and wide-angle lenses to document construction conditions and as-built components of a facility. Founded through a former electrical subcontractor, it was recognized that accurate images conveyed the conditions of his firm's work before it was covered up. Having digital photos integrated into construction documents minimized and properly designed liability if questions arouse. Although designers and builders utilize "as-built" drawings in their facility documentation turnover, it is recognized by most of the industry that inaccuracies are likely to occur within these documents. *Multivista* has developed into a franchise, and they now become involved in the project during the preconstruction stage, and integrate their services alongside the rest of the team. By identifying "hotspots" of the facility with the Owner, the photographers coordinate their database to align with the Owner's needs and the construction schedule. At the conclusion of the project, the Owner has a database of photographs, which have been indexed within the construction documents, and can be referenced as desired (Judy, 2011).



"THE IMAGES ARE THEN INDEXED TO PLANS AND UPLOADED TO A SECURE INTERNET-BASED SYSTEM FOR PROJECT TEAM ACCESS." Scott Judy, Engineering News-Record

As the construction industry begins to transform into an information-technology based industry, it is important to identify the characteristics of the digital intuitive generation. As companies seek differentiation in a network that is becoming ever connected, the following five observations have been made:

- (1) Digital natives live publically online
- (2) They share knowledge
- (3) They believe transparency yields trust
- (4) They are timely, but not time-managed
- (5) They believe in interactions, not transactions.

As the construction industry continues to transition into the digital generation, it must also recognize the capabilities, training, and personalities of Owners, partners and consultants in which they interact with. It must be recognized that as new collaborative, digital, environments become the hub of company interface; the development must be catered to new innovations which make work more efficient, but also permit earlier generations to seek the added-value (Manafy, 2011).

"COMPANIES THAT PRAISE COLLABORATION, LEARNING AND SOCIALIZATION WILL LOOK MORE ATTRACTIVE THAN THOSE THAT FOCUS SOLELY ON STRUCTURED TIMELINESS AND PRODUCTIVITY." *Michelle Manafy, Engineering News-Record*

INDUSTRY RESEARCH

On March 12, 2012, *Engineering News-Record* released the results of a survey performed with the *ENR Future Tech* reader group to assist in identifying the current state of technology use and wishes for future development. The article, titled "Hot Tech Topics" includes the summary of 445 responses received in late February and includes feedback from a variety of firms as shown in Figure 40.




FIGURE 40: SURVEY RESPONDENT FIRM TYPES⁸

The survey was prepared to allow the respondents answer open-ended questions, permitted a wider range of results to eliminate any suggestion towards a particular tool or product. The results were gathered by category, and ranked by frequency into two series of results:

TABLE 16: WHAT READERS LIKE ABOUT THEIR INFORMATION TECHNOLOGY TODAY⁹

01 BIM	02 iPads	03 Collaboration Environment
04 Online Project Documents 05 3D CAD 06 Mobile Tools		06 Mobile Tools & Devices
07 iPhones	08 Smart Phones	09 Tablets
10 The Cloud	11 VELA	12 GIS/GPS/Mapping
13 Enterprise Systems	14 Laser Scans and LIDAR	15 Digital Photos, Job Cams
16 Videoconferencing	17 PDF Distribution and Markups	18 Other Responses

TABLE 17: WHAT READERS SAY ABOUT THEIR FUTURE INFORMATION TECHNOLOGY NEEDS¹⁰

01 Cheaper, Better Software	02 Data Integrations (BIM)	03 Online Collaboration
04 Mobile Hardware	05 Cloud Storage & Tools	06 Linked & Live Project Controls
07 Construction-Specific Apps	08 Broadband Coverage	09 Standardized Data Formats
10 Ruggedized Tablet PC	11 Single-Source EPS	12 Estimating/Scheduling Apps
13 Technology Training	14 GIS Utilization	15 Project Marketing & Tools
16 Online Bid Tools	17 Paperless Work Flow	18 Social Media Marketing

⁸ (Sawyer, Hot Tech Topics, 2012, March 12) "Survey Respondent Firm Types" Page 27

⁹ (Sawyer, Hot Tech Topics, 2012, March 12) "Information Technology Today" Page 28-29

¹⁰ (Sawyer, Hot Tech Topics, 2012, March 12) "Future Information Technology Needs" Page 26-27



Major trends in results focused on BIM tools, mobility, and a collaborative project environment. Responses focused on the need for better organization, document, transitions, and an easier to build, use, and update interface to personalize the process for the parties involved. Consistently, over the past three years, the topics mentioned in the previous articles found themselves at the top of discussion boards, and the need to provide these components as a package to the Owner for facility management use became ever-more present with the results delivered in this article. The future of our industry rests in a concept which is "versatile, works flawlessly and can be tailored to specific needs" (Sawyer, Hot Tech Topics, 2012, March 12).

"THE INDUSTRY DOESN'T REALLY NEED ONE MORE NEW DEVICE. THE SYSTEMS NEED TO BE INTEGRATED BETTER." *Ray Chen, Faith Technologies*

"THE WORDS THAT CAME UP MOST OFTEN WERE 'CHEAPER,' 'SIMPLER,' STREAMLINED,' 'USER-FRIENDLY,' 'INTEROPERABLE,' AND 'INTEGRATED'." *Tom Sawyer, Engineering News-Record*

NEW REGIONAL MEDICAL CENTER TURNOVER

The turnover process for the New Regional Medical Center consists of a print set of the as-built specifications, and building plans. Additionally, all submittal information that has been logged by Gilbane Building Company will be supplied to the owner. The current document management software is Prolog Web, and this site will remain accessible for a short duration after the project for document retrieval and download.

Overall, the turnover is focused on paper documents and digital construction photography. Although digital PDFs of pertinent construction data are provided to the owner, this means is only included for a digital backup of the print items. There will be no models, drawings, or writable files delivered with the completed project.

RESEARCH & COLLABORATION

Concurrent to the discussions during the *PACE Roundtable*, Penn State's Computer Integrated Construction Research Program has been finalizing their report and guide for "Owner Execution Planning." This guide is designed to supplement their current release of "The BIM Project Execution Planning Guide and Templates Version 2.0" and focus on "a guide for Owners that provides a structured procedure to develop a strategy for integrating BIM throughout their organization including the following focus areas:

- 1. Defining Standard BIM Processes and Practices [...]
- 2. Designing Information Integration Strategies [...]
- 3. Identifying BIM Contract Requirements [...]"

As mentioned in the State of the Industry section, there will be a one day workshop which has been designed to spark discussion within the group of industry members regarding current implementation of the "BIM Project Execution Plan" in addition to previewing the "BIM for Owners Planning Procedure." Although this



workshop takes place after the conclusion of this senior thesis report, one of the key components of the industry feedback will result from the "[development of] information exchange requirements for exchanges between project participants" (The Computer Integrated Construction Research Program, 2011).

CASE STUDY: OFFICE OF PHYSICAL PLANT

On June 21 2011, the Computer Integrated Construction Research Program released the draft of their "Case Study Procedures." This document outlines the methods used to analyze an Owner's organization to understand their structure and plan for BIM implementation. At the same time, the results of the procedure, and the application of the analysis on Penn State University's Office of the Physical Plant (OPP) were released. Below is an excerpt of their findings.

PENN STATE UNIVERSITY'S OFFICE OF PHYSICAL PLANT (OPP) OFFICIALLY BEGAN THEIR ADOPTION OF BIM IN JANUARY 2010 AFTER IT WAS DISCOVERED THAT THE UNIVERSITY SAVED A SUBSTANTIAL AMOUNT IN THE CONSTRUCTION OF A NEW LABORATORY BUILDING BY USING BIM. TO BEGIN THE BIM INTEGRATION PROCESS, THE ASSISTANT ASSOCIATE VICE PRESIDENT PROVIDED SUPPORT FOR THE APPLIED FACILITIES RESEARCH GROUP (AFRG) TO BE FORMED. THIS GROUP WAS TASKED TO IMPROVE THE EFFICIENCY OF INTERNAL AND EXTERNAL PROCESSES PRIMARILY THROUGH THE USE OF BIM.

THE AFRG BEGAN BIM IMPLEMENTATION BY RESEARCHING THE PHYSICAL PLANT'S ORGANIZATIONAL STRUCTURE AND INTERVIEWING ALL DIVISIONS WITHIN THE ORGANIZATION. THE INTENT OF THE INTERVIEWS WAS TO LEARN EACH DIVISION'S INTERNAL PROCESSES, RESPONSIBILITIES, STRENGTHS, AND CHALLENGES. AFTER EACH OF THE ELEVEN DIVISIONS WITHIN OPP WERE INTERVIEWED AND ANALYZED, THE WORK CONTROL CENTER¹¹ AND DESIGN & CONSTRUCTION¹² WERE IDENTIFIED AS HAVING THE GREATEST POTENTIAL FOR BIM. THE TEAM BEGAN WORKING WITH THE TWO DEPARTMENTS DEVELOPING PROCESS CHANGES AND INFORMATION REQUIREMENTS WHICH WOULD ALLOW THE INCORPORATION OF BIM.

IN DECEMBER 2010 THE AFRG PUBLISHED THE FIRST VERSION OF BIM REQUIREMENTS FOR NEW CONSTRUCTION. THESE REQUIREMENTS WHICH INCORPORATE MANY OF THE NEEDS OF BOTH THE WORK CONTROL CENTER AND DESIGN & CONSTRUCTION ARE THE FIRST STEP TO FULL BIM INTEGRATION, BUT THERE IS STILL SIGNIFICANT EFFORT REQUIRED TO FURTHER ADVANCE BIM USE WITHIN THE ORGANIZATION

(The Computer Integrated Construction Research Program, 2011).

¹¹ The Work Control Center department plans, prioritizes, and schedules maintenance, repair, and renovation work at Penn State's University Park Campus.

¹² The Design & Construction department oversees all design and construction at Penn State's University Park Campus. They are composed of five sub—divisions: Construction Services, Contract Administration, Design Services, IT Support Staff, and Project Management.



This report recognized that the Work Control Center consists of one of the most advanced asset management staffs in the country; however, it takes as much as two years to incorporate new asset data after substantial completion of the project. A reduction in the delay is possible if asset information begins incorporation during the construction processes by developing a more appropriate translation of construction to facility maintenance information. Additionally, the Design & Construction department was recognized in having no requirement for record modeling, and no process of updating "as-maintained" models. Although a more developed interface for document databases will not fix the training and competency needed to manage models, a manage file of as-built models and drawings should be provided in a way where revisions can be modeled directly into the file, and saved, without having to reattribute and save as a new file. Ideally, these updates should be tracked, with revisions of each update archived for reference if needed.

ANALYSIS INFLUENCES

OWNER INTERVIEW¹³

On January 31, 2012, a phone interview was conducted with Richard Montalbano, who is the Vice President and Project Executive for Albert Einstein Healthcare Network, and is overseeing the design, construction, and operations of the New Regional Medical Center. Using the guidance provided in the CIC Research Program's "Case Study Procedures," the interview consists of predetermined interview questions.

Below is an overview of the outcomes of the interview.

DESIGN AND CONSTRUCTION

Q: How are projects procured?

A: Design-Bid-Build with a CM hired for construction services. Due to funding from the state or government programs, the only way to integrate a CM for collaboration early into the process is hiring them for preconstruction services.

Q: What is the level of participation?

A: There is a project executive overseeing the project development and the construction phase. As needed, other members of the New Regional Medical Center, Inc. become involved. Although the facility management staff is not directly incorporated in the process, great efforts are provided to procure the most practical design for the patient and the facility staff.

Q: Has the Owner used BIM on prior projects?

A: BIM has not been used by the Owner on previous project. Although the project team may use BIM in the design process for internal benefits, the Owner does not request any BIM specific components.

Q: How is a facility handed over?

¹³ Richard Montalbano - Vice President & Project Executive, Albert Einstein Healthcare Network



A: The facility is handed over after substantial completion, which allows the Owner to finalize outfitting the medial equipment and training staff member. A model is not provided to the Owner at turnover.

Q: How do you manage as-built & record drawings?

A: The as-built and record drawings and specifications are provided to the facility management department for archival and reference when needed. No commentary on the condition and quality of these drawings. Lack of accuracy was mentioned, which permits for debate over the need for maintenance and updates of facility information as renovations and installations occur.

FACILITY MANAGEMENT

Q: What are the Facility Management staff's primary duties?

A: The facility management staff's primary duties are to locate, interpret, and correct problems. Additionally, they manage the asset database for the healthcare network, and handle maintenance schedule for corrective, preventative, and emergency procedures.

Q: What information do they manage?

A: They manage as-built and record drawings for their facilities. This also includes the library of specifications, operations and maintenance manuals, and finish submittals. The current format that the information is stored in consists of both paper documentation and electronic formats. The team does not have 3D models of any assets or facilities.

Q: What do they use to manage this information?

A: Asset management software was not provided; however, the current task of management was considered a challenging process and involved great efforts to update the process with the incorporation of a new facility and medical campus in the coming years.

Q: Do they share/receive information from other departments?

A: Information shared and received through other departments consisted of paper copies, email, or integrated into their asset management or work order programs. Asset information is taken off of record drawings and specifications.

Q: What issues do they experience with their facilities?

A: The facilities within the healthcare network are very old, and have very old documentation which is not necessarily accurate, nor do some of the documents exist. With a variety of format, there is never an easy way to solve the issue at hand. There is currently a plan room located at the existing campus to host the documents for reference; however, organization and accessibility for off-campus facilities [the new hospital] could be a challenge.

Q: What would assist them in doing their job more efficiently?

A: The implementation of electronic documentation and databases, with minimal training, will make their workflow more efficient. Faster access to the necessary documents, and ability to view, update, and override current documents. Eliminate duplicate sources and "out-of-date" plans.



Q: Who are the best people to work with in order to gain information on day-to-day processes?

A: The facility management staff is the best people to contact for more information regarding the workflow of daily tasks. Additionally, anyone with similar healthcare FM management would be assistive. However, note that the current staff is resistant to change, notably with all data located in a model, which would be inefficient for them to access due to lack of experience. Consider giving them options for various methods of accessing information.

Additional Comments:

- In order to incorporate BIM, the FM staff needs the hardware, software, and training capabilities.
- The Owner need to furnish continued training and development once BIM becomes incorporated in order to accurately take advantage of the system, unless a detached, viewer concept is developed, with certain team member with training for updating models and databases.
- Great deal of resistance for FM staff to use a computer keyboard, mouse, and small screen to use drawings and specifications. The staff is hands-on and prefers large work plans in order to get multiple team members involved in investigation.
- Tablet utilization would be helpful; however, no current system to efficiently incorporate them.
- Finding the room information, location on a plan, equipment in the room, etc. fast is important.
- The ability to review the information remotely (not in the plan room) would be helpful.
- Photographs of key locations, assemblies, etc. would be more helpful then plans in understanding what is in place in the facility.
- Want to understand how to modify, and "exchange" a new OR layout into an existing OR, utilizing BIM to minimize rework, and understand the depth of the renovated to minimize the downtime of the space.

CONCEPT A: FM DASHBOARD DEVELOPMENT

In order to anticipate a particular portion of industry commentary at the *BIM Planning Education Session*, in addition to creating additional interest regarding research in construction and facility management document controls, a Facility Management Dashboard will be developed for the New Regional Medical Center. The basis of this dashboard is to reflect recent trends in information exchange and technology being discussed by the industry and researchers, alike. Additionally, the solutions created within the dashboard are designed in a way to reflect commentary received though industry articles, case studies, and interviews. Throughout development, consultation with user groups will be performed to enhance the analysis, and detailed as feedback. Common observations will be reflected in the final adaptation of the document dashboard, which is located within the <u>AE Senior Thesis E-Portfolio</u> under the FMPortal tab. *Note: a password is required for access. To request the password, consult the "Student Biography" section and make request via email.*

DASHBOARD CONCEPT

During investigation and development into new options and methods of embedding pertinent information in a model, it was recognized that although logical, there is a much stronger solution, which permits a majority of the data to be developed into usable facility-management information in its original form. Although this does not precisely provide a 'BIM' deliverable which many Owners are beginning to analyze, it does answer many other concerns and questions. The development of this dashboard concept was derived through direct



interview of the needs and capability of the Owner's facility management team, and the status of much of the documentation they were requesting.

The development of this interface provides many layers of solutions to resolve, expedite, and transition the New Regional Medical Center into a digital facility management interface. Figure 41 presents the key data the Owner would have requested for a digital turnover if this system was currently on the market.

The essential logic behind the system is a very simple file structure, which hosts all of the necessary digital files, as explained later in Figure 45. As the life-cycle of the facility evolves, these original files can be updated or overridden, providing the facility team to always have access to the latest files, and system information. Once these files are formatted properly and linked to each other, much of which is performed already by leading construction firms during the preconstruction or construction process, the data and exchanges between documents and into other facet of project information becomes available.

In order to develop a user-friendly system, that is accessible via any internet connection, and any style of mobile device, it was decided that an HTML format, or other web-based platform, is most appropriate. Utilizing the background file structure as the host, the data can be developed (or operated) by either a construction firm – as part of a lifecycle facility management program, or by the Owner – as their own internal system in which multiple projects can be hosted, maintained, and controlled by their own IT Department. This dashboard is configured as a database which hosts access points and document information in order to quickly access and solve typical facility management inquiries.






FIGURE 41: DASHBOARD COMPONENTS

Due to the research goals to understand document exchanges and interactions between different project mediums, the dashboard interface was developed in dreamweaver, following simple HTML coding practice, and including some additional javascript functions to simulate organizational options and usability feedback from the associated testing groups.

One of the key concerns from the Owner's perspective was document security as all of their project documentation will be placed on a server that may be access from outside of the network. Similar to current construction document interface, such as Prolog, a username and password would be required for access. Additionally, depending on the level of development, expertise of the members coding the dashboard, in addition to the requests of the Owner, multiple security tiers could be developed and associated with each username. This would in effect, control the user's interface and dictate limitations to opening, overriding, and updating data within the interface and the project's file structure. In order to suggest this option, the document dashboard developed in tandem with this report includes a login script as shown in Figure 42.



Document Management Portal

The New Regional Medical Center | East Norriton, PA

💿 The page at ww	w.engr.psu.edu says:
Please enter your Management Por	password to view the Document
	OK Cancel

FIGURE 42: WEB-INTERFACE LOGIN SCRIPT

Currently the New Regional Medical Center's campus will open with two facilities on the property. With time, additional facilities associated to the healthcare network will begin to populate much of the surrounding space available on the campus. As this occurs, the Owner will request the development of multiple Project Pages within the dashboard in order to properly organize the project and facility information as the campus grows. This would be a similar situation to a University or other large Owner-group. As an internal facility document management system to a healthcare or university provider, they will easily be able to add facility, assets, and new document exchange concepts without reliance on a particular firm to construct the entire campus, in addition to hosting all of the document management exchanges.

Document Management Portal

The New Regional Medical Center | East Norriton, PA



Enter Project Site

This interface was last updated by Brian Nakas and is hosted by the AE Department © 2012. This site is for educational use only.

FIGURE 43: PORTAL HOMEPAGE



Although the documents are managed through a server and can be accessed directly, the dashboard concept provides the ability to build a digital planroom environment. This room would consist of touch screen monitors, multiple tablet PCs, in additional to the necessary desktop computer stations. The goal would be to engage the Owner in a paperless facility management system, in unison with the construction team. The project homepage, as shown in Figure 44, was develop in collaboration with the Owner, and was based on the logical workflows the facility management team experiences during their inquiry.

- (1) Provided Room Name need to access particular data concerning this space
- (2) Provided Renovation Request need to access overall plans in all disciplines to investigate
- (3) Provided Design Alternative need to access and develop alternate models of the new space
- (4) Provided Work Order need to access Equipment or Submittal data for maintenance/reordering

These inquiries outline the initial application and investigation into the facility documentation. Once inside each method of information organization, applicable components will create links and dialog with other components and make transitions into other file types seamless.



FIGURE 44: PROJECT HOMEPAGE



FILE STRUCTURE MANAGEMENT

The file structure for the Document Management Portal can be seen in Figure 45. The key to file develop for this concept is to adopt a logical structure prior to development. Although much of the interface is linked via relative-links, if documents are moved or relocated, some of the pages may not work properly or locate the information as needed. Another key goal is to identify the major turnover items and create catagories for their use. Additional use of the dashboard may be considered for during the construction process, or as a combined construction – facility management information exchange program. Note that if this system is developed, the related folder file structure must be thought out to accommodate how the construction project team members utilize the structure in relation to how the facility management team and Owners organize this information .




FIGURE 45: FILE STRUCTURE

DATA MANAGEMENT CONCEPT

ROOM LOG DATABASE

The room-log database section references components located in multiple folder systems within the file structure shown in Figure 45. This logic permits the files to be updated and modified as necessary within the lifecycle of the facility, and the room log automatically reference the new components. This builds on the concept of a single-source document enterprise. All of the references in the room log can be accessed through other pathways in the dashboard; however, this section is organized by room number, permitting the user to easily obtain all of the necessary documentation for reference. The intial access of the page promts the user to select the floor level in which the room is located on. Once the rooms are loaded below, a series of drop-down menus host all of the data links. Notable features include the 180 degree photography. This concept was developed off of concern that as-built drawings are not necessarily accurate to what is in place; however, with a photograph, all of the elements can be defined. The photos can be taken as a particular point in construction



or at building turnover as requested by the Owner. These images contain hotspots which also link to pertinant information depending on the photo's progress.



FIGURE 46: ROOM LOG DATABASE WEBPAGE




FIGURE 47: ROOM LOG [ENLARGED]



AS-BUILT DRAWINGS

The as-built drawing section references the 'As-Built' file structure and permits direct access into the drawing file of reference. These drawings contain hyperlinks on common details, such as building sections, elevations, and wall details. Utilizing the hyperlink capabilities of software such as Adobe Acrobat Professional or Bluebeam CAD Revu, links can be embedded in the construction documents, or after the construction process is completed, and saved into the documents. As long as the links are embedded as 'relative path' items, the file structure can be relocated without losing operability. The as-built drawing section provides an entry point into the plan set. Once a sheet is opened, users can navigate the plans utilizing the hyperlinks to access additional drawings for more details or information.

				-	
The second		-			9
*	COL -			-4	Ites
			-	-	Paraset and
AS-BUILT	- www.ball	UCULT STATE		r . A	1/1/1/2000

SELECT DISCIPLINE TO ACCESS AS-BUILT DRAWING LOG

ARCHITECTURAL	
 CIVIL	
ELECTRICAL	
 FIRE ALARM	
FIRE PROTECTION	
FOOD SERVICE	

FIGURE 48: AS-BUILT DRAWINGS WEBPAGE

AS-BUILT MODELS

The O&M data section references the 'As-Built' file structure and permits direct access into the model files of reference. These models contain the overall geometry used in the design process, and updated to reflect the as-built conditions of the facility. The page is configured to permit two levels of document access. The 'viewer' option only permits viewer capabilities of the models. This file will open in the file format according the the selected type. Additionally, the 'manage' option will open the editable file, and will also permit the document to be saved, allowing the user group to make updates as the facility is renovated. Once updates are complete, the user may created a new 'viewer' file and override the old version, permitting the latest file to be referenced by others. The level of detail and the quality of information embedded in the model can be designated in the BIM execution plan for the project. Since this webpage creates an access point into the files, any style or level of detail model can be incorporated into the page.






FIGURE 49: AS-BUILT MODELS WEBPAGE

SUBMITTALS | O&M DATA

The Equipment Manual tab in the O&M data section references the 'O&M Data' file structure within the 'Construction Documents' folder, and permits direct access into a log of equipment in the facility for reference. This page has be developed under the concept that the user will know the equipment name, permitting query to open for additional equipment information and direct access into the equipment manual file. Additionally, this drop-down menu includes the room locations of the equipment, a service log or link to an asset management structure, a direct link to the manufacturer, and the contact information of the subcontractor or supplier of the equipment for servicing or replacement parts. Although similar information can be embedded into a model, this pages provides ease of access for users not familiar with model navigation.



FIGURE 50: O&M DATA WEBPAGE

Similar to the Equipment Manuals tab, the Submittal Database tab references the 'Submittal' file structure within the 'Construction Documents' folder, and permits direct access into a log of approved submittal processed during construction, for reference. This page has be developed under the concept that the user will



know the submittal log number, or have developed a naming system to permit a search filter of the page. This section also includes a drop-down development, allowing users to easily scan the submittal log, and quickly access important information regarding the document. If necessary, a link is provided for the option to open or download the approved submittal for reference. Additionally, the drop-down menu includes the related discipline of the submittal, a direct link to the manufacturer, and the contact information for reordering replacement materials. Although similar information can be embedded into a model, this pages provides ease of access for users not familiar with model navigation.



FIGURE 51: SUBMITTAL WEBPAGE

TRADE DIRECTORY

The Trade Directory section references the 'Trade Directory' file structure within the 'Construction Documents' folder, and permits direct access into a PDF file containing the contact information in addition to scope of work to trades accociated with construction and renovation of the facility, for reference. This page has be developed by loading a PDF file into the internet brower interface. The document contains hyperlinks to email addresses, which permits direct means of contact if the mobile device or workstation is configured with email software. Within the file structure, the original excel file can be opened and updated as needed. By resaving as a PDF document within this file structure, the webpage will automatically update to include the new information. It has been discussed that the ability to submit a new entry via the webpage may increase usability of the directory. After research in webcoding to perform this task, it was decided that the frequency of adding new contacts does not offset the additional effort to develop the javascript and it also increases the load time of the page.





FIGURE 52: TRADE DIRECTORY WEBPAGE

$Feedback^{14}$

COMPLETED ITEMS

- Include a room log for quick access to pertinent information (Mort).
- Incorporate as-built photography to help identify in-wall or above ceiling scenarios (NRMC).
- Simplify file structure and development in construction to transfer into facility management (AE).
- Include submittal items, as not all components are represented with an O&M manual (GBCo).
- Link related sheets and details to show capabilities of interactive PDF documents (Mort).
- Include a combined model (for viewing only) which shows all modeled elements of a room (NRMC).
- Include hyperlinks to access free viewer software for various software platforms utilized (Mort).
- Password protect pages to show capabilities to create usernames and access restrictions (NRMC).
- Include links to editable files, notably for models, for "as-maintained" modeling (NRMC, Mort).
- Make As-Built Drawing Log "interactive" to simplify the page layout (Mort).
- Hotspot the image to hyperlink to related information (NRMC).
- Test the configurations on multiple browsers, tablets, smart phones, and touch screens (Mort).

ITEMS FOR FUTURE RESEARCH

- Permit the room models to show alternative design concepts (NRMC).
- Include an updatable Trade Directory via a web submission form (GBCo).
- Include RFI documents so when referenced in PDF plans, the hyperlink loads correctly (GBCo).
- Design a welcome page to show capabilities for multiple buildings (AE).
- Look into ability to make an integrated construction/facility management information system (AE).

¹⁴ Feedback and input provided by the New Regional Medical Center, Inc. [NRMC], Gilbane Building Company [GBCo], Mortenson Construction [Mort], Penn State AE Faculty [AE], and Penn State's Office of the Physical Plant [OPP].



CONCEPT B: FM INTERACT DEVELOPMENT

With the development of the FM Document Dashboard, further interest engaged the ability to streamline this process, and eliminate the need for custom pages, each with their own embedded links and images. With the ability to create a database with Microsoft Excel, and include various file types, metadata, and hyperlinks, a more concise and fine-tuned deliverable can be created quickly and easily.

Additionally, this method creates the ability to leverage open source programming and development tools through Microsoft Live Labs and Silverlight, creating an interactive, streamlined, and customizable document management portal, hosted via a webserver or on a local computer.

Although the FM Document Dashboard provides accessible information to an owner during the lifecycle of the facility, the setup process can be laborious depending on the format in which the document are developed during the construction process. Without a commitment to this interface at project startup, it is very challenging to integrate this system as an after though. With the FM Document Dashboard moving past a "Prolog Web" interface and into a more visual stimulating and easier to navigate interface, it still does not create an open web of document correspondence and relationships, as desired.

Through more defined exploration into html code and software development, a stronger understanding of enterprise-sized document exchanges were found, in addition to how to properly attribute and search metadata. Without the utilization of an enterprise server, such as Oracle, to host and develop the infrastructure, it is challenging to host this interface in an efficient manner.

"A FM DOCUMENT INTERFACE SHOULD NOT CONSIST OF A SERIES OF INTERNET PAGES BUILT AROUND A SPECIFIC ATTRIBUTE; IT SHOULD CONSIST OF AN INTERFACE WHICH READS A DATABASE OF RELATIVE INFORMATION, DATA, AND ASSET." Dr. Craig Dubler, Office of the Physical Plant [PSU]

Through this concept, inquiry was reached though the identification of Microsoft Silverlight's PivotViewer, and the ability to transform document management from a paper based, or website page interface, into a single source viewers for document controls and facility information access.

The concept is called "FM Interact." It is hosted through a webpage, however, it features an interactive system which reads an excel database which displays inquiries -- sorting, and distributing information to identify results, trends, and an overall understanding of relations within the FM documents embedded in the database. Additionally, specific information and links can be attributed to the information, permitting accessibility and additional inquiries to drive down to the ideal document.

FM Interact becomes a visual tool, as opposed to a windows explorer file folder system. It permits stronger interactions between relevant information, it hosts all the data as single source, and it still permits a database for information updating, addition, and deletion as the life-cycle of the facility progresses.

INTERACT DATABASE CONCEPT

The driving force behind the investigation of an FM Interact concept, through the utilization of Microsoft Silverlight and Pivot Viewer, is to create a more efficient and accessible format to access construction photos during the life cycle of the building. Additionally, lifecycle photos can be added to the interface, permitting a photo log of searchable, and relatable images. Through additional investigation, other document formats can be included as hyperlinks within this interface, permitting the viewer to sort the data as necessary, while also allowing accessibility into the original file when needed.



Current PivotViewer applications include interfaces developed by companies such as Netflix, as shown in Figure 53. PivotViewer allows visitors to search large amounts of data easily and effectively. Additional sort critera can be applied in order to narrow in on related documents, as shown in Figure 54. Through the utilization of the open source programming, the host only has to identify which data collection to reference, and the user interface allows them to apply controls and access search and sort criteria of the information, as shown in Figure 55. Finally, once an element is selected, specific data regarding the document which has been included in the database is shown in Figure 56. This information can include descriptions, metadata, hyperlinks to external sources, and are completely customizable




FIGURE 53: PIVOTVIEWER NETFLIX APPLICATION




FIGURE 54: DEEPZOOM CONCEPT



Clear	All (3
Search	3	ρ
Rating		
Genre	(8
Sort: Quantity		
 Documentaries 	138	î
Dramas	115	
Comedies	84	
Foreign Movies	84	
Independent Movies	74	
Biographical Documenta	55	
Social & Cultural Docum	55	
Action & Adventure	52	
TV Shows	50	
Independent Dramas	47	
Romantic Movies	46	
Thrillers	42	
Foreign Dramas	41	
Children & Family Movie	38	
Crime Thrillers	30	
Independent Comedies	30	
Movies for ages 8 to 10	29	
Historical Documentaries	28	
Political Documentaries	27	
Action Thrillers	26	
British Movies	25	
Family Features	25	Ŧ
MPAA Rating		
Year	(8
Cast		
Director		
AvailableFrom		
AvailableTo		

FIGURE 55: CUSTOM FILTER PARAMETERS



	lut	-		- +
	+∣ →			٦
	180° S	outh		
	rvon Cho van trip t America, surfer-m 2007, by	by pioneering ouinard's free to Patagonia, a band of bli ountaineers s boat to rei n this advent	wheeling South ss-seeking ets out make the	1968
1 1 1 1 1 1	documer ouddies the Galar sland be a region	ntary. Jeff Joh hug the coas pagos Islands fore arriving that's still bre esieged by er	nson and t, stopping and Easte in Patagor eathtaking) at er nia but
N	Less			
	Rating 4.2 Genre Docume			
1	Sports D Sports N Travel 8	Adventure D	s	
	MPAA R PG	ating		
	Year 2010 Cast			
	Keith Ma Yvon Ch Timmy (ouinard		
	Jeff Johr Doug To Makohe	nson ompkins		
	Director Chris Ma Available June 8, 1	alloy	10	
ik V2	Available January	eTo 1, 12:00 AM,	2100	
-				
L				

FIGURE 56: CUSTOM DATA ENTRY & DOCUMENT RELATIONSHIPS



Although this system has never been used for document management and correlations, it has been recognized that if proper filter tabs are created, this interface would prove to be a strong candidate for facility management data retrieval. With the ability to create relationships and data standards, the user can quickly identify a room, building sector, level, or even a piece of equipment, and narrow in on the documents pertinent to their query. Once they reach the level necessary, the user can scroll though the remaining document and open their source file.

Currently this system is operated by hosting an image set to associate all of the files together. The current obstacle is that in construction documents, other than photograph, every other medium is utilized. In order to wrok beyond this restriction, the developer can create an image from the first page of the document, or construction drawing, and export that as an image, creating the placeholder in the system. Once this image is referenced, the attributes can be added, and the original file type referenced via a hyperlink. Additionally, through the use of an additional filter parameter which identifies the facility name, multiple facility's doucments can be hosted in a common file. This concept would be used my effectively for an owner, such as the New Regional Medical Center, who plans to host multiple buildings within a campus. Additionally, one could step even deeper, adding a campus category, allowing a single document to host all construction and life cycle documents for all of their facilities and assets. Table 18 contain the capabilities of how all of these documents can be organized and related for Facility Management of construction and life cycle documents for the New Regional Medical Center.

Filter Parameter	Document Data & Relationships		
System	Construction Photos, Submittals, Request for Information, Contract		
	Drawings, Design Model, As-Built Model, Equipment Data Sheet		
Zoom Format	JPG, TIFF		
Link to Original File	JPG, PDF, RVT, DWG, NWD, DOC, XLS, SKP, Hyperlink, Other		
Document Name	Individual Description		
Campus	East Norriton		
Facility Name	New Regional Medical Center		
Building Sector	A, B, C, D, Central Utility, Site		
Floor Level	Ground Level, 1, 2, 3, 4, Roof		
Room Number	####		
Date Added to Database	YYYY-MM-DD		
Model/Drawing	Yes, No		
CSI Discipline	## - Title		
Bid Package #	BP ##		
Trade Contractor	Company Name		
Trade Contact	Contact – linked to email address		
Design Team	Company Name		
Design Contact	Contact – linked to email address		
Construction Manager	Company Name		
Construction Contact	Contact – linked to email address		
Asset Management	Hyperlink to external software/file		

TABLE 18: PIVOTVIEWER FOR FACILITY DOCUMENT MANAGEMENT



OUTCOME

This analysis focused on the research into the development of an accessible, easy to use, and updatable, document management system for the facility management team after the construction of the building. Through industry discussion, interface development, and continued feedback from the user group, it was identified that this system is critical to streamlining the workflow of a facility management team. By creating not only a database system for a post-construction document turnover, but one which can be updated, and expanded upon during facility use, this concept leverages technology in a new and innovative way to provide digital toolsets and document controls to the end users.

Through the development of the FM Document Dashboard, difficulties in working in html links surfaced, helping to dictate and develop a file management structure in order to easily store and access documents for reference. Additionally, though the web development of this concept, many of the advantages and disadvantages of opening files beyond a PDF in an internet explorer window. With the application of the research theory in this analysis, recognition was made on the development of a more concise and easy to use photo log of the facility. With this concept, FM Interact came into perspective. With added insight into this software platform, and the capabilities to access the information both locally and over the internet, developed was reached to identify how to host other file formats, and finally the most efficient way to create view filters and set up the document data for the software to build the relationships.

Moving from research insight, into baseline application development through Dreamweaver, and finally into advanced document controls though PivotViewer, this analysis reached well beyond its intention to analyze document exchanges. With the application of both the FM Document Portal and FM Interact, new methods on how to efficiently transition between related file types was created, quickly and accurately accessing the necessary data for facility management through a user friendly interface.

Reflection

It is believed that this analysis confirms the capabilities of new approaches to document controls and turnover packages for an owner. Although a digital turnover interface is not included with the original package of the New Regional Medical Center, with development, the concepts shared through this research will permit the Owner to incorporate the ideas into their new healthcare campus in East Norriton, PA. Due to the current state of the industry, and much unknown about value-added features of VDC applications for building turnover, very little is expected. With the release of Penn State's CIC guide for "Owner Execution Planning," great strides will be made to assist Owners and project teams in the proper direction regarding data management and delivery methods.

With the growing appeal of implementing BIM and other data management tools into the modeled components, one must be cautioned if this is necessarily the most efficient package. Although all of the information would be stored and cataloged within the model elements, the information retrieval may not be the most efficient process for a user group. By providing new methods such as an FM Dashboard and FM Interact to host the BIM packages and construction documents in a simple interface, the user group can easily sort through great quantities of documents to find applicable items. Once sorted, they can then continue deeper into the document file, whether it would be a BIM model, a contract document, or photograph, and quickly retrieve their inquiry.



RECOMMENDATIONS & CONCLUSIONS

The New Regional Medical Center was analyzed throughout the academic year, providing the basis for the development of research and evaluation of four construction management concepts, centered on the theme of implementing virtual design and construction methods within each of the phases of a project. Once an understanding of the existing conditions was developed, four analyses were conducted to implemented prevalent and new industry technologies into this project. These topics include:

- BIM in Preconstruction
- Redesign of Atrium Enclosure Process
- Redesign of Structural Pour Strip
- Document Management for the Owner

The following conclusions have been reached through the each analysis process, as detailed in this report.

ANALYSIS 1 | BIM IN PRECONSTRUCTION

QTO & ESTIMATING

Model-based estimating is a growing VDC concept within construction firms. Over the past few years, industry leaders have begun developing internal processes in order to identify and understand the capabilities of this method. This analysis investigated the implementation of this strategy for estimating the structural bid packages, identifying strengths, weaknesses, and industry growth.

The structural steel Revit-based estimate produced a cost of \$7,710,326, which is 0.50% above schedule of values logged for this system. Additionally, it was 8.82% more accurate than Gilbane's traditional quantity takeoff method, reducing the preconstruction bid package estimate by \$635,361. The cast-in-place concrete estimate was not as successful, resulting in a 10.70% deviation for the schedule of values for construction.

It is recommend that firms begin using 5D estimating for the basis of structural steel bid packages (Nahas, 2012) and interior partition bid packages (Kreider, 2009). Additionally, it is recommended that companies continue internal research in Revit-Based Methods concurrent to traditional estimating practices on more complicated modeled systems, such as concrete (Nahas, 2012), and curtain wall systems (Abousaid, 2010). Through implementation and continued development, construction firms can provide input and monitor design firms' evolution towards transferrable parameters and modeled features into an estimating matrix.

CRANE PLANNING & LOGISTICS

As the industry develops into a comprehensive usage of BIM, VDC solutions need to be derived to assist in areas beyond current application, such as estimating and coordination. Through the utilization of modeled components and attribute data, information can be extracted to assist with analysis to determine the most economical construction process for structural steel based on crane logistics.

This analysis developed a Microsoft Excel based visualization that identifies trending data regarding critical picks for steel erection. It was recognized that the workflow process of the structural erection of the New Regional Medical Center contained an oversize crane for 77% of the duration. Through this visual analysis of Revit-based data, it was recognized that construction by Sector is a more efficient process. In total, this analysis identified a new VDC method in order to highlight trending data within a structural steel model, and resulted in a savings of two weeks on the construction schedule, in addition to \$315,727 of the project cost.



It is recommended that VDC tactics be investigated in other facets of the industry. As displayed in this analysis, data stored within the models have usage beyond construction document development and facility management information. By capturing this data in new and innovative formats, visual relationships are recognized, identifying areas for improvement or reconsideration on a construction method.

ANALYSIS 2 | REDESIGN OF ATRIUM ENCLOSURE PROCESS

Prefabrication and unitization of glazing systems have been recognized for developing higher quality, faster installation, and a safer working environment. Similar to the applications of MEP prefabrication, the unitization of glazing units is a trending topic present in the industry. This analysis investigates the consideration of unitization of the atrium's curtain wall. Additionally, it includes a related architectural redesign to facilitate a safer installation process, and the reintroduction of public space removed during design development.

In order to create a safe working environment for the unitization of the curtain wall system, it was recommend by the subcontractor performing the work that floor level access at the exterior wall would assist with the placement and affixing the system to the structure. Paring their review with the recognition that public space for seating in the atrium is limited and would require relocating to the ground level, Level 1 and Level 3 were redesign to include a walkway area along the curtain wall. The costs of this addition amount to \$123,455. An aesthetically pleasing space was designed in order to improve constructability and eliminate a high-risk construction process on the site, while also providing a space for patient and visitors to enjoy the greenfield landscape surrounding the hospital. It was recognized that the unitization of the curtain wall system would reduce field assembly duration; however, require a 20-week lead-time to procure and assemble the units. Unitization would have only been logical if the glazing subcontractor was brought into the project earlier to assist with design development.

From this analysis, it is recommended that design teams review their curtain wall systems with a stronger focus. Additionally, obtaining a glazing subcontractor for consultation would also assist in design development in order to ensure that the expected product meets the schedule, cost, and quality level that the owner and construction team expects to produce. With the assistance of a prefabricated glazing system, the construction site requires fewer trades working in high-risk locations, in addition to less equipment on site. Finally, the key to this system being implemented is open communications and consultation during design development and design revisions.

ANALYSIS 3 | REDESIGN OF STRUCTURAL POUR STRIP

Constructability issues versus design decisions are consistently reviewed in order to understand the implication of a chosen system. It is commonly known that a structural pour strip is more difficult to coordinate in construction when compared to a typical building expansion joint. This analysis preforms a cost comparison of the systems to identify if the selected system is the best option for the owner.

This analysis identified that the building's pour strip system is a more cost effective design decision. The choice to utilize the pour strips over expansion joints saved the project approximately \$57,800. Although the expansion joint system permitted a simpler construction schedule, a decrease in the size of the foundation



system, and slight decrease in the concrete slab and metal deck, these reductions did not offset the increase in other system costs. The analysis also clarified that the building's pour strip system is a more aesthetically pleasing system and is preferred by the Owner.

It is recommended that other design teams and Owners investigate the implications of a pour strip within their facility in lieu of an expansion joint. Although the expansion joint provides a simpler construction method, the aesthetic results and additional costs may not be worthwhile. It has become commonplace that an expansion joint is more efficient; however, it is recommended that the design team or construction management firm use the design alternate process within Autodesk Revit to quickly analyze the cost benefits of a building pour strip, and cross-reference these outcomes with the intentions and goals of the Owner and facility user group.

ANALYSIS 4 | DOCUMENT MANAGEMENT FOR THE OWNER

This analysis focused on the research into the development of an accessible, easy to use, and updatable, document management system for the facility management team after the construction of the building. Through industry discussion, interface development, and continued feedback from the user group, it was identified that this system is critical to streamlining the workflow of a facility management team.

Moving from research insight, into baseline application development through Dreamweaver, and finally into advanced document controls though PivotViewer, this analysis reached well beyond its intention to analyze document exchanges. With the application of both the FM Document Portal and FM Interact, new methods on how to efficiently transition between related file types was created, quickly and accurately accessing the necessary data for facility management through a user friendly interface.

It is believed that this analysis confirms the capabilities of new approaches to document controls and turnover packages for an owner. Although a digital turnover interface is not included with the original package of the New Regional Medical Center, with development, the concepts shared through this research will permit the Owner to incorporate the ideas into their new healthcare campus in East Norriton, PA. By providing new methods such as an FM Dashboard and FM Interact to host BIM packages and construction documents in a simple interface, the user group can easily sort through great quantities of documents to find applicable items.

It is recommended that Owners, notably from Universities and Healthcare Systems, begin to develop their internal goals of document management. Although construction companies will be capable of developing a web based interface and document controls for turnover, larger Owners should outline their own methods in order to streamline and combine all of this facilities into a common system.



RESOURCES & REFERENCES

Microsoft Excel. (2010). USA: Microsoft.

Microsoft Visio. (2010). USA: Microsoft.

Microsoft Word. (2010). USA: Microsoft.

CAD Revu. (2011). USA: Bluebeam PDF Revu.

Dreamweaver CS5.5. (2012). USA: Adobe.

Fireworks CS5. (2012). USA: Adobe.

Microsoft Pivot Viewer. (2012). USA: Microsoft.

Microsoft Silverlight. (2012). USA: Microsoft.

Revit Architecture. (2012). USA: Autodesk.

- Revit MEP. (2012). USA: Autodesk.
- Revit Structural. (2012). USA: Autodesk.
- Sketch Up 8. (2012). USA: Google.
- Abousaid, R. (2010). *Final Report: National Intrepid Center of Excellence*. University Park, PA: Penn State AE Department.
- Batten, A. (2012, March 22). Project Manager | R.A. Kennedy & Sons, Inc. (B. Nahas, Interviewer)
- buildingSMART International Ltd. (2012, March 13). *Open BIM Program for Improved AEC Collaboration*. Retrieved March 13, 2012, from buildingSMART: http://buildingsmart.com/openbim/
- Das, B. (2011). Principles of Foundation Engineering (7th ed.). Stamford, CT: Cengage Learning.
- *Environmentally Friendly Design*. (n.d.). Retrieved September 5, 2011, from Einstein Medical Center Montgomery: http://www.einsteinmontgomery.com
- Hodge, G. (2012, Feburary 13). Senior Project Manager | Mortenson Construction. (B. Nahas, Interviewer)
- Judy, S. (2011, August 1). Multivista Keeps Focus on Construction Images and Data. *Engineering News-Record*.
- Kreider, R. G. (2009). Senior Thesis Final Report The End is Only the Beginning. University Park, PA: Penn State AE Department.
- Leet, K., Uang, C.-M., & Gilbert, A. (2008). *Fundamentals of Structural Analysis* (3rd ed.). New York, NY: McGraw Hill.
- Manafy, M. (2011, November 29). Employing the Digital Native: Five Keys to Success. *Engineering News-Record*.

Moor, C., & Faulkner, L. (March 2012). Interoperability for Construction. Modern Steel Construction, 48-51.


Packer, A. (2011, September 16). Field Engineering | Gilbane Building Co. (B. Nahas, Interviewer)



- Packer, A. (2012, Feburary 7). Field Engineering | Gilbane Building Co. . (B. Nahas, Interviewer)
- Partnership Vision. (n.d.). Retrieved September 3, 2011, from Einstein Medical Center Montgomery: http://www.einsteinmontgomery.com
- Post, N. M. (2009, April 29). 3D Modeling Spurs Architect to Reorganize Division of Labor. *Engineering News-Record*.
- Ross, S. (2011, September 9). Case Study: Facilities Management as Engineering Deliverable. *Engineering News-Record*.
- Sawyer, T. (2011, March 7). Data for the Life Cycle. *Engineering News-Record*, pp. 26-32.
- Sawyer, T. (2012, March 12). Hot Tech Topics. *Engineering News-Record*, 24-29.
- Standing Committee on Structural Engineering of the Federal Construction Council. (1974). *Federal Construction Council Technical Report No. 65: Expansion Joints in Buildings.* Washington, DC: The National Academy of Sciences.
- Stein, B., Reynolds, J., Grondzik, W., & Kwok, A. (2006). *Mechanical and Electrical Equipment for Buildings* (10th ed.). Hoboken, NJ: John Wiley & Sons, Inc.
- The Computer Integrated Construction Research Program. (2011). *Case Study Procedure*. University Park, PA: The Pennsylvania State University's Architectural Engineering Department.
- The Computer Integrated Construction Research Program. (2011). *Office of Physical Plant Case Study*. University Park, PA: The Pennsylvania State University's Architectural Engineering Department.
- The Computer Integrated Construction Research Program. (2011). *Owner Execution Planning*. Retrieved March 10, 2012, from BIM Execution Planning: http://bim.psu.edu/Owner/default.aspx
- The Standing Committee on Structural Engineering of the Federal Construction Council, Building Research Advisory Board, Division of Engineering, National Research Council. (1974). *Expansion Joints in Buildings [Technical Report No. 65]*. Washington, D.C.: National Academy of Sciences.
- U.S. Architectural and Transportation Barriers Compliance Board. (2003). *Accessibilty Guidelines for Buildings and Facilities.* Washington, D.C.: U.S. Architectural and Transportation Barriers Compliance Board.
- Wojtak, M. (2012, Feburary 13). Integrated Construction Manager | Mortenson Construction. (B. Nahas, Interviewer)
- Wojtak, M. (2012, March 13). Integrated Construction Manager | Mortenson Construction. (B. Nahas, Interviewer)
- Wooley, L. (2010, May 24). HUD Approves \$292.5 Million Financing Plan to Build State-of-the-Art Hospital in East Norriton, Pennslyvania. Retrieved September 7, 2011, from U.S. Department of Housing & Urban Development: http://www.portal.hud.gov




APPENDIX A | ORGANIZATIONAL CHART






APPENDIX B | STAFF ORGANIZATIONAL CHART





APPENDIX C | GENERAL CONDITIONS PLAN





NEW REGIONAL MEDICAL CENTER

EAST NORRITON, PA

BRIAN NAHAS CONSTRUCTION MANAGEMENT


SENIOR THESIS FINAL REPORT

APPENDIX C

GENERAL CONDITIONS PLAN



APPENDIX D | STRUCTURE & ENCLOSURE PLAN





 (\mathbf{Z})



NEW REGIONAL MEDICAL CENTER

EAST NORRITON, PA

BRIAN NAHAS CONSTRUCTION MANAGEMENT

> SENIOR THESIS FINAL REPORT

> > APPENDIX D

Structure & Enclosure Plan



APPENDIX E | PROJECT SCHEDULE

E 481W - Senior Thesis															BRIA	N N/	AHA	s																								
													(CONT	RUCT			AGEN	MENT	-																						
ctivity Name	Start	Finish	Origin Duratio	ial ^{DN} O	Q ND	JF		Q A M	L		2 A S	D N I O		G J F	-	Q M	JJ	Q	S C	Q	J	Q	Q M A M		Q	S O	Q N I I		2 = м	Q A M		Q A S	Q O N		Q JEII	MA	Q MJ			Q O N	D,	Q
Total	01-Oct-07	15-Oct-12	130		: :		-			-					; ;				-		-			;							+ +											2, Tota
01 Design & Preconstruction	01-Oct-07	11-May-10	68	31													-							11-N	/lay-10	, 01 De	esign	& Prec	onstru	uction												
Preliminary Geotechnical Investigation	01-Oct-07	24-Oct-07		18 🗖	Prelir	hinary	, Geo	technic	al In	ives	tigation	n																														
Supplemental Geotechnical Investigation	13-Mar-08	02-Jun-08		58					н н.	- E	Ч I		eotec	hnical	Investi	dation	ו א																									
Civil Design	15-Jan-09	23-Oct-09	20	02											i i	7 ;	i	: i		Civil	i Desi	sign																				
Architectural Design	05-Mar-09	28-Oct-09			++							+						• +		Arcl	hitect	tural	Design		++		+-		· -¦								+					
Geotechnial Infiltration Testing	30-Jun-09	28-Aug-09	2	14															Geo	technia	ial Infi	filtrati	on Testir	nģ																		
Issue for GMP, Permits, PADOH Approval	09-Dec-09	-		0																•	lissu	ue for	GMP, P	Permit	s, PAD	OH Ap	; prov	al														
Issue for Early Bid	11-Feb-10			0																	1	1.1.1	sue for	1	1.1		ſ.															
Issue for FHA Closing	18-Feb-10			0			i			i										i i	i.	i i	ssue for	-i [- i i	a								1								
Issue for Construction	08-Mar-10			0	++		·					+						· +		·		-!!- :	lssue f				+-		· -¦ -								+¦					
Owner Review GMP & Award	18-Mar-10	11-May-10	(39																	Ì		1 1	1	1 1		MP &	Award														
02 Construction		31-Aug-12		53																				V															▼ 31	-Aug-	12, 02	2 Cons
NTP	01-Jul-10			0																					NTP																	
Site Clearing		24-Sep-10	ļ	58			-																	Ī			ite Cle	earing														
Excavation		06-Oct-10		35	÷										·			· :				+				المتعالم من ا	L L _	ation	·													
Foundations	-	09-Dec-10		50																								Found	, dation	s												
Incoming High Voltage Electrical	21-Mar-11*			65 65																	i.											mina	Hiah V	Initan	e Elect	rical						
Interior Framing		29-Sep-11		10																														1 E	raming	incar						
Building Enclosure	04-Aug-11 08-Aug-11	23-0ep-11	-	0																	i.											Built	ding Er	i i	1 1							
Substantial Completion	31-Aug-12			0					 																				·											hetan	tial Co	omplet
02.01 Structure	-	18-Apr-11	ç	39																								: :	1 1	▼ 18-/	Apr-11	02.01	Struct	ture					Ų Ju	DSLAIN		Sinpler
		17-Dec-10		15																									1 1	1 1	11 II	- 1 - 1										
F/R/P Footings & Retaining Wall				15			-																				i i] F/R/	i i	- i	- i - i	- i i	i i									
Structural Steel (Sequence 4 - 9)	13-Dec-1(14																	-							Str		ai Steel Iral Ste			1. 1									
Structural Steel (Sequence 10 - 15)	04-Jan-11*			12	<u></u>													·		·								ب الم الم الم الم						i - i -			+					
Structural Steel (Sequence 16 - 21)	04-Jan-11*			16																										ural Ste				1 1								
Prepare & Place SOD (Sequence 1 - 9)		04-Feb-11		10			i			i										i i	i.							1 1	1 1	are & F	1 1	1 1 1	1 I I	1 1	-9)							
Structural Steel (Sequence 22 - 27)		07-Feb-11		10			-																					- i - i -	- i - i	ctural \$	- i ii			- 27)								
Prepare & Place SOG		21-Feb-11		20																										epare 8												
Structural Steel (Sequence 28 - 33)		28-Feb-11		15	ļ				 -					 																ructura	$= - []_{-}$	2-9-2-9	!!	1								
Prepare & Place SOD (Sequence 10 - 15)		15-Feb-11		5																	i.									pare &		1 1		1 1	1 11							
Prepare & Place SOD (Sequence 16 - 21)		01-Mar-11		10			-																						1 1	epare	1 1			1 1	1 1	1)						
Structural Steel (Sequence 34 - 40)		24-Mar-11		18																									- i - i	Structu	- i - i -	- i i	- i - i	i i	- i - i -			: :				
Prepare & Place SOD (Sequence 22 - 27)		15-Mar-11		10																										Prepare				1 1								
Prepare & Place SOD (Sequence 28 - 33)		04-Apr-11		10	l		L		i i L.	L.				 								L.L.					L			Prepa				L J -	! !- !		4!					
Prepare & Place SOD (Sequence 34 - 40)		18-Apr-11		10] Pre∣												
02.02 Enclosure	22-Mar-11	01-Sep-11	11	16																												-v 0	1-Sep-	-11, 0	2.02 E	nclosi	ure					
Exterior Walls	22-Mar-11	03-Aug-11	ę	95																	Ì								📫			Exter	ior Wa	alls								
Curtain Wall Pre-Cast Section C	04-Apr-11*	12-Apr-11		7			-																							I Curt	ain Wa	ll Pre-	Cast S	Sectio	nC							
Curtain Wall Pre-Cast Section D	13-Apr-11*	21-Apr-11		7																										Cui	tain W	allPre	-Cast	Secti	on D							
Low Roof Section C	13-Apr-11*	17-May-11	2	25					,													- 					+- 				ow Ro	of Sec	ction C				 					
Metal Panels North	14-Apr-11*	18-May-11	2	25																											Metal P	anels	North									
Curtain Wall Pre-Cast Section A	22-Apr-11*	29-Apr-11		6					. 																					🛛 Οι	rtạin W	/all Pr	e-Cast	t Sec	tion A							
Low Roof Section D	22-Apr-11*	19-May-11	2	20																											_ow Ro	oof Se	ction D									
															Pa	ige 1 d	of 7									NEW	/ REC	GIONA			CENTE	ER										
Activity V Summary																	<i></i>																									
Milestone																										EAS	T NO	RRITO	N, PA	1												

															с							MEN	т																	
tivity Name	Start	Finish	Original Duration		Q		Q			ג		Q		Q		(ג		Q		Q		C			Q			ך ר		Q		Q	T	Q	\square		Q		
Curtain Wall Pre-Cast Section B	02-May-1 ⁻	13-May-11	10	0	Ν	D	JF	M	AN	ΛJ	J	A	s o	N	D	JF	M	A	M	IJ	A	S			J	F	М	AN	ΛJ	J	A	S		<u>J</u>	F	M	_	_	J Curt	
High Roof Section A	02-May-1 02-May-1	-	20																					·							++-					·			Hig	1
Metal Panels West	02-May-1 02-May-1		30													Ì																							i i	Me
High Roof Section B	20-May-1		20																																			-		
Curtain Wall Atrium	20-101ay-1 06-Jun-11*		40																																		Ì			ng
Metal Panels East	14-Jun-11*	-	30																																				Ċ	_
Metal Panels South	27-Jul-11*		10	4							·													·							++-					·				
High Roof Clerestory Curtain Wall	29-Jul-11*	-	10													Ì																					į			ĺ
Ground Floor South Elevation	29-Jul-11*	-	15	1																																				ĺ
Ground Floor East Elevation		-	10	1												Ì											Ì							į			į		- i	
	19-Aug-11	25-May-12						· · ·																											,					_
02.03 Ground Level								; ; ; ; ;						+													+													
Top Track	11-Mar-11*	•	20					· · ·																															Trac	
Spray on Fire Proofing (Interior Columns & Beam		-	15																																				ayo	
Frame & Drywall Non-Accessible Walls	08-Apr-11*		25																																	1		ļ	Fra'n	ne
Electrical Overhead Rough In	02-May-1 ⁻	26-Jul-11	60																																			-	-	
Sheetmetal Overhead Rough In	02-May-1 ⁻	26-Jul-11	60												41-																+									
HVAC Overhead Piping Rough In	02-May-1 ⁻	26-Jul-11	60																																					
Med Gas Overhead Piping Rough In	02-May-1 ⁻		60													Ì											Ì					i						=	—	
Pneumatic Tube Overhead Piping Rough In	02-May-1 ⁻	26-Jul-11	60																																			-	-	
Sprinkler Overhead Rough In	02-May-1 ⁻	26-Jul-11	60																													÷						÷	—	
F/A Security Overhead Rough In	10-Jun-11*	19-Aug-11	50																																				—	
Controls Overhead Rough In	10-Jun-11*	19-Aug-11	50																																				-	
Med Gas Overhead Distribution	10-Jun-11*	19-Aug-11	50																																				—	
Complete Frame Partition Walls	20-Jun-11*	01-Aug-11	30							i.						Ì								Ì			Ì					- i		į			į		Ļ	
Electrical In-Wall Rough In	30-Jun-11*	23-Sep-11	60																																				į,	
F/A Security In-Wall Rough In	30-Jun-11*	23-Sep-11	60													Ì											Ì							į			į		į,	
Controls In-Wall Rough In	30-Jun-11*	23-Sep-11	60			!									4!- 		-	*									+		!						- -		+-	-		
Med Gas In-Wall Rough In	30-Jun-11*	23-Sep-11	60													Ì								j.			Ì					Ì		į			į			
Pneumatic Tube In-Wall Rough In	30-Jun-11*	23-Sep-11	60					· ·																															į	
Drywall Paritions & Gypsum Ceiling	08-Sep-11	02-Nov-11	40																																					
Acoustical Ceiling Grid	26-Sep-11	28-Oct-11	25																																					
Light Fixtures in Acoustical Grid	17-Oct-11*	28-Nov-11	30			!												*								- -	+		!								+-			
Diffusers, Grilles, Registers in Acoustical Grid	17-Oct-11*	28-Nov-11	30																																					
Sprinkler Heads	17-Oct-11*	28-Nov-11	30																																					
Final Paint	14-Nov-11	11-Jan-12	40													÷																					į			
Electrical In-Wall Finishes	19-Dec-11	27-Mar-12	70																																					
F/A Security In-Wall Finishes	19-Dec-11	27-Mar-12	70									i		+				•						· •		-ii-	+													
Controls In-Wall Finshes		27-Mar-12	70																																					
Med Gas In-Wall Finishes	19-Dec-11	27-Mar-12	70																																					
Pneumatic Tube In-Wall Finishes		27-Mar-12	70																																					
Millwork		11-May-12	35																																					
Casework		11-May-12																						• • • • • •			+				++-				-ii -				-	
Electrical & Plumbing Tie into Casework		25-May-12																																						
02.03 Level 1	-	28-Feb-12																																		V	Ė	1	÷	_
Top Track	08-Apr-11*		10																																	ļ	.	Tor	p Tra	ac
· · · · · · · · · · · · · · · · · · ·		•								1	i		1			1		Doc		f 7	Ĺ		I	1						_			WREC					Ĺ		
Activity V Summary																		rag	e 2 c	n 7																VICL	104	AL		an I

Q	Q	Q		Q		Q			Q			Q		Q
A S	OND	JFN	/ A	ΜJ	J	А	s	0	Ν	D	J	F	М	A
Wall I	Pre+Cast S	ection B												
loọf S	ection A													
ıl 🛱 an	els West													
Roo	Section B													
Curt	ain Wall At	rium					į							
Meta	Panels Ea	ast	- L L											
Met	al Panels	South												
] ¦Hig	h Roof Cl	erestory	Curta	in Wal			į							
Gr	ound Flooi	South E	levati	ion										
	round Flo	or East E	levat	ion										
:				- 25	-Ma	ıy-1	2, 0)2.(03 (Gro	und	Le	vel	
		4 	+				!-							
ire Pr	oofing (Int	erior Coli	umns	& Bea	ms)									
k	vall Non-A	ccessible	Wal	s										
Electi	ical Overh	ead Rou	gh In											
Shee	tmetal Ove	rhead R	ough	In										
HVAC	Overhea	d Piping I	Roug	h lņ										
Med	Gas Overh	ead Pipir	ng R¢	ough In										
Pņeu	matic Tube	overhe	ad Pij	pinģ Ro	bugł	۱ In	į							
Sprin	kler Overh	ead Rou	gh In											
] F//	A Security	Overhead	d Roi	ugh In										
Cc	ntrols Ove	rhead R	ough	In										
∎ ¦Me	d Gas Ove	erhead D	istrib	ution										
Com	plete Fran	ne Partiti	on W	alls										
÷	Electrical	In-Wall	Roug	h ln										
	F/A Secu	rity In-W	/all R	ough li										
-	Controls	In-Wall F	Roug	n In										
-	Med Gas	1 1 1	- i - ī	1										
-	Pneumat	ic Tube I	n-Wa	III Roug	h In	۱								
		vall Pariti		·1 ·	um (Ceil	ing							
	🔲 Acou	stical Cei	ling 🤆	Grid									1	
		ight Fixtu												
	D	iffusers,	Grille	s, Regi	ster	s in	Acc	us	tica	l Gr	id			
	s 🗖 S	prinkler I	lead	S										
		Final	1 1	1										
		4	E	ectrica	l In-	W	all Fi	nis	hes	\$			1	
			1 1	ASecu										
				ontrols	н н		1	- 1						
			- 1 - 1	ed Gas		- 1	- i							
		: : :	Pr	neuma			e In-	Wa	all F	inis	hes			
					work									
					sewc									
				1	ectri				nbir	ng T	ie ir	nto	Cas	sew
			28-F	eb-12,	02.0)3 [eve	1						
R														

481W - Senior Thesis																	IAN			•																	
					<u> </u>		<u> </u>				_			C	ONT				ANA		MEN			_					_								
tivity Name	Start	Finish	Original Duration			JF			ว <u>งโ</u> ม		Q	slo	Q	D	Q J F			Q <u>м .</u>		Q A	S		ว N D		Q F	м		ב <u>ג ו</u> א	J	Q	s o		D.	Q J F		Q A M	
Spray on Fire Proofing (Interior Columns & Beam	15-Apr-11*	28-Apr-11	10	-		<u> </u>							1.1	-	<u> </u>						-	-		-					-				-	<u> </u>			
Frame & Drywall Non-Accessible Walls	22-Apr-11*	11-May-11	14	4					!					!						+								!		4 J - 1 - 1 1 - 1	!					F F	Fram
Sheetmetal Overhead Rough In	10-May-1 ⁻	06-Jul-11	40																																		
HVAC Overhead Piping Rough In	10-May-1	06-Jul-11	40																																		
Med Gas Overhead Piping Rough In	10-May-1 ⁻	06-Jul-11	40																																		
Pneumatic Tube Overhead Piping Rough In	10-May-1 ⁻	06-Jul-11	40																	1																	
Sprinkler Overhead Rough In	10-May-1 ⁻	06-Jul-11	40						!			!	+							+!								!		4 J - 	!				J L		
Electrical Overhead Rough In	01-Jun-11*	27-Jul-11	40																																		
F/A Security Overhead Rough In	01-Jun-11*	27-Jul-11	40																																		i,
Controls Overhead Rough In	01-Jun-11*	27-Jul-11	40																																		_
Med Gas Overhead Distribution	01-Jun-11*	27-Jul-11	40	į.																1							÷.										<u> </u>
Complete Frame Partition Walls	22-Jun-11*	20-Jul-11	20		 		- L J 		!			!		!						+!								!		4 J - 	!						
Electrical In-Wall Rough In	30-Jun-11*	09-Sep-11	50																	ļ																	
F/A Security In-Wall Rough In	30-Jun-11*	09-Sep-11	50																																		Ē
Controls In-Wall Rough In	30-Jun-11*	09-Sep-11	50																																		. 🗖
Med Gas In-Wall Rough In	30-Jun-11*	09-Sep-11	50																																		, i
Pneumatic Tube In-Wall Rough In	30-Jun-11*	09-Sep-11	50						!			!		!		· 4		!		+! ! ! !				-!	(1= = = 1= 1 1 1 1			!		4 J - 	!				Jk		t-
Drywall Paritions & Gypsum Ceiling	08-Sep-11	12-Oct-11	25																	1																	,
Acoustical Ceiling Grid	15-Sep-11	12-Oct-11	20																																		
Light Fixtures in Acoustical Grid	03-Oct-11*	28-Oct-11	20																																		
Diffusers, Grilles, Registers in Acoustical Grid	03-Oct-11*	28-Oct-11	20																																		
Sprinkler Heads	03-Oct-11*	28-Oct-11	20		 				!				1 J 	!						+							- 4	!			!						
Final Paint	04-Nov-11	02-Dec-11	20																	1																	
Electrical In-Wall Finishes	14-Nov-11	11-Jan-12	40																																		
F/A Security In-Wall Finishes	14-Nov-11	11-Jan-12	40	į																							į.										
Controls In-Wall Finshes	14-Nov-11	11-Jan-12	40																																		
Med Gas In-Wall Finishes	14-Nov-11	11-Jan-12	40						!				1	!						+								!			!	1 1					!-
Pneumatic Tube In-Wall Finishes	14-Nov-11	11-Jan-12	40																								÷										
Millwork	28-Dec-11	15-Feb-12	35																																		
Casework	28-Dec-11	15-Feb-12	35																																		, 1
Electrical & Plumbing Tie into Casework		28-Feb-12	15																																		
02.03 Level 2	22-Apr-11	28-Feb-12	217		 				!			!		!						+					·	+-		!			!	1 1				V	
Top Track		05-May-11	10																	1																t t	op T
Spray on Fire Proofing (Interior Columns & Beam	02-May-1	-	10																																		н ^с . н.
Frame & Drywall Non-Accessible Walls	-	24-May-11	10																																		ii
Sheetmetal Overhead Rough In	23-May-1	•	40																																		
HVAC Overhead Piping Rough In	23-May-1		40	· ¦ - ·																+												++					
Med Gas Overhead Piping Rough In	23-May-1 23-May-1		40																																		
Pneumatic Tube Overhead Piping Rough In	23-May-1 ⁻		40																	: :																	
Sprinkler Overhead Rough In	23-May-1 23-May-1		40																	; ;							į.										
Electrical Overhead Rough In	06-Jun-11*		40																																		
F/A Security Overhead Rough In	06-Jun-11*	-	40										+							+						+-						+					
Controls Overhead Rough In		01-Aug-11 01-Aug-11	40 40																																		
Med Gas Overhead Distribution		01-Aug-11 01-Aug-11	40 40																																		
Complete Frame Partition Walls	27-Jun-11*	-	40 20																																		
			20	1		1		-	1	<u> </u>		1	: :	1	1	: :		1	1	: :	1	1	1	1	: :		1	1		: :	1	: :	1	1	<u>: :</u>		
Activity V Summary																	Page	e 3 o	of 7												NEV	V RE	GIO	NAL	ME	DICAL	CEI
Activity Summary Milestone																	5																				

2	Q		Q		Q		Q			Q			Q		Q
ASO	N D	J	FM	Α	ΜJ	J	Α	S	0	Ν	D	J	F	М	А
Fire Proof	ing (Ir	iteri	or Co	lumr	ns & B	am	s)								
Drywall	lon-A	cce	ssible	Wal	s		L 								
neetmetal	Overt	lead	l Rou	gh Ir			1								
VAC Over	nead	Pipir	ng Ro	ugh	In		1		1						
ed Gas O	/erhea	id P	iping	Rou	gh In										
neumatic 1	Tube (Dver	head	Pipir	ng Roi	ıgh	In								
orinkler O	erhea	d R	ouģh	In			1								
Electrical	Overh	ead	Rộug	gh In			, , ,								
F/A Secur	ity Ov	erh	ead R	oug	n In										
Controls (Dverh	ead	Roug	h In											
Med Gas	Overl	ieac	l Distr	ibuti	pn		 								
Complete	Fram	₽ P	rtition	Wa	lls										
Elect	rical li	h-W	all Ro	ugh	In										
- i i i	. i	i i		1 1	ugh In		1								
Cont	rols Ir	i-W	all Ro	ugh	In										
💻 Med	Gas I	n-W	all Ro	ough	In										
		i i		- i - i	Roug	÷ .									
	- T				Sypsur	1 Ce	iling	5							
1 1 1		с I	Ceilin	ī I			, , ,								
	-	: :		1 1	oustica	1 1									
		!!	!		legiste	rs in	Ac	ous	tical	Gr	id				
	1	: :	Heac	1 1			1 1 1								
	- F		Paint	1.1											
		: :		1 1	In-Wa	1 1									
		: :		1 1	ty In-	1 1			es						
		11		- L	n-Wal	1 1	L								
		: :		1 1	In-Wa	1 1									
			1	1 1	Tube	In-V	Vall	Fin	ishe	es					
		: :	i	llwo											
		: :		asew		_			_						
				. L	rical &	1	L		!	}	Ca	sew	orl	κ 	
			- V 2	28-F	eb-12	02.	031	Lev	el 2						
<															
n Fire Pro	i i	i i	i i	i i		Bea	ms)								
& Drywall		: :	1	1 1											
Sheetmeta		41	i	· F 4											
IVAC Ove		: :					1 1 1								
/led Gas C	1	н н	· · · · ·	`н н											
Pneumatic	i i	i i	i i	i i	ing Ro	bugh	i In								
Sprinkler C		: :	1	1 1											
Electrical		41		· 4											
F/A Secu	-	: :		-											
Controls	1	! !		1.1											
Med Gas	i i	i i	i i	i i	i i										
Complete	Fram	e P	artițioi	n Wa	alls		1								
R															

E 481W - Senior Thesis											со				ANAC		ENT														
tivity Name	Start	Finish	Original Duration	Q O N		Q		Q M J		Q		Q	M A	Q		Q		Q N C		Q		Q		Q		Q		Q J F		Q	<u> </u>
Electrical In-Wall Rough In		07-Sep-11	50		DJ				JA		DJ				J	AS	10							JA	5			JF			l l
F/A Security In-Wall Rough In	28-Jun-11*		50							 								 						· - ‡			;;-				
Controls In-Wall Rough In	28-Jun-11*	-	50																												
Med Gas In-Wall Rough In	28-Jun-11*		50																												
Pneumatic Tube In-Wall Rough In	28-Jun-11*		50					i			į																				
Drywall Paritions & Gypsum Ceiling	08-Sep-11	-	25																												
Acoustical Ceiling Grid	15-Sep-11		20		!	L L .				 							-11	L L	!										È-		
Light Fixtures in Acoustical Grid	03-Oct-11*	28-Oct-11	20																												
Diffusers, Grilles, Registers in Acoustical Grid	03-Oct-11*	28-Oct-11	20								-																				
Sprinkler Heads	03-Oct-11*	28-Oct-11	20											Ì																	
Final Paint	04-Nov-11	02-Dec-11	20																												
Electrical In-Wall Finishes	09-Nov-11	06-Jan-12	40		!					 								L L 	!			 					 _				
F/A Security In-Wall Finishes	09-Nov-11	06-Jan-12	40																												
Controls In-Wall Finshes	09-Nov-11	06-Jan-12	40																												
Med Gas In-Wall Finishes	09-Nov-11	06-Jan-12	40																												
Pneumatic Tube In-Wall Finishes	09-Nov-11	06-Jan-12	40																												
Millwork	28-Dec-11	15-Feb-12	35		!!			!	· · · · · · · · · · · · · · · · · · ·	 	!			!		!			!						_ 		+		 !		
Casework	28-Dec-11	15-Feb-12	35								÷																				
Electrical & Plumbing Tie into Casework	08-Feb-12*	28-Feb-12	15																												
02.03 Level 3	04-May-11	28-Feb-12	209																												
Top Track	04-May-1 ⁻	17-May-11	10					i			i			i																п т	on T
Spray on Fire Proofing (Interior Columns & Beam	-	-	10							 								+ - ·									++-				
Frame & Drywall Non-Accessible Walls	23-May-1	-	14					į						Ì																	Fra
Sheetmetal Overhead Rough In	01-Jun-11*		40																												
HVAC Overhead Piping Rough In	01-Jun-11*		40																												-
Med Gas Overhead Piping Rough In	01-Jun-11*		40					i																							-
Pneumatic Tube Overhead Piping Rough In	01-Jun-11*		40							 			- +					+ - ·									+				
Sprinkler Overhead Rough In	01-Jun-11*		40																												
Electrical Overhead Rough In	06-Jun-11*		40								÷																				-
F/A Security Overhead Rough In	06-Jun-11*	•	40								-																				1
Controls Overhead Rough In	06-Jun-11*	-	40					Ì																							-
Med Gas Overhead Distribution	06-Jun-11*	0	40							 								+													
Complete Frame Partition Walls	27-Jun-11*	-	20																												
Electrical In-Wall Rough In	28-Jun-11*		50					i			į																				
F/A Security In-Wall Rough In	28-Jun-11*	-	50																												1
Controls In-Wall Rough In	28-Jun-11*	-	50					Ì																							-
Med Gas In-Wall Rough In	28-Jun-11*	•	50							 			- +					+													
Pneumatic Tube In-Wall Rough In	28-Jun-11*	-	50																												1
Drywall Paritions & Gypsum Ceiling	06-Sep-11	-	25					i			i			i																	
Acoustical Ceiling Grid	12-Sep-11		20																												
Light Fixtures in Acoustical Grid	03-Oct-11*		20					į						Ì																	
Diffusers, Grilles, Registers in Acoustical Grid	03-Oct-11*		20							 					+-			+ +													
Sprinkler Heads	03-Oct-11*		20																												
Final Paint	04-Nov-11		20					-										 													
Electrical In-Wall Finishes	07-Nov-11		40																												
				<u>i</u> i	i	<u> i </u>	<u> i i</u>	i	<u>ı i</u>	 <u> i i</u>	i	<u> i i </u>	<u> </u>	i	<u> i i </u>	<u> </u>	. :	<u> i </u>	i	<u> i i </u>	i	. :		- i	<u>. i</u>	i	<u>ı i</u>		í	ı i	
Activity V Summary													Pag	ge 4 o	of 7										NE	WR	EGIO	NAL	MED	ICAL C	EN7
Milestone																															

)	Q	Q	0)		Q			Q			Q		Q
s	OND	JFN	/ A N	1 J	J	А	S	0	Ν	D	J	F	М	А
	Electrical I	n-Wall Ro	bugh In											
	F/A Securi	ty In-Wa	ll Roug	hIn		4		!	1					
<u> </u>	Controls Ir	-Wall Ro	ugh In											
1	Med Gas I	1 1 1												
i i	Pneumatic	i i i	1 i	i i	In									
		Parition		-	1 1	ilind	, ,							
	بالمريد المريد المريد المريد	tical Ceilir						1						
		Fixtures		stica	Gr	id								
		sers, Grill	1 1	1	1 1	1	פווכ	ical	Gr	id				
	1 1 1	ikler Hea	- i - i - i	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	5 11	1.00	-43							
		inal Pain												
			ical In-'			icho								
		1 1 1		1	1 1			•						
		1 1 1	ecurity	1	1 1	1		5						
		i i i	ols In-\	-i -	i i	i								
		T 1 1	Gas In-	1	: :									
¦	· · · · · · · · · · · · · · · · · · ·	4!!	natic Tı	ipe l	n-M	all	⊢ini	she	S					
			lillwork											
		1 1 1	asewoi	1										
		1 1 1	Electric		1 1		I		nto	Ca	sew	ork	(
:			28-Feb	-12,	02.	03 I	_ev	el 3						
ķ														
n' Fir	e Proofing	d (Interior	Colum	n's &	Be	ams	5)							
1	Drywall No					1							1	
1	tmetal Ov	1 I I I	- E - E											
÷	C Overhea	i i i	-	- i										
1	Gas Overl	1 1 1	1 1	1										
-i	imatic Tub			-1	i i	h Ir								
÷ .	kler Overl				9									
î.	trical Over	1 1 1	- I I											
1	Security O		9	n										
1		1 1 1	-	1										
	rols Overl Gas Over		- + +											
1		1 1 1		1										
1.1	plete Fran	1 1 1	- I I	,										
÷ .	Electrical I	1 1 1	-											
1	F/A Securi	f ! !		n; In										
	Controls Ir		- + +											
1	Med Gas I	1 1 1	-											
-	Pneumatic	1 1 1	- E - E											
		II Parition		s¦um	i Ce	iling								
	Acoust	ical Ceilin	g Grid											
	🔲 Light	Fixtures	in Acou	stica	l Gr	id								
	🔲 Diffu	sers, Grill	es, Reg	jiste	rs in	Ac	bus	ical	Gr	id		1		
	🔲 Sprir	nkler Hea	ds											
	🔲 F	inal Pain	t											
		Electri	cal In-	Nall	Fini	she	s							
	. (1	- I I			. 1		. 1							

E 481W - Senior Thesis															c	ON.					HAS		/EN	т																			
stivity Name	Start	Finish	Origina		Q		Q		Q)		Q		Q			Q	T	Q			Q		C)		Q		(ג		Q		Q			Q			Q	Τ	_	(
			Duration	10	Ν	DJ	JF	MA	A M	J	J	AS	sc	D N	D	JI	FN	1 A	M	J	J	A	S	л С	I D	J	F	М	AN	ΛJ	J	А	SC) N	D	J	F	М	A	М	J	J	ſ
F/A Security In-Wall Finishes	07-Nov-11	04-Jan-12	4()																																							Ē
Controls In-Wall Finshes	07-Nov-11	04-Jan-12	4()															1																								
Med Gas In-Wall Finishes		04-Jan-12	4()					÷.				į						į.			Ì	÷.		Ì																- i		
Pneumatic Tube In-Wall Finishes	07-Nov-11	04-Jan-12	4()						-									1																								
Millwork		15-Feb-12	35	5																																							
Casework	28-Dec-11	15-Feb-12	35	5																																							
Electrical & Plumbing Tie into Casework	08-Feb-12*	28-Feb-12	15	5						-									1																	-							
02.03 Level 4	11-May-11	28-Feb-12	204	1																																					=	_	F
Top Track	11-May-11	24-May-11	1()															į.			÷																			Τģ	рT	i 1
Spray on Fire Proofing (Interior Columns & Beam	18-May-1 ⁻	01-Jun-11	10)															1																						S	pra	ŀ
Frame & Drywall Non-Accessible Walls	25-May-1 ⁻	14-Jun-11	14	1															ł																					¢	-	Fra	1
Sheetmetal Overhead Rough In	03-Jun-11*	29-Jul-11	4()	+				!	-		 									+-	!-					-	+-				+			+				+	Į			i
HVAC Overhead Piping Rough In	03-Jun-11*	29-Jul-11	4()															ł																					ſ	Ż		ļ
Med Gas Overhead Piping Rough In	03-Jun-11*	29-Jul-11	4()						-									1																					Ī	i i i i i i i i i i i i i i i i i i i		ļ
Pneumatic Tube Overhead Piping Rough In	03-Jun-11*	29-Jul-11	40)			1 1		ł	: :					-				1			ł	ł	-		1				-		: :								Í	, i		ļ
Sprinkler Overhead Rough In	03-Jun-11*	29-Jul-11	4()																																				j	i i i i i i i i i i i i i i i i i i i		i
Electrical Overhead Rough In	10-Jun-11*	05-Aug-11	4()	+													1	1		+-								- 1			+	!						+	!-			Ì
F/A Security Overhead Rough In	10-Jun-11*	05-Aug-11	4()															-					-																			i
Controls Overhead Rough In		05-Aug-11	4()			11		ł	1					1				ł				ł	-								-								÷			ľ
Med Gas Overhead Distribution		05-Aug-11	4()															1																								İ
Complete Frame Partition Walls	29-Jun-11*	-	20	1															ł			ł																			į		ľ
Electrical In-Wall Rough In		09-Sep-11	50																													+			+				+				1
F/A Security In-Wall Rough In		09-Sep-11	50							1									1																						İ	_	ľ
Controls In-Wall Rough In		09-Sep-11	50																ł																						Ē		ļ
Med Gas In-Wall Rough In		09-Sep-11	50																1																						Ļ		ļ
Pneumatic Tube In-Wall Rough In		09-Sep-11	50																ł																						Ē	_	Ì
Drywall Paritions & Gypsum Ceiling	08-Sep-11	-	25																						+		-								+				+		!-		7
Acoustical Ceiling Grid	15-Sep-11		20																ł																								1
Light Fixtures in Acoustical Grid	03-Oct-11*		20							-									1																								1
-	03-Oct-11*		20																				÷																				į
Diffusers, Grilles, Registers in Acoustical Grid Sprinkler Heads	03-Oct-11*									-									1																								;
Final Paint		28-00-11 02-Dec-11	20																						+							++			+				· +				i
Electrical In-Wall Finishes			20																1																								1
		06-Jan-12	4(÷.				į		1	Ì			į.			Ì	÷.																		Ì		į
F/A Security In-Wall Finishes		06-Jan-12	4(1																								;
Controls In-Wall Finshes		06-Jan-12	4(1									į			i			į.			i	÷.		Ì														į		į		į
Med Gas In-Wall Finishes		06-Jan-12	4(+																+-						-					++	!						+				1
Pneumatic Tube In-Wall Finishes		06-Jan-12	4(ł																								i
Millwork		15-Feb-12	35																																								i
Casework		15-Feb-12	35	1																																							i
Electrical & Plumbing Tie into Casework		28-Feb-12	15	_															ł																_								
02.08 Electrical Room	28-Dec-10	15-Aug-11	162	2															<u> </u>																V	/							i
Install Electrical Ductbank	28-Dec-1(10															-																	ļ	—	Inst		1				ļ
35kv Generator Set on Site		28-Mar-11	()																																			35	5kv (Ger	ier	FFF
Switch Gear on Site		01-Apr-11	()						-								-	}																			<u> </u>	· Si	wit¢ł	hĢ	iea	Ì
Permanent Power	04-Apr-11*	20-Jun-11	55	5																																		J	<u> </u>			Pe	i
																		Pa	ne l	5 of	7												NE		FOI			ME				-NT	i
																		١d	ge i	0.01	'														Lan	014			510	~			
Activity V Summary Milestone																		Pa	ige (5 of	7																			NEW REGIONAL MEDIC EAST NORRITON, PA			NEW REGIONAL MEDICAL CENT EAST NORRITON, PA

Q	Q)	Q			Q			Q			Q		Q
AS					J	J		S	0	N	D	J	F	М	A
				curity Ir	-	-		-	-			•	-		
				ls In-W											
			÷	as lin-W		: :									
		1.1	1	atic Tub					cho	e					
			i -	llwork			ui								
			1	sework											
				lectrica		Plu	nhi		 Tio i	nto	Ca	2014	ork		
i			- i	8-Feb-				-			Ua	SCVV		`	
			1		· <u>~</u> ,		001								
ack _			1												
	ire Proof	T I	1	1 1		k Be	am	IS)							
	Drywall N			\vdash +	IS										
1	tmetal O	1 1	1												
	C Overhe	- I - I -		1 1											
	Gas Ove	i i	- i	i i		ii									
	imatic Tu	1. 1.	-	1 1	g R	oug	ih Ir	1							
	kler Ove			++											
	trical Ove	1. 1.	1	T											
1	Security	1.1.1	1	1 Ī	n										
	trols Ove		1												
1	l Gas Ov	1.1.1	1	1 1											
	plete Fra			H +											
	Electrical	1 1		-											
	F/A Secu	10 I.			In										
- i	Controls	i i	- i	-											
	Med Gas		1												
	Pneumat			+ +											
		- i - i -	- i	& Gyps	um	Ce	eiling								
	1 I I	stical C		Т I											
		i i	i i	n Acous		: :									
		1 1	1	s, Regi	ster	's in	AC	bus		Gr	a				
	Spr	inkler H		+ +											
		Final F	1	1 1	1-1										
		i i	i -	al In-V		i i									
		- i - i -	÷ .	curity li					S						
		1.1	1	ls In-W											
			-i	as In-V		i i									
			1	latic Tuk Ilwork	be i	n-v	a	FIN	sne	s					
			-i	i i					1			1			
			1	sework		DI	nhi			nto	<u></u>	-	orl		
7 45		∟ _¦ م∂مؤر		lectrica			וועה	y			Ja	5eW			
	Aug-11,	∪∠.UĢ E	-iec(i -¦	μισαι ΠΟ										;	
ank															
i	t on Site														
on Si	1 1 1		-												
mane	nt Power		1						1				1		
R															

| Start | Finish | Original | Q | |)

 | 0 |

 | 0 | - | 0
 | |

 | | - | MAN

 | -
 |

 | | | Q |
 | 0 |
 | 0 |
 | Q | | Q |
 | 0 | |
|-----------------------|---|---|--|---
--
--
--
---|---
--
--
--
---|---|---|---|---
--
--
--|---|---
--
--
--|--
--

--|---|--
--
--|---|--|---
--
---|---|---|--
---|---|--|
| Otart | | | | |

 | | JJ

 | | s o |
 | DJ |

 | MA | | J

 |
 |

 | | D | | MA
 | | J
 | | s
 | | DJ | | | |
 | | JJA |
| 09-May-1 ⁻ | 13-May-11 | 5 | | |

 | |

 | | _ |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | et Emer |
| 16-May-1 [.] | 27-May-11 | 10 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | Piping to |
| 31-May-1 [.] | 27-Jun-11 | 20 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | 1 1 | Elec |
| | 20-Jun-11 | 0 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | • | Emer |
| 27-Jun-11* | 01-Jul-11 | 5 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | Set |
| 05-Jul-11* | 08-Aug-11 | 25 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| 09-Aug-11 | 15-Aug-11 | 5 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| | 15-Aug-11 | 0 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | • |
| 14-Mar-11 | 07-Jun-12 | 316 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | 7 | | |
 | | |
| | 14-Mar-11 | 0 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | • | Cor
 | olinģ | Tower c |
| 23-Mar-11* | 05-Apr-11 | 10 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | Ì | |
 | Set C | ooling T |
| | 05-Apr-11 | 0 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | • /
 | AHU's | s on Site |
| 06-Apr-11* | 07-Jun-11 | 44 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | <u> </u> | Set AH |
| | 12-Apr-11 | 0 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | •
 | Fire F | ² ump or |
| | 11-May-11 | 0 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | ♦ Br | oiler on i |
| | 11-May-11 | 0 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | CI | hillers or |
| 12-May-1 ⁻ | 09-Jun-11 | 20 | + | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | | +-
 | |
 | |
 | | | | +
 | | Set Ch |
| 12-May-1 ⁻ | 09-Dec-11 | 148 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | <u> </u> |
| 10-Jun-11* | 11-Aug-11 | 44 | | |

 | |

 | | į |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | i i |
| 17-Jun-11* | 29-Jul-11 | 30 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | F |
| 05-Jul-11* | 05-Oct-11 | 66 | | |

 | |

 | | į |
 | | i i

 | Ì | |

 |
 |

 | | | | Ì
 | |
 | |
 | | į | |
 | | |
| 18-Jul-11* | 03-Jan-12 | 118 | + | | · • • • • • • • • • • • • • • • • • • •

 | |

 | | | +
 | |

 | + | |

 | +
 |

 | | | !!- | +-
 | |
 | -+ |
 | | | | +
 | | |
| 18-Jul-11* | 18-Jul-11 | 1 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | l Po |
| 25-Jul-11* | 02-Sep-11 | 30 | | |

 | |

 | | |
 | |

 | Ì | |

 |
 |

 | | | |
 | |
 | |
 | | Ì | | | |
 | | i 🛑 |
| 16-Aug-11 | 27-Sep-11 | 30 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| 06-Sep-11 | 17-Oct-11 | 30 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| 06-Sep-11 | 18-Nov-11 | 54 | | |

 | | 1

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| 13-Feb-12* | 09-Apr-12 | 41 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| 10-Apr-12* | 07-Jun-12 | 42 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| 25-Oct-11 | 23-Mar-12 | 105 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| | 25-Oct-11 | 0 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| 26-Oct-11* | 01-Nov-11 | 5 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| 02-Nov-11 | 21-Dec-11 | 35 | | |

 | |

 | | |
 | - |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| 21-Dec-11 | 16-Feb-12 | 40 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| 09-Jan-12* | 02-Mar-12 | 40 | | |

 | |

 | | į |
 | |

 | i | |

 |
 |

 | | | | Ì
 | |
 | |
 | | į | | | |
 | | |
| 05-Mar-12* | 23-Mar-12 | 15 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| 09-Apr-12 | 15-Oct-12 | 133 | | |

 | 1 |

 |]] | |
 | |

 | | |

 |
 |

 | | | |
 |]] |
 | |
 | | | | | |
 | [] | |
| 09-Apr-12 | 31-Aua-12 | 103 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| • | - | | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| | | | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| | - | | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| | | - | | |

 | |

 | | | ++-
 | |

 | + | |

 |
 |

 | | | | +-
 | |
 | - + + - |
 | | | | · +
 | + | |
| | | 0 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | | | | |
 | | |
| 30-Aua-10 | | 114 | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | . ▼ |
 | : : | | - |)-Feb
 | 5-11. I | |
| | | | | |

 | |

 | | |
 | |

 | | |

 |
 |

 | | | |
 | |
 | |
 | | round | | 1 1
 | 1 1 | |
| JU-Aug-It | 00-110 | 4/ | | |

 | |

 | | |
 | |

 | | |

 | :
 |

 | | | : : |
 | |
 | |
 | | | | | |
 | | |
| | | | | |


 | |

 | | |
 | |

 | Pa | age 6 | o of 7

 | ,
 |

 | | | |
 | |
 | | NE
 | W REC | GION | IAL M | EDIC
 | AL C | ENTER. |
| | 16-May-1'
31-May-1'
27-Jun-11*
05-Jul-11*
09-Aug-11
14-Mar-11
23-Mar-11*
12-May-1'
12-May-1'
12-May-1
12-May-1
10-Jun-11*
17-Jun-11*
17-Jun-11*
18-Jul-11*
18-Jul-11*
18-Jul-11*
18-Jul-11*
18-Jul-11*
18-Jul-11*
18-Jul-11*
18-Jul-11*
18-Jul-11*
18-Jul-11*
18-Jul-11*
18-Jul-11*
18-Jul-11*
18-Jul-11*
18-Jul-11*
18-Jul-11*
18-Jul-11*
18-Jul-11*
19-Apr-12*
09-Apr-12
09-Apr-12
09-Apr-12
17-Apr-12*
09-Aug-12
30-Jul-12*
06-Aug-12 | QQ09-May-113-May-1116-May-127-May-1111-May-127-Jun-1120-Jun-1120-Jun-1107-Jun-1101-Jul-1105-Jul-1108-Aug-1109-Aug-1115-Aug-1110-Aug-1115-Aug-1111-Mar-1107-Jun-1223-Mar-11*05-Apr-1106-Apr-11*07-Jun-1112-May-1111-May-1112-May-1111-May-1112-May-1109-Jun-1112-May-1109-Jun-1112-May-1109-Jun-1112-May-1109-Jun-1112-May-1109-Jun-1112-May-1111-Aug-1113-Jun-11*29-Jul-1113-Jul-11*03-Jan-1214-Aug-1113-Jul-1115-Jul-11*13-Jul-1116-Aug-1117-Oct-1116-Aug-1117-Oct-1116-Aug-1118-Nov-1113-Feb-12*09-Apr-1210-Apr-12*07-Jun-12* | Ope-May-1: 13-May-11 S 16-May-1: 27-May-11 10 31-May-1: 27-Jun-11 20 20-Jun-11 01 20-Jun-11 00 27-Jun-11* 01-Jul-11 05 05 05-Jul-11* 08-Aug-11 25 09-Aug-11 15-Aug-11 0 15-Aug-11 0 316 05-Jul-11* 07-Jun-12 316 03-Aug-11 07-Jun-11 0 23-Mar-11* 05-Apr-11 0 06-Apr-11* 07-Jun-11 44 12-Apr-11 0 1 11-May-11 0 1 12-May-1: 09-Jun-11 20 12-May-1: 09-Jun-11 20 12-May-1: 09-Jun-11 30 05-Jul-11* 03-Jan-12 1188 10-Jun-11* 1-Aug-11 1 25-Jul-11* 02-Sep-11 30 05-Jul-11* 02-Sep-11 30 06-Sep-11 17-Oct-11 | Ouration O N D 09-May-1' 13-May-11 10 1 1 16-May-1' 27-May-11 100 1 1 31-May-1' 27-Jun-11 200 100 1 1 20-Jun-11' 01-Jul-11 55 1 1 1 1 27-Jun-11' 05-Aug-11 05 1 1 1 1 05-Jul-11' 05-Aug-11 00 1 1 1 1 05-Apr-11 00 1 1 1 1 1 1 06-Apr-11' 07-Jun-11 4 1 1 1 1 1 12-May-1' 09-Jun-11 100 1 | Duration Duration O N D J F 09-May-11 13-May-11 5 I <t< td=""><td>Duration O N D J F M A 09-May-1' 13-May-11 10 1</td></t<> <td>Ouration O N D J F M A M 09-May-11 13-May-11 5 .<td>Ouration O N D J F M A M J J 09-May-11 13-May-11 27-May-11 100 27-May-11 100 27-May-11 100 27-Jun-11 20-Jun-11 20-Jun-11 20-Jun-11 20-Jun-11 20-Jun-11 20-Jun-11 20-Jun-11 10 27-Jun-11 10 27-Jun-11 10 27-Jun-11 15-Aug-11 0 1</td><td>Duration O N D J F M M J J A M J A M J A M J A M J A M J A M J A M J A M J A M J A M J A M J A M J A M J A M J J A M J J A M J J A M J J F M M M M J J F M M M J J A M J J A M J J A M J J A M J J A M J J A M J J A M J A M<</td><td>Duration O N D J F M M J J A N J J A N J J A N J J A N J J A N J J A N J J A N J J A N J J A N J J A N J J A N J<</td><td>Duration Duration O N D J F M A M J J A S O N 09-May-1' 27-May-11 10 27-Jun-11 20
27-Jun-11 0 27-Jun-11 27-Jun-11 0 27-Jun-11 0 27-Jun-11 0 27-Jun-11 0 27-Jun-11</td><td>Start Finish Original Duration Q<!--</td--><td>Start Finish Original Q</td><td>Start Finish
Duration Original
Duration Q</td><td>Start Finish Original
Duration Q Q Q Q<td>Start Driski
Duration Original
Duration O <tho< th=""> <tho< th=""> <tho< th=""> <</tho<></tho<></tho<></td><td>Start Diraction Q Q <t< td=""><td>Start Finish Original
Ouration Q Q Q Q</td></t<><td>Start Fish Orginal O O <</td><td>Start Finish Original
Duration O<</td><td>Start Finish Original
During Q Q Q Q
 Q Q<td>Start Finish Original Q</td><td>Start Frieh Duration O</td><td>Start Finish Duration O</td><td>Sint
During
During
19May-1 O
b O
b<!--</td--><td>Start Finish Organization O</td><td>Sint Fluit Opinol Q <</td><td>Sint Origin Ourigin Ou</td><td>Star: Organization O <t< td=""><td>Sint Origination of the provide of</td><td>Sinter Onder the object of the
object of the object of</td></t<></td></td></td></td></td></td></td> | Duration O N D J F M A 09-May-1' 13-May-11 10 1 | Ouration O N D J F M A M 09-May-11 13-May-11 5 . <td>Ouration O N D J F M A M J J 09-May-11 13-May-11 27-May-11 100 27-May-11 100 27-May-11 100 27-Jun-11 20-Jun-11 20-Jun-11 20-Jun-11 20-Jun-11 20-Jun-11 20-Jun-11 20-Jun-11 10 27-Jun-11 10 27-Jun-11 10 27-Jun-11 15-Aug-11 0 1</td> <td>Duration O N D J F M M J J A M J A M J A M J A M J A M J A M J A M J A M J A M J A M J A M J A M J A M J A M J J A M J J A M J J A M J J F M M M M J J F M M M J J A M J J A M J J A M J J A M J J A M J J A M J J A M J A M<</td> <td>Duration O N D J F M M J J A N J J A N J J A N J J A N J J A N J J A N J J A N J J A N J J A N J J A N J J A N J<</td> <td>Duration Duration O N D J F M A M J J A S O N 09-May-1' 27-May-11 10 27-Jun-11 20 27-Jun-11 0 27-Jun-11 27-Jun-11 0 27-Jun-11 0 27-Jun-11 0 27-Jun-11 0 27-Jun-11</td> <td>Start Finish Original Duration Q<!--</td--><td>Start Finish Original Q</td><td>Start Finish
Duration Original
Duration Q
Q Q</td><td>Start Finish Original
Duration Q Q Q Q<td>Start Driski
Duration Original
Duration O <tho< th=""> <tho< th=""> <tho< th=""> <</tho<></tho<></tho<></td><td>Start Diraction Q Q <t< td=""><td>Start Finish Original
Ouration Q Q Q Q</td></t<><td>Start Fish Orginal O O <</td><td>Start Finish Original
Duration O<</td><td>Start Finish Original
During Q<td>Start Finish Original Q</td><td>Start Frieh Duration O
O</td><td>Start Finish Duration O</td><td>Sint
During
During
19May-1 O
b O
b<!--</td--><td>Start Finish Organization O</td><td>Sint Fluit Opinol Q <</td><td>Sint Origin Ourigin Ou</td><td>Star: Organization O <t< td=""><td>Sint Origination of the provide of</td><td>Sinter Onder the object of</td></t<></td></td></td></td></td></td> | Ouration O N D J F M A M J J 09-May-11 13-May-11 27-May-11 100 27-May-11 100 27-May-11 100 27-Jun-11 20-Jun-11 20-Jun-11 20-Jun-11 20-Jun-11 20-Jun-11 20-Jun-11 20-Jun-11 10 27-Jun-11 10 27-Jun-11 10 27-Jun-11 15-Aug-11 0 1 | Duration O N D J F M M J J A M J A M J A M J A M J A M J A M J A M J A M J A M J A
 M J A M J A M J A M J A M J J A M J J A M J J A M J J F M M M M J J F M M M J J A M J J A M J J A M J J A M J J A M J J A M J J A M J A M< | Duration O N D J F M M J J A N J J A N J J A N J J A N J J A N J J A N J J A N J J A N J J A N J J A N J J A N J< | Duration Duration O N D J F M A M J J A S O N 09-May-1' 27-May-11 10 27-Jun-11 20 27-Jun-11 0 27-Jun-11 27-Jun-11 0 27-Jun-11 0 27-Jun-11 0 27-Jun-11 0 27-Jun-11 | Start Finish Original Duration Q </td <td>Start Finish Original Q</td> <td>Start Finish
Duration Original
Duration Q</td> <td>Start Finish Original
Duration Q Q Q Q<td>Start Driski
Duration Original
Duration O <tho< th=""> <tho< th=""> <tho< th=""> <</tho<></tho<></tho<></td><td>Start Diraction Q Q <t< td=""><td>Start Finish Original
Ouration Q Q Q Q</td></t<><td>Start Fish Orginal O
 O O <</td><td>Start Finish Original
Duration O<</td><td>Start Finish Original
During Q<td>Start Finish Original Q</td><td>Start Frieh Duration O</td><td>Start Finish Duration O</td><td>Sint
During
During
19May-1 O
b O
b<!--</td--><td>Start Finish Organization O</td><td>Sint Fluit Opinol Q <</td><td>Sint Origin Ourigin Ou</td><td>Star: Organization O <t< td=""><td>Sint Origination of the provide of the
provide of the provide of</td><td>Sinter Onder the object of</td></t<></td></td></td></td></td> | Start Finish Original Q | Start Finish
Duration Original
Duration Q | Start Finish Original
Duration Q Q Q Q <td>Start Driski
Duration Original
Duration O <tho< th=""> <tho< th=""> <tho< th=""> <</tho<></tho<></tho<></td> <td>Start Diraction Q Q <t< td=""><td>Start Finish Original
Ouration Q Q Q Q</td></t<><td>Start Fish Orginal O O O O O O O O O O O O
 O O <</td><td>Start Finish Original
Duration O<</td><td>Start Finish Original
During Q<td>Start Finish Original Q</td><td>Start Frieh Duration O</td><td>Start Finish Duration O</td><td>Sint
During
During
19May-1 O
b O
b<!--</td--><td>Start Finish Organization O</td><td>Sint Fluit Opinol Q <</td><td>Sint Origin Ourigin Ou</td><td>Star: Organization O <t< td=""><td>Sint Origination of the provide of
the provide of the provide of</td><td>Sinter Onder the object of</td></t<></td></td></td></td> | Start Driski
Duration Original
Duration O <tho< th=""> <tho< th=""> <tho< th=""> <</tho<></tho<></tho<> | Start Diraction Q Q <t< td=""><td>Start Finish Original
Ouration Q Q Q Q</td></t<> <td>Start Fish Orginal O O <</td> <td>Start Finish Original
Duration O<</td> <td>Start Finish Original
During Q
 Q Q Q Q Q Q<td>Start Finish Original Q</td><td>Start Frieh Duration O</td><td>Start Finish Duration O</td><td>Sint
During
During
19May-1 O
b O
b<!--</td--><td>Start Finish Organization O</td><td>Sint Fluit Opinol Q <</td><td>Sint Origin Ourigin Ou</td><td>Star: Organization O <t< td=""><td>Sint Origination of the provide of</td><td>Sinter Onder the object of the
object of the object of</td></t<></td></td></td> | Start Finish Original
Ouration Q Q Q Q | Start Fish Orginal O O < | Start Finish Original
Duration O< | Start Finish Original
During Q <td>Start Finish Original Q</td> <td>Start Frieh Duration O</td> <td>Start Finish Duration O</td> <td>Sint
During
During
19May-1 O
b O
b<!--</td--><td>Start Finish Organization O</td><td>Sint Fluit Opinol Q
 Q <</td><td>Sint Origin Ourigin Ou</td><td>Star: Organization O <t< td=""><td>Sint Origination of the provide of</td><td>Sinter Onder the object of</td></t<></td></td> | Start Finish Original Q | Start Frieh Duration O | Start Finish Duration O | Sint
During
During
19May-1 O
b O
b </td <td>Start Finish Organization O</td> <td>Sint Fluit Opinol Q
 Q <</td> <td>Sint Origin Ourigin Ou</td> <td>Star: Organization O <t< td=""><td>Sint Origination of the provide of</td><td>Sinter Onder the object of</td></t<></td> | Start Finish Organization O | Sint Fluit Opinol Q < | Sint Origin Ourigin Ou | Star: Organization O <t< td=""><td>Sint Origination of the provide
of the provide of</td><td>Sinter Onder the object of</td></t<> | Sint Origination of the provide of | Sinter Onder the object of |




AE 481W - Senior Thesis												BR	RIAN N/	AHA	S																						
											CON	ITRUC		IANA	GEME	NT																					
Activity Name	Start	Finish	Original	Q		Q	Q		Q	Q		Q	Q		Q	Q		Q	Q	2	Q		Q	Q		Q	Q		Q	Q		Q		Q	Q		Q
			Duration	ΟN	DJ	FM	AM	JJ	A S	O N	DJ	FM	AM	JJ	AS	ON	DJ	FM	AM	J	JA	s o	N D	JF	MA	M J	JA	S O	N D	JF	M	A M J	IJ	AS	O N	DJ	FM
First Floor (Sector A - D)	27-Sep-1(01-Dec-10	47																				F	irst Flo	or (Se	ctor A	D)										
Second Floor (Sector A - B)	25-Oct-10*	15-Dec-10	37									· l 4			4! 1 1 1 1 1 1	L L L . I I I I I I I I	!	· l= = = l= = = - l	4 J 					Secon	d Floo	r (Secto	or A - B)										
Ground Floor Coordination Meeting		28-Oct-10	0											1				! !					Grou	ind Flo	br Ċoc	rdinatio	n Meet	ing			: :		1				
Third Floor (Sector A - B)	08-Nov-1(29-Dec-10	36																					Thire	d Floor	(Secto	r A - B)										
Fourth Floor (Sector A - B)	22-Nov-1(12-Jan-11	35																					Fo	urth FI	oor (Se	ctor A -	B)									
First Floor Coordination Meeting		24-Nov-10	0																				• F	irst Flo	or Coc	rdinatic	n Meet	ing			i i						
High & Low Roof (Sector A - D)	06-Dec-1(09-Feb-11	46										+		±	L L L . 			· ·						High 8	Low F	oof (Se	ctor A	- D)								
Second Floor Coordination Meeting		09-Dec-10	0																					Second	d Floor	Coord	ination I	Meeting	g								
Third Floor Coordination Meeting		23-Dec-10	0																				•	Third	Floor	Coordi	nation N	/leeting									
Fourth Floor Coordination Meeting		06-Jan-11	0																					♦ Fou	rth Flo	or Coo	rdinatio	n Meet	ting								
High & Low Roof Coordination Meeting		03-Feb-11	0																					- 🔶 i	High &	Low R	oof Coo	rdinatio	on Me	eting							

Activity V Summary	Page 7 of 7	NEW REGIONAL MEDICAL CENTER
Milestone		EAST NORRITON, PA



APPENDIX F | 5D ESTIMATE PROCESS MAP





	100					
termine they begin in the last the						
No. in the second second						
						1.2.2
_			1000			
The line is a second se	1.27.24			1000	1100	
	10.00	122	-		110	
concerns and an entering of the law	10.000 000	1.04				
the last state of the last state of the last			100			
personal presented	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1					
	1111111	10.0				
	10.000 000			THE R.		
for the formal	The second second second second second second second second second second second second second second second se		10		10.	
tion inclusion			10			
15 C			-	10.0		
1 mile (100 mile)		11.1		199		
	1.000 0.000		1			
		1.000	10	10.0		
1000 C						
	1.000	199	-	10.00		
	and the second s	The second		distant.		
			1			
	Country and a	1000	1	10.0	1000	
	100000			111	11.0	
	100 000	199		100		
				192		
	a sea la se	1000	1	10.0	1000	
	Conception and the			10.0		
	10000	1000		19.2		
	10.000	100		100		
		122		105	1 1 1 1 1	
	The same same	1000	100	10.0	1000	
Sector 10	100 93			11	1.000	

Family	Туре	v	WtperFt	Length	Weight (Tons)
W-Wide Flange-Column	W10x49		49	82'-1"	0.786042
W-Wide Flange-Column	W10x49		49	31'-9"	0.777875
W-Wide Flange-Column	W10x49		49	31'-9"	0.777875
W-Wide Flange-Column	W10x49		49	31'-9"	0.777875
W-Wide Flange-Column	W10x49		49	31'-9"	0.777875
W-Wide Flange-Column	W10x49		49	31'-9"	0.777875
W-Wide Flange-Column	W10x49		49	31'-9"	0.777875
W-Wide Flange-Column	W10x49		49	31'-1"	0.761542
W-Wide Flange-Column	W10x49		49	32'-1"	0.786042
W-Wide Flange-Column	W10x49		49	32'-1"	0.789042
W-Wide Flange-Column	W10x49		49	15'-8"	0.383833
W-Wide Flange-Column	W10x49		49	31'-9"	0.777875
W-Wide Flange-Column	W10x49		49	37'-8"	0.922833
W-Wide Flange-Column	W10x49		49	31'-1"	0.761542
W-Wide Flange-Column	W10x49		49	31'-9"	0.777875
W-Wide Flange-Column	W10x49		49	31'-1"	0.761542
W-Wide Flange-Column	W10x49		49	19'-5"	0.475708
W-Wide Flange-Column	W10x49		49	31'-9"	0.777875
W-Wide Flange-Column	W10x49		49	31'-1"	0.761542
W-Wide Flange-Column	W10x49		49	31'-1"	0.761542
W-Wide Flange-Column	W10x49		49	19'-5"	0.475708
W-Wide Flange-Column	W10x49		49	31'-1"	0.761542
W-Wide Flange-Column	W10x49		49	16'-8"	0.408333
W-Wide Flange-Column	W10x49		49	15'-5"	0.377708

093105.70	Placing Concrete									
	GB 30"x32": 1	4.18 CY	4.98	NA.						
150	3000 pzi		CY		99					411.04
3280	Grade Dears, direct shate		CT	f		11.45	0.21	11.79	**	
033105.70	Placing Concrete								\$	411.84
09.21 10.70	Glass Fiber Reinfornced Palymer	Bors			•					
	Flound Dar 11: 53	1537-9 9/16*	1532	0						
350	#0.bar 1.620.bW		U		2.02	0.21	0	2.53		3,554.24
03 22 10.70	Gloss Fiber Reinfornced Polymer	lors							\$	2,554.24
AK 11 11 17	Columna, Structural									
10111111	H356x2x3/8-16	ST-9 9/16"	4.333	0.445462						
	Structural Tubing, 6"x4"x646" x 12"	01:0.94%	B of 12' incoments		281	49	30	360		1,217,87
8080						40		360		1,217,87
	HSS6e4x378:1	1.00	0.966							
\$550	Second Tubing Character 212		B OI 15, BOHLAND		201	49	30	360		46.65
	HS58#6#3/8: 52	1015'-5 13/16"	72.5	16.501613						
4680	Structural Tables, ShiPutMir's W		B of W incoments		660	52	39.5	745.5	*	47.950.00



APPENDIX G | 5D ESTIMATE VALUES

Brian Nahas

umber	Family	Measured Units	Total Units	Weight (Tons)		ral Columns aterial	Labor	Equipment	Total	Mate	erial Cost	Labor Cost	Equipment Cost	Total C	`nst
inner	ranniy	wedsured Units		weight (10hs)	IVIE	aterial	Labul	equipment	Total	wate			Equipment Cost	Total C	.031
)5 12 23.4	40 Lightweight Framing														
	ž3x3x3/8: 4	6'-8 1/8"		7	NA										
4	176 Angle 3"x3"x3/8"			LF		4.86	20.5	1	L .91	27.27 \$	4.76	\$ 16.52	2 \$ 1.5	4\$	2
	Screenwall Post 1: 33	618'-3 3/8"	6:	18	NA										
7	750 Junior Beam, 8"			LF		12.4	22.5	2	2.06	36.96 \$	7,663.20	\$ 13,905.00) \$ 1,273.0	8\$	22,84
	Screenwall Post 2: 6	76'-0"	-	76	NA										
7	750 Junior Beam, 8"			LF		12.4	22.5	2	2.06	36.96 \$	942.40				2,80
)5 12 23.4	40 Lightweight Framing									\$	8,610.36	\$ 15,631.52	? \$ 1,431.1	8 \$	25,673
)5 12 23.	17 Columns, Structural				•										
	HSS4x4x3/8: 10	117'-2 3/4"	9.7	75	0.867496										
45	500 Structural Tubing, 4"x4"x1/4" x 12'		# of 12' incremen			18.6	4.55		2.8	25.95 \$	181.35	\$ 44.36	5 \$ 27.3	0 Ś	2
	HSS4x4x5/16:10	98'-0 3/8"	8.3		0.725446					+		•	· · ·	- 1	
45	500 Structural Tubing, 4"x4"x1/4" x 12'		# of 12' incremen			18.6	4.55		2.8	25.95 \$	151.78	\$ 37.13	3 \$ 22.8	5\$	2
	HSS5x5x3/8: 1	15'-8"	1.3		0.174683				-			•	•	- •	
45	550 Structural Tubing, 6"x6"x1/4" x 12'		# of 12' incremen			30.5	4.9	1	3	38.4 \$	40.57	\$ 6.52	2 \$ 3.9	9\$	
	HSS6x6x1/4: 3	37'-4 13/16"	3.0		0.355291							•	·		
45	550 Structural Tubing, 6"x6"x1/4" x 12'	· ·	# of 12' incremen	nts		30.5	4.9	1	3	38.4 \$	93.94	\$ 15.09	9.2	4\$	1
	HSS6x6x3/8: 40	443'-5 5/16"	36.9		6.075152										
45	550 Structural Tubing, 6"x6"x1/4" x 12'	· · · · · · · · · · · · · · · · · · ·	# of 12' incremen	nts		30.5	4.9	1	3	38.4 \$	1,126.06	\$ 180.91	L\$ 110.7	6\$	1,4
	HSS6x6x5/16:19	204'-7 11/16"	17.0	08	2.38404										
45	550 Structural Tubing, 6"x6"x1/4" x 12'		# of 12' incremen	nts		30.5	4.9	1	3	38.4 \$	520.94	\$ 83.69) \$	4\$	6
	HSS8x8x3/8: 3	33'-0"	2.3	36	0.6204										
46	500 Structural Tubing, 8"x8"x3/8" x 14'		# of 14' incremen	nts		66	5.3	3	8.25	74.55 \$	155.76	\$ 12.51	L\$ 7.6	7\$	1
	HSS12x6x3/8:4	8'-8"	0.562	25	0.185033										
57	700 Structural Tubing, 12"x8"x1/2" x 16'		# of 16' incremen	nts		12.25	5.55		3.4	21.2 \$	6.89	\$ 3.12	2 \$ 1.9	1\$	
	HSS12x6x5/16: 2	32'-7 3/8"	2.0	06	0.587039										
57	700 Structural Tubing, 12"x8"x1/2" x 16'		# of 16' incremen	nts		12.25	5.55	i i	3.4	21.2 \$	25.24	\$ 11.43	3 \$ 7.0	0\$	
5 12 23.	17 Columns, Structural									\$	2,302.52	\$ 394.76	5 \$ 241.9	6 \$	2,9 3
15 12 23	75 Structural Steel Members														
<i>J L L J L J L J L J L J L J L J L J L J L J L J L J L J L J L J L J L J L J L J J L L J J L J J L J J L J J L J J J L J J J J J J J J J J</i>	W6x25: 5	66'-8"		67	0.833333										
15	502 W12x26			LF	0.000000	32	3.01	1	L.84	36.85 \$	1,882.70	\$ 328.30) \$ 201.0	0 Ś	2,4
10	W12x87: 1	56'-10 9/16"		57	2.474388		0.01	_		50.05 Ç	1,002170	<i> </i>	,	• •	_,.
57	702 W24x84			LF		104	3.55		1.6 1	09.15 \$	3,762.00	\$ 302.10) \$ 185.2	5 Ś	4,2
	W14x82: 1	75'-4"		75	3.088667		0.00				0,1 02.00	+		- +	.,-
57	702 W24x84			LF		104	3.55		1.6 1	09.15 \$	4,950.00	\$ 397.50) \$ 243.7	5\$	5,5
5,	W24x306:4	299'-0"		99	45.747					- T	-,				-)-
81	L02 W36x302			LF		375	3.7	1	L.67 3	80.37 \$	19,734.00	\$ 1,584.70) \$ 971.7	5\$	22,2
	W10x49: 1	53'-4"		53	NA										,
9	002 W10x49			LF		60.5	4.82	. 2	2.95	68.27 \$	649.25	\$ 294.15	5 \$ 180.2	0\$	1,1
	W14x90: 2	119'-6 3/4"		20	NA										
25	502 W14x120	•		LF		149	3.68	2	2.25 1	54.93 \$	17,880.00	\$ 441.60) \$ 270.0	0\$	18,5
	W8x24:10	144'-8 1/2"		45	1.736509										
5	502 W8x31			LF		38.5	4.82	. 2	2.95	46.27 \$	1,776.25	\$ 804.75	5 \$ 493.0	0\$	3,0
	W8x31:15	247'-4 7/16"		47	3.834222										
5	502 W8x31			LF		38.5	4.82	. 2	2.95	46.27 \$	3,025.75	\$ 1,370.85	5 \$ 839.8	0\$	5,2
	W8x67:1	59'-2 1/4"		59	1.982781										
17	702 W12x72			LF		89	4.14	. 2	2.53	95.67 \$	722.75	\$ 327.45	5 \$ 200.6	0\$	1,2
	W10x33: 1	31'-1"		31	0.512875										
23	302 W14x34			LF		42	3.27	,	2	47.27 \$	1,302.00	\$ 101.37	7 \$ 62.0	0\$	1,4
	W10x39: 1	60'-2 1/4"		60	1.173656										
	302 W14x34	-		LF		42	3.27	,	2	47.27 \$	2,520.00	\$ 196.20) \$ 120.0	n ć	2,8

				Structural								
SI Number	Family	Measured Units	Total Units Weight (1	ons) Mater	ial Labo	r Equipr	ment	Total I	Material Cost	Labor Cost	Equipment Cost	Total Cost
	W10x49: 52	1360'-10 1/2"	1361	33.341407								
	902 W10x49		LF		60.5	4.82	2.95	68.27	\$ 16,672.25	\$ 7,553.55	\$ 4,627.40	\$ 92,915.4
	W10x60: 14	447'-10"	448	13.435								
1	702 W12x72		LF		89	4.14	2.53	95.67	\$ 5,488.00	\$ 2,486.40	\$ 1,523.20	\$ 42,860.1
	W10x68: 1	32'-9"	33	1.1135								
1	702 W12x72		LF		89	4.14	2.53	95.67	\$ 404.25	\$ 183.15	\$ 112.20	\$ 3,157.1
	W12x53: 37	1051'-4 5/16"	1051	27.861015								
3	902 W18x55		LF		68	4.2	1.9	74.1	\$ 71,468.00	\$ 4,414.20	\$ 1,996.90	\$ 77,879.1
	W12x65: 15	471'-4"	471	15.318333								
1	702 W12x72		LF		89	4.14	2.53	95.67	\$ 5,769.75	\$ 2,614.05	\$ 1,601.40	\$ 45,060.5
	W12x72: 18	388'-4"	388	13.98								
1	702 W12x72		LF		89	4.14	2.53	95.67	\$ 4,753.00	\$ 2,153.40	\$ 1,319.20	\$ 37,119.9
	W12x79: 29	907'-7"	908	35.849542								
5	502 W24x76		LF		94	3.45	1.56	99.01	\$ 27,694.00	\$ 4,449.20	\$ 2,724.00	\$ 89,901.0
	W12x87: 92	2305'-6 1/4"	2306	100.290156								
5	702 W24x76		LF		94	3.45	1.56	99.01	\$ 28,248.50	\$ 12,798.30	\$ 7,840.40	\$ 228,317.0
	W12x96: 27	524'-0"	524	25.152								
5	902 W27x94		LF		116	3.22	1.45	120.67	\$ 60,784.00	\$ 1,687.28	\$ 759.80	\$ 63,231.0
	W12x106: 4	117'-4"	117	6.218667								
6	302 W30x108		LF		134	3.19	1.44	138.63	\$ 15,678.00	\$ 373.23	\$ 168.48	\$ 16,219.
	W12x120: 17	473'-11"	474	28.435								
2	502 W14x120		LF		149	3.68	2.25	154.93	\$ 70,626.00	\$ 1,744.32	\$ 1,066.50	\$ 73,436.
	W12x136: 2	31'-4"	31	2.130667								
6	902 W33x130		LF		161	3.38	1.53	165.91	\$ 4,991.00	\$ 104.78	\$ 47.43	\$ 5,143.
	W12x152: 1	29'-4"	29	2.229333								
7	502 W36x150		LF		186	3.28	1.48	190.76	\$ 5,394.00	\$ 95.12	\$ 42.92	\$ 5,532.
	W12x170: 15	324'-5 3/4"	324	27.580729								
7	702 W36x194		LF		240	3.41	1.54	244.95	\$ 77,760.00	\$ 1,104.84	\$ 498.96	\$ 79,363.
	W14x90: 2	119'-10 5/8"	120	5.394823								
5	902 W27x94		LF		116	3.22	1.45	120.67	\$ 13,920.00	\$ 386.40	\$ 174.00	\$ 14,480.4
	W14x132: 9	147'-3 9/16"	147	9.72168								
6	902 W33x130		LF		161	3.38	1.53	165.91	\$ 23,667.00	\$ 496.86	\$ 224.91	\$ 24,388.
	W14x283: 1	23'-0"	23	3.2545								
8	102 W36x302		LF		375	3.7	1.67	380.37	\$ 8,625.00	\$ 85.10	\$ 38.41	\$ 8,748.
	75 Structural Steel Members								\$ 500,147.45		•	

					Structural Fra	aming								
SI Number	Family : Quantity	Measured Units	Total Units	Weight (Tons)	Material	Labor	Equipment	Tota	l Mat	terial Cost	Labor Cost	Equipment Cost	Tota	l Cost
05 12 23.40	Lightweight Framing													
00 12 20.10	C10x25: 64	837'- 4 9/16"	20925	5 10.4672	7									
60 ^r	0 Channel framing, 8" and larger	25 lb/lf	LBS		0.68	2.3	6	0.22	3.26 \$	14,229.00	\$ 49,383.00	\$ 4,603.5	0 Ś	68,215.50
	C12x30: 6	76' 7 11/16"	2299.172				-			_ ,	,,	· · · · · · · · ·		,
60'	0 Channel framing, 8" and larger	30 lb/lf	LBS		0.68	2.3	6	0.22	3.26 \$	1,563.44	\$ 5,426.05	\$ 505.8	2 \$	7,495.30
	ž3x3x3/8: 29	131'-0 15/16"	131				-	-		,	, , , , ,			,
47	6 Angle 3"x3"x3/8"	•	Lf		4.86	20.	5	1.91	27.27 \$	636.66	\$ 2,685.50	\$ 250.2	1\$	3,572.37
	ž3x3x5/16: 2	7'-0 7/8"	7	0.02121					· · · ·		. ,			
470	6 Angle 3"x3"x3/8"		Lf		4.86	20.	5	1.91	27.27 \$	34.02	\$ 143.50	\$ 13.3	57 \$	190.89
	ž4x4x3/8: 21	188'- 6 9/16"	1828.888	3 0.91444	1									
40	0 Angle Framing, 4" and larger	9.7 lbs/lf	LBS		0.65	2.6	9	0.25	3.59 \$	1,188.78	\$ 4,919.71	\$ 457.2	2\$	6,565.71
	ž6x4x5/16: 2	8' - 9 1/2"	90.538	0.04526	9									
40	0 Angle Framing, 4" and larger	10.3 lbs/lf	LBS	5	0.65	2.6	9	0.25	3.59 \$	58.85	\$ 243.55	\$ 22.6	3\$	325.03
	MC12x31: 10	249' - 1 7/8"	7722	2 3.86188	6									
60/	0 Channel framing, 8" and larger	31 lb/lf	LBS		0.68	2.3	6	0.22	3.26 \$	5,250.96	\$ 18,223.92	\$ 1,698.8	4 \$	25,173.72
	Lightweight Framing								\$	22,961.70		· · ·	-	111,538.52
									,	/	, -,	, ,		· · · · ·
03 31 05.70	Placing Concrete													
	GB 30"x32": 1	4.16 CY	4.16	5 N/	4									
15	0 3000 psi		C		. 99				99 \$	411.84	\$ -	\$ -	\$	411.84
	0 Grade Beam, direct chute		C			11.4	5	0.31	11.76 \$		\$ 47.63	1	.9 \$	48.92
	Placing Concrete		-				-		Ś	411.84			9 \$	460.76
									7		<i>•</i>	7	~ 7	
03 21 10.70	Glass Fiber Reinfornced Polymer	r Bars			x									
	Round Bar 1": 53	1531'-9 9/16"	1532	2)									
35	0 #8 bar 0.620 lb/lf		Lf		2.32	. 0.2	1	0	2.53 \$	3,554.24	\$ 321.72	\$ -	\$	3,875.96
	Glass Fiber Reinfornced Polymer	r Bars					-	-	\$	3,554.24			4	3,875.96
		2410							۴	0,00	<i>y</i> 021772	*	*	0,070.00
05 12 23.17	Columns, Structural				•									
00 12 2011/	HSS6x2x3/8: 16	51'-9 9/16"	4.333	3 0.44546	2									
555(0 Structural Tubing, 6"x4"x5/16" x 12'	51-5 5/10	# of 12' increments		28.1	. 4.	9	3	36 \$	121.77	\$ 21.23	\$ 13 (0\$	156.00
5550	HSS6x4x3/8: 1	1'-10"	0.166				5	<u> </u>	3 0 9		<i>y</i> <u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u></u>	<i>y</i> 15.0	, o ,	100.00
555(0 Structural Tubing, 6"x4"x5/16" x 12'		# of 12' increments		- 28.1	. 4.	۹	3	36 \$	4.66	\$ 0.81	\$ 05	io \$	5.98
5550	HSS8x6x3/8: 52	1015'-5 13/16"	72.5				<u> </u>	3	3 0 Ç	-100	<i>y</i> 0.01	<i>y</i> 0.3	, ų ų	5.50
460	0 Structural Tubing, 8"x8"x3/8" x 14'	1010 0 10,10	# of 14' increments		66	5.	3	3.25	74.55 \$	4,785.00	\$ 384.25	\$ 235.6	3\$	5,404.88
	HSS8x6x5/8: 4	78'-4 3/4"	5.57				-	0.20	7 1100 \$.,,	• ••••	+	- +	0,10100
460	0 Structural Tubing, 8"x8"x3/8" x 14'		# of 14' increments		66	5.	3	3.25	74.55 \$	367.62	\$ 29.52	\$ 18.1	.0\$	415.24
	HSS10x4x3/8: 24	288'-2 5/8"	20.57				-	0.20	7 1100 \$		·	+		
	0 Structural Tubing, 10"x6"x3/8" x 14'		# of 14' increments		- 66	5.	3	3.25	74.55 \$	1,357.62	\$ 109.02	Ś 66.8	5\$	1,533.49
5651							-			_,		,	- T	_,
565		812'-7"	50.81	L <u>ZZ.347</u> Z.										
	HSS10x8x1/2: 29	812'-7"	50.81 # of 16' increments			5.5	5	3.4	21.2 Ś	622.42	\$ 282.00	\$ 172.7	′5Ś	1.077.17
	HSS10x8x1/2: 29 O Structural Tubing, 10"x10"x1/2" x 16		# of 16' increments	5	12.25	5.5	5	3.4	21.2 \$	622.42	\$ 282.00	\$ 172.7	′5\$	1,077.17
4650	HSS10x8x1/2: 29 0 Structural Tubing, 10"x10"x1/2" x 16 HSS10x8x5/8: 12	812'-7" 305'-8 3/8"	# of 16' increments 306	5 10.33252	12.25 4									
4650	HSS10x8x1/2: 29 O Structural Tubing, 10"x10"x1/2" x 16' HSS10x8x5/8: 12 O Structural Tubing, 10"x10"x1/2" x 16'	305'-8 3/8"	# of 16' increments 306 # of 16' increments	5 10.33252 5	12.25 4 12.25			3.4 3.4	21.2 \$ 21.2 \$	622.42 3,748.50				
4650 4650	HSS10x8x1/2: 29 0 Structural Tubing, 10"x10"x1/2" x 16 HSS10x8x5/8: 12		# of 16' increments 306	5 10.33252 5 0.88556	12.25 4 12.25	5.5	5				\$ 1,698.30	\$ 1,040.4		1,077.17 6,487.20 91.43

CSI Number Family : Quantity Measured Units Total Units Weight (Tons) Material Labor Equipment Total Material 5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$ HSS12x8x5/16: 12 164'-6" # of 16' increments 10.28 5.55 3.4 21.2 \$ 5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$ 6 FSS14x6x5/8: 11 99'-7 3/8" # of 16' increments 12.25 5.55 3.4 21.2 \$ 5 5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$ 6 5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$ 6 5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$ HSS14x1	terial Cost Labo 96.47 \$ 126.67 \$ 76.56 \$	or Cost Equip 43.71 \$ 57.39 \$	26.78 \$	tal Cost 166.95
HSS12x8x5/16: 12 164'-6" 10.34 10.28 5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$ HSS14x6x5/8: 11 99'-7 3/8" 6.25 3.790414 5.55 3.4 21.2 \$ 5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$	126.67 \$			166.95
5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$ HSS14x6x5/8: 11 99'-7 3/8" 6.25 3.790414		57.39 \$	25.16	
HSS14x6x5/8: 11 99'-7 3/8" 6.25 3.790414 5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$		57.39 \$	25.10 6	
5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$	76.56 \$		35.16 \$	219.21
	76.56 \$			
HSS14x10x1/2: 4 82'-2 3/4" 5.125 3.120661		34.69 \$	21.25 \$	132.50
5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$	62.78 \$	28.44 \$	17.43 \$	108.65
HSS16x8x1/2: 2 25'-6" 1.59 0.967734				
5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$	19.48 \$	8.82 \$	5.41 \$	33.71
HSS16x8x5/16: 14 356'-2 3/4" 22.25 8.691968				
5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$	272.56 \$	123.49 \$	75.65 \$	471.70
HSS16x12x1/2: 7 122'-0 13/16" 7.626 5.468664				
5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$	93.42 \$	42.32 \$	25.93 \$	161.67
HSS16x12x5/8: 25 637'-1 9/16" 39.8 35.04203				
5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$	487.55 \$	220.89 \$	135.32 \$	843.76
HSS20x8x5/16: 6 148'-2 7/8" 9.25 4.24701				
5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$	113.31 \$	51.34 \$	31.45 \$	196.10
HSS20x12x1/2: 29 721'-2 3/16" 45.06 37.140774				
5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$	551.99 \$	250.08 \$	153.20 \$	955.27
HSS6x6x5/16: 16 131'-0 7/16" 10.92 1.526547				
4550 Structural Tubing, 6"x6"x1/4" x 12' # of 12' increments 30.5 4.9 3 38.4 \$	333.06 \$	53.51 \$	32.76 \$	419.33
HSS20x12x1/2 2: 16 818'-3 13/16" 51.125 42.143398				
5700 Structural Tubing, 12"x8"x1/2" x 16' # of 16' increments 12.25 5.55 3.4 21.2 \$	626.28 \$	283.74 \$	173.83 \$	1,083.85
05 12 23.17 Columns, Structural \$	<i>13,920.55</i> \$	3,747.49 \$	2,296.04 \$	19,964.08
05 12 23.75 Structural Steel Members				
W6x9: 1 1'-0" 1 0.0045				
102 W6x9 LF 11.15 4.42 2.7 18.27 \$	11.15 \$	4.42 \$	2.70 \$	18.27
W8x15: 24 137'-4 1/16" 137 1.030046				
502 W8x31 LF 38.5 4.82 2.95 46.27 \$	5,274.50 \$	660.34 \$	404.15 \$	6,338.99
W8x18: 188 1085'-8 5/8" 1086 9.771458				
502 W8x31 LF 38.5 4.82 2.95 46.27 \$	41,811.00 \$	5,234.52 \$	3,203.70 \$	50,249.22
W8x24: 37 378'-3 3/8" 378 4.539396				
502 W8x31 LF 38.5 4.82 2.95 46.27 \$	14,553.00 \$	1,821.96 \$	1,115.10 \$	17,490.06
W8x31: 49 339'-2 9/16" 339 5.25781				
502 W8x31 LF 38.5 4.82 2.95 46.27 \$	13,051.50 \$	1,633.98 \$	1,000.05 \$	15,685.53
W8x40: 30 265'-1" 265 5.301632				
902 W10x49 LF 60.5 4.82 2.95 68.27 \$	16,032.50 \$	1,277.30 \$	781.75 \$	18,091.55
W8x58: 17 396'-6" 396.5 11.498529				
902 W10x49 LF 60.5 4.82 2.95 68.27 \$	23,988.25 \$	1,911.13 \$	1,169.68 \$	27,069.06
W10x68: 2 62'-8" 63 2.130667				
LF 89 4.14 2.53 95.67 \$	5,607.00 \$	260.82 \$	159.39 \$	6,027.21
W12x16: 1 21'-11 15/16" 22 0.17596				
1102 W12x16 LF 19.8 3.01 1.84 24.65 \$	435.60 \$	66.22 \$	40.48 \$	542.30
W12x19: 408 4843'-1 1/2" 4843 46.009701				
1302 W12x22 LF 27 3.01 1.84 31.85 \$	130,761.00 \$	14,577.43 \$	8,911.12 \$	154,249.55
W12x26: 132 1369'-2 15/16" 4369 17.800207				
1502 W12x26 LF 32 3.01 1.84 36.85 \$	139,808.00 \$	13,150.69 \$	8,038.96 \$	160,997.65

					Structural Fran	ming							
CSI Number	Family : Quantity	Measured Units	Total Units Wei	ight (Tons)	Material I	Labor	Equipment	Tot	tal Ma	aterial Cost	Labor Cost	Equipment Cost	Total Cost
	W12x35: 1	8'-8"	9	0.151637									
220	3 W14x34		LF		42	3.27		2	47.27 \$	378.00	\$ 29.43	\$ 18.00	\$ 425.43
	W12x40: 135	1122'-6 11/16"	1122.5	22.451128									
310	2 W16x40		LF		49.5	3.32		2.03	54.85 \$	55,563.75	\$ 3,726.70	\$ 2,278.68	\$ 61,569.13
	W14x22: 524	13187'-3 9/16"	13187	145.06028									
190	2 W14x26		LF		32	2.65		1.62	36.27 \$	421,984.00	\$ 34,945.55	\$ 21,362.94	\$ 478,292.49
	W14x26: 18	504'-0"	504	6.552									
190	2 W14x26		LF		32	2.65		1.62	36.27 \$	16,128.00	\$ 1,335.60	\$ 816.48	\$ 18,280.08
	W14x30: 15	411'-9 1/4"	412	6.176563									
210	2 W14x30		LF		37	2.95		1.8	41.75 \$	15,244.00	\$ 1,215.40	\$ 741.60	\$ 17,201.00
	W14x34: 46	715'-5 11/16"	715.5	12.163026									
230	2 W14x34		LF		42	3.27		2	47.27 \$	30,051.00	\$ 2,339.69	\$ 1,431.00	\$ 33,821.69
	W14x38: 27	755'-9 3/4"	756	14.360437									
310	2 W16x40		LF		49.5	3.32		2.03	54.85 \$	37,422.00	\$ 2,509.92	\$ 1,534.68	\$ 41,466.60
	W14x43: 99	1158'-4 7/8"	1158	24.905694									
310	2 W16x40	· · ·	LF		49.5	3.32		2.03	54.85 \$	57,321.00	\$ 3,844.56	\$ 2,350.74	\$ 63,516.30
	W14x48: 33	902'-0 15/16"	902	21.649861									
370	2 W18x50		LF		62	4.2		1.9	68.1 \$	55,924.00	\$ 3,788.40	\$ 1,713.80	\$ 61,426.20
	W14x53: 22	501'-9 1/2"	502	13.297493									
390	2 W18x55		LF		68	4.2		1.9	74.1 \$	34,136.00	\$ 2,108.40	\$ 953.80	\$ 37,198.20
	W14x109: 6	78'-1 13/16"	78	4.259258									
250	2 W14x120		LF		149	3.68		2.25	154.93 \$	11,622.00	\$ 287.04	\$ 175.50	\$ 12,084.54
	W16x31: 135	3972'-9 1/2"	3973	61.578257									
290	2 W16x31		LF		38.5	2.95		1.8	43.25 \$	152,960.50	\$ 11,720.35	\$ 7,151.40	\$ 171,832.25
	W16x36: 41	1037'-4 1/2"	1037	18.672775									
310	2 W16x40		LF		49.5	3.32		2.03	54.85 \$	51,331.50	\$ 3,442.84	\$ 2,105.11	\$ 56,879.45
	W16x40: 21	697'-10 1/8"	698	13.956863									
310	2 W16x40		LF		49.5	3.32		2.03	54.85 \$	34,551.00	\$ 2,317.36	\$ 1,416.94	\$ 38,285.30
	W16x50: 8	208'-0"	208	5.2									
370	2 W18x50		LF		62	4.2		1.9	68.1 \$	12,896.00	\$ 873.60	\$ 395.20	\$ 14,164.80
	W16x67: 2	21'-6 5/16"	21.5	0.72104									
470	2 W21x68		LF		84	3.7		1.67	89.37 \$	1,806.00	\$ 79.55	\$ 35.91	\$ 1,921.46
	W18x35: 217	5840'-11 1/8"	5841	102.216269									
330	2 W18x35		LF		43.5	3.99		1.8	49.29 \$	254,083.50	\$ 23,305.59	\$ 10,513.80	\$ 287,902.89
	W18x40: 36	1078'-0 3/8"	1078	21.560655									
350	2 W18x40		LF		49.6	3.99		1.8	55.39 \$	53,468.80	\$ 4,301.22	\$ 1,940.40	\$ 59,710.42
	W18x46: 8	212'-7 1/4"	213	4.889896									
370	2 W18x50		LF		62	4.2		1.9	68.1 \$	13,206.00	\$ 894.60	\$ 404.70	\$ 14,505.30
	W18x50: 9	267'-8 5/8"	268	6.693003									
370	2 W18x50		LF		62	4.2		1.9	68.1 \$	16,616.00	\$ 1,125.60	\$ 509.20	\$ 18,250.80
	W18x60: 2	54'-0"	54	1.62									
450	2 W21x62		LF		76.5	3.7		1.67	81.87 \$	4,131.00	\$ 199.80	\$ 90.18	\$ 4,420.98
	W18x65: 1	32'-5 7/8"	32.5	1.05598									
470	2 W21x68		LF		84	3.7		1.67	89.37 \$	2,730.00	\$ 120.25	\$ 54.28	\$ 2,904.53
	W18x76: 4	77'-7 7/8"	78	2.951026									
550	2 W24x76		LF		94	3.45		1.56	99.01 \$	7,332.00	\$ 269.10	\$ 121.68	\$ 7,722.78
	W18x86: 2	66'-6 3/16"	66.5	2.860098									
570	2 W24x84		LF		104	3.55		1.6	109.15 \$	6,916.00	\$ 236.08	\$ 106.40	\$ 7,258.48

					Structural Framin	g						
CSI Number	Family : Quantity	Measured Units		eight (Tons)	Material Lab	or Equipme	ent T	otal Ma	terial Cost L	abor Cost	Equipment Cost	Total Cost
	W18x106: 22	664'-2 1/2"	664	35.203054								
63	802 W30x108		LF		134	3.19	1.44	138.63 \$	88,976.00	\$ 2,118.16	\$ 956.16	\$ 92,050.32
	W18x130: 1	9'-2 1/2"	9	0.598453								
69	002 W33x130		LF		161	3.38	1.53	165.91 \$	1,449.00	\$ 30.42	\$ 13.77	\$ 1,493.19
	W18x143: 7	209'-7"	210	14.985371								
7:	.02 W33x141		LF		174	3.38	1.53	178.91 \$	36,540.00	\$ 709.80	\$ 321.30	\$ 37,571.10
	W18x234: 5	114'-8 3/8"	115	13.419696								
79	002 W36x231		LF		286	3.41	1.54	290.95 \$	32,890.00	\$ 392.15	\$ 177.10	\$ 33,459.25
	W18x258: 3	156'-7 3/16"	157	20.201026								
79	002 W36x231		LF		286	3.41	1.54	290.95 \$	44,902.00	\$ 535.37	\$ 241.78	\$ 45,679.15
	W21x44: 243	7114'-9"	7115	156.524463								
41	.02 W21x44		LF		54.5	3.6	1.63	59.73 \$	387,767.50	\$ 25,614.00	\$ 11,597.45	\$ 424,978.95
	W21x50: 44	1281'-2 3/16"	1281	32.029572								
43	802 W21x50		LF		62	3.6	1.63	67.23 \$	79,422.00	\$ 4,611.60	\$ 2,088.03	\$ 86,121.63
	W21x55: 17	529'-4 1/16"	524	14.556862								
45	602 W21x62		LF		76.5	3.7	1.67	81.87 \$	40,086.00	\$ 1,938.80	\$ 875.08	\$ 42,899.88
	W21x62: 15	368'-11 7/16"	369	11.437557								
45	602 W21x62		LF		76.5	3.7	1.67	81.87 \$	28,228.50	\$ 1,365.30	\$ 616.23	\$ 30,210.03
	W21x68: 3	89'-4 1/4"	89	3.037974								
47	702 W21x68		LF		84	3.7	1.67	89.37 \$	7,476.00	\$ 329.30	\$ 148.63	\$ 7,953.93
	W21x83: 2	62'-8"	63	2.600667	•							
57	702 W24x84		LF		104	3.55	1.6	109.15 \$	6,552.00	\$ 223.65	\$ 100.80	\$ 6,876.45
	W21x101: 10	199'-11 15/16"	200	10.099633	i							
63	.02 W30x99		LF		123	3.19	1.44	127.63 \$	24,600.00	\$ 638.00	\$ 288.00	\$ 25,526.00
	W21x111: 3	94'-0 5/16"	94	5.218304	ļ							
63	02 W30x108: 49		LF		134	3.19	1.44	138.63 \$	12,596.00	\$ 299.86	\$ 135.36	\$ 13,031.22
	W21x122: 1	31'-4"	31	1.911333	6							
69	02 W33x130		LF		161	3.38	1.53	165.91 \$	4,991.00	\$ 104.78	\$ 47.43	\$ 5,143.21
	W21x132: 4	125'-4"	125	8.272	!							
69	02 W33x130		LF		161	3.38	1.53	165.91 \$	20,125.00	\$ 422.50	\$ 191.25	\$ 20,738.75
	W21x147: 2	62'-8"	63	4.606	i							
75	602 W26x150		LF		186	3.28	1.48	190.76 \$	11,718.00	\$ 206.64	\$ 93.24	\$ 12,017.88
	W24x55: 138	4196'-5 1/4"	4196.5	115.402068	8							
49	02 W24x55		LF		68	3.45	1.56	73.01 \$	285,362.00	\$ 14,477.93	\$ 6,546.54	\$ 306,386.47
	W24x62: 40	1062'-0 7/16"	1062	32.923157	,							
51	.02 W24x62		LF		76.5	3.7	1.67	81.87 \$	81,243.00	\$ 3,929.40	\$ 1,773.54	\$ 86,945.94
	W24x68: 17	523'-0 15/16"	523	17.784575	6							
53	02 W24x68		LF		84	3.45	1.56	89.01 \$	43,932.00	\$ 1,804.35	\$ 815.88	\$ 46,552.23
	W24x76: 21	671'-1 13/16"	671	25.503735	6							
55	02 W24x76		LF		94	3.45	1.56	99.01 \$	63,074.00	\$ 2,314.95	\$ 1,046.76	\$ 66,435.71
	W24x84: 3	84'-5 3/8"	84.5	3.546886	;							
57	/02 W24x84		LF		104	3.55	1.6	109.15 \$	8,788.00	\$ 299.98	\$ 135.20	\$ 9,223.18
	W24x117: 2	62'-8 3/16"	63	3.66683								
65	02 W30x116		LF		144	3.31	1.49	148.8 \$	9,072.00	\$ 208.53	\$ 93.87	\$ 9,374.40
	W24x131: 3	73'-3 3/4"	73	4.801811	•							
69	002 W33x130		LF		161	3.38	1.53	165.91 \$	11,753.00	\$ 246.74	\$ 111.69	\$ 12,111.43
	W24x176: 2	39'-9 3/8"	40	3.500602	2							
75	02 W26x150		LF		186	3.28	1.48	190.76 \$	7,440.00	\$ 131.20	\$ 59.20	\$ 7,630.40
								-				

				9	Structural Frai	ming							
CSI Number	Family : Quantity	Measured Units	Total Units W	eight (Tons) 🛛 🛛 🛛 🛛	laterial	Labor	Equipment	Тс	otal Ma	terial Cost	Labor Cost	Equipment Cost	Total Cost
	W27x84: 22	706'-0 5/8"	706	29.654106									
59	02 W27x94		LF		116	3.22		1.45	120.67 \$	81,896.00	\$ 2,273.32	\$ 1,023.70	\$ 85,193.02
	W30x90: 14	372'-6 7/16"	372.5	16.764225									
61	LO2 W30x99		LF		123	3.19		1.44	127.63 \$	45,817.50	\$ 1,188.28	\$ 536.40	\$ 47,542.18
	W30x99: 7	124'-10 5/8"	125	6.181903									
61	.02 W30x99		LF		123	3.19		1.44	127.63 \$	15,375.00	\$ 398.75	\$ 180.00	\$ 15,953.75
	W30x108: 49	1527'-10 5/8"	1528	82.505812									
63	302 W30x108		LF		134	3.19		1.44	138.63 \$	204,752.00	\$ 4,874.32	\$ 2,200.32	\$ 211,826.64
	W30x124: 2	34'-1 3/4"	34	2.117174									
69	002 W33x130		LF		161	3.38		1.53	165.91 \$	5,474.00	\$ 114.92	\$ 52.02	\$ 5,640.94
	W33x118: 28	745'-8 15/16"	746	43.999046									
67	702 W33x118		LF		146	3.26		1.47	150.73 \$	108,916.00	\$ 2,431.96	\$ 1,096.62	\$ 112,444.58
	W33x130: 2	66'-9 3/8"	67	4.340781									
69	002 W33x130		LF		161	3.38		1.53	165.91 \$	10,787.00	\$ 226.46	\$ 102.51	\$ 11,115.97
	W33x141: 1	42'-4"	42	2.9845									
71	l02 W33x141		LF		174	3.38		1.53	178.91 \$	7,308.00	\$ 141.96	\$ 64.26	\$ 7,514.22
	W33x152: 1	56'-9 9/16"	57	4.316442									
75	502 W36x150		LF		186	3.28		1.48	190.76 \$	10,602.00	\$ 186.96	\$ 84.36	\$ 10,873.32
	W36x135: 5	170'-8 1/2"	171	11.522836									
73	302 W36x135		LF		167	3.28		1.48	171.76 \$	28,557.00	\$ 560.88	\$ 253.08	\$ 29,370.96
	W36x150: 1	32'-6 3/4"	32.5	2.442318									
75	502 W36x150		LF		186	3.28		1.48	190.76 \$	6,045.00	\$ 106.60	\$ 48.10	\$ 6,199.70
	W36x182: 1	28'-0"	28	2.548									
77	702 W36x194		LF		240	3.41		1.54	244.95 \$	6,720.00	\$ 95.48	\$ 43.12	\$ 6,858.60
	W36x231: 1	72'-0"	72	8.316									
79	902 W36x231		LF		286	3.41		1.54	290.95 \$	20,592.00	\$ 245.52	\$ 110.88	\$ 20,948.40
	W36x302: 3	151'-4"	151	22.851333									
81	102 W36x302		LF		375	3.7		1.67	380.37 \$	56,625.00	\$ 558.70	\$ 252.17	\$ 57,435.87
	W36x487: 2	144'-0"	144	35.064									
81	l02 W36x302		LF		375	3.7		1.67	380.37 \$	54,000.00	\$ 532.80	\$ 240.48	\$ 54,773.28
	Unistrut P1001: 15	157'-9 11/16"	158	0									
1	L02 W6x9		LF		11.15	4.42		2.7	18.27 \$	1,761.70	\$ 698.36	\$ 426.60	\$ 2,886.66
05 12 23.7	75 Structural Steel Members								\$	3,743,346.75	\$ 223,204.10	\$ 118,238.39	\$ 4,084,789.24

				ating Frocess							
				Slab & Decking							
SI Number Category	Material: Volume	Material: Area	Total Units N	laterial Labor	Equi	pment Total	Mat	erial Cost Lab	oor Cost	Equipment Cost	Total Cost
05 31 13.50 Floor Decking											
Floor: 1 1/2" Composite Metal Deck: 4		605 SF	605								
5120 Non-cellular composite decking, galvanized, 1-1/2" deep, 18 gauge			SF	1.92	0.43	0.03	2.38 \$	1,161.60 \$	260.15	\$ 18.15	\$ 1,4
Floor: 3" Composite Metal Deck: 26		113672 SF	113672								
5900 Non-cellular composite decking, galvanized, 3" deep, 18 gauge			SF	2	0.55	0.04	2.59 \$	227,344.00 \$	62,519.60	\$ 4,546.88	\$ 294,4
Floor: 3" Composite Metal Deck: 26		209745 SF	209745					, 1	- ,		
5900 Non-cellular composite decking, galvanized, 3" deep, 18 gauge			SF	2	0.55	0.04	2.59 \$	419,490.00 \$	115,359.75	\$ 8,389.80	\$ 543,23
Floor: 3" Composite Metal Deck: 6		8361 SF	8361								
5900 Non-cellular composite decking, galvanized, 3" deep, 18 gauge			SF	2	0.55	0.04	2.59 \$	16,722.00 \$	4,598.55	\$ 334.44	\$ 21,6
Floor: 3" Composite Metal Deck: 4		253 SF	253					-, ,	,		
5900 Non-cellular composite decking, galvanized, 3" deep, 18 gauge			SF	2	0.55	0.04	2.59 \$	506.00 \$	139.15	\$ 139.15	\$ 6
05 31 13.50 Floor Decking							\$	665,223.60 \$	182,877.20	\$ 13,428.42	\$ 861,40
05 31 23.50 Roof Decking		50005.55									
Floor: 1 1/2" 22 Ga. Metal Roof Deck: 32		59896 SF	59896	4.00	0.31	0.03	1 35 4	61 002 02	10 503 30	ć 4.407.03	ć 00.0
2400 Open Type, 1-1/2" deep, Type B, 22 Ga.		1365 SF	SF	1.02	0.31	0.02	1.35 \$	61,093.92 \$	18,567.76	\$ 1,197.92	\$ 80,8
Floor: 1 1/2" 22 Ga. Metal Roof Deck: 6		1302 24	1365 SF	1 00	0.21	0.02	1 25 6	1 202 20 6	400 4F	ć <u>37.30</u>	ć 4.
2400 Open Type, 1-1/2" deep, Type B, 22 Ga.			5F	1.02	0.31	0.02	1.35 \$.\$	1,392.30 \$	423.15	•	
05 31 23.50 Roof Decking		_				_	Ş	62,486.22 \$	18,990.91	\$ 1,225.22	\$ 82,70
03 31 Structural Concrete											
Foundation Slab: 8" Foundation Slab	155.41 CF	233 SF	5.76								
1500 6" to 10" Thick, Pumped			CY	0	14.7	4.92	19.62 \$	- \$	84.67	\$ 28.34	\$ 1
200 3500 psi			CY	99.5	0	0	99.5 \$	573.12 \$	-	\$-	\$ 5
Foundation Slab: 12" Foundation Slab	1039.78 CF	1040 SF	38.51								
400 12" Thick, Pumped			CY	0	39	13.1	52.1 \$	- Ś	1,501.89	\$ 504.48	\$ 2,0
200 3500 psi			CY	99.5	0	0	99.5 \$	3,831.75 \$	-		
Foundation Slab: 18" Foundation Slab	25.89 CF	17 SF	25.89			-		-, +		T	, .,.
600 18" Thick, Pumped			CY	0	26	18.75	44.75 \$	- \$	673.14	\$ 485.44	\$ 1,1
200 3500 psi			CY	99.5	0	0	99.5 \$	2,576.06 \$	-		
Foundation Slab: 24" Foundation Slab	501.42 CF	251 SF	18.57	55.5	0	0		2,370.00 \$		y -	2,3
800 24" Thick, Pumped	501.42 CF	231 JF	СҮ	0	25.5	8.55	34.05 \$	- \$	473.54	\$ 158.77	\$ 6
				-	25.5			· · · · ·			
200 3500 psi	167.96 CF	1008 SF	CY	99.5	U	0	99.5 \$	1,847.72 \$	-	\$-	\$ 1,8
Floor: 2 1/2" NW Concrete 1400 Elevated Slabs, less than 6" thick, pumped	167.96 CF	1008 SF	6.22 CY	0	16.8	5.6	22.4 \$	- \$	104.50	\$ 34.83	\$ 1
200 3500 psi			CY	99.5	0	0	99.5 \$	618.89 \$	-	•	•
Floor: 3 1/4" LW Concrete	91035.16 CF	349575 SF	3371.67	55.5	0	0		010.05 Ş		y -	, U
1400 Elevated Slabs, less than 6" thick, pumped	51055.10 Cl	343373 31	CY	0	16.8	5.6	22.4 \$	- \$	56,644.06	\$ 18,881.35	\$ 75,5
200 3500 psi			CY	99.5	0	0	99.5 \$	335,481.17 \$	-		
Floor: 3 1/4" NW Concrete	3628.89 CF	13935 SF	134.4			-					,
1400 Elevated Slabs, less than 6" thick, pumped			CY	0	16.8	5.6	22.4 \$	- \$	2,257.92	\$ 752.64	\$ 3,0
200 3500 psi			CY	99.5	0	0	99.5 \$	13,372.80 \$	-	\$-	\$ 13,3
Floor: 4" Concrete	21173.80 CF	63521 SF	784.21								
1400 Elevated Slabs, less than 6" thick, pumped			CY	0	16.8	5.6	22.4 \$	- \$	13,174.73	\$ 4,391.58	\$ 17,5
200 3500 psi			CY	99.5	0	0	99.5 \$	78,028.90 \$	-	\$-	\$ 78,0
Floor: 4" NW Concrete	123.11 CF	422 SF	4.55								
1400 Elevated Slabs, less than 6" thick, pumped			CY	0	16.8	5.6	22.4 \$	- \$	76.44		
200 3500 psi			CY	99.5	0	0	99.5 \$	452.73 \$	-	\$ -	\$ 4
Floor: 5" NW Concrete	63151.17 CF	189453 SF	2338.93	•	16.0	F 6		^	20.204.02	ć 40.000.04	¢ 50.0
1400 Elevated Slabs, less than 6" thick, pumped			CY	0	16.8	5.6	22.4 \$	- \$	39,294.02		
200 3500 psi	17002 65 65	24027 55	CY	99.5	0	0	99.5 \$	232,723.54 \$	-	\$-	\$ 232,7
Floor: 6" Concrete 1500 Elevated Slabs, 6" to 8" Pumped	17002.65 CF	34027 SF	629.73 CY	0	14.7	4.92	19.62 \$	- \$	9,257.03	\$ 3,098.27	\$ 12,3
200 3500 psi			СҮ	99.5	0	0	99.5 \$	62,658.14 \$	9,257.03		
Floor: 6" Concrete (loading dock)	25.68 CF	51 SF	0.95	55.5	U	U	55.5 Ş	02,030.14 \$	-	- -	φ 02,0
1500 Elevated Slabs, 6" to 8" Pumped	23.00 LF	JI JI	0.95 CY	0	14.7	4.92	19.62 \$	- Ś	13.97	\$ 4.67	\$
200 3500 psi			CY	99.5	0	0	99.5 \$	94.53 \$	-		
Floor: 8" Concrete			U 1		-	-		y		•	

New Regional Medical Center

				Struct	ural Slab & De	cking							
CSI Number	Category	Material: Volume	Material: Area	Total Units	Material	Labor	Equipment	: Total	Mat	erial Cost Lal	bor Cost	Equipment Cost	Total Cost
												·	
	00 Elevated Slabs, 6" to 8" Pumped				CY	0	14.7	4.92	19.62 \$	- \$	9,877.96		
2	00 3500 psi				CY	99.5	0	0	99.5 \$	66,861.02 \$	-	Ş -	\$ 66,861.
45	Floor: 8" Concrete S.O.G.	810.67 CF	1216 SF	12		•			10.00 4	A	47 075 00	Å = 000 =	
	00 Elevated Slabs, 6" to 8" Pumped				CY	0	14.7	4.92	19.62 \$	- \$	17,875.20	· · · · · ·	
48	40 SOG (3500psi), no reinforcing				CY	2.59	0.88	0.01	3.48 \$	3,149.44 \$	-	ş -	\$ 3,149.
	Floor: 8" NW Concrete	900.22 CF	2274 SF	33.					40.00 4	A		*	
	00 Elevated Slabs, 6" to 8" Pumped				CY	0	14.7	4.92	19.62 \$	- \$	490.10	•	•
	00 3500 psi				CY	99.5	0	0	99.5 \$	3,317.33 \$	-	,	\$ 3,317.
03 3	1 Structural Concrete								\$	805,587.09 \$	151,799.15	\$ 50,916.7	1 \$ 1,008,302. 9
03 22 05.5	0 Welded Wire Fabric- ASTM A185												
	Floor: 2 1/2" NW Concrete	167.96 CF	1008 SF	10.	.08								
2	00 W6x6-W2.1xW2.1 WWF			C-		18.9	25	0	43.9 \$	190.51 \$	252.00	<u>\$</u> -	\$ 442.
	Floor: 3 1/4" LW Concrete	91035.16 CF	349575 SF	3495.								T	•
2	00 W6x6-W2.1xW2.1 WWF			C-		18.9	25	0	43.9 \$	66,069.68 \$	87,393.75	<u>\$</u> -	\$ 153,463.
	Floor: 3 1/4" NW Concrete	3628.89 CF	13935 SF	139.								· ·	·,
2	00 W6x6-W2.1xW2.1 WWF			C-		18.9	25	0	43.9 \$	2,633.72 \$	3,483.75	\$ -	\$ 6,117.
	Floor: 4" Concrete	21173.80 CF	63521 SF	635.							-,	· ·	· · · · ·
3	00 W6x6-W2.9xW2.9 WWF			C-		21.5	26.5	0	48 \$	13,657.02 \$	16,833.07	<u>\$</u> -	\$ 30,490.
	Floor: 4" NW Concrete	123.11 CF	422 SF		.22			-				*	÷
3	00 W6x6-W2.9xW2.9 WWF			C-		21.5	26.5	0	48 \$	90.73 \$	111.83	<u>\$</u> -	\$ 202.
	Floor: 5" NW Concrete	63151.17 CF	189453 SF	1894.	-							· ·	
3	00 W6x6-W2.9xW2.9 WWF			C-		21.5	26.5	0	48 \$	40,732.40 \$	50,205.05	Ś -	\$ 90,937.
	Floor: 6" Concrete	17002.65 CF	34027 SF	340.	-							· ·	+
2	00 W6x6-W2.1xW2.1 WWF			C-		18.9	25	0	43.9 \$	6,431.10 \$	8,506.75	<u>\$</u> -	\$ 14,937.
	Floor: 6" Concrete (loading dock)	25.68 CF	51 SF	0.				-	.0.0 +	c) ic=i=c +	0,000110	*	+,
2	00 W6x6-W2.1xW2.1 WWF			C-		18.9	25	0	43.9 \$	9.64 \$	12.75	<u>\$</u> -	\$ 22.
	Floor: 8" Concrete	18143.23 CF	27215 SF	272.	-							T	
2	00 W6x6-W2.1xW2.1 WWF			C-		18.9	25	0	43.9 \$	5,143.64 \$	6,803.75	\$ -	\$ 11,947.
	Floor: 8" Concrete S.O.G.	810.67 CF	1216 SF	12.				-		-, +	-,•	•	,
3	00 W6x6-W2.9xW2.9 WWF			C-		21.5	26.5	0	48 \$	261.44 \$	322.24	\$ -	\$ 583.
	Floor: 8" NW Concrete	900.22 CF	2274 SF	22.				-	+	+		•	,
3	00 W6x6-W2.9xW2.9 WWF				-SF	21.5	26.5	0	48 \$	488.91 \$	602.61	\$ -	\$ 1,091.
	0 Welded Wire Fabric- ASTM A185								Ś	135,708.77 \$	174,527.54	•	\$ 310,236.3
00 11 00.0									7	200,700.77 9	1, 1,52,1.54	7	+ 010/1000

New Regional Medical Center

					Stru	ctural Founda	tions							
CSI Number	Family and Type	Count	Material: Volume	Reinforcing	Total Units	Material	Labor	Eq	uipmen [,] Total	Mat	erial Cost	Labor Cost	Equipment Cost	Total Cost
	-													
03 03 53.	40 Concrete In Place													
	ON-Spread Footing - 4ks		204 7417	5.28	2747.									
	848 Spread Footings (4000psi) over 5 CY				CY	190	61.5	0.31	251.81 \$	521,973.70			
03 03 53.	40 Concrete In Place									\$	521,973.70	\$ 168,954.65	\$ 851.64	\$ 691,779.99
03 21	05 Reinforcing Steel													
	Reinforcing Bars		16	#4 EWB		16								
	100 #4 Bars					ars	4.55	6.35	0	10.9 \$	72.80	\$ 101.60	\$ -	\$ 174.40
	Reinforcing Bars		13	#5 EWB		13							•	
	105 #5 Bars				B	ars	5.55	6.35	0	11.9 \$	72.15	\$ 82.55	\$ -	\$ 154.70
	Reinforcing Bars		27	#6 EWB		27								
	110 #6 Bars				Ba	ars	6.4	8.05	0	14.45 \$	172.80	\$ 217.35	\$-	\$ 390.15
	Reinforcing Bars		12	#7 EWB		12								
	120 #7 Bars				B	ars	7.45	9.3	0	16.75 \$	89.40	\$ 111.60	\$-	\$ 201.00
	Reinforcing Bars		64	#8 EWB		64								
	300 #8 Bars				B	ars	21.9	10.5	0	32.4 \$	1,401.60	\$ 672.00	\$-	\$ 2,073.60
	Reinforcing Bars		15	#9 EW T&B		15								
	305 #9 Bars				B	ars	14.1	25	7.15	46.25 \$	211.50	\$ 375.00	\$ 107.25	\$ 693.75
	Reinforcing Bars		13	#9 EWB		13								
	305 #9 Bars				B	ars	14.1	25	7.15	46.25 \$	183.30	\$ 325.00	\$ 92.95	\$ 601.25
	Reinforcing Bars		24	#10 EWB		24								
	310 #10 Bars				Ba	ars	15.7	28	7.9	51.6 \$	376.80	\$ 672.00	\$ 189.60	\$ 1,238.40
	Reinforcing Bars		10	#9 LW T&B		10								
	305 #9 Bars				Ba	ars	14.1	25	7.15	46.25 \$	141.00	\$ 250.00	\$ 71.50	\$ 462.50
	Reinforcing Bars		12	#7 SW T&B		12								
	120 #7 Bars				Bi	ars	7.45	9.3	0	16.75 \$	89.40	\$ 111.60	\$-	\$ 201.00
	Reinforcing Bars		12	#8 LWB		12								
	300 #8 Bars				Bi	ars	21.9	10.5	0	32.4 \$	262.80	\$ 126.00	\$-	\$ 388.80
	Reinforcing Bars		24	#8 SWB		24								
	300 #8 Bars					ars	21.9	10.5	0	32.4 \$	525.60	\$ 252.00	\$-	\$ 777.60
	Reinforcing Bars		20	#10 LWB w/ #10@12" SWB		20								
	310 #10 Bars					ars	15.7	28	7.9	51.6 \$	314.00	\$ 560.00	\$ 158.00	\$ 1,032.00
	Reinforcing Bars		20	#10 LWB w/ #10@12" SWB		20								
	310 #10 Bars				B	ars	15.7	28	7.9	51.6 \$	314.00			
03 21	05 Reinforcing Steel									\$	4,227.15	\$ 4,416.70	\$ 777.30	\$ 9,421.15


					Structural Found	lation Walls											
CSI Number	Category Family and Type Concrete PSI Material: V		Material: Volume	Reinforcing	Units	nits Material Labor		Equipmer Total		Material Cost	Labor Cost		Equipment Cost		Total Cost		
03 03 53.40	Concrete In Place																
	Wall Foundation: BW1: 1	Wall Foundation: BW1	30	00 108.73 CF	(3) #4 LWB #4@24 SWB	4.03											
3851	Spread Footings (3000psi) unde	er 5 CY				CY	1	03 61.	5 0.31	164.81	\$ 414.78	\$	247.66	\$1.	25 \$	\$ 663	.70
	Wall Foundation: F20.12: 31	Wall Foundation: F20.12	30	00 1524.65 CF	(93) #4 LWB. #4@24" SWB	56.47											
3850	Spread Footings (3000psi) over	5 CY				CY	1	71 61.	5 0.31	232.81	\$ 9,656.12	\$	3,472.81	\$ 17.	51 \$	\$ 13,146	.44
	Wall Foundation: F40.12: 1	Wall Foundation: F40.12	30	00 106.77 CF	(5) #4 LWB #4@24 SWB	3.95											
3851	Spread Footings (3000psi) unde	er 5 CY				CY	1	03 61.	5 0.31	164.81	\$ 407.31	\$	243.20	\$1.	23 \$	\$651	.73
03 03 53.40	Concrete In Place										\$ 10,478.21	\$ 3	,963.68	\$ 19.9	18 \$	\$ 14,461.	86
03 21 05	Reinforcing Steel																
	Reinforcing Bars				(105) #4 LWB #4@24 SWB	105											
100) #4 Bars					Bars	4.	55 6.3	50	10.9	\$ 477.75	\$	666.75	\$ -	\$	\$ 1,144	.50
03 21 05	Reinforcing Steel										\$ 477.75	\$	666.75	\$ -	1	\$ 1,144.	50


					Structural	Walls										
CSI Number	Category	Material: Volum Concrete PSI	Reinforcing	Total Units	Material	Labor	Equipment	Tot	tal N	laterial Cost	Labor Cost		Equipment Cost		ost Total Cost	
03 03 5	53.40 Concrete In Place															
	Wall Foundation	43537.32	3000 Not Provided in Model	1612.5												
	3850 Spread Footings (3000psi) over 5 CY				1	71 61.	5	0.31	251.81 \$	275,737.50	\$	99,168.75	\$	499.88	\$	406,043.63
	Basic Wall: Generic	2439.24	3000 Not Provided in Model	90.3												
	3850 Spread Footings (3000psi) over 5 CY			CY	1	71 61.	5	0.31	0\$	15,441.30	\$	5,553.45	\$	27.99	\$	-
	Basic Wall: Retaining	48557.98	3000 Not Provided in Model	1798.4												
	3850 Spread Footings (3000psi) over 5 CY					71 61.	5	0.31	0\$	307,526.40	\$	110,601.60	\$	557.50	\$	-
03 03 5	53.40 Concrete In Place								ç	598,705.20	\$	215,323.80	\$ 1,0	085.37	\$	406,043.63

				Structural Concret	e Piers										
CSI Number	r Category	Family and Type	Concrete PS Material: Volume	Reinforcing	Units	Material Lat	bor	Equipment	Tota	l Mat	erial Cost	Labor Cost	Equipment Cost	Tot	al Cost
	03 03 53.40 Concrete In Place														
	Concrete Pier	P48: 1	4000 122.67 CF	See Below	4.54	1									
	3849 Spread Footings (4000psi) under 5 CY	14012					61.5	i 0.	31 2	32.81 \$	776.91	\$ 279.4	12 \$ 1	.41 \$	1,057.73
		P3036: 1	4000 93.42 CF	See Below	3.46		01.0	· •				+			_,
	3849 Spread Footings (4000psi) under 5 CY				C		61.5	; O.	31 2	32.81 \$	591.66	\$ 212.3	79 \$ 1	.07 \$	805.52
		P20: 9	4000 98.24 CF	See Below	3.64	1							· · ·		
	3849 Spread Footings (4000psi) under 5 CY				C	۲ ۲۱	61.5	i 0.	31 2	32.81 \$	622.19	\$ 223.	7 \$ 1	.13 \$	847.08
		P24: 2	4000 78.67 CF	See Below	2.91	L									
	3849 Spread Footings (4000psi) under 5 CY				C	۲ ۲۲۱	61.5	; O.	31 2	32.81 \$	498.24	\$ 179.:	.9 \$ 0	.90 \$	678.34
		P26: 40	4000 1741.44 CF	See Below	64.50)									
	3848 Spread Footings (4000psi) over 5 CY				C	Y 190	61.5	i 0.	31 2	51.81 \$	12,254.58	\$ 3,966.	61 \$ 19	.99 \$	16,241.19
		P30: 25	4000 887.10 CF	See Below	32.86	5									
	3848 Spread Footings (4000psi) over 5 CY				C	Y 190	61.5	i 0.	31 2	51.81 \$	6,242.56	\$ 2,020.	52 \$ 10	.19 \$	8,273.36
		P34: 1	4000 28.10 CF	See Below	1.04	1									
	3849 Spread Footings (4000psi) under 5 CY				C		61.5	i 0.	31 2	32.81 \$	177.97	\$ 64.0)1 \$ 0.	.32 \$	242.29
		P48: 2	4000 244.60 CF	See Below	9.06	5									
	3848 Spread Footings (4000psi) over 5 CY				C	Y 190	61.5	i 0.	31 2	51.81 \$	1,721.26		4 \$ 2	.81 \$	2,281.21
	03 03 53.40 Concrete In Place									\$	22,885.36	\$ 7,503.5	5 \$ 37.	82 \$	30,426.73
	03 21 05 Reinforcing Steel														
	Reinforcing Bars			(16) #10 VERT. w/ #3 TIES @ 12"	16	5									
	310 #10 Bars				Bar		28	1	7.9	51.6 \$	251.20	\$ 448.0	00 \$ 126	.40 \$	825.60
	Reinforcing Bars			(16) #10 VERT. w/ #3 TIES @ 12"	16				-					- •	
	310 #10 Bars				Bar	s 15.7	28	B	7.9	51.6 \$	251.20	\$ 448.0	00 \$ 126	.40 \$	825.60
	Reinforcing Bars			(72) #8 VERT. w/ #3 TIES @ 12"	72							·			
	300 #8 Bars				Bars	s 21.9	10.5	i	0	32.4 \$	1,576.80	\$ 756.0)0 \$.	- \$	2,332.80
	Reinforcing Bars			(16) #8 VERT. w/ #3 TIES @ 12"	16	5									
	300 #8 Bars				Bars	s 21.9	10.5	;	0	32.4 \$	350.40	\$ 168.0)0 \$ ·	- \$	518.40
	Reinforcing Bars			(320) #9 VERT. w/ #3 TIES @ 12"	320)									
	305 #9 Bars				Bar	s 14.1	25	5 7.	15	46.25 \$	4,512.00	\$ 8,000.0	0 \$ 2,288	.00 \$	14,800.00
	Reinforcing Bars			(300) #8 VERT. w/ #3 TIES @ 12"	300)									
	300 #8 Bars				Bar	s 21.9	10.5	;	0	32.4 \$	6,570.00	\$ 3,150.0	0 \$.	- \$	9,720.00
	Reinforcing Bars			(10) #10 VERT. w/ #3 TIES @ 12"	1()									
	310 #10 Bars				Bar	s 15.7	28	8	7.9	51.6 \$	157.00	\$ 280.0	00\$79	.00 \$	516.00
	Reinforcing Bars			(16) #9 VERT. w/ #3 TIES @ 12"	16	5									
	305 #9 Bars				Bar	s 14.1	25	7 .	15	46.25 \$	225.60			.40 \$	740.00
	03 21 05 Reinforcing Steel									\$	13,894.20	\$ 13,650.0	0 \$ 2,734.	20 \$	30,278.40



APPENDIX H | CRANE SEQUENCE TRENDING CHARTS







APPENDIX I | CRANE LOAD CHART



Grove TMS9000E Product Guide



Features

MEGAFORM[™] boom

The Grove MEGAFORM[™] boom shape eliminates weight and increases capacity compared to conventional shapes. The unique TWIN-LOCK[™] boom pinning system automatically pins the sections in position using two horizontal large diameter pins. A single cylinder inside the boom reduces weight which has been used elsewhere to strengthen the machine.



CraneST kR

CraneSTAR is an exclusive and innovative crane asset management system that helps improve your profitability and reduce costs by remotely monitoring critical crane data. Visit www.cranestar.com for more information.

Power luffing extension

For improved up-and-over reach, a power luffing extension is available on the TMS9000E hydraulically offsettable from the superstructure cab, 5° to 40°.

Counterweight

Up to 21 999 kg (48,500 lb) of counterweight can be power installed and removed from the superstructure cab allowing for easy transport to and from the job site.

Crane Control system

Crane functions are controlled by ECOS (Electronic Crane Operating System) with CAN-BUS. The EKS5 load moment indicator provides detailed feedback and control of the crane's operating functions.





Outriggers

Two-stage inverted jack outriggers provide three position settings – 0%, 50% and 100%.









Suspension

Standard front and rear air ride suspension provides a comfortable ride at 105 kph (65 mph).

Working range



Load charts



Load handling

33 ft - 56 ft folding boom extension (luffing or manual) 657 lb hookblock

	Without	With				
*33 ft extension (erected)	6600 lb	10,800 lb				
*56 ft extension (erected)	12,300 lb	19,300 lb				

*Reduction of main boom capacities

When lifting over main boom nose with 33 ft or 56 ft extension erected, the outriggers must be fully extended or 50% extended (15 ft 5 in spread)

NOTE: All load handling devices and boom attachments are considered part of the load and suitable allowances MUST BE MADE for their combined weights. Weights are for Grove furnished equipment.

Auxiliary boom nose	133 lb
---------------------	--------

Hookblocks and headache balls:	
80 Ust, 5-sheave	1609 lb +
60 USt, 5-sheave	1281 lb +
40 Ust, 3-sheave	1019 lb +
25 Ust, 1-sheave	657 lb +
8.3 Ust, overhaul ball	355 lb +
+ Refer to rating plate for actual w	eight.

When lifting over extension and/or jib combinations, deduct total weight of all load handling devices reeved over main boom nose directly from swingaway or jib capacity.

Hoists	Cable specs	Permissible line pulls	Nominal cable length
Main and auxiliary	19 mm (3/4 in) Caser Eurolift Rotation Resistant Min. breaking strength 78,683 lb	15,736 lb	738 ft
Main and auxiliary	19 mm (3/4 in) Endurance Dyform 34 LR Rotation Resistant, Left Lang Lay Min. Breaking Strength 80,000 lb	15,736 lb	738 ft
Main and auxiliary	19mm (3/4 in) 35x7 Class Rotation Resistant Min. breaking strength 85,800 lb	17,160 lb	702 ft

The approximate weight of 3/4 in wire rope is 1.5 lb/ft


	Hoist performa	ıce	
Wire rope layer	Hoist line pools	Drum rope o	apacity (ft)
	Available lb*	Layer	Total
1	22,122	109.95	109.95
2	20,247	120.14	230.09
3	18,665	130.32	360.41
4	17,312	140.50	500.91
5	16,142	150.68	651.59
6	15,120	160.87	812.46
WARAN CONTRACTOR	!		

*Max lifting capacity

19 mm Casar Eurolift: 15,736 lb


19 mm 35x7 Class: 17,160 lb

Working area diagram



Bold lines determine the limiting position of any load for operation within working areas indicated.

Symbols glossary





Manitowoc Cranes

Regional headquarters

Americas

Manitowoc, Wisconsin, USA Tel: +1 920 684 6621 Fax: +1 920 683 6277

Shady Grove, Pennsylvania, USA Tel: +1 717 597 8121 Fax: +1 717 597 4062

Regional offices

Americas

Brazil Alphaville Mexico Monterrey Chile Santiago

Europe, Middle East, Africa

Czech Republic Netvorice France Baudemont Cergy Decines Germany Langenfeld Hungary Budapest Italy Lainate Netherlands Breda Poland Warsaw Portugal Baltar Russia Moscow U.A.E. Dubai U.K. Buckingham

China Beijing Chengdu Guangzhou Xian

Greater Asia-Pacific Australia

Adelaide Brisbane Melbourne Sydney India Calcutta Chennai Delhi Hyderabad Pune Korea Seoul Philippines Makati City Singapore

Europe, Middle East, Africa

Ecully, France

Tel: +33 (0)4 72 18 20 20

Fax: +33 (0)4 72 18 20 00

Factories

Brazil Alphaville China TaiAn Zhangjiagang France Charlieu Moulins Germany Wilhelmshaven India Pune Italy Niella Tanaro Portugal Baltar Fânzeres Slovakia Saris USA Manitowoc Port Washington Shady Grove

Fax: +86 21 6457 4955

Shanghai, China

Tel: +86 21 6457 0066

China

Greater Asia-Pacific Singapore Tel: +65 6264 1188 Fax: +65 6862 4040

This document is non-contractual. Constant improvement and engineering progress make it necessary that we reserve the right to make specification, equipment, and price changes without notice. Illustrations shown may include optional equipment and accessories and may not include all standard equipment.



APPENDIX J | CRITICAL PATH SCHEDULE

	-	i	1	-																				-			_		 -		
<i>v</i> ity Name	Start	Finish	Original Duration	Oct	tr 4, 2010 Nov			tr 1, 2011	1 Mar	_	Qtr 2,		ı Jul	Qtr 3, 2				4, 2011			tr 1, 20 ⁻	12 Mar	-	Qtr 2, 20	-	-	Qtr 3, 20		 Qtr 4, 20		1, 2 Ja
Total	29-Oct-10	15-Oct-12	500		INOV	Dec	Jan	Feb	IVIAI	Apr	Ma	ay Jun	Jui	Aug	j Se	ep C		lov	Dec	Jan	Feb	Iviar	Apr	Мау	Jun	Jul	Aug	Sep	 Nov 5-Oct-1	_	Je
Critical Path	29-Oct-10	15-Oct-12	500																										5-Oct-1	2, Critica	l Path
Underslab Utilities	29-Oct-10*	09-Mar-11	91						l Un	derslab	Litilitie	29										1									
Domestic Water & Fire	13-Dec-1(40					Dom		Water &	1.1.1				į															i.	
Structural Steel Sequence 4 - 9	17-Dec-1(16	-			Str	uctural S		1					-						1	1								-	
Structural Steel Sequence 16 - 21	03-Jan-11*		16			· + -		Structura			!																		 		
Prepare & Place Slab on Grade Low Rise	25-Jan-11*		20					L L		1.		b on Grad	i ie i ow F	¦ Rice															-		
Prepare & Place Slab on Grade Tower Area	22-Feb-11*		10	1				i i		1		Slab on C			a							1									
•	14-Mar-11*		20	-						- 11	- <u>!</u>	n FP Inter	1	1		Fround	=loor				1	1 1 1							- - -	-	
Frame Non-Accessible Walls (Sector 4B)	31-Mar-11*		20							-i - i	1.5	on-Access	- i	- i	- i -	lioqiid	1001					1							-	1	
Drywall Non-Accessible Walls (Sector 4B)	04-Apr-11*		2		+	·					!	Non+Acces			!														 		
Sheet Metal Overhead Rough In (Sector 4B)	07-Apr-11*	•	20	-							- I	heet Meta	1	1	1	1	B)					1							-	1	
Frame Non-Accessible Walls (Sector 3A)	14-Apr-11*		20									e Non-Acc					<u>ر</u> م.					1 1 1								1	
Drywall Non-Accessible Walls (Sector 3A)	14-Apr-11 18-Apr-11*	•	2	1		1				1	1	all Non-Acc	1			· · ·						1							-	1	
			_								Чтуw				- i -	1.1					1	1 1 1								-	
Sheet Metal Overhead Rough In (Sector 3A)	25-Apr-11*	-	20											verhead	-	r	tor 3A)												 		
Frame Non-Accessible Walls (Sector 3B)	28-Apr-11*	•	2	-							1	ame Non-	1	1	1	1					1	 							-		
Drywall Non-Accessible Walls (Sector 3B)	02-May-1 ⁻	-	3									rywall No										1								1	
Sheet Metal Overhead Rough In (Sector 3B)	09-May-1		20									1	1	alOverh	1	- 1	· •	r 3B)			1	1 1 1							-		
Frame Non-Accessible Walls (Sector 2A)	12-May-1 ⁻	-	2								i i	Frame N		i i	- i `	i	1 i i					1							-	1	-
Drywall Non-Accessible Walls (Sector 2A)	16-May-1 ⁻		3								I	Drywal				` <u>'</u>	1 !					 							 		
Sheet Metal Overhead Rough In (Sector 2A)	23-May-1 ⁻		20	-								i i i i i i i i i i i i i i i i i i i	1	Metal O	1.1	1 7	í.	ector 2/	4)			1 1 1	-						-	1	
Frame Non-Accessible Walls (Sector 2B)	26-May-1 ⁻	•	2											Accessib							1	1 1 1								-	
Drywall Non-Accessible Walls (Sector 2B)	31-May-1 ⁻		3									Dry		n-Access	1	1.1	1 1	· · · ·				1								-	
Sheet Metal Overhead Rough In (Sector 2B)	06-Jun-11*		20										1	et Meta	1	1			r 2B)		1	1 1 1									
Frame Non-Accessible Walls (Sector GA)	09-Jun-11*	10-Jun-11	2					¦						on-Acce	!			!				 				ļ			 	<u> </u>	
Drywall Non-Accessible Walls (Sector GA)	13-Jun-11*	15-Jun-11	3										1.5	Non-Ao				· · · ·			1	1 1 1								-	-
Sheet Metal Overhead Rough In (Sector GA)	20-Jun-11*	18-Jul-11	20										!	Sheet I	Metal O	verhead	l Rough	h In (S	ector G	A)	1	1							-	-	
Frame Non-Accessible Walls (Sector GC)	23-Jun-11*	24-Jun-11	2										Fram	e Non-A	locessib	ole Wall	s (Secto	or GC)				- - - -								i.	
Drywall Non-Accessible Walls (Sector GC)	27-Jun-11*	29-Jun-11	3										Dry	wall Non	-Access	siblę Wa	alls (Sec	ctor Ġ0	C)			1								-	
Sheet Metal Overhead Rough In (Sector GC)	05-Jul-11*	01-Aug-11	20											📕 She	et Meta	al Overl	nead Ro	ough	n (Secto	or GC)										i.	
Frame Non-Accessible Walls (Sector 1A)	07-Jul-11*	08-Jul-11	2										I F	rame No	on-Acce	essible V	Valls (S	Sector	1A)												
Drywall Non-Accessible Walls (Sector 1A)	11-Jul-11*	13-Jul-11	3											Drywall I	Non-Ac	cessible	Walls ((Secto	r 1A)											i.	
Sheet Metal Overhead Rough In (Sector 1A)	18-Jul-11*	12-Aug-11	20			1									Sheet N	/letal O	erhead	Roug	h In (Se	ector 1A)	1								-	
Frame Non-Accessible Walls (Sector 1B)	25-Jul-11*	26-Jul-11	2											Fram	ne Non-	Access	ble Wa	alls (Se	ctor 1B)										i.	
Drywall Non-Accessible Walls (Sector 1B)	29-Jul-11*	02-Aug-11	3	-		1								📙 Dry	/wall No	on-Ácce	ssible V	Valls (S	Sector 1	B)									1	-	-
Sheet Metal Overhead Rough In (Sector 1B)	01-Aug-11	26-Aug-11	20	·;		·									She	et Meta	l Overh	nead R	ough In	(Secto	r 1B)	; 			- †				 		
Frame Non-Accessible Walls (Sector 1C)	08-Aug-11	09-Aug-11	2	-		1								I F	1	Ion-Acc						1								-	-
Drywall Non-Accessible Walls (Sector 1C)	12-Aug-11		3												Drywa	ll Non-A	ccessib	ole Wa	lls (Sec	or 1C)											
Sheet Metal Overhead Rough In (Sector 1C)	15-Aug-11	-	20			1									1.		1				ector 10	;)								-	
HVAC Overhead Piping Rough In (Sector 1C)	22-Aug-11	19-Sep-11	20	1		1									i	HVA	C Overh	head P	iping R	ough In	(Sector	1C)		-						1	
Med Gas Overhead Piping Rough In (Sector 1C)	22-Aug-11		20	·¦ ·		+									·¦ ·			'			In (Sec				- +				 		
	22-Aug-11	-	20	1												1	1		1		Rough	1	1							-	
Sprinkler Overhead Rough In (Sector 1C)	29-Aug-11		20	1											;			i			Sector 1	i - i									
Electrical Overhead Rough In (Sector 1C)	06-Sep-11	-	20	1										-		1 .					(Sector	1.1	-				-			-	
FA/Security Overhead Rough In (Sector 1C)	06-Sep-11		20													1			1		In (Sec	1									
Activity V Summary	-				· ·	1		· I			•	Page 1 of			,	1	1	1		-	GIONAL	,									<u> </u>

AE 481W -	Senior	Thesis
-----------	--------	--------

BRIAN NAHAS

vity Name	Start	Finish	Original	C.	0tr 4, 2010		Qtr 1, 2011		Qtr	2, 2011	IANAGE	Qtr 3, 20	11	Qtr 4, 2011	Otr	1,2012		Qtr 2, 2012	Qtr 3, 2	012	Qtr 4,	2012	1
			Duration	Oct		ec Jan	· · ·	Mar		May Ju	ın Ji	ul Aug	Sep			Feb Ma		May Jun	Jul Aug		Oct No		Dec
Controls Overhead Rough In (Sector 1C)	06-Sep-11	03-Oct-11	20											Controls Overhea	1 7 1	1 .							
Med Gas Alarms Overhead Rough In (Sector 1C)	06-Sep-11	03-Oct-11	20											Med Gas Alarms	Overhead Rou	igh In (Sect	or 1C)						
Complete Frame Partition Walls & HM Frames (S	29-Sep-11	12-Oct-11	10											Complete Fran	me Partition Wa	alls & HM F	rames (Se	ctor 1C)					
Plumbing In-Wall Rough In (Sector 1C)	17-Oct-11*	18-Nov-11	25											Plum	nbing In-Wall R	ough In (Se	ector 1C)						
Electrical In-Wall Rough In (Sector 1C)	17-Oct-11*	18-Nov-11	25											Electi	trical In-Wall Ro	ough In (Se	ctor 1C)						i
Med Gas In-Wall Rough In (Sector 1C)	17-Oct-11*	18-Nov-11	25											Med	Gas In-Wall Re	ough In (Se	ector 1C)						
FA/Security In-Wall Rough In (Sector 1C)	17-Oct-11*	18-Nov-11	25											FA/Se	Security In-Wall	Rough In (Sector 1C)						
Pneumatic Tube In-Wall Rough In (Sector 1C)	17-Oct-11*	18-Nov-11	25											Pneu	umatic Tube In-	Wall Rough	n In (Secto	r 1C)					
Plumbing In-Wall Inspections (Sector 1C)	21-Nov-11	21-Nov-11	1											I Plum	mbing In-Wall I	nspections ((Sector 1C)					
Electrical In-Wall Inspections (Sector 1C)	21-Nov-11	21-Nov-11	1											I Elec	ctrical In-Wall Ir	nspections (Sector 1C))				-	
Drywall Partition Walls/Gyp. Ceilings (Sector 1C)	21-Nov-11	19-Dec-11	20												Drywall Pai	rtition Walls	/Gyp. Ceilii	ngs (Sector 1C)					
Atrium Flooring	25-Nov-11	22-Dec-11	20												Atrium Flo	oring							
Drywall Finishes Walls/Gyp. Ceilings (Sector 1C)	28-Nov-11	23-Dec-11	20												📕 Drywall Fi	nishes Wall	s/Ġyp. Cei	lings (Sector 1C)				
Protect Atrium Floor	27-Dec-11	03-Jan-12	5												E Protect	Atrium Floo	or						
Erect Scaffolding (Atrium)	04-Jan-12*	17-Jan-12	10												📕 Ere	ct Scaffoldi	ng (Atrium))					
Sheet Metal Overhead Rough In (Atrium)	18-Jan-12*	14-Feb-12	20											i		Sheet N	Metal Over	head Rough In ((Atrium)				
HVAC Piping Overhead Rough In (Atrium)	23-Jan-12*	17-Feb-12	20													HVAC	Piping Ove	erhead Rough Ir	n (Atrium)			-	
Sprinkler Overhead Rough In (Atrium)	30-Jan-12*	17-Feb-12	15												-	S prink	ler Overhe	ad Rough In (At	rium)				
Electrical Overhead Rough In (Atrium)	30-Jan-12*	17-Feb-12	15													Electri	cal Overhe	ad Rough In (At	trium)				
Frame Gyp. Ceiling (Atrium)	20-Feb-12*	* 09-Mar-12	15													- F	rame Gyp	. Ceiling (Atrium)				
Electrical Rough In at Ceiling (Atrium)	27-Feb-12'	* 09-Mar-12	10													E E	Electrical R	o¦ugh In at Ceilin	ıġ (Atrium)		L		
Sprinkler Rough In at Ceiling (Atrium)	27-Feb-12'	* 09-Mar-12	10													— 9	Sprinkler R	ough In at Ceilin	g (Atrium)				
Drywall Ceiling (Atrium)	05-Mar-12'	* 16-Mar-12	10														Drywall C	eiling (Atrium)					i
Acoustical Ceiling Grid (Atrium)	12-Mar-12'	* 23-Mar-12	10														Acousti	cal Ceiling Grid (Atrium)				
Tape & Sand Ceiling (Atrium)	19-Mar-12'	* 23-Mar-12	5													1	Tape &	Sand Ceiling (A	trium)				
Prime & 1st Coat Paint (Atrium)	26-Mar-12*	* 30-Mar-12	5					L 									Prime	& 1st Coat Pair	nt (Atrium)		LL 		
Light Fixture & Sprinkler Heads (Atrium)	26-Mar-12*	* 06-Apr-12	10														Ligh	nt Fixture & Spri	nkler Heads (At	rium)			
Final Paint (Atrium)	02-Apr-12*	13-Apr-12	10														📃 📕 Fi	inal Paint (Atriun	n)			-	
Millwork / Architectural Finishes (Atrium)	16-Apr-12*	11-May-12	20															Millwork /	Architectural Fin	nishes (Atr	um)		
Electrical Trim & Finishes (Atrium)	07-May-1:	18-May-12	10															Electrica	I Trim & Finishe	s (Atrium)			
Remove Scaffolding (Atrium)	21-May-1:	25-May-12	5											<u></u>				Remov	ve Scaffolding (Atrium)			
A/E Prepare Punchlist		04-Jun-12	5															1 1	Prepare Punch	1			
Corrective Work	04-Jun-12*	22-Jun-12	15																Corrective Wo	ork			
		29-Jun-12	5															1 1	Final Walk T		Off		
DOH Inspections Ground Floor		16-Jul-12	10																DOH In	-			
FInal Inspections & Certifications		27-Jul-12	10																		ns & Certifica	!	
Substantial Completion	30-Jul-12*		0																1 1	stantial Co		1	
-		15-Oct-12	54																			ete Puno	nch Lis
Final Completion	15-Oct-12*		0			1															Final C	1	



APPENDIX K | POUR STOP QTO & ESTIMATE

round Level Sector A & B il Number System	Total Units	Ma	terial L	abor Equ	Jipment To	otal Ma	terial Cost Labor Cost	Equipment Cost	Total	Cost
03 31 Structural Concrete										
Floor: 4" NW Concrete		6.64	2.50	0.00	0.01	3.48 S	17.20 €	5.84 Ś	0.07 Š	23
4840 SOG (3500psi), no reinforcing 200 3500 psi		CY	2.59 99.5	0.88	0.01	3.48 \$ 99.5 \$	17.20 \$ 660.68 \$	- \$	- \$	660
03 22 05.50 Welded Wire Fabric- ASTM A185		8.2								
200 W6x6-W2.1xW2.1 WWF		8.2 C-SF	18.9	25	0	43.9 \$	154.98 \$	205.00 \$	- \$	35
st Level Sector A & B										
l Number System	Total Units	Ma	terial L	abor Equ	uipment To	otal Ma	terial Cost Labor Cost	Equipment Cost	Total	Cost
05 12 23.17 Columns, Structural										
W14x48: 4		224								
3702 W18x50 W14x43: 2		LF 104	62	4.2	1.9	68.1 \$	13,888.00 \$	940.80 \$	425.60 \$	15,25
3102 W16x40		LF	49.5	3.32	2.03	54.85 \$	5,148.00 \$	345.28 \$	211.12 \$	5,70
05 31 13.50 Floor Decking 3" 18 Gage Lok-Floor Composite Deck		410								
5900 Non-cellular composite decking, galvanized, 3" deep	, 18 gauge	SF	2	0.55	0.04	2.59 \$	820.00 \$	225.50 \$	16.40 \$	1,06
03 31 Structural Concrete Floor: 3 1/4" LW Concrete		6.64								
1400 Elevated Slabs, less than 6" thick, pumped		CY	0	16.8	5.6	22.4 \$	- \$	111.55 \$	37.18 \$	14
200 3500 psi 03 22 05.50 Welded Wire Fabric- ASTM A185		CY	99.5	0	0	99.5 \$	660.68 \$	- \$	- \$	66
W6x6-W2.0xW2.0 WWF		8.2								
200 W6x6-W2.1xW2.1 WWF		C-SF	18.9	25	0	43.9 \$	154.98 \$	205.00 \$	- \$	35
cond Level Sector A & B										
I Number System	Total Units	Ma	terial L	abor Equ	Jipment To	otal Ma	terial Cost Labor Cost	Equipment Cost	Total	Cost
05 12 23.17 Columns, Structural										
W14x48: 4 3702 W18x50		224 LF	62	4.2	1.9	68.1 \$	13,888.00 \$	940.80 \$	425.60 \$	15,25
W14x43: 2		104								
3102 W16x40 05 31 13.50 Floor Decking		LF	49.5	3.32	2.03	54.85 \$	5,148.00 \$	345.28 \$	211.12 \$	5,70
3" 18 Gage Lok-Floor Composite Deck		410								
5900 Non-cellular composite decking, galvanized, 3" deep 03 31 Structural Concrete	, 18 gauge	SF	2	0.55	0.04	2.59 \$	820.00 \$	225.50 \$	16.40 \$	1,06
Floor: 3 1/4" LW Concrete		6.64								
1400 Elevated Slabs, less than 6" thick, pumped 200 3500 psi		CY CY	0 99.5	16.8 0	5.6 0	22.4 \$ 99.5 \$	- \$ 660.68 \$	111.55 \$ - \$	37.18 \$ - \$	14
03 22 05.50 Welded Wire Fabric- ASTM A185		Cr	59.5	Ū	U	99.5 \$	660.68 \$	- ,	- ,	
W6x6-W2.0xW2.0 WWF 200 W6x6-W2.1xW2.1 WWF		8.2 C-SF	18.9	25	0	43.9 \$	154.98 \$	205.00 \$	- \$	3
200 W0X0-W2.1XW2.1 WWF		C-SF	16.9	25	U	43.3 3	154.96 \$	205.00 \$	- \$	3:
rd Level Sector A & B	*		terdel to the						Tata	6
Number System	Total Units	Ma	terial Li	abor Equ	Jipment To	otal Ma	terial Cost Labor Cost	Equipment Cost	Total	Cost
05 12 23.17 Columns, Structural W14x48: 4		224								
W14x48: 4 3702 W18x50		LF	62	4.2	1.9	68.1 \$	13,888.00 \$	940.80 \$	425.60 \$	15,25
W14x43: 2		104								
3102 W16x40 05 31 13.50 Floor Decking		LF	49.5	3.32	2.03	54.85 \$	5,148.00 \$	345.28 \$	211.12 \$	5,70
3" 18 Gage Lok-Floor Composite Deck	40	410 SF		0.55		2.50.4	820.00 \$	225.50	16.40 \$	1,06
5900 Non-cellular composite decking, galvanized, 3" deep 03 31 Structural Concrete	18 gauge	5F	2	0.55	0.04	2.59 \$	820.00 \$	225.50 \$	16.40 \$	1,08
Floor: 3 1/4" LW Concrete		6.64	-				· · ·			
1400 Elevated Slabs, less than 6" thick, pumped 200 3500 psi		CY CY	0 99.5	16.8 0	5.6	22.4 \$ 99.5 \$	- \$ 660.68 \$	- \$	37.18 \$	14
03 22 05.50 Welded Wire Fabric- ASTM A185										
W6x6-W2.0xW2.0 WWF 200 W6x6-W2.1xW2.1 WWF		8.2 C-SF	18.9	25	0	43.9 \$	154.98 \$	205.00 \$	- \$	35
								·		
urth Level Sector A & B I Number System	Total Units	Ma	terial L	abor Equ	Jipment To	otal Ma	terial Cost Labor Cost	Equipment Cost	Total	Cost
								-4		
05 12 23.17 Columns, Structural W14x48: 4		224								
3702 W18x50		LF	62	4.2	1.9	68.1 \$	13,888.00 \$	940.80 \$	425.60 \$	15,25
W14x43: 2 3102 W16x40		104 LF	49.5	3.32	2.03	54.85 \$	5,148.00 \$	345.28 \$	211.12 \$	5,70
05 31 13.50 Floor Decking					2.05	2	-,000 y			3,70
3" 18 Gage Lok-Floor Composite Deck 5900 Non-cellular composite decking, galvanized, 3" deep	18 gauge	410 SF	2	0.55	0.04	2.59 \$	820.00 \$	225.50 \$	16.40 \$	1,0
03 31 Structural Concrete	- -			2,00	0.04	, ¢	0,00 ¥			2,01
Floor: 3 1/4" LW Concrete 1400 Elevated Slabs, less than 6" thick, pumped		6.64 CY	0	16.8	5.6	22.4 \$	- \$	111.55 \$	37.18 \$	14
200 3500 psi		CY	99.5	0	0	99.5 \$	660.68 \$	- \$	- \$	66
03 22 05.50 Welded Wire Fabric- ASTM A185		8.2								
200 W6x6-W2.1xW2.1 WWF		8.2 C-SF	18.9	25	0	43.9 \$	154.98 \$	205.00 \$	- \$	35
nthouse Level Sector A & B										
I Number System	Total Units	Ma	terial L	abor Equ	Jipment To	otal Ma	terial Cost Labor Cost	Equipment Cost	Total	Cost
05 12 23.17 Columns, Structural										
W14x43: 6		328								
3102 W16x40		LF	49.5	3.32	2.03	54.85 \$	16,236.00 \$	1,088.96 \$	665.84 \$	17,9
05 31 13.50 Floor Decking 3" 18 Gage Lok-Floor Composite Deck		246								
5900 Non-cellular composite decking, galvanized, 3" deep		SF	2	0.55	0.04	2.59 \$	492.00 \$	135.30 \$	9.84 \$	6
		221.4 SF	1.02	0.31	0.02	1.35 \$	225.83 \$	68.63 \$	4.43 \$	2
1 1/2" 22 Gage Type 'B' Metal Roof Deck 2400 Open Type, 1-1/2" deep, Type B, 22 Ga.										
2400 Open Type, 1-1/2" deep, Type B, 22 Ga. 03 31 Structural Concrete		2.656	0	16.8	5.6	22.4 \$	- \$	44.62 \$	14.87 \$	
2400 Open Type, 1-1/2" deep, Type B, 22 Ga. 03 31 Structural Concrete Floor: 3 1/4" LW Concrete		CY			0	99.5 \$	264.27 \$	- \$	- \$	2
2400 Open Type, 1-1/2" deep, Type B, 22 Ga. 03 31 Structural Concrete Floor: 3 1/4" LW Concrete 1400 Elevated Slabs, less than 6" thick, pumped 200 3500 psi		CY	99.5	0						
2400 Open Type, 1-1/2' deep, Type B, 22 Ga. 03 31 Structural Concrete Floor: 31/4' LW Concrete 1400 Elevated Slabs, less than 6' thick, pumped 200 3500 pci Floor: 5' NW Concrete				0	5.6	22.4 \$	- \$	66.93 \$	22.31 \$	
2400 Open Type, 1-1/2" deep, Type B, 22 Ga. 03 31 Structural Concrete Floor: 3 1/4" LW Concrete 1400 Elevated Slabs, less than 6" thick, pumped 200 300 psi Floor: 5" NW Concrete 1400 Elevated Slabs, less than 6" thick, pumped 200 300 psi		CY 3.984	99.5				- \$ 396.41 \$			
2400 Open Type, 1-1/2" deep, Type 8, 22 Ga. 03 31 Structural Concrete Floro: 31/4" LW Concrete 1400 Elevated Slabs, less than 6" thick, pumped 200 3500 pis Floro: 5" NW Concrete 1400 Elevated Slabs, less than 6" thick, pumped 200 3500 pis 03 22 05:50 Welded Wire Fabric- ASTM A185		СҮ 3.984 СҮ СҮ	99.5 0	16.8	5.6	22.4 \$		66.93 \$	22.31 \$	
2400 Open Type, 1-1/2" deep, Type B, 22 Ga. 03 31 Structural Concrete Floor: 3 1/4" LW Concrete 1400 Elevated Slabs, less than 6" thick, pumped 200 3500 psi Floor: 5" NW Concrete 1400 Elevated Slabs, less than 6" thick, pumped 200 300 psi 03 22 05.50 Welded Wire Fabric- ASTM A185 Wose-W2.0.WU2 NWF 200 Wose-W2.1.WUF		CY 3.984 CY CY 3.28 C-SF	99.5 0	16.8	5.6	22.4 \$		66.93 \$	22.31 \$	8 39 14
2400 Open Type, 1-1/2" deep, Type B, 22 Ga. 03 31 Structural Concrete Floor: 3 1/4" LW Concrete 1400 Elevated Slabs, less than 6" thick, pumped 200 3500 psi Floor: 5" WW Concrete 1400 Elevated Slabs, less than 6" thick, pumped 200 3500 psi 03 22 05.50 Weided Wire Fabric- ASTIM A185 Weide Wure Fabric- WWF		CY 3.984 CY CY 3.28	99.5 0 99.5	16.8 0	5.6 0	22.4 \$ 99.5 \$	396.41 \$	66.93 \$ - \$	22.31 \$ - \$	3

05 12 23.17 Columns, Structural											
W12x87	336.3333333										
5702 W24x76	LF	94	3.45	1.56	99.01	\$ 31,615.33	\$ 1,1	60.35 \$	524.0	68 \$	33,300.36
W12x120	55.5										
2502 W14x120	LF	149	3.68	2.25	154.93	\$ 8,269.50	\$ 2	04.24 \$	124.1	88 \$	8,598.62
W12x106	86.5										
6302 W30x108	LF	134	3.19	1.44	138.63	\$ 11,591.00	\$ 2	75.94 \$	124.	56 \$	11,991.50
W12x79	74										
5502 W24x76	LF	94	3.45	1.56	99.01	\$ 6,956.00	\$ 2	55.30 \$	115.4	44 Ş	7,326.74
Foundation Systems											
CSI Number System	Total Units Mater	al La	bor Equipmen	nt T	Total	Material Cost	Labor Cost	Equ	ipment Cost	To	tal Cost
03 03 53.40 Concrete In Place											
Footing: 3' Thick Concrete	15.56										
3848 Spread Footings (4000psi) over 5 CY	CY	190	61.5	0.31	251.81	\$ 2,955.56	\$ 9	56.67 \$	4.1	82 \$	3,917.04
Footing: 2'-6" Thick Concrete	34.65										
3848 Spread Footings (4000psi) over 5 CY	CY	190	61.5	0.31	251.81	\$ 6,584.03	\$ 2,1	31.15 \$	10.3	74 \$	8,725.92
Footing: 2'-10" Thick Concrete	32.79										
3848 Spread Footings (4000psi) over 5 CY	CY	190	61.5	0.31	251.81	\$ 6,230.71	\$ 2,0	16.78 \$	10.:	17 \$	8,257.66
Footing: 4'-6" Thick Concrete	153.33										
3848 Spread Footings (4000psi) over 5 CY	CY	190	61.5	0.31	251.81	\$ 29,133.33	\$ 9,4	30.00 \$	47.	53\$	38,610.87
03 21 05 Reinforcing Steel											
Reinforcing Bars	82										
300 #8 Bars	Bars	21.9	10.5	0	32.4	\$ 1,795.80	\$ 8	61.00 \$	-	\$	2,656.80
Reinforcing Bars	24										
120 #7 Bars	Bars	7.45	9.3	0	16.75	\$ 178.80	\$ 2	23.20 \$	-	\$	402.00
Reinforcing Bars	40										
310 #10 Bars	Bars	15.7	28	7.9	51.6	\$ 628.00	\$ 1,1	20.00 \$	316.0	00 \$	2,064.00
Pour Strip System Total Cost							Ś			2	39,772.05



APPENDIX L | EXPANSION JOINT STRUCTURAL ANALYSIS

BRIAN NAHAS

ANALYSIS #3

EXPANSION JOINT SIZING

DES

SIGN TEMPER	CATURE:					
AT =	(Tw-Tm)	or ($(T_m - T_c)$	[WHICHEVE	er is Grea	TER

TIM = MEAN CONSTRUCTION SEASON TEMP.	0.0	550
Tw = SUMMER EXPREME WO	00	910
TC = WINTER EXTREME D6	:	110
DT = (36°F) or (44°F)		
$\Delta T = (36T) or (79F)$		

FROM ASHRAE 1997-* REFERENCE PHILADELPHIA AIRDOLT DATA

APPENDIX B

ALLOWARDE BUNDING LENGTHS RER FIGURE I IN TECH REPORT 65 [EVE. JOINTS IN BLOGS]

> DESIGN TEMP = 44°F ALLO-NELE LENGTH = 250' L- NON-RECTANGULAR CONFIGURATION (ANYMATECIAL)

CORRECTION FACTORS = A/C \$ NEAT \$15% LATERAL BRACE AT ENDS RELATIVE TO JOINT -25%

250' × (.9) = 225' ALLOWABLE LENGTH

BULDING LENGTH 3 556' - USE Z JOINTS IN PATENT TAVER L- CAN PLACE IN TVP. SPACE OF BUR STRIP. @ 125' FROM EXTRIOR EDGE OF BULDING

EXP. JOINT TO EXTEND OVER ENTIRE HEIGHT OF BUILDING LE TOP OF FOUNDATION THROUGH BOOF. --- CAN SHARE A FOOTING.

UPPER BOND CALCULATION - HORRONTAL JOINT CLOSING UB = G×106. At. . L


> L= EFFECTIVE LENGTH ste= (Tw-Te)

· UB= 6×106× 30°F · 125' UB= .06'

CONSTRUCTION TOLEPANCE & SEALANT - EXP. JOINT WIDTH W = C, - UB

 $C_{1} = 1.4 \text{ FOR HEATED } \neq A/c BULDINGS EJ-TMM-200W-W EJ-TMM-200-W U = 1.4.06 Z° DRENING 7.75"SYSTEM W = .084 Ft = 1.008 INCHES - USE NYSTRAM Dable SEAM$


AMPA




BRIAN NAH	15	ANALYSIS	#3		3
LIVE LOAD	REDUCTIONS.		LOAD CAL	EULATIONS	
				LEMENTS ON S-051.	
PENTHOUSE	-		SHO	MAN IN TABLES IN R	EPSIZI -
4TH FLOOR		-> 0.4	FLOSE LOA		
T PLOOK				DL: 65 PSF	
3RD FLOOR				L: 100 PSF	
		- 0.4			
2ND FLOOR		-0.7	ROOF LOAD	os -	1 1
		0.4		DL: 45 PSF(MECH)/	25 PSF (TYP)
1ST FLOOR				L: 30 PSF	
C. En		-> 0.4	a ll a a	S: 26 PSF	
GRAND FLOOR	L		FXTERIOR PBE	ECAST LOAD	
				L: 100 PSF (150 PC	= @ B"THICK)
* KL= 14	+-3" = USE H	SL= 15'			
* USE A	u wiz's	TO CORRES	SPOND WITH REST	OF COLLMAN SYSTEM	
	2D + 1.6L				
		F	L 4 4 1 7 2	2	
Column D	.5.0 \$ A.5.	0 [0.0-160	+ A.A -16.0]	SoTH Carmins	
Perman	12/25)/2	122)+16	26)(219.38) = 15;	7 K 58.47k	
	- 7	OUR			
4TH FLOOR	. 1.2(25)(219.3	3)+.5(26	(219.38) + 1.2 (0	(219.38) + 1.2 (100)	344.67)
	+ 1.6 (0.4)	(100)(1)(219	133), = 81.	87K	
		14 K	44.7.6	(219.33) + 1.2 (100) 87 k	17
3RD FLOOR :	9.4 + 1.	2(65)(219.3)	3)+1.2(100)(229.7	-8)+[58.47 +2[1	4 K
			= 140.	.57 "	
2ND FLOOR :	QUE +E	347K + 7	[44.7 k] + 3[14 k]] = 19977 k	
L MOR .					
IST FLOOR :	9.4 k + 58	5.47K +35	44.7 K] +4[14K	7 = 257.97k	
GRAND =	9.4 - + 53.4	174 + 4[4	1476]+5[14K	= 316.67 K	
					1 400
2				FROM TABLE 4	-1 AISC
PENTHOLSE 4TH FLOOR	15.7k 81.97k		SIZE@ 81.87 k	WIZX40	
3RD FLOOR	140.57 K	SPLICE			
ZNO FLOOR	199.27 k	-	SIZE @ 199.27 6	WIZX40	
1ST FLORE	257.97 K	SPLICE	SIZE@ 316.67 6	WIZ×50	
GROMD	36.67 K		STEECE STURAT		
1					

Annand

ANALYSIS #3 4 BRIAN NAHAS Carman B.5.0 \$ C.5.0 [B.B-16.0 \$ C.C-16.0] BOTH Corners PENTHONE = 1.2 (25) (423.09) + 1.6 (26) (423.09) = 40.4 K 33 K 4TH FLOOR: 1.2 (45)(423.09) +0.5 (26)(423.09) + 1.2 (65)(423.09) +1.6 (0.4)(100)(1)(423.09), = 88.42 k 77.08K 3ª FLOOR: 28.34 K + 2 33 K] + 2 [27.08 K] = 148.5 K 2ND FLOOR: 28.34K + 3 [33K] + 3 [27.08K] = 208.58K 15 FLOR: 28.34 + 4 [33 + 7 + 4 [27.08 +] = 268.66 K GRAND - 28.34 + 5 [33 k] + 5 [27.08 k] = 328.74 k FROM TABLE 4-1 AISC 40.4K PENTHERE Size @ 88.42 K WIZ ×40 88.42k LITH FLOOR SPUCE W12×40 3° FLOOR 148.5K SEE@ 208.53k 2ND FLOOR 208.53 K W12×50 SPLICE -15T FLOOR 2603.660 K SIZE @ 328.74K GRAND 328.74 K COLUMN SELF WEIGHT: WIZX40 (x2) W12×50 (×1) [40(2)+50] × 14.67' = 1907.116s -= 19.07 k LOAD @ Cauros A-5.0, A-A-16.0, D-5.0, D.D-16.0 316.67 + 19.07 = 335.74 k LOAD @ COLIMNS B-5.0, B.B-16.0, C-5.0, C-C-16.0 328,74+ 19.07 = 347.81 k BASE PLATE SIZE : ZXZOXI'-3" (SIM TO WIZX53 4 (1" \$)) ON SHEET 5-400 ANCHOR RODS 3



Copyright @ American Institute of Steel Construction, Inc. Reprinted with permission. All rights reserved.



	BRIAN NAHAS ANAWSIS #3 5	v
	FOOTING DESIGN & DETTAIL:	
	6 CASE 1: TYPICAL @ A-5.0, D-5.0, D.D-16.0	
	Lo Case la : Typical @ A.A-16.0	
	Lacase 2.3 Typical @ B-5.0, B.B-16.0, C-5.0, C.C-16.0	
dx	CASE 1: P= 335.74 k 2 INDIANCES @ 10.005" FROM CENTER 20 IN × 20 IN BASE PLATE FACH SQUARE - CONCRETE FOOTING 4000 PSI 28-DAY STRENGTH BEARING CAPACITY OF 4000 PSF (30" FRONT) CONCRETE	
TIME .	CASE 14: P= 335.74 C @ 10.095" Q XZ. 2Din X ZOIN BASE RATE EACH COMBINED 43" X43" CONC. PER @ 12'-3" HEIGHT SQUARE - CONCERTE FOTING 4000 PSI 28 DAY STRENGTH BEARING CAPACITY OF 4000 PSF (30" FROT)	
	CASE Z: P= 347.81 & @ 10.095" Q * Z 2011 * 20.11 BASE RATE FACH SQUARE CINCRETE FOOTING LUDD PSI 23 DAY STRENATH BEARING CAPACITY OF 4000 PSF (30" FROST)	
	NoTE: As THE TWO COLIMINS WILL LOAD WITH EQUAL LOADS, THE RESULTION OF THE APPLIED LOADS WILL COINCIDE WITH THE CENTROID OF THE FOOTING. HOWEVER, AS THE TWO COLIMINS ARE SO CLOSE, THEIR INDUMENTER FOOTINGS WOULD OVERLAP, REQUENCE A SHARED FOOTING [# PIRE AS REQUIRED].	
	CASE 13 CALCUATION 1.	
	$P= 2\times (335.74) = 671.48 \times Location of Resultant @ 5.0475" (or at Q of Fouring)$ $q_{A} \gg \frac{P}{A} \longrightarrow 4 \text{ ksf } \gg \frac{671.48}{B^2}$	
	B > 12.95' USE 13' × 13' FOOTING	
	$P_{D} = \left[9.4^{k} + 58.47^{k} + 4 \left[44.7 \right]^{k} + 19.07^{k} \right] \times 2 = 531.48^{k}$ $P_{L} = \left[5 \left[14^{k} \right] \right] \times 2 = 140^{k}$	

BRIAN NAMES

$$P_{n} = 1:2 P_{0} + 1:6 P_{1}$$

 $P_{u} = 1:2 [531.48^{2}] + 1:6 [140^{4}] = 861.776^{4}$
 $q = \frac{P_{u}}{A}$
 $q = \frac{P_{u}}{A}$
 $q = \frac{P_{u}}{(3^{2})^{2}}$
 5.099 MSF
 $U_{c} = 0.475 (L) (39 PS1 = 35.13 PS1 + RSF)$
 $V_{c} = 0.75 (L) (1400 Se1 + RSF)$
 $U_{c} = 0.75 (L) (1400 Se1 + RSF)$
 $U_{c} = 0.75 (L) (1400 Se1 + RSF)$
 $U_{c} = 189.744 PS1$
 $d^{2}(41V_{c} + q) + d(2V_{c} + q)(b+c) = q(B^{2} - bc)$
 $d^{2}(41(90) + 35) + d(2(90) + 25)(20^{4} + 20^{4}) = 35[(156)^{2} - (20^{4})(20^{4})]$
 $d^{2}(795) + d(16,600) = 837.760$
 $d = 23.77^{*}$
 $h = d + 3^{*} + d_{b}$
 $h = 27.325^{**}$
 $U_{SE} h = 30^{**}$
 $d_{1} = 30^{**} - 3^{**} - 0.5 (0.625^{**}) = 266.68^{**}$
 $d_{5} = 30^{**} - 3^{**} - 1.5 (0.625^{**}) = 760.06^{**}$

6

$$V_{uL} = 5.099 \text{ ksf} \left[\frac{13' - 167'}{Z} - 2.22' \right] = 17.57 \text{ k}$$

$$V_{u_s} = 5.099 \text{ ksf} \left[\frac{13' - 1.67'}{Z} - 2.17' \right] = 17.32 \text{ k}$$

$$\phi V_n = \phi 2.\sqrt{F_c} \text{ bd}$$

$$\phi V_n = 0.75(2)\sqrt{4000} (20'') (26.0c'')$$

$$\phi V_n = 49.445 \text{ lbs}$$

$$\phi V_n = 49.44 \text{ m} \text{ lps}$$

"Overwick

Beau Names
Long Directions

$$l = \frac{1}{2} \left[13^{2} - \left(\frac{20^{4}}{2} + \frac{158}{2}\right) \left(\frac{11^{2}}{12^{4}}\right) \right] = 5.80^{2}$$

 $M_{u} = \frac{1}{2} \left[\frac{1}{2} - \frac{1}{2} + \frac{158}{2} \right] \left(\frac{11^{2}}{12^{4}}\right) \right] = 5.80^{2}$
 $M_{u} = \frac{1}{2} \left[\frac{1}{2} - \frac{1}{2} + \frac{2$

BEAN NAMAS
MARYSIS ANALYSIS #3
SHORE DIRECTION

$$I = (13' - 6'')(12') = 6.25'$$

 $M_{11} = 5.099 ks (6.25)^{2} = 99.59' k$
 $a = A_{5}(60 ks) = a = 0.33 A_{5}$
 $0.35(4)(23)$
 $M_{12} = \phi M_{13} = \phi A_{5} f_{12} (d - \frac{\alpha}{2})$
 $Q_{1}59' k (12''A_{13}) = 0.9 A_{5} (60) (26.06'' - \frac{0.38A_{5}}{2})$
 $22.13 = 26.36 A_{5} - .444A_{5}$
 $A_{5} = 0.86 in^{2}$
 $U_{5E} # 7 @ Gin 0.C. A_{5} = 1.2$
 $P = 0k$
 $E_{5} = 0k$
SPROING is or K BY INSPECTION
 $- = U_{5E} (2C) # 7 BARS EACH WAY$
 $B = \frac{13'}{13'} = 1 - 1 (26 BARS) = 26 BARS.$

SPACING OK BY INSPECTION

$$PBn = 0.65(.35)(4 \text{ ksi})(400 \text{ in}^2)(2)$$

= 1763 k

\$Bn = 1768 K 7, 861.776 K

Science NAMES
Average #3
9

COSE 1A.

P= 2 × (335.74) = C71.43 K

P= 551.48 F

P= 557

USE 13' ×13' FOOTING

P= 12 P_{A} + 16 P_{A}

P= 12 F_{A} + 16 P_{A}

P= 5.099 KSF + 35.13 PS1

V_{C} = 139.74 PS1

Z-UMY SHEAR STRESS CONTREAS BY INSPECTION

d²(Ro +
$$\frac{P}{4}$$
) + d(V_{C} + $\frac{P}{2}$) $\omega = \frac{P}{4}(BC - \omega^{2})$

d²(Ro + $\frac{P}{24}$) + d(V_{C} + $\frac{P}{2}$) $(43^{-1})^{2} = \frac{35.13}{4}(56^{+1})^{2} - (43^{-1})^{2})$

INS.78 d² + 9963.12 d = P3.496.09

d = 14.95"

h= 14.95" + 3" + 625"

h= 18.575"

USE h = 24"

d = 24" - 3' - .625" = 20.375"

[= $\frac{12-4}{2} = 4.5'$

Mu = 'g(t' = $5.099(4.5)^{2} = 51.63'K^{-1}$

 $a = \frac{A_{5}F_{1}}{2} = \frac{A_{5}(\omega)}{2} = 0.735 A_{5}$

.55(Lo3(12) = .9A_{5}(\omega))(20.375" - $\frac{735A_{5}}{2}$)

"anamy

E

Beinn Name
 Anarys #3
 10

$$11.477 = 20.375 A_5 + .3675 A_5^{\pm}$$
 $A_5 = 0.57 in^{\pm}$
 $A_5 = 0.57 in^{\pm}$
 $Vsx \# 5 @ Gin a.c. A_5 = 0.62 in^{\pm}$
 $P = \frac{A}{bh} = \frac{0.02}{C^{10}(2h)} = .0018 \times$
 $Vsx \# 5 @ Gin a.c. A_{52} = 0.38 in^{\pm}$
 $Vsx \# 5 @ Gin a.c. A_{52} = 0.38 in^{\pm}$
 $P = \frac{A}{bh} = \frac{0.02}{C^{10}(2h)} = .0.0015 < 0.0018 \times$
 $Vsx \# 7 @ Gin a.c. A_{52} = 0.388 in^{\pm}$
 $Vsx \# 7 @ Gin a.c. A_{52} = 0.388 in^{\pm}$
 $P = \frac{1.32}{(2h)(2h)} = 0.0015 < 0.0018 \times$
 $Vsx \# 7 @ Gin a.c. A_{52} = 0.3018 \times$
 $Usx \# 7 @ Gin a.c. A_{52} = 1.20 in^{\pm}$
 $P = \frac{1.2}{(2h)(2h)} = 0.00228 \times 0.0018 \times$
 $Usx \# 7 @ Gin a.c. A_{52} = 0.0018 \times$
 $Usx \# 7 @ Gin a.c. A_{52} = 0.327 & 0.0018 \times$
 $Usx \# 7 @ Gin a.c. A_{52} = 0.0015 < 0.0018 \times$
 $a = 0.7355 A_5 + 0.735 (12) + 0.382^{*}$
 $a = 0.7355 A_5 + 0.735 (12) + 0.382^{*}$
 $c = \frac{a}{0.85} = \frac{.387}{.855} = 1.037^{*}$
 $E_5 = \frac{0.005}{.025} (20.375 - (0.37)) = 0.0559 \times 0.0055 iN_{10}$
 $v.b = .7$
 SPACING IS ac Bu INSPECTION
 $Vsx = (2b) \# 7$ BARS EACH UMAN.

 $\phi Bn = 4.35 f'_{2}A_{1}$
 $v.b = .5092 k \Rightarrow 8Gi .74k k = P_{10}$
 $A_{5min} = 0.005 (va)^{2}$
 $A_{5min} = 0.005 (va)^{2}$
 $A_{5min} = 0.005 (va)^{2}$
 $A_{5} = 12 in^{2}$
 $A_{5min} = 11.52''$
 $Vsx = 12 in^{2}$

$$Pere Names Anorea +3$$

$$P = 2 \times (3u \pm 3u \pm 3) = 695.62^{\pm} \\ Learnow or Research & Q & g & Forming \\ Q_{+} \ge \frac{P}{A} + 4hsr \ge \frac{695.62}{B^{\pm}} \\ B \ge 15.13^{2} \\ Use 13.5^{2} \times 13.5^{2} \\ Fund = \frac{1}{2} \\ S \ge 15.13^{2} \\ Use 13.5^{2} \times 13.5^{2} \\ Fund = \frac{1}{2} \\ S \ge 15.13^{2} \\ R_{+} = \frac{1}{2} \\ [5(2x,0x^{\pm})] \times 2 \\ R_{+} = \frac{1}{2} \\ [5(2x,0x^{\pm})] \times 2 \\ R_{+} = \frac{1}{2} \\ R_{+} = \frac{1}{2} \\ (2x,0x^{\pm})] \times 1 \\ R_{+} = \frac{1}{2} \\ R_{+} = \frac{1}$$

BRING MARK
 Analysis #3
 12

$$M_{n} = \Phi M_{n} = \Phi M_{n} \{ (M - \frac{\pi}{2}) \}$$
 $M_{n} = 5, 17 ((M - \frac{\pi}{2}))$
 $M_{n} = 5, 17 ((M - \frac{\pi}{2}))$
 $M_{n} = 5, 17 (M - \frac{\pi}{2})$
 $109, 21 (M - \frac{\pi}{2})$
 $109, 21 (M - \frac{\pi}{2})$
 $M_{n} = 5, 17 (M - \frac{\pi}{2})$
 $210, 21 (M - \frac{\pi}{2})$
 $M_{n} = 5, 17 (M - \frac{\pi}{2})$
 $M_{n} = 5, 17 (M - \frac{\pi}{2})$
 $M_{n} = 5, 17 (M - \frac{\pi}{2})$
 $M_{n} = 5, 17 (M - \frac{\pi}{2})$
 $M_{n} = 1, 176, 3 K > 86(1,776 K)$
 $M = 1, 176, 3 K > 86(1,776 K)$
 $M = 1, 176, 3 K > 86(1,776 K)$
 $M_{n} = 1, 176, 3 K > 86(1,776 K)$
 $M = 1, 176, 3 K > 86(1,776 K)$
 $M = 1, 176, 3 K > 86(1,776 K)$
 $M_{n} = 1, 176, 3 K > 1, 176, 3 K > 86(1,776 K)$
 $M = 1, 176, 3 K > 86(1,776 K)$
 $M = 1, 176, 3 K > 1, 156 K >$

AMPA

An



APPENDIX M | EXPANSION JOINT QTO & ESTIMATE

Crewed Level Center A.Q. D										
Ground Level Sector A & B 251 Number System	Total Units	Material	Lab	oor Equi	ipment To	otal Mate	erial Cost Labor	r Cost Equip	ment Cost Tota	al Cost
03 31 Structural Concrete										
Floor: 4" NW Concrete 4840 SOG (3500psi), no reinforcing		.64 CY	2.59	0.88	0.01	3.48 \$	17.20 \$	5.84 \$	0.07 \$	23.11
200 3500 psi		сү	99.5	0	0	99.5 \$	660.68 \$	- \$	- \$	660.68
03 22 05.50 Welded Wire Fabric- ASTM A185 W6x6-W1.4xW1.4 WWF		4.1								
200 W6x6-W2.1xW2.1 WWF		-SF	18.9	25	0	43.9 \$	77.49 \$	102.50 \$	- \$	179.99
rirst Level Sector A & B SI Number System	Total Units	Material	Lab	or Equi	ipment To	otal Mate	erial Cost Labor	Cost Equin	ment Cost Tota	al Cost
	Total Onits	Wateria	Lau		ipment to	iviate		Cost Equip	nent cost 100	arcost
05 12 23.17 Columns, Structural W14x48: 4	2	224								
3702 W18x50 W14x43: 2		LF 104	62	4.2	1.9	68.1 \$	13,888.00 \$	940.80 \$	425.60 \$	15,254.40
3102 W16x40		LF	49.5	3.32	2.03	54.85 \$	5,148.00 \$	345.28 \$	211.12 \$	5,704.40
05 31 13.50 Floor Decking 3" 18 Gage Lok-Floor Composite Deck	396	6.5								
5900 Non-cellular composite decking, galvanized, 3" deep, 18 gauge		SF	2	0.55	0.04	2.59 \$	793.00 \$	218.08 \$	15.86 \$	1,026.94
03 31 Structural Concrete Floor: 3 1/4" LW Concrete	,	5.8								
1400 Elevated Slabs, less than 6" thick, pumped 200 3500 psi		СҮ	0 99.5	16.8 0	5.6	22.4 \$ 99.5 \$	- \$ 577.10 \$	97.44 \$ - \$	32.48 \$	129.92 577.10
03 22 05.50 Welded Wire Fabric- ASTM A185			55.5	Ū	Ū	55.5 \$	577120 0	<u>,</u>	÷	577120
W6x6-W2.0xW2.0 WWF 200 W6x6-W2.1xW2.1 WWF		4.1 -SF	18.9	25	0	43.9 \$	77.49 \$	102.50 \$	- \$	179.99
05 12 23.40 Lightweight Framing										
ž3x3x5/16 476 Angle 3"x3"x3/8"		824 LF	4.86	20.5	1.91	27.27 \$	6,642.00 \$	618.84 \$	618.84 \$	8,835.48
second Level Sector A & B										
CSI Number System	Total Units	Material	Lab	or Equi	ipment To	otal Mate	erial Cost Labor	r Cost Equip	ment Cost Tota	al Cost
05 12 23.17 Columns, Structural										
W14x48: 4 3702 W18x50		224 LF	62	4.2	1.9	68.1 Š	12 888 00 4	940.80 \$	425.60 \$	15,254.40
W14x43: 2	1	104					13,888.00 \$	· ·		
3102 W16x40 05 31 13.50 Floor Decking		LF	49.5	3.32	2.03	54.85 \$	5,148.00 \$	345.28 \$	211.12 \$	5,704.40
3" 18 Gage Lok-Floor Composite Deck	396									
5900 Non-cellular composite decking, galvanized, 3" deep, 18 gauge 03 31 Structural Concrete		SF	2	0.55	0.04	2.59 \$	793.00 \$	218.08 \$	15.86 \$	1,026.94
Floor: 3 1/4" LW Concrete		5.8				22.4.4			32.48 \$	129.92
1400 Elevated Slabs, less than 6" thick, pumped 200 3500 psi		CY CY	0 99.5	16.8 0	5.6 0	22.4 \$ 99.5 \$	- \$ 577.10 \$	97.44 \$ - \$	- \$	577.10
03 22 05.50 Welded Wire Fabric- ASTM A185 W6x6-W2.0xW2.0 WWF		4.1								
200 W6x6-W2.1xW2.1 WWF		-SF	18.9	25	0	43.9 \$	77.49 \$	102.50 \$	- \$	179.99
05 12 23.40 Lightweight Framing ž3x3x5/16	3	324								
476 Angle 3"x3"x3/8"		LF	4.86	20.5	1.91	27.27 \$	6,642.00 \$	618.84 \$	618.84 \$	8,835.48
Third Level Sector A & B										
CSI Number System	Total Units	Material	Lab	oor Equi	ipment To	otal Mate	erial Cost Labor	r Cost Equip	ment Cost Tota	al Cost
05 12 23.17 Columns, Structural										
W14x48: 4 3702 W18x50		224 LF	62	4.2	1.9	68.1 \$	13,888.00 \$	940.80 \$	425.60 \$	15,254.40
W14x43: 2 3102 W16x40		L04	49.5	3.32	2.03	54.85 Ś	5,148.00 \$	345.28 \$	211.12 \$	5,704.40
05 31 13.50 Floor Decking			43.5	3.32	2.03	J4.0J Ş	3,148.00 3	343.20 3	211.12 3	3,704.40
3" 18 Gage Lok-Floor Composite Deck 5900 Non-cellular composite decking, galvanized, 3" deep, 18 gauge	396	6.5 SF	2	0.55	0.04	2.59 \$	793.00 \$	218.08 \$	15.86 \$	1,026.94
03 31 Structural Concrete Floor: 3 1/4" LW Concrete		5.8								
1400 Elevated Slabs, less than 6" thick, pumped		СҮ	0	16.8	5.6	22.4 \$	- \$	97.44 \$	32.48 \$	129.92
200 3500 psi 03 22 05.50 Welded Wire Fabric- ASTM A185		СҮ	99.5	0	0	99.5 \$	577.10 \$	- \$	- \$	577.10
W6x6-W2.0xW2.0 WWF		4.1								
200 W6x6-W2.1xW2.1 WWF 05 12 23.40 Lightweight Framing	C-	-SF	18.9	25	0	43.9 \$	77.49 \$	102.50 \$	- \$	179.99
ž3x3x5/16 476 Angle 3"x3"x3/8"		824 LF		20.5		A	6,642.00 \$	618.84 \$	618.84 \$	8,835.48
		LF	4.86	20.5	1.91	27.27 \$	6,642.00 \$	618.84 \$	618.84 \$	8,835.48
Fourth Level Sector A & B	Total Units	Material	Lab	or Equi	ipment To	otal Mate	erial Cost Labor	Cost Equip	ment Cost Tota	al Cost
				-40	10	mate	2000	Equip	100	
05 12 23.17 Columns, Structural W14x48: 4	2	224								
3702 W18x50		LF	62	4.2	1.9	68.1 \$	13,888.00 \$	940.80 \$	425.60 \$	15,254.40
W14x43: 2 3102 W16x40		L04 LF	49.5	3.32	2.03	54.85 \$	5,148.00 \$	345.28 \$	211.12 \$	5,704.40
05 31 13.50 Floor Decking 3" 18 Gage Lok-Floor Composite Deck	396	6.5								
5900 Non-cellular composite decking, galvanized, 3" deep, 18 gauge		SF	2	0.55	0.04	2.59 \$	793.00 \$	218.08 \$	15.86 \$	1,026.94
03 31 Structural Concrete Floor: 3 1/4" LW Concrete		5.8								
1400 Elevated Slabs, less than 6" thick, pumped		CY	0	16.8	5.6	22.4 \$	- \$	97.44 \$	32.48 \$	129.92
200 3500 psi 03 22 05.50 Welded Wire Fabric- ASTM A185		CY	99.5	0	0	99.5 \$	577.10 \$	- \$	- \$	577.10
W6x6-W2.0xW2.0 200 W6x6-W2.1xW2.1 WWF		4.1 -SF	18.9	25	0	43.9 \$	77.49 \$	102.50 \$	- \$	179.99
05 12 23.40 Lightweight Framing			10.9	25	U		//.43 Ş	102.30 \$	- >	179.99
ž3x3x5/16 476 Angle 3"x3"x3/8"		124 LF	4.86	20.5	1.91	27.27 \$	6,642.00 \$	618.84 \$	618.84 S	8,835.48
Penthouse Level Sector A & B 251 Number System	Total Units	Material	Lab	or Equi	ipment To	otal Mate	erial Cost Labor	r Cost Equip	ment Cost Tota	al Cost
05 12 23.17 Columns, Structural										
		328								
W14x43: 6		LF	49.5	3.32	2.03	54.85 \$	16,236.00 \$	1,088.96 \$	665.84 \$	17,990.80
W14x43: 6 3102 W16x40										
W14x43: 6 3102 W16x40 05 31 13.50 Floor Decking 3° 18 Gage Lok-Floor Composite Deck	239.	.25		0.57			•		*	
W14x3:6 3102 W16x40 OS 31 13:50 Floor Decking 3* 18 Gage tok-Roor Composite Deck 5900 Non-cellular composite decking, galvanized, 3* deep, 18 gauge 1 1/2* 22 Gage Type 1% Metal Roof Deck	239. 214.	.25 SF .65	2	0.55	0.04	2.59 \$	478.50 \$	131.59 \$	9.57 \$	619.66
W14x43: 6 3102 W15x40 05 31 13.50 Floor Decking 3* 18 Gage Lok-Floor Composite Deck 5900 Non-cellular composite decking, galvanized, 3* deep, 18 gauge 11/2* 22 Gage Type ¹⁵ Metal Roof Deck 2400 Open Type, 1-1/2* deep, Type B, 22 Ga.	239. 214.	. 25 SF	2	0.55	0.04	2.59 \$ 1.35 \$	478.50 \$ 218.94 \$	131.59 \$ 66.54 \$	9.57 \$ 4.29 \$	619.66 289.78
W14x83 - 6 3102 W16x80 05 31 13.50 Floor Decking 3* 18 Gage Lok-Roor Composite Deck 5900 Non-cellular composite decking, galvanized, 3* deep, 18 gauge 11/2* 22 Gage Type 'B' Metal Roof Deck 2400 Open Type, 1-1/2* deep, Type B, 22 Ga. 03 31 Structural Concrete Floor: 3 1/4* UW Concrete	239. 214. 2.	.25 SF .65 SF .32	1.02	0.31	0.02	1.35 \$	218.94 \$	66.54 \$	4.29 \$	289.78
W1443: 6 3102 W1640 05 31 13:50 Floor Decking 3" 18 Gage lok-floor Composite Deck 5990 Non-cellular composite decking, galvanized, 3" deep, 18 gauge 1 1/2" 22 Gage Type 'B' Metal Roof Deck 2400 Open Type, 1:12" deep, Type B, 22 Ga. 0 33 I Structural Concrete	239. 214. 2.	.25 SF .65 SF								

	" NW Concrete		3.48												
	d Slabs, less than 6" thick, pumped		CY	0	16.		5.6	22.4 \$		-		58.46		19.49	
200 3500 ps			CY	99.5)	0	99.5 \$		346.26	ş	-	ş	-	\$ 34
	d Wire Fabric- ASTM A185														
	V2.0xW2.0 WWF		1.64												
	/2.1xW2.1 WWF		C-SF	18.9	2	5	0	43.9 \$		31.00	\$	41.00	\$	-	\$ 7
	V2.9xW2.9 WWF		2.46												
	/2.9xW2.9 WWF		C-SF	21.5	26.	5	0	48 \$		52.89	\$	65.19	\$	-	\$ 11
05 12 23.40 Lightw															
ž3x3x5/			324												
476 Angle 3	'x3"x3/8"		LF	4.86	20.	5	1.91	27.27 \$		6,642.00	\$	618.84	\$	618.84	\$ 8,83
Column Systems															
CSI Number System	n	Total Units	Materi	al La	abor	Equipment	т	otal I	Material Cost		Labor Cost		Equipment Cost		Total Cost
05 12 23.17 Colum	ns. Structural														
W12x50		2	296.00												
902 W10x49			LF	60.5	4.8	2	2.95	68.27 \$		17,908.00	s	1,426.72	s	873.20	\$ 20,20
W12x40			856							,					
2302 W14x34			LF	42	3.2	,	2	47.27 \$		35,952.00	\$	2,799.12	\$	1,712.00	\$ 40,46
Foundation Systems															
		Total Units	Materi		abor		-		Material Cost				F		Total Cost
CSI Number System	n	Iotal Units	Iviateri	ai La	ibor	Equipment		otal I	viaterial Cost		Labor Cost		Equipment Cost		Total Cost
03 03 53.40 Concre	ete in Place														
	2'-6" Thick Concrete	1	130.09												
	Footings (4000psi) over 5 CY		CY	190	61.	;	0.31	251.81		24.717.10	s	8.000.54	\$	40.33	\$ 32,75
03 21 05 Reinfo										,	•	-,	•		,
	rcing Bars		416												
120 #7 Bars			Bars	7.45	9.3	1	0	16.75 \$		3,099.20	¢	3.868.80	¢	-	\$ 6.96
	rcing Bars		12	7.45	5.	•	•	10.75 ,		3,033.20	Ŷ	3,000.00	Ŷ		ç 0,50
305 #9 Bars			Bars	14.1	2		7.15	46.25 \$		169.20	\$	300.00	\$	85.80	\$ 55
303 %3 5013			5015	1411		•	7.125	40.25 ,	•	105.20	Ý	500.00	¥.	05.00	÷ 55.
Foundation Systems															
CSI Number System	n	Total Units	Materi	al La	abor	Equipment	т	otal I	Material Cost		Labor Cost		Equipment Cost		Total Cost
07 95 13 Expan	sion Joint Cover Assemblies														
	late Cover Track		648												
	EJ-TMM-200W		LF	21.5	9.0	5	0	30.55		13.932.00	s	5.864.40	\$	-	\$ 19.79
	ate Cover Track		480		5.0.		•	50.55 4		10,002.00		2,004.40			- 15,75
	n EJ-TMM-200w-W		LF	18.1	9.0		0	27.15		8.688.00	s	4.344.00	\$	-	\$ 13,03
	ate Cover Track		162	1011	5.0.		•			5,000.00		.,			- 15,05
	n EJ-RJ-200		LF	40	6.0		0	46.05 \$		6.480.00	s	980.10	\$	-	\$ 7,46
14950.001					5.0.	•		-0.05 \$		5,400.00	•	500.10			, ,,,,,
Expansion Join	t System Total Cost										Ś				297.569.9
-xpuilision join	cost cost										Ŷ				237,303.3




APPENDIX N | NYSTROM EXPANSION JOINT PRODUCT GUIDE


Expansion Joint Systems



Complementary Building Products
















Right to site.

Right to site.


Interior Floor Joints Expansion Joint Systems

Double Seam

TMM



TMMw





- No visible hardware for extra aesthetic appeal
- Flat seal design
- No block-outs required
- Accepts most finished flooring
- Suggested for vertical gyp. board applications



Standard Colors

Black (-B)	Gray (-G)	White (-W)	Beige (-E)
Add the I	wohen and cold	or code at the en	d of the

Add the hyphen and color code at the end of the model number to specify color. Ex: EJ-TMF-300-G


Floor to Floor			Syst Widt		Total Movement		
Model #	in	mm	in	mm	in	mm	
EJ-TMM-200	2.0	51	7.75	197	4.25	108	
EJ-TMM-400	4.0	102	9.75	248	6.25	159	
EJ-TMM-600	6.0	152	11.75	298	8.25	210	


Floor to Wall	Joint Opening (A)		Syst Widt		Total Movement		
Model #	in	mm	in	mm	in	mm	
EJ-TMM-200w	2.0	51	4.88	124	2.5	64	
EJ-TMM-400w	4.0	102	6.88	175	4.5	114	
EJ-TMM-600w	6.0	152	8.88	225	6.5	165	

Right to site.

Exterior Roof Joints Expansion Joint Systems

Roof Cover





- Flat or sloped roofs
- Engineered for snow and ice loads
- Puncture proof



Roof to Roof	Joint Opening (A)		Sys Widt		Total Movement		
Model #	in	mm	in	mm	in	mm	
EJ-RJS-200	2.0	51	8.0	203	3.0	76	
EJ-RJS-400	4.0	102	11.0	279	6.0	152	
EJ-RJS-600	6.0	152	14.0	356	9.0	229	
EJ-RJS-800	8.0	203	17.0	432	12.0	305	
EJ-RJS-1000	10.0	254	20.0	508	15.0	381	
EJ-RJS-1200	12.0	305	23.0	584	18.0	457	
EJ-RJS-1800	18.0	457	32.0	813	27.0	686	
EJ-RJS-2400	24.0	610	41.0	1041	36.0	914	

Roof to Corner	Joint Opening (A)		Syst Widt		Total Movement		
Model #	in	mm	in	mm	in	mm	
EJ-RJS-200w	2.0	51	5.5	140	3.00	76	
EJ-RJS-400w	4.0	102	8.5	216	6.00	152	
EJ-RJS-600w	6.0	152	11.5	292	9.00	229	
EJ-RJS-800w	8.0	203	14.5	368	12.00	305	
EJ-RJS-1000w	10.0	254	17.5	445	9.75	248	
EJ-RJS-1200w	12.0	305	20.5	521	11.75	298	
EJ-RJS-1800w	18.0	457	29.5	749	17.75	451	
EJ-RJS-2400w	24.0	610	38.5	978	23.75	603	

For the latest CAD, BIM, Spec, LEED, and general product information, please visit NYSTROM.com