

Table of Contents

Executive Summary	2
Introduction	3
Structural Overview	6
Foundation	6
Floor System	7
Lateral System	9
Design Codes and Standards	
Materials	11
Loads	12
Dead Loads	12
Live Loads	13
Existing Floor System	14
Two-Way Flat Slab with Drop Panels	16
One-Way Concrete Slab and Beam System	
Hollow Core Precast Planks with Steel Framing	20
Floor System Summary	23
Conclusion	24
Appendix A: Existing System Hand Calculations	25
Appendix B: Flat Slab with Drop Panels	35
Appendix C: One-way Slab with Beam	46
Appendix D: Hollow Core Precast Plank on Steel Framing	54

Executive Summary

In the following report, an analysis was performed of three alternate floor systems for the Patient Pavilion. Hand calculations supplemented with computer-aided calculations to determine schematic sizes for each system. Each system was then compared with each other, as well as the existing system, based on the weight, deflections, depth, cost, constructability, and architectural impacts. The existing floor system is composite steel framing with composite steel deck, the alternate systems designed in this report include:

- Two-Way Flat Slab with Drop Panels
- One-Way Concrete Slab with Concrete Beams
- Hollow Core Precast Plank on Steel Framing

The design of the two-way flat slab resulted in a 10" slab with 11'x11'x12.5" drop panels, reinforced with No. 7 bars, the location and span direction dictates the amount of bars used. The advantages of this system include minimal formwork, and no fireproofing needed. Some disadvantages of this system include the difficulty of construction, large deflections, and the need for shear walls for lateral load resistance. The two-way slab system with drop panels is a viable solution to the Patient Pavilion, however with the large deflections and mass of the system it is not the best solution.

The one-way system comprises of a 5" slab spanning 10', framed by a 30' girder spanning column to column with two infill beams at 10' on center. This system is slightly over designed due to trying to increase the constructability and reducing the amount of formwork. The depth of the girder was designed first because it controlled the depth of the beam in order to create redundant formwork. In addition, the girder is 30" wide to be flush with the 30"x30" column further reducing the cost of formwork and the difficulty of constructability. Advantages of this system include low cost of formwork due to redundancy, good constructability, and a good damping response to floor vibrations. Some negative aspects of this system include high over price, increase of floor weight, and larger seismic loads due to the increase in floor weight. The one-way slab with beams system is a viable solution to the Patient Pavilion; however, it is not the most optimal option.

The final system is a hollow core precast plank with steel framing, the Nitterhouse catalog was used to pick a plank size and an 8" plank reinforced with (6) 1/2" Ø 270k tendons with a 2 hour fire rating was chosen. Due to the large span and tributary width of the girders, a W18x175 was designed to be the most optimal. However, if the plank were to sit on top of the girder the total depth of the floor system would be approximately 30". To reduce the height a special connection has been designed to box the W-shape and have the plank sit on an angle the is welded to the face of this boxed in W-shape. The advantages of this system include minimal formwork and fireproofing included however, these are obsolete compared to the disadvantages of this system. The disadvantages include large deflections, difficult construction, special in-shop connections, deep girders, and difficult to renovate due to the prestressed tendons. The hollow core precast plank system was determined to not be a viable solution for the Patient Pavilion.

<u>Introduction</u>


The Patient Pavilion is located in Albany, NY, at the intersection of New Scotland Avenue and Myrtle Avenue, on the eastern end of the existing Albany Medical Center Hospital (AMCH) campus. Constructed as an expansion to the AMCH, the Patient Pavilion utilizes pedestrian bridges to tie into an existing parking structure across New Scotland Avenue, as well as tying into an existing building on the AMCH campus as shown in Figure 1.

The Patient Pavilion will retain the architectural style, forms, and materials of downtown Albany and the AMCH campus, as specified in the City of Albany Zoning Ordinance. The façade primarily consists of brick and stone with punched windows and white stone accenting the upper levels. To add emphasis to the pedestrian walkway over New Scotland Avenue, metal paneling and glazed aluminum curtain-walls added an integrated modern look to the traditional façade.

The Patient Pavilion consists of two phases; Phase 1, contains the demolition of an existing building on the AMCH campus, and the construction of a six story medical

center see Figure 2 and Phase 2 is a future four story vertical expansion of the Patient Pavilion see Figure 3. The building height of Phase 1 is 75 feet above grade and the vertical expansion of Phase 2 will increase the building height to 145 feet above grade. Due to a small site and large square footage demands, the building cantilevers over the site on the side of New Scotland Avenue, demanding for the design of





This patient care facility, contributes 229 patient beds, 20 operating rooms, and 1000 new permanent jobs to the AMCH campus. The 348,000 square foot expansion consists of six stories above grade with a four story vertical expansion in the future. Phase 1 construction on the Patient Pavilion began in September of 2010 and projects to finish in June of 2013.

To better understand the terminology used for referring to designated levels, an architectural elevation is provided on the next page.



Figure 3 - Phase 2 of the Patient Pavilion; Vertical Expansion





Figure 5 – Site Plan

New Scotland Avenue Myrtle Avenue

Structural Overview

The majority of the Patient Pavilion rests on a 36" thick mat foundation, and some piles located near existing buildings. The floor system utilizes composite beams, girders, and slabs to carry the loads derived from ASCE07-02. The lateral forces are collected on the brick non-bearing façade, transfers into the slab and is distributed to the foundation/grade by the integration of braced and moment frames. On the southern end of the site, 62" deep plate girders are utilized to cantilever nine stories over the edge of the site. Multi-story trusses are utilized to carry multiple levels with a large clear span, these are located over the emergency access ramp and at the pedestrian bridge that ties into an existing AMCH building see *Figure 6*.



Foundation

Vernon Hoffman PE Soil and Foundation Engineering supplied the geotechnical report for the Patient Pavilion site. Procedures used were site boring, vane shear testing, pressure testing, and cone testing. Soil testing concluded that foundations must be designed to a net bearing pressure of 3000psf. Design ground water level was reported to be between 4' and 10' throughout the site. After a full analysis of the site, the


geotechnical report recommended the building to sit on a mat foundation resting on a controlled fill.

Because of the relatively low allowable soil bearing pressure, the majority of the Patient Pavilion sits on a 36" mat foundation resting on a 4" mud slab with a 12" compacted aggregate base. Alternatively, 20'-0" deep piles are utilized in order to prevent unwanted settlement of the existing buildings. Piles are utilized in place of shallow foundations because piles will control settlements and provide uplift resistance more effectively than shallow foundations.

Foundation walls are utilized along existing building C and along New Scotland Avenue to lessen the demand on the excavation shoring; these walls also serve the purpose of shear walls in the lateral system. Backfilling behind these walls was needed to provide construction access for equipment and materials to build the pile caps and grade beams.

Floor System

The Patient Pavilion utilizes 3"x20ga galvanized composite steel deck with 3 1/2" lightweight topping, reinforced with #4's at 16" O.C. for shrinkage and temperature, this floor system is typical throughout the levels, unless otherwise noted. On level 2, the floor slab is thickened with a 3" lightweight concrete topping in order to reduce floor vibrations in the operating rooms. The entry level utilizes an 8" lightweight concrete slab on 3 1/2"x16ga composite metal deck because of longer deck spans and larger live loads. In areas where radiation is prevalent, the slabs above and below that level are stiffened with a steel plate anchored to the slab with angles. These plates are located on levels 2 and 3 and their function is to provide a shield from the radiation for adjacent areas, refer to Figure 7 for radiation slab details.



Typical beam spacing throughout is 10'-0" O.C., creating a 10'-0" deck span requirement, all beams are composite beams, typically W12's. However, on the Basement Level and Level 2, typical beams range from W16's to W18's. Reasons for deeper beams are that the live load requirements on the Entry Level through Level 2 are greater than the other floors. However, the Basement Level and Level 2 utilize deeper beams

than the Entry Level and Level 1 due to greater floor-to-floor heights.

Typical beams span 27'-4", these beams sit on girders that typically span 30'-0". Girder sizes range from W14's to W18's; however, on the Basement Level and Level 2 girder sizes fluctuate from W18's to W24's, refer to Figure 8 for a typical bay on Level 3.

A demand for specialty framing is needed in certain areas in this project; on the southern end of the site, a column is cantilevered 18' over the edge of the site resting on a 62" plate girder. The pedestrian bridge on the tying into the existing AMCH building spans 83' over another existing AMCH building. A two-story truss was designed on bottom two levels of this pedestrian bridge, consisting of W10x77's and W10x100's.



Lateral System

The lateral system for the Patient Pavilion predominantly consists of braced frames, with some moment frames. Within the structure, there are 14 braced frames and 5 moment frames, because of the locations of the braced frames, Chevron bracing is utilized to allow openings for doorways and corridors. See *Figure 8* for a typical braced frame. Figure 7 shows the locations of the braced and moment frames, the location of some braced frames fluctuate from level to level. For instance, braced frame 13 is braced between the Basement Level through Level 2 and above Level 2 is a moment frame.

The braced frames along the western side of the site sit on retaining walls in the basement, which also act as concrete shear walls. A strong connection is required to transfer the shear load from the column into the concrete shear wall, for these connections a 30"x30"x3½" baseplate with a 2" diameter anchor bold anchored 42" into the wall is specified. Diagonal bracing on the lower levels range from W10's to W12's and HSS8x6's to HSS8x8's on the upper levels. Heavier bracing on the lower levels provides a greater resistance to shear, which increases as the force moves down the frame. Columns used in these lateral resisting frames range from W14x43 to W 14x233.




Figure 10 - Typical Braced Frame

Design Codes and Standards

Ryan-Biggs Associates abided by these standards and codes when developing the design of the Patient Pavilion:

- ♣ AISC 13th Edition Manual
- ♣ AISC Specification 360-05
- 2007 Building Code of New York State (BCNYS)
- Minimum Design Loads for Buildings and Other Structures (ASCE7-02)
- AISC Manual of Steel Construction, Load Resistance Factor Design (LRFD)

Standards and codes utilized for this report:

- ♣ AISC 14th Edition Manual
- AISC Specification 360-10
- ♣ 2006 International Building Code (IBC 2006)
- ♣ Minimum Design Loads for Buildings and Other Structures (ASCE7-05)
- 🖶 AISC Manual of Steel Construction, Load Resistance Factor Design (LRFD)

Materials

The structural materials designated by the AISC 13th Ed. were used in the design of the Patient Pavilion by Ryan-Biggs; see Table 1 for the capacities of the large variety of structural elements. The materials were specified on the General Notes page, S001, on the Construction Documents provided via Gilbane Building Company. All steel materials below are according to ASTM standards.

Table 1 – Material Properties

Materia	l Properties	
Material		Strength
Rolled Steel	Grade	f _y = ksi
W Shapes	A 992	50
C, S, M, MC, and HP Shapes	A 36	36
Plates, bars, and angles	A 36	36
HSS pipe	A53 type E or S Grade B	35
Reinforcing Steel	A 615	60
Concrete	Weight (lb/ft³)	f' _c = psi
Footings/mat foundation	145	3,000
Interior S.O.G or Slab on Deck	145	3,500
Foundation Walls, Shear walls, Piers, Pile caps, and Grade beams	145	4,000
Exterior S.O.G.	145	4,500
Masonry	Grade	f' _m = psi
Concrete Block	C 90	2,800
Mortar	C 270 Type S	n/a
Unit Masonry	n/a	2,000
Grout	C 476	2,500
Brick	C 216 type FBS Grade SW	3,000
Welding Electrodes	E70 XX	70 ksi

Loads

In the following tables, dead and live loads that were used to analyze and design the Patient Pavilion are listed as well as the loads used for this thesis. Live loads interpreted by the designer were derived from ASCE7-02, live loads used in this thesis were derived from ASCE 7-05; dead loads were assumed or calculated and verified with specified dead loads on the structural general notes.

Dead Loads

The dead loads listed on the general notes of the structural drawings are listed below in *Table 2*. Upon further analysis shown in *Table 3* and *Table 4*, the assumptions of these loads were verified to be accurate and conservative in some cases. The MEP is larger than typical because in a hospital the MEP weight is to be assumed larger than typical.

Table 2 - Superimposed Dead Loads

Dead Loads (As Shown on General Notes S100)					
Description	Weight (psf)				
Roof Without Conc. Slab	30				
Roof With Conc. Slab	95				
Roof Garden	325				
Floor	95				
Level 9 Mechanical Penthouse	125				

Table 3 - Roof without Conc. Slab Verification

Roof Without Conc. Slab Verification (ASCE7-05 and Vulcraft)					
Description	Weight (psf)				
MEP	12				
3"x16ga decking	5				
Rigid Insulation (tapered starting at 8")	.75psf per in thickness=(.75x8x.5)= 12				
Total	29				

Table 4 - Roof with Conc. Slab and Floor Verification

Roof With Conc. Slab and Floor	Roof With Conc. Slab and Floor Verification (ASCE7-05 and Vulcraft)					
Description	Weight (psf)					
MEP	12					
3"x20ga Composite Decking	48					
Steel Framing	13					
Finishes and Partitions	15					
Fireproofing	2					
Miscellaneous	5					
Total	95					

Live Loads

See Table 5 for the controlling live load description per each level with the exception of elevator lobbies and stairs. The live loads given on the structural general notes were obtained using ASCE7-02, they were rechecked according to ASCE7-05 and were deemed accurate, see Table 6.

Table 5 – Live Loads

Live Loads (As Shown	on General Notes S100)
Description	Weight (psf)
Entry	100
Basement	100
Level 1	100
Level 2	100
Level 3	80
Level 4	80
Level 5	80
Level 6	80
Level 7	80
Level 8	80
Level 9 (Mechanical Penthouse)	125
Elevator Lobbies and Stairs	100

Table 6 – Verifying Live Loads per ASCE7-05

Level 1 – Level 2; Verification (ASCE7-05)							
Occupancy	Weight (psf)						
Assembly Areas – Lobby	100						
Hospitals – OR Rooms	60 + Partitions						
Hospitals – Patient Rooms	40 + Partitions						
Hospitals – Corridors above 1 st Floor	80						

Existing Floor System

Spot checks were performed on a typical 27'x30' bay located on Level 3; columns J-1, J-2, K-1, and K-2 make up the corners for the bay see *Figure 11*. Spot checks were performed to utilize knowledge learned in previous courses to verify the structural system of the building. Complete hand calculations are located in Appendix A.




Figure 11 - Typical Bay

General

The existing composite system weighs 60 pounds per square foot (psf), and costs approximately \$17.76 per square foot, the second cheapest system. This system was chosen because within the area of Albany, New York steel is cheaper than concrete and most of the contractors are more familiar with steel construction. The cost of the system was derived using RS Means Costs Works.

Decking

Typical floor construction for the Patient Pavilion utilizes a 3"x20ga unshored composite steel deck with 3 1/2" lightweight concrete topping. Using Vulcraft Steel Decking (2008) catalog, the specified deck type is acceptable according to the allowable strengths and unshored lengths for a 3VLI20. The allowable superimposed live load is 157psf, roughly double the live load on Level 3; a possible reason for this is because the live load at the penthouse is 125psf, increasing the demand for strength in the deck. Verifying the fire rating with the 2001 Fire Resistance Directory, a 3 1/2" lightweight concrete topping allows for a 2-hour rating. After verifying the fire rating, the deck size was governed by the fire rating not strength.

Beam

Gravity spot checks were performed on a W12x30 beam highlighted in blue in *Figure 11*. This is the most typical beam used throughout, spanning 27'-0" with a tributary width of 10'-0". Hand calculations as well as Table 3-19 in the AISC were used to calculate strength and deflection for both pre-concrete curing and post concrete curing. The spot check analysis verified that the W12x30 with 14 studs was adequate for the given loading on Level 3.

Girder

The girder analyzed was a W16x89 with 36 studs, as shown highlighted in green in *Figure 11*. Spanning 30'-0" this girder is typical from Level 3 up. The girder was analyzed using a tributary width of 27'-0", the live load was reduced and the distributed load along the girder was transformed into two point loads. The girder was checked for flexural, shear, and unshored strength, as well as wet concrete deflection and live load deflection. After analyzing the girder, it was found that the strength of the girder was approximately 45% larger than the ultimate moment of the floor loads. The reason for a larger capacity could be because the live load in the elevator lobbies is 20psf greater than the rest of the floor, and the girder is typical throughout the building.

Architectural

The low floor-to-floor heights on Level 3 up, restrict the beams and girders from going deeper than 16", this requires heavy sections to resist the factored loads. A heavier topping had to be utilized to meet the fire-rating minimum of 2 hours; also, spray fireproofing had to be added to all structural members.

Structural

The composite system is the most practical for the long spans that are needed for the Patient Pavilion; the structural system should not change for this system.

Serviceability

Maximum deflections were calculated for wet concrete deflection and live load deflection. The deflections for this system are deemed adequate for serviceability with a total deflection of 0.89 inches. A deflection criterion is stringent in hospitals due to operating rooms and intensive care units.

Pros and Cons


Pros:

- Lightweight system
 - Less seismic base shear
 - Smaller foundations
- Low cost per square foot
- Very flexible to meet floor-to-floor height requirements
- Small deflection

Cons:

- Floor vibrations are average
 - Deeper slabs utilized in critical areas to reduce vibrations
- Additional spray fireproofing needed
 - Additional construction cost
 - Delays construction

Two-Way Flat Slab with Drop Panels






Figure 13 - Long Span

The design of the two-way reinforced flat slab systems is comprised of a $10^{\prime\prime}$ inch slab with 5000psi concrete and at the columns a $12\ 1/2^{\prime\prime}$ thick drop panel was utilized to prevent punching shear. Drop panels were sized using ACI318-08 section 13.2.5, resulting in an 11ft x 11ft drop panel 10ft x 10ft, see *Figure 14* for drop panel detail. The two-way slab is reinforced with #6 bars, with spacing fluctuating depending on the location of the bar.




Figure 14 - Drop Panel Detail

Preliminary column sizes were needed in order to proceed with the slab analysis, using spColumn and analyzing a column on Level 3, it was found that a 30"x30" column would be sufficient for the factored axial loading. The Direct Design Method prescribed in ACI318-08 was used to obtain positive and negative bending values for the slab. Minimum slab thickness was determined per Table 9.5(c), using the larger of the two spans, t_{min} was found to be 10". After the moments were calculated in each direction, moments were distributed to column and middle strips, per ACI318-08 section 13.6.4.

General

The two-way flat plate system is one of the more costly of the systems at \$20.65 per square foot; this was expected due to the cost of concrete in the Albany, New York area. This is also the heaviest system; however, it has the smallest total system depth, which is an advantage due to small floor-to-floor heights. The increase in weight due to the deep slab would increase the size of the foundations and the lateral resisting systems.

Architectural

The two-way flat slab with drop panels is an ideal system for the floor-to-floor height restrictions on this project allowing for more space for MEP. Fire rating for this system is achieved without any additional fireproofing, therefore reducing ceiling finishing costs in permitted areas. Some architectural spaces would be impeded because of the use of concrete shear walls in the building to resist the lateral forces.

Structural

Although the floor-to-floor heights are easily met with this system, it is not a viable solution structurally due to the total weight of the system, and the larger deflections. However the extra weight to benefit this project specifically because an issue with soil rebounding arose during construction of this building. There was elastic rebounding due to the unloading of the weight of the excavated material, and the extra weight of the system on this subgrade could counteract this uplift.

Serviceability

Long-term deflections were calculated assuming 25% of the live load is dead load after a long time; the deflections met the serviceability standards set by ACE. The long-term deflections were calculated to be 1.19", which would not be ideal for a hospital due to disruptions of ceiling equipment that is finely calibrated.

Pros and Cons


Pros:

- Low floor-to-floor heights
- No fire-proofing required
- Cost saving on ceiling finishes
- Minimal formwork

Cons:

- Large deflections
- Difficult to construct
- Tedious formwork for drop panels
- Longer construction timeline

One-Way Concrete Slab and Beam System



Another alternate floor system is a one-way concrete slab and beam system, the slab depth is 5" and total depth is 20". The same column dimensions of 30"x30" were also used in this system, the compressive strength of concrete is 4000psi, and the beam depths are the same as the girder depths for constructability.

The one-way slab spans 10'-0" between the two-infill beams spanning 27'-0", sitting on a 30" wide by 20" deep girder that spans 30'-0". To prevent tedious formwork between the column face and the girder, the girder is 30" to be flush with the faces of the column. When designing the beams ACI moment coefficients were used to find the negative and positive moments for the span. The moments in the girders were obtained by modeling the girder in STAAD Pro. Refer to Appendix C for hand calculations.

General

The one-way slab and beam system is the most costly system used due to the amount of formwork required compared to a two-way flat slab. The increase in weight will create a greater demand for the size of the foundations as well as the seismic detailing due to an increase in base shear, but the additional mass is better for vibration resistance. The one-way system is obsolete to the one-way composite system because of cost, total deflection, and weight.

Architecture

Fireproofing is not needed in this system because the 2-hour fire rating is obtained by providing a minimum clear cover of 3/4" for slabs and 1 1/2" for beams and girders. The depth of this system is appropriate for the floor-to-floor height limitations, but it would be more efficient if the column spacing were rearranged to reduce the depth of the beam and girders.

Structural

The floor weight is significantly increased compared to the one-way composite; this will help floor vibrations around critical areas; however, it will increase the size of foundations and the seismic base shear. Compared to a flat slab, less shear walls will be needed, because moment frames can be utilized to resist the lateral forces, this will create more openings within the building.

Serviceability

Total deflections for the beam were found by using deflection calculations given in Chapter 3 of the AISC 14th Edition, and for the girder, STAAD Pro was utilized to determine the deflections at third points on the girder. Adding the deflection of the girder where the beam rests to the total deflection of the beam gives an approximate total deflection. This deflection is .902 inches, which passes the deflection criteria of L/240 per Section 8.4.2 in ACI318-08. Refer to *Figure 16 and Figure 17* for STAAD deflection results for the girder.

Pros and Cons

Pros: No fire-proofing required Good vibration resistance Cons: Most costly Increase in lateral loads




Figure 16 – Live Load Deflection of Girder




Figure 17 – Total Load Deflection of Girder

Hollow Core Precast Planks with Steel Framing




Figure 18 - Frame Layout

Hollow core precast plank with steel framing spanning 27'-0" demanded for an 8" plank and a 2" topping added for floor vibrations and fire-rating requirements. The planks rest on a seated connection consisting of an angle welded to the web of the girder in order to comply with the floor-to-floor height limitations see *Figure 19*.

The hollow core plank was chosen from the Nitterhouse catalog, using an 8"Dx4'-0"W plank with (6) 1/2" φ 270kip tendons, see *Figure 20*. Using 6 tendons provides the option of cutting a plank in half without cutting through any of the tendons. Cutting the 4'-0" plank into a 2'-0" plank is necessary because the bay width is 30'-0", (7) 4'-0" planks and (1) 2'-0" plank must be used to accommodate the bay sizes.

General

Hollow core precast plank is the cheapest and relatively lightest; however it is not a viable solution for the Patient Pavilion. The issue with this system is the girder needs to be very deep in order to support the weight of the plank over a large span. Making the girder deeper is the only solution and in turn, this will affect the allowable total system depth.

Architectural

The hollow core plank chosen has a 2-hour fire rating incorporated in its design; however the steel girders would still need fire proofing. Column spacing should be rearranged in order to reduce the span of the steel girder, in turn reducing the depth of the girder.

Structural

The weight of the hollow core plank demands for a heavy deep girder, making this not a viable solution for the Patient Pavilion. The depth of a W18x175 is 20.04 inches with the plank sitting on top of the girder; the total system depth would be 30" deep, which is not acceptable. Using the connection shown in *Figure 19*, a depth of 20" will be achieved and the total depth will be acceptable for floor-to-floor height restrictions.




Figure 19 - Connection Detail

Serviceability

The overall deflection of the hollow core plank is very small which is due to the initial camber in the system, however the span of the girder and the weight of the plank results in a large deflection. The total deflection of this system is 0.97 inches, which passes the deflection criteria of L/240.

Pros and Cons

Pros:

- Minimal formwork
- Less weight

Cons:

- Construction difficult
- Heavy girders
- Large deflection
- Slab renovation is difficult

54"

2"

 $5\frac{1}{2}$

Prestressed Concrete 8"x4'-0" Hollow Core Plank

2 Hour Fire Resistance Rating With 2" Topping

PHYSICAL PROPERTIES Composite Section $A_c = 301 \text{ in.}^2$ Precast $b_w = 13.13$ in. I_c = 3134 in.4 Precast S_{bcp}= 616 in.³ $Y_{bcp} = 5.09 \text{ in.}$ Topping $S_{tct} = 902 \text{ in.}^3$ Y_{tcp}= 2.91 in. Precast S_{tcp} = 1076 in.3 Precast Wt. = 245 PLF $Y_{tct} = 4.91 \text{ in.}$ Precast Wt. = 61.25 PSF

DESIGN DATA

- 1. Precast Strength @ 28 days = 6000 PSI
- 2. Precast Strength @ release = 3500 PSI
- 3. Precast Density = 150 PCF
- 4. Strand = 1/2"Ø 270K Lo-Relaxation.
- 5. Strand Height = 1.75 in.
- 6. Ultimate moment capacity (when fully developed)...
 - 4-1/2"Ø, 270K = 92.3 k-ft at 60% jacking force 6-1/2"Ø, 270K = 130.6 k-ft at 60% jacking force
 - 7-1/2"Ø, 270K = 147.8 k-ft at 60% jacking force
- 7. Maximum bottom tensile stress is 10 √fc = 775 PSI
- 8. All superimposed load is treated as live load in the strength analysis of flexure and shear.
- 9. Flexural strength capacity is based on stress/strain strand relationships.
- 10. Deflection limits were not considered when determining allowable loads in this table.
- 11. Topping Strength @ 28 days = 3000 PSI. Topping Weight = 25 PSF.
- 12. These tables are based upon the topping having a uniform 2" thickness over the entire span. A lesser thickness might occur if camber is not taken into account during design, thus reducing the load capacity.
- 13. Load values to the left of the solid line are controlled by ultimate shear strength.
- 14. Load values to the right are controlled by ultimate flexural strength or fire endurance limits.
- 15. Load values may be different for IBC 2000 & ACI 318-99. Load tables are available upon request.
- 16. Camber is inherent in all prestressed hollow core slabs and is a function of the amount of eccentric prestressing force needed to carry the superimposed design loads along with a number of other variables. Because prediction of camber is based on empirical formulas it is at best an estimate, with the actual camber usually higher than calculated values.

SAFE S	UPERIMPOSED	SEF	RVIC	ΈL	OAE	os				П	BC :	2006	3 & 7	ACI	318	-05	(1.2	D +	1.6	L)
St							S	PAI	۷ (F	EET)									
Pa	attern	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35
4 - 1/2"ø	LOAD (PSF)	280	248	214	185	159	138	118	102	87	74	62	52	42			>	<		
6 - 1/2"ø	LOAD (PSF)	366	341	318	299	271	239	211	187	165	146	129	114	101	88	77	67	58	50	42
7 - 1/2"ø	LOAD (PSF)	367	342	320	300	282	265	243	221	202	181	161	144	128	114	101	90	79	70	61

11/03/08

NITTERHOUSE



2655 Molly Pitcher Hwy. South, Box N Chambersburg, PA 17202-9203 717-267-4505 Fax 717-267-4518

This table is for simple spans and uniform loads. Design data for any of these span-load conditions is available on request. of heavy loads, concentrated loads, cantilevers, flange or stem openings and narrow widths. The allowable loads shown in this table reflect a 2 Hour & 0 Minute fre resistance rating.

3'-10¹/₈"

71/8

4'-0" +0",-1"

71/8


19"

18

5<u>1</u>"

8SF2.0T

Figure 20 - Nitterhouse Catalog



Floor System Summary

Table 7 – Alternate Floor System Summary

		Existing		Alternatives	
		One-way Composite	Two-way Flat Slab With Drop Panels	One-way Slab and Beams	Hollow Core Precast Planks with Steel Framing
	Weight(psf)	60	150	100	95
	Cost (\$/SF)	\$17.76	\$20.65	\$21.76	\$14.45
General	Slab Depth (inches)	6.5	10	5	8
	Total System Depth (inches)	22.5	12.5 20		22
Structural	Lateral System Alterations	N/A	Shear Walls	Shear Walls and Moment Frame Detailing	Braced and Moment Steel Frames
	Foundations	N/A	Yes	Yes	Yes
Architectural	Bay Size Alteration	N/A	Yes	Yes	Possibly
Architectural	Fire-Rating	2 hr with Spray fireproofing	2 hr	2 hr	2 hr with spray fireproofing
Serviceability	Max Deflection (Inches)	2 hr with Spray	1.19	.902	.97
	Vibration	Average	Average	Good	Good
Construction	Constructability	Easy	Difficult	Moderate	Difficult
Construction	Formwork	Minimal	Fair	Ample	None
Conclusion	Viable Option	N/A	Yes	Yes	No

Conclusion

The results of this study concluded whether or not each alternate floor system is a viable solution for the Patient Pavilion, as well as comparing them against the existing floor system. Hand calculations supplemented with computer modeling were used to obtain schematic sizes and deflections for each floor system. Comparing the aspects of each system structurally, architecturally, and for constructability helped determine the most viable solution.


The existing composite beam and composite deck system seems to be the most viable solution for the Patient Pavilion. The cost of this system is the second lowest at \$17.76, which is expected in the area of Albany because of the high cost of concrete. A composite system requires minimal formwork and is easily constructed, which lowers the overall cost of the system. Because of the large bay sizes, a steel system is the most appropriate due to the flexibility of the beam sizes to meet floor-to-floor height requirements. This system is deemed the most viable solution out of the floor systems analyzed.

The two-way slab system with drop panels was the heaviest of the systems analyzed, however the low slab depth is superb for the floor-to-floor height restrictions. The advantages of this system include minimal formwork, and no fireproofing needed. Some disadvantages of this system include the difficulty of construction, large deflections, and the need for shear walls for lateral load resistance. The two-way slab system with drop panels is a viable solution to the Patient Pavilion, however with the large deflections and weight of the system it is not the best solution.

The one-way slab with beams system was the most expensive system analyzed, however it did have the best deflection control other than the existing composite system. The advantages of this system include low cost of formwork due to redundancy, good constructability, and a good damping response to floor vibrations. Some negative aspects of this system include costly, increase of floor weight, and larger seismic loads due to the increase in floor weight. The one-way slab with beams system is a viable solution to the Patient Pavilion; however, it is not the most optimal option.

The hollow core precast plank system is the cheapest of all the systems used, however this does not include the additional cost of the special connection. The advantages of this system include minimal formwork and fireproofingis not needed; however, these are obsolete compared to the disadvantages of this system. The disadvantages include large deflections, difficult construction, special in-shop connections, deep girders, and difficult to renovate due to the prestressed tendons. The hollow core precast plank system was determined to not be a viable solution for the Patient Pavilion.

Appendix A: Existing System Hand Calculations




THOMAS KLEWOSKY Gravity	Checks Page Z of 10
Beam Checks:	
W12×30[4] <	C+364) W12×30 Properties
Tributary width = Span = 27'-4"	101-0" Fy = 50ksi Ix = 238 in 3 A = 8.79 in ²
Loads	
LL = 80 psf - NON-reducal SDL = 47 psf OL = 48 psf -> Slab + Dec	
We = 1.20+ 66 C	
(47+48) +10/200 = 0.99	5 KLF
Live	
(80 psf) 10ft = 0.	8 KLF
Wu= 1.2(.95)+1.6(0.8)	= 2.42 KLF + Beam Selfe wt.
* * * *	24 = 2.42 KLF
Mu = 2.42(27.332) = 22	
$V_u = \frac{2.92(2733)}{2} = 3$	3 × > drawings call out 35 x: OK
beff = 2x 1/2 dist to	3 x -> drawings call out 35 x : OK = 2(27.33) x 12 = 82 w> Controls adjudent boom - 2x 2x 12 = 120 w.


R	for 3/	4" p Qn=	stude +	BECKS 3500 ps. (Lable 3-2	conc.			
_a			17.2×	Cable 3-2	(1)			
_a		1						
		SE TIM						
	Yz =	6.5	- lu/2 =	610				
	PMn =	244	k-ft > 2	225 k-ft	:. OK	/		
	ΣQn	= 110	4					
	number a	of st	uds = 2	Qn = 1	7.2 = 4.	4 study	sile	
			6.442	= 12.8 st	ids ->	use 1	4studs	
	dVn=	95.9	x (to	be 3-6	(,)			
		95	. 9K7 :	33× 0	KV.			
Chee	k unshare	d len	gth:					
	WI	2×30) -> p1	Mp = 1621	e-Ft			
	Construct	tion	Loads =	ZOPE				
	wa = 10							
			32 klf	Ft) + 1.Z	130,15	+ 1.66	20ps f x 10 Ft)
	Mu	0.9	132 (27.	332) = 8	37k-Ft	-		
	4	Mp >	Ma :-	OKV				

	THOMAS KLEWOSKY	GRAVITY	CHECKS	Page 4of	0	
	Check wet a	oncrete deflece	tion: K			
U		1448)+ 30 =				
	AD _{ioa}	= 5wl4 =	5 (51)(2)	7.33)4 (1728)	= 0.93 IN	
		= 20 = 2				
		0.931W < 1.41W	:. OK/			
	Check Live Lo					
	(table 3-20) ILB = 4	80psf x 10f	t = 0.8 k.l	(8		
		= 5(0.8)(2 384/2	?7.33")(1728 ??@)(498)	0.695	īw.	
	Acena	$=\frac{L}{360}=\frac{27.3}{3}$	53 x 12 = 0			
		ALL & ALLMAN	:. OK ~			
	Lu:	se a WIZ	30 [4]			
0						


THOMAS KLEWOSKY Gravity Checks Pag	ne 5 of 10
Composite airder: Wller 89 [36]	Properties:
Pa Pa	Fy = 50 ksi Ty = 1300 in 3 A = Z6. Zw = to = 0.89 in
Arr Ar	bf = 10.41N
Pu = Puperso + Pucine Uses =	0.25+ 15 - 0.62
Dead: Pup (95psf & 10 x 27.33) = 26 K	
Live: Puz= (80psf x 10ft x 27.33ft) x 0.62 =	13.6k
Pu = 1.2(26) + 1.6(136) = 58k	
Vu = 53 k Mu = 53 k x 10 Ft = 53 C	0 k-ft
Find bess	
bess = $2 \times \frac{5pan}{8} = 2 \times \frac{30}{8} \times 12 =$	= 90 w.
FIND EQN For Girder, Qn = Rg Rp Ase Fu = 16.75) WA SASE FEE = .56	(·돌)² 11/65)= 21,5k
WA 15 ASC VECE - 19.2	* -> Use
EQn = 19.2 x x 30 stude = 346 K	
Is it Partially composite?	
V'c = 0.85 (3.5)(10)(4.5) = 1740 K V's = 24.2 (50) = 1310 5	
EQ = 346 & 1740K Yes	it's Partially osite




Page 705 10
CHECK WISHORED LENGTH :
W16×89 - & Mp=657FE-k
Wu = 1.2(48 psf x 27.33)+1.2(89 plf)+ 1.6(20psf x 27.32)
= 2.6 klf
Ma= Z.6(302) = 292.5 FE-5: OK-
Check wet concrete deflection:
Wwe=(48+27.33)+89=1.4kls
0. 5/14)/30)4/1728) 0707
Ause: 5(1.4)(30)4(1728) - 0.382110 384(29000)(1300)
A Wenny = 210 = 30(12) = 1.5 IN 3. OK
Check Acc:
ALL = 5(0.8)(304)(1728) = 0.386 W.
Average = 30(12) = 110: OK





	THOMAS	KLEWOSKY	Gravity Checks	Page for 10)
		Column Load	4		
		Roof:			
		Po:	= 30fsfx 820ft2:	Z4.6K	
		PL=	4016F x 820FE =	32.85	
		Part house:			
		Po	5 = P = 125 psf = 820 ft	Z= 102.5K	
		Level 2:			
		Po	= 95psF x 820 Ft ==	77.95	
			$res = .25 + \frac{15}{15250} = 0$		
			,51 (80 ×820) = 3		
		Level 3	= 95 psF + 820 = 77.9	K	
		L.	ru = 125+ 15 = a	44	
		Pe=	.44 (80.820) = Z8.9		
		P.	= 95 × 820 = 77.9 k		
		u	= 95 × 820 = 77.9 k (4) = .25+ (5) = 0.	25 -> 0.4	
			= 0.4 (80 × 820) = 2	6.2	
		Level 5 Po	- 77 0¢		
		P	= 0.4(80.820) = 26.	2 K	
		Level GA Po Pe	7 9		
		Po	> 77.95		
		re	= 26.6		
		1000 8 9	9		
		Po	= 77.9K		
		6	9 = 77.9× = (100 p=F × 820) = 8	BZK	
U -		Total			
	1	the state of the s	750.3 × Pz=		
		P=17(750)	+ 1.6(466) = 1650 K	5 2210 K : OK W	



Appendix B: Flat Slab with Drop Panels











	0 +0	xt d'is	deng	10 - 0.75 - 0.75 =	0, 01
1	Eall colum str	ip	Mida	le Strip	
	M+	M-	M ⁺	M-	
Ma (Ft-K)	172	- 396	114	-132	
With of stip (w)	142	162	162	162	
effective dythlu	8.876	8.876	8.876	8.875	
Mux12 (K-18/14)	12.7	29.3	8.44	9.8	
	191.1	-440	126.7	-146.7	
R= Ma bdz	177.1	-413.8	119.2	-138	
P	0.00302	0.0073	0.00 202	0.0023	
As=pbd	(4.34)	10.5	2.9	(3.31)	
Asmin = 0.00186	t Z.9Z	2.92	2.92	2.92	
N = As	10	24	8	8	
Unia = b	9	9	9	9	
Spacing	14,500	Cow	18w	1810	

			Page 5 of 11
	Rein	Forcement design - Long 5	ран
		Drop Panel	
	dieng	25w WW	deg = 12.575 - 0.75 = 11.4 in.
		Column Strig	
	Mn	396 Ft-k	
	Width	17.0w	
	10	11,40.	
	Mu	440	
	R	338.6	
	P	0.00589	
	As=pbd	8.06 W2	
	Asma = 0.001860.	2,7,02	
	N	[19]	
	Vrist 2	5	
	Spacing	Gw.	












	Page 10 of 11
	Deflection
	Service Coads Assame:
	$\omega_{\rm D}=34+125=159{\rm psf}$ G7.5% moment is in column strip $\omega_{\rm L}=80{\rm psf}$ 32.5% moment is in middle strip $\omega_{\rm consc}=20{\rm psf}$
	Column Strip along lines
	$I_9 = \frac{(L_2/2)(t^3)}{12} = \frac{27 \times 12}{2} (10^3) = 13500 \times 12$
	E= 57000 JF & = 57000 J5000 = 4030 ksi
	Loads: Wo = 159psf x 27ft = 4.3 Klf x 0.675 = 2.9 klf
	We = 80 psf + 27 ft = 2.7 klf x 0.675= 1.5 klf
	Went = ZOPSF x ZTFt = 0.54 klf x 0.675 = 0.36 klf
	$\Delta_{p_{max}} = 0.0024 \frac{w_0 L^4}{E I_g} = 0.0024 \frac{2.9(30^4)}{4030(13500)} \times 12^3 = 0.193 w.$
	Acmax = 0.0048 We lu = 0.0048 1.5(304) x 123 = 0.185 m
	ALONG term = 3 (0.193+ 0.25 (0.185)) = 0.71810


Page 1108 11
Deflection
Middle Strip
$I_9 - (18)(10)^3 = 14500w^4$
We = 80x 30x 0.325 = 1.6 klf We = 80x 30x 0.325 = 0.78 klf
DOMAY = 0.0026 (1.6)(274) ×123 = 0.057510.
$A_{CMAy} = \frac{0.0048(0.78)(274)}{4030(14500)} \times 12^3 = 0.05171N$
Along = 3 (0.0575+0.25 (0.0517)) = 0.211 w
Immediate live Load deflection
AL = 0.185 + 0.0517 = 0.236 W
ACI Code Limit = 2 = 30x12 = 1.01N = OK
Check total deflection after attachment of Partitions
Amax = 0.1 (0.193+0.0575)+0.236+ (0.718+0.211)
DMax = 1.1910
ACI Code limit = 2 = 30 812 = 1,5 in : OK





	Page Zof8
0	Shear Cheek Vu = 1.5 wu ln = 1.5 (0.24) (10-12) = 1.65 Mewith Z
	ΦVc = 0.75 (2) Fe bwd) = 0.75 (21) 14000 (12)(4) = 4,5 K/Fe width
	Asis = 0.0086h = 0.173w2 : As = 0.18902 Governs
	Reinforcement Specing $5 = 15 \left(\frac{40000}{F_S} \right) - 2.5 C_0 \le 12 \left(\frac{400000}{F_S} \right)$ $5 = 15 \left(\frac{40000}{F_S} \right) - 2.5 \left(.75 \right) = 13.125 \le 12.0 \Rightarrow 900 = 18.5 $
0	Shrinkage and temperature $A_{gat} = 0.0018(12)(8) = 0.1728w^2 \rightarrow use #4s$ $Max spacing s 5h = 5(8) = 4010$
	Mia 1810 -> Governs
	Slab Summary: - 5 in Slab with #4 Bars @ 12 in O.C. For top 4 Botton Flexural Steel - No. 4 Bars @ 18 in For Shrinkape + temperature











Deflection Checks: Beam :		Page 8 of 8	
$\Delta_{LL} = \frac{5(80 \times 10)(27^4)1728}{389(3.61 \times 10^6)(8000)} = 0.3310$ $\Delta_{LL} = \frac{5((12.5 + 74)(9) \times 250 \times (80 \times 10))}{389(3.61 \times 10^6)(8000)} = 0.799$ $ACI Code Limitations$ $\Delta_{LL} = \frac{1}{240} = 0.910 \times 0.3310 = 0.06$ $\Delta_{LL} = \frac{1}{240} = 1.35 \times 10.7910 : 0K$ $\Delta_{LL} = 0.09510$ $\Delta_{LL} = 0.09510$		DeFlection Checks	
$\Delta_{u} = \frac{5(80 \times 10)(27^{4})(728}{384(3.61 \times 10^{4})(8000)} = 0.33 \times 10$ $\Delta_{rc} = \frac{5(20.5 + 74)(4)(7.250 + (80 \times 10))}{384(3.61 \times 10^{4})(8000)} = 0.794$ $AC1 (ode Limitations)$ $\Delta_{u} = \frac{L}{760} = 0.9 \times 10.70.33 \times 1.0K$ $\Delta_{rc} = \frac{L}{240} = 1.35 \times 10.79 \times 1.0K$ $\Delta_{ud} = 0.045 \times 10$ $\Delta_{ud} = 0.045 \times 10$		Beam: I = 1/12 (12) (203) = 8000103	
$\Delta_{LL} = \frac{5([42.5+34)(9)\cdot 250\cdot (8010)]}{384(3.6410^6)(8000)} = 0.794$ $\frac{384(3.6410^6)(8000)}{4(1)(1000)}$ $\Delta_{LL} = \frac{1}{360} = 0.910 \cdot 70.3310 : 0K$ $\Delta_{LL} = \frac{1}{240} = 1.3510 \cdot 70.7910 : 0K$ $\Delta_{LL} = 0.04510$ $\Delta_{LL} = 0.04510$	*	E = 5/000/ 7000 = 5.4/10 KSI	
384 (3.61×10 ⁶)(8000) ACI Code Limitations. $\Delta_{LL} = \frac{L}{760} = 0.910 \ 70.3310 \pm 0K$ $\Delta_{TL} = \frac{L}{240} = 1.35 \text{ in } 70.7910 \pm 0K$ $\Delta_{LL} = 0.04510$ $\Delta_{LL} = 0.04510$			
$\Delta_{LL} = \frac{Q}{760} = 0.910 \ 70.3310 = 0.8$ $\Delta_{\Gamma L} = \frac{Q}{240} = 1.3510 \ 70.7910 = 0.8$ $\Delta_{LL} = 0.04510$ $\Delta_{LL} = 0.04510$		An = 5 [(42.5+34)(4)+250+(80×10)] 274 x 1728 = 0.799 384 (3.61×106)(8000)	
$\Delta TL = \frac{L}{240} = 1.35 \text{ in } 7 \text{ O.79 is} : OK$ $Childer: Done In Stadd$ $\Delta LL = 0.045 \text{ is}$			
DLL = 0.045 in			
		Cander: Pone In Stadd	
Δτς = Θ, 134ω			
		ATC = 0.134w	
	74		
	9		

Appendix D: Hollow Core Precast Plank on Steel Framing

