

# SUPPORTING DOCUMENTS

# APPENDIX A: MEETING MINUTES

Meeting Minutes
-----------------

**350 Mission** Team: 05-2014  
 350 Mission Street  
 San Francisco, CA 94105

**Team Coordination Meeting #3**

Date	Time	Next Meeting (Date/Time)	Team
9/29/2013	2:30 PM	9/30/2013 3:30 PM	AEI 05-2014

Purpose	Location	General Notes
Weekly coordination meeting to discuss the current state of the project, discuss new findings/conflicts, as well as looking ahead to upcoming week's activities	Thesis Studio	M - Mechanical CM - Construction Managmnet E - Electrical/Lighting S - Structural

Attendees		Non-Attendees
Scott Brown	E	
Andrew Levy	E	
Jordan Huey	M	
Helen Leenhouts	M	
Patrick Vogel	CM	
Rebecca Bires	CM	
Jeff Loeb	S	
Scott Eckhart	S	

Item #	Item	Responsible	Status	Date Created	Date required
1	<b>Hot Items:</b> Google sketchup model to import into IES All options to have powerpoint slide completed by Sunday				
2	<b>Mechanical</b> Narrow down Net Zero definition to combining definitions Floor plan design to be finalized			9/29/2013	
3	<b>Lighting/Electrical</b> To determine lighting density DaySim model to be finished			9/9/2013 9/29/2013	
4	<b>Structural</b> Basic siesmic calcs			9/17/2013	
5	<b>Construction</b> Researching site logistics Begin constructing the Revit model			9/9/2013	

## APPENDIX B: REFERENCES:

- “2013 California Building Code.” *International Code Council*.  
California Building Standards Commission, n.d. Web. Fall 2013.
- “Budget Calculator For Access Floors.” *Access Floor Systems, Inc.* N.p., n.d. Web. Spring 2014.
- Leadership in Energy and Environmental Design (2008). LEED 2009 For Schools New Construction and Major Renovations. Fall 2013.  
Web.<<http://www.usgbc.org/ShowFile.aspx?DocumentID=5547>>.
- “My Solar Estimator.” *Solor-Estimate*. N.p.,nd. Web. Spring 2014  
<<http://www.solar-estimate.org>>
- Reed Construction Data Inc. (2014). RSMMeans Online Version 5.0.3. Spring 2014. Web.  
<<http://www.rsmeansonline.com/SearchData>>.
- “Combined Heat and Power Partnership.” *EPA*. United States Environmental Protection Agency, 7 November 2013.  
<http://www.epa.gov/chp/>.
- “Renewable Energy Program.” *California Energy Commission*.  
[http://www.energy.ca.gov/renewables/renewable\\_links.html](http://www.energy.ca.gov/renewables/renewable_links.html)
- “Delivering Low-Emission Energy.” *Clean Energy Solutions*. PG&E  
<http://www.pge.com/en/about/environment/pge/cleanenergy/index.page>
- “Combined Heat and Power (CHP) is it Rightyou’re your Facility.” *University of Illinois*.[https://www1.eere.energy.gov/manufacturing/pdfs/webcast\\_2009-0514\\_chp\\_in\\_facilities.pdf](https://www1.eere.energy.gov/manufacturing/pdfs/webcast_2009-0514_chp_in_facilities.pdf)
- “Natural Gas and Environment.” *Natural Gas*. <http://www.naturalgas.org/environment/naturalgas.asp>
- “Capture and Storage of Carbon Dioxide From Earth’s Atmosphere.” *Mission 2013 Carbon Sequestration*. Massachusetts Institute of Technology <http://igutek.scripts.mit.edu/terrascope/?page=Algae>
- ASHRAE, ANSI/ASHRAE Standard 62.1-2007.
- ASHRAE, ANSI/ASHRAE Standard 55-2007

APPENDIX C: DETAILED ESTIMATE

Detailed Estimate			
Scope of Work	Cost	Scope of Work	Cost
<b>General Conditions</b>	\$7,562,918	<i>Boilers</i>	\$52,526
<b>Sitework</b>		<i>Mictoturbines</i>	\$937,250
<i>Excavation</i>	\$281,187	<i>Chillers</i>	\$1,191,170
<i>Dewatering</i>	\$940,295	<i>Raised Access Floor</i>	\$10,666,586
<b>Foundation</b>		<i>Ductwork</i>	\$2,414,135
<i>Slurry Wall</i>	\$1,760,581	<b>Electrical</b>	
<i>Mat Foundation</i>	\$1,111,231	<i>Switch Gear</i>	\$106,490
<i>Mat Foundation Rebar</i>	\$111,122	<i>Generator</i>	\$90,942
<i>Parking Garage</i>	\$8,363,950	<i>Transfer Switch</i>	\$29,900
<b>Structure</b>		<i>Distribution Panel</i>	\$152,490
<i>Metal Decking</i>	\$1,252,359	<i>Transformer</i>	\$102,258
<i>Concrete</i>	\$4,344,157	<i>Panelboards</i>	\$301,030
<i>Reinforcement</i>	\$304,013	<i>Wiring</i>	\$4,775,284
<i>Formwork/Curing</i>	\$225,257	<i>Lighting Fixtures</i>	\$8,693,575
<i>Steel</i>		<i>Receptacles</i>	\$4,473,976
<i>Beams</i>	\$7,612,926	<i>Photovoltaic</i>	\$718,000
<i>Columns</i>	\$7,351,078	<b>Services</b>	
<i>Built Up Columns</i>	\$202,643	<i>Gas Sprinkler System</i>	\$8,954,485
<i>Brace Framing</i>	\$4,095,231	<i>Rain Water Collection</i>	\$671,543
<i>Shear Connections</i>	\$490,743	<i>Plumbing Fixtures and Fittings</i>	\$1,233,944
<i>Fireproofing</i>	\$260,837	<i>Elevator and Lifts</i>	\$8,601,080
<b>Double Façade</b>	\$15,566,226	<i>Stair Construction</i>	\$691,840
<b>Roof</b>	\$120,659	<b>Finishes</b>	
<b>Interiors</b>	\$14,384,990	<i>Ceiling Finishes</i>	\$1,369,580
<b>Mechanical</b>		<i>Floor Finishes</i>	\$2,834,763
<i>Cooling Tower</i>	\$102,810	<i>Wall Finishes</i>	\$6,044,944
<i>Air Handling Units</i>	\$3,604,618	<b>Total</b>	<b>\$148,095,270</b>

GENERAL CONDITIONS ESTIMATE:

Staffing				
<i>Personnel</i>	<i>Qty.</i>	<i>Unit</i>	<i>\$/Unit</i>	<i>Cost</i>
Project Manager	120	Week	\$3,275.00	\$393,000
Engineer	120	Week	\$3,275.00	\$393,000
Superintendent	120	Week	\$2,050.00	\$393,000
Safety Superintendent	120	Week	\$1,638.00	\$393,000
BIM Engineer	120	Week	\$900.00	\$393,000
			<b>Total</b>	<b>\$1,336,560</b>

Temporary Facilities				
<i>Description</i>	<i>Qty.</i>	<i>Unit</i>	<i>\$/Unit</i>	<i>Cost</i>
On Site Trailer	25	Months	\$223.00	\$5,575
Off Site Trailer	5	Months	\$4,200.00	\$21,000
Temporary Fencing	630	LF	\$26.75.00	\$16,853
Sanitary Facilities	30	Months	\$200.00	\$6,000
			<b>Total</b>	<b>\$49,428</b>

Temporary Utilities					
<i>Description</i>	<i>Qty.</i>	<i>Unit</i>	<i>\$/Unit</i>	<i>Cost/month</i>	<i>Total Cost</i>
Dewatering System	208	VLF	\$3,931.00	-	\$817,648
Temporary Power	160	CSF	\$110.00	\$17600	\$809,600
Temporary Lighting	160	CSF	\$3.63	\$581	\$26,717
Temporary Heating	160	CSF	\$31.78	\$5085	\$233,901
Water	46	Months	\$65.00	-	\$2,990
			<b>Total</b>		<b>\$1,890,856</b>

Bonds, Insurance and Tax			
<i>Description</i>	<i>Percentage</i>	<i>Project Cost</i>	<i>Cost</i>
Performance Bond	1%	\$137,594,704	\$1,375,947
General Liability Insurance	0.50%	\$137,594,704	\$687,974
Builder's Risk Insurance	0.25%	\$137,594,704	\$343,987
Permits	0.50%	\$137,594,704	\$687,974
Contingences	3%	\$137,594,704	\$4,127,841
Tax	6%	\$137,594,704	\$8,255,682
		<b>Total</b>	<b>\$15,479,404</b>



APPENDIX D: LIFE CYCLE COST ANALYSIS

LIFE CYCLE COST ANALYSIS						
System	Cost	Annual Energy Load Reduction	Annual Energy Cost Savings	Payback Period	Lifetime	Return on Investment
Photovoltaic System	\$218,000	149,800 kWhr	\$26,964	8.1 years	25 years	\$456,100
Combined Heat-and-Power	\$503,000	1,014,000 kWhr	\$101,400	5.0 years	15 years	\$1,018,000
UFAD/DFS	\$2,390,882	1,111,144 kWhr	\$200,006	12.0 years	100 years	\$17,609,710
<b>NOTES:</b>	<b>The cost of the UFAD/DFS systems is the cost of upgrading from a traditional system, estimating that a traditional air distribution system would cost \$10,228,260, and a single façade would cost \$13,613,670</b>					

The life cycle cost analysis was a vital part of the decision making process for system design. We wanted to make sure that in designing a near net-zero energy building, we were still taking into consideration the economic feasibility for the owner. The photovoltaic and CHP systems both have a payback period of less than 10 years, making them a reasonable choice for a system.

Notably, the cost to upgrade from a tradition system to our designed underfloor air distribution system, and double façade is only \$2.4 million (less than 1.5% of the project budget). These systems, however, are responsible for the majority of our cooling and heating load savings, and will save the owner a great deal of money in the long run.

SIMPLE CASHFLOW DIAGRAM				
Year	Notes	Cost/Maintenance	YTD Savings	Cashflow
1	All systems bought	\$3,132,410	\$328,370	-\$2,804,040
2	-	\$56,528	\$328,370	-\$2,532,198
3	-	\$56,528	\$328,370	-\$2,260,356
4	-	\$56,528	\$328,370	-\$1,988,514
5	-	\$56,528	\$328,370	-\$1,716,672
6	-	\$56,528	\$328,370	-\$1,444,830
7	-	\$56,528	\$328,370	-\$1,172,988
8	-	\$56,528	\$328,370	-\$901,146
9	-	\$56,528	\$328,370	-\$629,304
10	-	\$56,528	\$328,370	-\$357,462
11	-	\$56,528	\$328,370	-\$85,620
12	-	\$56,528	\$328,370	\$186,222
13	-	\$56,528	\$328,370	\$458,064
14	-	\$56,528	\$328,370	\$729,906
15	CHP system replaced	\$559,528	\$328,370	\$498,748
16	-	\$56,528	\$328,370	\$770,590
17	-	\$56,528	\$328,370	\$1,042,432
18	-	\$56,528	\$328,370	\$1,314,274
19	-	\$56,528	\$328,370	\$1,586,116
20	-	\$56,528	\$328,370	\$1,857,958
21	-	\$56,528	\$328,370	\$2,129,800
22	-	\$56,528	\$328,370	\$2,401,642
23	-	\$56,528	\$328,370	\$2,673,484
24	-	\$56,528	\$328,370	\$2,945,326
25	PV system replaced	\$274,528	\$328,370	\$2,999,168
<b>General Notes: Assuming a yearly maintenance cost of \$12,168 for CHP, \$4360 for PV, and \$40,000 for DF/UFAD. Also assuming a lifetime of 15 years for CHP system (per Capstone spec sheet), and 25 years for PV system (per SunPower spec sheet)</b>				

APPENDIX E: LEED



**LEED 2009 for New Construction and Major Renovations**  
Project Checklist

350 Mission Street  
January 27th, 2014

**21 Sustainable Sites Possible Points: 26**

Y	?	N			
Y			Prereq 1	Construction Activity Pollution Prevention	
1	C		Credit 1	Site Selection	1
5	C		Credit 2	Development Density and Community Connectivity	5
	C		Credit 3	Brownfield Redevelopment	1
6	C		Credit 4.1	Alternative Transportation—Public Transportation Access	6
1	C		Credit 4.2	Alternative Transportation—Bicycle Storage and Changing Room	1
3	C		Credit 4.3	Alternative Transportation—Low-Emitting and Fuel-Efficient Vehicle	3
2	C		Credit 4.4	Alternative Transportation—Parking Capacity	2
	C		Credit 5.1	Site Development—Protect or Restore Habitat	1
	C		Credit 5.2	Site Development—Maximize Open Space	1
	C		Credit 6.1	Stormwater Design—Quantity Control	1
	C		Credit 6.2	Stormwater Design—Quality Control	1
1	C		Credit 7.1	Heat Island Effect—Non-roof	1
1	E		Credit 7.2	Heat Island Effect—Roof	1
1	E		Credit 8	Light Pollution Reduction	1

**8 Water Efficiency Possible Points: 10**

Y	?	N			
Y			Prereq 1	Water Use Reduction—20% Reduction	
2	C		Credit 1	Water Efficient Landscaping	2 to 4
2	M		Credit 2	Innovative Wastewater Technologies	2
4	M		Credit 3	Water Use Reduction	2 to 4

**30 Energy and Atmosphere Possible Points: 35**

Y	?	N			
Y			Prereq 1	Fundamental Commissioning of Building Energy Systems	
Y			Prereq 2	Minimum Energy Performance	
Y			Prereq 3	Fundamental Refrigerant Management	
19	M		Credit 1	Optimize Energy Performance	1 to 19
2	E		Credit 2	On-Site Renewable Energy	1 to 7
2	C		Credit 3	Enhanced Commissioning	2
2	M		Credit 4	Enhanced Refrigerant Management	2
3	E		Credit 5	Measurement and Verification	3
2	M		Credit 6	Green Power	2

**8 Materials and Resources Possible Points: 14**

Y	?	N			
Y			Prereq 1	Storage and Collection of Recyclables	
	C		Credit 1.1	Building Reuse—Maintain Existing Walls, Floors, and Roof	1 to 3
	C		Credit 1.2	Building Reuse—Maintain 50% of Interior Non-Structural Element	1
2	C		Credit 2	Construction Waste Management	1 to 2
2	C		Credit 3	Materials Reuse	1 to 2

**Materials and Resources, Continued**

Y	?	N			
2	C		Credit 4	Recycled Content	1 to 2
2	C		Credit 5	Regional Materials	1 to 2
	C		Credit 6	Rapidly Renewable Materials	1
	C		Credit 7	Certified Wood	1

**12 Indoor Environmental Quality Possible Points: 15**

Y	?	N			
Y			Prereq 1	Minimum Indoor Air Quality Performance	
Y			Prereq 2	Environmental Tobacco Smoke (ETS) Control	
1	M		Credit 1	Outdoor Air Delivery Monitoring	1
			Credit 2	Increased Ventilation	1
1	C		Credit 3.1	Construction IAQ Management Plan—During Construction	1
1	C		Credit 3.2	Construction IAQ Management Plan—Before Occupancy	1
1			Credit 4.1	Low-Emitting Materials—Adhesives and Sealants	1
1			Credit 4.2	Low-Emitting Materials—Paints and Coatings	1
1			Credit 4.3	Low-Emitting Materials—Flooring Systems	1
1			Credit 4.4	Low-Emitting Materials—Composite Wood and Agrifiber Product	1
1			Credit 5	Indoor Chemical and Pollutant Source Control	1
1	E		Credit 6.1	Controllability of Systems—Lighting	1
1	M		Credit 6.2	Controllability of Systems—Thermal Comfort	1
1	M		Credit 7.1	Thermal Comfort—Design	1
1	M		Credit 7.2	Thermal Comfort—Verification	1
1	E		Credit 8.1	Daylight and Views—Daylight	1
1	E		Credit 8.2	Daylight and Views—Views	1

**6 Innovation and Design Process Possible Points: 6**

Y	?	N			
1	M		Credit 1.1	Innovation in Design: Specific Title	1
1	M		Credit 1.2	Innovation in Design: Specific Title	1
1	M		Credit 1.3	Innovation in Design: Specific Title	1
1	M		Credit 1.4	Innovation in Design: Specific Title	1
1	M		Credit 1.5	Innovation in Design: Specific Title	1
1	C		Credit 2	LEED Accredited Professional	1

**4 Regional Priority Credits Possible Points: 4**

Y	?	N			
1	C		Credit 1.1	Regional Priority: Specific Credit	1
1	C		Credit 1.2	Regional Priority: Specific Credit	1
1	C		Credit 1.3	Regional Priority: Specific Credit	1
1	C		Credit 1.4	Regional Priority: Specific Credit	1

**89 Total Possible Points: 110**

Certified 40 to 49 points Silver 50 to 59 points Gold 60 to 79 points Platinum 80 to 110

## SUSTAINABLE SITES 21/26

## Prerequisite 1: Construction Activity Pollution Prevention

Prevented sedimentation of storm sewers and dust from polluting of the air

Site Selection 1 Point

Site was previously developed land

SS Credit 1: Development Density and Community Connectivity 4 Points

Option 1: Development Density

SS Credit 4.1: Alternative Transportation – Public Transport 6 Points

Option 2: Bus Stop Proximity

SS Credit 4.2: Alternative Transportation – Bicycle Storage 1 Point

Case 1: Commercial Projects

SS Credit 4.3: Alternative Transportation – Low Emitting and 3 Points

Option 1: Provide preferred parking for low-emitting and fuel-efficient vehicles

SS Credit 4.4: Alternative Transportation – Parking Capacity 2 Points

Case 1: Option 1: Preferred/discounted parking for carpools

SS Credit 7.1: Heat Island Effect – Non roof 1 Point

Option 2: Underground parking garage

SS Credit 7.2: Heat Island Effect – Roof 1 Point

Option 1: Solar reluctant roofing material

SS Credit 8: Light Pollution Reduction 1 Point

Option 1: Reduce input power of nonemergency lights

## WATER EFFICIENCY 6/10

## Prerequisite 1: Water Use Reduction

Water demand reduced by 26% (see Appendix G)

WE Credit 1: Water Efficient Landscaping 2 Points

Option 1: Reduce by 50%

WE Credit 2: Innovative Wastewater Technologies 2 Points

Option 1: Water use reduced by 56% (Appendix G and Table 9 in the mechanical report) through rainwater collection and demand reduction

WE Credit 3: Water Use Reduction 4 Points

Water use reduced by 56% (Appendix G and Table 9 in the mechanical report)

## ENERGY &amp; ATMOSPHERE 30/35

## Prerequisite 1: Fundamental Commissioning of Building Energy Systems

Budgeted for a commissioning authority

## Prerequisite 2: Minimum Energy Performance

Option 1: Whole Building Energy Simulation – Used IES to simulate and achieved a savings of 52% (see Table 7 in the mechanical report)

## Prerequisite 3: Fundamental Refrigerant Management

Designed chilled water system

## EA Credit 1: Optimize Energy Performances

Achieved an overall energy use savings of 52% (see Table 7 in the mechanical report)

EA Credit 2: On-Site Renewable Energy 2 Points

Photovoltaic array on the roof produces over 3% of total building energy use

EA Credit 3: Enhanced Commissioning 2 Points

Achieved an overall energy use savings of 52% (see Table 7 in the mechanical report)

EA Credit 4: Enhanced Refrigerant Management 2 Points

Option 1: Did not use refrigerants

EA Credit 5: Measurement and Verification 3 Points

Option 1: Budgeted for a measurement and verification plan

EA Credit 6: Green Power – 35% from renewable sources 2 Points

Option 1: Determine Baseline Electricity Use – We used IES to determine the annual electricity demand of the site

## MATERIALS AND RESOURCES 8/14

## MR Prerequisite 1: Storage and Collection of Recyclables

Provided an area for the collection and storage of materials for recycling of the building.

MR Credit 2: Construction Waste Management 2 Points

Recycled or Salvaged Material by 75%

MR Credit 3: Materials Reuse 2 Points

Reused Materials by 10%

MR Credit 4: Recycled Content 2 Points

Used material with 20% recycled content

MR Credit 5: Regional Materials 2 Points

Used 20% of materials that were produced within 500 miles of the project site

## INDOOR ENVIRONMENTAL QUALITY 4/15

## IEQ Prerequisite 1: Minimum Indoor Air Quality Performance

Met both Case 1 and Case 2 because our building utilizes both natural and mechanical ventilation

## IEQ Prerequisite 2: Environmental Tobacco Smoke (ETS) Control

Option 1: We are prohibiting smoking on the entire property, inside and outside

## IEQ Credit 1: Outdoor Air Delivery Monitoring 1 Point

Case 1 and Case 2: We have provided for CO<sub>2</sub> for all spaces

## IEQ Credit 3.1: Construction IAQ Management Plan – During... 1 Point

Developed and implemented an IAQ Management Plan

## IEQ Credit 3.2: Construction IAQ Management Plan – Before... 1 Point

Option 1: Flush-Out, path 1

## IEQ Credit 4.1: Low Emitting Materials – Adhesives and Sea... 1 Point

All adhesive and sealant complied with the requirements applicable

## IEQ Credit 4.2: Low Emitting Materials – Paints and Coatings 1 Point

Paint and coatings complied with the criteria applicable

## IEQ Credit 4.4: Low Emitting Materials – Composite Wood ... 1 Point

Composite wood had no added urea-formaldehyde

## IEQ Credit 6.1: Controllability of Systems – Lighting 1 Point

90% of the building occupants are able to adjust the lights

## IEQ Credit 6.2: Controllability of Systems - Thermal Comfort 1 Point

Because of our underfloor system, the occupants have control over the vent closest to their desks

## IEQ Credit 7.1: Thermal Comfort – Design 1 Point

Our HVAC system was designed using ASHRAE Standard 55-2004

## IEQ Credit 7.2: Thermal Comfort – Verification 1 Point

We budgeted for a monitoring system

## IEQ Credit 8.1: Daylight and Views - Daylight 1 Point

Option 1: Simulation

## IEQ Credit 8.2: Daylight and Views - Views 1 Point

Achieved a direct line of sight to the outdoor environment via vision glazing

## INNOVATION IN DESIGN 6/6

## ID Credit 1: Innovation in Design

5 Points

Path 1: Innovations in Design – Cogeneration, algae bioreactors



Path 2: Exemplary Performance – two incremental increases in EA Credit 1 (2 pts), three incremental increases in WE Credit 3 (1 pt)

---


**TOTAL**
**89 POINTS**



### APPENDIX F: ROOF SYSTEM: SYSTEM SPACE COORDINATION



APPENDIX G: DOUBLE FAÇADE



- 1 Double Façade System (DFS)
- 2 Daylight Control Retractable Shading
- 3 Daylight Dimming
- 4 Underfloor Ducts and Data Cables
- 5 Structural System
- 6 Return Duct

COLLABORATION:

To ensure that all goals were satisfied, the disciplines had to confirm that all systems worked integrally with each other



- **DFS**

Mechanical:	Energy Savings	<b>Raised Access Floor</b>	Mechanical:	Coordinate with Electrical for Clash
Electrical:	Light Control		Electrical:	Coordinate with Mechanical for Clash
Structural:	Additional Imposed Weight			
- **Retractable Shading**

Mechanical:	Effects Space Loads	<b>Structural System</b>	Mechanical:	Coordinate with Structural for Clash
Electrical:	Effects Surface Lighting Levels		Structural:	Coordinate with all Disciplines for Loads
			Structural:	Coordinated with System Clash
- **Daylight Dimming**

Mechanical:	Effects Space Loads			
Construction:	Additional Sensor Costs			

# DOUBLE FAÇADE DETAIL



Horizontal Section Detail



## APPENDIX H: CLASH DETECTION

### STAGE 1:

Once the structural system and mechanical systems were placed into revit, clash detection was run. The results showed that in several places the mechanical ducts clashed with the raised access floor panel supports. In addition, we found that the return ducts from the elevator lobby were clashing with the beams over the opening into the space. Because the ceiling could not be dropped, the ducts had to be rerouted in an alternate direction. Finally, the main branch ducts were clashing with the columns around the core and had to be moved over a few inches.

**Duct Vs UFD Clash**

Tolerance	0.00m
Total	30
New	30
Active	0
Reviewed	0
Approved	0
Resolved	0
Type	Hard
Status	OK

	<b>Name</b> Clash1
	<b>Distance</b> -0.00m
	<b>Description</b> Hard
	<b>Status</b> New
	<b>Clash Point</b> -3.44m, 1.27m, 0.00m
	<b>Date Created</b> 2014/1/23 22:50:43




  

**Item 1**

<b>GUID</b>	9f5167e5-6fba-40b6-bea1-40df8fab96ce
<b>Item Name</b>	Raised_Floor_System_7475 [325474]
<b>Item Type</b>	Shell

**Item 2**

<b>GUID</b>	b395e624-86a5-41bd-a271-96b60f431494
<b>Item Name</b>	Rectangular Duct [327167]
<b>Item Type</b>	Shell






STAGE 2:

After the mechanical system was fixed, the electrical system was added. While there were no clashes with the electrical system, we did find that there were more mechanical clashes. At some point during the process some of the mechanical ducts were move over by several feet into the center of a beam. This is an error that was to be expected at some point because there were several systems being added by several different people. Clash detection allowed us to catch and fix the problem with relative ease.

**Mech Vs Structure Clash**

Tolerance	0.00m
Total	11
New	11
Active	0
Reviewed	0
Approved	0
Resolved	0
Type	Hard
Status	Old

	Name	Clash1
	Distance	-0.25m
	Description	Hard
	Status	New
	Clash Point	9.22m, 0.00085m, -0.93m
	Date Created	2014/1/24 18:34:19

**Item 1**

GUID	7f346662-caf6-4fa9-83c6-220a1d79a833
Item Name	Rectangular Duct [336492]
Item Type	Shell



  

**Item 2**

GUID	ce3fabcd-06a6-4f00-81e7-9270e8e9c7e8
Item Name	W-Wide Flange [187349]
Item Type	Shell

STAGE 3:


After the duct and beam clash was fixed, we ran a final clash detection to ensure that there were no clashes.




## APPENDIX I: DUCT SIZING

		Room Airflow (CFM)	Duct Airflow (CFM)	Duct Length (ft)	Friction Loss	Duct Velocity	Duct Size
<b>Duct A</b>							
500	Perimeter Open Office	1,407.9	1407.9	140.0	0.28	1300	13x12
<b>Duct B</b>							
508	Private Office	167.9					
509	Private Office	165.5					
510	Private Office	166.8	1,398.2	70.0	0.15	1300	13x12
511	Executive Office	336.6					
512	Copy Room	188.5					
513	Private Office	186.4					
514	Server Room	186.5					
<b>Duct C</b>							
500	Perimeter Open Office	1,407.9	1,407.9	140.0	0.3	1300	13x12
<b>Duct D</b>							
519	Private Office	262.8					
520	Private Office	257.4					
521	Private Office	246.7	1,728.5	70.0	0.15	1300	13x12
515	Copy Room	186.5					
516	Private Office	186.0					
517	Private Office	189.1					
518	Executive Office	400.0					
<b>Duct E</b>							
500	Open Office	500.0					
501	Elevator Lobby	1,294.6	2,005.7	65.0	0.11	1300	17x12
501A	Telecom	52.6					
501B	Electrical	50.4					
504	Stair 2	108.1					
<b>Duct F</b>							
500	Open Office	500.0					
502	Stair 1	94.5					
502A	Stair 1 Vestibule	82.7	1,302.5	110	0.25	1300	11x12
503	Service Lobby	31.7					
522	Conference	296.7					
523	Conference	296.9					

The duct sizing was vital to clash detection and integration. The supply ducts could not be any taller than 13 inches because the raised access flooring is only 14 inches off of the slab. Therefore, the ducts needed to be wider in many cases, but still had to fit within the 24 inches between panels.

*APPENDIX J: LATERAL SYSTEM DESIGN*

Shown left is the preliminary design of the lateral system of the building. The core, composed of a steel plate shear wall and braced frames, can be seen in the core in the center of the building.



Shown left is the final design of the lateral system of the building. The core composed of two different configurations of braced frames can be seen in the core in the center of the building.
















## Lighting Controls




Open office area split into seven zones, which dim independently depending on the quantity and distribution of daylight entering the office.


## Prefabricated Pods



## Lateral System




## Double Façade System



## Raised Access Floor



- ① Raised Access Floor (RAF)
- ② Data Cable Tray
- ③ Supply Air Duct
- ④ Seismic Bracing
- ⑤ Supply Diffuser



No.	Description	Date

**AEI Team Number**  
**05-2014**

**Office**  
**Engineering Systems**























