

TBD ENGINEERING | PROJECT DECISION MATRIX


Project Decision Matrix												
Option	Notes/ Justification	1	2	3	4	5	6	7	8	9	10	Decision
Mechanical Systems												
FCU w/DOAS	Save energy by recirculation	5	4	3	4	1	4	5	3	3	4	
Valance Clg & Htg w/ DOAS	Eliminates Fan Power assoc. w/ Clg & Htg	4	4	3	4	4	5	4	3	3	4	
WSHP w/ DOAS	Heat Rejection to Water Loop	4	4	3	4	5	3	4	3	3	5	Heat rejection to aquaponic system if present
Ground Source Heat Pump	Heat Rejection to Ground	4	3	3	4	5	3	3	2	3	4	
Electrical Distribution Options												
DC	renewable energy driven	2	4	3	3	5	3	5	2	3	5	
AC	standard from grid	4	5	3	3	3	3	5	3	3	3	X
Generator Location Options												
Generator Outside		5	2	3	3	5	5	2	5	3	3	Invasive to site, prototypability affected
Generator Basement	added areaway for maintenance, out of public eye	2	5	3	3	3	2	2	2	3	3	X
Generator Roof		4	4	3	3	1	4	2	1	3	3	Invasive to growing spaces, fuel storage must be pumped vertically
Grow Light Options												
LED	more specific wavelengths generated	5	4	3	5	5	3	4	4	3	4	X
HID		3	3	3	3	5	3	3	1	3	3	more power required, more maintenance
Support Space Lighting Options												
LED		5	3	3	5	4	3	4	5	3	4	X
FLUORESCENT		3	3	3	3	1	4	4	3	3	3	more power required, more maintenance
Gravity System												
Steel Noncomposite		4	2	3	3	3	3	3	2	5	2	
Steel Composite		4	2	2	3	3	4	3	3	5	2	X
Steel Castellated Beams		4	3	3	3	4	5	3	5	4	4	Manufacturing different
Timber Framing		2	2	5	3	4	2	1	2	2	4	Slightly specialized market
Concrete Two2way slab		2	4	4	3	3	3	3	3	5	2	
Concrete pre-cast double tee		4	2	4	3	3	4	4	2	2	4	Slightly specialized market
Concrete Post tension		3	3	3	3	3	5	4	4	3	2	
Concrete Bubble deck		2	4	5	3	4	4	3	2	1	5	Extremely specialized market
Acetylated wood		2	2	5	3	4	3	5	3	4	5	
Foundation System												
Mat Foundation		4	3	3	3	3	2	4	3	5	3	
Spread/Strip Footing		4	4	3	3	3	5	4	4	5	3	X
Beam (Grillage)		2	3	3	3	3	2	2	3	4	3	
Deep Foundations		2	2	3	3	3	2	3	2	2	4	Expensive, invasive, slow
Slurry Wall		2	2	3	3	3	3	3	2	2	4	Expensive, invasive, slow
Geopiers		4	4	4	3	4	5	4	4	2	5	X
Lateral Systems												
Steel Moment Frame	Requires Steel Gravity System	5	5	3	3	3	2	3	5	4	3	X
Steel Braced Frame		2	4	3	3	3	3	3	3	4	3	
Masonry Shear Walls		2	2	4	3	3	3	4	1	4	3	
Concrete Moment Frame	Requires Concrete Gravity System	5	5	4	3	3	4	4	4	4	3	
Concrete Shear Wall		2	3	4	3	3	4	4	2	4	3	
Green House Structural System												
Wood		2	2	4	3	4	5	1	2	5	4	
Steel		5	4	4	3	3	5	4	4	5	3	
Non-toxic Treated Wood		4	2	5	3	4	4	5	3	4	5	X
Façade Systems												
Precast Panel		3	1	2	3	4	4	4	3	3	2	
Brick Cavity Wall		2	2	2	3	3	3	4	3	3	2	Efflorescence, moisture, weight, slow
Rain Screen		5	5	3	5	5	3	4	5	2	4	Terra Cotta shipping location
Renewable Energy On Site												
Solar Power		3	5	5	5	4	5	3	2	-	3	Milwaukee building blocking some sunlight
Wind Power		2	5	5	5	4	5	3	2	-	3	Invasive to Milwaukee site
Anaerobic Digestion	Use food waste for primary fuel for CHP	2	4	3	3	5	4	2	3	3	4	X
Rainwater Collection	Effectiveness for GH and Rest of Building	4	3	3	3	5	4	4	3	3	4	X

In order to consider a wide variety of options for the Growing Power facility, TBD developed and implemented a project decision matrix, shown left. Each design partner developed a list of options for various systems, listed in the leftmost column of the matrix. Each option was evaluated against the project goals (shown below) in each row, on a scale of 1-4. Project specific goals that fit into the 4 overarching goals of flexibility, community, economy, and sustainability are color coded as such.

Project Goals	
1	Flexibility/ Adaptability to account for multiple space types/ locations
2	Prototypability of building/ ability to replicate in other locations
3	Recyclability of materials
4	Energy Saving Potential
5	Educational value
6	Economic use of materials
7	Maintainability of system for life span
8	Consideration of other systems (depth, size, etc.)
9	Specialized Market
10	Innovation



TBD ENGINEERING | DESIGN SCHEDULE




Throughout the design phases, TBD set milestones during detailed in the process map to the left. The process map into horizontal swimlanes according to the developed design packages contained in the Growing Power facility.

Tasks described in the process map are filled with a color to indicate the responsible partner; orange indicates management tasks, blue indicates mechanical tasks, yellow indicates electrical tasks, red indicates structural tasks, and purple indicates tasks that require input from all disciplines. Tasks can be seen displayed chronologically from left to right, in order of expected completion, to maintain a continuous, efficient workflow.


The process map was developed in parallel with TBD's collaborative planning sessions, as a way to visually represent the flow of the project's development. The map was continuously updated with each planning session, and displayed in the team's co-located office space to guide the team.

TBD ENGINEERING | COST TRENDING ANALYSIS

Milestone	Growing Spaces	Admin and Learning	Market and Service	Gathering Space	Back of House	Miscellaneous	G-Sitework	Renewable Allowance	Contingency	TV Low	TV	"OH SHIT"
Ideation (Rev0)	\$ 2,850,710.36	\$ 2,267,737.50	\$ 1,573,687.24	\$ 1,479,187.50	\$ 2,685,900.00	\$ 2,947,612.50	\$ 1,380,483.51	\$ 2,760,967.02	\$ 4,141,450.53	\$ -	\$ 10,185,185.19	\$ 11,000,000.00
Ideation (Rev1)	\$ 2,280,568.29	\$ 1,814,190.00	\$ 1,258,949.79	\$ 1,183,350.00	\$ 2,148,720.00	\$ 2,358,090.00	\$ 1,104,386.61	\$ 2,208,773.62	\$ 3,313,160.42	\$ -	\$ 10,185,185.19	\$ 11,000,000.00
Schematic (Rev2)	\$ 2,774,618.12	\$ 2,558,870.72	\$ 967,171.22	\$ 1,669,086.30	\$ 1,607,761.83	\$ 1,764,421.19	\$ 1,134,192.94	\$ 2,268,385.88	\$ 2,835,482.34	\$ -	\$ 10,185,185.19	\$ 11,000,000.00
Schematic (Rev3)	\$ 2,219,694.49	\$ 2,047,096.58	\$ 773,736.98	\$ 1,335,269.04	\$ 1,286,209.47	\$ 1,411,536.95	\$ 907,354.35	\$ 1,814,708.70	\$ 2,268,385.88	\$ -	\$ 10,185,185.19	\$ 11,000,000.00
STR Development	\$ 2,344,743.11	\$ 1,990,445.63	\$ 862,689.26	\$ 1,298,317.06	\$ 1,274,078.33	\$ 1,398,223.77	\$ 916,849.72	\$ 1,833,699.43	\$ 1,833,699.43	\$ -	\$ 10,185,185.19	\$ 11,000,000.00
ENC Development	\$ 2,527,497.21	\$ 1,916,099.93	\$ 895,190.54	\$ 1,249,823.26	\$ 1,392,363.17	\$ 1,528,034.21	\$ 950,900.83	\$ 1,901,801.67	\$ 1,901,801.67	\$ -	\$ 10,185,185.19	\$ 11,000,000.00
GRW Development	\$ 2,527,497.21	\$ 1,916,099.93	\$ 895,190.54	\$ 1,249,823.26	\$ 1,392,363.17	\$ 1,528,034.21	\$ 950,900.83	\$ 1,901,801.67	\$ 1,426,351.25	\$ -	\$ 10,369,532.43	\$ 11,000,000.00
BOH Development	\$ 2,314,127.57	\$ 1,916,099.93	\$ 895,190.54	\$ 1,249,823.26	\$ 1,515,925.25	\$ 1,528,034.21	\$ 941,920.08	\$ 1,517,000.00	\$ 1,412,880.11	\$ -	\$ 10,369,532.43	\$ 11,000,000.00
ADM Development	\$ 2,314,127.57	\$ 1,777,489.02	\$ 895,190.54	\$ 1,249,823.26	\$ 1,515,925.25	\$ 1,528,034.21	\$ 928,058.99	\$ 1,017,000.00	\$ 928,058.99	\$ -	\$ 10,369,532.43	\$ 11,000,000.00
GTH Development	\$ 2,314,127.57	\$ 1,777,489.02	\$ 895,190.54	\$ 1,249,823.26	\$ 1,515,925.25	\$ 1,528,034.21	\$ 919,017.75	\$ 1,017,000.00	\$ 919,017.75	\$ -	\$ 10,369,532.43	\$ 11,000,000.00
MKT Development	\$ 2,314,127.57	\$ 1,777,489.02	\$ 929,549.50	\$ 1,159,410.88	\$ 1,515,925.25	\$ 1,528,034.21	\$ 922,453.64	\$ 1,017,000.00	\$ 691,840.23	\$ -	\$ 10,369,532.43	\$ 11,000,000.00




Milestone	A-Sub	B10-Super	B20-Enc	B30-Roof	C-Int	D10-Conv	D20-Plumb	D30-HVAC	D40-FP	D50-Elec	E-Equip	F-Special	G-Sitework	Renewables	Contingency
Ideation (Rev0)	\$ 1,426,785.68	\$ 1,623,176.63	\$ 1,746,423.53	\$ 504,338.10	\$ 2,146,776.19	\$ 486,055.50	\$ 826,798.61	\$ 1,393,387.54	\$ 636,243.83	\$ 2,492,143.24	\$ 190,329.04	\$ 332,377.24	\$ 1,380,483.51	\$ 2,760,967.02	\$ 4,141,450.53
Ideation (Rev1)	\$ 1,141,428.54	\$ 1,298,541.30	\$ 1,397,138.82	\$ 403,470.48	\$ 1,717,420.95	\$ 388,844.40	\$ 661,438.89	\$ 1,114,710.03	\$ 508,995.06	\$ 1,993,714.59	\$ 152,263.23	\$ 265,901.79	\$ 1,104,386.81	\$ 2,208,773.62	\$ 3,313,160.42
Schematic (Rev2)	\$ 935,318.04	\$ 1,396,450.90	\$ 1,464,346.71	\$ 332,387.89	\$ 1,927,299.51	\$ 538,739.76	\$ 708,072.52	\$ 1,248,630.32	\$ 464,046.02	\$ 2,012,656.89	\$ 115,022.03	\$ 198,958.80	\$ 1,134,192.94	\$ 2,268,385.88	\$ 2,835,482.34
Schematic (Rev3)	\$ 748,254.43	\$ 1,117,160.72	\$ 1,171,477.37	\$ 265,910.31	\$ 1,541,839.60	\$ 430,991.81	\$ 566,458.02	\$ 998,904.26	\$ 371,236.82	\$ 1,610,125.51	\$ 92,017.62	\$ 159,167.04	\$ 907,354.35	\$ 1,814,708.70	\$ 2,268,385.88
STR Development	\$ 770,370.25	\$ 1,189,998.55	\$ 1,171,477.37	\$ 265,910.31	\$ 1,541,839.60	\$ 430,991.81	\$ 566,458.02	\$ 998,904.26	\$ 371,236.82	\$ 1,610,125.51	\$ 92,017.62	\$ 159,167.04	\$ 916,849.72	\$ 1,833,699.43	\$ 1,833,699.43
ENC Development	\$ 770,370.25	\$ 1,189,998.55	\$ 1,195,257.05	\$ 582,641.80	\$ 1,541,839.60	\$ 430,991.81	\$ 566,458.02	\$ 998,904.26	\$ 371,236.82	\$ 1,610,125.51	\$ 92,017.62	\$ 159,167.04	\$ 950,900.83	\$ 1,901,801.67	\$ 1,901,801.67
GRW Development	\$ 770,370.25	\$ 1,189,998.55	\$ 1,195,257.05	\$ 582,641.80	\$ 1,541,839.60	\$ 430,991.81	\$ 566,458.02	\$ 998,904.26	\$ 371,236.82	\$ 1,610,125.51	\$ 92,017.62	\$ 159,167.04	\$ 950,900.83	\$ 1,901,801.67	\$ 1,426,351.25
BOH Development	\$ 770,370.25	\$ 1,189,998.55	\$ 1,195,257.05	\$ 582,641.80	\$ 1,541,839.60	\$ 430,991.81	\$ 566,458.02	\$ 909,096.70	\$ 371,236.82	\$ 1,610,125.51	\$ 92,017.62	\$ 159,167.04	\$ 941,920.08	\$ 1,517,000.00	\$ 1,412,880.11
ADM Development	\$ 770,370.25	\$ 1,189,998.55	\$ 1,195,257.05	\$ 582,641.80	\$ 1,541,839.60	\$ 430,991.81	\$ 566,458.02	\$ 770,485.78	\$ 371,236.82	\$ 1,610,125.51	\$ 92,017.62	\$ 159,167.04	\$ 928,058.99	\$ 1,017,000.00	\$ 928,058.99
GTH Development	\$ 770,370.25	\$ 1,189,998.55	\$ 1,195,257.05	\$ 582,641.80	\$ 1,541,839.60	\$ 430,991.81	\$ 566,458.02	\$ 680,073.41	\$ 371,236.82	\$ 1,610,125.51	\$ 92,017.62	\$ 159,167.04	\$ 919,017.75	\$ 1,017,000.00	\$ 919,017.75
MKT Development	\$ 770,370.25	\$ 1,189,998.55	\$ 1,195,257.05	\$ 582,641.80	\$ 1,541,839.60	\$ 430,991.81	\$ 566,458.02	\$ 714,432.36	\$ 371,236.82	\$ 1,610,125.51	\$ 92,017.62	\$ 159,167.04	\$ 922,453.64	\$ 1,017,000.00	\$ 691,840.23




In order to continually evaluate project costs against their targets, an in-depth analysis was devised. The overall project tracked designed costs by Integrated Design Packages and by Unifomat II divisions, shown to the left. The 6 IDPs were broken down further by Unifomat II divisions, with examples shown below. The multi-layer approach allowed TBD to quickly identify alarming trends through the course of the project's development and utilize cost as an informant to design, rather than a "design now, estimate later" approach which, more often than not, results in cost cutting techniques rather than truly engineering value as defined by the ownership partners at Growing Power.

At the end of the project's development, the project estimate stood at a value of \$11.9 million, including a \$1 million allowance for a Combined Heat and Power plant in the Back of House area, and rainwater and groundwater harvesting systems.


Milestone	A-Sub	B10-Super	B20-Enc	B30-Roof	C-Int	D10-Conv	D20-Plumb	D30-HVAC	D40-FP	D50-Elec	E-Equip	F-Special	G2-Demolition	TV Low	TV	"OH SHIT"
Ideation (Rev0)	\$ 99,675.19	\$ 259,155.49	\$ 185,111.06	\$ 51,261.53	\$ 791,705.78	\$ 62,652.98	\$ 418,635.79	\$ 412,940.06	\$ 65,000.84	\$ 501,223.80	\$ 2,887.86	\$ -	\$ -	\$ -	\$ -	\$ -
Ideation (Rev1)	\$ 79,746.15	\$ 207,824.39	\$ 148,088.85	\$ 41,009.22	\$ 633,364.62	\$ 50,122.38	\$ 334,908.63	\$ 330,352.05	\$ 52,400.67	\$ 400,979.04	\$ 2,278.29	\$ -	\$ -	\$ -	\$ -	\$ -
Schematic (Rev2)	\$ 97,014.62	\$ 252,380.01	\$ 180,170.01	\$ 49,891.23	\$ 770,573.26	\$ 60,980.62	\$ 407,463.40	\$ 401,917.21	\$ 63,752.46	\$ 487,844.94	\$ 2,273.85	\$ -	\$ -	\$ -	\$ -	\$ -
Schematic (Rev3)	\$ 72,611.70	\$ 201,970.41	\$ 144,116.01	\$ 39,914.59	\$ 616,458.61	\$ 48,784.49	\$ 325,969.12	\$ 325,534.17	\$ 51,001.97	\$ 390,275.95	\$ 2,217.48	\$ -	\$ -	\$ -	\$ -	\$ -
STR Development	\$ 158,937.85	\$ 245,512.87	\$ 245,512.87	\$ 120,206.92	\$ 616,458.61	\$ 48,784.49	\$ 325,969.12	\$ 325,534.17	\$ 51,001.97	\$ 390,275.95	\$ 2,217.48	\$ -	\$ -	\$ -	\$ -	\$ -
ENC Development	\$ 158,937.85	\$ 245,512.87	\$ 245,512.87	\$ 120,206.92	\$ 616,458.61	\$ 48,784.49	\$ 325,969.12	\$ 325,534.17	\$ 51,001.97	\$ 390,275.95	\$ 2,217.48	\$ -	\$ -	\$ -	\$ -	\$ -
GRW Development	\$ 158,937.85	\$ 245,512.87	\$ 245,512.87	\$ 120,206.92	\$ 616,458.61	\$ 48,784.49	\$ 325,969.12	\$ 325,534.17	\$ 51,001.97	\$ 390,275.95	\$ 2,217.48	\$ -	\$ -	\$ -	\$ -	\$ -
BOH Development	\$ 158,937.85	\$ 245,512.87	\$ 245,512.87	\$ 120,206.92	\$ 616,458.61	\$ 48,784.49	\$ 325,969.12	\$ 325,534.17	\$ 51,001.97	\$ 390,275.95	\$ 2,217.48	\$ -	\$ -	\$ -	\$ -	\$ -
ADM Development	\$ 158,937.85	\$ 245,512.87	\$ 245,512.87	\$ 120,206.92	\$ 616,458.61	\$ 48,784.49	\$ 325,969.12	\$ 325,534.17	\$ 51,001.97	\$ 390,275.95	\$ 2,217.48	\$ -	\$ -	\$ -	\$ -	\$ -
GTH Development	\$ 158,937.85	\$ 245,512.87	\$ 245,512.87	\$ 120,206.92	\$ 616,458.61	\$ 48,784.49	\$ 325,969.12	\$ 325,534.17	\$ 51,001.97	\$ 390,275.95	\$ 2,217.48	\$ -	\$ -	\$ -	\$ -	\$ -
MKT Development	\$ 158,937.85	\$ 245,512.87	\$ 245,512.87	\$ 120,206.92	\$ 616,458.61	\$ 48,784.49	\$ 325,969.12	\$ 325,534.17	\$ 51,001.97	\$ 390,275.95	\$ 2,217.48	\$ -	\$ -	\$ -	\$ -	\$ -



Milestone	A-Sub	B10-Super	B20-Enc	B30-Roof	C-Int	D10-Conv	D20-Plumb	D30-HVAC	D40-FP	D50-Elec	E-Equip	F-Special	G2-Demolition	TV Low	TV	"OH SHIT"
Ideation (Rev0)	\$ 47,622.49	\$ 371,008.95	\$ 394,563.31	\$ 113,338.69	\$ 980,050.85	\$ 256,250.34	\$ 83,496.65	\$ 294,865.88	\$ 65,264.39	\$ 373,208.95	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Ideation (Rev1)	\$ 38,097.99	\$ 297,527.16	\$ 315,699.06	\$ 9,070.95	\$ 312,040.68	\$ 205,003.47	\$ 50,297.32	\$ 235,844.70	\$ 22,811.51	\$ 292,527.16	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Schematic (Rev2)	\$ 53,736.29	\$ 419,654.80	\$ 445,243.51	\$ 12,794.35	\$ 440,125.76	\$ 280,152.39	\$ 71,648.38	\$ 332,653.19	\$ 74,207.25	\$ 419,654.80	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Schematic (Rev3)	\$ 42,989.03	\$ 335,723.84	\$ 356,194.80	\$ 10,235.48	\$ 352,100.61	\$ 231,321.91	\$ 57,318.70	\$ 266,122.55	\$ 59,365.80	\$ 335,723.84	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
STR Development	\$ 126,563.35	\$ 195,500.57	\$ 196,364.47	\$ 95,720.12	\$ 352,100.61	\$ 231,321.91	\$ 57,318.70	\$ 266,122.55	\$ 59,365.80	\$ 335,723.84	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
ENC Development	\$ 126,563.35	\$ 195,500.57	\$ 196,364.47	\$ 95,720.12	\$ 352,100.61	\$ 231,321.91	\$ 57,318.70	\$ 266,122.55	\$ 59,365.80	\$ 335,723.84	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
GRW Development	\$ 126,563.35	\$ 195,500.57	\$ 196,364.47	\$ 95,720.12	\$ 352,100.61	\$ 231,321.91	\$ 57,318.70	\$ 266,122.55	\$ 59,365.80	\$ 335,723.84	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
BOH Development	\$ 126,563.35	\$ 195,500.57	\$ 196,364.47	\$ 95,720.12	\$ 352,100.61	\$ 231,321.91	\$ 57,318.70	\$ 266,122.55	\$ 59,365.80	\$ 335,723.84	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
ADM Development	\$ 126,563.35	\$ 195,500.57	\$ 196,364.47	\$ 95,720.12	\$ 352,100.61	\$ 231,321.91	\$ 57,318.70	\$ 127,511.64	\$ 59,365.80	\$ 335,723.84	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
GTH Development	\$ 126,563.35	\$ 195,500.57	\$ 196,364.47	\$ 95,720.12	\$ 352,100.61	\$ 231,321.91	\$ 57,318.70	\$ 127,511.64	\$ 59,365.80	\$ 335,723.84	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
MKT Development	\$ 126,563.35	\$ 195,500.57	\$ 196,364.47	\$ 95,720.12	\$ 352,100.61	\$ 231,321.91	\$ 57,318.70	\$ 127,511.64	\$ 59,365.80	\$ 335,723.84	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -



TBD ENGINEERING | BASEMENT FLOOR PLAN



Mechanical Room Expansion


Freezer and Cooler Storage

Community Elevator and MEP Shaft Added



Top: Basement Floor Plan as provided to the team
Bottom: Modified Basement Floor Plan by TBD

TBD ENGINEERING | LEVEL 1 FLOOR PLAN




Wall Addition for Food Processing Separation

Redefined Freezer and Cooler Storage

Community Stairwell Addition


Community Elevator and MEP Shaft Added




Top: Level 1 Floor Plan as provided to the team

Bottom: Modified Level 1 Floor Plan by TBD

TBD ENGINEERING | LEVEL 2 FLOOR PLAN



Auziliary Mechanical and Electrical Space Added




Community Stairwell Addition


Community Elevator and MEP Shaft Added

Top: Level 2 Floor Plan as provided to the team
Bottom: Modified Level 2 Floor Plan by TBD

TBD ENGINEERING | LEVEL 3 FLOOR PLAN



IT Room Added




Community Stairwell Addition

Community Elevator and MEP Shaft Added

Top: Level 3 Floor Plan as provided to the team
Bottom: Modified Level 3 Floor Plan by TBD


TBD ENGINEERING | LEVEL 4 FLOOR PLAN



Auziliary Mechanical and Electrical Space Added


Community Elevator and MEP Shaft Added

Added Collaboration Space




Top: Level 4 Floor Plan as provided to the team
Bottom: Modified Level 4 Floor Plan by TBD

TBD ENGINEERING | LEVEL 5 FLOOR PLAN



Mechanical Equipment
Roof Space



Top: Level 5 Floor Plan as provided to the team
Bottom: Modified Level 5 Floor Plan by TBD