

GROWING POWER VERTICAL FARMING FACILITY



TOTAL BUILDING DESIGN ENGINEERING

Architectural Engineering Institute, Annual Student Competition
Registration Number: 04-2015



EXECUTIVE SUMMARY

Growing Power's recent success and growth of their nonprofit organization has created a need of a new vertical farming facility to enhance their mission of providing equal access to healthy, high-quality, safe and affordable food for people in all communities. The facility will provide space to demonstrate innovative farming techniques, an area to host large lectures, office space, and a market to sell food grown on site. In order for the Growing Power facility to be successful, the project goals defined as flexibility, community, sustainability, and economy, must be achieved through an integrated design approach, prioritizing efficiency, mutual trust and respect between partners, and an openness to collaboration. Total Building Design approached and completed the design of the vertical farm with an integrated process embraced by all team members, which resulted in a quality facility for Growing Power.

INFORMATION EXCHANGE

Integration was empowered through an efficient and effective method of information exchange, intricately mapped through team collaborative planning sessions with the aid of the Last Planner System®. TBD utilized a co-located space and various methods of digital communication, including virtual information exchange between different design partners' modeling software, to create and maintain a valuable flow of information.

DECISION MAKING PROCESS

To ensure all major design decisions benefited the Growing Power organization and their goals, as well as confirm that the most advantageous decisions were made, a decision matrix was created to analyze the value added to the project by design solutions. Continuous cost tracking throughout the design phases enabled cost to influence decisions across all design partners' scopes, and target values to be shifted from one Unitformat II section into another.

INTEGRATED DESIGN PACKAGES

To create an environment of simultaneous discipline design focus, 5 design packages were identified, grouping spaces of similar intended use together. The 5 distinct packages were created with synchronized design by all parties, enabling real time coordination, integration, with clash resolution and system integration input from all team members concurrently.

BUILDING INFORMATION MODELING

Support for an integrated design process was provided by Building Information Modeling (BIM) tools and processes. The TBD design partners engaged in BIM Project Execution Planning to take full advantage of the potential added value by identifying BIM goals and clearly explaining the processes required to achieve those goals and the information exchanges associated with them.

INTEGRATION POINTS

The facility developed through an integrated approach took determination, input, and creative problem solving from all team members, specifically with development of the rainscreen façade system, the unique greenhouse design and analysis, and the redesign of the gathering space without the visual interruption of unnecessary columns. Through facilitated, integrated design management and coordination, and value driven effort, a cost effective facility aligned with Growing Power's current goals and the potential for organizational growth, was produced to be turned over to the ownership partners at Growing Power.

TABLE OF CONTENTS

Executive Summary	i
Table of Contents	ii
Project Introduction	1
Project Goals	1
An Integrated Team Environment.....	2
Information Exchange.....	2
Collaborative Planning.....	2
Co-location.....	4
Face to Face Communication.....	5
Digital Communication.....	5
Decision Making Process.....	5
Integrated Design Packages	6
Building Information Modeling.....	7
BIM Execution Planning.....	7
Design Integration.....	8
Building Context.....	9
Building Enclosure Design	10
Rainscreen Backup System.....	10
Moisture Protection and Insulation for any Climate	10
Architectural Context.....	11
Growing Spaces	12
Original Design.....	12
A More Efficient Growing Space	12
A Flexible Floor Layout.....	13
Efficiency Through an Integrated Approach.....	13
Gathering Space	14
Original Design.....	14
TBD Improvements and Challenges	14
Efficiency Through an Integrated Approach.....	15
References.....	SD I
Last Planner System®.....	SD II
Integrated Design Packages	SD III
Planning the Implementation of BIM	SD IV

Defining BIM Information Exchanges SD|V

Coordination SD|VI

Rainscreen Façade and GlazingSD|VII

Lower Greenhouse Design..... SD|VIII

Top Greenhouse Redesign SD|IX

Raised Grate Floor SD|X

Aquaponics SD|XI

Gathering Space Design Coordination.....SDX|II

Project Decision Matrix D1

Design Schedule..... D2

Cost Trending Analysis..... D3

Basement Floor Plan D4

Level 1 Floor Plan..... D5

Level 2 Floor Plan..... D6

Level 3 Floor Plan..... D7

Level 4 Floor Plan..... D8

Level 5 Floor Plan..... D9

PROJECT INTRODUCTION

Growing Power Inc., a national nonprofit organization, was established in 1993 to support surrounding communities and the environment they live in by providing affordable, quality food, grown and distributed with sustainable methods. They aim to better their communities through the education of sustainable farming techniques with hands on experience, technical aid, and live demonstration. Growing Power has found great success in hosting a number of projects to grow food, grow minds, and to grow community. This success has led to a need of a new, sustainable facility to enable Growing Power to influence more communities while promoting sustainable farming techniques.

The new 52,585 square foot Growing Power facility is to be constructed on a plot of land the nonprofit currently owns at 5500 West Silver Springs Drive Milwaukee, Wisconsin. The prominent vertical farming facility embraces four custom designed greenhouses equipped with flexible MEP systems for demonstrations of farming techniques and the allotment of different growing methods; an open floor gathering space for presentations and lectures taking advantage of noteworthy structural feats with an integrated MEP design; and a sustainable, innovative cogeneration heat and power plant providing clean and affordable energy, all wrapped in a façade that provides Growing Power the flexibility of placing the facility in any community, in any climate.

PROJECT GOALS

To produce a project valuable to the owner, TBD project goals were developed to align with Growing Power's vision of inspiring communities to build sustainable food systems that are equitable and ecologically sound; creating a just world, one food secure community a time. Incorporating those values with TBD's own project initiatives, four goals were created and prioritized to be carried through the entirety of the design and construction phases of the project: flexibility, community, sustainability, and economy. Prioritizing these goals ensures the development of a project that meets the needs and expectation of the owner. The project goals have been defined as:

PROJECT INITIATIVES

Flexibility



The ability for the facility to be used as a prototype for other possible sites across the country, while meeting the changing needs of Growing Power by providing options for continuous improvement.

Community



Strengthen the community outreach by providing ample space for education and enabling the surrounding population to participate in the growing methods used within the vertical farm.

Sustainability



Create a facility with a manageable lifecycle cost aided by the use and optimization of renewable energy, renewable resources, and sustainable practices in design and construction.

Economy



Provide the best product for the budget developed by Growing Power while continuously providing cost savings and exploring funding expansion.



AN INTEGRATED TEAM ENVIRONMENT

A highly integrated project team environment is widely viewed as a solution to many of the issues prevalent in the Architecture, Engineering, and Construction (AEC) industry. Although TBD has recommended a Design-Build (DB) approach to delivering the Growing Power facility (CM|2), the philosophy of Integrated Project Delivery and its core principles can be applied to any project to improve the process and the product. An integrated team environment was essential in order to support the project goals on a facility as complicated as that being pursued by TBD and Growing Power. TBD defined a number of key factors that would enable the philosophy of IPD to thrive in the team setting, driving a more efficient process and delivering more value to Growing Power.⁽⁵⁾

Mutual trust and respect, an openness to collaboration, and a sense of security without judgment were identified as essential contributors to a successful team and the delivery of a successful project. By




Figure 1. TBD integrated, flat team organization

establishing TBD early in the planning and design process as one team comprised of equals (fig. 1), a culture defined by a lack of judgment input was maintained through the course of the project's development. This culture provided the potential to contribute greatly to the success of the team, as evidenced through examples such as TBD's initial planning stage,

dubbed Ideation (p. 2).

Numerous tools were employed to support the team's efforts to function and communicate as a highly integrated entity, such as the implementation of a modified version of the Last Planner System® (LPS), a map of the overall project process, team co-location, the development of Integrated Design Packages, and a goal-oriented decision making process. Driven by a team of management partners who brought useful industry experience in the field of project integration, the combination of these techniques was designed to eliminate waste from the design process by facilitating and maintaining effective communication among TBD team members. The integrated process ensured that the end product was a sustainable, economic prototype that will enable Growing Power to connect with and educate the surrounding community for years to come.

INFORMATION EXCHANGE

The development of a free and open flow of communication is extremely important to any integrated team such as TBD's. Communication is a major cause of conflicts among project teams throughout the industry, and TBD engaged in multiple tactics to combat this potential challenge. In addition to supporting team integration, both the Last Planner System® (SD|II) and team co-location proved to be immense assets in aiding effective communication between partners. While face to face communication was strongly preferred, TBD also planned for the inevitable situation where all partners were not able to attend project meetings by defining alternative, digital communication techniques.

COLLABORATIVE PLANNING

The Last Planner System® was identified in the preliminary planning phase of the project as a tool that would support TBD's integration efforts by allowing the team to develop a project plan in a collaborative

manner. LPS was founded on the “Plan, Do, Check, Act cycle,” and is designed to facilitate communication among team members much more effectively than a more traditional, deadline-oriented scheduling strategy. The Last Planner System® is comprised partly of a master scheduling phase, followed by implementation of the pull planning technique. The practice of involving the entire team in collaborative planning sessions proved vital to the project’s development, as it generated an attitude among team members of adding value to the project to support Growing Power, and created a more intimate connection between team members and the project plan.

PROJECT PHASING

The planning and design phases of the project were broken into four main categories: Ideation, Scheming, Development, and Iteration (fig. 2). The division of the design process allowed for the team to clearly define milestones, enabling predictable and trackable design progress. Ideation kicked off the project with numerous brainstorming sessions. The opportunity to create without limit, based on the business model of IDEO and Walt Disney Imagineering’s “Blue Sky” principle ⁽¹³⁾, produced innovative ideas like installing waterwheels in a rainwater collection system to produce electricity, or implementing a heat and power cogeneration plant in the basement of the facility. During the Scheming phase, these ideas were refined by evaluating them against the project goals, as well as investigating feasibility as interpreted by the TBD partners, and the impact implementation would have on other ideas. The theoretical processes were defined further in Development by detailing the idea in the building and analyzing its effect on the total building assembly and its influence towards the project goals. The bulk of the design process was encompassed in the tasks completed in the Development phase. As a final check on the progress the TBD team made during the design process, iteration was used as a period of review and reflection. The developed ideas were analyzed to ensure they were the best option for the Growing Power vertical farm and beneficial towards the enhancement of Growing Power’s vision.




Figure 2. TBD’s collaboratively developed project phases

PULL PLANNING

The second portion of the Last Planner System® that TBD implemented was the pull planning technique, which reverses the planning process. Instead of scheduling from a start date forward, pull planning begins with a future milestone and works backward, so that information is pulled from downstream customers. By using sticky notes detailing a partner’s commitment and what he or she needs to keep that promise (fig. 3), the process created a more collaborative environment for TBD by generating an attitude among the team of adding value to the design process. Additionally, collaborative planning sessions generated more social commitment to the plan, and the displaying of the agreed-upon plan with sticky notes on a wall in the team’s office served as a constant reminder to all partners of their commitment to other team members, the project as a whole, and, ultimately, to Growing Power.

Resp. Partner	Duration	Delivery Date
I will produce...		
In order to produce that, I need...		

Figure 3. Sample pull planning sticky note



Figure 4. Informal LPS implementation

The initial implementation of the pull planning technique posed a challenge due to many design partners' lack of familiarity with the strategy. To familiarize the team with the concept of pull planning, TBD engaged in an informal simulation in which the team applied the method to plan and execute the construction of a small tower out of children's interlocking toy blocks (fig. 4). This initial session enlightened many team members to the importance of effective exchange of information to the delivery of a quality design, as even something as simple as a tower of blocks did not go as smoothly as the team had envisioned. Throughout all four phases of TBD's planning and design process, pull planning sessions (fig. 5) were held on a weekly basis to plan the

development of the team's Integrated Design Packages (p. 6). Several key exchanges of information occurred during these sessions that would not have normally taken place, such as the interaction between mechanical, structural, and construction partners in the design of the floor slab system of the Growing Spaces (p. 12) and the plenum of the Gathering Space (p. 14).



Figure 5. Snapshot of TBD collaborative planning

MAPPING PROJECT PROCESSES

Mapping project processes is a technique often used by the research community in order to understand project development and establish a baseline plan against which to measure actual progress. Although collaborative planning through LPS is a great facilitator for information exchange, a logical process flow diagram, (fig. 6, D2) is beneficial in enabling all partners to visually understand how each fits into the broader picture of developing an integrated design. As a form of documentation of the collaboratively developed plan, the process map allowed the team to look ahead to understand the overall direction of the team.




Figure 6. Snapshot of TBD project process map

Process mapping is an important tool to support team integration, which allowed TBD to eliminate waste in the design process and support all four major project goals.

CO-LOCATION

The location of essential team members in a common space significantly contributes to an integrated design process by making team members easily accessible for questions, responses, and spontaneous integrated design sessions. Throughout the entirety of the planning and design phases, TBD team members utilized an easily accessible, secure, co-located office for the majority of effort towards the Growing Power facility design. The space had enough room for all team members to work comfortably, held all team computers and drawing tables, had ample wall space for the hanging of relevant material, and contained a meeting space complete with a SMART Board (fig. 7).




Figure 7. Components of co-located office

Locating the team members in the same room also permitted the opportunity to witness the development of the design as it was created. This kept all pertinent players informed of the design and its process while simultaneously alerting them to their required deliverables necessary for the advancement of design. Co-location also enhanced design by providing continuous review by multiple team members, ensuring an optimized product.

FACE TO FACE COMMUNICATION

Whether team members were working on the Growing Power project, or other individual projects, an enormous portion of their time was spent together in the co-located office space, which allowed for frequent face to face interaction between all team members, the team’s preferred method of communication. Not only did face to face interaction contribute to the team building process of TBD, which in turn developed trust in team members, but also enabled effective flows of information through verbal communication. Everyone could be reached quickly if a question pertaining to their field of expertise arose, and the questions were promptly answered. The co-location of the team also opened all conversations to input from other team members, allowing them to provide aid from their own perspective, resulting in spontaneous, integrated design sessions.

DIGITAL COMMUNICATION

While face to face interaction was the preferred method of communication, it was not always an available option. An effective transfer of information is necessary to the success of an integrated design project and communication channels must be clearly identified to easily reach team members. TBD identified four methods of digital communication to be used during the planning and design phases of the project to reach team members and information (fig. 8). The electronic files created during design, including plans, research articles, calculations, spreadsheets, and reports, were uploaded to Box, a secure online file sharing and cloud content management service. Any file a team member uploaded to Box could be viewed by the entire team, creating a way for information to be pulled quickly when needed without direct contact between partners. The model files were the only files not saved to cloud storage, but were instead saved locally on a secure server. Cell phones were utilized when questions needed to be answered or decisions needed to be made quickly with the input of one individual. Publicly displaying the cell numbers of the team members provided the option to be contacted when needed. GroupMe, a mobile group messaging app, was an agreed-upon method to reach all partners simultaneously. This became a highly useful tool for decision making that required the input of a group when not all team members could be present in the co-located office.



Figure 8. TBD digital communication methods

DECISION MAKING PROCESS

In order to ensure that all major decisions were made in support of the defined project goals of economy, sustainability, flexibility, and community, a decision matrix was conceived that facilitated team analysis of those decision (fig. 9, D1). TBD’s decision matrix discouraged design partners from producing a system that they were familiar with, by encouraging the exploration of multiple options to design a facility that most effectively balanced all project goals. After developing a list of ideas, the design partner most familiar with the system

Option	Notes/Justification	1	4	7	9	10	2
Mechanical Systems							
FCU w/DOAS	Save energy by recirculation	5	4	3	4	1	4
Valance Clg & Htg w/ DOAS	Eliminates Fan Power assoc. w/ Clg & Htg	4	4	3	4	4	5
WSHP w/ DOAS	Heat Rejection to Water Loop	4	4	3	4	5	3
Ground Source Heat Pump	Heat Rejection to Ground	4	3	3	4	5	3

Figure 9. Snapshot of TBD decision matrix

evaluated each option against the four primary project goals, as well as secondary intra-team goals. Final decisions were made as a collective unit, and consisted of discussing the tradeoff that took place between the system options and how they contributed to each goal.



To support Growing Power’s goal of delivering an economic facility, cost trending was also used as a tool to inform design decisions. Management partners employed the use of “over-the-shoulder”⁽¹¹⁾ (OTS) estimating in order to maintain an accurate database of the design’s cost. The OTS strategy involves defining design milestones to perform a detailed financial estimate of the design to date. Each system of the facility was tracked independently and charted on a graph (fig. 10, D3), and constant evaluation of the project’s total value against Growing Power’s defined target allowed the team to identify if any portion of the facility was experiencing an alarming trend in cost growth, and facilitated numerous discussions




Figure 10. Evaluation of project cost against established target

throughout the design process. For example, the design and installation of an on-site combined heat and power (CHP) facility was identified early in the design process as a potential option to support Growing Power’s goal of community, but represented a significant portion of the mechanical system’s target value. This design option triggered further discussion and justification from an economic standpoint, and was ultimately accepted (M|10). Throughout the planning and design process, a contingency was carried to account for potential unknowns, inversely reflecting the level of confidence in the evaluation of the current estimate against the design target.

INTEGRATED DESIGN PACKAGES

Rather than designing the entire facility independent of each other’s progress, TBD chose to group similar space types into Integrated Design Packages (IDP). After analysis of the desired program, TBD identified five major IDPs within the footprint of the facility (fig. 11, SD|III), and identified the enclosure as another key IDP. Throughout the design phases, the team targeted efforts on one specific design package at a time, creating more interactions than a traditional design strategy. Working within the IDP better displayed the interactions among building systems and facilitated discussions within the team regarding potential conflicts. The near real-time discovery and resolution of collisions between systems allowed for much quicker design progression, as the team spent less time in traditional coordination meetings and more time detailing and developing the facility design.




Figure 11. TBD Integrated Design Packages

BUILDING INFORMATION MODELING



Building Information Modeling (BIM) is both a tool and a process that is designed to support the integration and flow of information among team members. The application of BIM is becoming the new standard of practice in the AEC industry, although the quantification of the value it adds is difficult due to varying levels of implementation on a case by case basis. However, promising data was produced from a case study of the Pegula Ice Arena, which earned a 2014 BIM Award from the American Institute of Architects, where research measured a savings of over \$1 million.⁽³⁾ However, the power of BIM is not limited to achieving only goals related to economy, but can also allow the team to develop a more sustainable building through energy analysis, utilize the information to improve upon the initial prototype, and help further Growing Power’s mission of educating the community.

BIM EXECUTION PLANNING

In order to take full advantage of the value that can be added through the use of BIM, a plan was put in place for the implementation of the tool throughout the lifecycle of both the project and the facility (SD|IV). Utilizing the BIM Project Execution Planning Guide⁽¹¹⁾, TBD developed a detailed plan for the utilization of BIM throughout the project, following a process consisting of defining BIM goals, identifying BIM uses, and recognizing how information should be exchanged between the different tools.

BIM GOALS AND USES

A key aspect of the Planning Guide is the idea to “begin with the end in mind.” Instead of identifying how BIM can add value to a project from the planning phase forward through design, construction, and operations, reversing the process ensures that each use of BIM is working toward an end goal, and that developed information is leveraged to improve design communication and integration

A key goal for TBD was to allow for the Growing Power facility designed in Milwaukee, WI to be a flexible prototype that is continuously improved upon with each new facility’s construction in a different location. As

such, the efficient operation of the facility was seen as paramount to the success of the overall project. Goals were then identified for the construction of the building, and through the design and planning phases (fig. 12, SD|IV).

Operate	Construct	Design	Plan
<ul style="list-style-type: none"> Allow for an easily maintainable facility Continuously improve upon prototype 	<ul style="list-style-type: none"> Minimize field conflicts Communicate schedule to project stakeholders 	<ul style="list-style-type: none"> Deliver an efficient, sustainable facility Ensure mechanical design complies with guidelines Ensure comfortable (day)lighting in spaces Ensure structural design complies with guidelines Review design progress to gather input from team Ensure project aligns with target value 	<ul style="list-style-type: none"> Validate and update arch program

Figure 12. TBD BIM goals, planned with the operation phase in mind




Figure 13. BIM uses per project phase

After clear definition of the goals TBD strived to achieve through the implementation of BIM, applications of different tools were identified to support the pursuit of those goals, (fig. 13, SD|IV). The primary uses were

divided by lifecycle phase, and further by TBD’s four custom phases which fit into the more generic “planning” and “design” phases.

BIM PROCESS AND INFORMATION EXCHANGES

With the goals and uses defined for the implementation of BIM throughout the Growing Power facility’s lifecycle, a process was undertaken to define how the partners’ models needed to develop and how




Figure 14. Sample BIM process

software would interface to perform each of the BIM uses. To begin, a high-level process was modeled for the team (fig. 14) in order to guide the implementation of the BIM efforts, beginning with preliminary programming and energy modeling. Once designs were authored, they were synchronized to an integrated central model, where review, coordination, and analysis could take place, aiding the iterative, integrated nature of TBD’s design process. In order to support the design authoring portion of the models, the AIA’s Level of Development (LOD) matrix^(14, 15) was utilized along with AIA’s LOD Specification.⁽¹⁶⁾

TBD designed specific information exchanges to leverage the software at hand, partaking in a detailed session defining how information could be extracted from the intelligent model and used to run simulations and analyses (SD|V).

DESIGN INTEGRATION

The result of Total Building Design’s integrated team processes is a highly integrated facility to turn over to the ownership partners at Growing Power. While the entire building required efficient coordination and communication, three key aspects of the design stood above the rest as considerable focused efforts of the team. The context of the facility is extremely important when analyzing its interior systems, as were the facility’s enclosure, the community gathering space, and the growing spaces.

BUILDING CONTEXT

In order to engage design partners in a more focused approach, the program described in schematic documents provided to TBD was categorized into integrated design packages (p. 6, SD|III) based on the intended use of the space. After analyzing the schematic documents, the project goals, and internal team goals, five distinct design packages were identified: growing spaces, administration and learning space, gathering space, market space, and support spaces, or back of house (fig. 15).



Figure 15. TBD Integrated Design Packages

TBD designed the Growing Power facility to take advantage of iconic architectural features and innovative, sustainable integrated building systems. The result, is a multi-use facility comprised of four terraced growing spaces (green) that showcase a flexible layout of aquaponic farming techniques (SD|XI), connected to the interior spaces with specially designed view corridors. Additionally, the facility will include two levels of educational and administrative space (purple) to actively support Growing Power's



Figure 16. Rendering of Growing Power facility

goal of community education and outreach. Below the administrative and learning spaces is a level of gathering, also designed to enhance Growing Power's outreach in the community with ample space for lectures, presentations, and storage to support a flexible layout. The storefront of the facility invites community members into Growing Power's market (cyan), which sells the sustainably grown produce from the growing spaces above. To support the entire

facility, a back of house area (basement, not shown) includes space for shipping and receiving, a workshop for the creation of plant beds, and mechanical and electrical zones. All packages are connected by a grand hybrid switchback staircase to unite the operation in connecting the surrounding community to all aspects of Growing Power. The facility (fig. 16) is supported by a rigid steel frame (red), conditioned with a water source heat pump distribution system (blue), and features efficient LED lighting controlled by occupancy and daylight sensors (yellow).

BUILDING ENCLOSURE DESIGN




Figure 17. Virtual mockup of rainscreen

The selection of an enclosure impacts design decisions for all team members, as well as defines the image of the Growing Power organization to the surrounding community. Multiple options for an enclosure were considered during the planning and design phases using TBD’s decision matrix (D1) to ensure the final selection supported project goals of flexibility, sustainability, economy, and community. After thorough analysis, a rainscreen assembly (SD|VII) was determined to be the most beneficial for the project needs, especially supporting Growing Power’s goal of flexibility. The rainscreen system (fig. 17) consists of metal studs, an exterior fiberglass sheathing layer, moisture barrier, Z-furring channel, rigid insulation, and architectural façade panels. Numerous components of the rainscreen, such as the insulation, can be adapted based on specific locations’ project conditions, supporting Growing Power’s

effort to use the facility in Milwaukee as a national prototype. Additionally, the enclosure is easily constructed (CM|9) and alleviates maintenance issues, like efflorescence and moisture penetration, associated with other systems. The rainscreen system created easier collaboration between the construction, structural, and mechanical partners since the wall could utilize multiple insulation R-values without added challenges to the respective systems.

RAINSCREEN BACKUP SYSTEM

The rainscreen assembly permits a great deal of flexibility in the design of its structural backup, allowing for either CMU or steel stud backup depending on the specific load case of a certain location (Struc|13). The system designed for Growing Power in Milwaukee consists of steel studs which reduced the enclosure’s backing weight, aiding in the economization of the structure’s perimeter beams and slightly increasing the usable interior space. The specific arrangement of studs was verified using AISIWIN structural modeling, but the stud size, spacing, and strength is also a flexible aspect of the rainscreen’s backup. The wind loads of Miami-Dade County pose a situation that requires consideration for high wind loads, but the flexibility of the rainscreen’s backup allows the assembly to be an effective enclosure in all locations.

MOISTURE PROTECTION AND INSULATION FOR ANY CLIMATE

The differentiating characteristic of the rainscreen theory is to prevent moisture from penetrating the enclosure, which usually occurs due to an air pressure differential across the enclosure created by windy conditions. Positive pressure created outside the enclosure in these conditions results in moisture being driven into the wall cavity in more traditional enclosure systems. The rainscreen assembly eliminates the pressure differential across the exterior wall through an open joint assembly—

Equal Pressurization Barrier



Figure 18. Equal Pressurization Barrier Section

The rainscreen system acts as a double line of defense in building moisture penetration. The architectural panels block driving wind, which equalizes pressure across the assembly and avoids pressure driven moisture penetrations into the facility (SD|VII)

essentially leaving small gaps between façade panels. By allowing rain and air between the façade panel and the bulk of the rain screen’s thermal and structural backup system, an equal pressure is achieved across the wall, which aids the traditional moisture barrier in keeping the Growing Power facility safe from moisture penetration, (fig. 18).

Additionally, the rainscreen’s utilization of rigid insulation outside the fiberglass sheathing layer allows for the enclosure to be thermally efficient in any location. The R-value of the insulation can be designed for any specific location based on the heating and cooling loads of the region. To simulate the flexibility, TBD modeled the Growing Power facility in both Milwaukee and Miami with Trane TRACE 700, allowing the team to analyze the rainscreen’s performance against the baseline ASHRAE 90.1, which proved that the rainscreen can meet the baseline in both locations with a simple upgrade of the rigid insulation layer. In fact, the assembly can greatly outperform the ASHRAE baseline in both climates (fig. 19, Mech|2).




Figure 19. Heating and cooling loads of Milwaukee (left) and Miami (right)



ARCHITECTURAL CONTEXT

Although the rainscreen assembly provides many benefits through its equal pressurization theory and the flexibility of its backing system and thermal performance, a major impact of the facility’s enclosure is its architectural style’s perception by the surrounding community. TBD chose a terracotta façade panel for the majority of Growing Power’s prototype in Milwaukee due to its natural composition and reflection of the community in which the facility is to be located. The terracotta panels also complement the sizing and placement of the glazing (fig. 20).

Analysis in DAYSIM and Trane TRACE 700 resulted in the selection of a glazing panel with an appropriate U-value and solar heat gain coefficient to reduce heat and cooling loads of the facility, supporting Growing Power’s goal of an economically operable facility while maintaining the architectural integrity of the facility’s façade (Elec|10). Furthermore, the team investigated the use of vertical fins on the east and west facades to block direct, low-angle sunlight from penetrating the facility’s interior spaces and further reducing the heating and cooling loads, resulting in slightly reduced energy consumption.



Figure 20. Façade complemented by glazing



GROWING SPACES

Growing Power’s primary mode of community outreach and education is through the demonstration of sustainable growing techniques. Currently, this process takes place in multiple greenhouses on-site, which are vital in order for the organization to provide “important opportunities for individuals and communities to network with each other as they work in partnership to promote food security and environmentally sound food production practices.” The success of the vertical farming facility depends significantly on the ability for all four greenhouses to operate efficiently. As a space for the growth and maintenance of plant life is also heavily reliant on various building systems, the greenhouses were a major point of integration throughout TBD’s design process (SD|VIII).

ORIGINAL DESIGN

The original design for the Growing Power facility, contained in schematic documents provided to TBD (fig. 21), included four levels of rooftop greenhouses to support the organization’s efforts to educate the community through demonstration of different growing techniques. While understandably an effort to provide an economic solution for Growing Power, the specified pre-manufactured greenhouses left TBD room for improvement. The rooftop greenhouses originally specified for the Growing Power facility rose to a peak height of 26 feet above the finished floor and consisted completely of exterior glazing. Through extensive research and analysis with various BIM tools, TBD made the decision to investigate redesigning the growing spaces to allow for optimum plant growth, a safe and flexible layout of aquaponic systems, reduced conditioning costs, and the creation of an iconic architectural statement when viewed from the surrounding community.

A MORE EFFICIENT GROWING SPACE

TBD’s initial investigation of the specified pre-manufactured rooftop greenhouses suggested that the space contained an unnecessary volume of space to condition, an inefficient plant layout, and excessive glazing (Elec|5). Further research also indicated that the pre-manufactured greenhouses could not be reduced to a favorable height while maintaining the necessary fire rating to comply with IBC code (Struc|11). TBD discovered that a custom greenhouse structure could be designed that contained less volume and a more efficient glazing layout, allowing the mechanical system to more efficiently condition the space without negative impacts on the natural light reaching the plant beds within the space. Additionally, a custom-designed greenhouse structure provided the potential to take into account multiple locations’ load cases, resulting in a more prototypable space.




Figure 21. Elevation comparison of original greenhouse (left) and TBD custom design (right)

In order to minimize the roof structure’s effect on the natural light obtained by the plant beds, multiple concepts were devised and analyzed simultaneously in DAYSIM and RAM to ensure both their structural integrity and their impact on natural light reaching the plant beds (Elec|6). While large steel elements could have been easily designed and implemented, their negative impact on the plants’ lighting significantly hindered the greenhouse’s ability to operate efficiently, detracting from Growing Power’s goal of an economically operated facility to educate the community. The final design consisted of a glulam structure, sized as narrowly as possible to allow an optimum amount of light to reach the beds and provide a greenhouse design that is as conducive to efficient plant growth as possible. The use of heavy

timber also alleviated the fireproofing concern regarding the greenhouse roof (Struc|11), and provided a unique architectural feature in the use of a sustainable material in the sawtooth profile of the greenhouses (fig. 21).

Further daylighting analysis proved that the original design contained excessive glazing that created a greater conditioning load than necessary. In order to increase the thermal resistivity of the greenhouses' walls without negatively impacting the plants' growth, the facility's rainscreen façade was carried from the main portion of the building to the east and west sides of the greenhouse, as well as partially up the south wall (REF).



A FLEXIBLE FLOOR LAYOUT

Another major goal for TBD was to provide Growing Power with the flexibility to install and demonstrate a variety of growing techniques throughout the rooftop greenhouses. An aquaponic system (Mech|3) was a targeted system and provided numerous challenges and constraints to the flexibility desired. The tanks designed for the aquaponic system account for a large load on the structural slab, requiring the slab to be designed for much higher live loads than normal (Struc|4) in order for the tanks to be placed anywhere in the greenhouse and to allow Growing Power the flexibility to place an aquaponic system in the greenhouse on any level.




Figure 22. Detail view of TBD's greenhouse floor system

An aquaponic system also consists of a great deal of water piping at the floor level, posing a safety hazard for those exploring the space. As an educational tool for the community, safety was a vital consideration for the growing spaces. To reduce the amount of piping resting on the greenhouse floor, TBD designed a unique, grated floor system that allowed the pipe to be routed under the raised grate (fig. 22, SD|X). Coincidentally, the plenum below the floor grate also created space to run conduit and other mechanical piping, removing as many obstructions as possible from blocking the plants' sunlight.

As the greenhouses were designed to house numerous systems containing vast amount of water, water leakage was a major consideration that needed to be taken into account throughout the design's development. After investigating multiple options, a solution was designed providing two layers of defense against water penetration into the Growing Power facility (fig. 22, Struc|12).

EFFICIENCY THROUGH AN INTEGRATED APPROACH

While the introduction of pre-manufactured greenhouses could provide a much lower up front construction cost, their implementation left room for improvement with respect to the project goals of community education, flexibility, and long term economy. TBD's integrated design approach led to the creation of a greenhouse design that more effectively supported those goals. Through the definition of an Integrated Design Package consisting strictly of the growing spaces on each level, TBD focused efforts of all team members on the greenhouses at once, devising a solution that benefitted all design partners, but most importantly Growing Power. The use of various analysis tools was essential in order to balance the needs of each building system and the plant life within, and the communication facilitated by collaborative planning sessions provided pertinent information to all team members as the design developed, allowing TBD to design a flexible space to house numerous types of growing systems, while efficiently conditioning the space and quickening the facility's watertight milestone.



GATHERING SPACE

Growing Power exists not only to grow food, but also to grow the local community in which the facility and organization are situated. A key support to the goal of community outreach and education is the Gathering design package, highlighted by the completely open plan Gathering Space located on the facility's second floor.

ORIGINAL DESIGN

The schematic documents provided to TBD included the aforementioned space on the second floor of the Growing Power facility. However, while the original plan was spacious enough to host a large gathering of people, the columns in the plan created a visual and physical obstruction of the space (fig. 23). TBD fully agreed with the placement of the gathering space in the context of the facility—the second floor is slightly less public than the market below, but much more so than the private education and administrative spaces above. However, in order to support Growing Power's goal of community involvement and outreach, TBD identified an opportunity to improve upon the original design for the gathering space by removing two interior columns (SD|XII). The removal of the interior columns resulted in more usable space for seating in a large presentation setting, as well as uninterrupted views to those seated farthest from the presenter. The team proceeded with the decision to support Growing Power's goal of community with the understanding that developing a successful design would take great effort by




Figure 23. Comparison of original design for Gathering Space (left) and TBD's open plan (right)

all partners and a highly integrated approach.

TBD IMPROVEMENTS AND CHALLENGES

By focusing the entire team on the Gathering Space design package at the same time, communication was facilitated through the use of collaborative planning (p. 3). This ensured that the design process went as smoothly as possible by identifying key points of interaction that needed to occur in the process. The integrated planning session determined that the first step of redesigning the open Gathering Space was to begin with a discussion of installation sequencing and shipping logistics to ensure that any structural element that was designed supported the construction sequencing plan, or that the plan could be altered to make any necessary accommodations.

In the scheming phase of the Gathering Space's development, the team convened to discuss options to overcome the challenge of eliminating the two interior columns. This discussion resulted in numerous design guidelines for all systems to be integrated within the plenum space, such as the idea that the structural members needed to be shallow enough to allow duct to pass




Figure 24. Transfer girders (red) open the Gathering Space floor layout

between the steel and the space's ceiling, or deep enough to safely cut through the members.




Figure 25. MEP linear scheme to coordinate with girders

Through the extensive use of RAM modeling, TBD determined that the best option to transfer the facility's load to the exterior columns was through the utilization of three transfer elements, (fig. 24, Struc|7). With the understanding that these elements had the potential to consume most of the plenum space, TBD designed a linear scheme of mechanical and electrical equipment and fixtures that fit between the locations of the three transfer elements. The size of some mechanical equipment posed a potential challenge with the reduced plenum space, so the team determined that space along the exterior walls could house the heat pumps feeding the space.

With a schematic layout devised, TBD moved forward developing the integrated design. Again the targeted approach of the team proved extremely beneficial, as all partners modeled their designs simultaneously, with the structural layout slightly leading the MEP system layout. Coordination views developed in Revit (fig. 26), also proved invaluable to the team in the modeling process, as they allowed all partners to author their design within the context of the entire, integrated space. Continuous coordination by all design partners significantly reduced the number of conflicts that needed to be resolved in coordination sessions (SD|VI).

The decision to open up the space also resulted in challenges to be overcome during the construction process. Structural members of the depth and weight utilized in the Gathering Space are not rolled at all steel mills, and lengths exceeding that of a standard semi-permanent trailer require permits to travel on various highways, presenting the potential for significant added costs. Additionally, the massive members posed a challenge in that they were preliminarily identified as a potential to be the project's critical path (CM|9). However, extensive research resulted in solutions to all challenges, as TBD identified a mill in Arkansas and fabricator near the Milwaukee site, with a path routed by a shipping partner that resulted in a nominal transportation fee (CM|9).




Figure 26. Coordination view in Revit

EFFICIENCY THROUGH AN INTEGRATED APPROACH

Utilizing TBD's integrated design approach and BIM technology, a solution beneficial to all designed systems and the building as a whole was created. While the original design contained in schematic documents was undoubtedly a simpler option to construct and an attempt to provide a more economic design, TBD determined that its design left room for improvement, specifically in its contribution to the space's community education aspect. While altering the design to feature a completely open second floor created multiple challenges, the strategies implemented by the team allowed a successful design to be achieved. Through the definition of a specific design package, TBD focused all design partners in the space at once. The utilization of collaborative planning facilitated important discussion regarding the interactions between various design systems, resulting in such ideas as making the transfer elements either deep enough to cut through or shallow enough to run air distribution between the steel and the ceiling. The end design's linear lighting and mechanical scheme (fig. 25) was the result of a defined "coordination view" in each design partner's virtual model, allowing the team to continuously coordinate the space to alleviate any possible issues, or catalyze discussion among the team.

REFERENCES

INDIVIDUALS

Robert Holland, AIA – President, AMKEV Consulting PL

Craig Dubler, Ph.D., DBIA – Friend and Colleague

Robert Leicht, Ph.D.

John Messner, Ph.D.

Mila Corkins—Director, Planning, Scheduling, and Management Controls, Walt Disney Imagineering

David Van Wyk – Project Integration Executive, Walt Disney Imagineering

PRINT

1. Bucklin, R. A. "Fan and Pad Greenhouse Evaporative Cooling Systems1." EDIS New Publications RSS. University of Florida IFAS Extension, Dec. 1993. Web. 11 Oct. 2014.
2. Chapman, John. "Interview with John Chapman on Aquaponics." Personal interview. 24 Oct. 2014.
3. Murphy, David, and Corvaia, Joe. 2014 AIA TAP BIM Awards. April 22, 2014, Boston, MA. Print.
4. Zimmerman, Alex. "Integrated Design Process Guide." (n.d.): n. pag. Canada Mortgage and Housing Corporation. Web.
5. NASFA, COAA, APPA, AIA, and AGC. "Integrated Project Delivery for Public and Private Owners." (2010). Web.
6. AIA. "Integrated Project Delivery: A Guide." (2007). Web.
7. Mossman, Alan. "What Is Integrated Lean Project Delivery?" (2008). Web.
8. Busby Perkins+Will, and Stantec. "Roadmap to the Integrated Design Process." (n.d.): n. pag. Web.
9. Macomber, Hal, and John Barberio. "Target-Value Design: Nine Foundational Practices for Delivering Surprising Client Value." (2007): n. pag. Lean Project Consulting, Inc. Web.
10. Ballard, Glenn. "Target Value Design: Current Benchmark." *Lean Construction Journal* (2011): 79-84. *Lean Construction Journal*. Web.
11. Computer Integrated Construction Research Program. (2010). "BIM Project Execution Planning Guide—Version 2.0." The Pennsylvania State University, University Park, PA, USA.
12. Virtual Facility Group, Office of Physical Plant. "Asset Attribute List." The Pennsylvania State University, University Park, PA, USA.
13. Wright, Alex. *The Imagineering Field Guide to the Magic Kingdom at Walt Disney World: An Imagineer's-eye Tour*. New York: Disney Editions, 2005. Print.

DOCUMENTS AND SPECIFICATIONS

14. AIA E202-2008
15. AIA G202-2013
16. 2013 BIM Forum LOD Specification




LAST PLANNER SYSTEM (LPS)



OVERVIEW

In a recent study on production in design and construction teams, it was found that an average of 54% of planned work was completed on time. The major reason given for this low percentage was that prerequisite work was not completed in order to begin tasks on time. The Last Planner System is a planning strategy that aims to make teams more productive by completing a high percentage of planned work. According to the Lean Construction Institute, the Last Planner System (LPS) is a “collaborative, commitment-based planning system that integrates should-can-will-did planning with constraint analysis, weekly work planning based upon reliable promises, and learning based upon analysis of PPC (plan percent complete) and reasons for variance.” LPS follows a 5-step process built on the Plan-Do-Check-Act cycle that ensures that a team is performing work that needs to be done, when it needs to be done, so that successors can proceed as planned.

THE 5-STEP SYSTEM



MASTER SCHEDULING

The first step of LPS involves Master Scheduling, or the act of setting milestones. Generally this portion of the process is performed similarly to traditional scheduling practice, as milestones are often constrained by substantial completion dates or other deadlines. However, more intermediate milestones are generally specified than in a traditional approach, making the next step of phase/pull planning more clear.

PHASE PLANNING/ PULL PLANNING

Phase planning, or pull planning, is sometimes thought of as synonymous with LPS. However, phase planning does not represent actual promises or commitments between team members, but rather

serves to specify the handoffs that need to be made in order to complete work—it specifies what *should* occur in the phase. Pull Planning is performed in a backwards fashion, working from a milestone. Individual tasks are identified collaboratively with zero or minimal-float durations so that once the process is complete, activities are completed or decisions are made at the last responsible moment. This ensures that downstream activities are pulling the work from earlier activities, and the process flows smoothly. Pull planning is usually used with sticky notes that follow a particular fashion, specifying the work an individual is to complete with the work that needs to be completed immediately prior.

MAKE READY PLANNING

Making work ready is an important part of LPS that ensures that the upcoming work can be completed per the initial plan—it defines what work *can* be completed. The initial step of making work ready involves documenting the handoffs that were specified in the previous step. However, the documentation goes one step farther by allowing space for constraints to be documented. By identifying constraints to the phase plan—what *should* happen—the team can work to resolve those constraints ahead of time before they restrict the actual work being performed.

WEEKLY WORK PLANNING

Weekly planning exists for team members to make commitments to each other once it has been determined that the work has been made ready. The weekly plan defines what work *will* be done by each party. This follows a similar process as phase planning, but is much more detailed for the week ahead. It also involves daily check-in meetings with the team to ensure that work is progressing as planned. A recommendation is for these meetings to take no longer than 15 minutes, and to identify what promises have been fulfilled, and what work will be fulfilled.

LEARNING/ IMPROVING

Perhaps the most important part of LPS is the learning/ improving stage, which defines what *did* happen, and aims to support the lean principle of continuous improvement. On a weekly basis, the promises that were to be completed in the week prior are analyzed to determine the Plan Percent Complete (PPC). A common strategy is to publish the entire team’s PPC, but track privately per individual or trade. Publishing the team’s PPC on a regular basis allows the team to strive for as high a percentage as possible, but the management team can determine if a particular trade is routinely performing at a low percentage. From here, the PPC can be analyzed to determine what needs to be done for the project to be completed better, and bring the average of 54% to a much higher level.

CONCLUSIONS

The Last Planner System is a collaborative way to enhance the planning and scheduling process. With construction having a much lower efficiency than other non-agricultural industries, and only 54% of tasks being completed, LPS has the potential to greatly improve the industry. Through thorough implementation of the 5 steps of LPS, teams can generate more realistic schedules and build chemistry with their trade partners. While often implemented after problems arise through work with consultants, champions of the process can implement the system throughout an entire project to experience clearer understanding of the interactions among team members and develop more useful schedules and planning techniques.

INTEGRATED DESIGN PACKAGES

In order to facilitate focused integration, TBD's management partners devised a plan to develop Integrated Design Packages (IDP) within the larger context of the Growing Power facility. Upon receipt of schematic documents, the team analyzed the facility's program in order to group spaces by their use. The result, shown in the image below, was a facility that was massed into five major IDPs within the facility.


First and foremost, the Growing Power facility is to be used to implement demonstration techniques of vertical farming. As such, the team grouped the three cascading greenhouses, as well as the rooftop greenhouse, into a Growing Space design package, shown in green.

The first floor consists of market-related spaces, such as the public market itself and its support spaces. As such, the team defined a Market IDP, shown in cyan.

The second floor contributes greatly to Growing Power's vision of community involvement, and is made up almost entirely of the gathering space and break-out spaces. TBD defined this level as a Gathering package, shown in orange.

The two floors above the Gathering package housed the administrative and educational spaces, and were also grouped into a package (purple).

Lastly, the facility is to be served by equipment housed in the basement, distributed on each level, and connected by a vertical shaft. The Back of House package was defined to envelop all the facility's support equipment and systems, such as the mechanical and electrical room in the basement. The Back of House package is shown in red.




As the project developed, it became apparent that some designed systems became their own design packages in order to unite the entire facility. The structure and building enclosure, while contained partly in each space, needed to be analyzed on a macro level in order to make them most efficient, and enclose the entire facility, shown to the left.

PLANNING THE IMPLEMENTATION OF BIM

As the use of Building Information Modeling was extremely important to the Growing Power facility's development, a plan was put together at the project's outset for the tool's implementation. The process for BIM planning includes defining project goals, determining BIM uses to support the goals, and defining how models are shared and information is extracted from the models. An excerpt of each portion of the process is shown below.


DEFINING BIM GOALS AND USES

Operate	Construct	Design	Plan
<ul style="list-style-type: none"> Allow for an easily maintainable facility Continuously improve upon prototype 	<ul style="list-style-type: none"> Minimize field conflicts Communicate schedule to project stakeholders 	<ul style="list-style-type: none"> Deliver an efficient, sustainable facility Ensure mechanical design complies with guidelines Ensure comfortable (day)lighting in spaces Ensure structural design complies with guidelines Review design progress to gather input from team Ensure project aligns with target value 	<ul style="list-style-type: none"> Validate and update arch program



DEFINING BIM PROCESS

In order to effectively take advantage of the benefits of BIM, the decided upon uses of the tools must be organized into a process. Shown below is a visualization of TBD's BIM process. For example, the mechanical partner's BIM process began by developing an energy model to analyze potential systems. Once a design was selected, the mechanical partners authored their design in Revit, and continuously synchronized to a shared, central model, which allowed for information to be extracted for data analysis. From there, the cycle was an iterative process, as shown by the loop in the partner's process.



Building Information Modeling Use Case Worksheet									
BIM USE	PROJECT VALUE	RESPONSIBLE PARTNER(S)	VALUE TO RESPONSIBLE PARTNER(S)	CAPABILITY RATING			ADDITIONAL RESOURCES REQUIRED	NOTES	PROCEED?
				SCALE 1-3 (1=LOW)					
	HIGH/MED/LOW		HIGH/MED/LOW	RESOURCES	COMPETENCY	EXPERIENCE			YES/ NO/ TBD
Existing Conditions Modeling	Medium	Architectural Partner	High	3	3	3	Topography, utility locations	To be modeled in Infraworks.	TBD
		Construction Partner	High	3	3	3			
		Electrical/ Lighting Partner	Medium	3	2	1			
Cost Estimation	High	Construction Partner	High	2	3	3		Export QTO from Revit.	Yes
		Electrical/ Lighting Partner	High	2	2	1			
		Mechanical Partner	High	2	2	1			
Phase Planning	Medium	Structural Partner	High	2	2	2		Apply RSMean cost data.	
Programming	High	Architectural Partner	High	3	3	3		N/A to this project.	No
Site Analysis	Low	Electrical/ Lighting Partner	Medium	3	2	2		Analyze schematic documents.	Yes
		Mechanical Partner	High	3	2	2			
		Structural Partner	High	3	2	2			
Design Reviews	High	Owner	High	1	1	1		To be conducted in immersive environment (ICON Lab).	Yes
		Architectural Partner	High	3	3	3			
		Construction Partner	High	3	3	3			
		Electrical/ Lighting Partner	High	3	2	2			
		Mechanical Partner	High	3	2	2			
Structural Partner	High	3	2	2					

DEFINING BIM INFORMATION EXCHANGES


Throughout the design process, key information needed to be extracted from the shared, central model in order to perform various analyses, as displayed on the previous page. Each line type represents different information exchange, whether that be a human resource, direct link, or defined information exchange between BIM software. Below is a key detailing the numerous exchanges that took place throughout TBD’s planning and design phases.

Line Type	Involved Design Partner	Information Exchange Description	File Transfer?	Origin	Receiver 1	Receiver 2	File Type
.....	All	Human resource input	No	N/A	N/A	N/A	N/A
====	All	Directly synchronize to central	No	N/A	N/A	N/A	N/A
----	Mechanical Partner	Build energy model	No	TRACE	Revit	N/A	Data only
		Extract data for energy analysis	No	Revit	TRACE	N/A	Data only
		Extract data for energy analysis	Yes	Sketchup	IES	N/A	.skp
----	Structural Partner	Extract data for structural analysis	Yes	Revit	CAD	RAM	.dxf
		Extract data for structural analysis	Yes	Revit	CAD	SAP2000	.dxf
		Extract data for structural analysis	Yes	Revit	CAD	ETABS	.dxf
----	Electrical Partner	Perform daylighting analysis	Yes	Revit	CAD	DAYSIM	.dwg
		Perform lighting system analysis	No	Revit	ElumTools		plugin
		Perform solar site analysis	Yes	Revit	Ecotect		.3ds
----	Management Partner	Assemble 4D model	Yes	Revit	Navisworks		.nwc
		Perform 3D coordination	Yes	Revit	Navisworks		.nwc
		Perform design review	Yes	Revit	Navisworks		.nwc
		Perform design review	Yes	Revit	3DS Max	Unity	.3ds
		Analyze cost	Yes	Revit	Excel		.csv
----	Architecture Partner	Analyze surrounding site	Yes	Revit	Infraworks		.fbx
		Analyze GIS data	Yes	Civil 3D	Infraworks		.shp
		Programming	Yes	Sketchup	Revit		.dwg





In order to guide the development of TBD’s models, the management partners employed the AIA’s Model Development Specification, specifically the Level of Development matrix, shown below. Based on a collaborative discussion, the team determined what components needed to be developed to what level of development at what point in time. The matrix was also supplemented by the AIA’s LOD specification, to support the team in its understanding of different levels for various components.

		Design Intent Model				
		Model Element	Scheming		Development	
			Yes/No	LOD	MEA	LOD
A 1010 Standard Foundations						
	Wall & Column Foundations	Y	100	SP	200	SP
	Foundation Walls	Y	100	SP	200	SP
	Grade Beams	Y	100	SP	200	SP
	Pile Caps	Y	100	SP	200	SP
	Excavation, Backfill & Compaction	Y	100	SP	200	SP
	Footings & Bases	Y	100	SP	200	SP
	Perimeter Insulation	N				
	Perimeter Drainage	N				
	Anchor Plates/Bolt Patterns	N				
	Means & Methods (Erection/Sequencing/ Shop Standards)	N				
A 1020 Special Foundations						
	Pile Foundations	Y	100	SP	200	SP
	Grade Beams	Y	100	SP	200	SP
	Caissons	Y	100	SP	200	SP
	Underpinning	N				
	Dewatering	N				
	Raft Foundations	N				
	Pressure Injected Grouting	N				
	Other Special Conditions	N				
	Means & Methods (Erection/Sequencing/ Shop Standards)	N				

COORDINATION



The management team tracked clashes between different technical systems to monitor progress and evaluate the impact of managerial decisions at each collaboration review. After the first coordination review, the high amount of initial clashes signified an opportunity for a better approach to design. To enable the design partners to deliver a more integrated product with less clashes, the management team created coordination views in the discipline specific models, which clearly displayed everyone's technical systems. The change in designing method is reflected by the reduced number of clashes for the remaining duration of design, as indicated in the figure above. Although the change did not completely eliminate all design clashes, it greatly reduced the time and effort required by all parties to resolve clashed through system redesign.




Continuous coordination throughout the design phase of the Growing Power facility enabled the designing partners to develop a facility with minimal clashes. Clashes between the mechanical, electrical, and structural design were identified early in the design process in Navisworks. The clashes, an example of which can be seen to the left, were then discussed in coordination reviews with the entire team. The design teams and construction managers would meet at the planned completion deadlines of the different design packages to conduct an immersive walk through the building, and a coordination review, utilizing a local Semi Immersive Design laboratory, as seen to the left. Clashes identified through the design process were displayed for the team to create group discussions on innovative solutions in a collaborative environment. The team analyzed the potential advantages and disadvantages of the proposed solutions, compromising negative discipline effects for beneficial overall project success. An example of this process would cutting through a steel element to allow piping to remain hidden from the public. The proposed solutions the team agreed upon did not always immediately resolve all clashes, but pushed the project towards the team's clash free goal, while supporting Growing Power's mission.



RAINSCREEN FAÇADE AND GLAZING


The team oriented design phase of the vertical farming facility, yielded the selection of a terracotta rainscreen façade system to enclose the building. Each discipline partner analyzed the façade system to provide input and suggestions, which led to a constructible, energy efficient system with ample daylighting for occupant comfort, complementing the team goals of sustainability, flexibility, and economy.

Heating and Cooling Demand Changes Affected by Varying Façade R-value in Milwaukee and Miami



ENERGY SAVINGS

The rainscreen façade can be installed with a range of insulation, influence by thermal requirements of specific locations. The mechanical partners analyzed the R-value of different rainscreen assemblies with Trane TRACE 700, to determine if the rainscreen façade could meet the ASHRAE minimum, and identify an optimum insulation value. The figure above displays heating and cooling loads for Milwaukee and Miami, indicating an optimum R-Value of 25, based on the installation cost and energy savings.



Providing adequate daylighting, while maintaining the thermal integrity of the envelope system, is necessary to an energy efficient Growing Power facility. Daylighting studies, performed with Daysim, analyzed different glazing types to determine optimum characteristics (ELEC REFERENCE). By specifying the use of automating lighting controls, the daylighting study indicates a substantial energy savings when using Solarban 67 glazing and shading fins to reduce direct sunlight, compared to standard glazing types.

The study also indicated a reduced need of automated shading, which contributes to energy savings, as well as increases a connection to the exterior site by decreasing blocked views.

	70XL	67 + fins
Shade Up	59.69%	87.30%
Shade Down	40.31%	12.65%

CONSTRUCTABILITY

The specification of the rainscreen alleviated structural dead loads from the façade when compared to traditional masonry façade designs, but still required detailed analysis to confirm its feasible use in the facility design. To ensure safe and proper design of the rainscreen assembly, the structural design partners analyzed appropriate placement of steel stud backup. WHAT ELSE HERE adam/todd


The rainscreen system is a complex assembly that requires diligent effort to install, and price correctly. To ensure the proper installation, the construction team created a virtual mock-up, clearly displaying the assembly pieces, and the order of installation. The visual can be used to indicate to trade contractors, the expectations of the design team. The construction team also conducted a production study to accurately schedule the installation process (Const SD II). The production study, conducted on the installation of a similar rainscreen assembly, provided accurate results to contribute to the reliable scheduling of the vertical farm construction.

Terracotta Panel Size		Terracotta Production Rate								
1 ft x 4 ft		Date	Completed Area	Unit	No. of Panels	Unit	Crew Size	SF/Crew Mem.	No./Crew Member	Note
		10/20/2014	1047.8	SF	262	SF	4	261.95	65.5	First Day Tracking
		10/21/2014	237.39	SF	63	SF	4	59.35	15.75	
		10/22/2014	231.25	SF	55	SF	4	57.81	13.75	Raining
		10/23/2014	227.3	SF	92	SF	5	45.46	18.4	
							Average	54.21	15.97	

Applicable Studs for Exterior Façade - Milwaukee						
Wall Height	14	ft				
Axial Load	350	plf				
Wall Weight	25	psf				
Axial Load per Stud	12" o.c.	350			lbs	
	16" o.c.	467			lbs	
	24" o.c.	700			lbs	
Wind Pressure	36	psf				Zone 5
Clark Dietrich Designation						
Spacing	Depth	Flange Width	Minimum Gage	Fy	Depth	Gage
12	600	137	54	50	6	16
		162	54	50	6	16
		200	43	50	6	18
		250	43	50	6	18
		300	54	50	6	16
	800	137	54	50	8	16
		162	54	50	8	16
		200	54	50	8	16
		250	54	50	8	16
		300	54	50	8	16
16	600	137	68	50	6	14
		162	54	50	6	16
		200	54	50	6	16
		250	54	50	6	16
		300	54	50	6	16
	800	137	54	50	8	16
		162	54	50	8	16
		200	54	50	8	16
		250	54	50	8	16
		300	54	50	8	16
24	600	137	97	50	6	12
		162	68	50	6	14
		200	68	50	6	14
		250	54	50	6	16
		300	54	50	6	16
	800	137	97	50	8	12
		162	68	50	8	14
		200	54	50	8	16
		250	54	50	8	16
		300	54	50	8	16




TC Rain Screen Façade							
Material	ID	Cost	Qty	Unit	Unit Price	Unit/SF	\$/SF
Stud	1	\$ 6.21	10	LF	\$ 0.62	0.75	\$ 0.47
Sheathing	2	\$ 19.00	32	SF	\$ 0.59	1	\$ 0.59
Vapor Barrier	3	\$ 175.00	112.5	SF	\$ 1.56	1	\$ 1.56
Z Strip	4	\$ 200.00	192	LF	\$ 1.04	0.5	\$ 0.52
Insulation	5	\$ 32.00	32	SF	\$ 1.00	1	\$ 1.00
Furring	6	\$ 4.49	12	LF	\$ 0.37	1	\$ 0.37
TC Panel	7	\$ 32.00	1	SF	\$ 32.00	1	\$ 32.00

Mat'l	\$ 36.51
Inst	\$ 2.10
Total	\$ 38.61





LOWER GREENHOUSE DESIGN

Analysis of the original, pre-manufactured greenhouse design indicated an opportunity for improvement through an integrated design. Analysis through Daysim indicated the elimination of the non-south facing glazing has a minimal impact on the sunlight supplied to the growing spaces, as shown in the daylighting autonomy figure to the right. While the elimination of the excessive glazing has a minimal impact on the daylighting of the space, the reduction of glazing and the addition of the rainscreen facade created a lower heating demand, reflected in the graph below for heating load in January. Redesigning the greenhouse spaces and reducing the amount of glazing in the greenhouses, reduced the cost associated with heating the space, without sacrificing the daylighting necessary to healthy plant life.





The cascading greenhouse roofs utilizing renewable glulam members framing into HSS components designed to optimize daylighting providing to the plants. As the design is comprised of a number of different parts, several STAAD models were created to analyze the components independently while applying loads from one model to another as appropriate. The structural modeling, combined with a DAYSIM analysis indicated the final design to be beneficial for both structural and electrical design partners.




TOP GREENHOUSE REDESIGN

The original, prefabricated greenhouse design on the top of the growing power facility included redundant structural elements and excessive conditioned space. The TBD design team determined this to be an area with the potential for improvement and redesigned the growing space to be more relatable to other locations across the country without sacrificing the sunlight necessary to plant life. The structural, mechanical, and electrical partners determined a 15° slope on the south side of the greenhouse roof, limiting the structural height to 30 feet, was an effective angle to reduce conditioned space without sacrificing daylight. The structural team conducted multiple SAP2000 and RAM SS analyses to determine optimum member dimensions required to create an open floorplan with minimal structural column interference, while simultaneously comparing member sizes with Daysim analyses by the electrical partner..

Top Greenhouse Roof Slope Comparison				
Start Height	10			
Length	73.5			
Roof Slope (Degrees)	Start Height	Length	Change in Height	Total Final Height
0	10	73.5	0	10
1	10	73.5	1.3	11.3
2	10	73.5	2.6	12.6
3	10	73.5	3.9	13.9
4	10	73.5	5.1	15.1
5	10	73.5	6.4	16.4
6	10	73.5	7.7	17.7
7	10	73.5	9.0	19.0
8	10	73.5	10.3	20.3
9	10	73.5	11.6	21.6
10	10	73.5	13.0	23.0
11	10	73.5	14.3	24.3
12	10	73.5	15.6	25.6
13	10	73.5	17.0	27.0
14	10	73.5	18.3	28.3
15	10	73.5	19.7	29.7
16	10	73.5	21.1	31.1
17	10	73.5	22.5	32.5
18	10	73.5	23.9	33.9
19	10	73.5	25.3	35.3
20	10	73.5	26.8	36.8



RAISED GRATE FLOOR




COMX Aluminum Raised Floor System

- 24”x24” raised aluminum panels
- 1250 lb concentrated load rated - exceeds live load requirements of the space
- Corrosion Resistant – Ideal for humid greenhouse spaces
- Easy to Install – Lightweight with locking corners for vibration control
- Different Options – Flexible to the needs of the owner

The greenhouse flooring system was designed to take advantage of the benefits of a raised, grated flooring system, by placing all piping below aluminum panels. The tile grates are easily removable to allow access to the piping below, enabling Growing Power employees to install caps, or valves on any pipe to supply future growing bed designs. The greenhouse spaces are designed to accommodate everything from traditional growing beds to vertical stacked systems. The raised aluminum floor provides the greenhouse with the flexibility to educate the community about numerous greenhouse growing techniques.


The grated system also contributes to the safety of the community members on educational tours of the vertical farming facility. It is expected that groups of neighbors, students, and children will be traveling through the spaces to learn about sustainable farming methods. Placing all piping under the raised flooring immensely reduces potential tripping hazards and creates a safer environment.



AQUAPONICS


The aquaponic system designed by the mechanical partners, allows Growing Power to demonstrate the symbiotic relationship between the fish and plant life as part of their community education program. Correctly sizing the components of the system required the use of equations detailed in the ASHRAE Handbook – HVAC Applications, the product of which is detailed in the table to the left.

The large components were designed to house enormous amounts of water within the system, which contributed substantial load to be supported by the structural system. The load from the water-filled aquaponic growing beds was so large, it required the use of steel elements, as a concrete alternative created shear excessive shear issues (Struc5). Steel members were specified to support the growing layout as well as the dropdown in the floor to create space for the necessary piping, and are highlighted in the graphic below



Growing Place Level	Growing Beds				Aquaculture Raceway *				Aquaponic Sump			Evaporative Cooling Sump			
	Quantity	Length ft	Width ft	Area SF	Length ft	Width ft	Height ft	Volume gallons	Volume gallons	Length ft	Width ft	Height ft	Volume gallons	Diameter ft	Height ft
2	16	4	13	832	40	6.31	3.5	6604	140	2.66	2.66	2.5	16	1.25	2.66
3	16	4	13	832	20	6.25	3.5	6604	140	2.66	2.66	2.5	16	1.25	2.66
4	8	4	13	416	25	5.04	3.5	3302	70	2.1	2.1	2	16	1.25	2.66
5	36	4	13	1872	40	14.13	3.5	14794	300	3.66	3.66	3	56	2	2

*It should be noted that the greenhouse on Level 3 includes two tanks at the size specified due to coordination with the structural system



Gathering Space Design Coordination

The Gathering Space redesign included the elimination of two structural columns to open the floorplan and allow for better visual connections during presentations. Successful redesign of the space required focus and input from all design partners engaged in the TBD integrated project approach. The resulting Gathering Space provides Growing Power with a space to engage community and industry members in an active learning environment.



Gathering Space Lighting Scheme

The lighting scheme within the gathering space was planned to work with the linear mechanical scheme to minimize conflicts with structure. ElumTools was used to ensure that the proper illuminance could be achieved in the space with the linear lighting scheme. Information exchanges within Revit were crucial to avoid conflicts between systems before group clash detection took place.



Transfer Element Design Methodology


The structural transfer elements were limited in depth by the plenum depth to avoid impeding upon the gathering space while providing area for MEP systems. As discussed in the Structural Report, the structural partners originally explored the use of typical W-shapes, castellated beams, story trusses, and plate girders, but these options were deemed unfeasible for various reasons. As a result, the structural partners developed the concept of attaching steel plates to W-shapes to achieve the necessary section properties to control deflection, while simultaneously limiting depth of the elements.



Mechanical Systems Layout and Acoustic Analysis

Effective information exchanges between structural, mechanical and electrical design partners were key to the successful execution of the gathering space design. The elimination of the center column line opened up the gathering space, but put additional stress on the mechanical layout. Autodesk Revit was used to coordinate structural, mechanical and electrical systems early on in the project to avoid physical system clashes in the future.

Once the gathering space was designed the mechanical partners performed a reverberation time calculation on the gathering space to insure that the design would be appropriate for the intended uses of the space. An optimum reverberation time of 0.69 seconds was achieved by coordinating appropriate acoustical materials in the ceiling using input from the construction and electrical partners.



TBD ENGINEERING | PROJECT DECISION MATRIX


Project Decision Matrix												
Option	Notes/ Justification	1	2	3	4	5	6	7	8	9	10	Decision
Mechanical Systems												
FCU w/DOAS	Save energy by recirculation	5	4	3	4	1	4	5	3	3	4	
Valance Clg & Htg w/ DOAS	Eliminates Fan Power assoc. w/ Clg & Htg	4	4	3	4	4	5	4	3	3	4	
WSHP w/ DOAS	Heat Rejection to Water Loop	4	4	3	4	5	3	4	3	3	5	Heat rejection to aquaponic system if present
Ground Source Heat Pump	Heat Rejection to Ground	4	3	3	4	5	3	3	2	3	4	
Electrical Distribution Options												
DC	renewable energy driven	2	4	3	3	5	3	5	2	3	5	
AC	standard from grid	4	5	3	3	3	3	5	3	3	3	X
Generator Location Options												
Generator Outside		5	2	3	3	5	5	2	5	3	3	Invasive to site, prototypability affected
Generator Basement	added areaway for maintenance, out of public eye	2	5	3	3	3	2	2	2	3	3	X
Generator Roof		4	4	3	3	1	4	2	1	3	3	Invasive to growing spaces, fuel storage must be pumped vertically
Grow Light Options												
LED	more specific wavelengths generated	5	4	3	5	5	3	4	4	3	4	X
HID		3	3	3	3	5	3	3	1	3	3	more power required, more maintenance
Support Space Lighting Options												
LED		5	3	3	5	4	3	4	5	3	4	X
FLUORESCENT		3	3	3	3	1	4	4	3	3	3	more power required, more maintenance
Gravity System												
Steel Noncomposite		4	2	3	3	3	3	3	2	5	2	
Steel Composite		4	2	2	3	3	4	3	3	5	2	X
Steel Castellated Beams		4	3	3	3	4	5	3	5	4	4	Manufacturing different
Timber Framing		2	2	5	3	4	2	1	2	2	4	Slightly specialized market
Concrete Two2way slab		2	4	4	3	3	3	3	3	5	2	
Concrete pre-cast double tee		4	2	4	3	3	4	4	2	2	4	Slightly specialized market
Concrete Post tension		3	3	3	3	3	5	4	4	3	2	
Concrete Bubble deck		2	4	5	3	4	4	3	2	1	5	Extremely specialized market
Acetylated wood		2	2	5	3	4	3	5	3	4	5	
Foundation System												
Mat Foundation		4	3	3	3	3	2	4	3	5	3	
Spread/Strip Footing		4	4	3	3	3	5	4	4	5	3	X
Beam (Grillage)		2	3	3	3	3	2	2	3	4	3	
Deep Foundations		2	2	3	3	3	2	3	2	2	4	Expensive, invasive, slow
Slurry Wall		2	2	3	3	3	3	3	2	2	4	Expensive, invasive, slow
Geopiers		4	4	4	3	4	5	4	4	2	5	X
Lateral Systems												
Steel Moment Frame	Requires Steel Gravity System	5	5	3	3	3	2	3	5	4	3	X
Steel Braced Frame		2	4	3	3	3	3	3	3	4	3	
Masonry Shear Walls		2	2	4	3	3	3	4	1	4	3	
Concrete Moment Frame	Requires Concrete Gravity System	5	5	4	3	3	4	4	4	4	3	
Concrete Shear Wall		2	3	4	3	3	4	4	2	4	3	
Green House Structural System												
Wood		2	2	4	3	4	5	1	2	5	4	
Steel		5	4	4	3	3	5	4	4	5	3	
Non-toxic Treated Wood		4	2	5	3	4	4	5	3	4	5	X
Façade Systems												
Precast Panel		3	1	2	3	4	4	4	3	3	2	
Brick Cavity Wall		2	2	2	3	3	3	4	3	3	2	Efflorescence, moisture, weight, slow
Rain Screen		5	5	3	5	5	3	4	5	2	4	Terra Cotta shipping location
Renewable Energy On Site												
Solar Power		3	5	5	5	4	5	3	2	-	3	Milwaukee building blocking some sunlight
Wind Power		2	5	5	5	4	5	3	2	-	3	Invasive to Milwaukee site
Anaerobic Digestion	Use food waste for primary fuel for CHP	2	4	3	3	5	4	2	3	3	4	X
Rainwater Collection	Effectiveness for GH and Rest of Building	4	3	3	3	5	4	4	3	3	4	X

In order to consider a wide variety of options for the Growing Power facility, TBD developed and implemented a project decision matrix, shown left. Each design partner developed a list of options for various systems, listed in the leftmost column of the matrix. Each option was evaluated against the project goals (shown below) in each row, on a scale of 1-4. Project specific goals that fit into the 4 overarching goals of flexibility, community, economy, and sustainability are color coded as such.

Project Goals	
1	Flexibility/ Adaptability to account for multiple space types/ locations
2	Prototypability of building/ ability to replicate in other locations
3	Recyclability of materials
4	Energy Saving Potential
5	Educational value
6	Economic use of materials
7	Maintainability of system for life span
8	Consideration of other systems (depth, size, etc.)
9	Specialized Market
10	Innovation



TBD ENGINEERING | DESIGN SCHEDULE




Throughout the design phases, TBD set milestones during detailed in the process map to the left. The process map into horizontal swimlanes according to the developed design packages contained in the Growing Power facility. Tasks described in the process map are filled with a color to indicate the responsible partner; orange indicates management tasks, blue indicates mechanical tasks, yellow indicates electrical tasks, red indicates structural tasks, and purple indicates tasks that require input from all disciplines. Tasks can be seen displayed chronologically from left to right, in order of expected completion, to maintain a continuous, efficient workflow.

The process map was developed in parallel with TBD's collaborative planning sessions, as a way to visually represent the flow of the project's development. The map was continuously updated with each planning session, and displayed in the team's co-located office space to guide the team.

TBD ENGINEERING | COST TRENDING ANALYSIS


Cost Trending- Overall Project by Package

Milestone	Growing Spaces	Admin and Learning	Market and Service	Gathering Space	Back of House	Miscellaneous	G-Sitework	Renewable Allowance	Contingency	TV Low	TV	"OH SHIT"
Ideation (Rev0)	\$ 2,850,710.36	\$ 2,267,737.50	\$ 1,573,687.24	\$ 1,479,187.50	\$ 2,685,900.00	\$ 2,947,612.50	\$ 1,380,483.51	\$ 2,760,967.02	\$ 4,141,450.53	\$ -	\$ 10,185,185.19	\$ 11,000,000.00
Ideation (Rev1)	\$ 2,280,568.29	\$ 1,814,190.00	\$ 1,258,949.79	\$ 1,183,350.00	\$ 2,148,720.00	\$ 2,358,090.00	\$ 1,104,386.61	\$ 2,208,773.62	\$ 3,313,160.42	\$ -	\$ 10,185,185.19	\$ 11,000,000.00
Schematic (Rev2)	\$ 2,774,618.12	\$ 2,558,870.72	\$ 967,171.22	\$ 1,669,086.30	\$ 1,607,761.83	\$ 1,764,421.19	\$ 1,134,192.94	\$ 2,268,385.88	\$ 2,835,482.34	\$ -	\$ 10,185,185.19	\$ 11,000,000.00
Schematic (Rev3)	\$ 2,219,694.49	\$ 2,047,096.58	\$ 773,736.98	\$ 1,335,269.04	\$ 1,286,209.47	\$ 1,411,536.95	\$ 907,354.35	\$ 1,814,708.70	\$ 2,268,385.88	\$ -	\$ 10,185,185.19	\$ 11,000,000.00
STR Development	\$ 2,344,743.11	\$ 1,990,445.63	\$ 862,689.26	\$ 1,298,317.06	\$ 1,274,078.33	\$ 1,398,223.77	\$ 916,849.72	\$ 1,833,699.43	\$ 1,833,699.43	\$ -	\$ 10,185,185.19	\$ 11,000,000.00
ENC Development	\$ 2,527,497.21	\$ 1,916,099.93	\$ 895,190.54	\$ 1,249,823.26	\$ 1,392,363.17	\$ 1,528,034.21	\$ 950,900.83	\$ 1,901,801.67	\$ 1,901,801.67	\$ -	\$ 10,185,185.19	\$ 11,000,000.00
GRW Development	\$ 2,527,497.21	\$ 1,916,099.93	\$ 895,190.54	\$ 1,249,823.26	\$ 1,392,363.17	\$ 1,528,034.21	\$ 950,900.83	\$ 1,901,801.67	\$ 1,426,351.25	\$ -	\$ 10,369,532.43	\$ 11,000,000.00
BOH Development	\$ 2,314,127.57	\$ 1,916,099.93	\$ 895,190.54	\$ 1,249,823.26	\$ 1,515,925.25	\$ 1,528,034.21	\$ 941,920.08	\$ 1,517,000.00	\$ 1,412,880.11	\$ -	\$ 10,369,532.43	\$ 11,000,000.00
ADM Development	\$ 2,314,127.57	\$ 1,777,489.02	\$ 895,190.54	\$ 1,249,823.26	\$ 1,515,925.25	\$ 1,528,034.21	\$ 928,058.99	\$ 1,017,000.00	\$ 928,058.99	\$ -	\$ 10,369,532.43	\$ 11,000,000.00
GTH Development	\$ 2,314,127.57	\$ 1,777,489.02	\$ 895,190.54	\$ 1,159,410.88	\$ 1,515,925.25	\$ 1,528,034.21	\$ 919,017.75	\$ 1,017,000.00	\$ 919,017.75	\$ -	\$ 10,369,532.43	\$ 11,000,000.00
MKT Development	\$ 2,314,127.57	\$ 1,777,489.02	\$ 929,549.50	\$ 1,159,410.88	\$ 1,515,925.25	\$ 1,528,034.21	\$ 922,453.64	\$ 1,017,000.00	\$ 691,840.23	\$ -	\$ 10,369,532.43	\$ 11,000,000.00



Cost Tracking- Overall Project by Division


Milestone	A-Sub	B10-Super	B20-Enc	B30-Roof	C-Int	D10-Conv	D20-Plumb	D30-HVAC	D40-FP	D50-Elec	E-Equip	F-Special	G-Sitework	Renewables	Contingency
Ideation (Rev0)	\$ 1,426,785.68	\$ 1,623,176.63	\$ 1,746,423.53	\$ 504,338.10	\$ 2,146,776.19	\$ 486,055.50	\$ 826,798.61	\$ 1,393,387.54	\$ 636,243.83	\$ 2,492,143.24	\$ 190,329.04	\$ 332,377.24	\$ 1,380,483.51	\$ 2,760,967.02	\$ 4,141,450.53
Ideation (Rev1)	\$ 1,141,428.54	\$ 1,298,541.30	\$ 1,397,138.82	\$ 403,470.48	\$ 1,717,420.95	\$ 388,844.40	\$ 661,438.89	\$ 1,114,710.03	\$ 508,995.06	\$ 1,993,714.59	\$ 152,263.23	\$ 265,901.79	\$ 1,104,386.81	\$ 2,208,773.62	\$ 3,313,160.42
Schematic (Rev2)	\$ 935,318.04	\$ 1,396,450.90	\$ 1,464,346.71	\$ 332,387.89	\$ 1,927,299.51	\$ 538,739.76	\$ 708,072.52	\$ 1,248,630.32	\$ 464,046.02	\$ 2,012,656.89	\$ 115,022.03	\$ 198,958.80	\$ 1,134,192.94	\$ 2,268,385.88	\$ 2,835,482.34
Schematic (Rev3)	\$ 748,254.43	\$ 1,117,160.72	\$ 1,171,477.37	\$ 265,910.31	\$ 1,541,839.60	\$ 430,991.81	\$ 566,458.02	\$ 998,904.26	\$ 371,236.82	\$ 1,610,125.51	\$ 92,017.62	\$ 159,167.04	\$ 907,354.35	\$ 1,814,708.70	\$ 2,268,385.88
STR Development	\$ 770,370.25	\$ 1,189,998.55	\$ 1,171,477.37	\$ 265,910.31	\$ 1,541,839.60	\$ 430,991.81	\$ 566,458.02	\$ 998,904.26	\$ 371,236.82	\$ 1,610,125.51	\$ 92,017.62	\$ 159,167.04	\$ 916,849.72	\$ 1,833,699.43	\$ 1,833,699.43
ENC Development	\$ 770,370.25	\$ 1,189,998.55	\$ 1,195,257.05	\$ 582,641.80	\$ 1,541,839.60	\$ 430,991.81	\$ 566,458.02	\$ 998,904.26	\$ 371,236.82	\$ 1,610,125.51	\$ 92,017.62	\$ 159,167.04	\$ 950,900.83	\$ 1,901,801.67	\$ 1,901,801.67
GRW Development	\$ 770,370.25	\$ 1,189,998.55	\$ 1,195,257.05	\$ 582,641.80	\$ 1,541,839.60	\$ 430,991.81	\$ 566,458.02	\$ 998,904.26	\$ 371,236.82	\$ 1,610,125.51	\$ 92,017.62	\$ 159,167.04	\$ 950,900.83	\$ 1,901,801.67	\$ 1,426,351.25
BOH Development	\$ 770,370.25	\$ 1,189,998.55	\$ 1,195,257.05	\$ 582,641.80	\$ 1,541,839.60	\$ 430,991.81	\$ 566,458.02	\$ 998,904.26	\$ 371,236.82	\$ 1,610,125.51	\$ 92,017.62	\$ 159,167.04	\$ 941,920.08	\$ 1,517,000.00	\$ 1,412,880.11
ADM Development	\$ 770,370.25	\$ 1,189,998.55	\$ 1,195,257.05	\$ 582,641.80	\$ 1,541,839.60	\$ 430,991.81	\$ 566,458.02	\$ 770,485.78	\$ 371,236.82	\$ 1,610,125.51	\$ 92,017.62	\$ 159,167.04	\$ 928,058.99	\$ 1,017,000.00	\$ 928,058.99
GTH Development	\$ 770,370.25	\$ 1,189,998.55	\$ 1,195,257.05	\$ 582,641.80	\$ 1,541,839.60	\$ 430,991.81	\$ 566,458.02	\$ 680,073.41	\$ 371,236.82	\$ 1,610,125.51	\$ 92,017.62	\$ 159,167.04	\$ 919,017.75	\$ 1,017,000.00	\$ 919,017.75
MKT Development	\$ 770,370.25	\$ 1,189,998.55	\$ 1,195,257.05	\$ 582,641.80	\$ 1,541,839.60	\$ 430,991.81	\$ 566,458.02	\$ 714,432.36	\$ 371,236.82	\$ 1,610,125.51	\$ 92,017.62	\$ 159,167.04	\$ 922,453.64	\$ 1,017,000.00	\$ 691,840.23




In order to continually evaluate project costs against their targets, an in-depth analysis was devised. The overall project tracked designed costs by Integrated Design Packages and by Uniformat II divisions, shown to the left. The 6 IDPs were broken down further by Uniformat II divisions, with examples shown below. The multi-layer approach allowed TBD to quickly identify alarming trends through the course of the project's development and utilize cost as an informant to design, rather than a "design now, estimate later" approach which, more often than not, results in cost cutting techniques rather than truly engineering value as defined by the ownership partners at Growing Power.

At the end of the project's development, the project estimate stood at a value of \$11.9 million, including a \$1 million allowance for a Combined Heat and Power plant in the Back of House area, and rainwater and groundwater harvesting systems.


Milestone	A-Sub	B10-Super	B20-Enc	B30-Roof	C-Int	D10-Conv	D20-Plumb	D30-HVAC	D40-FP	D50-Elec	E-Equip	F-Special	G2-Demolition	TV Low	TV	"OH SHIT"
Ideation (Rev0)	\$ 99,675.19	\$ 259,155.49	\$ 185,111.06	\$ 51,261.53	\$ 793,705.78	\$ 62,652.98	\$ 418,635.79	\$ 412,940.06	\$ 65,000.84	\$ 501,223.80	\$ 2,847.86	\$ -	\$ -	\$ -	\$ -	\$ -
Ideation (Rev1)	\$ 79,746.15	\$ 207,424.39	\$ 148,088.85	\$ 41,009.22	\$ 633,364.62	\$ 50,122.38	\$ 334,908.63	\$ 330,352.05	\$ 52,400.67	\$ 400,979.04	\$ 2,278.29	\$ -	\$ -	\$ -	\$ -	\$ -
Schematic (Rev2)	\$ 97,014.62	\$ 252,380.01	\$ 180,170.01	\$ 49,891.23	\$ 770,573.26	\$ 60,980.62	\$ 407,465.40	\$ 401,917.21	\$ 63,752.46	\$ 487,844.94	\$ 2,773.85	\$ -	\$ -	\$ -	\$ -	\$ -
Schematic (Rev3)	\$ 72,611.70	\$ 201,970.61	\$ 144,181.01	\$ 39,914.59	\$ 616,458.61	\$ 48,784.49	\$ 325,969.12	\$ 325,534.17	\$ 51,001.97	\$ 390,275.95	\$ 2,217.48	\$ -	\$ -	\$ -	\$ -	\$ -
STR Development	\$ 158,937.85	\$ 245,512.87	\$ 246,597.77	\$ 120,206.92	\$ 616,458.61	\$ 48,784.49	\$ 325,969.12	\$ 325,534.17	\$ 51,001.97	\$ 390,275.95	\$ 2,217.48	\$ -	\$ -	\$ -	\$ -	\$ -
ENC Development	\$ 158,937.85	\$ 245,512.87	\$ 246,597.77	\$ 120,206.92	\$ 616,458.61	\$ 48,784.49	\$ 325,969.12	\$ 325,534.17	\$ 51,001.97	\$ 390,275.95	\$ 2,217.48	\$ -	\$ -	\$ -	\$ -	\$ -
GRW Development	\$ 158,937.85	\$ 245,512.87	\$ 246,597.77	\$ 120,206.92	\$ 616,458.61	\$ 48,784.49	\$ 325,969.12	\$ 325,534.17	\$ 51,001.97	\$ 390,275.95	\$ 2,217.48	\$ -	\$ -	\$ -	\$ -	\$ -
BOH Development	\$ 158,937.85	\$ 245,512.87	\$ 246,597.77	\$ 120,206.92	\$ 616,458.61	\$ 48,784.49	\$ 325,969.12	\$ 325,534.17	\$ 51,001.97	\$ 390,275.95	\$ 2,217.48	\$ -	\$ -	\$ -	\$ -	\$ -
ADM Development	\$ 158,937.85	\$ 245,512.87	\$ 246,597.77	\$ 120,206.92	\$ 616,458.61	\$ 48,784.49	\$ 325,969.12	\$ 325,534.17	\$ 51,001.97	\$ 390,275.95	\$ 2,217.48	\$ -	\$ -	\$ -	\$ -	\$ -
GTH Development	\$ 158,937.85	\$ 245,512.87	\$ 246,597.77	\$ 120,206.92	\$ 616,458.61	\$ 48,784.49	\$ 325,969.12	\$ 325,534.17	\$ 51,001.97	\$ 390,275.95	\$ 2,217.48	\$ -	\$ -	\$ -	\$ -	\$ -
MKT Development	\$ 158,937.85	\$ 245,512.87	\$ 246,597.77	\$ 120,206.92	\$ 616,458.61	\$ 48,784.49	\$ 325,969.12	\$ 325,534.17	\$ 51,001.97	\$ 390,275.95	\$ 2,217.48	\$ -	\$ -	\$ -	\$ -	\$ -



Milestone	A-Sub	B10-Super	B20-Enc	B30-Roof	C-Int	D10-Conv	D20-Plumb	D30-HVAC	D40-FP	D50-Elec	E-Equip	F-Special	G2-Demolition	TV Low	TV	"OH SHIT"
Ideation (Rev0)	\$ 47,622.49	\$ 371,008.95	\$ 394,586.31	\$ 113,338.69	\$ 980,050.85	\$ 256,259.34	\$ 63,496.65	\$ 294,865.88	\$ 65,764.39	\$ 373,208.95	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Ideation (Rev1)	\$ 38,097.99	\$ 297,527.16	\$ 315,699.06	\$ 92,070.95	\$ 812,040.68	\$ 205,003.47	\$ 50,797.32	\$ 235,844.70	\$ 52,811.51	\$ 297,527.16	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Schematic (Rev2)	\$ 53,736.29	\$ 419,654.80	\$ 445,243.51	\$ 12,794.35	\$ 440,125.76	\$ 289,152.39	\$ 71,648.38	\$ 332,653.19	\$ 74,207.25	\$ 419,654.80	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Schematic (Rev3)	\$ 42,989.03	\$ 335,723.84	\$ 356,194.80	\$ 10,235.48	\$ 352,100.61	\$ 231,321.91	\$ 57,318.70	\$ 266,122.55	\$ 59,365.80	\$ 335,723.84	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
STR Development	\$ 126,561.35	\$ 195,500.57	\$ 196,364.47	\$ 95,720.12	\$ 352,100.61	\$ 231,321.91	\$ 57,318.70	\$ 266,122.55	\$ 59,365.80	\$ 335,723.84	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
ENC Development	\$ 126,561.35	\$ 195,500.57	\$ 196,364.47	\$ 95,720.12	\$ 352,100.61	\$ 231,321.91	\$ 57,318.70	\$ 266,122.55	\$ 59,365.80	\$ 335,723.84	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
GRW Development	\$ 126,561.35	\$ 195,500.57	\$ 196,364.47	\$ 95,720.12	\$ 352,100.61	\$ 231,321.91	\$ 57,318.70	\$ 266,122.55	\$ 59,365.80	\$ 335,723.84	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
BOH Development	\$ 126,561.35	\$ 195,500.57	\$ 196,364.47	\$ 95,720.12	\$ 352,100.61	\$ 231,321.91	\$ 57,318.70	\$ 266,122.55	\$ 59,365.80	\$ 335,723.84	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
ADM Development	\$ 126,561.35	\$ 195,500.57	\$ 196,364.47	\$ 95,720.12	\$ 352,100.61	\$ 231,321.91	\$ 57,318.70	\$ 127,511.64	\$ 59,365.80	\$ 335,723.84	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
GTH Development	\$ 126,561.35	\$ 195,500.57	\$ 196,364.47	\$ 95,720.12	\$ 352,100.61	\$ 231,321.91	\$ 57,318.70	\$ 127,511.64	\$ 59,365.80	\$ 335,723.84	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
MKT Development	\$ 126,561.35	\$ 195,500.57	\$ 196,364.47	\$ 95,720.12	\$ 352,100.61	\$ 231,321.91	\$ 57,318.70	\$ 127,511.64	\$ 59,365.80	\$ 335,723.84	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -



TBD ENGINEERING | BASEMENT FLOOR PLAN



Mechanical Room Expansion


Freezer and Cooler Storage

Community Elevator and MEP Shaft Added



Top: Basement Floor Plan as provided to the team
Bottom: Modified Basement Floor Plan by TBD

TBD ENGINEERING | LEVEL 1 FLOOR PLAN




Wall Addition for Food Processing Separation

Redefined Freezer and Cooler Storage

Community Stairwell Addition


Community Elevator and MEP Shaft Added




Top: Level 1 Floor Plan as provided to the team

Bottom: Modified Level 1 Floor Plan by TBD

TBD ENGINEERING | LEVEL 2 FLOOR PLAN



Auziliary Mechanical and Electrical Space Added




Community Stairwell Addition


Community Elevator and MEP Shaft Added

Top: Level 2 Floor Plan as provided to the team
Bottom: Modified Level 2 Floor Plan by TBD

TBD ENGINEERING | LEVEL 3 FLOOR PLAN



IT Room Added




Community Stairwell Addition

Community Elevator and MEP Shaft Added

Top: Level 3 Floor Plan as provided to the team
Bottom: Modified Level 3 Floor Plan by TBD


TBD ENGINEERING | LEVEL 4 FLOOR PLAN



Auziliary Mechanical and Electrical Space Added


Community Elevator and MEP Shaft Added

Added Collaboration Space




Top: Level 4 Floor Plan as provided to the team
Bottom: Modified Level 4 Floor Plan by TBD

TBD ENGINEERING | LEVEL 5 FLOOR PLAN



Mechanical Equipment
Roof Space



Top: Level 5 Floor Plan as provided to the team
Bottom: Modified Level 5 Floor Plan by TBD