AE 481W

Technical Assignment 1: Construction Project Management



Jonathan Revtai

Construction Management Consultant: Dr. Riley Bakery Square – Building 1 9/29/2008

Ρ

R OWNER/ DEVELOPER BAKERY SQUARE J HOLDINGS, L.P. Ε ARCHITECT С Т ASTORINO Т CM AT RISK E Α P.J. DICK INC. M

BUILDING 1 AT BAKERY SQUARE

BUILDING 1 IS PART OF THE BAKERY SQUARE PROJECT BUILT AROUND THE RENOVATION OF THE 1918 NABISCO FACTORY. THIS FACILITY INCLUDES RETAIL SPACES, A FITNESS CENTER, RE-STARAUNTS, AND A PARKING GARAGE. THE PARKING GARAGE STRUCTURE IS BUILT AROUND ALL OF THE OTHER SPACES INCLUDING A CAST-IN-PLACE SWIMMING POOL ON LEVEL TWO. FACADE FINISHES WILL BE PROVIDED DURING FIT OUT, AND HAVE NOT BEEN FINALIZED.

PITTSBURGH, PA

SERINAL

MEP

ROOF TOP UNITS ARE USED TO CONDITION THE RETAIL FITNESS SPACES, WHILE WALL UNITS ARE USED IN THE PARKING GARAGE SECTION. PLUMBING IS LIMITED TO BATH-ROOMS

ELECTRICAL

THE FITNESS CENTER IS FED BY A SEPARATE SWITCH BOARD FROM THE REST OF THE BUILDING. THE FEED TO EACH SWITCH-BOARD IS A 3 PHASE, 480 V CONNECTION.

STRUCTURAL

PRECAST CONCRETE IS USED FOR MOST OF THE SUPERSTRUCTURE. STRUCTURAL STEEL IS USED FOR AN OUTSIDE BRIDGE, AND A HANG-ING MEZZANINE IN THE FITNESS CENTER.THE FOUNDATIONS ARE BUILT WITH AUGUER CAST PILES.



Building 1 at Bakery Square

EXECUTIVE SUMMARY

Building 1 at Bakery Square cannot be considered as a typical project. The building is just one of five facilities that are being built on site, and therefore the general conditions differ from most jobs because the construction manager is already in place for other buildings. The functionality of the spaces in the building makes it difficult to estimate on a basic level.

Background information for this project is listed below. Completion of the project is scheduled for May 21, 2009. Erection of the structure will occur in a west to east fashion and building enclosure will be achieved by February 3, 2009.

A building systems summary has been included in this report. A few major areas of interest include a hanging steel mezzanine level inside the fitness center, a cast-in-place pool located on the second floor, and a building integration of retail space, fitness center, and parking garage.

Project cost estimations were performed using D4Cost2002 software and R.S. Means. Results from these investigations yielded a building cost of \$24,038,430 and \$22,946,120 respectively. Cost information was not available due to owner's request.

Local and site condition investigations did not reveal any major concerns. The largest amount of risk involved with the site is the existence of railroad tracks in unknown subsurface locations. With four other Bakery Square facilities being built on site, special planning may be required once all projects are under construction. Since a number of large scale projects have recently begun in the Pittsburgh area, subcontractors must plan carefully to ensure their labor forces are sufficient to meet schedule demands.

After research of Walnut Capital's interests, a few conclusions about their organization have been made. It is a priority of Walnut Capital to aid in the development of the surrounding community evident from the close proximity of their office and the project. Quality, cost, and scheduling goals must be accomplished in order for Building 1 to be labeled a successful project.

P.J. Dick is delivery the building as a construction manager at risk with a GMP. Subcontractors were selected based upon lump sum bids. Both project and staffing organizational charts have been included in this report and clearly show the chain of command.

Table of Contents

cecutive Summary	1
oject Schedule Summary	3
uilding Systems Summary	4
oject Cost Evaluation	7
te Plan of Existing Conditions	8
ocal Conditions	9
ient Information1	0
oject Delivery System 1	1
affing Plan 1	2
ppendix A: 1	3
ppendix B: 1	5
ppendix C:	3
ppendix D:	:5
Figure 1 - Project Schedule Summary	3
Figure 2 - Existing Site Conditions	8
Figure 3 - Project Organizational Chart1	1

PROJECT SCHEDULE SUMMARY

Construction for Building 1 at Bakery Square starts with the installation of auger cast piles from East to West. Foundation wall and pile cap placement follows while site rough grading is finished. Foundation construction is scheduled to take a little longer than three months. Precast erection quickly follows the foundation sequence and is scheduled to progress one bay at a time from West to East. Steel erection will occur about five months after the precast sequence starts. Finishes are very limited because the contract is for the parking garage and core and shell only. Building enclosure is scheduled for February 3, 2009, and makes it possible for fit-out of the unfinished spaces to begin.

Project Schedule	e Summary		_		Classic	WBS La	iyout				29-Sep-08 14:14 2008 2009 22 Q3 Q4 Q1 Q2 Q3 Q4 02-S n Procurement Sitework					
Activity ID	Activity Name	Original	Start	Finish		2	007		8	2	008	-	8	20	9	
		Duration			1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Buildin	ng 1 @ Bakery Sq	697	02-Jan-07	02-Sep-09			1 1 1			: : :	1 1 1					02-Sep
01	Design	300	02-Jan-07	25-Feb-08	-					Design						
02	Procurement	351	03-Dec-07	06-Apr-09										Procu	ement	1.13
03	Sitework	124	25-Mar-08	12-Sep-08								Sitework				
04	Foundations - East	51	27-Mar-08	05-Jun-08						\rightarrow	Foundatio	ns - East				
05	Foundations - Center	65	01-Apr-08	30-Jun-08					111		Found	tions - Ce	inter	1111		
06	Foundations - West	49	23-Apr-08	30-Jun-08							Found	tions - W	est			1.13
07	Mobilize Crane - Precast	5	09-Jul-08	15-Jul-08			111			111	I Mobi	ze Crane	- Precast		111	1.13
08	Start Precast Erection	0	16-Jul-08								+ Start	Precast E	rection			111
09	Erect Precast - West	58	16-Jul-08	03-Oct-08								Erect F	recast - V	West		
10	100% GMP	0		06-Aug-08	11		TTT	111	TT	111	• 10	% GMP	I I I	TTT		111
11	Masonry	112	29-Sep-08	03-Mar-09										Masonry		
12	Erect Precast - Center	35	06-Oct-08	21-Nov-08						111	111	E	ect Preca	ast - Cent	er	
13	Water Protection / Expa	82	23-Oct-08	13-Feb-09			1 1 1			111	111		w w	ater Prote	ction / E	xpansion
14	Install Elevators	123	10-Nov-08	29-Apr-09							111			inst	all Eleva	tors
15	Erect Precast - East	32	24-Nov-08	06-Jan-09			TTT		TT	TTT	TTT		Erect	Precast -	East	
17	Plumbing	59	24-Nov-08	12-Feb-09			111				111		PI	umbing		
16	Fire Protection	59	24-Nov-08	12-Feb-09			111			111	111		Fir	e Protect	ion	111
18	Electrical	69	24-Nov-08	27-Feb-09						111				ectrical		
19	Erect / Detail Mezzanine	22	15-Dec-08	13-Jan-09									Erect	/ Detail N	lezzanin	e Steel
20	Install Permanent Power	30	22-Jan-09	04-Mar-09					TT	TTT				Install Per	manent	Power
21	Building Enclosure	0		03-Feb-09			111			111			🔶 Bui	Iding Enc	osure	
22	Glass / Glazing	25	04-Feb-09	10-Mar-09							111			Glass / G	lazing	
25	Urban Active Fit-out	110	02-Mar-09	31-Jul-09			1 1 1			111	111		: : 🗖		🗖 Úr	ban Activ
24	Houlihans Fit-out	110	02-Mar-09	31-Jul-09											He	ulihans I
23	Retail Tenant Fit-out	132	03-Mar-09	02-Sep-09			TTT		TT	TTT	TTT					Retail T
26	Anthropolgie Fit-out	88	01-Apr-09	31-Jul-09											An An	thropolg
27	Garage / C&S Substanti	0		21-May-09			111			111	111			• G	arage / (C&S Sub

• Figure 1 - Project Schedule Summary

Note: See Appendix A for full a full page version of the Project Schedule Summary.

BUILDING SYSTEMS SUMMARY

Demolition	Demolition for Building 1 at Bakery Square was limited to the
Required	removal of an existing parking lot and storm sewer system.
	Hazardous materials were not encountered during demolition.
	However, buried rail lines were discovered during excavation
	and needed to be removed in certain locations in order to
	construct the foundations.
Structural Steel	The design for Building 1 specifies structural steel to be used
Frame	in three places. Structural steel is used inside the fitness
	center for the mezzanine level, along the south façade as the
	main support for the apron, and for a pedestrian bridge
	located on the 4 th floor that connects Building 1 to the
	existing Building 3.
	Wide flanged members will be used in all three of these
	areas, and metal tube is required for the bridge and the
	apron. A hand winch material lift will be used to hoist most
	of the steel. Larger members, such as the W33x354, will be
	erected with the Manitowoc 999 crane that is being used for
	the precast concrete erection.
	Hanging columns, attached to steel supports located under
	the 4^{th} floor's precast tees, will be used to support the
	metric i noor s precusit tees, will be used to support the metric support the metric interval $\Delta 5.1\%$ composite slab is specified for the
	mezzanine level
Cast In Place	Construction of the foundations, slabs-on-grade, and the
Concrete (CIP)	swimming pool were accomplished using CIP methods.
	Placement was performed by direct chute or pumping.
	MevaLite, a lightweight clamp system, was used for forming
	purposes.
Precast Concrete	Sidley Precast Group was awarded the precast concrete
	package for Building 1. The firm is located in Thompson,
	Ohio, approximately 130 miles from the job site.

Precast Concrete								
(Continued)	Connections for the precast pieces include the following							
(continuou)	methods:							
	Columns							
	 Tube steel splice connections are used to aid with 							
	initial alignment between the columns.							
	 For final adjustment, plate welding is performed 							
	to secure the columns in place.							
	Structural Tees							
	 Tees are shimmed and grouted to the spandrels. 							
	 JVI vector connectors are used for tee-to-tee 							
	connections.							
	Spandrels							
	 Dywidag bars, a type of post-tensioning system, 							
	connect the spandrels to the columns in order to							
	achieve proper shear strength.							
	A Maintower 900 crawler crane is being used to creat the							
	A Maintowood 999 clawler change is being used to elect the							
	at the west and of the building with the grape located inside							
	the building footprint. The structure will be erected one hav							
	at a time, and the crane will move across the building							
	footprint from West to East							
	Tootprint from West to Last.							
Mechanical System	There are multiple mechanical systems in place in this							
	building due to the varying functionalities of the spaces. In							
	the Garage portion of the building, electrical wall heaters,							
	cabinet unit heaters, electric duct coils, and packaged							
	terminal AC (PTAC) units are placed in the lobbies and garage							
	office areas.							
	The restaurant, retail spaces, and the fitness center each							
	have their own separate forced air roof top units for heating							
	and cooling purposes, but are not included in this contract.							
	These units will be located on the low roots located directly							
	above level 1 and level 3.							
	Inside the parking garage, manual dry standpipes in the							
	stairwells are designated for fire protection. All other areas							
	will fulfill fire suppression requirements through the use of							
	sprinklers.							

Electrical System	A main switchhoard is dedicated to the fitness center, while								
Electrical System	the retail space and garage st	pare another separate							
	switchboard Both switchboard	rds have the following size and							
	sonacity attributor	Tus have the following size and							
	capacity attributes:								
	Retail & Garage	Fitness Center							
	- 480/277 V	- 480/277 V							
	- 3 Phase	- 3 Phase							
	- 4 W 2000 A	- 4W 2500A							
	- 80 KAIC	- 80 KAIC							
	switchboard. Both switchboards have the following size and capacity attributes: Retail & Garage Fitness Center - 480/277 V - 480/277 V - 3 Phase - 3 Phase - 4 W 2000 A - 4W 2500A - 80 KAIC - 80 KAIC A backup generator provides temporary power to the elevators, emergency lighting, and emergency systems located in the building should the power supply be disrupted. Temporary power is produced using a diesel generator with the following properties: • 100 KW • 480/277 V • 3 Phase • 4 Wire								
	A backup generator provides	temporary power to the							
	elevators, emergency lighting	, and emergency systems							
	located in the building should the power supply be disrupted.								
	Temporary power is produced using a diesel generator with								
	the following properties:								
	• 100 KW								
	• 480/277 V								
	3 Phase								
	• 4 Wire								
Masonry	Non-load bearing masonry wa	alls are used for stainwells							
mason y	Non load bearing masoning we	and are used for stall wens,							
indoorn y	elevator lobbies, and to partit	ion interior rooms. The							
ind solid y	elevator lobbies, and to partit masonry walls are used to act	ion interior rooms. The hieve fire ratings where							
ind solid y	elevator lobbies, and to partit masonry walls are used to acl necessary and are covered wi	ion interior rooms. The hieve fire ratings where th metal joists and gypsum							
ind solid y	elevator lobbies, and to partit masonry walls are used to acl necessary and are covered wi wallboards. Scaffolding will b	ion interior rooms. The hieve fire ratings where th metal joists and gypsum e required for the walls but will							
	elevator lobbies, and to partit masonry walls are used to acl necessary and are covered wi wallboards. Scaffolding will b only be needed to span one s	ion interior rooms. The hieve fire ratings where th metal joists and gypsum e required for the walls but will tory at a time.							
ind solid y	elevator lobbies, and to partit masonry walls are used to acl necessary and are covered wi wallboards. Scaffolding will b only be needed to span one s	ion interior rooms. The hieve fire ratings where th metal joists and gypsum e required for the walls but will tory at a time.							
Curtain Wall	elevator lobbies, and to partit masonry walls are used to acl necessary and are covered wi wallboards. Scaffolding will b only be needed to span one s There is a curtain wall system	ion interior rooms. The hieve fire ratings where th metal joists and gypsum e required for the walls but will tory at a time.							
Curtain Wall	elevator lobbies, and to partit masonry walls are used to acl necessary and are covered wi wallboards. Scaffolding will b only be needed to span one s There is a curtain wall system has not yet been finalized. Th	ion interior rooms. The hieve fire ratings where th metal joists and gypsum e required for the walls but will tory at a time.							
Curtain Wall	elevator lobbies, and to partit masonry walls are used to acl necessary and are covered wi wallboards. Scaffolding will b only be needed to span one s There is a curtain wall system has not yet been finalized. Th installed in the punched open	ion interior rooms. The hieve fire ratings where th metal joists and gypsum e required for the walls but will tory at a time. In for the building but the design RACO window systems are to be ings throughout the rest of							
Curtain Wall	elevator lobbies, and to partit masonry walls are used to act necessary and are covered wi wallboards. Scaffolding will b only be needed to span one s There is a curtain wall system has not yet been finalized. Th installed in the punched open Building 1, and it is believed b	ion interior rooms. The hieve fire ratings where th metal joists and gypsum e required for the walls but will tory at a time. In for the building but the design RACO window systems are to be ings throughout the rest of by the construction manager							
Curtain Wall	elevator lobbies, and to partit masonry walls are used to ach necessary and are covered wi wallboards. Scaffolding will b only be needed to span one s There is a curtain wall system has not yet been finalized. Th installed in the punched open Building 1, and it is believed b that a TRACO system will be u	ion interior rooms. The hieve fire ratings where th metal joists and gypsum e required for the walls but will tory at a time. In for the building but the design RACO window systems are to be ings throughout the rest of by the construction manager used for the curtain wall.							
Curtain Wall	elevator lobbies, and to partit masonry walls are used to act necessary and are covered wi wallboards. Scaffolding will b only be needed to span one s There is a curtain wall system has not yet been finalized. Th installed in the punched open Building 1, and it is believed b that a TRACO system will be u	ion interior rooms. The hieve fire ratings where th metal joists and gypsum e required for the walls but will tory at a time. In for the building but the design RACO window systems are to be ings throughout the rest of by the construction manager used for the curtain wall.							
Curtain Wall	elevator lobbies, and to partit masonry walls are used to ach necessary and are covered wi wallboards. Scaffolding will b only be needed to span one s There is a curtain wall system has not yet been finalized. Th installed in the punched open Building 1, and it is believed b that a TRACO system will be u	ion interior rooms. The hieve fire ratings where th metal joists and gypsum e required for the walls but will tory at a time. In for the building but the design RACO window systems are to be ings throughout the rest of by the construction manager used for the curtain wall.							
Curtain Wall Support of Excavation	elevator lobbies, and to partit masonry walls are used to act necessary and are covered wi wallboards. Scaffolding will b only be needed to span one s There is a curtain wall system has not yet been finalized. Th installed in the punched open Building 1, and it is believed b that a TRACO system will be u None has been necessary dur Sufficient room on the site en	ion interior rooms. The hieve fire ratings where th metal joists and gypsum e required for the walls but will tory at a time. In for the building but the design RACO window systems are to be ings throughout the rest of by the construction manager used for the curtain wall. Ing construction of Building 1. abled excavators to use layback							
Curtain Wall Support of Excavation	elevator lobbies, and to partit masonry walls are used to ach necessary and are covered wi wallboards. Scaffolding will b only be needed to span one s There is a curtain wall system has not yet been finalized. Th installed in the punched open Building 1, and it is believed b that a TRACO system will be u None has been necessary dur Sufficient room on the site en methods. However, trench sh	ion interior rooms. The hieve fire ratings where th metal joists and gypsum e required for the walls but will tory at a time. In for the building but the design RACO window systems are to be ings throughout the rest of by the construction manager used for the curtain wall. Ing construction of Building 1. abled excavators to use layback horing will be required during							
Curtain Wall Support of Excavation	elevator lobbies, and to partit masonry walls are used to acl necessary and are covered wi wallboards. Scaffolding will b only be needed to span one s There is a curtain wall system has not yet been finalized. Th installed in the punched open Building 1, and it is believed b that a TRACO system will be u None has been necessary dur Sufficient room on the site en methods. However, trench sh placement of the storm water	ion interior rooms. The hieve fire ratings where th metal joists and gypsum e required for the walls but will tory at a time. In for the building but the design RACO window systems are to be ings throughout the rest of by the construction manager used for the curtain wall. Ing construction of Building 1. abled excavators to use layback horing will be required during tine.							
Curtain Wall Support of Excavation	elevator lobbies, and to partit masonry walls are used to ach necessary and are covered wi wallboards. Scaffolding will b only be needed to span one s There is a curtain wall system has not yet been finalized. Th installed in the punched open Building 1, and it is believed b that a TRACO system will be u None has been necessary dur Sufficient room on the site en methods. However, trench sh placement of the storm water	ion interior rooms. The hieve fire ratings where th metal joists and gypsum e required for the walls but will tory at a time. In for the building but the design RACO window systems are to be ings throughout the rest of by the construction manager used for the curtain wall. Ing construction of Building 1. abled excavators to use layback horing will be required during tine.							
Curtain Wall Support of Excavation	elevator lobbies, and to partit masonry walls are used to acl necessary and are covered wi wallboards. Scaffolding will b only be needed to span one s There is a curtain wall system has not yet been finalized. Th installed in the punched open Building 1, and it is believed b that a TRACO system will be u None has been necessary dur Sufficient room on the site en methods. However, trench sh placement of the storm water Temporary dewatering was ac	ion interior rooms. The hieve fire ratings where th metal joists and gypsum e required for the walls but will tory at a time. In for the building but the design RACO window systems are to be ings throughout the rest of by the construction manager used for the curtain wall. Ing construction of Building 1. abled excavators to use layback horing will be required during tine.							
Curtain Wall Support of Excavation	elevator lobbies, and to partit masonry walls are used to ach necessary and are covered wi wallboards. Scaffolding will b only be needed to span one s There is a curtain wall system has not yet been finalized. Th installed in the punched open Building 1, and it is believed b that a TRACO system will be u None has been necessary dur Sufficient room on the site en methods. However, trench sh placement of the storm water Temporary dewatering was ac Elevator pits will house perma	ion interior rooms. The hieve fire ratings where th metal joists and gypsum e required for the walls but will tory at a time. In for the building but the design RACO window systems are to be ings throughout the rest of by the construction manager used for the curtain wall. Ing construction of Building 1. abled excavators to use layback horing will be required during tine.							
Curtain Wall Support of Excavation	elevator lobbies, and to partit masonry walls are used to acl necessary and are covered wi wallboards. Scaffolding will b only be needed to span one s There is a curtain wall system has not yet been finalized. Th installed in the punched open Building 1, and it is believed b that a TRACO system will be u None has been necessary dur Sufficient room on the site en methods. However, trench sh placement of the storm water Temporary dewatering was ac Elevator pits will house perma achieve dewatering after conse	ion interior rooms. The hieve fire ratings where th metal joists and gypsum e required for the walls but will tory at a time. In for the building but the design RACO window systems are to be ings throughout the rest of by the construction manager used for the curtain wall. Ing construction of Building 1. abled excavators to use layback moring will be required during tine.							

PROJECT COST EVALUATION

Parametric estimating with **D4Cost2002** yielded a result of \$24,038,430. Results were based on a 6 story parking garage structure. Since the building is either a parking garage structure or an unfinished core and shell building, the closest building in the database would be a similar parking garage structure. The estimate is based off of a three similar parking garage structures that were close to the same square foot and story height. Results are less than \$40,000 or .2% of the building cost.

Multiple building types were used to perform a square foot estimate with *R.S. Means* because of the varying functions in the structure. A 5 story parking garage was used to estimate the garage portion of the building, and a 1 story retail store with a 14' height was used for the retail, restaurant, and fitness portion. The square foot estimate for the parking garage came to be \$11,881,688 with a square foot cost of \$42.95. The square foot estimate for the retail portion equaled \$11,064,432 with a square foot cost of \$105.9. The total square foot cost of Building 1 equaled \$60.68/SF totaling \$22,946,120.

The multiuse nature of the building made it very difficult to make an estimate with standard parametric and square foot estimating methods. The total cost of construction for Building 1 is set with a GMP of \$24 Million. Even with the level of inaccuracy both estimates were very close to the actual number.

Overall Building Costs are \$24,000,000.

Square Foot Building Costs are \$63.47/SF.

Other information of cost was not available by owner request.

Note: See Appendix B for cost evaluation information.

SITE PLAN OF EXISTING CONDITIONS

Building #1 at Bakery Square is located on an old parking lot situated behind an existing building. The existing building, which is also owned by Walnut Capital, is currently under renovation. The foundations for Building #1 will come in close contact with existing caissons for Building #3.



• Figure 2 - Existing Site Conditions

The gas, electrical, and water lines are not a concern for excavation because they are all located outside of the building footprint. Fire hydrants are located at the west and south ends of the site, but they do not pose any major concerns. Subsurface concerns may include an existing storm water system and railroad tracks that are both located in unknown locations.

Traffic located around the site will not be affected by the work progressing at Bakery Square. Sidewalks along Liberty Blvd. and Penn Ave. are closed, but there are sidewalks available for pedestrians directly across the street.

See Appendix C for full Site Plan.

LOCAL CONDITIONS

Labor Unions are an important aspect of construction in the Pittsburgh region, and this project in particular requires 100% union participation. A Cast-In-Place concrete system is the preferred method of construction for most buildings in the area. However, precast concrete systems have made an immergence in recent years due to schedule and cost constraints. This trend is especially true for parking garages.

Construction has recently begun on a number of large scale projects in the Pittsburgh area, causing the labor pool to diminish. Mechanical, electrical, and plumbing subcontractors must plan their work carefully to ensure that the unions are able to supply them with enough workers to complete the work on schedule.

Concurrent construction and renovation work on four other Bakery Square Development buildings will make this site very congested. Onsite parking privileges are granted to the construction management team, subcontractor superintendants, and one foreman per company. All other personnel must park offsite. Workers take advantage of side street free parking located within one block from the site. Recycling and tipping fees in the area are priced around \$400 for a two week rental on a 30 CY dumpster.

A subsurface investigation report was performed in April of 2007. Twenty-three test bores were drilled across the Bakery Square site; twelve were within the footprint of Building 1. Through subsurface investigation it was revealed that the soil was of a silty/sandy composition and heavily saturated with ground water. Due to the nature of the soil and the moderate to high load of Building 1, the subsurface investigation report recommended the use of deep foundations.

Note: See Appendix D for boring locations and a sample test bore log.

CLIENT INFORMATION

Bakery Square Holdings is a limited partnership comprised of Pittsburgh real-estate developer Walnut Capital and The Feil Organization, a New York based investor. Walnut Capital prides itself as a leading developer and property manager of real estate in the Pittsburgh region.

It has been a priority of Walnut Capital to help develop the surrounding community, and Bakery Square Development is a prime example of that effort. When the management team discovered this real estate not even a mile from their office, they immediately took a special interest in it. Walnut Capital's dedication to this project is evident with their hands on approach and weekly meetings with the contractor. Another reason for constructing Bakery Square Development is to make a profit. Walnut Capital is an entrepreneurial business and invests in real estate to make a profit.

Since Walnut Capital and P.J. Dick have worked together on previous projects, both companies are on the same page when it comes to project expectations. A GMP has been set to ensure the cost of the building meets both the expectations of the developers and the requirements set forth by the investors. Bakery Square has been marketed as a high-end urban center, and therefore is expected to be built with quality in mind. Since leases have been signed for Building 1, it is also important that the building be constructed on time. Both P.J. Dick and Walnut Capital expect the construction at Bakery Square to be performed in a safe manner. A Safety Manager has been assigned to the job and routine inspections are performed to ensure compliance with the safety plan.

PROJECT DELIVERY SYSTEM

P.J. Dick is delivering Building 1 as a construction manager at risk with a GMP. This type of contract was chosen because of the previous relationships that Walnut Capital has had with P.J. Dick. Factors taken into consideration when evaluating the organizational structure include time, owner experience, team experience, quality, cost. Time, cost, and quality are important to this project, and both have experience. A construction manager at risk structure is well suited for all of these qualities.

Subcontractors were chosen based on a lump sum evaluation. Scopes were reviewed and prices were adjusted before the low bidder was given a contract to sign. Insurance was not included in any pricing because the project has an Owner Controlled Insurance Policy (OCIP), but bonds were required if any subcontract amount exceeded \$500,000.



• Figure 3 - Project Organizational Chart

STAFFING PLAN

P.J. Dick is the construction manager for the entire project of Bakery Square Development. This includes Building 1 and four other multiuse structures that are either being renovated or being newly constructed. The organizational chart shown in figure 2 is for Building 1. A Project Executives oversees all operations in the Pittsburgh area, including the Bakery Square Project. The Project Manager is responsible for all of the buildings on site, while other responsibilities are split among the rest of the staff. A Project Engineer is dedicated to Building 1, while the Safety Manager, Project Secretary, Intern, and Project Superintendent divide their time among multiple buildings.



APPENDIX A: Project Schedule Summary

Project Schedule	Summary			С	lassio	; WE	3S La	yout					29-Sep-08 14: 2008 22 Q3 Q4 Q1 Q2 Q3 Procurement Sitework Foundations - East Foundations - Center Foundations - West Mobilize Crane - Precast Start Precast Erection Erect Precast - West				14:14	
Activity ID	Activity Name	Original	Start	Finish			2	007				2	2008			20)09	
		Duration			21	(ຊ2	Q3	Q4	Q1		Q2	Q3	Q4	Q1	Q2	Q3	Q4
Building	1 @ Bakery Sq	697	02-Jan-0	02-Sep-09	:	: :						: :						02-Sep
01	Design	300	02-Jan-0	7 25-Feb-08						<u> </u>	Des	ign						
02	Procurement	351	03-Dec-0	06-Apr-09								<u> </u>	· · ·	1 1 1		Procu	urement	
03	Sitework	124	25-Mar-0	08 12-Sep-08			į				i 🗖	<u> </u>		Sitework				
04	Foundations - East	51	27-Mar-0)8 05-Jun-08							: 🛑	÷	Foundatio	ns - East				
05	Foundations - Center	65	01-Apr-08	8 30-Jun-08					·				E Found	ations - Ce	nter			
06	Foundations - West	49	23-Apr-08	8 30-Jun-08								<u> </u>	📕 Founda	ations - We	st			
07	Mobilize Crane - Precast	5	09-Jul-08	3 15-Jul-08									🛿 Mobi	ize Crane	- Precas	st		
08	Start Precast Erection	0	16-Jul-08	3									 Start 	Precast E	ection			
09	Erect Precast - West	58	16-Jul-08	3 03-Oct-08										🗎 Ērect P	recast -	West		
10	100% GMP	0		06-Aug-08									♦ 10	% GMP				
11	Masonry	112	29-Sep-0	08 03-Mar-09										(Masonry		
12	Erect Precast - Center	35	06-Oct-08	8 21-Nov-08										EI	ect Prec	cast - Cen	ter	
13	Water Protection / Expa	82	23-Oct-08	8 13-Feb-09												Vater Prot	ection / E	xpansior
14	Install Elevators	123	10-Nov-0	08 29-Apr-09												📕 Iņs	tall Eleva	tors
15	Erect Precast - East	32	24-Nov-0	08 06-Jan-09											Erect	Precast	East	
17	Plumbing	59	24-Nov-0	08 12-Feb-09											P	lumbing		
16	Fire Protection	59	24-Nov-0	08 12-Feb-09			į								F	ire Protec	tion	
18	Electrical	69	24-Nov-0	08 27-Feb-09										: : ⊏		Electrical		
19	Erect / Detail Mezzanine	22	15-Dec-0	08 13-Jan-09											Erec	t / Detail I	Mezzanin	e Steel
20	Install Permanent Power	30	22-Jan-0	9 04-Mar-09												Install Pe	ermanent	Power
21	Building Enclosure	0		03-Feb-09											🔶 βι	uilding En	closure	
22	Glass / Glazing	25	04-Feb-0	9 10-Mar-09			į									Glass /	Glazing	
25	Urban Active Fit-out	110	02-Mar-0)9 31-Jul-09													ur Ur	ban Activ
24	Houlihans Fit-out	110	02-Mar-0)9 31-Jul-09													Hc	oulihans I
23	Retail Tenant Fit-out	132	03-Mar-0	09 02-Sep-09														Retail T
26	Anthropolgie Fit-out	88	01-Apr-09	9 31-Jul-09													Ar Ar	thropolgi
27	Garage / C&S Substanti	0		21-May-09												•	Garage / (C&S Sub
Actua	Work Critica	al Remainir	ng Work 🔻	Summary			Pag	ge 1 of 1		Jonath	an Re	evtai						
Rema	ining Work \blacklozenge \blacklozenge Milest	one	-	,, ,											©F	Primavera	Systems	, Inc.

APPENDIX B: Cost Information

R.S. Means adjustments

Parking Structure Added 10' vertically to outside of building.

Retail Store

Added 10' vertically to outside of building Removed all interiors Removed all HVAC Removed all Plumbing

		Building 1 - Baker	y Square - Oct 20	07 - PA - Pittsburg	h	
	Prepared By:	Jonathan Revtai PSU		Prepared For:	Dr. Riley	
	Building Sq. Size: Bid Date: No. of floors: No. of buildings: Project Height: 1st Floor Height: 1st Floor Size:	, Fax: 378120 6		Site Sq. Size: Building use: Foundation: Exterior Walls: Interior Walls: Roof Type: Floor Type: Project Type:	, Fax: 59700 Commercial PIL PRE PRE NEW	
Division			Percent		Sq. Cost	Amount
00	Bidding Requiren	nents	4.70		2.99	1,130,548
	Bidding Requ	irements	4.70		2.99	1,130,548
04	Conorol Doguiron	mente	6.07		2.09	4 500 000
01	General Requiren	nents uirements	6.27		3.98 3.98	1,506,268
	Conordinitioq		0.21		0.00	1,000,200
02	Site Work		4.70		2.99	1,129,785
	Site Work		4.70		2.99	1,129,785
02	Conorato		24.62		20.44	7 602 626
03	Concrete		31.03		20.11	7,003,020
	Oblicicie		01.00		20.11	7,000,020
04	Masonry		1.24		0.79	297,099
	Masonry		1.24		0.79	297,099
0 5	M - (-) -		0.50		0.07	050 554
05	Motals		3.56		2.27	856,551
	IVIEIDIS		3.50		2.21	000,001
06	Wood, Plastics, a	ind Composites	0.18		0.11	42.699
	Wood, Plastic	cs, and Composites	0.18		0.11	42,699
07	Thermal & Moistu	are Protection	1.25		0.79	299,898
	i nermai & ivio	Disture Protection	1.25		0.79	299,898
08	Doors & Windows	s	4.26		2.71	1.025.045
	Doors & Wind	dows	4.26		2.71	1,025,045
09	Finishes		1.58		1.00	379,036
	Finishes		1.58		1.00	379,036
10	Specialties		0.26		0.17	63.301
	Specialties		0.26		0.17	63,301
11	Equipment		0.55		0.35	132,820
	Equipment		0.55		0.35	132,820
12	Furnishings		3.10		1.97	745,205
	Furnishings		3.10		1.97	745,205
	-					
14	Conveying Syste	ms	2.03		1.29	488,399
	Conveying Sy	ystems	2.03		1.29	488,399
15	Mechanical		3.26		2.07	783.053
-	Mechanical		3.26		2.07	783,053
16	Electrical		3.94		2.51	947,633
	Electrical		3.94		2.51	947,633
21			0.46		0.20	110 204
£1	Fire Suppression	sion	0.40 0.46		0.29	110, 201
			0.70		0.20	110,201
22	Plumbing		1.69		1.08	406,883
	Plumbing		1.69		1.08	406,883

23	HVAC	7.11	4.52	1,708,097		
	HVAC	7.11	4.52	1,708,097		
26	Electrical	10.60	6.74	2,547,644		
	Electrical	10.60	6.74	2,547,644		
27	Communications	0.28	0.18	66,225		
	Communications	0.28	0.18	66,225		
31	Earthwork	6.62	4.21	1,591,732		
	Earthwork	6.62	4.21	1,591,732		
32	Exterior Improvements	0.73	0.47	176,682		
	Exterior Improvements	0.73	0.47	176,682		
Total E	Building Costs	100.00	63.57	24,038,430		
Total N	Ion-Building Costs	100.00	0.00	0		
Total Non-Building Costs				24,038,430		

COMMERCIAL/INDUSTRIAL/ INSTITUTIONAL



M.270

Costs per square foot of floor area

Taka will	S.F. Areo	85000	115000	145000	175000	205000	235000	265000	295000	325000		
	LF. Perimeter	529	638	723	823	923	951	1037	1057	1132		
Face Brick with	Steel Frame	57.80	56.45	55.45	54.95	54.50	53.90	53.60	53.15	53.00		
Concrete Block Back-up	R/Conc. Frame	44.10	42.75	41.70	41.15	40.80	40.10	39.90	39.45	39.25		
Precast Concrete	Steel Frame	60.65	59.10	57.90	57.20	56.75	55.95	55.65	55.10	54.85		
	R/Conc. Frame	46.25	44.65	43.50	42.80	42.40	41.60	41.25	40.65	40.45		
Reinforced Concrete	Steel Frame	57.10	55.95	55.10	54.65	54.25	53.75	53.55	53.15	53.00		
	R/Conc. Frame	42.40	41.20	40.40	39.90	39.60	39.05	38.85	38.45	38.35		
Perimeter Adj., Add or Deduct	Per 100 L.F.	1.40	1.05	0.85	0.65	0.60	0.50	0.45	0.40	0.30		
Story Hgt. Adj., Add or Deduct	Per 1 Ft.	0.45	0.45	0.40	0.30	0.40	0.30	0.30	0.30	0.25		
	Basement—Not Applicable											

The above costs were calculated using the basic specifications shown on the facing page. These costs should be adjusted where necessary for design alternatives and owner's requirements. Reported completed project costs, for this type of structure, range from \$29.50 to \$114.10 per S.F.

Common additives

Description	Unit	\$ Cost
Elevators, Electric passenger, 5 stops		
2000# capacity	Each	127,300
3500# capacity	Each	134,300
5000# capacity	Each	139,800
Barrier gate w/programmable controller	Each	3950
Booth for attendant, average	Each	12,300
Fee computer	Each	14,900
Ticket spitter with time/date stamp	Each	7450
Mag strip encoding	Each	20,900
Collection station, pay on foot	Each	126,000
Parking control software	Each	25,200 - 103,000
Painting, Parking stalls	Stall	9.75
Parking Barriers		
Timber with saddles, 4" x 4"	L.F.	6.70
Precast concrete, $6'' \times 10'' \times 6'$	Each	69.50
Traffic Signs, directional, 12" x 18", high density	Each	79.50

Model costs calculated for a 5 story building with 10' story height and 145,000 square feet of floor area

Garage, Parking

A.	SUBSTRUCTURE			Unit	Cost	Per S.F.	Sub-Toto
1010	0 Standard Foundations	Poured concrete; strip and spread footings	a status at the	SE Group	1 640	1 1 00	
1020	Slab on Grade	N/A		-	-0.40	1.28	
2010	Basement Excavation	o" reinforced concrete with vapor barrier and granular base	•	S.F. Slab	6.06	1.22	11.9%
2020	Basement Walls	4' foundation wall	footing	S.F. Ground	.15	.03	11.770
B.	SHELL			L.F. Wall	61	1.22	
1010	B10 Superstructure						
1010	Floor Construction	Double tee precast concrete slab, precast concrete columns	and the second	CE Elasa	1 10 / 1		
1020	Root Construction	N/A		5.1. FIOOF	19.01	15.69	49.8%
2010	B20 Exterior Enclosure					The second	Name to Street
2010	Exterior Walls	Face brick with concrete block backup	40% of story height	S.F. Wall	20 /8	1 204	
2030	Exterior Doors		, 0	-	-	2.94	0.2%
	B30 DesC	N/A	1940 market and the second of the second	_	-	_	9.5%
3010	Roof Coverings					1945 Plan	
3020	Roof Openings	N/A					Provide Service
C. I	NTERIORS				-	-	0.0 %
1010	Partitions	Concrete block			-		
1020	Interior Doors	Hollow metal		S.F. Partition	28.08	1.08	
1030	Fittings	N/A		Each	16,840	.12	
2010	Stair Construction	Concrete		-	-	-	
3010	Wall Finishes	Paint		Flight	3625	.25	5.0%
3020	Floor Finishes	N/A		S.F. Surface	1.43	.11	
3030	Ceiling Finishes	N/A		_	_	_	
v. 5	ERVICES						
1010	DIO Conveying						
1020	Elevalors & Lins	Iwo hydraulic passenger elevators		Each	133 400	1 1 9 4 1	i kang kang pang kang pang pang pang pang pang pang pang p
	DOG DL	IV/A		-		-	5.8%
2010	Plumbing Fixtures					and the second	385225
2020	Domestic Water Distribution	folief and service fixtures, supply and drainage	1 Fixture/18,125 S.F. Floor	Each	2719	15 1	
2040	Rain Water Drainage	Roof drains		S.F. Floor	.07	.07	4.7%
and a second second	D30 HVAC			S.F. Roof	6.35	1.27	
3010	Energy Supply	l N/A				and the second	
3020	Heat Generating Systems	N/A		-		-	s w terin sharib, and s
3030	Cooling Generating Systems	N/A		-	-	-	
3050	Terminal & Package Units	N/A		-	, - 1	-	0.0 %
3040	Other HVAC Sys. & Equipment	N/A		_	-	-	
4010	040 Fire Protection			(MARINA SA)	1.3X A ANDA	Brittle Marchane	SG THE ALL MADE
4010	Sprinklers Standnings		1	energen en h	Children St. Worden 4. Desember 2010 Killer		
	Junupipes	Standpipes and hose systems		S.F. Floor	07	07	0.2 %
5010	Flootrical Service (Distribution						al Soudier and Alexandre
5020	Lighting & Branch Wiring	400 ampere service, panel board and feeders		S.F. Floor	23	23 1	S PARALE
5030	Communications & Security	Alarm systems and ansatz is hit		S.F. Floor	2.65	2 65	
5090	Other Electrical Systems	Emergency generator 7.5 kW		S.F. Floor	.11	.11	9.7%
E. EQ	UPMENT & FURNISHIN			S.F. Floor	.05	.05	
1010						Natel Tariba	
020 1	nstitutional Equipment	N/A	and the second	-	10437 <i>8.7</i> 93200.13		
020	ehicular Fauinment	N/A Ticket dimensional and		-	_	_	
030 1 1	entre equipment	N/A		S.F. Floor	1.11	1.11	3.5 %
090 0	Other Equipment			_		_	
090 (Other Equipment			N INCOMENTATION OF THE OWNER	Action Part of the	Contraction of the second	
090 (F. SPE 020 Ir	Other Equipment CIAL CONSTRUCTION Integrated Construction	N/A					
090 (090 (5. SPE 020 Ir 040 S	Dther Equipment CIAL CONSTRUCTION Integrated Construction Special Facilities	N/A N/A		-	-		0.0.%
030 0 090 0 SPE 020 Ir 040 S B U	Differ Equipment CIAL CONSTRUCTION Integrated Construction Special Facilities ILDING SITEWORK	N/A N/A				-	0.0 %
030 (090 (SPE 020 Ir 040 S 3. BU	Dther Equipment CIAL CONSTRUCTION Integrated Construction Special Facilities ILDING SITEWORK	N/A N/A N/A				-	0.0 %
030 090 (SPE 020 Ir 040 S J. BUI	Dther Equipment CIAL CONSTRUCTION ntegrated Construction pecial Facilities ILDING SITEWORK	N/A N/A N/A				31.49	0.0 % 1 00%
030 090 (F. SPE 020 Ir 040 S 3. BU	Differ Equipment CIAL CONSTRUCTION Integrated Construction opecial Facilities ILDING SITEWORK ONTRACTOR FEES (General Report for the second seco	N/A N/A N/A equirements: 10%, Overhead: 5%, Profit: 10%)		 Sub-1		 31.49	0.0 % 1 00%

Total Building Cost 41.70

CIAL/INDUSTRIAL/ MAL

Store, Retail



M.630

Costs per square foot of floor area

Exterior Wall	S.F. Area	4000	6000	8000	10000	12000	15000	18000	20000	22000
	LF. Perimeter	260	340	360	410	440	490	540	565	504
Split Face Concrete Block	Steel Joists	122.95	111.40	101.35	97.05	93 15	00.98	97.20	05 70	374
Stucco on Concrete Block	Steel Joists	120.05	108.90	99.40	95 20	91.55	99.15	07.20	65.70	84.60
Painted Concrete Block	Steel Joists	114.40	103.55	94 45	90.50	97.00	00.15	83.83	84.40	83.35
Face Brick on Concrete Block	Steel Joists	139.65	126.00	112.95	107.60	102.60	83./3	81.55	80.20	79.20
Painted Reinforced Concrete	Steel Joists	129,90	117 50	106.20	107.00	102.00	98.00	94.90	92.95	91.50
Tilt-up Concrete Panels	Steel loists	120.25	100.05	100.20	101.50	97.10	93.05	90.40	88.70	87.50
		120.25	109.05	99.50	95.40	91.65	88.25	85.95	84.50	83.50
Perimeter Adj., Add or Deduct	Per 100 L.F.	14.20	9.50	7.15	5.70	4.75	3.70	3 10	2 80	2.40
Story Hgt. Adj., Add or Deduct	Per 1 Ft.	1.75	1.60	1.25	1.15	1.00	0.90	0.85	0.75	2.00
	For Ba	sement, add \$3	30.70 per squ	are foot of bo	asement area			0.00	0.75	0.70

The above costs were calculated using the basic specifications shown on the facing page. These costs should be adjusted where necessary for design alternatives and owner's requirements. Reported completed project costs, for this type of structure, range from \$51.50 to \$179.05 per S.F.

Common additives

Description	Linit	\$ Cart
Emergency Lighting, 25 watt, battery operated	Ulli	9 COSI
Lead battery	Each	278
Nickel cadmium	Each	800
Safe, Office type, 4 hour rating	Eden	000
30" × 18" × 18"	Fach	1075
62" × 33" × 20"	Each	40/5
Smoke Detectors	Luch	0000
Ceiling type	Fach	174
Duct type	Each	1/4
Sound System	Edch	445
Amplifier, 250 watts	Fach	2225
Speaker, ceiling or wall	Each	101
Trumpet	Each	101
2 Martin	Luch	345

				Unit	Unit Cost	Cost Per S.F.	% C Sub-T
A.	SUBSTRUCTURE			-	- Participant - Alice	and a second second	1
1010 1020 1030 2010 2020	Standard Foundations Special Foundations Slab on Grade Basement Excavation Basement Walls	Poured concrete; strip and spread footings N/A 4" reinforced concrete with vapor barrier and granular base Site preparation for slab and trench for foundation wall and for 4' foundation wall	poting	S.F. Ground – S.F. Slab S.F. Ground L.F. Wall	1.70 - 4.63 .25 70	1.70 - 4.63 .25 2.12	12.9
B. :	SHELL				<u> </u>		STATISTICS Repair
	B10 Superstructure						
1010	Floor Construction	N/A	and a subsection of the second se	1 _	1	1	T
1020	B20 Exterior East	Metal deck, open web steel joists, beams, interior columns		S.F. Roof	6.40	6.40	8.5
2010	Exterior Walls	Decorative concrete block					
2020	Exterior Windows	Storefront windows	90% of wall 10% of wall	S.F. Wall	15.54	8.81	
2030	Exterior Doors	Sliding entrance door and hollow metal service doors		Each	1802	2.52	15.7%
3010	B30 Roofing Roof Coverings	Dilling to a start of the last start of the				1	
3020	Roof Openings	Roof hatches	lation	S.F. Roof	5.41	5.41	7 40
C. 11	NTERIORS			S.F. Roof	.12	.12	7.4%
1010	Partitions	Company based as well built					
1020	Interior Doors	Single leaf hollow metal	60 S.F. Floor/L.F. Partition	S.F. Partition	5.22	.87	
1030	Fittings	N/A	600 S.F. Floor/Door	Each	842	1.40	
3010	Stair Construction	N/A		_	_		15.0%
3020	Floor Finishes	Vinvl tile		S.F. Surface	5.37	1.79	13.0/0
3030	Ceiling Finishes	Mineral fiber tile on concealed zee bars		S.F. Floor	3.05	3.05	
D. S	ERVICES			S.r. Celling	4./4	4.74	1
	D10 Conveying						
1010	Elevators & Lifts	N/A				real second s	
1020	Escalators & Moving Walks	N/A		_	_	-	0.0 %
2010	D20 Plumbing	1 = -		North Art			
2020	Domestic Water Distribution	loilet and service fixtures, supply and drainage	1 Fixture/890 S.F. Floor	Each	2243	2.52	
2040	Rain Water Drainage	Roof drains		S.F. Floor	3.74	3.74	9.8%
I	D30 HVAC			S.F. Root	1.08	1.08	NECESSION STATE
3010	Energy Supply	N/A					
3030	Cooling Generating Systems	Included in D3050	2 12	_	_	_	
3050	Terminal & Package Units	Single zone unit, gas heating, electric cooling	× 1	-	-	-	9.2 %
3090	Other HVAC Sys. & Equipment	N/A		S.F. Floor	6.93	6.93	
L010	40 Fire Protection					- I	
4010	Sprinklers	Wet pipe sprinkler system		S.F. Floor	3.43	3 43	
	50 Electrical	N/A	CONTRACTOR AND	_	_	-	4.6%
5010 6	Electrical Service/Distribution	400 ampere service, panel board and fooders					
5020 L	ighting & Branch Wiring	Fluorescent fixtures, receptacles, switches, A.C. and misc. power		S.F. Floor	2.39	2.39	
030 0	Communications & Security	Alarm systems and emergency lighting	2	S.F. Floor	37	9.16	16.1%
	Siller Liechical Systems	Emergency generator, 15 kW		S.F. Floor	.19	.19	
E. EGI	JIFMENT & FURNISHIN	GS					
010 0	Commercial Equipment	N/A					
030 V	ehicular Equipment	N/A N/A		_	_	_	
090 C	Other Equipment	N/A		-	-	-	0.0 %
SPE				-	-	-	
020 In	tegrated Construction	N/A					
040 S	pecial Facilities	N/A		-	-	-	00%
	LDING SITEWORK	N/A	The second se	-	-	-	0.0 %
. BUI				C. San Stranger	Service Transfer		and the second
i. BUI							and the second
). BUI				Sub-1	lotal	75.08	100%
BUI	ONTRACTOR FEES (General R	equirements: 10%, Overhead: 5%, Profit: 10%)		Sub-1	lotal	75.08	100%

tors

うろう

-

)

Total Building Cost 101.35

APPENDIX C: Existing Conditions Site Plan



APPENDIX D: Site Test Bore Information



TE	ST E	201 Pitts (412 306	NSUI 8 War burgh 2) 351 RINC	TAN verly -646 GLC	NG, INC. Street 15218 5 DG B-14	PROJECT: NABISCO PROPERTY LOCATION: PITTSBURGH, PA DATE STARTED: 4/13/07 DRILLER: T. ZILKA SURFACE ELEVATION: 930.0' WATER LEVELS: AT COMPLETION: 0				PROJECT NO.: J-09140 DATE COMPLETED: 4/13/07 LOGGED BY: HSR LOG TYPE: ENGINEER'S SPOON SIZE: 2 INCHES HLW. STEM AGR.: 3.25 I.D.		
ELEVATION	DEFTH	CNSOS		SYMBOL :	, '	DESCRIPTION OF MATERIAL	RECOVERY (%)	SAMPLE NO.	SPOON BLOWS/6in.	THICKNESS OF SAMPLES	ROD, %	REMARKS
30.0° = 29.8° 26.7°	0.0 0.2 3.3	-		CL	ASPHALT FILL: Slag, cind organic materia CLAY: Brown to stiff, damp	ers, trace of brown clay and I, dense, dry to wet 9 gray, mottled, soft to medium	100% 27%	1 2	28-40-47 5-6-6	1.5-3.0 3.0-4.5		
21.3'	8.7	,			SAND: Reddisi brown silt, very	t brown to brown, with trace of loose to loose, damp	100%	3	3-5-6 3-3-6	6.0°-7.5° 9.0°-10.5°		
4		14		:			100% 100%	5	33-3 33-3	12.0°-13.5° 15.0°-16.5°		7
911.3"	18.7 [.] 21.8'	21		GM	SILT: Reddish rock fragments moist SILT: Gray, wit	brown, with Irace of weethered , soft to medium stiff, dry to h trace of sand, very soft to	- 100%	7 8.	2-5-5 5-4-5	18.0°-19.5° 21.0°-22.5°		
		- 28			meaun sun, n	KOSK.	100%	9 10	3-5-5	24.0'-25.5' 27.0'-28.5'		
							100%	11	3-2-5	30.0'-31.5'	~	
897.5	32.5	35			SAND: Gray, v loose, wet	with trace of silt, very loose to	100%	12	2-2-5	33.0-34.5		
000.0	33.7				SHLTY SHALE hard, dry	: Bluish gray, with bace of sand	100%	13	37-41-50/0.4	36.0*-37.4*		
890.7	39.3'	42			SILTSTONE: I and shale, ver medium hard,	Bluish gray, with trace of sand y broken to blocky, soft to damp	90%	R1	2010,3	39.3-44,3	57%	BEGIN CORING @ 39.3*
885.7	44.3'						T					Bottom of Boring @ 44.3*

1.1

· · ·

· · · ·