WESTINGHOUSE ELECTRIC COMPANY CORPORATE HEADQUARTERS CRANBERRY, PA



Final Report Spring 2009 B.A.E.

Jessica L. Laurito Structural Option Advisor: Dr. Linda Hanagan

WESTINGHOUSE ELECTRIC COMPANY CORPORATE HEADQUARTERS

BUIILDING OME CRAMBERRY, PA

BUILDING INFORMATION

OCCUPANCY
SIZE:
HEIGHT:
BUILD TIME:
Cost:
DELIVERY:

OFFICE 434,800 SQ FT 5 LEVELS, 87'-6" TALL FEB 2008-MAY 2009 \$80 MILLION DESIGN-BID-BUILD





OWNER: WELLS REAL ESTA ARCHITECT: IKM, INC. STRUCTURAL/MECH: LLI ENGINEERING CIVIL: CIVIL & ENVIRONM CONSTRUCTION: TURNER CONSTRU

PROJECT TEAM

Wells Real Estate Funds IKM, Inc. LLI Engineering Civil & Environmental Consultants, Inc. Turner Construction Company

STRUCTURAL

STRUCTURAL STEEL FRAMING WITH 2" COMPOSITE STEEL DECK AND 2-1/2" CONCRETE SLAB

TYPICAL BAY SIZE IS 45'-0"

MOMENT CONNECTIONS RESIST WIND FORCES

SLAB ON GRADE, GRADE BEAMS, AND CASSION FOUNDATION SYSTEM

ARCHITECTURE

SITE IS ON 83 ACRES IN CRANBERRY, PA

LEED CERTIFICATION GOAL

BIO-RETENTION PARKING LOT

BRICK FAÇADE IS TEXTURED TO CREATE VERTICAL ELEMENT WHILE POLISHED CONCRETE BLOCK EMPHASIZES IMPORANTANCE.

POWERFUL ENTRANCE MAKES USE OF TWO-STORY ATRIUM

FLOOR-TO-FLOOR HEIGHT OF 14'-0", ENTRANCE LEVEL IS 18'-0".

ROOF SYSTEM CONSISTS OF AN EDPM SYSTEM WITH A MEMBRANE OVER 1/2" PROTECTION BOARD OVER TAPERED INSULATION OVER 5/8" GWB ON THE ROOF DECKING.

JESSICA L. LAURITO | STRUCTURAL OPTION SPONSORED BY TURNER CONSTRUCTION COMPANY WWW.ENGR.PSU.EDU/AE/THESIS/PORTFOLIOS/2000/JILL5004/

MECHANICAL/ELECTRICAL/LIGHTING

Two Gas Fired Boilers Serve To Heat The Building With Capacities OF 1265 CFM And 960 CFM.

SIX AHU'S WITH VARYING CAPACITY SERVE THE BUILDING AND VAV UNITS.

480/277V, 3 Phase, 3 Wire Primary, 208/120V 3 Phase 4 Wire Secondary Delta-Wye Dry Type Transformers.

MAINLY FLOURESCENT LIGHTING TO CONTRIBUTE TO LEED CERTIFICATION.

GENERATOR PROTECTION ON CAMPUS FOR ALL CONTROLS.



TABLE OF CONTENTS

EXECUTIVE SUMMARY
ACKNOWLEDGEMENTS
INTRODUCTION
SITE PLAN
EXISTING STRUCTURAL SYSTEMS
PROBLEM STATEMENT
SOLUTION METHOD
CODE AND DESIGN REQUIREMENTS
APPLICABLE DESIGN STANDARDS
DEFLECTION CRITERIA
MATERIALS
GRAVITY AND LATERAL LOADS
WIND DESIGN
SEISMIC DESIGN AND ANALYSIS
MEMBER DESIGN
MEMBER DESIGN
FOUNDATION IMPACT OF NEW STRUCTURE
FOUNDATION IMPACT OF NEW STRUCTURE
FOUNDATION IMPACT OF NEW STRUCTURE
FOUNDATION IMPACT OF NEW STRUCTURE
FOUNDATION IMPACT OF NEW STRUCTURE.27TORSION29PORTAL METHOD31MEMBER CHECKS33
FOUNDATION IMPACT OF NEW STRUCTURE.27TORSION29PORTAL METHOD31MEMBER CHECKS33DRIFT34
FOUNDATION IMPACT OF NEW STRUCTURE.27TORSION29PORTAL METHOD31MEMBER CHECKS33DRIFT34OVERTURNING MOMENT36
FOUNDATION IMPACT OF NEW STRUCTURE.27TORSION29PORTAL METHOD31MEMBER CHECKS33DRIFT34OVERTURNING MOMENT36DEPTH STUDY OVERVIEW36
FOUNDATION IMPACT OF NEW STRUCTURE.27TORSION29PORTAL METHOD31MEMBER CHECKS33DRIFT34OVERTURNING MOMENT36DEPTH STUDY OVERVIEW.36BREADTH STUDY 1- CONSTRUCTION MANAGEMENT ANALYSIS37
FOUNDATION IMPACT OF NEW STRUCTURE.27TORSION29PORTAL METHOD31MEMBER CHECKS33DRIFT34OVERTURNING MOMENT36DEPTH STUDY OVERVIEW36BREADTH STUDY 1- CONSTRUCTION MANAGEMENT ANALYSIS37COST ANALYSIS37
FOUNDATION IMPACT OF NEW STRUCTURE.27TORSION29PORTAL METHOD31MEMBER CHECKS33DRIFT34OVERTURNING MOMENT36DEPTH STUDY OVERVIEW36BREADTH STUDY 1- CONSTRUCTION MANAGEMENT ANALYSIS37COST ANALYSIS37SCHEDULE ANALYSIS37
FOUNDATION IMPACT OF NEW STRUCTURE.27TORSION29PORTAL METHOD31MEMBER CHECKS33DRIFT34OVERTURNING MOMENT36DEPTH STUDY OVERVIEW.36BREADTH STUDY 1- CONSTRUCTION MANAGEMENT ANALYSIS37COST ANALYSIS37SCHEDULE ANALYSIS37BREADTH STUDY 1 OVERVIEW.38
FOUNDATION IMPACT OF NEW STRUCTURE.27TORSION29PORTAL METHOD31MEMBER CHECKS33DRIFT34OVERTURNING MOMENT36DEPTH STUDY OVERVIEW36BREADTH STUDY 1- CONSTRUCTION MANAGEMENT ANALYSIS37COST ANALYSIS37SCHEDULE ANALYSIS37BREADTH STUDY 1 OVERVIEW38BREADTH STUDY 2- SUSTAINABLE ARCHITECTURE39

APPENDIX B: TO	ORSION EFFECTS CALCULATIONS	50
APPENDIX C: W	IND LOAD CALCULATIONS	53
APPENDIX D: SE	EISMIC LOAD CALCULATIONS	58
APPENDIX E: M	EMBER DESIGNS AND CHECKS	63
APPENDIX F: CO	ONSTRUCTION MANAGEMENT BREADTH STUDY	89
APPENDIX G: SU	USTAINABLE ARCHITECTURE BREADTH STUDY 10	28
APPENDIX H: RE	EFERENCES 1	12

Page 5 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report

EXECUTIVE SUMMARY

The Westinghouse Electric Company Corporate Headquarters will be a three-building campus with site features which include asphalt walking paths and volleyball courts on eighty-three acres in Cranberry, PA. For the purpose of the project, only Building One will be analyzed as the other two are considered a separate project by all parties involved. The truncated V-shape building has been given a look of importance with polished concrete block merging into brick stepped-out columns to accentuate the verticality of the five-story 74'-6" tall structure.

The purpose of this report is to redesign the structural system of the Westinghouse Electric Company Corporate Headquarters Building One using reinforced cast-in-place concrete and a one-way slab with beams floor system. The building was analyzed in concrete by hand and in the RAM Structural System program. The success of this part of the report relies on the implementation of the code effectively and correctly to determine if the proposed modifications could be implemented.

For this report, a detailed analysis of the alternative structural system was performed. In order for this method to be correct, all structural members were designed according to ACI 318-08 and ASCE 7-05 for gravity loads, lateral loads, and torsion. Hand calculations were done for spot checked members in addition to a RAM Structural System model and analysis. The new structural system consists of typical square columns 24"x24" and beams typically 24"x34" with a 10" thick one-way slab. The spread footings and caissons were also spot checked and updated as necessary for the new structural dead load. Uplift and overturning moment were considered and checked for this report, but due to the weight of the building, neither was determined to be an issue.

Since the building material was changed, it is necessary to compare the new building cost estimate and schedule to the as-built structure's cost budget and schedule. The new building was determined to be \$30.60/SF without a green roof and \$33.28/SF with a green roof, while the original design cost is \$30.90/SF. Also, it takes two months longer for the new concrete structure to be erected compared to the original steel structure. Despite the fact that the lead time for steel is much longer than concrete, most of the steel will be on site by the time the foundations are complete, so the lead time did not affect the schedule. While the goal of the project was to obtain a cost and schedule for the new building so a comparison could be made, it can clearly be see that the concrete structure is not the best alternative for this building.

The sustainable architecture study was an attempt to make the corporate headquarters stand out among headquarters buildings by being incorporated into the environment. A green roof was added, and the extra load of the soils and supporting structure was determined and evaluated with the entire building. The green roof was designed for the third floor area above what will be the employee cafeteria. This part of the building also conveniently faces the south, which is the optimum direction for a successful green roof. The area will be extremely beneficial to the company by its multiple purposes, whether it is as a lunch area, a break room, or an informal meeting location. The waterproofing, drainage system including pipe sizes, detail of the materials, specification of materials and plants acceptable for the green roof were all determined. A LEED analysis was performed for the new building also, since one of the goals of the owners was to have a LEED certified building. It was determined that it is possible for the building to be LEED silver rated, but would require further information and investigation to be rated higher.

Overall, the project was a success, even though it was not erected cheaper or faster than the original steel building. It is feasible to build the building in concrete, but it is not an effective alternative. It is recommended to add a green roof to the structure to emphasize the corporate headquarters aspect of the building and to incorporate it into the environment.

ACKNOWLEDGEMENTS

I would like to thank:

- Turner Construction Company for their assistance and support in completing my project and providing supplies for this project. Special thanks to Bob Hennessey for his time and efforts to help me with my questions throughout the year, providing the schedule and estimate, and also taking the time to show me the site.
- LLI Engineering, especially James D. White and Ernest M. Tillman for supplying the electronic versions of the drawings.
- Westinghouse Electric Company, particularly Russ Bussard for granting permission to study their Corporate Headquarters Building One.
- Wells Real Estate Funds, particularly Frank Mitzel for permission to study the Westinghouse Electric Company Corporate Headquarters Building One.
- The Pennsylvania State University Architectural Engineering Department and Staff for teaching us the skills necessary to become the best engineers possible and their advice and help throughout the past five years. In particular, Dr. Linda Hanagan, my thesis advisor, for her assistance and feedback throughout the year, and Prof. Kevin Parfitt and Prof. Robert Holland for teaching the class.
- Family and friends for their continued support and understanding throughout my college career. Whether it was through help directly with thesis or by providing support, you were there for me and it is much appreciated.

Page 7 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report

INTRODUCTION

WESTINGHOUSE ELECTRIC COMPANY CORPORATE HEADQUARTERS BUILDING ONE

The Corporate Headquarters building for the Westinghouse Electric Company is located in Cranberry, Pennsylvania. Just north of the city in Butler County, the site is on 83 acres in an office park easily accessible by I-79 and PA-228. With five above grade floors and a full 17' high basement, Building One will be the main building on this campus. Complete with cafeteria, gym, locker rooms, offices, and executive conference rooms, the flagship building comes well equipped and diverse. At 434,800 square feet, the building makes quite an architectural statement.

The main building utilizes a powerful entrance with a two-story atrium to express its importance. The first floor also has a height of 18'-0" to emphasize a larger space while floors two through four have floor-to-floor heights of 14'-0". The fifth floor has a height of 14'-6". Building One has a 74'-6" above grade with an 18' penthouse, making the final height 92'-6".



Aluminum and glass curtain walls add light and make the building feel more open while polished concrete at the base of the brick façade accentuate the height. The foundation system consists of caissons in addition to some spread footings and grade beams. A typical bay is 45'-0" by 24'-0", and uses a steel system with composite beams and deck. In most of the building, the girders are not composite, but the beams framing into the girders have some composite action. The floor system is a 2" 22 gage steel deck with 2-1/2" of lightweight concrete topping. The Westinghouse Electric Company Corporate Headquarters Building One has two expansion joints present, thus creating essentially three structural buildings inside of one. The expansion joints create the East, Center, and West parts of the building. These joints can be seen along column lines 7.9 and 8 between the east and center portions, and column lines 21 and 21.1 between the center and west parts of the building.

A successful redesign of this building will be completed and checked using a computer program, such as RAM Structural System, following the design procedure laid out by ACI 318-08 and ASCE 7-05, and will be constructible. The design will consist of gravity design of member, wind load calculations, seismic load calculation, torsion member checks, resizing of foundations, and uplift and overturning moment. Any changes will be evaluated in terms of cost and schedule implications and be compared to original values for both obtained from the Turner Construction Company. The construction management portion will compare these values. Ideally, the building will be built faster or less expensively than the original, but this is not a main point in the success or failure of this portion. Finally, the redesign will be a success if the building can be further integrated into the environment while providing details and specifications.

Page 8 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report


SITE PLAN



Figure 1: Site boxed in red and the road leading up to the site highlighted in red

Page 9 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report



Third floor plan- East with portal analysis Frame 2 and spot checked columns highlighted.

Figure 2: Third Floor Plan East

Page 10 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

Third Floor Plan Center with portal analysis Frame 13, interior beam designed, lateral member C.2-D.2- 13 checked, and spot checked columns B-15 and A-15 highlighted




Figure 3: Third Floor Plan Center

Page 11 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report

Second Floor Plan Center of as-built design with frames indicated




Figure 4: Second Floor Plan Center As-Built

EXISTING STRUCTURAL SYSTEMS FOUNDATIONS

Sixty-one caissons are the main elements in the foundation system. Each was designed to carry 8,000 psf. The caissons range from 36" to 84" in diameter and from 8'-0" to 30'-8" in height. On top of each caisson, there is a 2'-6" cap with #6 @8" each way on the top and the bottom as well as base plates for the columns. The 5" slab on grade in the basement bears directly on the soil and the thickened slabs under the non-load bearing walls. On the south side and the east portion of the building, where caissons are not present, there are spread footings or grade beams. The sub-grade walls in the basement (referred to as grade beams in the drawings) range from 1'-4" to 1'-8" wide and are 14'-4" deep. The bottom reinforcement in the grade beams is mainly (3) #6, but varies from #6 to #9 and in number. Top reinforcement also varies from #6 to #9 and from two bars to four bars.

FLOOR AND ROOF SYSTEM

The floor system for the corporate headquarters main building consists of 2" 22 gage metal deck with 2 $\frac{1}{2}$ " lightweight concrete topping, for a total slab depth of 4 $\frac{1}{2}$ ". The typical bay size of this composite steel system is 24'-0" by 45'-0". W21 beams (W21x44 typ.) spaced 24'-0" on center and W18x35 beams spaced 8'-0" on center support the deck and transfer the load to the W24 girders (W24x55 typ.). The girders then continue to transfer the load to the columns. The 5" thick slab-on-grade in the basement of the headquarters is the exception to the typical floors. The roof uses a different system uses 2" 20 gage metal deck with a 2 $\frac{1}{2}$ " lightweight concrete topping. Where the penthouse is absent, roof uses a fully adhered EPDM roofing system including the membrane over $\frac{1}{2}$ " protection board over tapered insulation over 5/8" type X GWB over the roof decking.

LATERAL SYSTEM

The Westinghouse Corporate Headquarters Building One uses moment connections at every column to resist lateral loads from wind and seismic forces and torsion forces. Wind moment connections with angles and bolts are provided at all members in the lateral system of the building.

COLUMNS

The columns used in the headquarters are typical for a mid-rise building. The large columns in the basement and first floor of the building are W36x230 at the largest, but typically are W14x90. The W36x230 columns are larger because the entire front façade of the building is bearing on a W36x230 beam and the two columns. On the roof, any columns that do not continue up from the fifth floor are W10x49 or W10x33. The rest of the building is generally the same size, of course with some smaller sizes of columns, such as W10's on the fifth and roof levels. The base plates have four possible layouts and range in thickness from 1 $\frac{3}{4}$ " to 3".

Page 13 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

PROBLEM STATEMENT

Based on the analysis performed on the Westinghouse Electric Company Corporate Headquarters Building, it can be concluded that the original composite deck and beam system is well suited for time and space considerations. In depth calculations and comparisons can be seen in Technical Report 2. However, with wind moment connections at every column, the lateral system could be explored further for efficiency. The size of the typical bays is fairly large and leads to larger beam sizes to keep the deflection reasonable. A one-way reinforced cast-in-place concrete slab with beams would be the best way to approach the 2:1 bays.

The building owners have decided to make the new corporate headquarters a LEED certified building. A study on the feasibility of making the building Silver Rated instead would be desirable and beneficial to the project. With a building and campus so large, integrating the site into the building is a must.

With so many changes in regard o the structure of the building, it would be beneficial to the project to perform a cost estimate for the new design and to generate a schedule. These were done in an effort to compare and evaluate the asbuilt design and the new redesign on a more even level.




Figure 5: As-Built Typical Bay Framing




Figure 6: New Design Concrete Typical Framing

Page 14 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

SOLUTION METHOD

The building will be redesigned for concrete with one-way reinforced concrete floors with beams. With the current column layout, the one-way slab has been shown to be more efficient than the two-way slab. Concrete moment resisting frames will be considered for the lateral system. Shear walls would have been an option, but without tenant fit-out drawings and a request for an open plan, they could not be the main system. In addition to changing the building to a concrete system, a green roof will be added to bring the building closer to the campus and its surroundings. Since the building is changed to concrete, the foundations will have to be re-examined and resized for the new loads. The building will be designed using a combination of hand calculations with ACI 318-08, IBC 2006, and a RAM model for verification of design. The project will be considered a success if it physically can be built and uses a design following all applicable codes. Also, it will be a success if the number of moment frames can be reduced.

In order to fully gauge which system is more effective overall, the steel and concrete buildings must be compared. Since the material is changing, there will be cost implications that need to be considered. Also, the difference in materials means there is a difference in erection time as well. To be able to make an assessment of the redesigned concrete system, a cost estimate and a schedule will be generated. The estimate will be compared to Turner Construction Company's budget for the building in steel, and the generated schedule will be compared to their actual schedule also. The building is currently under construction, but the structure was finished according to the schedule. Since the building owner wants it to be LEED certified, a LEED analysis of the new structure is required. A green roof was added to the building to integrate it into the surrounding land and to make the building unique as a corporate headquarters in Pittsburgh. The green roof also has structural implications which need to be addressed as well as cost and schedule impact. The potential plant inhabitants, waterproofing, and drainage system including pipes required to drain the water from the roof need to be evaluated. Achieving a LEED Silver Rating would be ideal, but ensuring the building still is capable of being rated would be acceptable. This portion of the project will be considered a success if a green roof can and is properly integrated into the building with proper drainage and detailing, and if a cost estimate can be calculated and a projected schedule can be generated. Ideally, the ultimate goal would be if the project could be completed faster or less expensively than the original steel building. However, the success of this project does not hinge entirely on obtaining the ideal goal.

CODE AND DESIGN REQUIREMENTS

These are the design standards, codes, and design criteria used by the design professional and in the calculations for this report.

APPLICABLE DESIGN STANDARDS

THE 2006 INTERNATIONAL BUILDING CODE

ACI 318-05 (REINFORCED CONCRETE DESIGN)

AISC STEEL CONSTRUCTION MANUAL, 13TH EDITION

ACI 530 (MASONRY STRUCTURES)

ASCE 7-05 (MINIMUM DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES)

DEFLECTION CRITERIA

FLOOR DEFLECTION CRITERIA

L/240 TOTAL LOAD

L/360 LIVE LOAD

L/600 CURTAIN WALL LOAD

LATERAL DEFLECTION CRITERIA

H/400 TOTAL ALLOWABLE WIND DRIFT

H/400 STORY WIND DRIFT

H/50 TOTAL ALLOWABLE SEISMIC DRIFT (Δ =0.02H_{SX} FROM TABLE 12.12-1 ASCE 7-05)

Page 16 of 112		
Jessica L. Laurito		
Structural Option		
Advisor: Dr. Hanagan		

MATERIALS

The materials used in the Westinghouse Electric Company Corporate Headquarters as listed on the general notes page of the structural drawing set are as follows and were used in design and analysis as appropriate.

CONCRETE

Mortar

Grout

Freezing Temperature Exposure Slab-on-grade Slab-on-deck Caissons Footings and Caisson Caps Walls and Piers	Air entrained (6% ±1%) 4,000 PSI 4,000 PSI 3,000 PSI 3,000 PSI 4,000 PSI
Over excavation fill	2,000 PSI
REINFORCING STEEL	
Reinforcing Bar Welded Wire Fabric	ASTM A-615 ASTM A-185
STRUCTURAL STEEL	
W-Shapes C-Shapes Steel Pipe Tubes	ASTM A-992 ASTM A-36 ASTM A-501 ASTM A-500 Grade B
Metal Deck	
Bolts Deck Studs	ASTM A-325, ¾" diameter ASTM A611 Grade C or D ¾"x 3 ½" headed stud
Masonry	
CMU	ASTM C-90

ASTM C-55 type N-1 **Concrete Brick** ASTM C-270 ASTM C-476

Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

GRAVITY AND LATERAL LOADS

The loads on the building are applied as such based on the design professional's specification on the drawings. It is understood the values for the original building are conservative since the live load of 80 PSF was used everywhere on the upper floors and a partition load is also used. The loading on the new redesigned concrete building is a 50 PSF live load and a 20 PSF partition load everywhere on the upper floors. Load combinations from IBC 2006 were taken into consideration and the highlighted combinations were used for the lateral analysis of the frames in the building.

• LOADS FOR THE ORIGINAL STEEL BUILDING

•	Dead Loads	
	Concrete	115 PCF
	Steel	490 PCF
	Partitions	10 PSF
	M.E.P.	5 PSF
	Finishes	3 PSF
•	Live Loads	
	Public Areas	100 PSF
	Lobbies	100 PSF
	Corridors above 1 st	80 PSF
	Office	50 PSF
	Mechanical	150 PSF
	Stairs	100 PSF

• DIFFERENCES IN LOADS FOR NEW CONCRETE BUILDING

•	Dead Loads	
	Concrete	145 PCF
•	Live Loads	
	Partitions	20 PSF

From IBC 2006:

1605.2.1 Basic Load Combinations

	(As applied to this Report)
1.4 D	Eq 16-1
1.2D + 1.6L	Eq 16-2
1.2D+1.0L	Eq 16-3
1.2D+0.8W	Eq 16-3
1.2D+1.0L+1	.6W Eq 16-4
1.2D+1.0E+1	.0L Eq 16-5
0.9D+1.6W	Eq 16-6
0.9D+1.0E	Eq 16-7

Page 18 of 112		Westinghouse Electric Company
Jessica L. Laurito		Corporate Headquarters
Structural Option		Cranberry, PA
Advisor: Dr. Hanagan		April 7, 2009
	Final Report	

WIND DESIGN

Wind loads were determined using Section 6.5 of ASCE 7-05. The building was analyzed using a Main Wind Force Resisting System. Typically, wind would be the controlling design factor for a building in Pennsylvania, and wind was for the original building. However, once the building was redesigned in concrete, the increase in weight was enough to cause the seismic load to control the lateral system. All the coefficients were determined, and the windward and leeward pressures were determined according to ASCE 7-05. A RAM Structural System analysis was performed to confirm the validity of the hand calculations. The RAM values are comparable to the hand checks, but are slightly different. This may be due to a computer program's ability to quickly perform a finite element analysis. More in depth calculations can be seen in Appendix C of the report.

Table 1: Wind Design Properties

Basic Wind Speed (V) mph	90
Exposure Category	В
Importance Factor (I) Wind Directionality Factor (Kd)	1
Wind Directionality Factor (Kd)	0.85
Topographic Factor (Kzt)	1

Table 2: Wind Pressure with Respect to Height

Floor		Total					Wind Pre	ssures (ps	f)	
Floor Heights	Level	Total Height	Kz	qz	N-S	N-S	N-S	E-W	E-W	E-W
Ticigitto		rieigin			Windward	Leeward	Side Wall	Windward	Leeward	Sidewall
18	Penthouse	92.5	0.9675	14.354	11.54	-8.21	-10.43	12.20	-4.91	-10.49
14.5	Roof	74.5	0.908	13.471	10.99	-8.21	-10.43	11.61	-4.91	-10.49
14	5	60	0.85	12.611	10.46	-8.21	-10.43	11.43	-4.91	-10.49
14	4	46	0.79	11.720	9.91	-8.21	-10.43	11.04	-4.91	-10.49
14	3	32	0.712	10.563	9.20	-8.21	-10.43	10.65	-4.91	-10.49
18	2	18	0.59	8.902	7.90	-8.21	-10.43	10.45	-4.91	-10.49

Table 3: Wind Story Forces, Shears, and Moments

	Wind Design							
Level	Load (kips)		Shear	(kips)	Moment (ft-k)			
	N-S	E-W	N-S	N-S E-W		E-W		
Pent	193.4	38.8	0	0	3481.3	698.2		
Roof	151.5	30.2	193.4	38.8	2196.7	437.6		
5	144.8	29.3	344.9	69.0	2026.7	410.7		
4	138.0	28.1	489.7	98.3	1932.5	393.8		
3	132.6	27.4	627.7	126.4	1856.3	384.1		
2	140.2	31.0	760.3	153.9	2523.7	557.2		
Total	900.5	184.8	900.5	184.8	10535.9	2183.4		

Note: Total Base Shear includes load from Windward and Leeward pressures

Page 19 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report

The wind story forces are summarized in these pictures of each side of the building. The story forces are on the left and the story shears are on the right side of the pictures.




Figure 7: Wind North-South Story Force and Shear Diagram




Figure 8: Wind East-West Story Force and Shear Diagram

Page 20 of 112	Westinghouse Electric Company
Jessica L. Laurito	Corporate Headquarters
Structural Option	Cranberry, PA
Advisor: Dr. Hanagan	April 7, 2009
· · · · ·	inal Dapart

These values are not extraordinary. The RAM checked values are different from the calculated ones from the point where q_z values come into the picture. They may be different because RAM actually calculated the values using finite element analysis instead of using Table 6-3 in ASCE 7-05.

From Table 6-3								
H (ft)	Kz	qz						
92.5	0.9675	14.354						
74.5	0.908	13.471						
60	0.85	12.611						
46	0.79	11.720						
32	0.712	10.563						
18	0.59	8.902						
0	0.57	8.456						

Table 4: Hand calculation and RAM values Comparison by Height

From RAM								
H (ft) K _z q _z								
92.5	0.966	14.331						
74.5	0.909	13.486						
60	0.854	12.670						
46	0.792	11.750						
32	0.714	10.593						
18	0.605	8.976						
0	0.575	8.531						

Since the wind pressures do not start with the same value, they cannot be expected to be equal at any point. However the values are similar to each other, confirming the accuracy of the hand calculated values.

Page 21 of 112	Westinghouse Electric Company
Jessica L. Laurito	Corporate Headquarters
Structural Option	Cranberry, PA
Advisor: Dr. Hanagan	April 7, 2009
-	Final Report

SEISMIC DESIGN AND ANALYSIS

Typically in Pennsylvania, wind controls the design of the building's lateral system. As previously stated, this is not the case for this particular redesigned concrete building. The weight of the concrete makes the building heavy enough to cause the seismic loads to increase dramatically. The seismic loads were calculated according to ASCE 7-05, Chapters 11 and 12. The loads were determined based on a response modification factor of 3. The structure fits into the "Concrete Moment-Resisting Frame" category of ASCE 7-05's Table 12.8-2 and the C_T and X values for the period calculations were found according to those values. Further calculations can be seen in Appendix D.

Seismic Design Values, ASCE 7-05									
Occupancy	ll	Table 1-1							
Importance Factor	I= 1	Table 11.5-1							
Site Class	D	Table 20.3-1							
Spectral Response Acceleration, short	S _S = 0.12	Figure 22-1							
Spectral Response Acceleration, 1 sec	S ₁ = 0.046	Figure 22-2							
Site Coefficient F _a	F _a = 1.6	Table 11.4-1							
Site Coefficient F _V	F _V = 2.4	Table 11.4-2							
MCE Spectral Response Acceleration, short	S _{MS} = 0.192	Eq. 11.4-1							
MCE Spectral Response Acceleration, 1 sec	S _{M1} = 0.1104	Eq. 11.4-2							
Design Spectral Acceleration, short	S _{DS} = 0.128	Eq. 11.4-3							
Design Spectral Acceleration, 1 sec	S _{D1} = 0.0736	Eq. 11.4-4							
Seismic Design Category	В	Table 11.6-1							

Table 5: Seismic Design Values and ASCE 7-05 References

Table 6: Seismic Design Values and ASCE 7-05 References

Seismic Design Values, ASCE 7-05								
Response Modification Coefficient	R= 3	Table 12.2-1						
Coefficient	C _U = 1.7	Table 12.8-1						
Fundamental Period	T= 1.600	Sec. 12.8.2						
Seismic Response Coefficient	C _S = 0.015	Eq. 12.8-3						
Building Height (above grade)	h= 92.5							

The weight of the building in concrete is over three and a half times as much as the weight of the original building in steel. The values in concrete are not even comparable to steel. The concrete loads are significantly larger, in every category. The values were checked in RAM and found to be similar. The different response modification coefficients yield different story forces, story shears, and moments as seen on the next page.

Page 22 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report

Floor	w _x (k)	h _x (ft)	h _x ^k (ft)	w _x h _x ^k	C _{vx}	Story Force F _x (k)	Story Shear V _x (k)	Moment at Floor (ft-k)
Penthouse	6481.1	92.5	1115.41	7229044	0.179	293.33	0	27133.348
Roof	18245.1	74.5	797.56	14551503	0.361	590.46	293.33	43989.083
5	14162.0	60	570.24	8075727	0.200	327.69	883.79	19661.364
4	13922.9	46	377.75	5259370	0.130	213.41	1211.48	9816.8534
3	16960.3	32	215.24	3650482	0.091	148.13	1424.89	4740.0283
2	17785.3	18	88.23	1569200	0.039	63.67	1573.02	1146.1239
1	19178.2						1636.69	
Sum	106734.9	92.5	3164.42	40335326	1.000	1636.69	1636.69	106486.8

Table 7: Story Shears, Forces, and Moments for R=3.0 in concrete new design

Table 8:	Story	shears.	Forces,	and	Moments	for	R=3.0 ir	i steel	as-built	desian

Floor	w _x (k)	h _x (ft)	h _x ^k (ft)	$w_x h_x^{\ k}$	C _{vx}	Story Force F _x (k)	Story Shear V _x (k)	Moment at Floor (ft-k)
Penthouse	4213	92.5	884.38	3725874	0.330	154.13	0	14256.981
Roof	4240.5	74.5	639.41	2711449	0.240	112.17	154.13	8356.3249
5	4713.6	60	462.27	2178985	0.193	90.14	266.29	5408.3285
4	4726.5	46	310.43	1467216	0.130	60.69	356.43	2791.9616
3	4724.0	32	180.20	851252	0.075	35.21	417.13	1126.8496
2	4653.4	18	76.08	354028	0.031	14.65	452.34	263.61354
1	5444.4						466.99	
Sum	28502.4	74.5	1668.39	11288804	1.000	312.86	466.99	17947.078




Figure 9: Seismic Forces and Story Shears

Page 23 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

MEMBER DESIGN

To determine the members to be used in the RAM Structural System model, hand calculations were performed. The loading used for the building was 70 PSF live load (50 PSF office and 20 PSF partition load) everywhere. An 80 PSF corridor live load could also have been used, but would have been excessive since corridors do not exist everywhere on the floor.

The one-way concrete slab was designed for the 45'x24' bay. Since after the beams are removed from the length, it is a 45'x22' bay, the $L_1>2L_2$ requirement is met for a one-way slab. The slab was determined to be 10" thick with #8 @ 12" O.C. in the top of the slab and also in the bottom at mid-span of the slab. The 10" thickness was determined based on the ACI 318 deflection criteria table and was designed by hand and checked in RAM. The minimum transverse reinforcement for shrinkage and temperature is #5@12" O.C. This design is also appropriate for both green roof areas. The calculation can be viewed in Appendix E. Even though the deflection table was used, the deflections were also checked by hand and found to be within the allowable limits of L/360 for live load and L/240 for total loading. Since the new system used is a one-way slab with beams, there is no punching shear requirement for the slab.




Figure 10: Redesigned Concrete Layout

Page 24 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report

After the preliminary design was done, the RAM model was built using RAM structural System and the Concrete module of the program. The lateral system was determined to be concrete moment resisting frames and spaced according to the picture below. The blue members are the gravity members and take no lateral forces. They are spaced every other frame on the plan.




Figure 11: Whole building framing

The beams sizes were calculated also for a 45' length and a 24' distribution along the entire length of the beam. The slab weight was taken into account as well as the weight of the beam. The beams are 24"x34" and for the particular one designed two rows of (6) #8 bars were sufficient. Shear reinforcement for the interior beam was also designed and found to need (3) #3 stirrups @5" at the ends of the beam and another section of the beam was found to require (3) #3 stirrups @12". The calculation can be seen in Appendix E of this report.

The beam design was checked in RAM and the beams were updated as necessary. The green indicates the members were ok as originally designed and needed by RAM no updating to make the members meet code. The blue members needed updating of beam size, rebar size and or placement, or stirrup placement in order to meet all the code requirements. Any red members would indicate a failure to meet one of the code requirements. As seen in the picture below, all beams meet the code requirements.

Page 25 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report




Figure 12: Beam Framing for Whole Building

The columns were originally designed in PCA column for a few members. Once placed in RAM, they were evaluated for strength, slenderness, and torsion. The columns were also updated as required. The different colors represent the percent strength required vs. the available strength of the member. The closer to the color red the column is, the higher the ratio. Blue is the lowest ratio color. As is visible, all the columns also meet the code requirements after updating. Some needed to be resized, the rebar changed, and or the transverse reinforcing altered. The columns were also spot checked after design with PCA column and the loads taken from RAM. The typical column size is 24"x24" but there is also a significant number of 28"x28" columns, mainly in the lateral system. Most of the rebar layouts have 12 bars in them, but a few have 16 bars. The typical rebar size is #10's. The PCA spot checks for select columns can be seen in Appendix E.





Figure 13: Column Framing for Whole Building

Page 26 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

The lateral system is more clearly shown here with the third floor plan. The blue frames are gravity only and the red are lateral members.






Figure 14: Whole building plan

Concrete moment resisting frames are the main lateral system. A typical detail can be seen on the right. CMRF's are more in the concept phase now. They work by assuming a concrete frame is forced to work a certain way. The rebar proceeds through the slab at an angle and continues up into the above column. The rest of the reinforcing remains the same as is designed for gravity and lateral loading. Because the rebar extends through the slab, it is possible to transfer the moment through the frames easier than in typical concrete columns.

Page 27 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report

FOUNDATION IMPACT OF NEW STRUCTURE

The redesigned building is much heavier than the as-built steel structure. Since the original spread footings and deep foundation caissons were designed for a lighter dead load, they must be resized and updated. The difference was taken into account in the schedule and cost. A sample of the spread footings and caissons were taken and the original capacity was determined. For the spread footings, a simple Capacity= Area/ Soil Bearing Pressure calculation was performed. The bearing pressure is 8000 PSF for the site in Pittsburgh, according to the current drawings and foundation notes. The required force was determined by comparing all possible combinations and taking the most critical. The area of the spread footing foundation was calculated by using the same equation, with a slight alteration, Area= Capacity/Bearing Pressure. The required height of the new spread footing involved checking punching shear and overturning moment.

The three equations used to check punching shear are:

 $\begin{array}{l} & \phi(2+4\beta_{\rm C})\sqrt{(fc)b_{\rm O}d} \\ V_{\rm C} \leq & \phi 4\sqrt{(fc)b_{\rm O}d} \\ & \phi(\alpha_{\rm s}d/b_{\rm o}+2)\sqrt{(fc)b_{\rm o}d} \end{array}$

After punching shear was determined, the required height on the footing could be calculated using

 $d^{2} (4V_{C}+q) + (2V_{C}+q) w = q (BL-w^{2})$

The caisson calculation was more difficult. The depth was kept the same for both the old and new caissons. This calculation consisted of finding the axial capacity of the caisson (uplift was considered, but is resisted based on 0.9*Building Weight). The calculation performed was taking the area of the caisson and multiplying it by the allowable rock bearing pressure (which in this case is 30 KSF) and then subtracting the weight of the caisson. The size for the caissons listed in the next table is the diameter.

 π D/4*Bearing- π D/4*H*145= Capacity

The equation was entered into Excel to allow for ease of comparison of sizes and to allow for easier evaluation.

The new foundation sizes for the selected columns can be seen in the following table. The table was later used to determine the difference in the amount of concrete required for the foundations and to estimate the cost and labor required for the larger foundation system.

Size	Column	Type of Foundation	Size (ft)	Height (in)	Capacity (k)	Required (k)	Required Size	Required Height (in)	New Size (ft)	New Capacity (k)	Final Height (in)	RAM Size (ft)	RAM Height (in)
28	0.7-C	spread footing	5	18	200	384.844	6.936	18.273	7	392	22	8	24
24	1-B	spread footing	9.5	28	722	978.696	11.061	39.397	11.5	1058	44	11	36
24	1-C	spread footing	12	36	1152	1471.816	13.564	49.499	14	1568	54	13	42
24	1-D	spread footing	11	34	968	1606.032	14.169	51.518	14.5	1682	56	14	42
28	2-D	spread footing	12	36	1152	2179.108	16.504	56.044	17	2312	60	16	48
24	4-B	spread footing	10	32	800	1417.268	13.310	47.480	13.5	1458	52	13	42
30	1-E	caisson #48	5.5	146	712.749	957.832		146	7.00	1084.30	150		
28	6-B	spread footing	10	32	800	1454.464	13.484	42.858	13.5	1458	48	13	36
24	7.9-C	spread footing	13	40	1352	1342.364	12.954	45.460	13	1352	50	12	36
28	8-B	spread footing	11	34	968	922.328	10.737	33.426	11	968	38	11	30
24	8-C	spread footing	13	40	1352	1330.536	12.896	45.460	13	1352	50	12	36
48	13-A	spread footing	8	32	512	570.728	8.446	14.111	9	648	18	9	24
24	14-A.4	spread footing	8	32	512	418.416	7.232	25.211	8	512	30	7	18
24	15-B.7	spread footing	12	36	1152	1782.08	14.925	53.536	15	1800	58	14	48
28	16-E	caisson #53	4	306	376.991	1316.164		306	8.25	1399.22	310		

Table 9: Foundation size comparison

Page 29 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report

TORSION

Torsion must be accounted for in lateral systems due to the possibility for twisting and portions of the building being loaded in a non-uniform manner. The expansions joints allow the building to be treated structurally as three separate buildings based on the locations of the joints. To find the torsion, relative stiffness needs to be taken into account. Relative stiffness is a measure of stiffness as compared to other members in the frame. These relative stiffness values for each frame are distributed throughout the building by frames using distribution factors. The distribution factors are calculated by finding the total value of the stiffness for all the frames in a particular direction, and then finding what percent of the total each frame makes up. The stiffness is used as a basis to distribute the lateral loading through the building frames. Once both are found, the lateral loads can be distributed throughout the building. The center of mass of each section is shown in red on the following picture.




Figure 16: Center of Mass of concrete new design

Page 30 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report




Figure 17: Centers of Rigidity of new concrete design

Torsion was not an issue with the redesigned building in concrete. However, the concepts were taken into consideration accordingly. The RAM model checked for extra torsional requirements of the lateral members and found the concrete and the stirrups were enough to resist the accidental torsion= 5% and inherent torsional loading. The lateral members clearly incurred more torsion that the gravity members in the same direction. The story shears of the lateral system frames are higher than those of the gravity system frames, as they should be. Also, frames further away from the centers of rigidity and mass are more susceptible to torsion, and as such, have higher story shears, which are reflected in the RAM output in Appendix B.




Figure 18: Center of Rigidity and Frames for Comparison

Page 31 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

PORTAL METHOD

A portal method analysis was performed to find the moments and shear forces in the members of two frames (one from each the East-Frame 2 and Center- Frame 13 portions). This analysis was performed using the controlling seismic force on the individual frame as determined through the analysis and a RAM confirmation.




Figure 19: Portal Analysis of Frame 2 East Building with Seismic Loads Applied

Page 32 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009






Figure 20: Portal Analysis of Frame 13 in the Center Building with Seismic Loads Applied

Page 33 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

MEMBER CHECKS

For the new design of the building, before sizes could be checked in RAM Structural system, preliminary sizes needed to be determined. The preliminary beam checks can be seen in Appendix E. A live load of 70 PSF (50 PSF office loading and 20 PSF partition load) was used to determine the sizes. A live load of 80 could have been used, but the load of 80 PSF is for a corridor, and although there are no tenant fit-out drawings, there will not be corridors everywhere in an office building and it is acceptable to use the current loading. The preliminary design indicated the initial sizes of beams and columns for the building model. Once the sizes were assigned in the RAM Concrete design module, a full analysis was performed to check for the feasibility of all the members in the building and the lateral system's integrity. After the building gravity and lateral loads were determined by hand, they were then checked by RAM and their validity was confirmed. The columns were checked by using PCA column and can also be seen in Appendix E. An example column check is shown on the next page. A lateral beam check was performed after the moments determined through the portal analysis were applied to a specific member. The lateral beam check can also be seen in the beam is adequate for all load combinations in ASCE 7-05. The lateral beam check can also be seen in the Member Design Appendix.




Figure 21: PCA Column Output of Column 5-C 3rd Floor

For the column check, column 5-C was chosen. This column is also on the third floor of the building. The seismic building response controls the design of the building in concrete.

Page 34 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report

DRIFT

ASCE 7-05 was used to determine the appropriate allowable drifts for wind and seismic effects. Due to drift involving serviceability rather than strength, ASCE 7-05 requires in section CC.1.2 the drift be less than H/400 on a wall or frame. The story drift was determined through RAM Analysis and checked against the ASCE 7-05 requirements. The wind was checked for all three portions of the building for each controlling load combination. The maximum story drift for each of the three portions was checked against the allowable drift according to ASCE 7-05 and the worst case scenario drift is seen below and is compared to the original steel building drift.

Table 10: Wind Drift of Concrete Redesign

	Controlling Wind											
Story	Story	Story Drift	Allo	owable S	Story Drift (in)	Total Drift	Al		Total Drift (in)			
Story	height (ft)	(in)		Δ_{Wind} =	= H/400	(in)		Δ_{Wind}	_i =H/400			
Penthouse	92.5	0.045	<	0.54	Acceptable	0.38814	<	2.775	Acceptable			
Roof	74.5	0.033	<	0.435	Acceptable	0.34359	<	2.235	Acceptable			
5	60.0	0.050	<	0.42	Acceptable	0.31057	<	1.8	Acceptable			
4	46.0	0.068	`	0.42	Acceptable	0.2606	<	1.38	Acceptable			
3	32.0	0.088	<	0.42	Acceptable	0.19286	<	0.96	Acceptable			
2	18.0	0.105	<	0.54	Acceptable	0.10536	<	0.54	Acceptable			

Table 11: Wind Drift of Original Steel Design

	Controlling Wind											
Story	Story height (ft)	Story Drift (in)		le Story Drift (in) _{/ind} = H/400	Total Drift (in)		Allowable Total Drift (in) Δ_{Wind} =H/400					
Roof	74.5	0.127	< 0.435	5 Acceptable	1.02425	<	2.235	Acceptable				
5	60.0	0.187	< 0.42	Acceptable	0.89767	<	1.8	Acceptable				
4	46.0	0.247	< 0.42	Acceptable	0.71044	<	1.38	Acceptable				
3	32.0	0.257	< 0.42	Acceptable	0.46336	<	0.96	Acceptable				
2	18.0	0.207	< 0.54	Acceptable	0.20662	<	0.54	Acceptable				

For seismic drift, table 12.12-1 was used to find the maximum drift of $0.02h_{sx}$, since the structure falls into the "All other structures" category of the table. This was then converted into an elastic drift ratio using equation 12.8-15 as follows so the values could be compared to RAM output, which is available upon request.

$$\delta_x = C_d * \delta_{xe} / I$$

 $0.02h_{sx} = (3^* \delta_{xe}) / 1.0 = 0.06$
drift ratio= $\delta_{xe} / h_{sx} = 0.02^* 1.0 / 3 = 0.0066667$

Table 12: Seismic Drift of Concrete Redesign

Controlling Seismic						
Story	Story height (ft)	Acutal Drift Ratio	Allowable _{5xe} /h _{sx} =0	e Total Drift Ratio).02*1.0/3		
Pent	92.5	0.0004	<	0.006667		
Roof	74.5	0.0005	<	0.006667		
5	60.0	0.0008	<	0.006667		
4	46.0	0.0009	<	0.006667		
3	32.0	0.001	<	0.006667		
2	18.0	0.0009	<	0.006667		

Table 13: Seismic Drift of Steel Design

Controlling Seismic					
Story	Story height (ft)	Acutal Drift Ratio	Allowable Total Drift Ratio δ_{xe}/h_{sx} =0.02*1.0/3		
Roof	74.5	0.0011	< 0.006667		
5	60.0	0.0013	< 0.006667		
4	46.0	0.0014	< 0.006667		
3	32.0	0.0012	< 0.006667		
2	18.0	0.0006	< 0.006667		

Comparing the drift ratios for wind and seismic forces to the allowable drift, it can be concluded that drift is not an issue for either load. It can also reasonably be confirmed that the concrete structure is less susceptible to drift than the steel building.

Page 36 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report

OVERTURNING MOMENT

Overturning moment is a design issue that needs to be taken into consideration for steel building, but in general concrete buildings resist the overturning moment purely by the weight of the building. The calculation below is just to show how little the overturning moment impacts the design for this concrete building.

 $M_{WN-S} = 1.6^*Moment from Wind Design = 81566 \text{ k-ft}$ $M_E = \Sigma H(\text{ft})^*Earthquake Design Load(k) = 106487 \text{ k-ft}$ $P_{Uplift} = M/L = 647.3497 \text{ k}$ $P_{DBIdg} = 87557 \text{ kips}$ Load on Opposite Columns = 0.9P_D = 78800.99 \text{ kips} $M_{Resisting} = P^*Trib \text{ Area} = 4964462 \text{ k-ft}$ $M_{Resisting} > M_E > M_W$

Clearly the overturning moment is insignificant when compared to the weight of the building.

DEPTH STUDY OVERVIEW

The intent of this study was to practice concrete design and design a building capable of being built according to all applicable codes. Lateral analysis determined both the wind and seismic loads, and also determined the building to be seismically controlled as opposed to the original steel building being controlled by wind load. Lateral frames were eliminated from every frame, to every other frame, which is definitely a success in the design. Torsion was checked for this building, and found to be as expected. As also would be expected, the lateral members are a bit larger than the gravity only members, though not significantly. The addition of the green roof had some structural implications with the sizing of columns and beams supporting such a massive load, but did not cause any serious issues in the design.

Page 37 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

BREADTH STUDY 1- CONSTRUCTION MANAGEMENT ANALYSIS

COST ANALYSIS

Before a final response to the proposed changes can be evaluated, cost and schedule implications must be considered. The building in concrete is completely structurally different from a steel building. A budget for the asbuilt building was obtained from Turner Construction Company and was compared to the redesigned concrete building cost. An estimate for the redesign was calculated using RSMeans and the new structure volume of concrete and weight of steel rebar. Cost estimates for the building structure with and without the green roofs were developed. It was necessary to develop a schedule and estimate without a green roof so it could be more accurately compared to the existing steel building, which does not have a green roof.

 Table 14: Cost Estimate for Redesigned Building without Green Roofs

Detailed Cost Analysis of the Structure-No Green Roof									
Level	Description	Amount	Material Price	Material Cost	Labor Price	Labor Cost	Equipment Price	Equipment Cost	Total Cost
	Foundation	58 Ton	\$935.00	\$54,230	\$430.00	\$24,940	\$30.35	\$1,760	\$80,930
Deinforcoment	Columns	156Ton	\$935.00	\$147,263	\$430.00	\$430.00	\$30.35	\$4,780	\$152,473
Reinforcement	Beam/Slabs	504 Ton	\$935.00	\$470,642	\$430.00	\$216,445	\$30.35	\$15,277	\$702,363
	SUB-TOTAL	719	\$935.00	\$672,134	\$430.00	\$241,815	\$30.35	\$21,817	\$935,766
	Foundations	6100 CY	\$109.00	\$664,900	\$14.90	\$90,890	\$5.55	\$33,855	\$789,645
Cast in Place	Columns	1443 CY	\$109.00	\$157,189	\$34.00	\$49,031	\$16.95	\$24,444	\$230,664
ouor in r ideo	Slabs	14192 CY	\$109.00	\$1,546,928	\$18.20	\$258,294	\$9.15	\$129,857	\$1,935,079
Concrete	Beams	6477 CY	\$109.00	\$706,026	\$26.50	\$171,648	\$1,320.00	\$8,550,036	\$9,427,710
	SUB-TOTAL	28211	\$109.00	\$3,075,043	\$20.20	\$569,864	\$1,352	\$8,738,191	\$12,383,098
Location Factor:	Total Structure	Estimate:	\$13,17	73,000		Total L	abor Cost:	\$812,0	00
98.9%	Total Materia	al Cost:	\$3,74	8,000	-	Total Equ	uipment Cost:	\$8,761,	000

Table 15: Turner's Budgets

Turner Construction Company Budgets				
Deep foundations (caissons)	\$215,000			
Concrete (Spread ftgs, slabs)	\$5,199,000			
Structural Steel	\$7,892,000			
Total Structure	\$13,306,000			
Whole Building	\$55,878,000			

Turner's whole building budget was \$55,878,000. Their entire structure budget was \$13,306,000, which is approximately equal to the concrete redesign estimate. The cost per square foot for the as-built building is \$30.90/SF while the new building in concrete is \$30.60/SF. Some reasons for the cost of the building being so much greater for concrete than for the steel could be Turner's budget came directly from subcontractors and there was competition for the work or also that their estimates were real numbers and are therefore more accurate than an RSMeans estimate.

SCHEDULE ANALYSIS

A schedule analysis was also necessary to evaluate the two structures. Microsoft Project was used to generate a schedule for the redesigned concrete building. To develop the duration times of each slab, the building was split into

Page 38 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

columns. The beams were formed first, then the slab right after. The two were reinforced together, but the beams were placed before the slab. After the slab had accrued three-day strength, the columns on that floor were formed. The columns went through the same process with the beams above being formed after the columns had accrued the same three-day strength. Both structures were started on the same day, March 3, 2008. Turner's schedule has the concrete on the penthouse done being placed on October 10, 2008. The schedule produced for the redesigned concrete building estimates the penthouse slab finished on December 9, 2008. The entire schedule calendar can be seen in Appendix F. A Gantt chart is available upon request but was not included due to its length but a condensed Gantt chart is included. The condensed Gantt chart shows the first few tasks, and the method is repeated for each section on each floor throughout the building.



Figure 22: Sample Floor Plan Divided (3rd Floor)

ent Slab Sec. 1 Slab Sec. 1 Slab Sec. 1 Sasement Slab Sec. 1 Columns Sec. 1	1 day Tr 6 days W 1 day Th 1 day Fr 1 day Fr 1 day Mo 5 days Tu 5 days Tu	Ion 3/3/08 Mon 3/3/ Fue 3/4/08 Tue 3/4/ Ved 3/5/08 Wed 3/12/ Ved 3/5/08 Wed 3/12/ Ved 3/13/08 Thu 3/13/ Fri 3/14/08 Fri 3/14/ Fri 3/14/08 Fri 3/14/ Fri 3/14/08 Fri 3/14/ Sri 3/17/08 Mon 3/17/ Mon 3/17/08 Mon 3/2/ ve 3/18/08 Mon 3/2/	
Jec. 1 ent Stab Sec. 1 Stab Sec. 1 Stab Sec. 1 Stab Sec. 1 Journes Sec. 1 Columns Sec. 1 Columns Sec. 1 Columns Sec. 1	6 days W 1 day Th 1 day Fi 1 day Fi 1 day Ri 1 day Mo 5 days Tu 5 days Tu	Ved 3/5/08 Wed 3/12/ hu 3/13/08 Thu 3/13/ Fri 3/14/08 Fri 3/14/ Fri 3/14/08 Fri 3/14/ an 3/17/08 Mon 3/17/ ae 3/18/08 Mon 3/24/	
ent Slab Sec. 1 Slab Sec. 1 Slab Sec. 1 Issement Slab Sec. 1 Columns Sec. 1 Columns Sec. 1 Columns Sec. 1	1 day Th 1 day Fi 1 day Fi 1 day Mo 5 days Tu .5 days Tu	hu 3/13/08 Thu 3/13/ Fri 3/14/08 Fri 3/14/ Fri 3/14/08 Fri 3/14/ an 3/17/08 Mon 3/17/ Jae 3/18/08 Mon 3/24/	
Slab Sec. 1 Slab Sec. 1 Sasement Slab Sec. 1 Columns Sec. 1 Columns Sec. 1 Columns Sec. 1	1 day Fi 1 day Fi 1 day Mo 5 days Tu .5 days Tu	Fri 3/14/08 Fri 3/14/ Fri 3/14/08 Fri 3/14/ an 3/17/08 Man 3/17/ ar 3/18/08 Man 3/24/	
Slab Sec. 1 Sasement Slab Sec. 1 Columns Sec. 1 ent Columns Sec. 1 Columns Sec. 1	1 day Fi 1 day Mo 5 days Tu .5 days Tu	Fri 3/14/08 Fri 3/14/ an 3/17/08 Man 3/17/ ar 3/18/08 Man 3/24/	
Sasement Slab Sec. 1 Columns Sec. 1 ent Columns Sec. 1 1 Columns Sec. 1	1 day Mo 5 days Tu .5 days Tu	an 3/17/08 Man 3/17/ ue 3/18/08 Man 3/24/	· · · · · · · · · · · · · · · · · · ·
Columns Sec. 1 ent Columns Sec. 1 1 Columns Sec. 1	5 days Tu .5 days Tu	ue 3/18/08 Mon 3/24/	» ****
ent Columns Sec. 1 1 Columns Sec. 1	.5 days Tu		
Columns Sec. 1		e 3/25/08 Wed 3/264	
	1 4		38
asement Columns Sec. 1		ed 3/26/08 Thu 3/27/	38
	1 day Ti	Tue 4/1/08 Wed 4/2/	м — — — — — — — — — — — — — — — — — — —
sams Sec. 1	2 days Th	hu 3/27/08 Mon 3/31/	м на
		an 3/31/08 Thu 4/3/	м
or Slab And Beams Sec. 1	1 day TI	hu 4/3/08 Fri 4/4/	38
earns Sec. 1	1 day	Fri 4/4/08 Mon 4/7/	N
ab Sec. 1		Ion 4/7/08 Tue 4/6	
lab Sec. 1		fon 4/7/08 Tue 4/6/	
st Beams Sec. 1	1 day Th	w 4/10/08 Fri 4/11/	· · · · · · · · · · · · · · · · · · ·
inst Floor Slab Sec. 1	1 day Fr	ri 4/11/08 Mon 4/14	36 Temperature 1 and
slumns Sec. 1		an 4/14/08 Mon 4/21/	
		m 4/21/08 Tue 4/22	»
ns Sec. 1	1 day We	ed 4/23/08 Wed 4/23/	»
st Columns Sec. 1	1 day Mo	an 4/28/08 Mon 4/28/	s
earns Sec. 1 1	.5 days T	hu 5/1/08 Fri 5/2/	n Tresser
et. 1	4 days	Fri 5/2/08 Thu 5/8	» ***
or Slab And Beams Sec. 1 1	5 days T	hu 5/8/08 Fri 5/91	x
lab Sec. 1	1 day Mo	an 5/12/08 Mon 5/12/	»
Sab Sec. 1			
olumns Sec. 1			38 · · · · · · · · · · · · · · · · · · ·
		ve 5/20/08 Wed 5/21/	
ns Sec. 1			
	r Bab And Beans Sec. 1 amma Sec. 1 amma Sec. 1 bab Sec.	rgbb And Banns Sec.1 1 day T mm Sec.1 1 day M do Ber.1 1 day M do Ber.1 1 day M do Ber.1 1 day M mark Ber.1 1 day M dotter.1 1 day M mark Ber.1 1 day M dotter.1 1 day M	r Bab And Barron Stort 1 day The 4.000 FF 44400 nam Stort 1 day FF 4460 Mon 477 nam Stort 1 day Mon 4770 The 4400 na line: 1 1 day Mon 4770 The 440 na line: 1 1 day Mon 47700 The 4400 na line: 1 1 day Mon 47700 The 440 na line: 1 1 day Mon 47700 The 440 nam 56: 1 1 day Mon 47700 The 440 nam 56: 1 5 day Mon 47100 Mon 47200 nam 56: 1 1 day Mon 47200 The 4400 nam 56: 1 1 day Mon 47200 Mon 47200 nam 56: 1 1 day Mon 47200 Mon 47200 nam 56: 1 1 day Mon 57200 Mon 47200 nam 56: 1 1 day Mon 57200 Mon 5720 nam 56: 1 1 day Mon 57200 Mon 5720 nam 56: 1 5 day Ta 55300 Mon 57100

Figure 23: Condensed Gantt chart

BREADTH STUDY 1 OVERVIEW

The goals for the construction management breadth study of calculating a cost estimate and generating a schedule were certainly met. Also, a cost estimate and schedule were generated and compared with the addition of the green roof and to Turner Construction Company's original estimate and schedule. It was determined that Turner Construction Company managed to erect the building much faster and cheaper in steel than the design would have been in concrete. Concrete generally does take longer to erect than steel due to the curing time and placing and stripping of the formwork. This breadth portion of the project was a success even though it was not the most efficient - in time or money- way to build this building.

Page 39 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

BREADTH STUDY 2- SUSTAINABLE ARCHITECTURE

Since one of the owner's goals was to have a LEED certified building, adding another green feature seemed to be a realistic option. The way the Westinghouse Electric Company Corporate Headquarters Building One is situated, with a large portion of the building facing south, a green roof would be just one more way to make the building "green". Green roofs help to integrate their buildings into the natural surroundings and can be used for various activities for the office. These areas can be used as patios, lunch areas, or meeting areas.




Figure 24: 3rd Floor Plan Center with Green Roof

A LEED credit analysis was also performed to check to see the viability of making the redesigned concrete building a LEED Certified building as well as the as-built one. The redesigned building was able to achieve 28 credits, with the requirement for certification at 26. The actual checklist can be seen in Appendix G. The benefits of a green roof are extensive. They make the recycled water content quality better, and provide a clean way to collect it as well as limiting the heat island effects.

The green roof materials selected are modular, meaning the sod and plants come in rectangular sections capable of being moved around if the owner decides to change the layout of the walkways and the soil. Native Pennsylvania plants will be used on the green roof patio. The green roof on the third floor will be available for use as an outdoor patio, and was treated as such with loading.




Figure 25: Roof Plan Center with Green Roof





Page 40 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report

However, the green roof on the top of the building will not be accessible except for service conditions.

Green roofs typically consist of soil and vegetation, a filter of some sort of fabric, a drainage system, a moisture barrier, insulation, a root barrier, a protection layer, and a waterproofing membrane.




Figure 27: Green Roof Detail courtesy of www.deq.state.mi.us/documents/deq-ess-p2-p2week-greenroofreources.doc


Carlisle Coatings and Waterproofing has a green roof waterproofing system that fits exactly what this building requires. CCW is located in Carlisle, PA, which is approximately 205 miles away from the site. They specify for an extensive green roof a CCS 500R Hot applied waterproofing membrane system, CCW Protection Board HS, a CCW Root Barrier consisting of 40-mil non-reinforced Geomembrane, a CCW MiraDRAIN 9800 Drainage Board, insulation as required, MiraDRAIN GR 9200, and CCW 300HV Water Retention Mat, all underneath the soil. The full specification can be found at

www.carlisle-ccw.com/Doco/spec07555613CCW500RGreenRoofWaterproofingSystem.pdf.

Also, for this study, since the green roof will be retaining water, pipes were spaced and sized for water flow. The green roof on the third floor was separated into three parts- two 6,131 SF sections and one 6,419 SF section. The green roof on the roof level of the building was split into six equal 6,434 SF sections. For all the sections used, two 3" pipes were found to meet the code requirements. The Portal Plus Roof Drain Calculator was used to help size the drains and pipes (located at www.portalplus.com/drain_calc.htm). The calculation is performed based on the 100-year storm. This calculation takes each local code and translates it based on the area of the roof area.

Detailed Cost Analysis of the Structure									
Level	Description	Amount	Material Price	Material Cost	Labor Price	Labor Cost	Equipment Price	Equipment Cost	Total Cost
	Foundation	58 Ton	\$935.00	\$54,230	\$430.00	\$24,940	\$30.35	\$1,760	\$80,930
Deinforcoment	Columns	175 Ton	\$935.00	\$163,625	\$430.00	\$430.00	\$30.35	\$5,311	\$169,366
Reinforcement	Beam/Slabs	572 Ton	\$935.00	\$534,820	\$430.00	\$245,960	\$30.35	\$17,360	\$798,140
	SUB-TOTAL	805	\$935.00	\$752,675	\$430.00	\$346,150.00	\$30.35	\$24,432	\$1,123,257
	Foundations	6100 CY	\$109.00	\$664,900	\$14.90	\$90,890	\$5.55	\$33,855	\$789,645
Orat in Diana	Columns	1518 CY	\$109.00	\$165,462	\$34.00	\$51,612	\$16.95	\$25,730	\$242,804
Cast in Place	Slabs	14192 CY	\$109.00	\$1,546,928	\$18.20	\$258,294	\$9.15	\$129,857	\$1,935,079
Concrete	Beams	7197 CY	\$109.00	\$784,473	\$26.50	\$190,721	\$1,320.00	\$9,500,040	\$10,475,234
	SUB-TOTAL	29007	\$109.00	\$3,161,763	\$23.40	\$271,330	\$1,352	\$9,689,482	\$13,122,575
Location Factor:	Total Structure	Estimate:	\$14,33	32,000		Total Labor Cost:		\$863,0	000
98.9%	Total Materi	al Cost:	\$3,91	5,000		Total Equ	ipment Cost:	\$9,714,	.000


Table 16: Cost Estimate with green roof



Page 42 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

Some of the plants native to Pennsylvania able to be planted on the roof material are:



All the plants and figures are from the Audubon Society of Western Pennsylvania, Audubon Center for Native Plants webpage located at: <u>http://www.aswp.org/acnp_culture_and_use_guide.html</u>. Also, all the plants are smaller plants, which will mesh nicely into the green roof environment or rain garden environment and can be moved around and resituated easily. The plants also bloom at different points of the season, so from May until mid-winter there will be plants blooming on the roof. The Blue-eyed Mary emerges in the fall and stays green through the winter. The smallest plants tend to be shrubby, spread easily, and require little maintenance, which will keep costs down. Instead of grass for a base on the roof, the main plant is sedum, which is hardier than grass and is a preferred plant on such surfaces.

BREADTH STUDY 2 OVERVIEW

The green roof has a weight much larger than a typical roof and since one of the green roofs is going to be used as a patio, the live load also increases. These differences impact the size of the structural members, which also impact the cost of the structure and the schedule. The columns require an additional 19 tons more reinforcing and the beams and slabs require an additional 68 tons. The volume of concrete required for the structure to be able to support the green roof is: 75 CY for columns and 750 CY for the beams. These differences translate into \$1,159,000 which is equivalent to \$2.68/SF, more to add a green roof onto this redesigned concrete structure. As far as schedule is concerned, the building could be completed one week earlier without a green roof.

After all these items are considered, it can be concluded that adding a green roof is certainly a viable option for this building. The green roof portion of this report was a success. It met all the goals set for it such as proper integration of a green roof system into the building, detailing, specifying native plants and laying them out, and sizing of a pipe for water flow from the roof for drainage. The system also had a cost estimate and a schedule generated for it so the green roof could be compared to the new concrete design system. The difference in cost from the new system with a green roof and without a green roof was able to be calculated and compared and found to be not considerably higher when compared to the total cost of the building.

Page 43 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report

CONCLUSIONS AND RECOMMENDATIONS

The study and redesign of the Westinghouse Electric Company Corporate Headquarters Building One has been an overall success. Instead of using the same 80 PSF live load everywhere used in the previous technical reports, a live load of 70 PSF (50 PSF office load and 20 PSF partition load) was used uniformly throughout the upper floors of the building. The redesigned concrete building was able to be compared to the original steel building in terms of construction cost, schedule impact, and overall effectiveness. The redesigned building also had a green roof added to the building in order to integrate it into the environment and make a statement as a corporate headquarters.

The building was successfully redesigned with a concrete cast-in-place one-way slab with beams system using concrete moment resisting frames as the lateral system. Shear walls were considered for this design, but could not be used effectively due to the necessity of an open plan for tenant fit-out requirements. The slab, beams, columns, and foundations were all designed or resized according to ACI 318-08 and ASCE 7-05 and the applicable sections. Once a preliminary design was established, the building was modeled in RAM Structural System and checked for validity and uniformity of members and reinforcement and torsion.

Since the building material was changed to concrete, the weight of the building significantly increased, causing the seismic loads to change. In the original steel design, wind was the controlling lateral load in one of the directions and seismic controlled the other direction. However, in the concrete redesign seismic load controls the lateral system. The lateral loads were checked in RAM as well. Drift ratios and drift were determined in RAM and checked to the allowable values for serviceability from ASCE 7-05 and found to be acceptable. A hand check was performed on a lateral beam to ensure the validity of the structural design. Uplift is not an issue because the pure weight of the building will hold the building down. The foundations were resized according to the required strength for both the spread footings and the caissons. All the goals for the structural part of this project were met, making it a success.

After all analyses were performed for the design of the concrete building, the building was compared to the original steel building. It can be reasonably concluded steel is a more efficient system than concrete in this particular application. The cost estimate was compared to Turner's budget, and found to be significantly higher. The schedule for the new building was generated and also compared to Turner's and was found to be two months longer. While the project was a success in terms of the goals, it was not ideal since the proposed modifications extended the schedule and increased the cost.

As far as the sustainable architecture breadth is concerned, the project was also a success. The green roof was detailed, materials specified, drainage pipes sized based on local code requirements, and plants specified for the area. Additionally, the green roof impacts the structure and causes the columns and beams to be larger. The green roof increases the structural cost \$1,159,000 (\$2.68/SF) and increases the schedule by one week.

All parts of this analysis considered, it is not recommended to make the building structure concrete instead of steel. The building can be built at a better value and has a much faster erection time in steel. However, it is recommended to use more sustainable architecture in the form of a green roof. The total cost of the building does not change comparatively when it is added, and it increases the value of the building with respect to LEED certification and incorporation into the environment.

Further calculations can be found in the appendices. Additional calculations for wind and seismic loading and the RAM Model are available upon request.

Page 44 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

APPENDIX A: TYPICAL FLOOR LAYOUT



Figure 35: Second Floor Layout of As-Built Building




Figure 36: Second Floor Layout of Center or As-Built building



Figure 37: Third Floor East of Redesigned Concrete Building with Portal Analysis Frame Indicated and Columns for Column Checks Indicated





Figure 38: Third Floor Center of Redesigned Concrete Building with Portal Analysis Frame Indicated and Columns for Column Checks Indicated








Figure 40: Green Roof Plan Center of Redesigned Building with Portal frame Analysis, lateral Beam Check, Interior Beam Check, and Spot Checked Columns Indicated

Page 50 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report

APPENDIX B: TORSION EFFECTS CALCULATIONS

The centers of rigidity for each direction were determined by taking the sum of the stiffness in one direction multiplied by the distance from the perpendicular distance from the origin (distance from the opposite origin) all divided by the sum of the stiffness for each frame used in the calculation. For example, the center of rigidity in the Y direction was calculated by taking the K in the X direction and multiplying it by the distance from the Y origin, and finding the sum of all the values divided by the sum of the K's in the X direction (Kix*dix/ΣKix). The Ix was calculated by taking the sum of the K's in the X direction multiplied by the distance from the Y origin squared (Σ kix*yi²). The Iy was calculated using the same method.

> Center of Rigidity in Y= Kix*dix/ Σ kix Center of Rigidity in X= Kiy*dix/ Σ kiy Ix= Σ kix*yi² Iy= Σ kiy*xi²

After the K values were determined, the K in the direction of the force was divided by the sum of the K's in the same direction and multiplied by the force in the specific direction. The torsion induced moment in each direction was determined differently for wind and for seismic.

For seismic forces, the torsion induced moment was calculated by taking the force at the specified story multiplied by the center of rigidity subtracted from center of mass in the direction perpendicular to the force.

Torsion Induced Moment X= (Force)*(Center of Mass in Y direction- Center of Rigidity in X direction)




Figure 41: Centers of Mass for New Building

Page 51 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report




Figure 42: Centers of Rigidity for New Building




Figure 43: Center of Rigidity and Frames for Comparison

Page 52 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report

As is seen in the following figures of the wind shears from frames 19 and 22, the further away from the center of rigidity the frame is located, the more torsion and shear the frame takes. The concept of torsion is evident in these frames.

Load Case: W9 Win	d Wind IB	C06_4_X+Y_CW		
Level	Shear-X	Change-X	Shear-Y	Change-Y
	kips	kips	kips	kips
Roof	24.27	24.27	17.43	17.43
Fifth	29.05	4.78	20.97	3.54
Fourth	43.42	14.37	31.90	10.93
Third	51.17	7.75	38.22	6.32
Second	46.66	-4.51	33.40	-4.82
First	-9.04	-55.70	-11.12	-44.52

Figure 44: Wind Shears Frame 19

Load Case: W9 Wind	C06_4_X+Y_CW			
Level	Shear-X	Change-X	Shear-Y	Change-Y
	kips	kips	kips	kips
Penthouse	3.26	3.26	3.47	3.47
Roof	3.71	0.45	7.56	4.10
Fifth	9.77	6.06	15.69	8.12
Fourth	12.68	2.91	20.61	4.92
Third	18.67	5.99	27.52	6.92
Second	19.37	0.70	35.57	8.05
First	-3.24	-22.62	-10.30	-45.87

Figure 45: Wind Shears Frame 22

Load Case: E1 Seismic EO IBC06_X_+E_F						
Level	Shear-X	Change-X	Shear-Y	Change-Y		
	kips	kips	kips	kips		
Roof	50.00	50.00	15.85	15.85		
Fifth	49.63	-0.37	14.53	-1.33		
Fourth	64.72	15.09	19.06	4.54		
Third	66.40	1.68	20.10	1.04		
Second	73.12	6.72	15.00	-5.10		
First	-23.19	-96.31	7.26	-7.74		

Figure 46: Seismic Shears Frame 19

Load Case: E1 Seismic EQ IBC06_X_+E_F						
Level	Shear-X	Change-X	Shear-Y	Change-Y		
	kips	kips	kips	kips		
Penthouse	20.03	20.03	6.15	6.15		
Roof	26.35	6.32	-6.05	-12.20		
Fifth	47.99	21.64	-4.00	2.05		
Fourth	56.10	8.12	-5.38	-1.38		
Third	65.66	9.56	-5.03	0.35		
Second	60.39	-5.28	-4.42	0.61		
First	-17.19	-77.57	6.33	10.75		

Figure 47: Seismic Shears Frame 22

APPENDIX C: WIND LOAD CALCULATIONS

MAIN WIND-FORCE RESISTING SYSTEM (ASCE 7-05)

Table 18: Wind Calculation Conditions

Basic Wind Speed (V) mph	90
Exposure Category	В
Importance Factor (I)	1
Wind Directionality Factor (Kd)	0.85
Topographic Factor (Kzt)	1

BUILDING L/B AND VALUES

Table 19: Windward, Leeward, and Sidewall constants

		L/B	C _p
East-West Direction			
	Windward	4.317	0.8
	Leeward	4.317	-0.2
	Sidewall	4.317	-0.7
North-South Direction			
	Windward	0.232	0.8
	Leeward	0.232	-0.5
	Sidewall	0.232	-0.7

Table 17: Wind Calculation Constants

	Wind Direction			
Variable	N-S	E-W		
Stiffness	Flex	Flex		
В	544	126		
L	126	544		
h	92.5	92.5		
Z	30'	30'		
l	320	320		
E	0.333	0.333		
α	0.25	0.25		
β	0.05	0.05		
V	90	90		
Vz	67.644	67.644		
Lz	380.55	380.55		
n ₁	1.163	1.163		
N ₁	6.54	6.54		
R _n	0.043	0.043		
R _h	0.127	0.127		
R _b	0.023	0.095		
RL	0.030	0.007		
b	0.45	0.45		
R	0.037	0.074		
l _z	0.275	0.275		
g _R	0.000	0.000		
q _p	14.836	14.836		
g _v	3.4	3.4		
Q	0.731	0.832		
G _f	0.772	0.830		

0.731

0.832

WIND CALCULATIONS CONTINUED:

$$q_{p} = 0.00256 K_{h}K_{zt}K_{d}V^{2}l = 14.836$$

$$GCpn = 1.5 -1$$

$$Pp = q_{p}GCpn = 22.254 -14.836$$

$$n_{1} = 43.5 -1.163 eq (C6-15)$$

$$H^{0.9}$$

n₁> 1 therefore Rigid structure

$$\begin{array}{rcl} g_{Q} &=& g_{V} =& 3.4\\ G &=& 0.85\\ &z &=& 0.6h =& 55.5\\ z_{min} &=& 30'\\ I_{z} &=& c(33/z)^{1/6} &=& 0.275\\ L_{z} &=& l(z/33)^{e} &=& 380.55\\ Q_{N-S} &=& \sqrt{(1/(1+0.63(B+h/L_{z})^{0.63}))} =&& 0.731\\ Q_{E-W} &=& \sqrt{(1/(1+0.63(B+h/L_{z})^{0.63}))} =&& 0.832\\ G_{fN-S} &=& 0.925 \left[(1+1.7I_{z}g_{Q}Q)/(1+1.7g_{v}I_{z})\right] =&& 0.772274\\ G_{fE-W} &=& 0.925 \left[(1+1.7I_{z}g_{Q}Q)/(1+1.7g_{v}I_{z})\right] =& 0.829674 \end{array}$$

WIND CALCULATIONS CONTINUED:

	Table 20: Design Wind Pressure in N-S							
	Design Wind Pressures p in N-S Direction (Table 5.41)							
Location	Height above Ground Level z (ft)	q(psf)	External Pressure qGC _p (psf)	Internal Pressure q _h GC _{pi}	Net Press	ure p (psf)		
	2 (11)		qoo _p (psi)	Ч _h OO _{pi}	+Gcpi	-Gcpi		
Windward	92.5	14.354	8.87	2.67	6.20	11.54		
	74.5	13.47	8.32	2.67	5.65	10.99		
	70	13.20	8.16	2.67	5.49	10.83		
	60	12.61	7.79	2.67	5.12	10.46		
	50	12.02	7.42	2.67	4.75	10.09		
	46	11.72	7.24	2.67	4.57	9.91		
	40	11.28	6.97	2.67	4.30	9.64		
	32	10.56	6.53	2.67	3.86	9.20		
	30	9.79	6.05	2.67	3.38	8.72		
	25	9.20	5.68	2.67	3.01	8.35		
	20	8.46	5.22	2.67	2.55	7.90		
	18	8.46	5.22	2.67	2.55	7.90		
	15	8.46	5.22	2.67	2.55	7.90		
Leeward	All	14.35	-5.54	2.67	-8.21	-2.87		
Side	All	14.35	-7.76	2.67	-10.43	-5.09		

Table 21: Design Wind Pressure in E-W

	Design Wind Pressures p in E-W Direction (Table 5.41)						
Location	Height above Ground Level	q(psf)	External Pressure qGC _p (psf)	Pressure		sure p (psf)	
	z (ft)		400 _p (psi)	q _h GC _{pi}	+Gcpi	-Gcpi	
Windward	92.5	14.35	9.53	2.67	6.86	12.20	
	74.5	13.47	8.94	2.67	6.27	11.61	
	70	13.20	8.76	2.67	6.09	11.43	
	60	12.61	8.37	2.67	5.70	11.04	
	50	12.02	7.98	2.67	5.31	10.65	
	46	11.72	7.78	2.67	5.11	10.45	
	40	11.28	7.48	2.67	4.81	10.15	
	32	10.56	7.01	2.67	4.34	9.68	
	30	10.39	6.89	2.67	4.22	9.56	
	25	9.79	6.50	2.67	3.83	9.17	
	20	9.20	6.11	2.67	3.43	8.78	
	18	8.90	5.91	2.67	3.24	8.58	
	15	8.46	5.61	2.67	2.94	8.28	
Leeward	All	13.47	-2.24	2.67	-4.91	0.44	
Side	All	13.47	-7.82	2.67	-10.49	-5.15	

WIND CALCULATIONS CONTINUED:

							Wind Pre	ssures (psf)		
Floor Heights	Level	Total Height	Kz	q _Z	N-S	N-S	N-S	E-W	E-W	E-W
					Windward	Leeward	Side Wall	Windward	Leeward	Sidewall
18	Penthouse	92.5	0.9675	14.354	11.54	-8.21	-10.43	12.20	-4.91	-10.49
14.5	Roof	74.5	0.908	13.471	10.99	-8.21	-10.43	11.61	-4.91	-10.49
14	5	60	0.85	12.611	10.46	-8.21	-10.43	11.43	-4.91	-10.49
14	4	46	0.79	11.720	9.91	-8.21	-10.43	11.04	-4.91	-10.49
14	3	32	0.712	10.563	9.20	-8.21	-10.43	10.65	-4.91	-10.49
18	2	18	0.59	8.902	7.90	-8.21	-10.43	10.45	-4.91	-10.49

Table 22: Total Wind pressures by Height

	Wind Design							
Level	Load	Load (kips)		Shear (kips)		ent (ft-k)		
	N-S	E-W	N-S	E-W	N-S	E-W		
Pent	193.4	38.8	0	0	3481.3	698.2		
Roof	151.5	30.2	193.4	38.8	2196.7	437.6		
5	144.8	29.3	344.9	69.0	2026.7	410.7		
4	138.0	28.1	489.7	98.3	1932.5	393.8		
3	132.6	27.4	627.7	126.4	1856.3	384.1		
2	140.2	31.0	760.3	153.9	2523.7	557.2		
Total	900.5	184.8	900.5	184.8	10535.9	2183.4		

Table 23: Wind Forces, Shears, and Moment

Note: Total Base Shear includes load from Windward and Leeward pressures

WIND CALCULATIONS CONTINUED:

RAM COMPARISON

As these tables show, RAM values are around the same change from floor to floor as the hand calculations.

RAM values were compared further to the hand calculation method results used throughout the report and used in previous technical reports. The main differences have already been addressed, such as the possibility of a finite element analysis. The wind design table below is the final story force and story shears for the east portion of the building.

RAM CALCULATED VALUES

Table 24: RAM Calculated Wind Values

Гірат		Tatal				F	RAM Wind Pro	essures (psf)		
Floor Heights	Level	Total Height	Kz	q _z	N-S	N-S	N-S	E-W	E-W	E-W
ricigitta		ricigiti			Windward	Leeward	Side Wall	Windward	Leeward	Sidewall
18	Penthouse	92.5	0.966	14.331	11.57	-8.23	-10.46	11.57	-5.98	-8.23
14.5	Roof	74.5	0.909	13.486	11.05	-8.23	-10.46	11.05	-5.98	-8.23
14	5	60	0.854	12.670	10.54	-8.23	-10.46	10.54	-5.98	-8.23
14	4	46	0.792	11.750	9.97	-8.23	-10.46	9.97	-5.98	-8.23
14	3	32	0.714	10.593	9.25	-8.23	-10.46	9.25	-5.98	-8.23
18	2	18	0.605	8.976	8.25	-8.23	-10.46	8.25	-5.98	-8.23

Table 25: RAM Wind Forces, Shears, and Moments

	Wind Design					
Level	Load	(kips)	Shear	[·] (kips)	Moment (ft-k)	
	N-S	E-W	N-S	E-W	N-S	E-W
Pent	193.9	39.8	0	0	3491.0	716.6
Roof	152.1	31.1	193.9	39.8	2205.3	451.1
5	143.0	29.7	346.0	70.9	2001.8	415.3
4	138.6	28.1	489.0	100.6	1940.9	393.9
3	133.2	26.9	627.7	128.7	1864.2	376.2
2	161.4	28.7	760.8	155.6	2904.7	516.3
Total	922.2	184.3	922.2	184.3	10916.9	2152.9

Note: Total Base Shear includes load from Windward and Leeward pressures

APPENDIX D: SEISMIC LOAD CALCULATIONS

 Table 26:
 Seismic Design Values

	Seismic Design Values, ASCE 7-05		
Response Modification Coefficient	R= 3	R= 3.5	Table 12.2-1
Coefficient	C _U = 1.7	C _U = 1.7	Table 12.8-1
Fundamental Period	T= 1.497	T= 1.497	Sec. 12.8.2
Seismic Response Coefficient	C _S = 0.016	C _S = 0.014	Eq. 12.8-3
Building Height (above grade)	h= 74.5	h= 74.5	

Table 27: Seismic Design Values continued

Seismic Design Values, ASCE 7-05						
Occupancy	II	Table 1-1				
Importance Factor	I= 1	Table 11.5-1				
Site Class	D	Table 20.3-1				
Spectral Response Acceleration, short	S _S = 0.12	Figure 22-1				
Spectral Response Acceleration, 1 sec	S ₁ = 0.046	Figure 22-2				
Site Coefficient F _a	F _a = 1.6	Table 11.4-1				
Site Coefficient F _V	F _V = 2.4	Table 11.4-2				
MCE Spectral Response Acceleration, short	S _{MS} = 0.192	Eq. 11.4-1				
MCE Spectral Response Acceleration, 1 sec	S _{M1} = 0.1104	Eq. 11.4-2				
Design Spectral Acceleration, short	S _{DS} = 0.128	Eq. 11.4-3				
Design Spectral Acceleration, 1 sec	S _{D1} = 0.0736	Eq. 11.4-4				
Seismic Design Category	В	Table 11.6-1				

Table 28: Fv Values

F _v Values (Table 11.4-2 ASCE 7-05)					
	S₁≤0.1	S ₁ =0.3	S ₁ =0.3	S ₁ =0.4	S₁≥0.5
D	2.4	2	1.8	1.6	1.5

Table 29: Fa Values

F _a Values (Table 11.4-1 ASCE 7-05)					
	S _S ≤0.25	S _S =0.5	S _S =0.75	S _S =1.0	S _S ≥1.25
D	1.6	1.4	1.2	1.2	1

SEISMIC CALCULATIONS CONTINUED:

The values for all the seismic coefficients were determined using ASCE 7-05 equations and tables. The building was first confirmed as Seismic design category B by using Table 11.6-2 of ASCE 7-05. Once the design category had been confirmed, the approximate period was calculated by using equation 12.8-7 and table 12.8-2. Since ASCE 7-05 section 11.6 requires where an S₁ value is less than 0.75 the Seismic Design Category can be determined solely on table11.6-1 and 11.6-2 when T_a > 0.8T_S, the period used to calculate drift is less than T_S, equation 12.8-2 is used to find C_S, and rigid diaphragms are present.

Table 30: Seismic Response Value Comparison

Calculate	USGS Website Values	
S _S = 0.12	(From Figure 22-1)	S _S = 0.125
S ₁ = 0.046	(From Figure 22-2)	S ₁ = 0.048
$S_{MS} = F_a * S_s = 0.192$		S _{MS} = 0.2
$S_{M1} = F_V * S_1 = 0.1104$		S _{M1} = 0.116
S _{DS} = 2S _{MS} /3= 0.128	A (Table 11.6-1)	S _{DS} = 0.133
$S_{D1} = 2S_{M1}/3 = 0.0736$	B (Table 11.6-2)	S _{D1} = 0.077

 $C_{T} = 0.016$ (From Table 12.8-2) X = 0.9 (From Table 12.8-2) $T_{a} = C_{t}h_{n}^{x} = 0.9411255$ $T_{s} = S_{D1}/S_{DS} = 0.575$

 $0.8T_s = 0.46$ < T_a therefore must use Table 11.6-1,2

T_L= 12 (From Fig. 22-15 p. 228 ASCE 7-05)

 C_S values were calculated according to Section 12.8.1.1 equations 12.8-2, 12.8-3, and 12.8-4 and checked against the minimum requirement from EQ 12.8-5 of $C_S \ge 0.01$. Equation 12.8-3 is a maximum for this structure, and equation 12.8-4 does not apply since equation 12.8-3 does. The values were then compared based on R and what the professional calculated.

Page 60 of 112	
Jessica L. Laurito	
Structural Option	
Advisor: Dr. Hanagan	

		R=3
	$S_{DS}/(R/I) =$	0.0427
C _S = MAX	$S_{D1}/(T^*R/I) =$	0.0153
for T>T _L	$S_{D1}T_L/(T^2R/I) =$	0.3324
	2	0.01
C _S = 0.0153		
$T = C_{U}^{*}T_{a} =$	1.5999134	

k= 1.550 W= 106734.9 V= $C_s*W=$ 1636.69

The floor weights used for the seismic calculations were calculated using a 10" NWC slab over the entire area, added to the column weights. Also, the superimposed loads were added and a bracing allowance to account for beams as part of the floor system.

Table 31: Beams on 4th floor with total beam weight

Beams:			
Shape	Unit Weight (Ib/ft)	Beam Length (ft)	Total Weight
32x34	1095.56	0	0.0 kips
30x34	1027.08	0	0.0 kips
34x34	1164.03	48	55.9 kips
24x34	821.667	5443.9	4473.1 kips
Total Weight=	4528.9	kips	

Page 61 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

Table 32: Fourth Floor weight calculation

Approx. Area:	64231.7	ft ²	Floor to Floo	or Height:	14
Slab:					
NWC	145	PCF			
Thickness=	10	inches			
unit weight=	120.8333	psf			
total weight=	7761	kips			
Columns:					
Shape	Quantity	Unit Weight (Ib/ft)	Column Height (ft)	Total Weigh	t
24x24	102	580	14	828.2 kips	;
28x28	3	789.44444	14	33.2 kips	;
30x30	6	906.25	14	76.1 kips	6
32x32	0	1031.1111	14	0.0 kips	i
34x34	0	1164.0278	14	0.0 kips	6
36x36	0	1305	14	0.0 kips	6
48x48	0	2320	14	0.0 kips	6
Column Reinf =	22.35	Kips			
X-verse Reinf=	2.77	kips			
Total Weight=	962.6	kips			
Beam =	4528.9	kips			
Reinforcement=	156.177	kips			
Total Weight=	4685.1	kips			
Super Imposed:					
MEP=	5	psf			
Finishes=	3	psf			
Total Weight=	513.9	kips			
TOTAL FLOOR WE	IGHT:		13922.9	or 216	6.8
			kips	ps	sf

The values in this portion of the report were calculated using the method described in the Seismic design portion of this report and the same method used in Technical Report One.

Table 33: Seismic Forces, Shears and Moments for As- Built with R=3

R=3

Floor	w _x (k)	h _x (ft)	h _x ^k (ft)	w _x h _x ^k	C _{vx}	Story Force F _x (k)	Story Shear V _x (k)	Moment at Floor (ft-k)
Roof	4240.5	74.5	639.41	2711449	0.359	167.42	0	12473.065
5	4713.6	60	462.27	2178985	0.288	134.55	167.42	8072.7394
4	4726.5	46	310.43	1467216	0.194	90.60	301.97	4167.4204
3	4724.0	32	180.20	851252	0.113	52.56	392.57	1681.9916
2	4653.4	18	76.08	354028	0.047	21.86	445.13	393.48265
1	5444.4						466.99	
Sum	28502.4	74.5	1668.39	7562930	1.000	466.99	466.99	26788.699

R=3.5

Table 34: Seismic Forces, Shears, and Moments for As-Built with R=3.5

Floor	w _x (k)	h _x (ft)	h _x ^k (ft)	$w_x h_x^{\ k}$	C _{vx}	Story Force F _x (k)	Story Shear V _x (k)	Moment at Floor (ft-k)
Roof	4240.5	74.5	639.41	2711449	0.359	143.51	0	10691.199
5	4713.6	60	462.27	2178985	0.288	115.32	143.51	6919.4909
4	4726.5	46	310.43	1467216	0.194	77.65	258.83	3572.0746
3	4724.0	32	180.20	851252	0.113	45.05	336.48	1441.7071
2	4653.4	18	76.08	354028	0.047	18.74	381.54	337.27085
1	5444.4						400.28	
Sum	28502.4	74.5	1668.39	7562930	1.000	400.28	400.28	22961.742

Table 35: Seismic Forces, Shears, and Moments for Redesigned with R=3

Floor	w _x (k)	h _x (ft)	h _x ^k (ft)	$w_x h_x^{\ k}$	C _{vx}	Story Force F _x (k)	Story Shear V _x (k)	Moment at Floor (ft-k)
Penthouse	6481.1	92.5	1115.41	7229044	0.179	293.33	0	27133.348
Roof	18245.1	74.5	797.56	14551503	0.361	590.46	293.33	43989.083
5	14162.0	60	570.24	8075727	0.200	327.69	883.79	19661.364
4	13922.9	46	377.75	5259370	0.130	213.41	1211.48	9816.8534
3	16960.3	32	215.24	3650482	0.091	148.13	1424.89	4740.0283
2	17785.3	18	88.23	1569200	0.039	63.67	1573.02	1146.1239
1	19178.2						1636.69	
Sum	106734.9	92.5	3164.42	40335326	1.000	1636.69	1636.69	106486.8

Page 63 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report


APPENDIX E: MEMBER DESIGNS AND CHECKS

Interior 45' span beam Design

Page 64 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report


MEMBER DESIGN CONTINUED:



Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

MEMBER DESIGN CONTINUED:



Page 66 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

MEMBER DESIGN CONTINUED:

Interior slab thickness design

INTERIOR DESIGN
LOADING: 50 OFFICE LOAD-LIVE 20 PARTITION LOAD-LIVE 8 SUPERIMPOSED DEAD (FOR MEP, ETC)- +? CONC SLAB
$W_{u} = 1.2(8PSF) + 1.6(70) = 121.6 PSF$
MATERIALS: $f'_{c} = 4000 \text{ psi}$ $f'_{v} = 60 \text{ hsi}$
MINIMUM SLAB THICKNESS :
·ASSUME COLUMNS ARE 24'X24'
ln = 24' - 2' = 22'
· FROM ACI 318-08, TABLE 9.5 h7, 1/28
h7, (22 x12)/28
$n = 9.43'' \rightarrow h = 10''$
SLAB CONTRIBUTION TO DEAD LOAD
SLAB WEIGHT = 150 PCF x 10" = 125 PSF
WSLAB = 1.2(125 PSF) = 150 PSF
TOTAL LOAD:
Wu = 121.6 PSF+ 150PSF=271.6 PSF
Wa = 272, PSF
MOMENT VALUES USING ACI COEFFICIENTS
AT INTERIOR SUPPORTS: -M=(1) waln = (1) (272 (22) = 13.165 K-F.H
• AT MIDSPAU: $+M = (1 - 1) wuh^2 = (1 - 272)(22)^2 = 8.228 \text{ h-ft}$
• UN FACTORED : $Mu = \frac{wl^2}{8} = \frac{(70+8+125)(22)^2}{8} = 12.282$ h-ft

Page 67 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

MEMBER DESIGN CONTINUED:

REQUIRED REINFORCEMENT $\cdot \text{PMAX} = 0.85\beta (ft/fy) \left[\frac{c_s}{c_s + c_s} \right]$ $e_{MAX} = 0.85(0.85)(\frac{4}{60})[0.003] = 0.0200$ E FFECTIVE DEPTH : $bd^2 = 20Mu$ (12")(d2)=20(13.165 K-ft) [d=4.68"] · AREA OF STEEL PLEQUIRES PERFORT IN TOP OF SLAPS: $As = Mu = \frac{40}{40}$ AS= 13,165 = 0,703 INZ 4 ×4,68 USE #8 @12" (As=0.7917) · AREA OF STEEL REQUIRED PER FOOT @ MIDSPAN: As=Mu Hd AS = 8.228 = 0.4395 IN2 USE # 8 @12" (AS = 0.79 IN2) (FOR EASE OF CONSTRUCTION) . MINIMUM STEEL FOR SHEINKAGE + TEMPERATURE ASMIN = 0.001 8(12")(10") = 0, 216 IN2 ASMIN = 0.216 IN2 < AS = 031 In2 :00K USE # 5 @ 12" O.C.

Page 68 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

MEMBER DESIGN CONTINUED:

· CHECK SHEAR · SHEAR IN END MEMBERS @ FIRST INTERIOR SUPPORT $V_{u} = \frac{1.15}{2} = \frac{1.15(0.272)(22)}{2} = 3.44$ K · SHEAR AT OTHER SUPPORTS Va= Waln = (0.272) = 2.99 K · ALLOWABLE SHEAR QVn = 0.75(2) VF'C bd QVn= 0.75(2)-4000 (12)(4.68) DVn= 4.97 K Vu< DVn :OK ·DEFLECTION CHECK (TABLE 9.5 CONFIRMATION) $\Delta = \frac{5\omega J^4}{384 ET}$ $I = \frac{(24' \times 12''/1')^3}{12} = 41472 \text{ IN}^4$ E= 57000-14000 = 3605 hsi $\Delta = \frac{5(0.272 \text{ hs}F)(45)(24)^4}{384(3605 \text{ hs}F)(4472 \text{ hs}^4)} = 0.611^{11}$ $\Delta HAX = \frac{1}{240} = \frac{24 \times 12}{240} = 1.2"$ (AMAX) A : OK

Page 69 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report


MEMBER DESIGN CONTINUED: Third Floor Green Roof Slab Design

LOHUING	1: 50 PSF DEAD 100 PSF Live t SELF
w _u =	1.2(50) + 1.6(100) = 220 PSF
MATERIA	L5: f'c=4000 PS' fy = (0) HSI
MINIMUM	SLAB THICKNESS
·ASSUN	TE COLUMNIS ARE 24"X24"
ln=	= 24'-2' = 22'
· FROM	1 ACI 318-08, TABLE 9.5 h / ln/28
	$h_{1}(22 \times 12)/28$
	h7, 9.43" →h=10"
SLAB (CONTRIBUTION TO DEADLOAD
SLA	$B WT = 150PCF \times 10'' = 125 PSF$
Ws	LAB= 1.2(125)=150 PSF
TOTALL	OAD:
h	Ju= 220 PSF +150 PSF = 370 PSF
	Wu=370 PSF
MOHENT	VALUES USING ACI COEFFCIENTS
·AT	INTERIOR SUPPORTS: $-M = (\frac{1}{10}) wuln^2 = \frac{1}{10}(370)(22)^2 = 17.91 \text{ K-ft}$
·AT 1	$105PAN: #1=\frac{1}{16}(Waln^2=\frac{1}{16}(370)(22)^2=11.19 \text{ K-ft}$
° UNFI	ACTORED: $Mu = \frac{\omega l^2}{2} = \frac{(50 + 100 + 125)(22)^2}{9} = 16.64 \text{ M-ft}$

Page 70 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

MEMBER DESIGN CONTINUED:




Page 71 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

MEMBER DESIGN CONTINUED:

· CHECK SHEAR · SHEAR IN END MEMBERS @ FIRST INTERIOR SUPPORT Vu= 1.15waln = 1.15(0.37)(22) = 4.68 h . SHEAR AT OTHER SUPPORTS $V_{u} = \frac{W_{u} \ln z}{2} = \frac{(0.37)(22)}{2} = 4.07 \text{ K}$ · ALLOWABLE SHEAR Q Vn = 0.75 (2) TFC bd \$ Vn = 0.75(2) 14000 (12)(5.27) $\phi V_n = 6^k$ $\phi V_n = 6^k > V_u = 4.68^k \circ 0^k$


MEMBER DESIGN CONTINUED: TOP FLOOR GREEN ROOF SLAB DESIGN



Page 73 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

MEMBER DESIGN CONTINUED:



Page 74 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report


MEMBER CHECK CONTINUED: LATERAL BEAM GIRDER CHECK

GIEDER CHECK LATERAL END MOMENT = 290 "K [EG LOAD] LOADING : DEAD = 125 PSF+ 8 PSF+ 850 PJF LIVE = 50 PSF + 20 PSF $W_{u} = 1.2(125+8)(12)+1.2(850)+1.6(50+20)(12)$ W1=4779.7 PJF MAXIMUM MOMENT DETERMINATION GRAVITY MAXCENDS = $\frac{\omega J^2}{12} = \frac{(4.28 \text{ MJF})(36)^2}{12} = 462.2 \text{ H-ft}$ $M_{MHX} \otimes M_{1D} = \frac{\omega l^2}{22} = (4.28 \text{ KlF}(36)^2 = 231.1 \text{ K-f+}$ GRAVITY + LATERAL [1.2.D+1.6L+1.0E] MMAX@ENDS = 462.26-F++2906-F+ = 752.26-F+ MMAXOMID = 231,1 K-F++290 K-F+ = 521,1 K-F+ BM HAS (8) # 8'S IN 2 ROWS d = 31'' $A_{s} = 8(0.79 \text{ in}^{2}) = 6.32 \text{ in}^{2}$ $\Phi Mn = \Phi As fy(d - a/2) \rightarrow a = Asfy = (6.32)(60) = 4.647''$ $\oplus M_n = 0.9(6.32 \text{ Im}^2)(60 \text{ Hsi})(31''-4,647''/2)$ OMn = 9787 H-FN = 815,6 K-Ft >Mu = 752,2 K-Ft /OK

Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

MEMBER CHECK CONTINUED:




MEMBER CHECK CONTINUED:

DETERMINE MIN. SHEAR REINF. AU MIN = MAX \$0.75/FCbws/Fyt = 0.75/F000044(15)/60000 = 0.285 in² (50 bws/Fyt = $\frac{1}{2}\sqrt{24}(15)/60000 = 0.285 in²$ $f(V_{MIN} = 0.3 in²$ BM HAS (3)#3 STIERUPS, As = 0.33 in² > AUMIN = 0.31n² : 0K (HECK SPECING USE MIAX SPACING SHAX=15" SHAX=15"SPACING ON BH = 9" :: 0K Page 77 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan


Final Report

MEMBER CHECK CONTINUED: COLUMN C-5 PENTHOUSE LEVEL




Page 78 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report




MEMBER CHECK CONTINUED: COLUMN C-5 FIFTH FLOOR



MEMBER CHECK CONTINUED: COLUMN C-5 FOURTH FLOOR

Page 80 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009


Final Report



MEMBER CHECK CONTINUED: COLUMN C-5 THIRD FLOOR

Page 81 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan


Final Report



Page 82 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report


MEMBER CHECK CONTINUED: COLUMN C-5 FIRST FLOOR



Page 83 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan


Final Report

MEMBER CHECK CONTINUED: COLUMN D-7.9 PENTHOUSE FLOOR



Page 84 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report




MEMBER CHECK CONTINUED: COLUMN D-7.9 FIFTH FLOOR

Page 85 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan


Final Report

MEMBER CHECK CONTINUED: COLUMN D-7.9 FOURTH FLOOR



Page 86 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report



MEMBER CHECK CONTINUED: COLUMN D-7.9 THIRD FLOOR

Page 87 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan


Final Report

P (kip) 1800 (Pmax) 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 fs=0¹³⁴/fs=0 24 x 24 in 14438 Code: ACI 318-02 152 156 fs=0.5fy fs=0.5fy Units: English Run axis: About X-axis Run option: Investigation Slenderness: Considered Column type: Structural -700 700 Bars: ASTM A615 Mx (k-ft) Date: 02/28/09 Time: 16:52:51 (Pmin) -600 pcaColumn v3.64. Licensed to: Penn State University. License ID: 52411-1010265-4-22545-28F4D File: G:\thesis stuff\FINAL\PCA\column7.9-D 4.col Project: Column: 7.9-D 1 Engineer: fc = 4 ksi fy = 60 ksi Ag = 576 in^2 16 #7 bars Ec = 3605 ksi Es = 29000 ksi As = 9.60 in^2 Rho = 1.67% fc = 3.4 ksi fc = 3.4 ksi Xo = 0.00 in lx = 27648 in^4 e_u = 0.003 in/in Yo = 0.00 in ly = 27648 in^4 Beta1 = 0.85 Clear spacing = 3.97 in Clear cover = 1.88 in Confinement: Tied phi(a) = 0.8, phi(b) = 0.9, phi(c) = 0.65 kx(braced) = 0.965049, kx(sway) = N/A

MEMBER CHECK CONTINUED: COLUMN D-7.9 SECOND FLOOR

Page 88 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report



MEMBER CHECK CONTINUED: COLUMN D-7.9 FIRST FLOOR

APPENDIX F: CONSTRUCTION MANAGEMENT BREADTH STUDY

Table 36: Cost Analysis Estimate for Concrete Structure with Green Roof

			Detai	led Cost Analy	sis of the Stru	icture			
Level	Description	Amount	Material Price	Material Cost	Labor Price	Labor Cost	Equipment Price	Equipment Cost	Total Cost
	Foundation	58 Ton	\$935.00	\$54,230	\$430.00	\$24,940	\$30.35	\$1,760	\$80,930
Deinfersenset	Columns	2221 Ton	\$935.00	\$2,076,635	\$430.00	\$430.00	\$30.35	\$67,407	\$2,144,472
Reinforcement	Beam/Slabs	572 Ton	\$935.00	\$534,820	\$430.00	\$245,960	\$30.35	\$17,360	\$798,140
	SUB-TOTAL	2851	\$935.00	\$2,665,685	\$430.00	\$430.00	\$30.35	\$86,528	\$2,752,643
	Foundations	6100 CY	\$109.00	\$664,900	\$14.90	\$90,890	\$5.55	\$33,855	\$789,645
Cost in Diasa	Columns	1518 CY	\$109.00	\$165,462	\$34.00	\$51,612	\$16.95	\$25,730	\$242,804
Cast in Place	Slabs	14192 CY	\$109.00	\$1,546,928	\$18.20	\$258,294	\$9.15	\$129,857	\$1,935,079
Concrete	Beams	8415 CY	\$109.00	\$917,235	\$26.50	\$222,998	\$1,320.00	\$11,107,800	\$12,248,033
	SUB-TOTAL	30225	\$109.00	\$3,294,525	\$23.40	\$623,794	\$1,352	\$11,297,242	\$15,215,561
Location Factor:	Total Structure	Estimate:	\$36,07	7,000		Total L	abor Cost:	\$896,0	00
98.9%	Total Materia	al Cost:	\$5,96	1,000		Total Equ	uipment Cost:	\$11,384	,000

Table 37: Cost Analysis Estimate for Concrete Structure, No Green Roof

			Detailed Cos	t Analysis of th	e Structure-N	o Green Roof			
Level	Description	Amount	Material Price	Material Cost	Labor Price	Labor Cost	Equipment Price	Equipment Cost	Total Cost
	Foundation	58 Ton	\$935.00	\$54,230	\$430.00	\$24,940	\$30.35	\$1,760	\$80,930
Deinfersonsent	Columns	2000 Ton	\$935.00	\$1,868,972	\$430.00	\$430.00	\$30.35	\$60,667	\$1,930,068
Reinforcement	Beam/Slabs	544 Ton	\$935.00	\$470,642	\$430.00	\$216,445	\$30.35	\$15,277	\$702,363
	SUB-TOTAL	2560	\$935.00	\$2,393,843	\$430.00	\$430.00	\$30.35	\$77,704	\$2,471,977
	Foundations	6100 CY	\$109.00	\$664,900	\$14.90	\$90,890	\$5.55	\$33,855	\$789,645
Oratin Diasa	Columns	1443 CY	\$109.00	\$157,189	\$34.00	\$49,031	\$16.95	\$24,444	\$230,664
Cast in Place	Slabs	14192 CY	\$109.00	\$1,546,928	\$18.20	\$258,294	\$9.15	\$129,857	\$1,935,079
Concrete	Beams	7574 CY	\$109.00	\$917,235	\$26.50	\$222,998	\$1,320.00	\$11,107,800	\$12,248,033
	SUB-TOTAL	30149	\$109.00	\$3,286,252	\$23.40	\$621,213	\$1,352	\$11,295,955	\$15,203,421
Location Factor:	Total Structure	Estimate:	\$35,44	10,000		Total L	abor Cost:	\$864,0	000
98.9%	Total Materia	al Cost:	\$5,68	1,000	-	Total Equ	uipment Cost:	\$11,374	,000

Page 90 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report




Figure 48: Condensed Gantt Chart

Page 91 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

>	8		15			22		29						
Friday Salurday	7 kec. 1, 5 days	Reinforce Foundations & Flace Foundations Sec. 4	14	Form Basement Sec. 2, 6 days	Flace Basement Stab Sec Flace Foundations Sec. 5	54	Form Basement Columns Sec. 1, 5 days	28	i Sec. 2, 3.5 days	Reinforce Basement Columns Sec. 1,	Form Basement Columns Sec. 2, 5 days			
Thursdey	5 6 Form Basement Sec. 1, 6 days	Reinforce Foundations St (Reinforce Foundations St) Reinforce Foundations St Place Foundations Sec. 2 (Place Foundations Sec. 3) (Place Foundations Sec. 4)	12 13	Reinforce Basement Slab	Reinforce Foundations Sé Place Foundations Sec. 8	19 20		26 27 Form Basement Sec. 3.6 days	Finish Basement Slab Sec. 2, 3.5 days	[Reinforce Bas				
Wednesday	4	000	11		Reinforce Foundations St (Reinforce Foundations St Place Foundations Sec. 6 Place Foundations Sec. 7	18 Ecom Decomposit Social 2 Endote	00. 1, 3.5 days	25)(Strip Formwork Baseme		7	
Tuesday		Reinforce Foundations St Place Foundations Sec. 1		Form Basement Sec. 1, 6 days			Finish Basement Steb Sec. 1, 3.5 days		Place Basement Slab Sec	Form Basement Columns Sec. 1, 5 days	Strip Form	5		ent Columns Form Basement Columns Sec. 2,5 days
Wonday	3	Reinforce Foundations Sc	9 10	Form Basemen	Reinforce Foundations Se Place Foundations Sec. £	16 17		23 24 Reinforce Basement Slab		Form Basem		30 31 Form Basement Sec. 3. 6 davs	sec. 2, 3.5 cays	Place Basement Columns
Sundey													Finish Basement Slab Sec.	

Figure 49: March Schedule Calendar

Page 92 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

> Finish Basement Slab Sec. 3, 3.5 days Form 1st Floor Beams Sec. 5, 2 days Form 1st Floor Beams Sec. 4, 2 days Saturcay Reinforce 1st Floor Slab / Place 1st Floor Beams St Form Basement Columns Sec. 5, 5 days Form Basement Columns Sec. 3, 5 days Form Basement Columns Sec. 6, 5 days Form Basement Columns Sec. 4, 5 days Place 1st Flod Strip Formwork Basemei loor Beams Sec. 3, 2 days Finish Basement Slab Sec. 5, 3.5 days Form Basement Sec. 4, 6 days Form 1st Floor Sec. 1, 3 days o F 25 Reinforce Basement Columns Sec. 2, Strip Formwork Baseme Reinforce Basement Slab Reinforce Basement Columns Sec. 5, Strip Formwork Basemen or Slab Sec. Reinforce Basement Columns Sec. 4, Strip Formwork Basemen Reinforce Basement Columns Sec. 3, Strip Formwork Basemen Friday 10 17 Form 1st Floor Sec. 3, 3 days 24 Form Basemen Place Basement Slab Set Place Basement Column por Slab Sec. Strip Formwork 1st Beam Strip Formwork First Floo Thursday Form 1st Floor Colune Strip Formwork Baseme Finish Basement Slab Sec. 4, 3.5 days Form 1st Floor Columns Sec. 2, 5 days 10 **April 2008** 30 33 Strip Formwork First Floo (Reinforce 1st Floor Slab / Reinforce Basement Slab Place Besement Column; Reinforce 1st Floor Slab / Place 1st Floor Beams St Strip Formwork First Floc Place Basement Slab Sec Wednesday Form 1st Floor Beams Sec. 1, 2 days Place Besement Columns Reinforce 1st Columns Sec. 1, 1,5 days [Place 1st Columns Sec.] Finish Basement Stab Sec Reinforce Basement Columns Sec. 1, 1 Form Basement Sec. 4, 6 days 15 22 29 Form Basement Columns Sec. 3, 5 days Reinforce Basement Slab Place Basement Columns Form Reinforce 1st Floor Slab / Place 1st Floor Beams St Form Basement Columns Sec. 2, 5 days Form Basement Columns Sec. 5, 5 days Form Basement Columns Sec. 6, 5 days Form Basement Columns Sec. 4, 5 days Jesday Strip Formwork Baseme Form Basement Sec. 3, 6 days 14 2 8 Form 1st Floor Beams Se Place Basement Slab Ser Place Besement Columns Finish Basement Slab Sec. 5, 3.5 days Form 1st Floor Beams Sec. 4, 2 days Form 1st Floor Beams Sec. 5, 2 days Monday Form 1st Floor Sec. 1, 3 days G 9 20 27 Sunday

Final Report

Figure 50: April Schedule Calendar

Overflow Tasks

ID Name

- 498 Place Basement Columns Sec. 1
- 490 Reinforce Basement Columns Sec. 1
- 573 Strip Formwork 1st Beams Sec. 1

575 Strip Formwork 1st Beams Sec. 3



Start

Finish

Page 93 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

Sunday Monday	day	Tuesday		Wedresday	Thursday	Friday	Saturcay
					Reinforce Basement Slab	_	ms Sec. 6, 2 days
						Place Basement Slab Ser	
	Form Basement Columns Sec. 6, 5 days	t Columns Sec.	6, 5 days			Form Basement Columns Sec. 7, 5 days	ec. 7, 5 days
			Form	Form 1st Floor Columns Sec. 2, 5 days		Reinforce Basement Columns Sec. 6,	
					Place 1st Floor Beams St		Strip Formwork Easement Slab Sec. 5
						Strip Formwork Basemen	
4	5		9	2		8	
Form 1st Floor Beams Sec. 6, 2 days	lays 5		ſ	t Sec. 7, 6 days		Form 1st Floor Beams Sec. 7, 2 days	ms Sec. 7, 2 days
_	Ľ	Finish Basement Slab Sec. 6, 3.5 days	t Slab Sec.	. 6, 3.5 days	Reinforce t	Reinforce Basement Columns Sec. 7,	
	Form Basement Columns Sec. 7, 5 days	t Columns Sec.	7,5 days			Strip Formwork Basemen	
Place Besement Columns	ent Columns		Form	Form 1st Floor Columns Sec. 3, 5 days	days		
Strip Forrwork Basement Slab Sec. 5, It	It Columns Sec. 2, 1.5 days by Place 1st Columns Sec.	2, 1.5 days p(P	lace 1st C	olumns Sec.	Place 1st Floor Beams Se		
	Strip Formwork 1st Colur	k 1st Colui		Reinforce 1st Floor Slab /	Strip Formwork First Floo		
11	t		13	14	15	5 16	
Form 1st Floor Bea Reinforce Bas	Reinforce Basement Slab s			Ľ	Form Basement Sec. 8, 6 day	Form 1st Floor Beams Sec. 9, 2 days	ms Sec. 9, 2 days
Place Besement Columns	<u> </u>	Place Basement Slab Ser	Slab Ser		Finish Basement Slab Sec.	Slab Sec. 7, 3.5 days	
]		S	trip Formw	Strip Formwork Baseme		Strip Formwork Basemen	
		J	Form	Form 1st Floor Columns Sec. 4, 5 days	days		
Reinforce 1st	Reinforce 1st Columns Sec. 3, 1.5 days		lace 1st C	Place 1st Columns Sec.	Place 1st Floor Beams St		
	Strip Formworl	k 1st Colui ec. 2	2. 1.5 day	Strip Formwork 1st Colur e. 2, 1.5 day Reinforce 1st Floor Slab /	Strip Formwork First Floo		
18	19		20	21	22	2 23	
Form 1st Floor Beams Sec. 9, 2 days	lays s			Reinforce Basement Slab Form 1st Floor Sec. 9, 3 days	orm 1st Floor Sec. 9, 3 day	s Is	
Finish Basement Slab Sec. 7, 3.5 days					Place Basement Slab Set	Finish Basement Slab Sec. 8, 3.5 days	ab Sec. 8, 3.5 days
					Strip Form	Strip Formwork Baseme or Slab Sec.	
		C	Form	Form 1st Floor Columns Sec. 5, 5 days	days		
Reinforce 1st	Reinforce 1st Columns Sec. 4, 1.5 days		lace 1st C	Place 1st Columns Sec.	Place 1st Floor Beams St		
	Strip Formwork 1st Colui	k 1st Colui		Reinforce 1st Floor Slab / Strip Formwork First Floo	Strip Formwork First Floo		
25	26		27	28	29	30	
		Form	1 2nd Floor	Form 2nd Floor Sec. 1, 4 days		Reinforce Basement Slab r Sec. 2, 4 days	Sec. 2, 4 days
Finish Basem	Finish Basement Slab Sec. 8, 3.5 days	, 3.5 days		or Slab Sec.			
				Finish 1st Floor Slab Sec.		Reinforce 2nd Floor Slab And Beams Sec. 1, 1.5 days	nd Beams Sec. 1, 1.5 d
			Form	Form 1st Floor Columns Sec. 6, 5	5 days	· · · ·	
Reinforce 1st	Reinforce 1st Columns Sec. 5, 1.5 days)c	5, 1.5 days of P	Place 1st C	Place 1st Columns Sec.			
Dainforma 1st	Chrin Enmund	to 4 of Colum			Strin Eormisory First Floo	~	

Figure 51: May Schedule Calendar

Overflow Tasks

- Strip Formwork 1st Beams Sec. 4 Strip Formwork 1st Beams Sec. 5 Strip Formwork 1st Beams Sec. 6
- 576 577 578
- Form 2nd Floor Beams Sec. 3 Strip Formwork 1st Beams Sec. 7 Strip Formwork 1st Beams Sec. 8 Form 2nd Floor Beams Sec. 4
- 206 579 580 207

Finish

Start

Thu 5/1/08 Wed 5/7/08 Wed 5/14/08 Thu 5/1/08 Wed 5/7/08 Wed 5/14/08 Mon 5/19/08 Wed 5/21/08 Wed 5/28/08 Mon 5/26/08 Tue 5/20/08 Wed 5/21/08 Wed 5/28/08 Tue 5/27/08

Sunday	Monday	Jay Tuesday	vednesday Wednesday	ssday Thursday		Friday S	Saturday
F		2	n	4	5	9	
Plac	ce Baseme	Place Basement Slab Sec]	Finish Basem	Finish Basement Slab Sec. 9, 3.5 days		r Sec. 3, 4 days	
		Place 2nd Floor Beams (Flace 2nd Floor Slab Se		-		
Reinforce 2nd Floor Slab And Beams S	eams S.	Strip Formwork Baseme	Finish 2nd Floor Slab Se				
Strip	ip Formwor	Strip Formwork 1st Beam Strip Formwork First Floo	rk First Floo 1st Floor Colur		Form 2nd Floor Columns Sec. 1, 5 days	Sec. 1, 5 days	
Rein	inforce 1st	Reinforce 1st Columns Sec. 6, 1.5 days	Place 1st Columns Sec.	Reinforce 2nd Floor	Reinforce 2nd Floor Slab And Beams Si	Place 2nd Floor Beams Sec. 2, 1 day	s Sec. 2, 1 day
		Strip Formwork 1st Colui				Strip Formwork 2nd Beams Sec. 1, 1 di	ams Sec. 1, 1 d
8		6	10	11	12	13	1
Form 2	2nd Floor 5	Form 2nd Floor Sec. 3, 4 days		Form 21	Form 2nd Floor Sec. 4, 4 days	si	
Rein	inforce 1st	Reinforce 1st Columns Sec. 7, 1.5 days	Place 1st Columns Sec.			Place 2nd Floor Slab Sec. 3, 1 day	Sec. 3, 1 day
		Finish 2nd Floor Slab Se				Finish 2nd Floor Slab Sec. 3, 1 day	Sec. 3, 1 day
Fom	Form 2nd Floo	Strip Formwork 1st Colui		Form	Form 2nd Floor Columns Sec. 2, 5 days	Sec. 2, 5 days	
Place 2nd Floor Beams Sec. 2,	ec. 2, 1 day	Strip Formwork 2nd Floc		Strip Formwork Baseme pec. 1, 1.5 da	1.5 da Place 2nd Columns Sec.	olumns Sec.	
Strip Formwork 2nd Beams Sec.	Sec. 1, 1 dg		Reinforce 2nd	Reinforce 2nd Floor Slab And Beams Sv) Place	Place 2rd Floor Beams (Strip Formwork 2nd Floor Slab Sec. 2,	oor Slab Sec. 2,
15		16	17	8,	19	20	21
Form 2nd Floor Sec.	Sec. 4, 4 days		Fc	Form 2nd Floor Sec. 5, 4 days			
Place 2nd Floor Slab Sec. 3, 1 day	1 day			Plac	Place 2rd Floor Slab Se		
Finish 2nd Floor Slab Sec. 3, 1	c. 3, 1 day			Finis	Finish 2nd Floor Slab Se		
Fom	m 2nd Floc	Form 2nd Floor Columns Sec. 2, 5 days		Form	Form 2nd Floor Columns Sec. 3, 5 days	Sec. 3, 5 days	
		Reinforce 2nd	Reinforce 2nd Floor Slab And Beams Si	Reinforce 2nd Columns Sec. 2, 1.5 da [Place 2nd Columns Sec.	1.5 da Place 2nd Co	olumns Sec.	
Strip Formwork 2nd Floor Slab S	Slab Sec. 2, 1	Strip Formwork 1st Colui		Place 2nd Floor Beams (Strip	Strip Fortwork 2nd Floc		
22		23	24	25	26	27	28
		Ű	Form 2nd Floor Sec. 6, 4 days			Form 2nd Floor Sec. 7, 4 days	fays
				Place 2nd Floor Slab Se Finish 2nd Floor Slab Se	2 		
Fom	m 2nd Floc	Form 2nd Floor Columns Sec. 3, 5 days			Form 2nd Floor Columns Sec. 4, 5 days	Sec. 4, 5 days	
Rein	inforce 2nd	Reinforce 2nd Floor Slab And Beams St	Place 2nd Floor Beams :	Reinforce 2nd Columns Sec. 3, 1.5 da	1.5 da Place 2nd Columns Sec.	olumns Sec.	
			Strip Formwork 2nd Bea	Strip Formwork 2nd Floc	Reinforce 2n	Reinforce 2nd Floor Slab And Beams Sec. 6, 1.5 days	Sec. 6, 1.5 days
29		30					
	ß	Form 2nd Floor Sec. 7, 4 days					
Fom	m 2nd Floc	Form 2nd Floor Columns Sec. 4, 5 days					
		Place 2nd Floor Beams (
Reinforce 2nd Floor Slah And Reams Si	ams Si	Strip Formwork 2nd Rea					

Overflow Tasks

ID Name

|--|

N

Mon 6/2/08	Tue 6/3/08
Thu 6/12/08	Fri 6/13/08
Mon 6/9/08	Tue 6/10/08
Ned 6/18/08	Thu 6/19/08
Thu 6/19/08	Thu 6/19/08
Mon 6/16/08	Tue 6/17/08
Thu 6/19/08	Fri 6/20/08
Thu 6/26/08	Thu 6/26/08
Thu 6/26/08	Fri 6/27/08
ri 6/27/08	Mon 6/30/08

Finish

208	Form 2nd Floor Beams Sec. 5
584	Strip Formwork 2nd Beams Sec. 2
209	Form 2nd Floor Beams Sec. 6
585	Strip Formwork 2nd Beams Sec. 3
645	Strip Formwork 2nd Columns Sec. 1
210	Form 2nd Floor Beams Sec. 7
211	Form 3rd Floor Beams Sec. 1
GAG	Strip Formwork 2nd Columne Sec 2

- 584 209 585 645 210 211

- 646 212 213 Strip Formwork 2nd Columns Sec. 2 Form 3rd Floor Beams Sec. 2 Form 3rd Floor Beams Sec. 3

Page 95 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

	Saturday					Place 2nd Flcor Beams Sec. 7, 1 day	12	Sec. 3, 3 days			mns Sec. 1, 4 days		Strip Formwork 2nd Floor Slab Sec. 7.,	15				days			26													
	Friday 4	Form 3rd Floor Sec. 1, 3 days		Form 2nd Floor Columns Sec. 5, 5 days	Place 2nd Columns Sec.	\square		Form 3rd Floor Sec. 3, 3 days	Place 2nd Columns Sec.		Form 3rd Floor Columns Sec. 1, 4 days	Reinforce 3rd Floor Slab ,	Strip Formwork 2nd Bea Strip Formw	18		Place 3rd Floor Slab Sec.	Finish 3rd Floor Slab Sec	Form 3rd Floor Columns Sec. 2, 4 days	Place 3rd Columns Sec. *	Strip Fortwork 3rd Bearr	25	Form 3rd Floor Sec. 6, 3 days			Form 3rd Floor Columns Sec. 3, 4 days	Place 3rd Floor Beams Si	Strip Fortwork 3rd Colun							
	Thursday 3			Form 2nd Flu	Reinforce 2nd Columns Sec. 4, 1.5 da	Reinforce 2nd Floor Slab And Beams Si	10		Place 3rd Floor Slab Sec.	Finish 3rd Floor Slab Sec	Reinforce 2nd Columns Sec. 5, 1.5 da		Strip Formw	17	Form 3rd Floor Sec. 4, 3 days			Form	Reinforce 3rd Columns E Flace 3rd Columns Sec.	Place 3rd Floor Beams St Strip Formwork 3rd Beam	2				Form 3rd Floor Colu	Place 3rd Columns Sec. £)	Reinforce 3rd Floor Slab J	31		Place 3rd Floor Slab Sec.	Finish 3rd Floor Slab Sec	Form 3rd Floor Columns Sec. 4, 4 days	Strip Formwork 3rd Beam	
July 2008	Wednesday 2		Place 2nd Floor Slab Se Finish 2nd Floor Slab Se		Strip Formwork 2nd Floc Reinforce 2			Form 3rd Floor Sec. 2, 3 days			Reinforce 2	Reinforce 3rd Floor Slab / Place 3rd Floor Beams Sr		16					Reinforce 3rd Floor Slab ,	Strip Formwork 3rd Floor	23	5	Place 3rd Floor Slab Sec.	Finish 3rd Floor Slab Sec		Reinforce 3rd Columns S	Place 3rd Columns Sec. 4	30	Form 3rd Floor Sec. 7, 3 days			Form 3rd Floor Colt	Place 3rd Floor Beams Si	Strip Formwork 3rd Colun
	Tuesday	Sec. 7, 4 days	Place 2nd F Finish 2nd F	ec. 4, 5 days		ork 2nd Bea	8	Ľ	loor Slab Se	loor Slab Se	ec. 5, 5 days	Reinforce 3rd Floor Slab /	ork 2nd Floc	15		Place 3rd Floor Slab Sec.	Finish 3rd Floor Slab Sec	mns Sec. 1, 4 days	Strip Formwork 3rd Beam		22	Form 3rd Floor Sec. 5, 3 days			days	Place 3rd Columns Sec. (Place 3rd Floor Beams St	29	Ľ				Reinforce 3rd Columns €	Reinforce 3rd Floor Slab / Strip Formwork 3rd Colun
	Sunday	Form 2nd Floor Sec. 7, 4 days		Form 2nd Floor Columns Sec. 4, 5 days	Place 2nd Floor Beams :	Strip Formwork 2nd Bea	6	Form 3rd Floor Sec. 1, 3 days	Place 2nd Floor Slab Se	Finish 2nd Floor Slab Se	Form 2nd Floor Columns Sec. 5, 5 days		Place 2nd Floor Beams Sec. 7, 1 day Strip Formwork 2nd Floc	13	Form 3rd Floor Sec. 3, 3 days			Form 3rd Floor Columns Sec. 1, 4 days	[Place 3rd Floor Beams Si] Strip Formwork 3rd Beam] [Reinforce 3rd Floor Slab ,	Strip Formwork 2nd Floor Slab Sec. 7.,	20	Ē			Form 3rd Floor Columns Sec. 2, 4 days	Place 3rd Columns Sec. 2	Reinforce 3rd Floor Slab	27 28	Form 3rd Floor Sec. 6, 3 days	Place 3rd Floor Slab Sec.	Finish 3rd Floor Slab Sec	Form 3rd Floor Columns Sec. 3, 4 days	Strip Formwork 3rd Bearr	Strip Formwork 3rd Colun

Figure 53: July Schedule Calendar

Overflow Tasks

JULY OVERFLOW TASKS

ID	Name	Start	Finish
588	Strip Formwork 2nd Beams Sec. 6	Fri 7/4/08	Mon 7/7/08
647	Strip Formwork 2nd Columns Sec. 3	Thu 7/3/08	Thu 7/3/08
214	Form 3rd Floor Beams Sec. 4	Thu 7/3/08	Fri 7/4/08
215	Form and Floor Beams Sec. 5	Fri 7/4/08	Mon 7/7/08
648	Strip Formwork 2nd Columns Sec. 4	Thu 7/10/08	Thu 7/10/08
	Form 3rd Floor Beams Sec. 6	Thu 7/10/08	
216			Fri 7/11/08
217	Form 3rd Floor Beams Sec. 7	Fri 7/11/08	Mon 7/14/08
649	Strip Formwork 2nd Columns Sec. 5	Thu 7/17/08	Thu 7/17/08
218	Form 3rd Floor Beams Sec. 8	Thu 7/17/08	Fri 7/18/08
219	Form 3rd Floor Beams Sec. 9	Fri 7/18/08	Mon 7/21/08
535	Strip Formwork 3rd Floor Slab Sec. 2	Mon 7/21/08	Mon 7/21/08
536	Strip Formwork 3rd Floor Slab Sec. 3	Thu 7/24/08	Thu 7/24/08
593	Strip Formwork 3rd Beams Sec. 3	Wed 7/23/08	Wed 7/23/08
651	Strip Formwork 3rd Columns Sec. 1	Thu 7/24/08	Thu 7/24/08
220	Form 4th Floor Beams Sec. 1	Tue 7/22/08	Wed 7/23/08
221	Form this Floor Beams Sec. 2	Thu 7/24/08	Fri 7/25/08
537	Strip Formwork 3rd Floor Slab Sec. 4	Tue 7/29/08	Tue 7/29/08
654	Strip Formwork 3rd Columns Sec. 4	Tue 7/29/08	Tue 7/29/08
222	Form 4th Floor Beams Sec. 3	Mon 7/28/08	Tue 7/29/08
223	Form 4th Floor Beams Sec. 4	Wed 7/30/08	Thu 7/31/08

AUGUST OVERFLOW TASKS

	Overflow Tasks		
ID	Name	Start	Finish
538 224 468 539 225 226 227 228 229 230	Strip Formwork 3rd Floor Slab Sec. 5 Form 4th Floor Beams Sec. 5 Place 3rd Floor Beams Sec. 7 Strip Formwork 3rd Floor Slab Sec. 6 Form 4th Floor Beams Sec. 6 Form 5th Floor Beams Sec. 7 Form 5th Floor Beams Sec. 1 Form 5th Floor Beams Sec. 2 Form 5th Floor Beams Sec. 3 Form 5th Floor Beams Sec. 4	Fri 8/1/08 Fri 8/1/08 Mon 8/4/08 Wed 8/6/08 Tue 8/5/08 Thu 8/7/08 Mon 8/11/08 Wed 8/13/08 Fri 8/15/08 Tue 8/19/08	Fri 8/1/08 Mon 8/4/08 Mon 8/4/08 Wed 8/6/08 Wed 8/6/08 Fri 8/8/08 Tue 8/12/08 Thu 8/14/08 Mon 8/18/08 Wed 8/20/08
231 232	Form 5th Floor Beams Sec. 5 Form 5th Floor Beams Sec. 6	Thu 8/21/08 Mon 8/25/08	Fri 8/22/08 Tue 8/26/08
232	Form 5th Floor Beams Sec. 7	Wed 8/27/08	Thu 8/28/08
234	Form Roof Beams Sec. 1	Fri 8/29/08	Mon 9/1/08

Page 97 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009


Final Report

	2			6						16					23			20	2	
Saturday	Sec. B, 3 days															Sec. 4, 3 days				
Friday	Form 3rd Floor Sec. 8, 3 days		Reinforce 3rd Floor Slab ,	8		Place 3rd Floor Slab Sec.	Firish 3rd Floor Slab Sec	Reinforce 3rd Columns E	Strip Formwork 3rd Bearr	15	Form 4th Floor Sec. 2, 3 days				33	Form 4th Floor Sec. 4, 3 days	Reinforce 4th Floor Stab /	Ϋ́,		
Thursday		mns Sec. 4, 4 days		7	Form 3rd Floor Sec. S, 3 days				Reinforce 3rd Columns £] Strip Formwork 3rd Beam] [Reinforce 3rd Floor Slab ,] [Place 3rd Floor Beams Sh] Strip Formwork 3rd Beam	14	Ľ	Reinforce 4th Floor Slab /	Strip Formwork 3rd Floor		21			¢C.	Form 4th Floor Sec. 5. 3 davs	
Wednesday		Form 3rd Floor Columns Sec. 4, 4 days		9	Ľ			mns Sec. 5, 4 days	Reinforce 3rd Floor Slab ,	13		-	Finish 3rd Floor Slab Sec	Strip Formwork 3rd Bear	20	orm 4th Floor Sec. 3, 3 d		20	1	Reinforce 4th Floor Slab J
Tuesday				9		Place 3rd Floor Slab Sec.	Finish 3rd Floor Slab Sec	Form 3rd Floor Columns Sec. 5, 4 days	Strip Formwork 3rd Beam	12	Form 4th Floor Sec. 1, 3 days	Place 3rd Floor Beams & Place 3rd Floor Slab Sec.			19		Reinforce 4th Floor Slab / Strip Formwork 3rd Floor	90		
Monday				3 4	Form 3rd Floor Sec. 8, 3 days				Reinforce 3rd Columns €	10 11		Reinforce 3rd Floor Slab J	Strip Formwork 3rd Floor		17 18	Sec. 2, 3 days	Strip Formwork 3rd Beam	30 30	arm 4th Ficor Sec. 4. 3 d	5
Sunday																Form 4th Floor				

Figure 54: August Schedule Calendar

Page 98 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report



Overflow Tasks

Start

Mon 9/1/08
Tue 9/2/08
Thu 9/4/08
Fri 9/5/08
Tue 9/9/08
Wed 9/10/08
Fri 9/12/08
Tue 9/16/08
Thu 9/18/08
Mon 9/22/08
Wed 9/24/08

Finish

ID	Name

Form Roof Beams Sec. 1 Form Roof Beams Sec. 2 Form Roof Beams Sec. 3 234 235 236 237 238 239 240 241 242 243 244 Form Roof Beams Sec. 4 Form Roof Beams Sec. 5 Form Roof Beams Sec. 6 Form Roof Beams Sec. 7 Form Penthouse Beams Sec. 1 Form Penthouse Beams Sec. 2 Form Penthouse Beams Sec. 3

Form Penthouse Beams Sec. 4

Page 99 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

Sunday Mon day	Tuesday	Wednesday	Thursday	Fridey	Saturday
		Form 5th Floor Sec. 6, 3 days		Form Roof	c. 1, 3 days
		Place 5th Floor Beams Se	Place 5th Floor Slab Sec.	Reinforce 5th Floor Slab /	
			Strip Formwork 5th Beam		
2	2	7		9 10	
Form Roof Sec. 1, 3 days			Form Roof Sec. 2, 3 days		
Place 5th Floor Beams St	Place 5th Floor Slab Sec.	Reinforce 5th Floor Slab	Place 5th Floor Beams St	Place 4th Floor Slab Sec.	
	Strip Formwork 5th Beam		Place 4th Floor Beams St	Place 5th Floor Slab Sec.	
				Finish 4th Floor Slab Sec	
				Place 4th Floor Beams St	
		Reinforce Roof Slab And Beams Sec. 1, 2 days	d Beams Sec. 1, 2 days	Strip Formwork 5th Beam	
12	13 14	4	16	17	
	Form Roof Sec. 3, 3 days			Form Roof Sec. 4, 3 days	
Place 4th Floor Slab Sec.	Place 4th Floor Slab Sec.	Place 4th Floor Slab Sec.	Place Roof Slab Sec. 2, 1	Place 4th Floor Slab Sec.	
Finish 4th Floor Slab Sec	Finish 4th Floor Slab Sec	Finish 4th Floor Slab Sec		Finish 4th Floor Slab Sec	
			Finish 4th Floor Slab Sec	Form 4th Floor Columns Sec. 2, 4 days	Ins Sec. 2, 4 days
	Form 4th Floor Col	Form 4th Floor Columns Sec. 1, 4 days		Reinforce 4th Columns S	
Reinforce Roof Slab A	Reinforce Roof Slab And Beams Sec. 2, 2 days				
19	20 21	1 22	23	24	
Form Roof Sec. 4, 3 days		Form Roof Sec. 5, 3 days		Form Roof Sec. 6, 3 days	c. 6, 3 days
Place 4th Floor Slab Sec.	Place Roof Slab Sec. 3, 1	Finish 5th Floor Slab Sec [Finish 5th Floor Slab Sec	Finish 5th Floor Slab Sec	Place Roof Slab Sec. 4, 1	
Finish 4th Floor Slab Sec	Finish 5th Floor Slab Sec			Finish 5th Floor Slab Sec	
Form 4th Floor Col	Form 4th Floor Columns Sec. 2, 4 days		Form	Form 4th Floor Columns Sec. 3, 4 di	4 days
Reinforce 4th Columns S	Reinforce 4th Columns S	Reinforce 4th Columns S	Reinforce 4th Columns S	Place 4th Columns Sec. 5	
Place 4th Columns Sec. 1	Place 4th Columns Sec. 2	Place 4th Columns Sec. 3	Place 4th Columns Sec. 4		
26 27	7 28	8 29	30	31	
Form Roof Sec. 6, 3 days			Form Roof Sec. 7, 3 days		
Finish 5th Floor Slab Sec	Finish 5th Floor Slab Sec	Place Roof Slab Sec. 5, 1	Finish Roof Slab Sec. 1, *	Finish Rcof Slab Sec. 1, ') [Finish Roof Slab Sec. 2, '	
		Finish 5th Floor Slab Sec			
Form 4th Floor Columns Sec. 3, 4 days	4 days		Form 4th Floor Col	Form 4th Floor Columns Sec. 4, 4 days	
				Form 5th Floor Columns Sec. 2, 7 days	ins Sec. 2, 7 day
				Deletant Ch. Onlymon C	

Figure 56: October Schedule Calendar

Page 100 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

Overflow Tasks

OCTOBER OVERFLOW TASKS

ID	Name	Start	Finish
439	Place Roof Beams Sec. 2	Wed 10/15/08	Wed 10/15/08
456	Place 4th Floor Beams Sec. 3	Mon 10/13/08	Mon 10/13/08
457	Place 4th Floor Beams Sec. 4	Tue 10/14/08	Tue 10/14/08
458	Place 4th Floor Beams Sec. 5	Wed 10/15/08	Wed 10/15/08
459	Place 4th Floor Beams Sec. 6	Thu 10/16/08	Thu 10/16/08
460	Place 4th Floor Beams Sec. 7	Fri 10/17/08	Fri 10/17/08
422	Reinforce Roof Slab And Beams Sec. 3	Thu 10/16/08	Fri 10/17/08
544	Strip Formwork 4th Floor Slab Sec. 1	Thu 10/16/08	Thu 10/16/08
545	Strip Formwork 4th Floor Slab Sec. 2	Fri 10/17/08	Fri 10/17/08
601	Strip Formwork 4th Beams Sec. 1	Wed 10/15/08	Wed 10/15/08
602	Strip Formwork 4th Beams Sec. 2	Thu 10/16/08	Thu 10/16/08
603	Strip Formwork 4th Beams Sec. 3	Fri 10/17/08	Fri 10/17/08
615	Strip Formwork 5th Beams Sec. 7	Wed 10/15/08	Wed 10/15/08
617	Strip Formwork Roof Beams Sec. 1	Thu 10/16/08	Thu 10/16/08
331	Form 5th Floor Columns Sec. 1	Wed 10/22/08	Thu 10/30/08
423	Reinforce Roof Slab And Beams Sec. 4	Tue 10/21/08	Wed 10/22/08
424	Reinforce Roof Slab And Beams Sec. 5	Fri 10/24/08	Mon 10/27/08
440	Place Roof Beams Sec. 3	Mon 10/20/08	Mon 10/20/08
441	Place Roof Beams Sec. 4	Thu 10/23/08	Thu 10/23/08
546	Strip Formwork 4th Floor Slab Sec. 3	Mon 10/20/08	Mon 10/20/08
547	Strip Formwork 4th Floor Slab Sec. 4	Tue 10/21/08	Tue 10/21/08
548	Strip Formwork 4th Floor Slab Sec. 5	Wed 10/22/08	Wed 10/22/08
549	Strip Formwork 4th Floor Slab Sec. 6	Thu 10/23/08	Thu 10/23/08
550	Strip Formwork 4th Floor Slab Sec. 7.	Fri 10/24/08	Fri 10/24/08
604	Strip Formwork 4th Beams Sec. 4	Mon 10/20/08	Mon 10/20/08
605	Strip Formwork 4th Beams Sec. 5	Tue 10/21/08	Tue 10/21/08
606	Strip Formwork 4th Beams Sec. 6	Wed 10/22/08	Wed 10/22/08
607	Strip Formwork 4th Beams Sec. 7	Thu 10/23/08	Thu 10/23/08
618	Strip Formwork Roof Beams Sec. 2	Tue 10/21/08	Tue 10/21/08
619	Strip Formwork Roof Beams Sec. 3	Fri 10/24/08	Fri 10/24/08
657	Strip Formwork 4th Columns Sec. 1	Fri 10/24/08	Fri 10/24/08
346	Form Roof Columns Sec. 1	Fri 10/31/08	Wed 11/5/08
425	Reinforce Roof Slab And Beams Sec. 6	Wed 10/29/08	Thu 10/30/08
442	Place Roof Beams Sec. 5	Tue 10/28/08	Tue 10/28/08
443	Place Roof Beams Sec. 6	Fri 10/31/08	Fri 10/31/08
552	Strip Formwork 5th Floor Slab Sec. 1	Mon 10/27/08	Mon 10/27/08
553	Strip Formwork 5th Floor Slab Sec. 2	Tue 10/28/08	Tue 10/28/08
554	Strip Formwork 5th Floor Slab Sec. 3	Wed 10/29/08	Wed 10/29/08
555	Strip Formwork 5th Floor Slab Sec. 4	Thu 10/30/08	Thu 10/30/08
556	Strip Formwork Sth Floor Slab Sec. 5	Fri 10/31/08	Fri 10/31/08
620	Strip Formwork Roof Beams Sec. 4	Wed 10/29/08	Wed 10/29/08
658	Strip Formwork 4th Columns Sec. 2	Mon 10/27/08	Mon 10/27/08
659	Strip Formwork 4th Columns Sec. 3	Tue 10/28/08	Tue 10/28/08
661 660	Strip Formwork 4th Columns Sec. 5 Strip Formwork 4th Columns Sec. 4	Thu 10/30/08 Wed 10/29/08	Thu 10/30/08 Wed 10/29/08
000	Sup romwork an Colomb Sec. 4	wed 10/29/08	Weg 10/29/08

Page 101 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

F			ŝ		1 day				15					days	22					29					
Friday Saturcay	nns Sec. 4, 4 clays	Form 5th Floor Columns Sec. 2, 7 days	7	Form Penthouse Sec. 3, 2 days	Flace Penthouse Slab Sec. 1, 1 day	Finish Roof Slab Sec. 7, *		1	14	tuse Stab S	ouse Slab S)	days	Form Roof Columns Sec. 4, 3.5 days	21		Form 5th Floor Columns Sec. 4, 7 days	Place 5th Columns Sec. 5	Form Roof Columns Sec. 5, 3.5 days	58		days			
Thursdey	Form 4th Floor Columns Sec. 4, 4 clays		9	Sec. 2, 2 days	Place Roof Slab Sec. 7, 1	Finish Roof Slab Sec. 6, -	nns Sec. 5, 4 days	days	13	Place Penthouse Slab S	Finish Penthouse Stab S		Form 5th Floor Columns Sec. 3, 7 days		20		Form	Reinforce 5th Columns S Flace 5th Columns Sec. 3	Form	27		Place Roof Columns Set Jumns Sec. 3, 5 days			
Wedresday			2	Form Penthouse Sec. 2, 2 days	Finish Roof Slab Sec. 5, 7 Place Roof Slab Sec. 7,		Form 4th Floor Columns Sec. 5, 4 cays	Form 5th Floor Columns Sec. 2, 7 days	12	e Sec. 4, 2 days	Place Penthouse Slab S	Finish Penthouse Slab S	Form	Place 5th Columns Sec. 2	19					25	mns Sec. 4, 7 days	Reinforce Roof Column: Place Roof (Place Penthouse Column		
Tuesday			4	: Sec. 1, 2 days	Finish Roof Slab Sec. 4, *			Form	11	Form Penthouse Sec. 4, 2 days	Place Penth	Finish Penth		Reinforce 5th Columns S Place 5th Columns Sec. 2	18	Place Penthouse Slab S Finish Penthouse Slab S		mns Sec. 3, 7 days	s Sec. 4, 3.5 days	25	Form 5th Floor Column's Sec. 4, 7 days	Reinforce R	Reinforce Perthouse Col Place Penthouse Column		
Mondey			3	Form Penthouse Sec. 1, 2 days	Place Roof Slab Sec. 5, 1	Finish Roof Slab Sec. 3.	Form 4th Floor Columns Sec. 4, 4 days		9 10	ouse Sec. 3, 2 days	o Sec. 1, 1 day	Finish Penthouse Slab Se		Form 5th Floor Columns Sec. 2, 7 days	16 17	Place Penth Finish Penth		Form 5th Floor Columns Sec. 3, 7 days	Form Roof Columns Sec. 4, 3.5 days	23			Columns Sec. 5, 3.5 days	30	Form Penthouse Columns Sec. 3, 5 days
Sunday							Form 4th Floor (Form Penthouse	Place Penthouse Slab Sec. 1, 1 day			Form 5th Floor (Form Roof		Form Penthouse

Figure 57: November Schedule Calendar

Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Start

Finish

Final Report

NOVEMBER OVERFLOW TASKS

ID

Name

Overflow	Tasks

		otan	1.111911
346	Form Roof Columns Sec. 1	Fri 10/31/08	Wed 11/5/08
347	Form Roof Columns Sec. 2	Wed 11/5/08	Mon 11/10/08
341	Place 5th Columns Sec. 1	Mon 11/3/08	Mon 11/3/08
352	Reinforce Roof Columns Sec. 1	Wed 11/5/08	Thu 11/6/08
358	Place Roof Columns Sec. 1	Thu 11/6/08	Fri 11/7/08
426	Reinforce Roof Slab And Beams Sec. 7	Mon 11/3/08	Tue 11/4/08
428	Reinforce Pent Slab And Beams Sec. 1	Wed 11/5/08	Thu 11/6/08
429	Reinforce Pent Slab And Beams Sec. 2	Fri 11/7/08	Mon 11/10/08
433	Place Penthouse Beams Sec. 1	Thu 11/6/08	Fri 11/7/08
444	Place Roof Beams Sec. 7	Wed 11/5/08	Wed 11/5/08
557	Strip Formwork 5th Floor Slab Sec. 6	Mon 11/3/08	Mon 11/3/08
558	Strip Formwork 5th Floor Slab Sec. 7.	Tue 11/4/08	Tue 11/4/08
560	Strip Formwork Roof Slab Sec. 1	Wed 11/5/08	Wed 11/5/08
561	Strip Formwork Roof Slab Sec. 2	Thu 11/6/08	Thu 11/6/08
562	Strip Formwork Roof Slab Sec. 3	Fri 11/7/08	Fri 11/7/08
621	Strip Formwork Roof Beams Sec. 5	Mon 11/3/08	Mon 11/3/08
663	Strip Formwork 5th Columns Sec. 1	Fri 11/7/08	Fri 11/7/08
622	Strip Formwork Roof Beams Sec. 6	Thu 11/6/08	Thu 11/6/08
348	Form Roof Columns Sec. 3	Tue 11/11/08	Fri 11/14/08
354	Reinforce Roof Columns Sec. 3	Fri 11/14/08	Mon 11/17/08
364	Form Penthouse Columns Sec. 1	Tue 11/11/08	Mon 11/17/08
353	Reinforce Roof Columns Sec. 2	Tue 11/11/08	Tue 11/11/08
359	Place Roof Columns Sec. 2	Wed 11/12/08	Wed 11/12/08
430	Reinforce Pent Slab And Beams Sec. 3	Tue 11/11/08	Wed 11/12/08
431	Reinforce Pent Slab And Beams Sec. 4	Thu 11/13/08	Fri 11/14/08
436	Place Penthouse Beams Sec. 4	Fri 11/14/08	Mon 11/17/08
434	Place Penthouse Beams Sec. 2	Mon 11/10/08	Tue 11/11/08
435	Place Penthouse Beams Sec. 3	Wed 11/12/08	Thu 11/13/08
568	Strip Formwork Penthouse Slab Sec. 1	Fri 11/14/08	Fri 11/14/08
563	Strip Formwork Roof Slab Sec. 4	Mon 11/10/08	Mon 11/10/08
564	Strip Formwork Roof Slab Sec. 5	Tue 11/11/08	Tue 11/11/08
565	Strip FormworkRoof Slab Sec. 6	Wed 11/12/08	Wed 11/12/08
566	Strip Formwork Roof Slab Sec. 7.	Thu 11/13/08	Thu 11/13/08
623	Strip Formwork Roof Beams Sec. 7	Tue 11/11/08	Tue 11/11/08
626	Strip Formwork Penthouse Beams Sec. 2	Thu 11/13/08	Fri 11/14/08
625	Strip Formwork Penthouse Beams Sec. 1	Tue 11/11/08	Wed 11/12/08
668	Strip Formwork Roof Columns Sec. 1	Wed 11/12/08	Thu 11/13/08
355	Reinforce Roof Columns Sec. 4	Thu 11/20/08	Thu 11/20/08
360	Place Roof Columns Sec. 3	Mon 11/17/08	Tue 11/18/08
361	Place Roof Columns Sec. 4	Fri 11/21/08	Fri 11/21/08
365	Form Penthouse Columns Sec. 2	Tue 11/18/08	Mon 11/24/08
372	Place Penthouse Columns Sec. 1	Wed 11/19/08	Wed 11/19/08
368	Reinforce Penthouse Columns Sec. 1	Tue 11/18/08	Tue 11/18/08
570	Strip Formwork Penthouse Slab Sec. 3	Wed 11/19/08	Thu 11/20/08
571	Strip Formwork Penthouse Slab Sec. 4	Fri 11/21/08	Mon 11/24/08
569	Strip Formwork Penthouse Slab Sec. 2	Mon 11/17/08	Tue 11/18/08
628	Strip Formwork Penthouse Beams Sec. 4	Wed 11/19/08	Thu 11/20/08
670	Strip Formwork Roof Columns Sec. 3	Fri 11/21/08	Mon 11/24/08
627 664	Strip Formwork Penthouse Beams Sec. 3	Mon 11/17/08	Tue 11/18/08
669	Strip Formwork 5th Columns Sec. 2 Strip Formwork Roof Columns Sec. 2	Tue 11/18/08 Tue 11/18/08	Tue 11/18/08 Tue 11/18/08
665	Strip Formwork Root Columns Sec. 2		
		Thu 11/27/08	Thu 11/27/08
671	Strip Formwork Roof Columns Sec. 4	Thu 11/27/08	Thu 11/27/08
674	Strip Formwork Penthouse Columns Sec. 1	Tue 11/25/08	Tue 11/25/08

Page 103 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report




Figure 58: December Schedule Calendar

Page 104 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

uilding 1 onstruction	Description	Dur	Start	Early Finish	Start	Finish	Var	JAN	FEB		APR MAY	JUN 1		AUG	JULI		NOV	-0
	n - Structure/Enclosure																	
0006	Start Construction	0	11FEB08A		21JAN08*		-15		♦ Sta	t Const	ruction							
	Temp Weather Tight Close in of Shell	0	TIFEBOOK	03NOV08A	213/1100	01SEP08*	-45		- Ola	CONIS	luction	Temp W	eather	Tight C	lose in i	of Shell		
	Natural Gas to Building	0		14NOV08A	13AUG08	22AUG08	-60									o Building		
	Temporary Heat	0		14NOV08A			0								Temp	orary Hea	at 🔷	
0132	Water to Building	0		05JAN09A	01OCT08	10OCT08	-61									VVa	ater to	Buil
0392	Fire Protection Water to Building	0		05JAN09A			0							F	ire Prote	ection Wa	ater to I	Bui
Aobilization																		
0002	Mobilization	1*	11FEB08A	11FEB08A	21JAN08	25JAN08	-11		Mob	lization								
	Mobilization - Caissons	5	11FEB08A	11FEB08A	21JAN08	25JAN08	-11				- Caissons							
	Mobilization - Excavator	5	11FEB08A	11FEB08A	21JAN08	25JAN08	-11				- Excavator							
0072	Mobilization - Foundations	5	11FEB08A	11FEB08A	21JAN08	25JAN08	-11		Mob	lization	- Foundations							
nitial Sitewor	ork/Excavation																	
0007	Temporary Construction Roads/Fence/Binder	79*	12FEB08A	30MAY08A	28JAN08	20FEB08	-72				ì	Temporary	Const	truction	Roads/	Fence/Bir	nder	
	Trumbull Work Complete	0	121 LOOUN	11APR08A	200/11100	201 2000	0		_		Trumbull W			douon	noudan	i chice bii		
	Install Access Road	10	12FEB08A	14APR08A	28JAN08	08FEB08	-46				Install Acces							
	Install Construction Ramps	10	13FEB08A	24MAR08A			0		-	li i	stall Constructio							
0067	Build Laydown Area - Parking Lot	10	31MAR08A	04APR08A	28JAN08	07MAR08	-20				Build Laydown	Area - Pa	rking L	ot				
	Install Fence & Double-Wide Gate	5	27MAY08A	30MAY08A	14FEB08	20FEB08	-72				1	Install Fen	ce & D	ouble-V	Nide Ga	te		
aissons																		
0076	Lavout Baselines - Turner	5	08FEB08A	11FEB08A	14JAN08*	18JAN08	-16		aw	ut Baer	lines - Turner							
	Caissons: E-BLDG	5	11FEB08A	11FEB08A 14FEB08A	14JAN08* 04FEB08	18JAN08 08FEB08	-16				E-BLDG							
	Caissons: E-BLDG Caissons: W-BLDG	5	11FEB08A	19FEB08A	11FEB08	15FEB08	-4				W-BLDG							
	Elevator Jack Hole - W	3	20MAY08A	20MAY08A	11FEB08	13FEB08	-69					avator Jack	Hole	w				
irade Beams														_				-
	1	1			m													
	Wall Footers (0.7-3): E-BLDG	8	11FEB08A	27FEB08A			0				oters (0.7-3): E-							
	Wall Footers (3-7): E-BLDG	8	11FEB08A	28FEB08A	0455000	10111 000	0			Wall Fo	oters (3-7): E-B		DI DO					
	Grade Beams: E-BLDG	59* 3	11FEB08A 26FEB08A	01MAY08A 29FEB08A	21FEB08	12MAR08	-36 0			Mall Ea	Grade I oters (N 7-21):		BLDG					
	Wall Footers (N 7-21): C-BLDG Grade Beams: C-BLDG	61*	26FEB08A 26FEB08A	20MAY08A	25FEB08	14MAR08	-47				Gr		e C-B	IDG				
	Wall Footers (S 15-20): C-BLDG	4	28FEB08A	05MAR08A	ZOFEDUO	THMARUO	-4/				ooters (S 15-20)						-	-
	Wall Footers (S 9-15): C-BLDG	4	29FEB08A	03MAR08A			0				ooters (S 9-15):							
	Wall Footers (S 7-9): C-BLDG	4	03MAR08A	06MAR08A			0				ooters (S 7-9):							
	Wall Footers (S 20-22): C-BLDG	2	05MAR08A	13MAR08A			0			Wal	Footers (S 20-2	2): C-BLD	G					
	Interior Spread Footers (S 9-20 / A-B):	3	07MAR08A	12MAR08A			0			Inter	ior Spread Foot	ers (S 9-20	(A-B)	C-BL	DG			
	Wall Footers (S 22-25): W-BLDG	3	10MAR08A	14MAR08A			0			Wa	Footers (S 22-	25): W-BL	DG			1		
0308	Wall Footers (N 22-26): W-BLDG	3	10MAR08A	14MAR08A			0			∎ Wa	Il Footers (N 22-:	26): W-BL	DG					
0018	Grade Beams: W-BLDG	20*	10MAR08A	04APR08A	10MAR08	28MAR08	-5				Grade Beams:							
0328	Wall Footers (S 25-31): W-BLDG	3	20MAR08A	28MAR08A			0			-	Wall Footers (S							
	Interior Spread Footers (C-D): C-BLDG	8	17MAR08A	20MAY08A			0				-	erior Sprea			D): C-B	LDG		
	Interior Spread Footers: W-BLDG	5	24MAR08A	04APR08A			0				Interior Spread							
	Interior Spread Footers: E-BLDG	10	07APR08A	01MAY08A			0				Interior			E-BLD	G			
	Elevator Pits: C-BLDG	10	09APR08A	01MAY08A	25FEB08	07MAR08	-39				Elevato							
	Elevator Pits: W-BLDG	5	13MAY08A	27MAY08A	10MAR08	14MAR08	-52			_	Trench Drain	levator Pit						
	Trench Drain: Excavation to Swale (NOT Trench Drain: C-BLDG	5	17MAR08A 24MAR08A	09APR08A 08APR08A			0				Trench Drain		ontoa	wale (i	IOT FOI	JND)	-	
	Trench Drain: E-BLDG	4	24MAR08A	09APR08A			0				Trench Drain							
	Trench Drain: W-BLDG	4	31MAR08A	03APR08A			0				Trench Drain:							
oundation V													1	-			-	1
	Foundation Walls: E-BLDG	30*	03MAR08A	11APR08A	28FEB08	07MAY08	18				Foundation V							
	Foundation Walls: C-BLDG	17*	10APR08A	02MAY08A	06MAR08	14MAY08	8				Founda							
0022 orth Elevation	Foundation Walls: W-BLDG	24*	17APR08A	20MAY08A	07APR08	13JUN08	18				Fo	undation V	valis:	W-BLD	3	-		_
	Form (E / 0.7-3): E-BLDG	3	03MAR08A	06MAR08A			0			Form	(E / 0.7-3): E-BI	DG						
	Resteel / MEPs (E / 0.7-3): E-BLDG	3	06MAR08A	25MAR08A			0				esteel / MEPs (E-BLC	G				
	Pour (E / 0.7-3): E-BLDG	1	03APR08A	03APR08A			0				Pour (E / 0.7-3	E-BLDG	3					
2480	Form (E / 3-7): E-BLDG	2	04APR08A	08APR08A			0				Form (E / 3-7							
	Resteel / MEPs (E / 3-7): E-BLDG	2	07APR08A	08APR08A			0				Resteel / MEI			.DG				
	Pour (E / 3-7): E-BLDG	1	09APR08A	09APR08A			0				Pour (E / 3-7)							
	Form (E / 7-16): C-BLDG	2	10APR08A	11APR08A			0				Form (E / 7-1							
	Resteel / MEPs (E / 7-16): C-BLDG	2	14APR08A	15APR08A			0				Resteel / M			-BLDG				
	Pour (E / 7-16): C-BLDG	1	16APR08A	16APR08A			0				Pour (E / 7-							
	Form (E / 16-25): W-BLDG	2	17APR08A	18APR08A			0				Form (E / 1	-			DC	-	-	-
	Resteel / MEPs (E / 16-25): W-BLDG	2	18APR08A	24APR08A 30APR08A			0				Resteel /	MEPs (E /						
	Resteel / MEPs (E / 25-29): W-BLDG Form (E / 25-29): W-BLDG	2	28APR08A 28APR08A	01MAY08A			0					/ MEPS (E						
	Porr (E / 16-25): W-BLDG Pour (E / 16-25): W-BLDG	1	29APR08A	29APR08A			0					/ 16-25):						
	Form (E / 29-31, E-D / 31): W-BLDG	2	01MAY08A	14MAY08A			0					n (E / 29-3			W-BLDG	2		
	Pour (E / 25-29): W-BLDG	1	02MAY08A	02MAY08A			0					E / 25-29):						Ē
	Resteel / MEPs (E / 29-31, E-D / 31):	2	09MAY08A	13MAY08A			0											
	Pour (E / 29-31, E-D / 31): W-BLDG	1	20MAY08A	20MAY08A			0				1							
	Form (D-C / 31, C / 28-31): W-BLDG	2	08MAY08A	08MAY08A			0				1							
0410	Resteel / MEPs (D-C / 31, C / 28-31):	2	A80YAME0	09MAY08A			0				1		1					
	Pour (D-C / 31, C / 28-31): W-BLDG	1	16MAY08A	16MAY08A			0				1		1					Ē
			00111 5 5 5	00144 5555									1					1
	Form (B-D / 0.7-4): E-BLDG Resteel / MEPs (B-D / 0.7-4): E-BLDG	3	03MAR08A	06MAR08A	24 (41)00	27552000	0			-								
0034		3	06MAR08A	19MAR08A	24JAN08	27FEB08	-15			-								
0044		4	20110 000*															
0034 0044 0074	Pour (B-D / 0.7-4): E-BLDG	1	20MAR08A	20MAR08A	25JUN08	01JUL08	73											
0034 0044 0074 0194		1 2 2	20MAR08A 03APR08A 04APR08A	20MAR08A 08APR08A 11APR08A	25JUN08	0130108	73 0 0											

Finish Date 18,UN00 Progress Bar Data Date 13,UN00 Progress Bar Figure 59: Turner Construction Schedule 1/4 Page 105 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

Activity ID	Activity Description	Orig Dur	Early Start	Early Finish	Plan Start	Plan Finish	Fin Var	JAN FEB MAR	2008 APR MAY JUN JUL AUG SEP OCT NOV D
0204	Resteel / MEPs (B / 4-7): E-BLDG	2	07APR08A	07APR08A			0		Resteel / MEPs (B / 4-7): E-BLDG
0214	Pour (B / 4-7): E-BLDG	1	09APR08A	09APR08A			0		IPour (B / 4-7): E-BLDG
0234	Resteel / MEPs (B / 7-9): E-BLDG	2	09APR08A	10APR08A			0		Resteel / MEPs (B / 7-9): E-BLDG
0244	Pour (B / 7-9): E-BLDG	1	14APR08A	11APR08A			0		Pour (B / 7-9): E-BLDG
0033	Form (A-Line, A / 9-12): C-BLDG	2	10APR08A	17APR08A			0		Form (A-Line, A / 9-12): C-BLDG
0103	Form (A / 12-16): C-BLDG	2	11APR08A	22APR08A	13AUG08	19AUG08	85		Form (A / 12-16): C-BLDG
0073	Resteel / MEPs (A-Line, A / 9-12): C-BLDG	2	14APR08A	16APR08A	10SEP08	16SEP08	109		Resteel / MEPs (A-Line, A / 9-12): C-BLDG
0143	Form (A / 16-20, A-A.4): C-BLDG	2	17APR08A	24APR08A	16OCT08	20OCT08	127		Form (A / 16-20, A-A.4): C-BLDG
0193	Resteel / MEPs (A / 16-20, A-A.4): C-BLDG	2	17APR08A	24APR08A			0		Resteel / MEPs (A / 16-20, A-A.4): C-BLDG
0093	Pour (A-Line, A / 9-12): C-BLDG	1	18APR08A	18APR08A	16JUL08	22JUL08	67		Pour (A-Line, A / 9-12): C-BLDG
0123	Resteel / MEPs (A / 12-16): C-BLDG	2	18APR08A 23APR08A	21APR08A 23APR08A	010CT08 28AUG08	07OCT08 01SEP08	121 93		Resteel / MEPs (A / 12-16): C-BLDG Pour (A / 12-16): C-BLDG
	Pour (A / 12-16): C-BLDG	1		01MAY08A	28AUGU8	UISEPU8			Form (A,4-B, B / 20-24); C-BLDG
00921 0203	Form (A.4-B, B / 20-24): C-BLDG Pour (A / 16-20, A-A.4): C-BLDG	2	23APR08A 25APR08A	25APR08A		-	0		Pour (A / 16-20, A-A.4): C-BLDG
0203	Resteel / MEPs (A.4-B, B / 20-23): C-BLDG	2	25APR08A 25APR08A	29APR08A		01SEP08*	89		Resteel / MEPs (A.4-B, B / 20-23): C-BLDG
0182	Pour (A.4-B, B / 20-23): C-BLDG	1	02MAY08A	02MAY08A		UISEF00	0.0	1 1	Pour (A.4-B, B / 20-23); C-BLDG
0292	Form (B / 23-28): W-BLDG	2	23APR08A	07MAY08A			0		Form (B / 23-28): W-BLDG
0302	Resteel / MEPs (B / 23-28): W-BLDG	2	01MAY08A	07MAY08A			0		Resteel / MEPs (B / 23-28): W-BLDG
0312	Pour (B / 23-28); W-BLDG	1	08MAY08A	08MAY08A			0		Pour (B / 23-28): W-BLDG
	Waterproofing	<u> </u>	Competition	- CONTRACT CONT					
	1								Maturat 0 BLDC (4 Line)
0030	Waterproof: C-BLDG (A-Line)	2	01MAY08A	22JUL08A	07JUL08	08JUL08	-10		Waterproof: C-BLDG (A-Line) Waterproof: C-BLDG (E-Line)
0121	Waterproof: C-BLDG (E-Line)	2	01MAY08A	23JUL08A	22APR08	23APR08	-65		
0099	Waterproof: E-BLDG (B-Line)	2	30APR08A	01AUG08A	04AUG08	05AUG08	2		Waterproof: E-BLDG (B-Line)
0031	Waterproof: E-BLDG (E-Line)	2	01MAY08A 13MAY08A	01AUG08A 01AUG08A	22APR08 13MAY08	23APR08 14MAY08	-72 -57		Waterproof: E-BLDG (E-Line) Waterproof: W-BLDG (E-Line)
0131 0029	Waterproof: W-BLDG (E-Line) Waterproof: W-BLDG (B-Line)	2	13MAY08A 19MAY08A	01AUG08A 01AUG08A	13MAY08 22SEP08	14MAY08 23SEP08	-57 37		Waterproof: W-BLDG (E-Line) Waterproof: W-BLDG (B-Line)
.G. Utilities		2	TOWATUBA	JINOGUSA	2236908	2336908	51		
0113E	Elec Main Feeders UG: E-BLDG	5	21APR08A	28APR08A			0		Elec Main Feeders UG: E-BLDG
0223	UG Sanitary Mechanical Rm: E-BLDG	5	22APR08A	01MAY08A			0		UG Sanitary Mechanical Rm: E-BLDG
0213	Elec UG Mechanical Rm: E-BLDG	5	29APR08A	08MAY08A			0		Elec UG Mechanical Rm: E-BLDG
0233	UG Sanitary: E-BLDG	5	09MAY08A	19AUG08A			0		UG Sanitary: E-BLDG
0243	UG Sanitary: C-BLDG	5	05MAY08A	17JUL08A			0		UG Sanitary: C-BLDG
0253	UG Sanitary: W-BLDG	5	05MAY08A	19AUG08A	40.000	44 8 4 5 5 5 5	0		UG Sanitary: W-BLDG UG Utilites (Crane Path): E-I
0058 0052	UG Utilites (Crane Path): E-BLDG UG Utilites (Crane Path): W-BLDG	5	15AUG08A 25AUG08A	19AUG08A 29AUG08A	16JUN08 13MAR08	11JUL08 09APR08	-27 -102		UG Utilites (Crane Path): E-t UG Utilites (Crane Path): W-BLDG
0052 OG	OG Otilites (Crane Path). W-BLDG	5	2340G084	29403084	TSWARUS	USAPROS	- 102		
0046	SOG: C-BLDG	35*	22JUL08A	08SEP08A	14APR08	02MAY08	-91		SOG: C-BLDG
0045	SOG: W-BLDG	13*	21AUG08A	08SEP08A	28APR08	06MAY08	-89		SOG: W-BLDG
0047 levator Pits	SOG: E-BLDG	25*	02SEP08A	060CT08A	10APR08	18APR08	-121		SOG: E-BLDG
P100-11	Excavate (EP 1-2)	1	02MAY08A	02MAY08A			0		Excavate (EP 1-2)
P100-01	Form Bottom (Elevator Pit 1-2)	2	15MAY08A	16MAY08A		-	0		Form Bottom (Elevator Pit 1-2)
EP110-01	Pre-Proof Waterproofing (EP 1-2)	2	20MAY08A	20MAY08A			0		Pre-Proof Waterproofing (EP 1-2)
EP120-01	Place Footing (EP 1-2)	2	20MAY08A	21MAY08A			0		Place Footing (EP 1-2)
EP130-01	Place Walls (EP 1-2)	2	22MAY08A	27MAY08A			0		Place Walls (EP 1-2)
EP140-01	Cure Period (7 Days)	7	27MAY08A	02JUN08A			0		Cure Period (7 Days)
EP150-01	Bituthene Waterproof (EP 1-2)	2	03JUN08A	03JUN08A			0		Bituthene Waterproof (EP 1-2)
EP160-01	Backfill (EP 1-2)	2	03JUN08A	04JUN08A			0		Backfill (EP 1-2)
EP095-03	Excavate (EP 3-4)	1	02MAY08A	02MAY08A			0		Excavate (EP 3-4)
EP100-03	Form Bottom (Elevator Pit 3-4)	2	19MAY08A	19MAY08A			0		Form Bottom (Elevator Pit 3-4)
EP110-03	Pre-Proof Waterproofing (EP 3-4)	2	20MAY08A	20MAY08A			0		Pre-Proof Waterproofing (EP 3-4)
EP120-03	Place Footing (EP 3-4)	2	21MAY08A	21MAY08A			0		Place Footing (EP 3-4)
EP130-03	Place Walls (EP 3-4)	2	23MAY08A	28MAY08A			0		Place Walls (EP 3-4)
EP140-03	Cure Period (7 Days)	7	28MAY08A	04JUN08A			0		Cure Period (7 Days)
EP150-03	Bituthene Waterproof (EP 3-4)	2	08JUL08A	09JUL08A			0		Bituthene Waterproof (EP 3-4)
EP160-03	Backfill (EP 3-4)	2	10JUL08A	11JUL08A			0		Backfill (EP 3-4)
EP095-05	Excavate (EP-5)	1	12MAY08A	13MAY08A			0		Excavate (EP-5)
EP100-05	Form Bottom (Elevator Pit 5)	2	20MAY08A	21MAY08A			0		Form Bottom (Elevator Pit 5)
P110-05	Pre-Proof Waterproofing (EP 5)	2	21MAY08A	21MAY08A			0		Pre-Proof Waterproofing (EP 5)
EP120-05	Place Footing (EP 5)	2	22MAY08A	27MAY08A			0		Place Footing (EP 5)
EP130-05	Place Walls (EP 5)	2	28MAY08A	29MAY08A			0		Place Walls (EP 5)
EP140-05	Cure Period (7 Days)	7	30MAY08A	06JUN08A			0		Cure Period (7 Days)
EP150-05	Bituthene Waterproof (EP 5)	2	23JUN08A	20JUN08A			0		Bituthene Waterproof (EP 5)
EP160-05	Backfill (EP 5)	2	08JUL08A	09JUL08A			0		Backfill (EP 5)
EP095-06	Excavate (EP 6)	1	09APR08A	09APR08A			0		Excavate (EP 6)
EP100-06	Form Bottom (Elevator Pit 6)	2	16JUN08A	16JUN08A			0		Form Bottom (Elevator Pit 6)
	Pre-Proof Waterproofing (EP 6)	2	19JUN08A	19JUN08A			0		Pre-Proof Waterproofing (EP 6)
EP120-06	Place Footing (EP 6)	2	20JUN08A	20JUN08A			0		Place Footing (EP 6)
EP130-06	Place Walls (EP 6)	2	26JUN08A	26JUN08A			0		Place Walls (EP 6)
EP140-06	Cure Period (7 Days)	7	27JUN08A	03JUL08A	-		0		Cure Period (7 Days)
EP150-06	Bituthene Waterproof (EP 6)	2	08JUL08A	09JUL08A			0		Bituthene Waterproof (EP 6) Backfill (EP 6)
EP160-06	Backfill (EP 6)	2	10JUL08A	11JUL08A			0		
EP100-07	Form Bottom (Elevator Pit 7)	2	13JUN08A	13JUN08A			0		Form Bottom (Elevator Pit 7)
EP120-07 EP110-07	Place Footing (EP 7)	2	13JUN08A 23JUN08A	13JUN08A 20JUN08A		-	0		
EP110-07 EP130-07	Pre-Proof Waterproofing (EP 7) Place Walls (EP 7)	2	23JUN08A 01AUG08A	20JUN08A 01AUG08A	-		0		
P130-07	A	2	01AUG08A 02AUG08A	01AUG08A 08AUG08A			0		
EP140-07 EP150-07	Cure Period (7 Days) Bituthene Waterproof (EP 7)	2	02AUG08A 08AUG08A	08AUG08A 08AUG08A		-	0		
P150-07	Bituthene vvaterproof (EP 7) Backfill (EP 7)	2	11AUG08A	11AUG08A			0		
G110	Place Stone & Underdrain (D.5 / 3-20)	2	28MAY08A	29MAY08A			0		
SG120	Form, Vapor Barrier & Mesh (D.5 / 3-20)	2	30MAY08A	02JUN08A			0		
	Waterproof (D.5 / 3-20)	1	02JUN08A	02JUN08A			0		
	Place Concrete (D.5 / 3-20)	1	02JUL08A	02JUL08A			0		
	Strip Forms (D.5 / 3-20)	1	07JUL08A	07JUL08A			0		1
G150		2	12JUN08A	13JUN08A			0		1
G 150 G 160	Place Stone & Underdrain (C-D / 1-0.7)								
5G150 5G160 5G110-02	Place Stone & Underdrain (C-D / 1-0.7) Form, Vapor Barrier & Mesh (C-D / 1-0.7)	1	14JUL08A	14JUL08A			0		
5G130 5G150 5G160 5G110-02 5G120-02 5G130-02			14JUL08A 16JUL08A	14JUL08A 16JUL08A			0		
6G150 6G160 6G110-02 6G120-02	Form, Vapor Barrier & Mesh (C-D / 1-0.7)	1							

Figure 60: Turner Construction Schedule 2/4

Page 106 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan Westinghouse Electric Company Corporate Headquarters Cranberry, PA April 7, 2009

Final Report

ID	Activity Description	Orig Dur	Early Start	Early Finish	Plan Start	Plan Finish	Fin Var	2008 JAN FEB MAR APR MAY JUN JUL AUG SEP OCT NOV DE
SG110-05	Place Stone & Underdrain (C-E / 28-31)	2	19AUG08A	20AUG08A			0	Place Stone & Underdrain (C-E / 28-31)
SG120-05	Form, Vapor Barrier & Mesh (C-E / 27-31)	2	02SEP08A	16SEP08A			0	Form, Vapor Barrier & Mesh (C-E / 27-31)
SG130-05	Waterproof (C-E / 27-31)	1	16SEP08A	16SEP08A			0	Waterproof (C-E / 27-3
SG150-05	Strip Forms (C-E / 27-31)	1	18SEP08A	18SEP08A	-		0	IStrip Forms (C-E / 27- Place Concrete (C-E / 27-31)
SG140-05 SG110-06	Place Concrete (C-E / 27-31) Place Stone & Underdrain (A-B / 9-20) [1]	1 2	26SEP08A 22JUL08A	26SEP08A 05AUG08A	-		0	Place Stone & Underdrain (A-B / 9-20) [1]
SG110-06 SG130-06	Waterproof (A-B / 9-20) [1]	1	18AUG08A	18AUG08A			0	Waterproof (A-B / 9-20) [1]
SG120-06	Form, Vapor Barrier & Mesh (A-B / 9-20) [1]	2	18AUG08A	26AUG08A	-		0	Form, Vapor Barrier & Mesh (A-B / 9-20) [1]
SG140-06	Place Concrete (A-B / 9-20) [1]	1	27AUG08A	27AUG08A	-		0	IPlace Concrete (A-B / 9-20)
SG150-06	Strip Forms (A-B / 9-20) [1]	1	28AUG08A	28AUG08A			0	Strip Forms (A-B / 9-20) [1]
SG110-11	Place Stone & Underdrain (B-D / 15-21) [2]	2	02SEP08A	03SEP08A			0	Place Stone & Underdrain (B-D / 15-21) [2]
SG120-11	Form, Vapor Barrier & Mesh (B-D / 15-21) [2]	2	04SEP08A	05SEP08A			0	Form, Vapor Barrier & Mesh (B-D / 15-21) [2]
SG130-11	Waterproof (B-D / 15-21) [2]	1	05SEP08A	05SEP08A			0	Waterproof (B-D / 15-21)
SG140-11	Place Concrete (B-D / 15-21) [2]	1	08SEP08A	08SEP08A			0	Place Concrete (B-D / 15-21) [2]
SG150-11	Strip Forms (B-D / 15-21) [2]	1	09SEP08A	09SEP08A			0	IStrip Forms (B-D / 15-21
SG110-09	Place Stone & Underdrain (C-D.5 / 5-15) [3]	2	02SEP08A	03SEP08A			0	Place Stone & Underdrain (C-D.5 / 5-15) [3]
SG120-09	Form, Vapor Barrier & Mesh (C-D.5 / 5-15) [3]	2	04SEP08A	05SEP08A			0	Form, Vapor Barrier & Mesh (C-D.5 / 5-15) [3]
SG130-09	Waterproof (C-D.5 / 5-15) [3]	1	05SEP08A	05SEP08A			0	Waterproof (C-D.5 / 5-15)
SG140-09	Place Concrete (C-D.5 / 5-15) [3]	1	08SEP08A	08SEP08A			0	Place Concrete (C-D.5 / 5-15) [3]
SG150-09	Strip Forms (C-D.5 / 5-15) [3]	1	09SEP08A	09SEP08A			0	Strip Forms (C-D.5 / 5-15) [3]
SG110-04	Place Stone & Underdrain (B-C / 5-14) [4]	2	20AUG08A	21AUG08A			0	Place Stone & Underdrain (B-C / 5-14) [4]
SG120-04	Waterproof (B-C / 5-14) [4]	3	22AUG08A	22AUG08A			0	Waterproof (B-C / 5-14) [4]
SG130-04	Form & Mesh (B-C / 5-14) [4]	1	23AUG08A	24AUG08A			0	Form & Mesh (B-C / 5-14) [4]
SG140-04	Place Concrete (B-C / 5-14) [4]	1	02SEP08A	02SEP08A			0	Place Concrete (B-C / 5-14) [4]
SG150-04	Strip Forms (B-C / 5-14) [4]	1	09SEP08A	09SEP08A			0	IStrip Forms (B-C / 5-14)
SG110-07	Place Stone & Underdrain (B-D / 21-25) [5]	2	19AUG08A	20AUG08A	-		0	Place Stone & Underdrain (B-D / 21-25) [5]
SG120-07	Form, Vapor Barrier & Mesh (B-D / 21-25) [5]	2	21AUG08A	22AUG08A	-		0	Form, Vapor Barrier & Mesh (B-D / 21-25) [5]
SG130-07	Waterproof (B-D / 21-25) [5]	1	22AUG08A	22AUG08A			0	Waterproof (B-D / 21-25) [5] Place Concrete (C-D / 21-25) [5]
SG140-07	Place Concrete (C-D / 21-25) [5]	1	29AUG08A	29AUG08A			0	Place Concrete (C-D / 21-25) [5] Strip Forms (C-D / 21-25)
SG150-07 SG150-17	Strip Forms (C-D / 21-25) [5]	1	02SEP08A	02SEP08A			0	
SG150-17 SG110-03	Place Concrete (B-C / 21-26)	1	03SEP08A 02SEP08A	03SEP08A 03SEP08A	-		0	Place Concrete (B-C / 21-2 Place Stone & Underdrain (B-C / 1-5) [7]
SG110-03 SG120-03	Place Stone & Underdrain (B-C / 1-5) [7] Form Vanor Barrier & Mesh. (B-C / 1-5) [7]	-	02SEP08A 04SEP08A	03SEP08A 05SEP08A	-		0	Form, Vapor Barrier & Mesh (B-C / 1-5) [7]
SG120-03 SG130-03	Form, Vapor Barrier & Mesh (B-C / 1-5) [7] Waterproof (B-C / 1-5) [7]	2	04SEP08A 05SEP08A	05SEP08A 05SEP08A	-		0	Waterproof (B-C / 1-5) [7]
SG130-03 SG140-03	Viaterproof (B-C / 1-5) [7] Place Concrete (B-C / 1-5) [7]	1	08SEP08A	08SEP08A			0	Place Concrete (B-C / 1-5) [7]
SG150-03	Strip Forms (B-C / 1-5) [7]	1	09SEP08A	09SEP08A			0	IStrip Forms (B-C / 1-5) [
SG105-12B		4	02SEP08A	29SEP08A			0	Complete Foundation Wall: 0.7 Line
SG110-10	Place Stone & Underdrain (C-E / 0.7-3) [8]	2	01OCT08A	010CT08A	-		0	Place Stone & Underdrain (C-E / 0.7-3) [8]
SG120-10	Form, Vapor Barrier & Mesh (C-E / 0.7-3) [8]	2	010CT08A	030CT08A			0	Form, Vapor Barrier & Mesh (C-E / 0.7-3) [8]
SG130-10	Waterproof (C-E / 0.7-3) [8]	1	020CT08A	020CT08A	-		0	Waterproof (C-E / 0.7-3) [8]
SG140-10	Place Concrete (C-E / 0.7-3) [8]	1	060CT08A	060CT08A			0	Place Concrete (C-E / 0.7-3) [8]
SG150-10	Strip Forms (C-E / 0.7-3) [8]	1	070CT08A	070CT08A			0	Strip Forms (C-E / 0.7-3) [8]
SG110-12A	Place Stone & Underdrain (B-C / 24-28) [10]	2	02SEP08A	03SEP08A			0	Place Stone & Underdrain (B-C / 24-28) [10]
SG120-12A	Form, Vapor Barrier & Mesh (B-C / 24-28)	2	04SEP08A	05SEP08A			0	Form, Vapor Barrier & Mesh (B-C / 24-28) [10]
SG130-12A	Waterproof (B-C / 24-28) [10]	1	05SEP08A	05SEP08A			0	Waterproof (B-C / 24-28)
SG140-12A	Place Concrete (B-C / 24-28) [10]	1	08SEP08A	08SEP08A			0	Place Concrete (B-C / 24-28) [10]
SG150-12A	Strip Forms (B-C / 24-28) [10]	1	09SEP08A	09SEP08A			0	Strip Forms (B-C / 24-28) [10]
SG105-12A	Complete Foundation Wall: 28-Line	4	02SEP08A	020CT08A			0	Complete Foundation Wall: 28-Line
SG105-20	Complete Foundation Walls @ 0.7, 01 Line	10	15SEP08A	29SEP08A			0	Complete Foundation Walls @ 0.7, 01 Line
Backfill/Wall North Elevation	Bracing							
North Elevation								
	Backfill: F-Line, C-BLDG	2	16MAY08A	31JUL08A	07MAY08	08MAY08	-60	Backfill: F-Line, C-BLDG
0397 0577	Backfill: F-Line, C-BLDG Caissons: F-Line, C-BLDG	2	16MAY08A 22MAY08A	31JUL08A 23MAY08A	07MAY08	08MAY08	-60 0	Backfill F-Line, C-BLDG
0397					07MAY08 30APR08	08MAY08 01MAY08	-	
0397 0577	Caissons: F-Line, C-BLDG	3	22MAY08A	23MAY08A			0	Caissons: F-Line, C-BLDG
0397 0577 0327	Caissons: F-Line, C-BLDG Piers: F-Line, C-BLDG	3	22MAY08A 10JUN08A	23MAY08A 13JUN08A	30APR08	01MAY08	0 -31	Caissons: F-Line, C-BLDG Piers: F-Line, C-BLDG
0397 0577 0327 0317	Caissons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG	3 2 2	22MAY08A 10JUN08A 16JUN08A	23MAY08A 13JUN08A 17JUN08A	30APR08 28APR08	01MAY08 29APR08	0 -31 -35	Caissons: F-Line, C-BLDG ■Piers: F-Line, C-BLDG ■Footings: F-Line, C-BLDG
0397 0577 0327 0317 0227	Caissons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG	3 2 2 3	22MAY08A 10JUN08A 16JUN08A 07JUL08A	23MAY08A 13JUN08A 17JUN08A 09JUL08A	30APR08 28APR08 21APR08	01MAY08 29APR08 23APR08	0 -31 -35 -55	ICaissons: F-Line, C-BLDG IPrets: F-Line, C-BLDG IFootings: F-Line, Q-BLDG IVail Branding: F-Line, C-BLDG
0397 0577 0327 0317 0227 0367	Caissons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Masonry: F-Line, C-BLDG	3 2 2 3 3	22MAY08A 10JUN08A 16JUN08A 07JUL08A 16SEP08A	23MAY08A 13JUN08A 17JUN08A 09JUL08A 07NOV08A	30APR08 28APR08 21APR08	01MAY08 29APR08 23APR08	0 -31 -35 -55 -133	Caissons: F-Line, C-BLDG Pierts: F-Line, C-BLDG IFootings: F-Line, C-BLDG Milli Brandag: F-Line, C-BLDG Masony: F-Line, C-BLDG
0397 0577 0327 0317 0227 0367 0587	Caissons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Masony: F-Line, C-BLDG Caissons: F-Line, E-BLDG	3 2 2 3 3 3 2	22MAY08A 10JUN08A 16JUN08A 07JUL08A 16SEP08A 28MAY08A	23MAY08A 13JUN08A 17JUN08A 09JUL08A 07NOV08A 30MAY08A	30APR08 28APR08 21APR08 02MAY08	01MAY08 29APR08 23APR08 06MAY08	0 -31 -35 -55 -133 0	Caissons: F-Line, C-BLDG IPrets: F-Line, C-BLDG IFootings: F-Line, C-BLDG IMail Brands; F-Line, C-BLDG Caissons: F-Line, C-BLDG ICaissons: F-Line, E-BLDG IPcotings: F-Line, E-BLDG IWall Brading; F-Line, E-BLDG
0397 0577 0327 0317 0227 0367 0587 0297	Calssons: F-Line, C-BLDG Piers: F-Line, C-BLDG Foolings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Galssons: F-Line, E-BLDG Footings: F-Line, E-BLDG Wall Bracing: F-Line, E-BLDG Piers: F-Line, E-BLDG	3 2 2 3 3 2 2 2	22MAY08A 10JUN08A 16JUN08A 07JUL08A 16SEP08A 28MAY08A 18JUN08A	23MAY08A 13JUN08A 17JUN08A 09JUL08A 07NOV08A 30MAY08A 20JUN08A	30APR08 28APR08 21APR08 02MAY08 28APR08	01MAY08 29APR08 23APR08 06MAY08 29APR08	0 -31 -35 -55 -133 0 -38	ICaissons: F-Line, C-BLDG IPerter, F-Line, C-BLDG IProtings: F-Line, C-BLDG Matil Brades; F-Line, C-BLDG Caissons: F-Line, C-BLDG IFoctings: F-Line, F-BLDG IProtings: F-Line, F-BLDG IPerter; F-Line, E-BLDG IPerter; F-Line, E-BLDG
0397 0577 0327 0317 0227 0367 0587 0297 0217 0307 0387	Calssons: F-Line, C-BLDG Piers: F-Line, C-BLDG Foolings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Calssons: F-Line, F-BLDG Calssons: F-Line, F-BLDG Wall Bracing: F-Line, F-BLDG Piers: F-Line, F-BLDG Bachtlit: F-Line, F-BLDG	3 2 2 3 3 2 2 2 3	22MAY08A 10JUN08A 16JUN08A 07JUL08A 16SEP08A 28MAY08A 18JUN08A 07JUL08A 25AUG08A 22SEP08A	23MAY08A 13JUN08A 17JUN08A 09JUL08A 07NOV08A 30MAY08A 20JUN08A 09JUL08A 28AUG08A 07NOV08A	30APR08 28APR08 21APR08 02MAY08 28APR08 21APR08 30APR08 08MAY08	01MAY08 29APR08 23APR08 06MAY08 29APR08 23APR08 01MAY08 09MAY08	0 -31 -35 -55 -133 0 -38 -55 -85 -85 -130	ICaissons: F-Line, C-BLDG IPretirs: F-Line, C-BLDG IFootings: F-Line, C-BLDG IMasony: F-Line, C-BLDG ICaissons: F-Line, E-BLDG IFootings: F-Line, E-BLDG IFootings: F-Line, E-BLDG IVall Bracing: F-Line, E-BLDG IPretirs: F-Line, E-BLDG Backfilt: F-Line, E-BLDG
0397 0577 0327 0317 0227 0367 0587 0297 0217 0307 0387 0357	Calssons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Gissons: F-Line, E-BLDG Footings: F-Line, E-BLDG Wall Bracing: F-Line, E-BLDG Backfill: F-Line, E-BLDG Masony: F-Line, E-BLDG	3 2 3 3 2 2 2 3 4 2 3 4 2 4	22MAY08A 10JUN08A 16JUN08A 07JUL08A 16SEP08A 28MAY08A 18JUN08A 07JUL08A 25AUG08A 22SEP08A 24SEP08A	23MAY08A 13JUN08A 17JUN08A 09JUL08A 07NOV08A 20JUN08A 09JUL08A 28AUG08A 07NOV08A	30APR08 28APR08 21APR08 02MAY08 28APR08 21APR08 30APR08	01MAY08 29APR08 23APR08 06MAY08 29APR08 23APR08 01MAY08	0 -31 -35 -55 -133 0 -38 -55 -85 -130 -132	ICaissons: F-Line, C-BLDG IPerter: F-Line, C-BLDG IFootings: F-Line, C-BLDG Wall Brands: F-Line, C-BLDG ICaissons: F-Line, E-BLDG ICaissons: F-Line, E-BLDG IVail Brands: F-Line, E-BLDG IVail Brands: F-Line, E-BLDG Backti: F-Line, E-BLDG Backti: F-Line, E-BLDG Backti: F-Line, E-BLDG Maisony: F-Line, E-BLDG
0397 0577 0327 0317 0227 0367 0587 0297 0217 0307 0387 0387 0357 0597	Calssons: F-Line, C-BLDG Piers: F-Line, C-BLDG Foolings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Calssons: F-Line, E-BLDG Foolings: F-Line, E-BLDG Wall Bracing: F-Line, E-BLDG Backfilt: F-Line, E-BLDG Backfilt: F-Line, E-BLDG Calssons: F-Line, K-BLDG Calssons: F-Line, K-BLDG	3 2 3 3 2 2 2 3 4 2 4 2 4 2	22MAY08A 10JUN08A 16JUN08A 07JUL08A 16SEP08A 28MAY08A 18JUN08A 07JUL08A 07JUL08A 25AUG08A 22SEP08A 24SEP08A 26MAY08A	23MAY08A 13JUN08A 17JUN08A 09JUL08A 07NOV08A 30MAY08A 20JUN08A 09JUL08A 28AUG08A 07NOV08A 07NOV08A 28MAY08A	30APR08 28APR08 21APR08 02MAY08 28APR08 21APR08 30APR08 08MAY08 02MAY08	01MAY08 29APR08 23APR08 06MAY08 29APR08 23APR08 01MAY08 09MAY08 07MAY08	0 -31 -35 -55 -133 0 -38 -55 -85 -130 -132 0	Icaissons: F-Line, C-BLDG IPerts: F-Line, C-BLDG IPerts: F-Line, C-BLDG Mail Bracing: F-Line, C-BLDG Caissons: F-Line, F-BLDG IFootings: F-Line, F-BLDG IPerts: F-Line, F-BLDG IPerts: F-Line, F-BLDG Mail Bracing: F-Line, F-BLDG IPerts: F-Line, F-BLDG Maisons: F-Line, F-BLDG Masons: F-Line, F-BLDG Masons: F-Line, K-BLDG ICaissons: F-Line, K-BLDG
0397 0577 0327 0317 0227 0367 0587 0297 0217 0307 0387 0367 0357 0597 0337	Calssons: F-Line, C-BLDG Piers: F-Line, C-BLDG Foolings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Galssons: F-Line, E-BLDG Foolings: F-Line, E-BLDG Wall Bracing: F-Line, E-BLDG Backfil: F-Line, E-BLDG Backfil: F-Line, E-BLDG Calssons: F-Line, V-BLDG Calssons: F-Line, V-BLDG	3 2 3 3 2 2 3 4 2 3 4 2 4 2 2 2	22MAY08A 10JUN08A 16JUN08A 07JUL08A 28MAY08A 18JUN08A 07JUL08A 25AUG08A 22SEP08A 24SEP08A 24SEP08A 20MAY08A	23MAY08A 13JUN08A 17JUN08A 09JUL08A 07NOV08A 30MAY08A 20JUN08A 09JUL08A 09JUL08A 07NOV08A 07NOV08A 07NOV08A 28MAY08A 23JUN08A	30APR08 28APR08 21APR08 02MAY08 28APR08 21APR08 30APR08 08MAY08 02MAY08 19MAY08	01MAY08 29APR08 23APR08 06MAY08 29APR08 29APR08 23APR08 01MAY08 09MAY08 09MAY08 20MAY08	0 -31 -35 -55 -133 0 -38 -55 -85 -130 -132 0 -24	ICalissons: F-Line, C-BLDG IPrets: F-Line, C-BLDG IFootings: F-Line, C-BLDG Ifootings: F-Line, C-BLDG Ifootings: F-Line, C-BLDG IFootings: F-Line, E-BLDG IFootings: F-Line, E-BLDG IPrets: F-Line, E-BLDG IPrets: F-Line, E-BLDG ISSUE: F-Line, V-BLDG IFootings: F-Line, V-BLDG
0397 0577 0327 0317 0227 0367 0297 0217 0307 0387 0387 0387 0357 0597 0337	Calissons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Masonry: F-Line, C-BLDG Calissons: F-Line, E-BLDG Footings: F-Line, E-BLDG Piers: F-Line, E-BLDG Backfill: F-Line, E-BLDG Backfill: F-Line, E-BLDG Calissons: F-Line, V-BLDG Footings: F-Line, V-BLDG Footings: F-Line, V-BLDG	3 2 3 3 2 2 3 4 2 3 4 2 2 4 2 2 2 2	22MAY08A 10JUN08A 16JUN08A 07JUL08A 28MAY08A 28MAY08A 18JUN08A 07JUL08A 25AUG08A 22SEP08A 24SEP08A 26MAY08A 20JUN08A 30JUN08A	23MAY08A 13JUN08A 17JUN08A 09JUL08A 07NOV08A 20JUN08A 20JUN08A 09JUL08A 28AUG08A 07NOV08A 07NOV08A 28MAY08A 22JUN08A 07JUL08A	30APR08 28APR08 21APR08 21APR08 28APR08 21APR08 30APR08 08MAY08 02MAY08 19MAY08 21MAY08	01MAY08 29APR08 23APR08 06MAY08 29APR08 23APR08 01MAY08 09MAY08 07MAY08 20MAY08 22MAY08	0 -31 -55 -133 0 -38 -55 -130 -132 0 -24 -32	ICaissons: F-Line, C-BLDG IPerty: F-Line, C-BLDG IFootings: F-Line, C-BLDG Mail Brading: F-Line, C-BLDG ICaissons: F-Line, F-BLDG ICaissons: F-Line, F-BLDG ICaissons: F-Line, F-BLDG ICaissons: F-Line, F-BLDG ICaissons: F-Line, F-BLDG ICaissons: F-Line, F-BLDG ICaissons: F-Line, WBLDG ICaissons: F-Line, W-BLDG ICaissons: F-Line, W-BLDG
0397 0577 0327 0317 0227 0367 0587 0297 0217 0307 0387 0367 0387 0597 0337 0347	Calssons: F-Line, C-BLDG Piers: F-Line, C-BLDG Foolings: F-Line, C-BLDG Wall Brancing: F-Line, C-BLDG Galssons: F-Line, E-BLDG Footings: F-Line, E-BLDG Wall Brachg: F-Line, E-BLDG Backfill: F-Line, E-BLDG Backfill: F-Line, E-BLDG Backfill: F-Line, E-BLDG Galssons: F-Line, W-BLDG Footings: F-Line, W-BLDG Wall Brachg: F-Line, W-BLDG	3 2 3 3 2 2 3 4 2 3 4 2 4 2 2 2	22MAY08A 10,UUN08A 16,UUN08A 07,UUL08A 185EP08A 28MAY08A 18,UUN08A 07,UU08A 25,AUG08A 22,SEP08A 24,SEP08A 24,SEP08A 24,SEP08A 26,MAY08A 20,UUN08A 07,UUN08A	23MAY08A 13JUN08A 17JUN08A 09JUL08A 07NOV08A 20JUN08A 20JUN08A 09JUL08A 07NOV08A 07NOV08A 07NOV08A 28M4Y08A 23JUN08A 07JUL08A 10JUL08A	30APR08 28APR08 21APR08 21APR08 202MAY08 28APR08 21APR08 30APR08 09MAY08 02MAY08 19MAY08 21MAY08 12MAY08	01MAY08 29APR08 23APR08 06MAY08 29APR08 23APR08 01MAY08 09MAY08 07MAY08 20MAY08 20MAY08 22MAY08 14MAY08	0 -31 -35 -55 -133 0 -38 -55 -85 -130 -132 0 -132 0 -24 -32 -41	Icaissons: F-Line, C-BLDG IPerts: F-Line, C-BLDG IFootings: F-Line, C-BLDG Mathematical Brading: F-Line, C-BLDG Caissons: F-Line, C-BLDG IFootings: F-Line, F-BLDG IFootings: F-Line, F-BLDG IPerts: F-Line, K-BLDG IElens: F-Line, K-BLDG IElens: F-Line, V-BLDD IElens: F-Line, V-BLDD
0397 0577 0327 0227 0367 0587 0297 0217 0367 0397 0367 0357 0357 0357 0357 0347 0347	Calssons: F-Line, C-BLDG Piers: F-Line, C-BLDG Foolings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Galssons: F-Line, E-BLDG Foolings: F-Line, E-BLDG Poolings: F-Line, E-BLDG Backfill: F-Line, E-BLDG Backfill: F-Line, E-BLDG Calssons: F-Line, W-BLDG Pooling: F-Line, W-BLDG Piers: F-Line, W-BLDG Piers: F-Line, W-BLDG Backfill: F-Line, W-BLDG Backfill: F-Line, W-BLDG	3 2 2 3 3 3 2 2 2 3 4 2 2 4 2 2 2 3 3 2 2	22MAY08A 10JUN08A 16JUN08A 07JUL08A 16SEP08A 28MAY08A 18JUN08A 07JUL08A 25AUG08A 22SEP08A 24SEP08A 24SEP08A 24SEP08A 20JUN08A 30JUN08A 10JUL08A	23MAY08A 13JUN08A 13JUN08A 09JUL08A 09JUL08A 20JUN08A 20JUN08A 09JUL08A 28AUG08A 07NOV08A 28AUG08A 07NOV08A 23JUN08A 07JUL08A 25JUL08A	30APR08 28APR08 21APR08 02MAY08 28APR08 21APR08 30APR08 08MAY08 19MAY08 19MAY08 21MAY08 21MAY08 21MAY08	01MAY08 29APR08 23APR08 23APR08 06MAY08 29APR08 23APR08 01MAY08 07MAY08 07MAY08 20MAY08 22MAY08 14MAY08 30MAY08	0 -31 -35 -55 -133 0 -38 -55 -85 -130 -132 0 -132 0 -24 -32 -41 -40	ICaissons: F-Line, C-BLDG IPers: F-Line, C-BLDG IFootings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG ICaissons: F-Line, C-BLDG IFootings: F-Line, E-BLDG IFootings: F-Line, E-BLDG IPers: F-Line, E-BLDG IDers: F-Line, E-BLDG IDers: F-Line, E-BLDG IDers: F-Line, E-BLDG IDers: F-Line, E-BLDG IDers: F-Line, V-BLDG IFooting: F-Line, V-BLDG IPers: F-Line, V-BLDG IDers: F-Line,
0397 0577 0327 0227 0367 0587 0297 0217 0307 0387 0387 0387 0387 0357 0397 0337 0397 0337 0407 0377	Calissons: F-Line, C-BLDG Piers: F-Line, C-BLDG Foolings: F-Line, C-BLDG Masonry: F-Line, C-BLDG Calissons: F-Line, E-BLDG Foolings: F-Line, E-BLDG Poolings: F-Line, E-BLDG Packfill: F-Line, E-BLDG Backfill: F-Line, E-BLDG Calissons: F-Line, W-BLDG Foolings: F-Line, W-BLDG Past-Fille, W-BLDG Masonry: F-Line, W-BLDG Backfill: F-Line, W-BLDG	3 2 3 3 2 2 3 4 2 3 4 2 2 4 2 2 2 2	22MAY08A 10,UUN08A 16,UUN08A 07,UUL08A 185EP08A 28MAY08A 18,UUN08A 07,UU08A 25,AUG08A 22,SEP08A 24,SEP08A 24,SEP08A 24,SEP08A 26,MAY08A 20,UUN08A 07,UUN08A	23MAY08A 13JUN08A 17JUN08A 09JUL08A 07NOV08A 20JUN08A 20JUN08A 09JUL08A 07NOV08A 07NOV08A 07NOV08A 28M4Y08A 23JUN08A 07JUL08A 10JUL08A	30APR08 28APR08 21APR08 02MAY08 28APR08 21APR08 30APR08 08MAY08 19MAY08 19MAY08 21MAY08 21MAY08 21MAY08	01MAY08 29APR08 23APR08 23APR08 06MAY08 29APR08 23APR08 01MAY08 07MAY08 07MAY08 20MAY08 22MAY08 14MAY08 30MAY08	0 -31 -35 -55 -133 0 -38 -55 -85 -130 -132 0 -132 0 -24 -32 -41 -40	ICaissons: F-Line, C-BLDG IPerts: F-Line, C-BLDG IPerts: F-Line, C-BLDG Wall Brading: F-Line, C-BLDG ICaissons: F-Line, C-BLDG IFootings: F-Line, F-BLDG IFootings: F-Line, F-BLDG IPerts: F-Line, K-BLDG IPerts: F-Line, W-BLDG IPerts: F-Line, W-BLDG
0397 0577 0327 0327 0227 0367 0297 0297 0297 0297 0387 0397 0387 0397 0337 0337 0347 0237 0407 9037 8045	Calssons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Calssons: F-Line, E-BLDG Colssons: F-Line, E-BLDG Wall Bracing: F-Line, E-BLDG Backfill: F-Line, E-BLDG Calssons: F-Line, V-BLDG Calssons: F-Line, W-BLDG Footings: F-Line, W-BLDG Piers: F-Line, V-BLDG Piers: F-Line, V-BLDG Backfill: F-Line, W-BLDG Backfill: F-Line, W-BLDG Backfill: F-Line, W-BLDG Masonry: F-Line, W-BLDG Masonry: F-Line, W-BLDG	3 2 2 3 3 2 2 2 3 3 4 2 2 4 2 2 2 3 3 2 2 4	22MAY08A 10JUN08A 16JUN08A 16JUN08A 16JUN08A 28MAY08A 16SEP08A 28MAY08A 7JUL08A 22SEP08A 24SEP08A 24SEP08A 24SEP08A 24SEP08A 20JUN08A 30JUN08A 10JUL08A 18NOV08A	23MAY08A 13,UIN08A 17,UIN08A 09,UIL08A 07NOV08A 20,UIN08A 22,UIN08A 28,AUG08A 07NOV08A 28,AUG08A 07NOV08A 23,UIN08A 07,UIN08A 23,UIN08A 23,UIN08A 23,UIN08A 23,UIN08A	30APR08 28APR08 21APR08 02MAY08 28APR08 21APR08 30APR08 08MAY08 02MAY08 21MAY08 21MAY08 22MAY08 23MAY08	01MAY08 29APR08 23APR08 06MAY08 29APR08 23APR08 07MAY08 07MAY08 07MAY08 20MAY08 20MAY08 14MAY08 30MAY08	0 -31 -35 -55 -133 0 -38 -55 -85 -130 -132 0 -24 -32 -41 -40 -132	ICalissons F-Line, C-BLDG IPerist: F-Line, C-BLDG IPerist: F-Line, C-BLDG Masony: F-Line, C-BLDG ICalissons: F-Line, F-BLDG IFactings: F-Line, E-BLDG IBress: F-Line, E-BLDG ICalissons: F-Line, E-BLDG ICalissons: F-Line, E-BLDG ICalissons: F-Line, E-BLDG ICalissons: F-Line, K-BLDG ICalissons: F-Line, WBLDG IFpotings: F-Line, WBLDG IFpotings: F-Line, WBLDG IMast Brading: F-Line, WBLDG IMasony: F-Line, WBLDG IMasony: F-Line, WBLDG
0397 0577 0327 0317 0227 0367 0297 0217 0307 0387 0357 0357 0357 0357 0337 0357 0337 0347 0237 0407 0237 0407 037 5oth Elevation 0177	Calissons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Masonry: F-Line, C-BLDG Calissons: F-Line, E-BLDG Footings: F-Line, E-BLDG Piers: F-Line, E-BLDG Backfill: F-Line, E-BLDG Calissons: F-Line, V-BLDG Footings: F-Line, V-BLDG Piers: F-Line, V-BL	3 2 2 3 3 2 2 2 3 4 4 2 2 4 2 2 3 3 2 2 4 4 5	22MAY08A 10JUN08A 115JUN08A 115JUN08A 116SEP08A 28MAY08A 25AUG08A 25AUG08A 25SEP08A 24SEP08A 24SEP08A 20JUN08A 07JUL08A 10JUL08A 115JUL08A 115JUL08A 115JUL08A 115JUL08A	23MAY08A 13JUN08A 17JUN08A 07NOV08A 07NOV08A 20JU08A 09JUL08A 28AUG08A 07NOV08A 28AUG08A 07NOV08A 23JUN08A 07JUL08A 10JUL08A 25JUL08A 25JUL08A 28NOV08A	30APR08 28APR08 21APR08 21APR08 28APR08 21APR08 30APR08 09MAY08 02MAY08 19MAY08 21MAY08 29MAY08 29MAY08 23MAY08 06AUG08	01MAY08 29APR08 23APR08 06MAY08 29APR08 07MAY08 07MAY08 07MAY08 20MAY08 22MAY08 14MAY08 30MAY08 28MAY08 14MAY08	0 -31 -35 -55 -133 0 -38 -55 -85 -130 -132 0 -132 0 -24 -32 -41 -40	ICaissons: F-Line, C-BLDG IPers:, F-Line, C-BLDG IProtings: F-Line, C-BLDG Mail Brans; F-Line, C-BLDG ICaissons: F-Line, E-BLDG ICaissons: F-Line, E-BLDG IFootings: F-Line, E-BLDG IPers: F-Line, E-BLDG IPers: F-Line, E-BLDG IEpers: F-Line, K-BLDG IEpers: F-Lin
0397 0577 0327 0327 0227 0367 0297 0297 0297 0297 0387 0397 0387 0397 0337 0337 0347 0237 0407 9037 8045	Calssons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Calssons: F-Line, E-BLDG Colssons: F-Line, E-BLDG Wall Bracing: F-Line, E-BLDG Backfill: F-Line, E-BLDG Calssons: F-Line, V-BLDG Calssons: F-Line, W-BLDG Footings: F-Line, W-BLDG Piers: F-Line, V-BLDG Piers: F-Line, V-BLDG Backfill: F-Line, W-BLDG Backfill: F-Line, W-BLDG Backfill: F-Line, W-BLDG Masonry: F-Line, W-BLDG Masonry: F-Line, W-BLDG	3 2 2 3 3 2 2 2 3 4 4 2 2 4 2 2 2 3 2 2 4 5 5 5	22MAY08A 10JUN08A 16JUN08A 16JUN08A 16JEP08A 16SEP08A 28MAY08A 22SEP08A 22SEP08A 24SEP08A 24SEP08A 24SEP08A 24SEP08A 24SEP08A 24SEP08A 20JUN08A 10JUL08A 10JUL08A 10JUL08A 10JUL08A 07JUL08A 07JUL08A	23MAY08A 13JUN08A 17JUN08A 09JUL08A 07NOV08A 30MAY08A 28AUG08A 07NOV08A 28AUG08A 07NOV08A 28AU708A 23JUN08A 10JUL08A 10JUL08A 15SEP08A 31JUL08A	30APR08 28APR08 21APR08 02MAY08 28APR08 21APR08 30APR08 08MAY08 02MAY08 21MAY08 21MAY08 22MAY08 23MAY08	01MAY08 29APR08 23APR08 23APR08 29APR08 23APR08 01MAY08 07MAY08 07MAY08 20MAY08 22MAY08 14MAY08 30MAY08 28MAY08 14MAY08 14MAY08 15JUL08	0 -31 -35 -55 -133 0 -38 -55 -85 -130 -132 0 -24 -32 -41 -40 -132 -24 -132	ICalissons: F-Line, C-BLDG IPerts: F-Line, C-BLDG IPerts: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Calissons: F-Line, C-BLDG IFootings: F-Line, F-BLDG IFootings: F-Line, F-BLDG IPerts: F-Line, K-BLDG IPerts: F-Line, V-BLDD IPerts: F-Line, V-BLDG IPerts: F-L
0397 0577 0327 0317 0227 0367 0297 0217 0367 0387 0387 0387 0387 0387 0397 0347 0337 0347 0237 0347 0237 0407 0377 5odt Elevation 0177 0197 East Elevation	Calssons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Matsong: F-Line, C-BLDG Calssons: F-Line, E-BLDG Colssons: F-Line, E-BLDG Wall Brachg: F-Line, E-BLDG Backfill: F-Line, E-BLDG Backfill: F-Line, K-BLDG Footings: F-Line, W-BLDG Footings: F-Line, W-BLDG Backfill F-Line, V-BLDG Backfill F-Line, V-BLDG	3 2 2 3 3 2 2 2 3 4 4 2 2 4 2 2 3 3 2 2 4 4 5	22MAY08A 10JUN08A 16JUN08A 07JUL08A 18SEP08A 23MAY08A 18JUN08A 07JUL08A 22SEP08A 22SEP08A 24SEP08A 24SEP08A 07JUL08A 07JUL08A 10JUL08A 10JUL08A 07JUL08A 07JUL08A 07JUL08A 07JUL08A 07JUL08A 07JUL08A 07JMY08A 07MAY08A	23MAY08A 13JUN08A 17JUN08A 07N0V08A 30MAY08A 20JUL08A 09JUL08A 09JUL08A 07N0V08A 07N0V08A 07N0V08A 07N0V08A 07N0V08A 07N0V08A 07JUL08A 07JUL08A 10JUL08A 28JUL08A 28JUL08A 28JUL08A 23JUL08A 15SEP08A 31JUL08A	30APR08 28APR08 21APR08 22MAY08 28APR08 21APR08 30APR08 08MAY08 20MAY08 21MAY08 21MAY08 21MAY08 23MAY08 23MAY08 06AUG08 09JUL08 24SEP08	01MAY08 29APR08 23APR08 06MAY08 09MAY08 09MAY08 07MAY08 07MAY08 20MAY08 20MAY08 30MAY08 30MAY08 14MAY08 14MAY08 12AUG08 15JUL08 30SEP08	0 -31 -35 -55 -133 0 -38 -55 -130 -132 0 -24 -32 -41 -40 -132 -24	ICaissons: F-Line, C-BLDG IPerts: F-Line, C-BLDG IPerts: F-Line, C-BLDG IPerts: F-Line, C-BLDG ICaissons: F-Line, C-BLDG ICaissons: F-Line, E-BLDG IFootings: F-Line, F-BLDG IPerts: F-Line, K-BLDG IPerts: F-Line, V-BLDG IPerts: F-Line, V-
0397 0577 0327 0317 0227 0267 0297 0217 0297 0217 0307 0387 0367 0367 0367 0367 0347 0337 0347 0347 0347 0347 0347 034	Calssons: F-Line, C-BLDG Piers: F-Line, C-BLDG Foolings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Calssons: F-Line, E-BLDG Collisons: F-Line, E-BLDG Wall Bracing: F-Line, E-BLDG Backfill: F-Line, E-BLDG Calssons: F-Line, W-BLDG Foolings: F-Line, W-BLDG Poolings: F-Line, W-BLDG Wall Bracing: F-Line, W-BLDG Backfill: F-Line, W-BLDG Backfill: F-Line, W-BLDG Backfill: F-Line, W-BLDG Backfill: F-Line, W-BLDG Backfill: F-Line, W-BLDG	3 2 2 3 3 2 2 2 3 4 4 2 2 4 2 2 2 3 2 2 4 5 5 5	22MAY08A 10JUN08A 16JUN08A 16JUN08A 16JEP08A 16SEP08A 28MAY08A 22SEP08A 22SEP08A 24SEP08A 24SEP08A 24SEP08A 24SEP08A 24SEP08A 24SEP08A 20JUN08A 10JUL08A 10JUL08A 10JUL08A 10JUL08A 07JUL08A 07JUL08A	23MAY08A 13JUN08A 17JUN08A 09JUL08A 07NOV08A 30MAY08A 28AUG08A 07NOV08A 28AUG08A 07NOV08A 28AU708A 23JUN08A 10JUL08A 10JUL08A 15SEP08A 31JUL08A	30APR08 30APR08 21APR08 21APR08 22APR08 21APR08 30APR08 02MAY08 02MAY08 21MAY08 21MAY08 21MAY08 21MAY08 21MAY08 22MAY08 06AU008 06AU008	01MAY08 29APR08 23APR08 23APR08 29APR08 23APR08 01MAY08 07MAY08 07MAY08 20MAY08 22MAY08 14MAY08 30MAY08 28MAY08 14MAY08 14MAY08 15JUL08	0 -31 -35 -55 -133 0 -38 -55 -85 -130 -132 0 -24 -32 -41 -40 -132 -24 -132	ICalissons: F-Line, C-BLDG IPerts: F-Line, C-BLDG IPerts: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Calissons: F-Line, C-BLDG IFootings: F-Line, F-BLDG IFootings: F-Line, F-BLDG IPerts: F-Line, K-BLDG IPerts: F-Line, V-BLDD IPerts: F-Line, V-BLDG IPerts: F-L
0397 0577 0327 0327 0367 0297 0217 0367 0367 0367 0367 0387 0367 0387 0397 0337 0347 0237 0407 0337 0407 0407 0407 0407 0407 04	Calissons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Masonry: F-Line, C-BLDG Gaissons: F-Line, E-BLDG Footings: F-Line, E-BLDG Pootings: F-Line, E-BLDG Pars: F-Line, E-BLDG Backfill: F-Line, E-BLDG Calissons: F-Line, W-BLDG Calissons: F-Line, W-BLDG Footings: F-Line, W-BLDG Backfill: F-Line, W-BLDG Backfill: F-Line, W-BLDG Backfill: F-Line, W-BLDG Backfill: F-Line, W-BLDG Backfill: Foundations: B-Line, E-BLDG Backfill: Foundations: B-Line, W-BLDG Backfill: Foundations: B-Line, W-BLDG Backfill: Foundations: B-Line, W-BLDG Backfill Foundations: B-Line, W-BLDG Backfill Foundations: B-Line, W-BLDG Backfill Foundations: D-Line, K-BLDG Backfill Foundations: D-Line, K-BLDG Backfill Foundations: D-Line, K-BLDG Backfill Foundations: D-Line, K-BLDG	3 2 2 3 3 2 2 3 4 4 2 2 2 2 3 3 2 2 4 5 5 5 5 3	22MAY08A 10JUN08A 10JUN08A 10JUN08A 07JUL08A 18SEP08A 23MAY08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 23MAY08A 23JUN08A 07JUL08A 10JUL08A 10JUL08A 10JUL08A 10JUL08A 10JUL08A 10JUL08A 10JUL08A 11MAY08A 09MAY08A 18SEP08A	23MAY08A 13JUN08A 13JUN08A 09JUL08A 07NOV08A 30MAY08A 20JUN08A 03JUL08A 20JUN08A 03JUL08A 28JUN08A 07NOV08A 07NOV08A 27NOV08A 23JUN08A 07NOV08A 10JUL08A 23JUN08A 10JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A	30APR08 28APR08 21APR08 02MAY08 28APR08 21APR08 30APR08 08MAY08 21MAY08 21MAY08 21MAY08 23MAY08 23MAY08 06AUG08 09JUL08 24SEP08 25AUG08	01MAY08 29APR08 23APR08 06MAY08 23APR08 01MAY08 07MAY08 07MAY08 07MAY08 20MAY08 20MAY08 20MAY08 22MAY08 14MAY08 30MAY08 12AUG08	0 -31 -35 -55 -133 0 -38 -55 -130 -132 0 -24 -32 -41 -132 -24 -132 -24 -12 41 -18	ICaissons: F-Line, C-BLDG IPeter: F-Line, C-BLDG IPeter: F-Line, C-BLDG IVali Bracing: F-Line, C-BLDG ICaissons: F-Line, E-BLDG ICaissons: F-Line, E-BLDG IFootings: F-Line, I-BLDG IPeter: F-Line, V-BLDG IPeter: F-L
0397 0577 0327 0327 0367 0587 0297 0307 0357 0597 0357 0597 0337 0347 0347 0237 0347 0347 0347 0347 0407 0377 0407 0377 0407 0377 0407 040	Calssons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Calssons: F-Line, E-BLDG Colssons: F-Line, E-BLDG Pootings: F-Line, E-BLDG Backfill: F-Line, E-BLDG Colssons: F-Line, W-BLDG Colssons: F-Line, W-BLDG Pootings: F-Line, W-BLDG Pooting: F-Line, W-BLDG Backfill: F-Line, W-BLDG	3 2 2 3 3 2 2 2 3 4 4 2 2 2 2 3 3 2 2 4 4 5 5 5 5	22MAY08A 10JUN08A 16JUN08A 07JUL08A 18SEP08A 23MAY08A 18JUN08A 07JUL08A 22SEP08A 22SEP08A 24SEP08A 24SEP08A 07JUL08A 07JUL08A 10JUL08A 10JUL08A 07JUL08A 07JUL08A 07JUL08A 07JUL08A 07JUL08A 07JUL08A 07JMY08A 07MAY08A	23MAY08A 13JUN08A 17JUN08A 07N0V08A 30MAY08A 20JUL08A 09JUL08A 09JUL08A 07N0V08A 07N0V08A 07N0V08A 07N0V08A 07N0V08A 07N0V08A 07JUL08A 07JUL08A 10JUL08A 28JUL08A 28JUL08A 28JUL08A 23JUL08A 15SEP08A 31JUL08A	30APR08 28APR08 21APR08 22MAY08 28APR08 21APR08 30APR08 08MAY08 20MAY08 21MAY08 21MAY08 21MAY08 23MAY08 23MAY08 06AUG08 09JUL08 24SEP08	01MAY08 29APR08 23APR08 06MAY08 09MAY08 09MAY08 07MAY08 07MAY08 20MAY08 20MAY08 30MAY08 30MAY08 14MAY08 14MAY08 12AUG08 15JUL08 30SEP08	0 -31 -35 -55 -133 0 -38 -55 -130 0 -132 0 -24 -32 -41 -40 -132 -24 -12 -41	ICaissons: F-Line, C-BLDG IPeter: F-Line, C-BLDG IPeter: F-Line, C-BLDG IVali Bracing: F-Line, C-BLDG ICaissons: F-Line, E-BLDG ICaissons: F-Line, E-BLDG IFootings: F-Line, I-BLDG IPeter: F-Line, V-BLDG IPeter: F-L
0397 0577 0327 0327 0367 0587 0297 0307 0357 0597 0357 0597 0337 0347 0347 0237 0347 0347 0347 0347 0407 0377 0407 0377 0407 0377 0407 040	Calssons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Calssons: F-Line, E-BLDG Colssons: F-Line, E-BLDG Pootings: F-Line, E-BLDG Backfill: F-Line, E-BLDG Colssons: F-Line, W-BLDG Colssons: F-Line, W-BLDG Pootings: F-Line, W-BLDG Pooting: F-Line, W-BLDG Backfill: F-Line, W-BLDG	3 2 2 3 3 2 2 3 4 4 2 2 2 2 3 3 2 2 4 5 5 5 5 3	22MAY08A 10JUN08A 10JUN08A 10JUN08A 07JUL08A 18SEP08A 23MAY08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 23MAY08A 23JUN08A 07JUL08A 10JUL08A 10JUL08A 10JUL08A 10JUL08A 10JUL08A 10JUL08A 10JUL08A 11MAY08A 09MAY08A 18SEP08A	23MAY08A 13JUN08A 13JUN08A 09JUL08A 07NOV08A 30MAY08A 20JUN08A 03JUL08A 20JUN08A 03JUL08A 28JUN08A 07NOV08A 07NOV08A 27NOV08A 23JUN08A 07NOV08A 10JUL08A 23JUN08A 10JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A	30APR08 28APR08 21APR08 02MAY08 28APR08 21APR08 30APR08 08MAY08 21MAY08 21MAY08 21MAY08 23MAY08 23MAY08 06AUG08 09JUL08 24SEP08 25AUG08	01MAY08 29APR08 23APR08 06MAY08 23APR08 01MAY08 07MAY08 07MAY08 07MAY08 20MAY08 20MAY08 20MAY08 22MAY08 14MAY08 30MAY08 12AUG08	0 -31 -35 -55 -133 0 -38 -55 -130 -132 0 -24 -32 -41 -132 -24 -132 -24 -12 41 -18	ICaissons: F-Line, C-BLDG IPeter: F-Line, C-BLDG IPeter: F-Line, C-BLDG IVali Bracing: F-Line, C-BLDG ICaissons: F-Line, E-BLDG ICaissons: F-Line, E-BLDG IFootings: F-Line, I-BLDG IPeter: F-Line, V-BLDG IPeter: F-L
0397 0577 0327 0327 0367 0587 0297 0307 0357 0597 0357 0597 0337 0347 0347 0237 0347 0347 0347 0347 0407 0377 0407 0377 0407 0377 0407 040	Calssons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Calssons: F-Line, E-BLDG Colssons: F-Line, E-BLDG Pootings: F-Line, E-BLDG Backfill: F-Line, E-BLDG Colssons: F-Line, W-BLDG Colssons: F-Line, W-BLDG Pootings: F-Line, W-BLDG Pooting: F-Line, W-BLDG Backfill: F-Line, W-BLDG	3 2 2 3 3 2 2 3 4 4 2 2 2 2 3 3 2 2 4 5 5 5 5 3	22MAY08A 10JUN08A 10JUN08A 10JUN08A 07JUL08A 18SEP08A 23MAY08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 23MAY08A 23JUN08A 07JUL08A 10JUL08A 10JUL08A 10JUL08A 10JUL08A 10JUL08A 10JUL08A 10JUL08A 11MAY08A 09MAY08A 18SEP08A	23MAY08A 13JUN08A 13JUN08A 09JUL08A 07NOV08A 30MAY08A 20JUN08A 03JUL08A 20JUN08A 03JUL08A 28JUN08A 07NOV08A 07NOV08A 27NOV08A 23JUN08A 07NOV08A 10JUL08A 23JUN08A 10JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A	30APR08 28APR08 21APR08 02MAY08 28APR08 21APR08 30APR08 08MAY08 21MAY08 21MAY08 21MAY08 23MAY08 23MAY08 06AUG08 09JUL08 24SEP08 25AUG08	01MAY08 29APR08 23APR08 06MAY08 23APR08 01MAY08 07MAY08 07MAY08 07MAY08 20MAY08 20MAY08 20MAY08 22MAY08 14MAY08 30MAY08 12AUG08	0 -31 -35 -55 -133 0 -38 -55 -130 -132 0 -24 -32 -41 -132 -24 -132 -24 -12 41 -18	ICaissons: F-Line, C-BLDG IPerts: F-Line, C-BLDG IPerts: F-Line, C-BLDG IPerts: F-Line, C-BLDG ICaissons: F-Line, C-BLDG ICaissons: F-Line, E-BLDG IFootings: F-Line, F-BLDG IPerts: F-Line, K-BLDG IPerts: F-Line, V-BLDG IPerts: F-Line, V-
0397 0577 0327 0327 0367 0587 0297 0217 0307 0387 0397 0397 0397 0397 0397 0397 0397 039	Calssons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Calssons: F-Line, E-BLDG Colssons: F-Line, E-BLDG Pootings: F-Line, E-BLDG Backfill: F-Line, E-BLDG Colssons: F-Line, W-BLDG Colssons: F-Line, W-BLDG Pootings: F-Line, W-BLDG Pootings: F-Line, W-BLDG Backfill: F-Line,	3 2 2 3 3 2 2 2 3 4 4 2 2 2 3 4 4 2 2 2 3 5 5 5 5 5 5 3 3	22MAY08A 10JUN08A 10JUN08A 10JUN08A 77JUL08A 28MAY08A 28MAY08A 28AJ06A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 20JUN08A 07JUL08A 10JU	23MAY08A 13JUN08A 13JUN08A 09JUL08A 07NOV08A 30MAY08A 20JUN08A 03JUL08A 20JUN08A 03JUL08A 28JUN08A 07NOV08A 07NOV08A 27NOV08A 23JUN08A 07NOV08A 10JUL08A 23JUN08A 10JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A	30APR08 28APR08 21APR08 02MAY08 21APR08 21APR08 30APR08 03MAY08 02MAY08 21MAY08 21MAY08 23MAY08 23MAY08 06AUG08 06AUG08 05JUL68 24SEP08 25AUG08 13OCT08	01MAY08 29APR08 23APR08 06MAY08 23APR08 01MAY08 07MAY08 07MAY08 07MAY08 20MAY08 20MAY08 20MAY08 22MAY08 14MAY08 30MAY08 12AUG08	0 -31 -35 -55 -133 0 -38 -55 -85 -130 -132 -132 -41 -132 -132 -132 -132 -132 -132 -132 -13	ICaissons: F-Line, C-BLDG IPerts: F-Line, C-BLDG IPerts: F-Line, C-BLDG IPerts: F-Line, C-BLDG ICaissons: F-Line, C-BLDG ICaissons: F-Line, E-BLDG IFootings: F-Line, F-BLDG IPerts: F-Line, K-BLDG IPerts: F-Line, V-BLDG IPerts: F-Line, V-
0397 0577 0327 0317 0227 0367 0297 0297 0297 0297 0307 0387 0387 0367 0367 0367 0367 0347 0347 0337 0347 0347 0347 0337 0347 0377 0347 0407 040	Calissons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Masonry: F-Line, C-BLDG Colissons: F-Line, E-BLDG Footings: F-Line, E-BLDG Piers: F-Line, E-BLDG Backtill F-Line, E-BLDG Calissons: F-Line, W-BLDG Footings: F-Line, W-BLDG Piers: F-Line, W-BLDG Piers: F-Line, W-BLDG Backtill Foundations: B-Line, C-BLDG Backtill Foundations: B-Line, K-BLDG Backtill Foundations: B-Line, K-BLD	3 2 2 3 3 2 2 2 3 4 2 2 2 2 2 2 3 3 2 2 4 4 5 5 5 5 3 3 3 3 0 0	22MAY08A 10JUN08A 10JUN08A 10JUN08A 16JUN08A 27JUL08A 18JUN08A 25AUG08A 225EP08A 225EP08A 225EP08A 245EP08A 245EP08A 23JUN08A 07JUL08A 18NOV08A 07JMV08A 07JMV08A 18NOV08A 18SEP08A 09JUN08A	23MAY08A 13JUN08A 17JUN08A 09JUL08A 07NOV08A 20JUN08A 20JUN08A 20JUN08A 28AUG08A 28AUG08A 28AUG08A 28AUG08A 23JUL08A 23JUL08A 23JUL08A 23JUL08A 23JUL08A 23JUL08A 23JUL08A 22JUL08A 22JUL08A 22JUL08A 22JUL08A 22JUL08A 23JUL08A	30APR08 28APR08 21APR08 21APR08 28APR08 21APR08 30APR08 08M4Y08 21APR08 21APR08 21APR08 21APR08 23MAY08 23MAY08 23MAY08 23MAY08 23MAY08 24SEP08 24SEP08 25AUG08 13OCT08	01MAY08 29APR08 23APR08 23APR08 29APR08 23APR08 01MAY08 09MAY08 07MAY08 20MAY08 22MAY08 14MAY08 22MAY08 14MAY08 28MAY08 12AUG08 15JUL08 30SEP08 27AUG08 15OCT08	0 -31 -35 -55 -133 0 -38 -55 -130 0 -24 -32 0 -132 0 -24 -132 -24 -132 -24 -12 -12 41 -18 -6 -6 -18	ICaissons: F-Line, C-BLDG IPerts: F-Line, C-BLDG IPerts: F-Line, C-BLDG IPerts: F-Line, C-BLDG ICaissons: F-Line, C-BLDG ICaissons: F-Line, E-BLDG IFootings: F-Line, F-BLDG IPerts: F-Line, K-BLDG IPerts: F-Line, V-BLDG IPerts: F-Line, V-
0397 0577 0327 0327 0327 0327 0297 0367 0297 0367 0367 0367 0367 0367 0367 0367 036	Calissons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Masonry: F-Line, C-BLDG Gaissons: F-Line, E-BLDG Pootings: F-Line, E-BLDG Pootings: F-Line, E-BLDG Pars: F-Line, E-BLDG Backfill F-Line, E-BLDG Calissons: F-Line, W-BLDG Calissons: F-Line, W-BLDG Pootings: F-Line, W-BLDG Backfill F-Line, V-BLDG Backfill F-Line	3 2 2 3 3 2 2 2 3 4 2 2 2 3 4 2 2 2 3 5 5 5 5 5 3 3 3 3 7 1*	22MAY08A 10JUN08A 10JUN08A 10JUN08A 07JUL08A 18SEP08A 28MAY08A 22SEP08A 22SEP08A 22SEP08A 23SUR08A 23UN08A 07JUL08A 07JUL08A 07JUL08A 07JUL08A 07JUL08A 07JUL08A 07JUL08A 18NOV08A 07MAY08A 09MAY08A 18SEP08A 18SEP08A	23MAY08A 13JUN08A 13JUN08A 09JUL08A 07N0V08A 30MAY08A 20JUN08A 09JUL08A 20JUN08A 20JUN08A 07N0V08A 07N0V08A 27N0V08A 27N0V08A 23JUN08A 07N0V08A 23JUN08A 07N0V08A 10JUL08A 25JUL08A 22J	30APR08 28APR08 21APR08 21APR08 21APR08 21APR08 30APR08 20MAY08 09MAY08 12MAY08 12MAY08 12MAY08 23MAY08 09JUL08 24SEP08 25AUG08 13OCT08 14MAY08	01MAY08 29APR08 23APR08 23APR08 23APR08 23APR08 09MAY08 20MAY08 20MAY08 20MAY08 20MAY08 20MAY08 22MAY08 14MAY08 30MAY08 22MAY08 15JUL08 27AUG08 15OCT08	0 -31 -35 -55 -133 0 -38 -55 -85 -130 0 -24 -32 0 -24 -32 -24 -132 -132 0 -24 -132 -132 -132 -132 -132 -132 -132 -132	ICaissons: F-Line, C-BLDG IPeter: F-Line, C-BLDG IPeter: F-Line, C-BLDG IVali Bracing: F-Line, C-BLDG ICaissons: F-Line, E-BLDG ICaissons: F-Line, E-BLDG IFootings: F-Line, I-BLDG IPeter: F-Line, V-BLDG IPeter: F-L
0.097 0.6577 0.0577 0.027 0.027 0.0367 0.0367 0.0367 0.0377 0.0277 0.0287 0	Calissons: F-Line, C-BLDG Prers: F-Line, C-BLDG Frodings: F-Line, C-BLDG Masonry: F-Line, C-BLDG Colissons: F-Line, E-BLDG Colissons: F-Line, E-BLDG Prers: F-Line, E-BLDG Backfill: F-Line, E-BLDG Masonry: F-Line, E-BLDG Calissons: F-Line, W-BLDG Fordings: F-Line, W-BLDG Press: F-Line, W-BLDG Backfill: Foundations: A-Line, C-BLDG Backfill Foundations: A-Line, W-BLDG Backfill Foundations: 28-31 Lines, W-BLDG Structural Steel: C-BLDG Structural Steel: W-BLDG	3 2 2 3 3 2 2 3 4 2 2 3 4 2 2 3 2 2 4 4 5 5 5 5 3 3 3 0 71* 54*	22MAY08A 10JUN08A 10JUN08A 10JUN08A 7JUL08A 28MAY08A 28MAY08A 28MAY08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 20JUN08A 07JUL08A 118NOV08A 07JUL08A 18NOV08A 118JUL08A 18SEP08A 09JUN08A 09JUN08A 09JUN08A	23MAY08A 13/UN08A 17/UN08A 09/UL08A 07/NOV08A 07/NOV08A 07/NOV08A 07/NOV08A 07/NOV08A 07/NOV08A 07/NOV08A 07/NOV08A 07/NOV08A 07/UL08A 07/	30APR08 28APR08 21APR08 21APR08 02MAY08 30APR08 30APR08 30APR08 08MAY08 21APR08 21APR08 21APR08 21APR08 21APR08 21APR08 23MAY08 08AU008 09JUL08 25AU308 13OCT08 14MAY08 14MAY08	01MAY08 29APR08 23APR08 23APR08 29APR08 29APR08 23APR08 01MAY08 09MAY08 22MAY08 22MAY08 14MAY08 22MAY08 14MAY08 28MAY08 15JUL08 30SEP08 27AUG08 15OCT08	0 -31 -35 -55 -133 0 -133 0 -132 0 -132 0 -132 0 -132 -24 -132 -24 -132 -132 -24 -132 -132 -132 -132 -32 -32 -32 -32 -32 -32 -32 -32 -32 -	ICaissons: F-Line, C-BLDG IPeter: F-Line, C-BLDG IPeter: F-Line, C-BLDG IVali Bracing: F-Line, C-BLDG ICaissons: F-Line, E-BLDG ICaissons: F-Line, E-BLDG IFootings: F-Line, I-BLDG IPeter: F-Line, V-BLDG IPeter: F-L
0397 0577 0577 0327 0327 0327 0327 0327 0367 0367 0367 0367 0367 0367 0367 036	Calissons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Masonry: F-Line, C-BLDG Calissons: F-Line, E-BLDG Footings: F-Line, E-BLDG Piers: F-Line, E-BLDG Backtill: F-Line, E-BLDG Calissons: F-Line, V-BLDG Piers: F-Line, V-BLDG Piers: F-Line, V-BLDG Piers: F-Line, V-BLDG Backtill: Foundations: B-Line, E-BLDG Backtill: Foundations: B-Line, C-BLDG Backtill: Foundations: B-Line, V-BLDG Backtill: Foundations: B-Line, V-BLDG Backtill: Foundations: B-Line, V-BLDG Backtill: Foundations: B-Line, C-BLDG Backtill: Foundations: B-Line, C-BLDG Backtill: Foundations: B-Line, C-BLDG Backtill: Foundations: B-Line, C-BLDG Backtill: Foundations: B-Line, V-BLDG Steel Start Structural Steel: C-BLDG Steel Erection Complete	3 2 2 3 3 2 2 3 3 2 2 4 4 2 2 2 3 3 2 2 4 4 5 5 5 5 3 3 3 3 0 71* 54* 42* 0	22MAY08A 10JUN08A 10JUN08A 10JUN08A 10JUN08A 27JUL08A 18SEP08A 23MAY08A 25AUG08A 22SEP08A 24SEP08A 24SEP08A 24SEP08A 23JUN08A 07JUL08A 07JUL08A 18NOV08A 07MAY08A 07MAY08A 07MAY08A 08MAY08A 18SEP08A 18SEP08A	23MAY08A 13,UN08A 17,UN08A 09,UL08A 07NOV08A 07NOV08A 20,UN08A 20,UN08A 20,UN08A 20,UN08A 20,UN08A 20,UN08A 27,NOV08A 27,NOV08A 27,NOV08A 23,UN08A 24,UN08A 23,UN08A 24,UN08A 24,UN08A 24,UN08A 24,UN08A 24,UN08A 24,UN08A 24,UN08A 24,UN08A 24,UN08A 24,UN08A 24,UN08A 24,UN08A 24,UN08A 24,UN08A 24,UN08A 24,UN08A 24,UN08A	30APR08 28APR08 21APR08 21APR08 02MAY08 30APR08 30APR08 30APR08 08MAY08 21APR08 21APR08 21APR08 21APR08 21APR08 21APR08 23MAY08 08AU008 09JUL08 25AU308 13OCT08 14MAY08 14MAY08	01MAY08 29APR08 23APR08 08MAY08 29APR08 23APR08 01MAY08 09MAY08 20MAY08 20MAY08 20MAY08 20MAY08 20MAY08 14MAY08 30MAY08 12AUG08 15JUL08 15JUL08 27AUG08 15OCT08	0 -31 -35 -555 -133 0 -38 -555 -855 -855 -130 -132 0 -24 -32 -41 -132 -24 -132 -132 -24 -112 -118 -6 -6 -18 -34 10 -14 15	Caissons: F-Line, C-BLDG IPrets: F-Line, C-BLDG IProtings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Caissons: F-Line, C-BLDG ICcaissons: F-Line, E-BLDG IFootings: F-Line, F-BLDG IPrets: F-Line, K-BLDG IPrets: F-
0397 0577 0577 0377 0327 0367 0567 0227 0227 0227 0367 0378 0379	Calissons: F-Line, C-BLDG Piers: F-Line, C-BLDG Fiers: F-Line, C-BLDG Masonry: F-Line, C-BLDG Calissons: F-Line, F-BLDG Gaissons: F-Line, F-BLDG Pooting: F-Line, F-BLDG Pooting: F-Line, F-BLDG Backfill F-Line, F-BLDG Calissons: F-Line, W-BLDG Calissons: F-Line, W-BLDG Calissons: F-Line, W-BLDG Pooting: F-Line, W-BLDG Backfill F-Dundations: B-Line, E-BLDG Backfill F-Dundations: B-Line, C-BLDG Backfill F-Dundations: B-Line, W-BLDG Backfill F-Dundations: B-BLDG Backfill F-DUNDA Backfill F-DUNDA Backfill F-DUNDA Backfill F-DUNDA Backfill F-DUNDA Backfill F-DUNDA Backfill F-DUNDA Backfi	3 2 2 3 3 2 2 3 3 4 2 2 2 3 4 2 2 2 3 2 2 4 4 2 2 3 3 2 4 5 5 5 5 3 3 3 3 0 71° 54* 4 2 2 2 3 2 2 3 3 4 2 2 2 3 3 3 2 2 2 3 3 3 2 2 2 3 3 3 2 2 2 3 3 3 2 2 2 3 3 3 2 2 2 3 3 3 3 2 2 2 3 3 3 2 2 2 3 3 3 3 2 2 2 2 3 3 3 2 2 2 2 3 3 3 2 2 2 2 3 3 3 2 2 2 2 3 3 3 2 2 2 2 3 3 3 2 2 2 2 3 3 3 2 2 2 2 3 3 3 2 2 2 2 3 3 3 2 2 2 2 3 3 3 2 2 2 2 3 3 3 2 2 2 2 3 3 2 2 2 3 3 3 2 2 2 2 3 3 3 2 2 2 3 3 3 2 2 3 3 3 3 2 2 2 3 3 3 3 2 2 2 3 3 2 2 3 3 3 3 3 3 2 2 2 3	22MAY08A 10JUN08A 10JUN08A 10JUN08A 07JUL08A 18SEP08A 23MAY08A 18JUN08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 23MAY08A 23JUN08A 07JUL08A 07JUL08A 07JUL08A 07JUL08A 07JUL08A 07JUL08A 18SEP08A 18SEP08A 18SEP08A 18JUN08A 09JUN08A	23MAY08A 13JUN08A 13JUN08A 09JUL08A 07NOV08A 30MAY08A 20JUN08A 09JUL08A 20JUN08A 20JUN08A 23JUN08A 27NOV08A 77NOV08A 27NOV08A 23JUN08A 10JUL08A 23JUN08A 10JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 25JUL08A 23JOCT08A	30APR08 28APR08 21APR08 21APR08 02MAY08 30APR08 30APR08 30APR08 08MAY08 21APR08 21APR08 21APR08 21APR08 21APR08 21APR08 23MAY08 08AU008 09JUL08 25AU308 13OCT08 14MAY08 14MAY08	01MAY08 29APR08 23APR08 08MAY08 29APR08 23APR08 01MAY08 09MAY08 20MAY08 20MAY08 20MAY08 20MAY08 20MAY08 14MAY08 30MAY08 12AUG08 15JUL08 15JUL08 27AUG08 15OCT08	0 -31 -35 -55 -133 0 -38 -85 -130 -132 0 -132 -24 -24 -32 -41 -132 -132 -132 -132 -132 -132 -132 -13	Caissons: F-Line, C-BLDG IPrets: F-Line, C-BLDG IProtings: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Caissons: F-Line, C-BLDG ICcaissons: F-Line, E-BLDG IFootings: F-Line, F-BLDG IPrets: F-Line, K-BLDG IPrets: F-
0397 0577 0577 0327 0327 0327 0327 0327 0367 0367 0367 0367 0367 0367 0367 036	Calissons: F-Line, C-BLDG Piers: F-Line, C-BLDG Footings: F-Line, C-BLDG Masonry: F-Line, C-BLDG Calissons: F-Line, E-BLDG Footings: F-Line, E-BLDG Piers: F-Line, E-BLDG Backtill: F-Line, E-BLDG Calissons: F-Line, V-BLDG Piers: F-Line, V-BLDG Piers: F-Line, V-BLDG Piers: F-Line, V-BLDG Backtill: Foundations: B-Line, E-BLDG Backtill: Foundations: B-Line, C-BLDG Backtill: Foundations: B-Line, V-BLDG Backtill: Foundations: B-Line, V-BLDG Backtill: Foundations: B-Line, V-BLDG Backtill: Foundations: B-Line, C-BLDG Backtill: Foundations: B-Line, C-BLDG Backtill: Foundations: B-Line, C-BLDG Backtill: Foundations: B-Line, C-BLDG Backtill: Foundations: B-Line, V-BLDG Steel Start Structural Steel: C-BLDG Steel Erection Complete	3 2 2 3 3 2 2 3 3 2 2 4 4 2 2 2 3 3 2 2 4 4 5 5 5 5 3 3 3 3 0 71* 54* 42* 0	22MAY08A 10JUN08A 10JUN08A 10JUN08A 10JUN08A 27JUL08A 18SEP08A 23MAY08A 25AUG08A 22SEP08A 24SEP08A 24SEP08A 24SEP08A 23JUN08A 07JUL08A 07JUL08A 18NOV08A 07MAY08A 07MAY08A 07MAY08A 08MAY08A 18SEP08A 18SEP08A	23MAY08A 13,UN08A 17,UN08A 09,UL08A 07NOV08A 07NOV08A 20,UN08A 20,UN08A 20,UN08A 20,UN08A 20,UN08A 20,UN08A 27,NOV08A 27,NOV08A 27,NOV08A 23,UN08A 23,UN08A 23,UN08A 23,UN08A 23,UN08A 23,UN08A 24,U008A 22,SEP08A 23,OCT08A 15,SEP08A 23,OSEP08A 23,SEP08A 23,SEP08A	30APR08 28APR08 21APR08 21APR08 02MAY08 30APR08 30APR08 30APR08 08MAY08 21APR08 21APR08 21APR08 21APR08 21APR08 21APR08 23MAY08 08AU008 09JUL08 25AU308 13OCT08 14MAY08 14MAY08	01MAY08 29APR08 23APR08 08MAY08 29APR08 23APR08 01MAY08 09MAY08 20MAY08 20MAY08 20MAY08 20MAY08 20MAY08 14MAY08 30MAY08 12AUG08 15JUL08 15JUL08 27AUG08 15OCT08	0 -31 -35 -555 -133 0 -38 -555 -855 -855 -130 -132 0 -24 -32 -41 -132 -24 -132 -132 -24 -112 -118 -6 -6 -18 -34 10 -14 15	ICaissons: F-Line, C-BLDG IPeter: F-Line, C-BLDG IPeter: F-Line, C-BLDG IVali Bracing: F-Line, C-BLDG ICaissons: F-Line, E-BLDG ICaissons: F-Line, E-BLDG IFootings: F-Line, I-BLDG IPeter: F-Line, V-BLDG IPeter: F-L
0397 0577 0577 0377 0377 0367 0567 0227 0227 0227 0227 0367 0378 0378	Calissons: F-Line, C-BLDG Piers: F-Line, C-BLDG Fronting: F-Line, C-BLDG Masonry: F-Line, C-BLDG Calissons: F-Line, E-BLDG Calissons: F-Line, E-BLDG Piers: F-Line, E-BLDG Backfill: F-Line, E-BLDG Calissons: F-Line, W-BLDG Calissons: F-Line, W-BLDG Piers: F-Line, W-BLDG Piers: F-Line, W-BLDG Backfill: Foundations: B-Line, E-BLDG Backfill: Foundations: B-Line, W-BLDG Backfill: Foundations: B-Line, W-BLDG Backfill: Foundations: B-Line, W-BLDG Backfill: Foundations: B-Line, W-BLDG Backfill: Foundations: B-Line, W-BLDG Structural Steel: C-BLDG Structural Steel: C-BLDG Steel Start Structural Steel: C-BLDG Steel Start Steel Start Steel Start Steel Start Steel Start Steel Start Steel Start Steel Start Steel Steel Steel Steel St	3 2 2 3 3 2 2 2 3 4 2 2 2 3 4 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 2 3 3 2 2 2 2 3 3 2 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 3 3 2 2 3 3 2 2 4 4 4 5 5 5 5 5 5 5 5 5 5 5 5 5	22MAY08A 10JUN08A 10JUN08A 10JUN08A 7JUL08A 18SEP08A 23MAY08A 23AU308AU308A 23AU308A 23AU308A 23AU308A 23AU308A 23AU308A 23AU308A	23MAY08A 13,UIN08A 17,UIN08A 09,UIL08A 07NOY08A 07NOY08A 20,UIN08A 20,UIN08A 20,UIN08A 20,UIN08A 28,UIL08A 28,UIL08A 28,UIL08A 23,UIL08A 23,UIL08A 23,UIL08A 23,UIL08A 25,UIL08A 25,UIL08A 22,SEP08A 23,OCT08A 23,OCT08A 23,OCT08A 23,SEP08A 27,UIN08A 17,JUL08A	30APR08 28APR08 21APR08 21APR08 02MAY08 30APR08 30APR08 30APR08 08MAY08 21APR08 21APR08 21APR08 21APR08 21APR08 21APR08 23MAY08 08AU008 09JUL08 25AU308 13OCT08 14MAY08 14MAY08	01MAY08 29APR08 23APR08 08MAY08 29APR08 23APR08 01MAY08 09MAY08 20MAY08 20MAY08 20MAY08 20MAY08 20MAY08 14MAY08 30MAY08 12AUG08 15JUL08 15JUL08 27AUG08 15OCT08	0 -31 -35 -55 -133 0 -38 -55 -38 -55 -330 0 -24 -132 0 -132 0 -232 -41 -41 -132 -132 -132 -132 -132 -132 -132 -13	ICaissons: F-Line, C-BLDG IPeter: F-Line, C-BLDG IPeter: F-Line, C-BLDG IVali Bracing: F-Line, C-BLDG ICaissons: F-Line, E-BLDG ICaissons: F-Line, E-BLDG IFootings: F-Line, I-BLDG IPeter: F-Line, V-BLDG IPeter: F-L
0397 0577 0577 0327 0327 0327 0367 0587 0227 0227 0237 0367 0367 0367 0367 0367 0367 0367 0367 0367 0367 0467 0377 0407 0478 04788 04788 04788 04788 04788 04788 04788 04788 04788 047	Calissons: F-Line, C-BLDG Prers: F-Line, C-BLDG Fronting: F-Line, C-BLDG Masonny: F-Line, C-BLDG Collissons: F-Line, E-BLDG Galssons: F-Line, E-BLDG Prers: F-Line, E-BLDG Masonry: F-Line, E-BLDG Masonry: F-Line, E-BLDG Masonry: F-Line, W-BLDG Footings: F-Line, W-BLDG Press: F-Line, W-BLDG Masonry: F-Line, W-BLDG Backfill Foundations: B-Line, K-BLDG Backfill Foundations: B-Line, E-BLDG Backfill Foundations: B-Line, C-BLDG Backfill Foundations: B-Line, C-BLDG Backfill Foundations: C-T-1 Lines, E-BLDG Backfill Foundations: C-T-1 Lines, E-BLDG Backfill Foundations: C-T-1 Lines, C-BLDG Backfill Foundations: C-T-1 Lines, C-BLDG Structural Steel: C-BLDG Steel Steel S	3 2 2 3 3 2 2 3 4 2 2 4 4 2 2 2 3 2 2 4 4 5 5 5 5 3 3 3 0 71 ⁺ 54 ⁺ 42 ⁺ 4 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9	22MAY08A 10JUN08A 115JUN08A 77JUL08A 18JUN08A 28MAY08A 28MAY08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 22JUN08A 07JUL08A 118NOV08A 118NOV08A 18SEP08A 18SEP08A 18SEP08A 18SEP08A 18SEP08A 18JUN08A 113JUL08A 113JUL08A 113JUL08A	23MAY08A 13JUN08A 17JUN08A 09JUL08A 07NOV08A 07NOV08A 07NOV08A 07NOV08A 07NOV08A 07NOV08A 07NOV08A 07NOV08A 07NOV08A 07NOV08A 28MAY08A 28MOV08A 15SEP08A 31JUL08A 23SEP08A 23OCT08A	30APR08 28APR08 21APR08 21APR08 02MAY08 30APR08 30APR08 30APR08 08MAY08 21APR08 21APR08 21APR08 21APR08 21APR08 21APR08 23MAY08 08AU008 09JUL08 25AU308 13OCT08 14MAY08 14MAY08	01MAY08 29APR08 23APR08 08MAY08 29APR08 23APR08 01MAY08 09MAY08 20MAY08 20MAY08 20MAY08 20MAY08 20MAY08 14MAY08 30MAY08 12AUG08 15JUL08 15JUL08 27AUG08 15OCT08	0 -31 -35 -555 -133 0 -38 -55 -85 -85 -85 -130 -132 0 -132 0 -132 -12 -40 -132 -12 -41 -118 -6 -6 -6 -6 -7 -84 -10 -118 -118 -118 -118 -118 -118 -118	ICaissons: F-Line, C-BLDG IPeter: F-Line, C-BLDG IPeter: F-Line, C-BLDG IVali Bracing: F-Line, C-BLDG ICaissons: F-Line, E-BLDG ICaissons: F-Line, E-BLDG IFootings: F-Line, I-BLDG IPeter: F-Line, V-BLDG IPeter: F-L
0.097 0.657 0.657 0.027 0.027 0.027 0.027 0.027 0.027 0.038 0.038 0.	Calissons: F-Line, C-BLDG Piers: F-Line, C-BLDG Fronting: F-Line, C-BLDG Masonry: F-Line, C-BLDG Calissons: F-Line, E-BLDG Calissons: F-Line, E-BLDG Piers: F-Line, E-BLDG Backfill: F-Line, E-BLDG Calissons: F-Line, W-BLDG Calissons: F-Line, W-BLDG Piers: F-Line, W-BLDG Piers: F-Line, W-BLDG Backfill: Foundations: B-Line, E-BLDG Backfill: Foundations: B-Line, W-BLDG Backfill: Foundations: B-Line, W-BLDG Backfill: Foundations: B-Line, W-BLDG Backfill: Foundations: B-Line, W-BLDG Backfill: Foundations: B-Line, W-BLDG Structural Steel: C-BLDG Structural Steel: C-BLDG Steel Start Structural Steel: C-BLDG Steel Start Steel Start Steel Start Steel Start Steel Start Steel Start Steel Start Steel Start Steel Steel Steel Steel St	3 2 2 3 3 2 2 2 3 4 2 2 2 3 4 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 2 2 3 3 2 2 2 2 3 3 2 2 2 2 3 3 2 2 2 3 3 2 2 2 3 3 2 2 3 3 2 2 3 3 2 2 4 4 4 5 5 5 5 5 5 5 5 5 5 5 5 5	22MAY08A 10JUN08A 10JUN08A 10JUN08A 7JUL08A 18SEP08A 23MAY08A 23AU308AU308A 23AU308A 23AU308A 23AU308A 23AU308A 23AU308A 23AU308A	23MAY08A 13,UIN08A 17,UIN08A 09,UIL08A 07NOY08A 07NOY08A 20,UIN08A 20,UIN08A 20,UIN08A 20,UIN08A 28,UIL08A 28,UIL08A 28,UIL08A 23,UIL08A 23,UIL08A 23,UIL08A 23,UIL08A 25,UIL08A 25,UIL08A 22,SEP08A 23,OCT08A 23,OCT08A 23,OCT08A 23,SEP08A 27,UIN08A 17,JUL08A	30APR08 28APR08 21APR08 21APR08 02MAY08 30APR08 30APR08 30APR08 08MAY08 21APR08 21APR08 21APR08 21APR08 21APR08 21APR08 23MAY08 08AU008 09JUL08 25AU308 13OCT08 14MAY08 14MAY08	01MAY08 29APR08 23APR08 08MAY08 29APR08 23APR08 01MAY08 09MAY08 20MAY08 20MAY08 20MAY08 20MAY08 20MAY08 14MAY08 30MAY08 12AUG08 15JUL08 15JUL08 27AUG08 15OCT08	0 -31 -35 -55 -133 0 -38 -55 -38 -55 -330 0 -24 -132 0 -132 0 -232 -41 -41 -132 -132 -132 -132 -132 -132 -132 -13	Icaissons: F-Line, C-BLDG IPerts: F-Line, C-BLDG IPerts: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Caissons: F-Line, F-BLDG IFootings: F-Line, F-BLDG IFootings: F-Line, F-BLDG IPerts: F-Line, F-BLDG IPerts: F-Line, V-BLDG IPerts: F-Line, V+BLDG IPerts: F-Lin
0097 0577 0577 027 027 027 027 027 027 027 0	Calissons: F-Line, C-BLDG Piers: F-Line, C-BLDG Piers: F-Line, C-BLDG Wall Bracing: F-Line, C-BLDG Masony: F-Line, C-BLDG Masony: F-Line, C-BLDG Masony: F-Line, C-BLDG Mall Bracing: F-Line, E-BLDG Mall Bracing: F-Line, E-BLDG Masony: F-Line, E-BLDG Masony: F-Line, E-BLDG Masony: F-Line, K-BLDG Calissons: F-Line, W-BLDG Footings: F-Line, W-BLDG Backfill: F-Line, K-BLDG Masony: F-Line, W-BLDG Backfill: Foundations: A-Line, C-BLDG Backfill: Foundations: A-Line, C-BLDG Backfill: Foundations: A-Line, K-BLDG Backfill Foundations: A-Line, K-BLDG Backfill Foundations: A-Line, K-BLDG Backfill Foundations: A-Line, K-BLDG Backfill Foundations: A-Line, K-BLDG Structural Steel: C-BLDG Structural Steel: C-BLDG Structural Steel: C-BLDG Structural Steel: C-BLDG Steel Erection Complete Erect: 13-15/A-E (Seq 1-7) Detait: 13-16/A-E (Seq 1-9) Detait: 13-17/A-E (Seq 1-9)	3 2 2 3 3 2 2 2 3 4 2 2 3 4 2 2 3 3 2 4 4 2 2 3 3 3 2 2 4 4 2 2 3 3 3 4 4 2 2 3 3 3 3 2 2 2 3 3 4 4 2 2 3 3 3 2 2 2 3 3 4 4 2 2 3 3 4 4 2 2 3 3 2 2 3 3 3 2 2 3 3 2 2 3 3 2 2 4 4 2 2 3 3 2 2 4 4 5 5 5 5 5 5 5 5 5 5 5 5 5	22MAY08A 10JUN08A 10JUN08A 10JUN08A 7JUL08A 28MAY08A 28JUN08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 22JUN08A 07JUL08A 18NOV08A 18NOV08A 18NOV08A 18SEP08A 18SEP08A 18SEP08A 18SEP08A 18SEP08A 18SEP08A 18SEP08A 18SEP08A 18JUN08A 09JUN08A 09JUN08A 18JUN08A 09JUN08A 20JUN08A 20JUN08A	23MAY08A 13JUN08A 13JUN08A 13JUN08A 09JUL08A 30MAY08A 20JUN08A 09JUL08A 20JUN08A 07NOV08A 27NOV08A 07NOV08A 07NOV08A 07NOV08A 07NOV08A 07JUL08A 23JUN08A 15SEP08A 31JUL08A 23SEP08A 15SEP08A 30SEP08A 15SEP08A 23S	30APR08 28APR08 21APR08 21APR08 02MAY08 30APR08 30APR08 30APR08 08MAY08 21APR08 21APR08 21APR08 21APR08 21APR08 21APR08 23MAY08 08AU008 09JUL08 25AU308 13OCT08 14MAY08 14MAY08	01MAY08 29APR08 23APR08 08MAY08 29APR08 23APR08 01MAY08 09MAY08 20MAY08 20MAY08 20MAY08 20MAY08 20MAY08 14MAY08 30MAY08 12AUG08 15JUL08 15JUL08 27AUG08 15OCT08	0 -31 -35 -55 -133 0 -38 -55 -85 -130 -32 0 -24 -132 0 -24 -132 -24 -132 -24 -132 -24 -132 -24 -112 -41 -118 -6 -6 -18 -34 0 -112 -112 -112 -112 -112 -112 -112 -1	Icaissons: F-Line, C-BLDG IPerts: F-Line, C-BLDG IPerts: F-Line, C-BLDG IPerts: F-Line, C-BLDG Matil Bracing: F-Line, C-BLDG Caissons: F-Line, F-BLDG IFootings: F-Line, F-BLDG IPerts: F-Line, F-BLDG IPerts: F-Line, V-BLDG IPerts: F-Line, V+BLDG IPerts: F-Line,
0097 0577 0577 0227 0237 0247 0257 0267 0267 0297 0297 0297 0297 0297 0397 0397 0397 0397 0397 0497 0397 0498 04988 04988 04988 04988 04988 04988 04988 04988 04988 049	Calissons: F-Line, C-BLDG Prers: F-Line, C-BLDG Frodings: F-Line, C-BLDG Masonry: F-Line, C-BLDG Colissons: F-Line, E-BLDG Galssons: F-Line, E-BLDG Prers: F-Line, E-BLDG Backtill F-Line, E-BLDG Backtill F-Line, E-BLDG Calissons: F-Line, W-BLDG Footings: F-Line, W-BLDG Prers: F-Line, W-BLDG Press: F-Line, W-BLDG Backtill Foundations: B-Line, E-BLDG Backtill Foundations: B-Line, E-BLDG Backtill Foundations: B-Line, C-BLDG Backtill Foundations: B-Line, C-BLDG Backtill Foundations: B-Line, C-BLDG Backtill Foundations: B-Line, V-BLDG Backtill F	3 2 2 3 3 3 2 2 2 3 4 4 2 2 2 3 3 4 2 2 2 3 3 4 4 2 2 2 3 3 4 4 2 2 2 3 3 4 4 2 2 2 3 3 3 3 3 3 3 3 3 3 3 3 3	22MAY08A 10JUN08A 10JUN08A 10JUN08A 77JUL08A 18SEP08A 23MAY08A 25AUG08A 22SEP08A 22SEP08A 22SEP08A 22SEP08A 24SEP08A 24SEP08A 23JUN08A 18NOV08A 18NOV08A 18NOV08A 18SEP08A 18SEP08A 09JUN08A 18SEP08A 09JUN08A 18JUL08A 13JUL08A 13JUL08A	23MAY08A 13,UN08A 17,UN08A 09,UL08A 07NOV08A 20,UN08A 20,UN08A 20,UN08A 20,UN08A 20,UN08A 20,UN08A 20,UN08A 27,UN08A 23,UN08A 23,UN08A 23,UN08A 23,UN08A 23,UN08A 23,UN08A 23,UN08A 23,UN08A 23,UN08A 23,UN08A 23,UN08A 23,UN08A 23,UN08A 23,UN08A 23,UN08A 15,SEP08A 23,OCT08A 23,SEP08A 24,SEP08A 24,S	30APR08 28APR08 21APR08 21APR08 02MAY08 30APR08 30APR08 30APR08 08MAY08 21APR08 21APR08 21APR08 21APR08 21APR08 21APR08 23MAY08 08AU008 09JUL08 25AU308 13OCT08 14MAY08 14MAY08	01MAY08 29APR08 23APR08 08MAY08 29APR08 23APR08 01MAY08 09MAY08 20MAY08 20MAY08 20MAY08 20MAY08 20MAY08 14MAY08 30MAY08 12AUG08 15JUL08 15JUL08 27AUG08 15OCT08	0 -31 -35 -55 -133 0 -38 -55 -132 0 -132 0 -132 -132 -132 -132 -132 -132 -132 -132	ICaissons: F-Line, C-BLDG IPerts: F-Line, C-BLDG IPerts: F-Line, C-BLDG IPerts: F-Line, C-BLDG ICaissons: F-Line, C-BLDG ICaissons: F-Line, E-BLDG IFootings: F-Line, F-BLDG IPerts: F-Line, K-BLDG IPerts: F-Line, V-BLDG IPerts: F-Line, V-

Figure 61: Turner Construction Schedule 3/4

Activity ID	Activity Description	Orig Dur	Early Start	Early Finish	Plan Start	Plan Finish	Fin Var	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP		
0489	Stair C1	15	21JUL08A	12AUG08A			0					1	1		Stair C	:1		
0499	Stair W2	15	22JUL08A	08AUG08A			0								Stair W	2		
0509	Stair W1	15	18AUG08A	05SEP08A			0									Stair W1		
Crane 2									1			1	1	_	1		i.	1
0359	Erect: 13-8 / A-E (Seq 101-112)	13	08JUL08A	18JUL08A			0				10.0				ect: 13-8 /	A-E (S	eq 101-1	12)
0449	Detail: 13-8 / A-E (Seq 101-112)	28	17JUL08A	15SEP08A			0			Detail	13-8/	A-E (3	Seq 101-			-	1	
0369	Erect: 8-4 / A-E (Seq 113-124)	25	18JUL08A	05AUG08A			0					1	1		Erect: 8	-4 / A-E	(Seq 11	3-124)
0459	Detail: 8-4 / A-E (Seq 113-124)	39	22JUL08A	15SEP08A			0						(Seq 11)		1	-		
0389	Erect: 4-0.07 / A-E (Seq 125-131)	18	05AUG08A	28AUG08A			0								1)			
0479	Detail: 4-0.07 / A-E (Seq 125-131)	31	06AUG08A	15SEP08A			0			De	tail: 4-0	0.07 / A	-E (Seq	125-13	1)	•		
0519	Stair E1	15	04AUG08A	20AUG08A			0								Stair	r E1		
0529	Stair E2	10	06AUG08A	20AUG08A			0								Stair	r E2		
SOD									1			1	1				i.	
	1					12AUG08									E - E	COD. C		
0050	SOD: C-BLDG	33*	23JUL08A	06SEP08A	25JUN08		-18									SOD: C	SOD: W	
0049	SOD: W-BLDG	32*	25AUG08A	070CT08A	10SEP08	280CT08	15											
0051	SOD: E-BLDG	22*	26AUG08A	24SEP08A	23JUL08	09SEP08	-11						-		-	ISO	D: E-BL	DG
08-21 0281B	MEP Hangers/Slab RI: 8-21 / A-E (1st Fir)	5	14JUL08A	18JUL08A			0							D.4F	P Hanger	e/Slah 5	1. 8-21	A-E (1et
0291B		-													SOD: 8-2			N-L (lat
	SOD: 8-21 / A-E (1st Fir)	5	23JUL08A	28JUL08A			0		1		anorole	lab Di	0.2111			17 A-E	(Ist Fir)	
0381B	MEP Hangers/Slab RI: 8-21 / A-E (5th Fir)	5	14AUG08A	15AUG08A			0		Ň	IEP Ha	ngers/S	ab RI:	0-2177	-E (5th				-
0391B	SOD: 8-21 / A-E (5th Fir)	5	15AUG08A	18AUG08A			0						1			8-21/	A-E (5th	i Fir)
0321B	MEP Hangers/Slab RI: 8-21 / A-E (2nd Fir)	5	24JUL08A	30JUL08A			0		MEPH	angers	olap RI	. 8-21	A-E (2	nd Flr)	1	-	1	
0331B	SOD: 8-21 / A-E (2rd Fir)	5	31JUL08A	04AUG08A			0						·		SOD: 8-	21 / A-E	. (2rd Flr)
0341B	MEP Hangers/Slab RI: 8-21 / A-E (3rd Fir)	5	25JUL08A	30JUL08A			0		MEPH	angers	/Slab R	1: 8-21	/A-E (3rd Flr)				
0351B	SOD: 8-21 / A-E (3rd Fir)	5	31JUL08A	12AUG08A			0									8-21 / A	-E (3rd F	fir)
0361B	MEP Hangers/Slab RI: 8-21 / A-E (4th Fir)	5	11AUG08A	12AUG08A			0		M	EP Han	gers/SI	ab RI:	8-21 / A	E (4th	Fir)			
0371B	SOD: 8-21 / A-E (4th Flr)	5	13AUG08A	14AUG08A			0						1			8-21 / A	A-E (4th	Flr)
0401D	MEP Hangers/Slab RI: 8-21 (Penthouse)	5	26AUG08A	02SEP08A			0			ME	Hang	ers/Sla	b RI: 8-3	21 (Pent	house)			1
0411D	SOD: 8-21 (Penthouse)	5	29AUG08A	06SEP08A			0								E 📮	SOD: 8	-21 (Per	nthouse)
08 - 04									i i						1		1	1
0281F	MEP Hangers/Slab RI: 8-4 / A-E (1st Fir)	4	25AUG08A	02SEP08A			0			MEP	Hange	ers/Slab	RI: 8-4	/ A-E (1st Flr)			
0291F	SOD: 8-4 / A-E (1st Fir)	4	26AUG08A	04SEP08A			0									SOD: 8-	4/A-E ((1st Fir)
0321F	MEP Hangers/Slab RI: 8-4 / A-E (2nd Fir)	4	29AUG08A	04SEP08A			0			MER	P Hange	ers/Slat	RI: 8-4	4/A-E (2nd Flr)			
0331F	SOD: 8-4/A-E (2rd Flr)	4	29AUG08A	08SEP08A			0	1								SOD: 8	3-4 / A-E	(2rd Fir)
0341F	MEP Hangers/Slab RI: 8-4 / B-E (3rd Fir)	4	11SEP08A	16SEP08A			0	1		-)	MEP Ha	angers/	Slab RI:	8-4/B-	E (3rd Fir)		
0351F	SOD: 8-4 / B-E (3rd Fir)	4	12SEP08A	17SEP08A			0									SOD:	8-4/B	E (3rd F
0361F	MEP Hangers/Slab RI: 8-4 / B-E (4th Fir)	4	12SEP08A	17SEP08A			0				MEP H	angers	Slab RI:	8-4/B	E (4th Fir	r)		
0371F	SOD: 8-4 / B-E (4th Fir)	4	15SEP08A	18SEP08A			0									SOD	: 8-4/B	-E (4th F
0381F	MEP Hangers/Slab RI: 8-4 / B-E (5th Fir)	4	16SEP08A	19SEP08A			0				MEPH	langer	s/Slab R	1: 8-4/1	B-E (5th F			
0391F	SOD: 8-4 / B-E (5th Fir)	4	17SEP08A	22SEP08A			0								1 1		D- 8-4/1	B-E (5th F
04-01	JOOD. DATI DE (DATTA)		TROEFOOR	220Er Ourt		1			1 1	-		1	1	-				
0281H	MEP Hangers/Slab RI: 4-1 / A-E (1st Fir)	4	02SEP08A	08SEP08A			0			M	EP Han	gers/SI	ab RI: 4	-1/A-E	(1st Fir)			
0291H	SOD: 4-1 / A-E (1st Fir)	4	03SEP08A	10SEP08A			0								1 i i	SOD	4-1 / A-E	(1st Fir)
0412H	Complete SOD: 0.7-01 (1st Fir)	4	060CT08A	060CT08A			0						Comp	lete SOI	0.7-01 (
0321H	MEP Hangers/Slab RI: 4-1 / A-E (2nd Fir)	4	03SEP08A	09SEP08A	-		0			ME	P Han	ers/SI			(2nd Fir)			
0331H	SOD: 4-1/A-E (2rd Fir)	4	05SEP08A	11SEP08A			0					1	1				4-1 / A-F	(2rd Fir)
0341H	MEP Hangers/Slab RI: 4-1 / B-E (3rd Fir)	4	15SEP08A	17SEP08A			0			-	MEPH	angers	Slab R	4-1/6	B-E (3rd F			(ard m)
0341H	-			18SEP08A							MILL I	ungen	-Ciub It	1 4 1 / 1	L (ordin			-E (3rd F
	SOD: 4-1 / B-E (3rd Flr)	4	16SEP08A				0				MEDI				B-E (4th F		: 4-17 D	-E (Srd F
0361H	MEP Hangers/Slab RI: 4-1 / B-E (4th Fir)	4	15SEP08A	18SEP08A	-		0				WIEP I	anger	Siab IC	. 4-171	2-C (4011			- 1
0371H	SOD: 4-1 / B-E (4th Fir)	4	17SEP08A	19SEP08A			0						1		1		< 4-1/B	B-E (4th F
0381H	MEP Hangers/Slab RI: 4-1 / B-E (5th Fir)	4	18SEP08A	22SEP08A			0		1		MEP	Hanger	s/Slab F	8: 4-1/	B-E (5th F		1	-
0391H	SOD: 4-1 / B-E (5th Fir)	4	19SEP08A	23SEP08A			0										D: 4-1/1	B-E (5th F
0401H	MEP Hangers/Slab RI: 8-1 (Penthouse)	4	16SEP08A	19SEP08A			0				MEP	Hange	rs/Slab	RI: 8-1	(Penthous			
0411H	SOD: 8-1 (Penthouse)	4	18SEP08A	24SEP08A			0									SO	D: 8-1 (Penthous
0411H10	Pour Curbs: 8-1 (Penthouse)	5	24SEP08A	30SEP08A			0				_		Pour C	urbs: 8-	1 (Pentho	use)		
01 - 0.7											11-			07.1.5 -	14-2 -			
0281DL	MEP Hangers/Slab RI: 1-0.07 / A-E (1st Fir)		04SEP08A	05SEP08A	-		0			MEP	Hange	rs/Slab	rti: 1-0	.u/ / A-E	(1st Fir)			
0291DL	SOD: 1-0.07 / A-E (1st Fir)	2	08SEP08A	10SEP08A			0						1		0	SOD:	1-0.07 / A	A-E (1st F
21-25		1	0041/0001	224110004	-					MEP H	anders	Slah P	21-25	/B-E (1	st FirM			
0281C	MEP Hangers/Slab RI: 21-25 / B-E (1st Fir)	4	22AUG08A	22AUG08A	-		0			WEP Ha	angers/	JIBD RI	21-25	, D-C (1				1
0291C	SOD: 21-25 / B-E (1st Fir)	4	25AUG08A	25AUG08A			0		E Î.	HER		Clark F	101.00			U: 21-2	5/B-E (ist Fir)
0321C	MEP Hangers/Slab RI: 21-25 / B-E (2nd Fir)	4	25AUG08A	28AUG08A			0		(MEPHa	angers/	Slab RI	21-25	/ B-E (2	and Fir)		1	1
0331C	SOD: 21-25 / B-E (2rd Flr)	4	26AUG08A	29AUG08A			0										25 / B-E	(2rd Flr)
0341C	MEP Hangers/Slab RI: 21-25 / B-E (3rd Fir)	4	26SEP08A	30SEP08A			0				MEPH	Hanger			5/B-E (3rd			
0351C	SOD: 21-25 / B-E (3rd Fir)	4	29SEP08A	01OCT08A			0								5 / B-E (3r			
0361C	MEP Hangers/Slab RI: 21-25 / B-E (4th Fir)	4	26SEP08A	30SEP08A			0				MEP	Hanger			5 / B-E (4th			
0371C	SOD: 21-25 / B-E (4th Fir)	4	010CT08A	030CT08A			0	1					SC	D: 21-2	25/B-E (4	th Fir)		
0381C	MEP Hangers/Slab RI: 21-25 / B-E (5th Fir)	4	30SEP08A	030CT08A			0	1			MEP	Hange	rs/Slab I	RI: 21-2	5/B-E (5	th Fir)		
0391C	SOD: 21-25 / B-E (5th Fir)	4	010CT08A				0	1					SC	D: 21-2	25/B-E (5	ith Fir)		
25 - 28							-				_	1	i.				-	
02811	MEP Hangers/Slab RI: 25-28 / B-E (1st Fir)	4	17SEP08A	22SEP08A			0			1	IEP Ha	ingers/s	Slab RI:	25-28 /	B-E (1st F	·ir)		
02911	SOD: 25-28 / B-E (1st Flr)	4	19SEP08A	25SEP08A			0	1					SOD:	25-28 /	B-E (1st	Fir)		
03211	MEP Hangers/Slab RI: 25-28 / B-E (2nd Fir)	4	16SEP08A	19SEP08A			0	1		M	EP Har	gers/S	ab RI: 2	25-28 / E	3-E (2nd F	lr)		
03311	SOD: 25-28 / B-E (2rd Fir)	4	22SEP08A	30SEP08A			0								B-E (2rd			
03411	MEP Hangers/Slab RI: 25-28 / B-E (3rd Fir)	4	223EP08A 29SEP08A	010CT08A			0				MEP	Hange			8 / B-E (3r			
03511	SOD: 25-28 / B-E (3rd Fir)	4	30SEP08A	020CT08A			0		t i						8/B-E (3)			- 1
					-								1 00	. 20-2		1		
03611	MEP Hangers/Slab RI: 25-28 / B-E (4th Fir)	4	30SEP08A	030CT08A	-		0									1		
03711	SOD: 25-28 / B-E (4th Fir)	4	010CT08A	040CT08A			0										. 1	
03811	MEP Hangers/Slab RI: 25-28 / B-E (5th Fir)	4	070CT08A	090CT08A			0										1	
03911	SOD: 25-28 / B-E (5th Fir)	4	080CT08A	100CT08A			0									1		
04011	MEP Hangers/Slab RI: 21-28 (Penthouse)	4	010CT08A	060CT08A			0									-		
04111	SOD: 21-28 (Penthouse)	4	020CT08A	070CT08A			0											
0411110	Pour Curbs: 21-28 (Penthouse)	3	100CT08A	100CT08A			0						1				1	
28 - 31									1				1		1 E			1
	MEP Hangers/Slab RI: 28-31 / B-E (1st Fir)	2	140CT08A	150CT08A			0										1	
0281K 0291K	SOD: 28-31 / B-E (1st Fir)	2	150CT08A	170CT08A			0										1	

Figure 62: Turner Construction Schedule 4/4

Page 108 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report

APPENDIX G: SUSTAINABLE ARCHITECTURE BREADTH STUDY



LEED for New Construction v 2.2 Registered Project Checklist

Project Name: Westinghouse Electric Company Corporate Headquarters

Project Address: 1000 Westinghouse Drive, Cranberry Township, PA 16066

Yes	?	No								
28	5	33	Project Totals (Pre-C	Project Totals (Pre-Certification Estimates)						
	CERTIFIED		Certified: 26-32 points	Silver: 33-38 points	Gold: 39-51 points	Platinum: 52-69 points				

Yes	?	No			
8	3	3	Sustaina	14 Points	
Yes			Prereq 1	Construction Activity Pollution Prevention	Required
1	0	0	Credit 1	Site Selection	1
0	0	1	Credit 2	Development Density & Community Connectivity	1
0	0	1	Credit 3	Brownfield Redevelopment	1
1	0	0	Credit 4.1	Alternative Transportation, Public Transportation	1
1	0	0	Credit 4.2	Alternative Transportation, Bicycle Storage & Changing Rooms	1
0	0	1	Credit 4.3	Alternative Transportation, Low-Emitting & Fuel Efficient Vehicles	1
1	0	0	Credit 4.4	Alternative Transportation, Parking Capacity	1
1	0	0	Credit 5.1	Site Development, Protect or Restore Habitat	1
1	0	0	Credit 5.2	Site Development, Maximize Open Space	1
1	0	0	Credit 6.1	Stormwater Design, Quantity Control	1
	1		Credit 6.2	Stormwater Design, Quality Control	1
	1		Credit 7.1	Heat Island Effect, Non-Roof	1
1	0	0	Credit 7.2	Heat Island Effect, Roof	1
	1		Credit 8	Light Pollution Reduction	1

Yes	?	No			
2	0	0	Water Ef	fficiency	5 Points
1	0	0	Credit 1.1	Water Efficient Landscaping, Reduce by 50%	1
1	0	0	Credit 1.2	Water Efficient Landscaping, No Potable Use or No Irrigation	1
			Credit 2	Innovative Wastewater Technologies	1
			Credit 3.1	Water Use Reduction, 20% Reduction	1
			Credit 3.2	Water Use Reduction, 30% Reduction	1



Last Modified: May 2008 1 of 4



LEED for New Construction v 2.2 Registered Project Checklist

Yes	?	No				
2	0	15	Energy 8	& Atmosp	here	17 Points
Yes			Prereg 1	Fundament	tal Commissioning of the Building Energy Systems	Required
Yes			Prereg 1		nergy Performance	Required
Yes			Prereg 1	Fundament	tal Refrigerant Management	Required
*Note for	FAc1: All I	FED for Ne	w Constructi		egistered after June 26, 2007 are required to achieve at least tw	(0, (2)) points
2	0	8	1			Sheke.
4	0	•	Credit 1		nergy Performance	1 to 10
				Credit 1.1	10.5% New Buildings / 3.5% Existing Building Renovations	1
			>	Credit 1.2	14% New Buildings / 7% Existing Building Renovations	2
				Credit 1.3	17.5% New Buildings / 10.5% Existing Building Renovations	3
				Credit 1.4	21% New Buildings / 14% Existing Building Renovations	4
				Credit 1.5	24.5% New Buildings / 17.5% Existing Building Renovations	5
				Credit 1.6	28% New Buildings / 21% Existing Building Renovations	6
				Credit 1.7	31.5% New Buildings / 24.5% Existing Building Renovations	7
				Credit 1.8	35% New Buildings / 28% Existing Building Renovations	8
				Credit 1.9	38.5% New Buildings / 31.5% Existing Building Renovations	9
			2	Credit 1.10	42% New Buildings / 35% Existing Building Renovations	10
0	0	3	Credit 2	On-Site Rer	newable Energy	1 to 3
				Credit 2.1	2.5% Renewable Energy	1
				Credit 2.2	7.5% Renewable Energy	2
				Credit 2.3	12.5% Renewable Energy	3
0	0	1	Credit 3	Enhanced (Commissioning	1
0	0	1	Credit 4	Enhanced F	Refrigerant Management	1
0	0	1	Credit 5	Measureme	ent & Verification	1
0	0	1	Credit 6	Green Pow	er	1

Adobe[®] LiveCycle[™]

Last Modified: May 2008 2 of 4



LEED for New Construction v 2.2 Registered Project Checklist

Yes	?	No			
5	0	8	Materia	13 Points	
Yes	ſ		Prereq 1	Storage & Collection of Recyclables	Required
0	0	1	Credit 1.1	Building Reuse, Maintain 75% of Existing Walls, Floors & Roof	1
0	0	1	Credit 1.2	Building Reuse, Maintain 95% of Existing Walls, Floors & Roof	1
0	0	1	Credit 1.3	Building Reuse, Maintain 50% of Interior Non-Structural Elements	1
1	0	0	Credit 2.1	Construction Waste Management, Divert 50% from Disposal	1
0	0	1	Credit 2.2	Construction Waste Management, Divert 75% from Disposal	1
1	0	0	Credit 3.1	Materials Reuse, 5%	1
1	0	0	Credit 3.2	Materials Reuse, 10%	1
0	0	1	Credit 4.1	Recycled Content, 10% (post-consumer + 1/2 pre-consumer)	ĩ
0	0	1	Credit 4.2	Recycled Content, 20% (post-consumer + 1/2 pre-consumer)	1
1	0	0	Credit 5.1	Regional Materials, 10% Extracted, Processed & Manufactured	1
1	0	0	Credit 5.2	Regional Materials, 20% Extracted, Processed & Manufactured	1
0	0	1	Credit 6	Rapidly Renewable Materials	1
0	0	1	Credit 7	Certified Wood	1

Yes	?	No			
10	2	3	Indoor E	Invironmental Quality	15 Points
Yes			Prereq 1	Minimum IAQ Performance	Required
Yes			Prereq 2	Environmental Tobacco Smoke (ETS) Control	Required
1	0	0	Credit 1	Outdoor Air Delivery Monitoring	1
1	0	0	Credit 2	Increased Ventilation	1
	1		Credit 3.1	Construction IAQ Management Plan, During Construction	1
	1		Credit 3.2	Construction IAQ Management Plan, Before Occupancy	1
1	0	0	Credit 4.1	Low-Emitting Materials, Adhesives & Sealants	1
1	0	0	Credit 4.2	Low-Emitting Materials, Paints & Coatings	1
1	0	0	Credit 4.3	Low-Emitting Materials, Carpet Systems	1
0	0	1	Credit 4.4	Low-Emitting Materials, Composite Wood & Agrifiber Products	1
0	0	1	Credit 5	Indoor Chemical & Pollutant Source Control	1
1	0	0	Credit 6.1	Controllability of Systems, Lighting	1
1	0	0	Credit 6.2	Controllability of Systems, Thermal Comfort	1
1	0	0	Credit 7.1	Thermal Comfort, Design	1
1	0	0	Credit 7.2	Thermal Comfort, Verification	1
1	0	0	Credit 8.1	Daylight & Views, Daylight 75% of Spaces	1
0	0	1	Credit 8.2	Daylight & Views, Views for 90% of Spaces	1

Adobe[®] LiveCycle[™]

Last Modified: May 2008 3 of 4

Figure 65: LEED Checklist from http://www.usgbc.org/showfile.aspx?documentid=3998 3/4

Page 111 of 112 Jessica L. Laurito Structural Option Advisor: Dr. Hanagan

Final Report



LEED for New Construction v 2.2 Registered Project Checklist

Yes	?	No		
1	0	4	Innovation & Design Process	5 Points
0	0	1	Credit 1.1 Innovation in Design: Provide Specific Title	ĩ
0	0	1	Credit 1.2 Innovation in Design: Provide Specific Title	1
0	0	1	Credit 1.3 Innovation in Design: Provide Specific Title	1
0	0	1	Credit 1.4 Innovation in Design: Provide Specific Title	1
1	0	0	Credit 2 LEED® Accredited Professional	1

Adobe[®] LiveCycle[™]

Last Modified: May 2008 4 of 4

Figure 66: LEED Checklist from http://www.usgbc.org/showfile.aspx?documentid=3998 4/4

APPENDIX H: REFERENCES

- American Concrete Institute. ACI 318-08: Building Code Requirements for Structural Concrete. ACI: Farmington Hills, MI, 2008.
- American Society of Civil Engineers. ASCE 7-05: Minimum Design Loads for Building and Other Structures. ASCE: Reston, VA, 2006.
- Audubon Society of Western Pennsylvania. "Culture and Use Guide For Western Pennsylvania Native Plants." <u>ACNP</u> <u>Culture and Use Guide</u>. 2008. Audubon Society of Western Pennsylvania. 16 Jan. 2009 http://www.aswp.org/acnp_culture_and_use_guide.html
- <u>CCW 500R Green Roof Waterproofing System</u>. 10 Mar. 2009. Carlisle Coatings and Waterproofing. 24 Mar. 2009 <www.carlisle-ccw.com/Doco/spec07555613CCW500RGreenRoofWaterproofingSystem.pdf.>.

International Code Council. International Building Code 2006. ICC: New York, NY, 2006.

- Local Native Plant Species Allegheny County Area. Audubon Society of Western Pennsylvania. 3 Apr. 2009 http://www.aswp.org/files/allegheny_county_pennsylvania_native_plants_aswp.pdf>.
- Roof Drain Calculator. Portal Plus. 29 Mar. 2009 http://www.portalsplus.com/drain_calc.htm.
- RSMeans Construction Publishers and Consultants. Building Construction Cost Data 2008 66th Annual Edition. Reed Construction Data, Inc.: Kingston, MA, 2007.
- Steel Construction Manual. 13th ed. American Institute of Steel Construction. AISC, 2005
- U.S. Green Building Council. <u>LEED for New Construction and Major Renovations</u>. Oct. 2005. U.S.G.B.C. 26 Mar. 2009 <http://www.usgbc.org/showfile.aspx?documentid=1095>.
- U.S. Green Building Council. <u>LEED For New Construction v 2.2 Registered Project Checklist</u>. May 2008. U.S.G.B.C. 26 Mar. 2009 <http://www.usgbc.org/showfile.aspx?documentid=3998>.
- <u>What are green roofs?</u> June 2008. Department of Energy Quality Michigan. 17 Jan. 2009 <www.deq.state.mi.us/documents/deq-ess-p2-p2week-greenroofresources.doc>.