

1000 Cranberry Woods Drive, Cranberry Township, PA



Mark Speicher Senior Thesis 2010 Construction Management April 12, 2010



Presentation Outline

- I. Project Overview
- II. Analysis 1: Energy and Environment
- III. Analysis 2: Concrete Slabs
- IV. Analysis 3: BIM Implementation
- V. Conclusions/Recommendations
- VI. Acknowledgements



PROJECT OVERVIEW

Presentation Outline

- I. Project Overview
- II. Analysis 1: Energy and Environment
- III. Analysis 2: Concrete Slabs
- IV. Analysis 3: BIM Implementation
- V. Conclusions/Recommendations
- VI. Acknowledgements

Location: Cranberry Township, PA


Occupant: Westinghouse Electric Company

Building Type: Office Size: 844,595 square feet

Construction Dates: February 2008 – May 2010

Overall Project Cost: \$240,000,000 Delivery Method: Design-Bid-Build






PROJECT OVERVIEW PROJECT TEAM: Owner: Wells Reit II

Tenant: Westinghouse Electric Company **GC/CM**: Turner Construction Company **Architect:** IKM Incorporated **Engineer:** LLI Engineering





PROJECT OVERVIEW **ARCHITECTURE**

- Consists of 3 Buildings ■ Primarily office space for over 4,000 engineers

STRUCTURAL



BUILDING ENCLOSURE

- Aluminum curtain wall
- Insulated wall panels
- Brick
- Polished concrete



VI. Acknowledgements

ANALYSIS 1: Energy and Environment

Presentation Outline

- I. Project Overview
- II. Analysis 1: Energy and Environment
- III. Analysis 2: Concrete Slabs
- IV. Analysis 3: BIM Implementation
- 1v. Analysis 5. Divi implementati
- V. Conclusions/Recommendations
 VI. Acknowledgements

BACKGROUND

- As energy company Westinghouse has opportunity to raise the standard
- Leased property → Wells Reit would benefit from reduced lifecycle cost

ECTIVE.

- OBJECTIVE
 Identify finishes which could be replaced with "greener" products
- Reduce the energy usage of the Westinghouse campus



Presentation Outline

Project Overview

Westinghouse Electric Company Nuclear Power

Engineering Headquarters Campus

II. Analysis 1: Energy and Environment

III. Analysis 2: Concrete Slabs

IV. Analysis 3: BIM Implementation

V. Conclusions/Recommendations

VI. Acknowledgements

Large percentage of building envelope

Potential for energy savings by implementing higher efficiency

CURRENT WINDOWS • 1" insulated tempered glass

ANALYSIS 1: Energy and Environment

Shading Coefficient (SC) Orientation

North

South

East

West

Total

Northwest

Southeast

U-value

Solar Heat Gain Factor (SHGF) **Window Square Footage**

14367

6717

6717

12547

5299

5896

51542

0.72 0.62 Wall Square

Tinted Double Pane

0.57

% of Wall **Footage** 25902 55% 18327 37%

18327 37% 25902 65% 8140 7599

104196 49%

Mark Speicher / Construction Management / Senior Thesis 2010

windows



ANALYSIS 1: Energy and Environment

Presentation Outline

- I. Project Overview
- II. Analysis 1: Energy and Environment
- III. Analysis 2: Concrete Slabs
- IV. Analysis 3: BIM Implementation
- iv. Analysis 3. bim implementatio
- V. Conclusions/Recommendations
- VI. Acknowledgements

PPG	SOLARBAN	80	WINDOWS
<u> </u>		\mathbf{v}	WINDOWS

- Excellent thermal properties
- Manufactured locally: United Plate Glass, Butler, PA


- 16	Transmittance		Reflectance		U-Value (Imperial)			2020	Selar	Light to	
Glass Type	Ultra- violet	Visible %	Total Solar Energy	Visible Light	Total Solar Energy	Winter Night- time	Summer Day- time	European U-Value	Coeff- cient	Setar Heat Gain Coeffi- cient	Solar Gain (LSG)
SOLARBAN* 80 Solar Control Low-E Glass											
SOLARBAN 80 (2) Clear + Clear	13	.48	20	33	38	0.29	0.27	1.52	0.28	0.24	1.98
SOLARBANBO (2) Clear + OPTIBLUE		34	15	32	38	0.29	0.27	1.52	0.27		1.48
SOLARBAN 80 (2) OPTIBLUE + Clear	9	34	15	19	28	0.29	0.27	1.52	0.23	0.20	1.70
ARCHARACTURE OF ARREST OF ARREST OF			1.1	1.70	200	0.00		1.00			

Solarban	Tinted Double
80 (2)	Pane
0.29	0.57
0.28	0.72
0.24	0.62
	80 (2) 0.29 0.28





Mark Speicher / Construction Management / Senior Thesis 2010



ANALYSIS 1: Energy and Environment ENERGY ANALYSIS

climate data

• U.S. Department of Energy (DOE) 2.2 Building Energy Analysis Simulation Tool Calculates hour-by-hour energy consumption using hourly

• City = Philadelphia, PA ■ Window Sq. Footage = 50,976 sq ft • Floor area = 270,000 sq ft

Assumptions:

VI. Acknowledgements

Mark Speicher / Construction Management / Senior Thesis 2010



Project Overview

Reculter

Rest	1115.		
Glazing	Electricity	Sus	Open Ca Capen Capen Capen Capen Capen Capen Ca Ca Capen Ca Ca Ca Ca Ca Ca Ca Ca Ca Ca Ca Ca Ca
Double Pane Tinted	4,227,796	80,139	\$270

Cost Savings of Low E 70,227 \$108,093 \$378,320 \$1,772,085 \$259,954 \$91,054 5351,000 51,652,400 527,312 \$119,597

Building One=460,000 square feet \$7,202,912 \$136,533 \$460,387 \$184,158 Double Pane Tinted Solarban 80 (2) \$6,672,309 \$437,041 \$150,347

- Savings \$530.603 \$25,341 \$23.346 \$33.812
 - ✓ Total operating cost reduced by 9% ✓ Total cooling HVAC cost reduced by 12.5%

Total Capital

\$3,019,108

\$2,642,490

\$376.617

\$644,545

VI. Acknowledgements

III. Analysis 2: Concrete Slabs

IV. Analysis 3: BIM Implementation

V. Conclusions/Recommendations

II. Analysis 1: Energy and Environment

Mark Speicher / Construction Management / Senior Thesis 2010

5255 524 | 500 247

\$344,771

\$361,375 \$1,718,370 \$16,945 \$347,690 \$1,580,829

31 990 91

\$1,551,027

ANALYSIS 1: Energy and Environment

513,549


\$221,059

230

246

9,024

4,858



BACKGROUND

 Campus constructed on a compressed schedule ■ 22 month \rightarrow 15 month Slabs on critical path of schedule • Cost of overtime had large impact on overall cost

OBIECTIVE

Explore the feasibility of precast concrete

Schedule

Cost Structural Ramifications

ANALYSIS 2: Prefabricated Concrete Slabs

Mark Speicher / Construction Management / Senior Thesis 2010

V. Conclusions/Recommendations

II. Analysis 1: Energy and Environment

IV. Analysis 3: BIM Implementation

V. Conclusions/Recommendations

III. Analysis 2: Concrete Slabs

Presentation Outline Project Overview

VI. Acknowledgements

CURRENT SLAB ON DECK SYSTEM

• 2 ½" lightweight concrete on 22 gauge metal deck

ANALYSIS 2: Prefabricated Concrete Slabs

- Schedule:
- Poured in the typical workflow pattern



End Date Location **Duration Start Date** Slab on Deck- Center 2-Sep-08 35 16-Jul-08 Slab on Deck- East 13-Aug-08 30-Sep-08 Slab on Deck- West 1-0ct-08 18-Nov-08 Total 90 16-Jul-08 18-Nov-08

Mark Speicher / Construction Management / Senior Thesis 2010



Engineering Headquarters Campus

Westinghouse Electric Company Nuclear Power

CURRENT SLAB ON DECK SYSTEM

No actual cost data provided

Cost:

ANALYSIS 2: Prefabricated Concrete Slabs

Location **Forming** Placing **WWF** Material Total 1st Floor \$476,079 36,641 \$126,564 \$639,284

II. Analysis 1: Energy and Environment

III. Analysis 2: Concrete Slabs

Presentation Outline

Project Overview

IV. Analysis 3: BIM Implementation

V. Conclusions/Recommendations

VI. Acknowledgements

Approximate cost = \$3,400,000

Estimate calculated using RS Means

Total

2nd Floor

3rd Floor

4th Floor

5th Floor

\$476,079

\$476,079

\$476,079

\$476,079

\$2,380,395

\$181.192

183.205

36.641

36,641

36,641

36,641

\$632.820 \$3,377,612

\$126,564

\$126,564

\$126,564

\$126,564

\$639,284

\$639,284

\$639,284

\$639,284

Mark Speicher / Construction Management / Senior Thesis 2010



PREFABRICATED CONCRETE SLABS

Double Tees



II. Analysis 1: Energy and Environment

Reduce steel

III. Analysis 2: Concrete Slabs IV. Analysis 3: BIM Implementation

I. Project Overview

V. Conclusions/Recommendations

VI. Acknowledgements

Placement

Larger widths

• 12' wide double tees selected

Typical bay sizes were maintained (24')

ANALYSIS 2: Prefabricated Concrete Slabs





Presentation Outline

Project Overview

VI. Acknowledgements

III. Analysis 2: Concrete Slabs

Westinghouse Electric Company Nuclear Power **Engineering Headquarters Campus**

ANALYSIS 2: Prefabricated Concrete Slabs

PREFABRICATED CONCRETE SLABS

Schedule Analysis:

• 20-30 minute erection time \rightarrow 20

Maintained initial start date → July 16, 2008

■ Duration → 32 days

■ Estimated completion date → August 28, 2008

Slab on Deck- East 1st Floor 2nd Floor 3rd Floor 4th Floor 5th Floor 6th Floor Slab on Deck: West 1st Floor 2nd Floor 3rd Floor

Slab on Deck- Center

1st Floor

2nd Floor 21-Jul-08 24-Jul-08 3rd Floor 24-Jul-08 28-Jul-08 4th Floor 28-Jul-08 30-Jul-08 5th Floor 30-lul-08 1-Aug-08 6th Floor 4-Aug-08 4-Aug-08 212 4240 8.83 5-Aug-08 15-Aug-08 5-Aug-08 6-Aug-08 7-Aug-08 8-Aug-08 8-Aug-08 11-Aug-08 12-Aug-08 13-Aug-08 13-Aug-08 14-Aug-08 15-Aug-08 15-Aug-08 212 18-Aug-08 28-Aug-08 18-Aug-08 19-Aug-08 20-Aug-08 21-Aug-08 4th Floor 5th Floor 6th Floor

Mark Speicher / Construction Management / Senior Thesis 2010

IV. Analysis 3: BIM Implementation

V. Conclusions/Recommendations

II. Analysis 1: Energy and Environment

✓ 58 days ahead of current schedule (November 18, 2008)

25-Aug-08 26-Aug-08 26-Aug-08 27-Aug-08

21-Aug-08 22-Aug-08

Erection Time Erection


1680

28-Aug-08 28-Aug-08

Start Date End Date

16-Jul-08 4-Aug-08

16-Jul-08 21-Jul-08



PREFABRICATED CONCRETE SLABS

Cost Analysis: Material and shipping costs from Nitterhouse Erection costs from RS Means • Removal of steel cost data taken from previous estimate ■ Cost after steel savings → \$1,723,017

Total 407000 \$3,052,500 \$1,190,700 \$

Precast Cost Summary

Square Material Cost Shipping Cost Erection Costs 1st Floor 2nd Floor 3rd Floor Total 272,160

29096 \$2,792,343

639,160

548,18

Steel Cost Summary

V. Conclusions/Recommendations

VI. Acknowledgements

Mark Speicher / Construction Management / Senior Thesis 2010

✓ Savings of \$1.654.5895 off current system (\$3.377.612)

ANALYSIS 2: Prefabricated Concrete Slabs

Total Precast Cost **Steel Savings**

Adjusted Total

\$4.515.360 \$2,792,343

\$1,723,017

VI. Acknowledgements

Mark Speicher / Construction Management / Senior Thesis 2010

STRUCTURAL RAMIFICATIONS (STRUCTURAL BREADTH ANALYSIS) Bay size and layout would remain the same

 Ceiling height would be reduced Calculations

Steel Manual

Redesign of steel members according to Table 3-10 of the AISC

✓ Increase steel joist size to W21x101 (from W24x80)

ANALYSIS 2: Prefabricated Concrete Slabs

■ Tributary Area: At= 864 sq ft • Live Load Reduction: L=61 psf

Calculations:


Unbraced length= 24'

■ Dead Load: D=108 psf

• Factored Load: Wu= 227 psf = 8.2 klf

Maximum Shear: Vu= 98 kips ≈ 100 kips

■ Maximum Moment: $Mu=590 \text{ kip} - \text{ft} \approx 600 \text{ kip} - \text{ft}$



BACKGROUND Large push from industry towards Building Information Modeling (BIM) • Can provide value by: Identifying potential clashes

ANALYSIS 3: BIM Implementation

 Enhancing coordination Better communicate ideas **OBJECTIVE**

 Determine where BIM could have been effective Explore views of Turner staff Analyze potential of clash detection



3D AND 4D MODELING

I. Project Overview

II. Analysis 1: Energy and Environment

Presentation Outline

III. Analysis 2: Concrete Slabs

IV. Analysis 3: BIM Implementation

V. Conclusions/Recommendations

VI. Acknowledgements

Autodesk Navisworks 2010

Autodesk Revit 2010

Ductwork

Piping

Steel

Equipment

ANALYSIS 3: BIM Implementation

• Chose to explore the benefits of clash detection Basement mechanical space was modeled



CLASH DETECTION

- Tests were run against:
 - Plumbing vs Mechanical → 10 clashes
 - Plumbing vs Structural → 2 clashes
- Structural vs Mechanical → 0 clashes

• If found in the field result in RFIs, change orders, and/or delays

ANALYSIS 3: BIM Implementation

V. Conclusions/Recommendations

Presentation Outline


Project Overview

III. Analysis 2: Concrete Slabs

VI. Acknowledgements

IV. Analysis 3: BIM Implementation

II. Analysis 1: Energy and Environment



ANALYSIS 3: BIM Implementation COST AND SCHEDULE ANALYSIS Difficult to quantify

 Problems never actually faced Slightly higher upfront cost • Even this is reducing with BIM becoming a standard Minor conflict found between piping and ceiling heights No money to cover coordination issues in budget Bulkheads installed to cover piping

VI. Acknowledgements

Opportunity to save money by implementing high efficiency

CONCLUSIONS/RECOMMENDATIONS

• Current finishes within building meet LEED requirements

Low levels of VOC and regionally manufactured


• Total operating costs could be reduced up to 9%

Load on mechanical equipment would be reduced

ANALYSIS 1: ENERGY AND THE ENVIRONMENT

windows

VI. Acknowledgements



ANALYSIS 2: PREFABRICATED CONCRETE SLABS Prefabricated Concrete slabs could have saved time and money

CONCLUSIONS/RECOMMENDATIONS

• 58 days ahead of schedule Negative impacts on structural system

• Difficult to determine the lead time necessary to complete the

• \$1.7 million less

project

Mark Speicher / Construction Management / Senior Thesis 2010

CONCLUSIONS/RECOMMENDATIONS

 Clashes found in mechanical room Value of these findings is unknown

due to incomplete drawings

ANALYSIS 3: BIM IMPLEMENTATION

Would not have been an issue if designed with BIM

Staff did not feel BIM could have been successfully employed

II. Analysis 1: Energy and Environment III. Analysis 2: Concrete Slabs


IV. Analysis 3: BIM Implementation

V. Conclusions/Recommendations

VI. Acknowledgements

Mark Speicher / Construction Management / Senior Thesis 2010

Clashes found in field which carried an additional cost



ACKNOWLEDGEMENTS ACKNOWLEDGEMENTS

Turner Construction Company

Penn State AE Department Dr. Chris Magent Dr. David Riley

Friends and Family

Kathleen McCartney **Bob Hennessey**

Nitterhouse Concrete Products Mark Tavlor V. Conclusions/Recommendations VI. Acknowledgements



Westinghouse Electric Company Nuclear Power Engineering Headquarters Campus



QUESTIONS?