

Project Overview

The 77 K Street project is a class A core and shell office base building project consisting of 11 above grade levels and 3 levels of below grade parking garage. The site is located at the intersection of 1st and K Streets in Washington, DC in the North of Massachusetts development district north of the Capitol Building. Additionally, the project is located only blocks from Union Station, Washington, D.C.'s primary rail terminal. The project includes approximately 350,000 gross square feet of above grade office space and an additional 100,000 square feet of below grade parking.



Figure 1.1: District of Columbia Map (Source: Mapquest.com)

Client Information

The owner of this project, 77 K Street LLC, is a joint venture between Brookfield Properties and ING Clarion. The original partnership at project startup was between Cafritz Company and ING Clarion but in July 2006 Brookfield Properties replaced Cafritz Company and the partnership as it is today was born.


Brookfield Properties had a number of goals and expectations that they sought to achieve on the project.


- **Tenant:** Though none have been named to date, the developer is seeking to lease the building to either a government or private sector tenant on a minimum ten year lease.
 - **Cost**: The firm is extremely determined to finish the project within budget. Their decision to abandon contract negotiations with a general contractor in favor of opening up the project to a competitive bid in an effort to drive down the costs is a testament to this.




- **Quality:** The building is class A construction. The owner wants high quality finishes and a first class commercial environment.
- Schedule: Schedule is important and the contractor must meet the substantial completion date of July 18, 2008 and the final completion date of September 18 or face liquidated damages.
 - **Safety:** Above all the project must achieve the above objectives with a superb safety record and no accidents resulting in lost time or injury.

If the project team is able to successfully meet these objectives by providing a high quality end product within budget with a minimal number of change orders and on time, the owner will be a satisfied client. Of primary importance, the owner is targeting the exterior skin enclosure as a sequencing issue of particular importance. They are pushing the general contractor, Davis Construction, to get the facade erected soon after topping out the concrete in order to allow critical interior work to commence.









Project Delivery Method

This project was developed via a design-bid-build delivery system. The ownership entity, 77 K Street LLC, sought to invest in a commercial development project in Washington, DC. After Davis, Carter, Scott developed a design, the project was put out to bid. The initial general contractor selection was based on a negotiated contract but after the owner sought a cheaper bid, the project was put out for competitive bid to a group of three shortlisted contractors. The ultimate decision was based on a number of criteria including cost, schedule, contractor's t eam, reputation, and qualifications with similar sized projects. Davis Construction won the job in November 2006.

The owner-general contractor agreement is AIA A111, a cost plus fee contract with a guaranteed maximum price. The guaranteed maximum price for the project is \$41,005,150 with a stipulated, lump sum fee of \$1,372,221. The contract includes clauses for increases in the fee based upon approved increases in the cost of construction. Additionally, there are stipulations for liquidated damages starting at \$1,000 per day for delays in substantial completion.

Local Conditions

Washington, DC has an ordinance restricting the height of all buildings in order to prevent any structure from standing taller than the nation's capitol building. Consequently, designers have turned to concrete design to maximize their design potential. Cast in place concrete allows for long spans with a decreased floor to floor height as compared to steel construction. When concrete is post tensioned, even longer spans are possible, such is the case in the 77 K Street project. By reducing floor heights and providing open floor plans, developers are able to maximize their rental space square footage in the district. Consequently, nearly every newly constructed building within Washington, DC will have a concrete structural system.

Tipping fees for garbage disposal are approximately \$850 per 20 CY dumpster. This includes pickup, disposal, and return of the dumpster. Dumpsters 40 CY in size are approximately double this cost. Recycling efforts were not pursued on this project.

The project is located in what is known as the Coastal Plain Physiographic Province of Washington, DC which contains mostly sedimentary soil materials. Stratum I which extends to a depth of between 13 and 22 feet below site grade consists of old fill predominantly composed of silty, clayey, and gravelly sand with varying amounts of organics, rock fragments, and gravel, as well as soils with stiff consistencies, classified as sandy clay. Stratum II which is first encountered at a depth between 13 and 22 feet below site grade consists of loose to dense silty and clayey sand with varying amounts of gravel and rock fragments. It also consists of cohesive soils classifying as clay with varying amounts of silt and sand. Such soil conditions in combination with groundwater conditions encountered at a depth between 18 and 39 feet below grade warranted the design of a mat foundation system.



Site Layout Plan

A site layout was developed for the concrete sequence of the project, which extends from April through December 2007. Concrete trucks will enter the site from K Street at the northwestern corner of the site or from the single entrance on 1^{st} street. Their entrance location will depend on which tower crane they will be supplying concrete to.

Also of note, the layout plan has lay down areas for structural steel rebar and formwork awaiting placement within the building. One critical feature of the site plan is the placement of the southern tower crane. The crane's placement intentionally just allowed the crane to reach the southwestern corner of the rear courtyard. At this location, the crane will make a critical precast concrete pick during the façade sequence of the project.

Included on the plan are the locations of Davis Construction's trailer and spaces for subcontractor trailers. During this sequence, Miller & Long, the concrete subcontractor, will occupy one of the two remaining trailer locations. Port-O-Johns and dumpsters are also provided on the site plan. Both can be serviced via the 1st Street entrance.


Additionally, pedestrian safety is of paramount importance so pedestrian walkways have been added to protect from vehicular traffic and site equipment. Additionally, site traffic cannot exit directly at the intersection of 1st and K Street as this would be a danger to pedestrians and other vehicles alike.

The site plan developed by Davis Construction is not only appropriate but highly effective as well. It best utilizes the limited space available in an efficient, safe manner.

77 K STREET

Washington, DC

Todd Povell | Construction Management | Consultant: Dr. John Messner





Thesis Report

April 9, 2008



Building Overview

Architecture

The 77 K Street base building project contains a variety of spaces including three levels of underground parking. The first floor contains a two-story lobby, retail space, an exercise facility, managerial offices, and a mailroom. The high-end lobby features honed granite floors, white Venetian plaster, wood veneer, and granite stone walls. Beginning at floor two, the building is designed for office tenants. The core of each floor contains the MEP rooms, elevator shafts, restrooms, and stairways.

The building was designed to reach its maximum height potential. It stands just shy of the 130' limitation, created in the District of Columbia to prevent any building from standing taller than the nation's capitol. The building also contains a rooftop terrace that provides views both east and south towards the Capitol Building, an appealing feature for the building's future tenants.

Zoning

77 K Street is zoned as type C-3-C under District of Columbia Title 11, Zoning 2002. C-3-C is a "high bulk major business and employment" zone. The code states that C-3-C "Permits matter-of-right development for major business and employment centers of medium/high density development, including office, retail, housing, and mixed uses to a maximum lot occupancy of 100%, a maximum FAR of 6.5 for residential and for other permitted uses, and a maximum height of ninety (90) feet." Because 77 K Street sits in the NoMa Development District, north of Massachusetts Avenue, the owner was able to obtain a code variance to increase both the maximum FAR and the building height.

Building Envelope

The exterior façade is predominantly composed of architectural precast concrete panels with punched out windows. Behind the precast panels, which are mounted at each slab level, there are 2" to 3-5/8" light gauge metal studs with R-13 batt insulation and either a single or double layer of 1/2" gypsum wallboard. The precast also has metal mullions attached to the outside to visually extend the lines of the windows both vertically and horizontally throughout the building.

At the entrances to the building on the north and east elevations, there are two story granite entries into the lobby. Proceeding up the building from these entranceways there are minimal amounts of precast but rather a façade predominantly composed of insulating vision glass windows, metal mullions, shadow boxes, and metal slab covers at the floor levels. The top two floors of the entire building have similar features. Elsewhere throughout the building façade, the eye is met for the most part by sets of two or three windows separated both above, below, and to the sides by light colored architectural precast.

The mechanical penthouse on the roof has an engineered insulating finish system mounted to structural steel which is not visible from street level.



The roofing system is composed of a hot fluid-applied roofing membrane directly above the concrete slab. Type VI rigid polystyrene insulation is placed above the roofing membrane. Finally, either a size 4 aggregate ballast ranging in size from 3/4'' to 1-1/2'' or two foot square roof pavers are placed above.

YES	NO	WORK SCOPE
Х		Demolition Required
Х		Support Excavation
	Х	Structural Steel Frame
Х		Cast in Place Concrete
Х		Precast Concrete
Х		Mechanical System
Х		Fire Suppression System
Х		Electrical System
	Х	Masonry
Х		Curtain Wall

Building Systems Summary

Demolition

The project is being constructed on the lot of the former 65 K Street building. 65 K Street was a two story masonry building with a basement. The building sat on 16,486 SF at the northwest corner of the lot. A fifty-two car asphalt parking lot wrapped around the south and east sides of the building. Demolition of the existing building was not included in the scope of work for the 77 K Street contract. The removal of 65 K Street, the asphalt parking lot, select utility lines, and certain site features took place prior to the general contractor selection for the new building.

Support of Excavation

In order to support the excavation of the three level underground parking garage, a system of piles, soldier beams, lagging, and tiebacks was utilized. Testing by ECS Mid Atlantic estimated that groundwater would be found between 18 an 39 feet below site grade, thus a temporary dewatering system was installed during excavation and construction with a discharge on the southeast corner of the building on 1st street. Discharge rates in the range of 50 to 100 gallons per minute were to be expected and additional sump pumps were needed as excavation progressed. A permanent sump pump is to be installed in the building as well.

Cast in Place Concrete

77 K Street utilizes a cast in place concrete structural system. The foundation is a 4'-0" thick, 4,000 psi concrete mat foundation resting on undisturbed soil with a minimum 4,000 psf bearing capacity. Below grade parking levels through the first floor are 9" reinforced



concrete flat slabs with 5-1/2" drop panels at select column locations. Floors two through the roof are 10" or 11" post-tensioned two-way slabs with 4-1/4" drop panels at all columns and around the slab perimeter. All post tensioned slabs have a force of between 130 and 1290 kips. The upper roof of the mechanical penthouse is framed using a combination of concrete and hollow structural steel members with a 8" one-way slab roof. Typical columns have a compressive strength of 5,000 psi with select columns having increased capacity up to 10,000 psi. Slab concrete capacities range from 3,000 psi at the lowest garage level to 5,000 psi for above grade slabs. Concrete is placed using two tower cranes, both staged within the footprint of the building.

Precast Concrete

The facade of the structure is a precast and glazing system. Precast panels are either exposed architectural cladding or support units with stone veneer. Precast pieces are being casted by Universal Concrete Products Corporation in Stowe, Pennsylvania and being erected by E.E. Marr Erectors. The southern and western facades will be erected utilizing the tower cranes already mobilized on site by the cast in place concrete contractor, Miller & Long. The precast on the northern and eastern facades will be erected using a mobile crane stationed on the sidewalk within the project worksite. Precast panels will be connected to the structure by embeds cast into the concrete during slab pours.

Mechanical System

In order to meet ventilation requirements, the three levels of underground garage parking each receive just over 49,000 CFMs of fresh air via intake and exhaust shafts and fans. Both the intake and exhaust shafts contain two propeller type fans at each garage level.

The first floor of 77 K Street contains two water cooled air conditioning units. One 7,200 CFM unit supplies air to the lobby of the building with a smaller 1890 CFM unit controlling air quality within the fitness center. The base building project has mechanical rooms located in the core of each floor with the primary mechanical equipment located on the roof of the building. Three 91,560 CFM cooling tower units supply chilled air to the building. One outside air, gas fired supply unit provides 50,000 CFMs to the mechanical rooms on each floor level. Additionally, each floor contains a 27,000 CFM air conditioning unit for distribution to VAV boxes located in the tenant spaces. At this time, only a limited number of variable air volume units will be installed in order to provide temporary heat to the building's tenant spaces. The majority of the VAV boxes will be stockpiled and installed during future tenant build out.

Stair pressurization shafts contain supply register diffusers at every second or third floor. Air volume at such diffusers is between 1,250 and 1,500. The top of stairwell two contains a 7500 CFM in line fan unit supplying outside air to the pressurization shaft. Stairwell one, which services only the above grade levels, contains a smaller 6,000 CFM fan.

Plenum spaces range in size from 29" in the core of the building to 22" in the tenant spaces. Typical supply ducts are 16" in height and reduce to a 12". Plenums in the tenant spaces also contain the recessed light fixtures, VAV units, and sprinkler pipes. They are concealed with two layers of gypsum drywall.



Fire Suppression System

The building is classified as a type 1-B structure and must adhere to the NFPA 13 standard for fire sprinklers. In order to reduce the fire risk to the building, above grade levels have a wet pipe fire suppression system, whereas the garage and loading dock areas have a typical dry pipe suppression system. A 6" incoming fire protection service is located on the P1 level. After passing through a double backflow preventer this service passes through a jockey and service pump to distribute water throughout the building, via two 1-1/2" standpipes with one located in each stairwell. The first level of the building contains a fire department siamese and pump test connection on the north elevation.

Electrical System

77 K Street contains a standard 408/277V and 208/120V four wire, three phase electrical system. The main switchgear room, located on the P1 level, contains three 4000A switchboards and a single 2000A switchboard. Two of the 4000A switchboards power the normal operations of the building with the third dedicated to emergency systems. The 2000A switchboard is dedicated to the retail space on the first floor. A 750kW diesel powered generator located on the roof powers the emergency systems in case of a power outage. Power is distributed throughout the building by 4000A plug-in feeder busways and panelboards ranging in size from 150 to 400 amps.

Curtain Wall

The exterior of the building is a precast cladding and glass curtain wall system. Precast panels are attached at each slab level and extend both horizontally as well vertically throughout the building. Insulating vision glass windows and shadow boxes contain metal mullions with metal mullions extending through precast elements to create a linear visual appearance. At the lower lobby entrances precast panels support a granite veneer. Precast and glazing system design will be closely coordinated between Universal Concrete Products Corporation and TSI Exterior Wall Systems, Inc. The curtain wall will be constructed using the tower cranes, mobile cranes, and from within the building.

Lighting System

The lighting in the building is a combination of metal halide and fluorescent fixtures. The metal halide lighting systems are located predominantly in the garage levels and loading dock areas. The linear and compact fluorescents are located in the core and tenant spaces. On the roof of the building there is an outdoor photocell facing north to control lighting levels within the building. Additionally, under consideration is the possibility of adding occupancy sensors with fifteen minute time-out delay settings to control lighting levels within the tenant spaces.

Transportation

The building contains two stairwells providing means of egress. Stairwell one, located on the northern side of the building core, services the above grade levels, floors one through the penthouse. Stairwell two extends from the P3 level through the penthouse, though the location of the shaft shifts when the stairwell reaches grade level.



The building also contains nine elevators. Two elevators service the garage, one large service elevator services floors one through eleven, five typical passenger elevators service floors one though eleven, and one additional passenger elevator services floors one through the penthouse. The six passenger elevators located in the core of the building have a rated capacity of 4000 pounds, the service elevator has a capacity of 4500 pounds, and the two garage elevators have a smaller capacity of 3500 pounds. All elevators travel at a rate of 350 feet per minute.

Estimate Summary

BUILDING CONSTRUCTION										
Construction Cost	\$41,005,150									
Cost Per Square Foot	\$91.30									

TOTAL PROJECT												
Including Land Acquisition and Design Fees												
Project Cost	\$125,000,000											
Cost Per Square Foot	\$278.32											

	BUILDING SYSTEM TOTAL AND SYSTEM PER SQUARE FOOT COSTS													
02000	Site Utilities	\$244,800	\$0.54											
02300	General Excavation	\$1,287,500	\$2.87											
03300	Cast in Place Concrete	\$11,296,000	\$25.15											
03450	Precast Concrete	\$2,950,000	\$6.57											
05000	Miscellaneous Metals	\$617,788	\$1.37											
07100	Waterproofing	\$201,432	\$0.45											
07500	Roofing	\$313,595	\$0.70											
08800	Curtainwall	\$3,734,000	\$8.31											
09250	Drywall	\$1,482,000	\$3.30											
14200	Elevators	\$2,334,000	\$5.20											
15000	Mechanical & Plumbing	\$4,764,000	\$10.61											
15300	Fire Protection	\$605,000	\$1.35											
16000	Electrical System	\$3,588,000	\$7.99											

Summary Schedule

A summary schedule outlining key project activities can be found on the following four pages. Activities are arranged by floor.

Todd Povell | Construction Management | Consultant: Dr. John Messner

K Street					-				C	lassic WBS La	yout					
tivity ID	Activity Name	Du	Start	Finish	-											
					Jan Feb Mar	20 Apr May Jun		Oct Nov Dec	Jan Feb Mar			p Oct Nov Dec	Jan Feb Mar		007	Oct
77 K Stre	et	952	03-Jan-05	18-Sep-08	out i co mai	Apr may our	our Aug ocp	Oct NOV Dec	our r co mar	Apr may our	our Aug oc		Vall I CD Mai	Apr may our	our Aug och	
and the second	Instruction	470	03-Jan-05	03-Nov-06							1	• 03-Nov-06, Pr	-Construction			
A1000	Initial Planning through Construction Documents	293	03-Jan-05	24-Feb-06					Initial P	anning through Construc	tion Documents					
A1010	General Contractor Selection	33	20-Sep-06	03-Nov-06							C	General Contr	actor Selection			
Constru	iction	468	28-Nov-06	18-Sep-08												
Excava	ation	126	28-Nov-06	24-May-07			*******************************							¥ 24-May-	07, Excavation	
A1020	Excavation			24-May-07										Excavat	lion	
A1030 A1040	Dewatering, Installation & Set-Up Sheeting & Shoring			26-Jan-07									Dewatering: In	stallation & Set Up Sheeting	& Shoring	
Substr				01-Aug-07									-		01-Aug-07, Si	ubstructure
Garage Leve		55	23-Mar-07	08-Jun-07									-	08-	Jun-07, Garage Level P3	
A1050 A1060				01-Jun-07 25-May-07									-	F/R/P Slab Wa	Mat Foundation aterproofing	
A1070	In Slab Plumbing			31-May-07										In Slat	Plumbing	
A1280 A1290	Erect Northern Tower Crane Erect Southern Tower Crane			16-Apr-07 08-Jun-07										Erect Northern Tov	ver Crane of Southern Tower Crane	
Garage Levi	el P2	45	17-Apr-07	19-Jun-07											9-Jun-07, Garage Level I	P2
A1080 A1090				19-Jun-07 01-Jun-07											R/P Walls, Columns, Sla or Wall Waterproofing	aos
Garage Leve	el P1	21	07-Jun-07	06-Jul-07											06-Jul-07, Garage Le	
A1100 A1110	F/R/P Walls, Columns, Slabs Exterior Wall Waterproofing			06-Jul-07 05-Jul-07											Exterior Wall Waterpr	
Building Ler A1120	vel 1		26-Jun-07	01-Aug-07 01-Aug-07											01-Aug-07, Bi	ui ding Lev
	Exterior Wall Waterproofing	16	26-Jun-07	17-Jul-07											Exterior Wall Wate	
Supers	structure Concrete	166	03-Aug-07	24-Mar-08												
A1140	Level 2			16-Aug-07											Level 2	
A1150 A1160	Level 3 Level 4			30-Aug-07 12-Sep-07											Evel	
A1170	Level 5	10	11-Sep-07	24-Sep-07												Level 5
A1180 A1190	Level 6 Level 7		21-Sep-07 03-Oct-07	04-Oct-07 16-Oct-07					n photos a funda o subserva da serva da ca							Level
A1200	Level 8	16	15-Oct-07													-
A1210 A1220	Level 9 Level 10		25-Oct-07 06-Nov-07	21-Nov-07 19-Nov-07												
A1230	Level 11			03-Dec-07			******					***	*****			
A1240	Main Roof		04-Dec-07													
A1250 A1260	Penthouse Roof Remove Southern Tower Crane			27-Dec-07 11-Feb-08												
A1270	Infill Slab Openings at Southern Tower Crane			25-Feb-08	1											
A1300 A1310	Remove Northern Tower Crane Infill Slab Openings at Southern Tower Crane	1	10-Mar-08 11-Mar-08	10-Mar-08 24-Mar-08	-											
Exterio	or Facade & Roof	140	20-Nov-07	02-Jun-08												
A1400	Substantially Watertight	0		09-Apr-08												
East Elevati A1320	Precast Using Mobile Crane	140 68		02-Jun-08 21-Feb-08									••••••			
A1330	Windows			02-Jun-08												
North Eleva A1340	Precast Using Mobile Crane	32	12-Dec-07	13-May-08 24-Jan-08												
A1350 South Eleva				13-May-08												
A1360	Precast Using Tower Crane	21	28-Dec-07	25-Jan-08												
A1370 West Elevat	Windows	77	28-Jan-08	13-May-08												
A1380	Precast Using Tower Crane	30	28-Jan-08	07-Mar-08												
A1390 Main Roof 8	Windows 5 Penthouse			13-May-08												
A1410		83	14-Jan-08	07-May-08 19-Mar-08												
A1420 A1430	Penthouse Steel, Framing, and EIFS Installation Penthouse Roofing Installation			19-Mar-08												
Core		177	05-Oct-07	80-nut-60												-
A1440	Elevator Installation			09-Jun-08												
A2930 A2940	PEPCO Work Energize Permanent Power	40	14-Jan-08	07-Mar-08 07-Mar-08												
A2950	Pull MCC Feeder Cable and Terminate	15		16-Apr-08												
A2960 Building Let	MEP System Start-Up			09-May-08 25-Mar-08									tin milan en constant rich now receipa			
Interiors		39	28-Dec-07													
A1460	0 CMU, Drywall, & Acoustical Ceiling Tile 0 Tile, Stone, Bathrooms, & Paint	19	25-Jan-08	20-Feb-08												
Mechanic	cal, Fire Protection, & Plumbing 0 Install Risers	100	05-Oct-07	21-Feb-08 08-Oct-07												n Insta
	0 Set SCU			16-Nov-07												
	0 Ductwork and Insulation Installation			17-Jan-08 23-Jan-08												
	0 Ductwork, Mechanical, Plumbing, & Sprinkler Rough-In 0 Set VAV's and Mechanical Connections to Equipment			23-Jan-08 07-Jan-08												
	0 Trim-Out & Plumbing Fixtures	4	18-Feb-08	21-Feb-08												
	0 Install Risers (Conduit) & Electrical, Fire Alarm Rough-In			25-Mar-08 22-Jan-08												
	0 Set Panel Boards and Transformers			29-Jan-08												
A1550	0 Terminations (Devices and Fire Alarm) and Trim Out	а	00-F6D-08	20-Feb-08												



					31-0	ct-07	19:55
	_						
			20	08			
t Nov Dec	Jan Feb	Mar Apr	May Jun	Jul	Aug Sep	Oct 8-Sep-08	Nov Dec 77 K Street
					1	8-Sep-08,	Construction
ture							
\$							
Level 1							
s, Slabs							
ng		24-Mar-	08, Superstructure	Concre	te	*******	
5							
vel 6							
Level 7 Level 8							
Level 0							
Level 10							
	ain Roof						
	Penthouse Roof	ove Southern T					
		a service a service ser	ngs at Southern T	ower Cra	ine		
			rthern Tower Crar		war Crano		
		mm 318	b Openings at So 02-Ju		erior Facade & Ro	of	
		• Sut	stantially Watertig	ht			
		ecast Using M	02-Ju		t Elevation		
	Pr	ecast using w	Windo	ws			
-	Precast U	sing Mobile Cri	13-May-08.	North El	evation		
	E	-	Windows				
	Precast U	sing Tower Cra	13-May-08. ane	South El	evation		
			Windows	Mast El	unting.		
		Precast Usin	g Tower Crane	TYEST EIG			
			Windows • 07-May-08, N	ain Roof	& Penthouse		
	C		Main Roof Int	stallation			
			e Steel, Framing, e Roofing Installa		Installation		
			7 09	un-08, C	ore		
	6		Elev	ator Inst	allation		
		PEPCO Wor Energize Per	k manent Power				
		P	ull MCC Feeder C	able and	Terminate		
		25-Mar-	MEP System 08, Building Leve	Start-Up	ina none contra estat un l		
	20 CMU	-Feb-08, Interio	ors sustical Celling Tile				
	Tile	e, Stone, Bathr	ooms, & Paint				
stall Risers	21	-Feb-08, Mech	anical, Fire Prote	tion, & P	lumbing		
I Set SCU							
	Ductwork an Ductwork,		stallation lumbing, & Sprinkl	er Roual	-In		
	Set VAV's and	Mechanical Co	nnections to Equi				
	a Tr	im-Out & Plum 25-Mar-	bing Fixtures 08, Electrical				
		rs (Conduit) &	Electrical, Fire Ala	rm Roug	h-In		
		I Boards and T rminations (De	Transformers vices and Fire Ala	rm) and	Trim Out		
	3432 AS			1.11.11.11.11	xc1h573	-	

Todd Povell | Construction Management | Consultant: Dr. John Messner

treet							U	lassic WBS Layou	at						51-0	ct-07
y ID Activity Name		Du Start	inish										Ver. 56			
				- Cables	20			2006		Orth New Dee			07	O at New Dee	2008	0.4
A1560 Install Bus Duct Risers & Major E	upment Terminations	4 20-Mar-08 2		n Feb Mar	Apr May Jun	Jui Aug Sep Oct Nov De	c Jan Feb Mar	Apr May Jun J	ul Aug Sep	Oct Nov Dec	Jan Feb Mar	Apr May Jun	Jui Aug Sep	Oct Nov Dec	Jan Feb Mar Apr May Jun Jul Aug Sep	lons
Building Level 3		117 17-Oct-07 :	7-Mar-08											-	27-Mar-08, Building Level 3	
A1570 Tile, Stone, Bathrooms, & Paint		42 31-Dec-07 20 30-Jan-08 2												20	26-Feb-08. Interiors Tile, Stone, Bathrooms, & Paint	
A1580 CMU, Drywall, & Acoustical Ceilin	Tile	32 31-Dec-07													CMU, Drywall, & Acoustical Celling Tile	11.53183
Mechanical, Fire Protection, & Plumbing		96 17-Oct-07												m Install Picars \$ M	27-Feb-08, Mechanical, Fire Protection, & Plumbing fechanical Piping Rough-In and Insulation	
A1590 Install Risers & Mechanical Piping A1600 Ductwork, Plumbing, & Sprinkler		4 17-Oct-07 1 17 31-Dec-07 1													Ductwork, Plumbing, & Sprinkler Rough-In	
A1610 Ductwork and Insulation Installati	a de line de la compañía de la comp	17 26-Dec-07													Ductwork and Insulation Installation	10000000000
A1620 Set VAV's and Mechanical Conne	tions to Equipment	3 10-Jan-08													Set VAV's and Mechanical Connections to Equipment Trim-Out & Plumbing Fixtures	
A1630 Trim-Out & Plumbing Fixtures A1640 Set SCU		4 22-Feb-08 2 2 15-Nov-07												I Set SCU		
Electrical		57 09-Jan-08	7-Mar-08												27-Mar-08, Electrical	
A1650 Install Risers (Conduit) & Electric A1660 Set Panel Boards and Transforme		13 09-Jan-08 3 3 30-Jan-08 0													Install Risers (Conduit) & Electrical, Fire Alarm Rough-In Set Panel Boards and Transformers	
A1650 Terminations (Devices and Fire A		10 13-Feb-08													Terminations (Devices and Fire Alarm) and Trim Out	
A1680 Install Bus Duct Risers & Major E	ulpment Terminations	4 24-Mar-08 2	7-Mar-08												Install Bus Duct Risers & Major Equipment Termina	tions
Building Level 4		111 29-Oct-07 3 42 02-Jan-08													28-Feb-08, Interiors	
A1690 Tile, Stone, Bathrooms, & Paint		19 04-Feb-08 3	8-Feb-08		******									*********	Tile, Stone, Bathrooms, & Paint	
A1700 CMU, Drywall, & Acoustical Cellin Mechanical, Fire Protection, & Plumbing	Tile	33 02-Jan-08 1 90 29-Oct-07												-	CMU, Dryvall, & Acoustical Ceiling Tile 29-Feb-08, Mechanical, Fire Protection, & Plumbing	
A1710 Install Risers & Mechanical Piping	Rough-In and Insulat													D Install Risers &	8 Mechanical Piping Rough-In and Insulation	
A1720 Ductwork, Plumbing, & Sprinkler		16 10-Jan-08													Ductwork, Plumbing, & Sprinkler Rough-In Ductwork and Insulation Installation	
A1730 Ductwork and Insulation Installati A1740 Set VAV's and Mechanical Conne		16 04-Jan-08 3 17-Jan-08 3													Ductwork and insulation installation Set VAV's and Mechanical Connections to Equipment	
A1750 Trim-Out & Plumbing Fixtures		4 26-Feb-08 2	the many participation of the												Trim-Out & Plumbing Fixtures	
A1760 Set SCU		2 15-Nov-07												Set SCU		
Electrical A1770 Install Risers (Condult) & Electric	Fire Alarm Rough-In	57 11-Jan-08 14 11-Jan-08													31-Mar-08, Electrical Install Risers (Conduit) & Electrical, Fire Alarm Rough-In	192222
A1780 Set Panel Boards and Transforme	'9	3 04-Feb-08 0	6-Feb-08												Set Panel Boards and Transformers	
A1790 Terminations (Devices and Fire A		9 18-Feb-08 2	and the second se												Terminations (Devices and Fire Alarm) and Trim Out	ations
A1800 Install Bus Duct Risers & Major E Building Level 5	upment Terminations	4 26-Mar-08 3 105 08-Nov-07												*	02-Apr-08, Building Level 5	auvna
A1810 Tile, Stone, Bathrooms, & Paint		44 03-Jan-08 0 19 07-Feb-08 0	4-Mar-08												V 04-Mar-08, Interiors Tile, Stone, Bathrooms, & Paint	
A1810 The stone, Bathrooms, a Paint A1820 CMU, Drywall, & Acoustical Cellin	Tile	35 03-Jan-08													CMU, Drywall, & Acoustical Ceiling Tile	
Mechanical. Fire Protection. & Plumbing		85 08-Nov-07 0	5-Mar-08											- Install Disa	05-Mar-08, Mechanical, Fire Protection, & Plumbing	
A1830 Install Risers & Mechanical Piping A1840 Ductwork, Plumbing, & Sprinkler		4 08-Nov-07 14 17-Jan-08 0												install Rise	ns & Mechanical Piping Rough-In and Insulation Ductwork, Plumbing, & Sprinkler Rough-In	
A1850 Ductwork and Insulation Installati		16 09-Jan-08	Characterization and the Contract of												Ductwork and Insulation Installation	
A1860 Set VAV's and Mechanical Conne	tions to Equipment	3 24-Jan-08													Set VAV's and Mechanical Connections to Equipment	
A1870 Trim-Out & Plumbing Fixtures A1880 Set SCU		4 29-Feb-08 0 2 08-Nov-07 0												I Set SCU	Trim-Dut & Plumbing Fixtures	
Electrical		56 16-Jan-08													v 02-Apr-08, Electrical	
A1890 Install Risers (Conduit) & Electric		14 16-Jan-08 (Install Risers (Condult) & Electrical, Fire Alarm Rough-In	
A1900 Set Panel Boards and Transform A1910 Terminations (Devices and Fire A		3 07-Feb-08 9 21-Feb-08 0													Terminations (Devices and Fire Alarm) and Trim Out	
A1920 Install Bus Duct Risers & Major E		4 28-Mar-08													install Bus Duct Risers & Major Equipment Termit	nations
Building Level 6		99 20-Nov-07 45 04-Jan-08													V 04-Apr-08, Building Level 6	
A1930 Tile, Stone, Bathrooms, & Paint		18 12-Feb-08 (6-Mar-08												Tile, Stone, Bathrooms, & Paint	
A1940 CMU, Drywall, & Acoustical Ceilir	1 Tile	36 04-Jan-08 2	A COLORADO AND A												CMU, Drywall, & Acoustical Ceiling Tile 11-Mar-08, Mechanical, Fire Protection, & Plumbing	
Mechanical, Fire Protection, & Plumbing A1950 Install Risers		81 20-Nov-07 2 20-Nov-07 2			******									1 Install Ri	sers	*******
A 1960 Ductwork, Mechanical, Plumbing,		11 24-Jan-08 0													Ductwork, Mechanical, Plumbing, & Sprinkler Rough-In	
A1970 Ductwork and Insulation Installati A1980 Set VAV's and Mechanical Conne		17 14-Jan-08 (3 31-Jan-08 (and a phone provide strength of the												Ductwork and Insulation Installation Set VAV's and Mechanical Connections to Equipment	
A1990 Trim-Out & Plumbing Fixtures	nona to Edupriterit	4 06-Mar-08													Trim-Out & Plumbing Fixtures	
A2000 Set SCU		2 20-Nov-07 2			******									I Set SCU		
A2010 Install Risers (Conduit) & Electric	Fire Alarm Rough-In	55 21-Jan-08 1 14 21-Jan-08 0													Install Risers (Conduit) & Electrical, Fire Alarm Rough-In	
A2020 Set Panel Boards and Transform		3 12-Feb-08	4-Feb-08												Set Panel Boards and Transformers	
A2030 Terminations (Devices and Fire A		9 25-Feb-08 0													Terminations (Devices and Fire Alarm) and Trim Out Install Bus Duct Risers & Major Equipment Termi	natione
A2040 Install Bus Duct Risers & Major E Building Level 7	upment Terminations	4 01-Apr-08 1 91 04-Dec-07												· ·	✓ 08-Apr-08. Building Level 7	1410115
Interiors		46 07-Jan-08	0-Mar-08												10-Nar-08, Interiors Tile, Stone, Bathrooms, & Paint	
A2050 Tile, Stone, Bathrooms, & Paint A2060 CMU, Drywall, & Acoustical Cellin	Tile	17 15-Feb-08 37 07-Jan-08													CMU, Drywall, & Acoustical Celling Tile	
Mechanical, Fire Protection, & Plumbing		71 04-Dec-07	1-Mar-08		*****			*****						·····	11-Mar-08, Mechanical, Fire Protection, & Plumbing	
A2070 Install Risers A2080 Ductwork, Mechanical, Plumbing,	Sprinkler Rough In	2 04-Dec-07 0 8 31-Jan-08												I Insta	Il Risers Ductwork, Mechanical, Plumbing, & Sprinkler Rough-In	
A2090 Ductwork mechanical Plumbing. A2090 Ductwork and Insulation Installati		19 17-Jan-08													Ductwork and Insulation Installation	
A2100 Set VAV's and Mechanical Conne		3 07-Feb-08	1-Feb-08												Set VAV's and Mechanical Connections to Equipment	
A2110 Trim-Out & Plumbing Fixtures A2120 Set SCU		4 06-Mar-08 2 04-Dec-07 0												I Set S	Trim-Out & Plumbing Fixtures	
Electrical		54 24-Jan-08	8-Apr-08												V08-Apr-08, Electrical	
A2130 Install Risers (Conduit) & Electric		14 24-Jan-08	2-Feb-08												Install Risers (Conduit) & Electrical, Fire Alarm Rough-In Set Panel Boards and Transformers	
A2140 Set Panel Boards and Transform A2150 Terminations (Devices and Fire A		3 15-Feb-08 3 9 27-Feb-08 3													Set Panel Boards and Transformers Terminations (Devices and Fire Alarm) and Trim Out	
A2160 Install Bus Duct Risers & Major E															Install Bus Duct Risers & Major Equipment Term	ninations
Building Level 8		81 20-Dec-07	0-Apr-08												10-Apr-06, Duilding Level 6 12-Mar-08, Interiors	
A2170 Tile, Stone, Bathrooms, & Paint		47 08-Jan-08 16 20-Feb-08													Tile, Stone, Bathrooms, & Pant	
A2180 CMU, Drywall, & Acoustical Cellin	Tile	38 08-Jan-08 3	8-Feb-08												CMU, Brywall, & Acoustical Ceiling Tile	
Mechanical, Fire Protection, & Plumbing A2190 Install Risers		61 20-Dec-07 2 20-Dec-07												1	13-Mar-08, Mechanical, Fire Protection, & Plumbing Install Risers	
A2200 Ductwork, Mechanical, Plumbing.	Sprinkler Rough-In	10 05-Feb-08													Ductwork, Mechanical, Plumbing, & Sprinkler Rough-In	
A2210 Ductwork and Insulation Installation		21 22-Jan-08											1		Ductwork and Insulation Installation	



Todd Povell | Construction Management | Consultant: Dr. John Messner

Street								C	Classic WBS La	yout					31-Oct-07 1
vity ID	Activity Name	Du Start	Finish												
				lan Eab Mar	20		Oct Nov Doc	lan Eab Mar			Oct Nov Doc	lan Ech Mar	2007		2008 v Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct N
A222	0 Set VAV's and Mechanical Connections to Equipment	3 14-Feb-08	18-Feb-08		Apr May Jun	Jui Aug Sep		Jan Feb Mar		Jui Aug Sep		Jan Feb Mar	Apr May Jun J	ui Aug Sep Oct No	Set VAV's and Mechanical Connections to Equipment
	0 Trim-Out & Plumbing Fixtures	4 10-Mar-08													Trim-Out & Plumbing Fixtures
Electrica	0 Set SCU	2 20-Dec-07 53 29-Jan-08													10-Apr-08, Electrical
	0 Install Risers (Conduit) & Electrical, Fire Alarm Rough-In	15 29-Jan-08	18-Feb-08												Install Risers (Conduit) & Electrical, Fire Alarm Rough-In Set Panel Boards and Transformets
	0 Set Panel Boards and Transformers 0 Terminations (Devices and Fire Alarm) and Trim Out	9 29-Feb-08	22-Feb-08 12-Mar-08												Terminations (Devices and Fire Alarm) and Trim Out
	0 Install Bus Duct Risers & Major Equipment Terminations														Install Bus Duct Risers & Major Equipment Terminations 14-Apr-08, Building Level 9
Building Le	wel 9	66 14-Jan-08 46 14-Jan-08	14-Apr-08 17-Mar-08												17-Mar-08, Interiors
	0 Tile, Stone, Bathrooms, & Paint	16 25-Feb-08													Tile, Stone, Bathrooms, & Paint CMU, Drywall, & Acoustical Ceiling Tile
	0 CMU, Drywall, & Acoustical Ceiling Tile cal, Fire Protection, & Plumbing	37 14-Jan-08 47 14-Jan-08	18-Mar-08												▼ 18-Mar-08, Mechanical, Fire Protection, & Plumbing
	0 Install Risers 0 Ductwork, Mechanical, Plumbing, & Sprinkler Rough-In		15-Jan-08 21-Feb-08												Install Risers Ductwork, Mechanical, Plumbing, & Sprinkler Rough-In
	0 Ductwork and Insulation Installation	23 25-Jan-08													Ductwork and Insulation Installation
	0 Set VAV's and Mechanical Connections to Equipment		25-Feb-08												Set VAV's and Mechanical Connections to Equipment T(im-Out & Plumbing Fixtures
	0 Trim-Out & Plumbing Fixtures 0 Set SCU	4 13-Mar-08 2 14-Jan-08													Set SCU
Electrica	A Contraction of the second	52 01-Feb-08	14-Apr-08												14-Apr-09, Electrical Install Risers (Conduit) & Electrical, Fire Alarm Rough-In
	0 Install Risers (Conduit) & Electrical, Fire Alarm Rough-In 0 Set Panel Boards and Transformers	17 01-Feb-08 3 25-Feb-08													Set Panel Boards and Transformers
A239	0 Terminations (Devices and Fire Alarm) and Trim Out	9 05-Mar-08	17-Mar-08												Terminations (Devices and Fire Alarm) and Trim Out
A240 Building Le	0 Install Bus Duct Risers & Major Equipment Terminations	4 09-Apr-08													Install Bus Duct Risers & Major Equipment Terminations 16-Apr-08, Building Level 10
Interiors		48 15-Jan-08	20-Mar-08									-			20-Mar-08, Interiors
	0 Tile, Stone, Bathrooms, & Paint 0 CMU, Drywall, & Acoustical Ceiling Tile	16 28-Feb-08 39 15-Jan-08													Tile, Stone, Bathrooms, & Paint CMU, Drywall, & Acoustical Ceiling Tile
Mechani	cal, Fire Protection, & Plumbing	50 14-Jan-08	21-Mar-08												21-Mar-08, Mechanical, Fire Protection, & Plumbing
	0 Install Risers 0 Ductwork, Mechanical, Plumbing, & Sprinkler Rough-In		17-Jan-08 27-Feb-08												Ductwork, Mechanical, Plumbing & Sprinkler Rough-In
	0 Ductwork and Insulation Installation		04-Mar-08												Ductvork and Insulation Installation
	0 Set VAV's and Mechanical Connections to Equipment		03-Mar-08												Set VAV's and Mechanical Connections to Equipment Trim-Out & Plumbing Fixtures
	0 Trim-Out & Plumbing Fixtures 0 Set SCU	4 18-Mar-08 2 14-Jan-08	21-Mar-08												I Set SCU
Electrica	1	51 06-Feb-08	16-Apr-08												16-Apr-08, Electrical Install Risers (Conduit) & Electrical, Fire Alarm Rough-In
	0 Install Risers (Conduit) & Electrical, Fire Alarm Rough-In 0 Set Panel Boards and Transformers	19 06-Feb-08 3 28-Feb-08													Set Panel Boards and Transformers
A251	0 Terminations (Devices and Fire Alarm) and Trim Out	9 10-Mar-08	20-Mar-08												Terminations (Devices and Fire Alarm) and Trim Out
A252	0 Install Bus Duct Risers & Major Equipment Terminations	4 11-Apr-08 68 16-Jan-08													Install Bus Duct Risers & Major Equipment Terminations 18-Apr-08, Building Level 11
Interiors		50 16-Jan-08	25-Mar-08												25-Mar-08, Interiors Tile, Stone, Bathrooms, & Paint
	0 Tile, Stone, Bathrooms, & Paint 0 CMU, Drywall, & Acoustical Ceiling Tile	16 04-Mar-08 41 16-Jan-08	25-Mar-08												CMU, Drywall, & Acoustical Gelling Tile
Mechani	cal, Fire Protection, & Plumbing	51 16-Jan-08	26-Mar-08												26-Mar-08, Mechanical, Fire Protection, & Plumbing
	0 Install Risers 0 Ductwork, Mechanical, Plumbing, & Sprinkler Rough-In	2 18-Jan-08 13 18-Feb-08	21-Jan-08 05-Mar-08												Ductvork, Mechanical, Plumbing, & Sprinkler Rough-In
	0 Ductwork and Insulation Installation	27 04-Feb-08													Ductwork and Insulation Installation
	0 Set VAV's and Mechanical Connections to Equipment	3 06-Mar-08 4 21-Mar-08	10-Mar-08												Set VAV's and Mechanical Connections to Equipment Trim-Out & Plumbing Fixtures
	0 Trim-Out & Plumbing Fixtures 0 Set SCU	2 16-Jan-08													Set SCU
Electrica	Install Risers (Conduit) & Electrical, Fire Alarm Rough-In	50 11-Feb-08													18-Apr-08, Electrical Install Risers (Conduit) & Electrical, Fire Alarm Rough-In
	0 Set Panel Boards and Transformers		06-Mar-08												Set Panel Boards and Transformers
	0 Terminations (Devices and Fire Alarm) and Trim Out		25-Mar-08												Terminations (Devices and Fire Alarm) and Trim Out
A264	0 Install Bus Duct Risers & Major Equipment Terminations	4 15-Apr-08													Install Bus Duct Risers & Major Equipment Termination 12-May-08, Penthouse
Interiors	0 Delet	40 17-Mar-08	09-May-08												09-May-08, Interiors
	0 Paint 0 Drywall & Acoustical Celling Tile	2 08-May-00 38 17-Mar-08													Drywall & Acoustical Ceiling Tile
Mechani	cal, Fire Protection, & Plumbing	86 14-Jan-08													Install Risers 12-May-08, Mechanical, Fire Protection, & Plumb
	0 Install Risers 0 Ductwork, Mechanical, Plumbing, & Sprinkler Rough-In	2 22-Jan-08 65 21-Jan-08													Ductwork, Mechanical, Plumbing, & Sprinkler Rough-In
A269	0 Ductwork and Insulation Installation	58 07-Feb-08	28-Apr-08												Ductwork and Insulation Installation
	0 Set Fans & Louvers and Mechanical Connections to Eq. 0 Trim-Out & Connect Roof Drains	5 31-Mar-08 16 21-Apr-08													Set Fans & Louvers and Mechanical Connections to Equipm Trim-Out & Connect Roof Drains
	0 Set Cooling Towers & Major Mechanical Equipment	5 14-Jan-08													Set Cooling Towers & Major Mechanical Equipment
Electrica	Install Risers (Conduit) & Electrical, Fire Alarm Rough-In	38 20-Mar-08													12-May-08, Electrical Install Risers (Conduit) & Electrical, Fire Alarm Rough-In
	0 Set MCC, Panel Boards, &Transformers	10 20-Mar-08													Set MCC, Panel Boards, & Transformers
	0 Terminations (Devices and Fire Alarm) and Trim Out	3 08-May-0													Terminations (Devices and Fire Alarm) and Trim
	0 Major Equipment Terminations	5 14-Apr-08 133 28-Dec-0													Major Equipment Terminations
	ng Level 1 (Lobby)														01-Jul-08, Lobby
Lobby Interiors		133 28-Dec-0 130 28-Dec-0	26-Jun-08												26-Jun-08, Interiors
	0 Stone, Ornamental Metals, Millwork, Handrails, Floorin 0 Drywall & Acoustical Ceiling Tile	. 62 02-Apr-08 101 28-Dec-07	26-Jun-08												Stone, Ornamental Metals, Millwork, Drywall & Acoustical Ceiling Tile
Mechani	cal, Fire Protection, & Plumbing	78 14-Mar-08	01-Jul-08												O1-Jul-08, Mechanical, Fire Protect
A279	0 Mechanical & Sprinkler Rough-In 0 HVAC Trim-Out	5 14-Mar-08	20-Mar-08												Mechanical & Sprinkler Rough-In
Electrica	1	3 27-Jun-08 123 11-Jan-08	01-Jul-08						+						V01-Jul-08, Electrical
A281	0 Electrical Wall Rough-In	3 11-Jan-08	15-Jan-08												Electrical Wall Rough-In
	0 Electrical Ceiling Rough-In 0 Trim Out	3 14-Mar-08 3 27-Jun-08													Electrical Ceiling Rough-In
Sitewo		194 13-Sep-0													v 10-Jun-08, Sitework
A2840	Site Utilities	35 13-Sep-0	31-Oct-07											Site	Utilities
A2850	Streetlights	7 10-Mar-08	18-Mar-08												Streetlights
A2860	Site Concrete and Landscaping	46 08-Apr-08	10-Jun-08												Site Concrete and Landscaping



Todd Povell | Construction Management | Consultant: Dr. John Messner

7 K Street									Classic WBS Layout																		
Activity ID	Activity Name	Du	. Start	Finish		2005 2006									2007												
					Jan Feb Ma	r Apr May Jun	Jul	Aug Sep	Oct I	Nov Dec	Jan F	eb Mar	Apr	May Jun	Jul	Aug Sep	Oct	Nov Dec	Jan	Feb Mar	Apr			Aug Sep	Oct		
Inspec	tions and Close-Out	83	27-May-08	18-Sep-08									_ · ·														
A2870	As-Builts, O&M's, Warranties	20	27-May-08	23-Jun-08																							
A2880	Final Inspections	11	02-Jul-08	16-Jul-08					1		1						1		-						1		
A2890	Substantial Completion	0		17-Jul-08																							
A2900	System Training and MEP Commissioning	31	01-Jul-08	12-Aug-08																							
A2910	Punchlist	45	18-Jul-08	18-Sep-08																							
A2920	Final Completion	0		18-Sep-08																							



31-Oct-07 19:55 As-Builts, OSM's, Warantes Flinal Inspections • Substantial Completion System Training and MEP Comm. Punchist • Final Completion 2008 Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec