DANIEL ALEXANDER | CM | DR. MESSNER



TECHNICAL REPORT 1

DOCTORS COMMUNITY HOSPITAL LANHAM, MD

SEPTEMBER 29, 2008



PROJECT TEAM

- Owner: Doctors Community HOSPITAL
- -CM: GILBANE BUILDING COMPANY
- -ARCHITECT: CR GOODMAN Associates
- -STRUCTURAL: MINCIN-PATEL-MILAND
- -Mech & Electrical: Leach WALLACE ASSOCIATES

STRUCTURE

- -Steel columns and Beams Built up ON EXISTING STEEL CONSTRUCTION
- -CONCRETE FOOTERS WITH GRADE BEAMS (\sim 50% EXISTING, 50% NEW)
- LIGHTWEIGHT CONCRETE ON METAL DECK TO FORM COMPOSITE SLAB
- -Non-load bearing brick on metal STUD FACADE

MECHANICAL

- -ROOF MOUNTED MECHANICAL PLANT
- 90,000 CFM AIR HANDLER FEEDING VAV BOXES
- -425 TON CHILLER
- DRAW THROUGH 425 TON COOLING TOWER
- -(3) 2,678 MBH DUEL FUEL BOILERS
- -Medical Gas and Vacuum tubes FEED EACH PATIENT ROOM

PROJECT OVERVIEW

- FUNCTION: MEDICAL HOSPITAL
- SIZE: 270,000 SF EXPANSION
- Cost: \$42 MILLION
- DELIVERY: DESIGN-BID-BUILD WITH A GMP FROM A CM@RISK
- OCCUPANT: DOCTORS COMMUNITY HOSPITAL
- -DATES: NOV 'O7- MARCH'10 ELECTRICAL/LIGHTING
- 1,200 AMP SWITCHGEAR
- -(2) 2,500 Amp switchboards
- -1,250 KVA EMERGENCY GENERATOR FED BY 5,000 GAL FUEL TANK
 - Power fed vertically through STACKED ELECTRICAL ROOMS WITH MULTIPLE TRANSFORMERS IN EACH
- LIGHTING TYPICALLY CONSISTS OF RECESSED 2x4 FLUORESCENT LIGHTS

Special Considerations

 Construction is occuring directly ABOVE AND ADJACENT TO AN OPERA-TIONAL HOSPITAL. DUTAGES MUST BE COORDIANTED WITH OWNER, AND SPE-CIAL DUST AND DEBRIS CONTROL IS NEEDED IN RENOVATION PORTIONS

ARCHITECTURE

- Patient rooms arranged on the OUTSIDE WITH SUPPORT AREAS IN THE CENTER ELLOPIG
- ·Brick facade with split-face CMU BANDING AND CAST STONE WINDOW
- -ROOF: BUILT UP STYRENE-BITUMEN-Styrene system on 3" POLYSTYRENE FOAM

Daniel Alexander

CONSTRUCTION MANGEMENT

TABLE OF CONTENTS

EXECUTIVE SUMMARY	2
PROJECT SCHEDULE SUMMARY	3
BUILDING SYSTEMS SUMMARY	
PROJECT COST EVALUATION	
SITE PLAN OF EXISTING CONDITIONS	
LOCAL CONDITIONS	
CLIENT INFORMATION	
PROJECT DELIVERY SYSTEMS	
STAFFING PLAN	
APPENDIX I	_
APPENDIX II	
APPENDIX III	
····	

EXECUTIVE SUMMARY

TECHNICAL REPORT 1 FOR THE DOCTORS COMMUNITY HOSPITAL IN LANHAM, MD EXAMINES THE SCHEDULE, COSTS, AND SYSTEMS EMPLOYED BY GILBANE CONSTRUCTION AND THE OWNER, DCH.

DCH COMMISSIONED THE PROJECT IN ORDER TO EXPAND ITS FACILITY TO BETTER SERVE THE NEEDS OF THE REGION. AN 18 MONTH DESIGN PHASE TRANSITIONED INTO A 28 MONTH CONSTRUCTION SCHEDULE SLATED FOR GROUND BREAKING IN NOVEMBER 2007, WITH PHASE 1 FINISHING IN FEBRUARY '09, PHASE 2 WRAPPING UP IN SEPTEMBER '09 AND THE FINAL PHASE COMPLETED IN MARCH '10. A UNIQUE ASPECT OF THIS PROJECT IS IT IS NOT ITS OWN STANDALONE WING WITH ONE OR TWO CONNECTION POINTS TO THE EXISTING STRUCTURE, BUT RATHER AN EXTENSION OF AN EXISTING TOWER, AND AN OVERBUILD ON TOP OF A TWO STORY EXISTING STRUCTURE. THE HOSPITAL IS EXPECTED TO MAINTAIN FULL FUNCTIONALITY DURING CONSTRUCTION, WHICH CAN IMPACT SCHEDULE AND PRODUCTIVITY IF CERTAIN PRECAUTIONS ARE NOT TAKEN.

The building is to house a 5 story patient tower, expand the $1^{\rm st}$ floor emergency department, and create second floor shell space (fitout yet to be determined). Brick on metal stud was the façade of choice for this structure. It will have a standalone mechanical plant placed on the roof and electrical service will be fed off of existing switchboards. N+1 redundancy will be incorporated in the form of a 1000 kW diesel generator.

GILBANE HAS BEEN CONTRACTED AS THE CM @ RISK FOR THIS PROJECT UNDER A GMP. THEY WERE BROUGHT ON EARLY IN THE PROJECT FOR CONSTRUCTABILITY REVIEWS AND INITIAL SCHEDULE ANALYSES.

PROJECTED COSTS AT THE START OF THE ENDEAVOR TOTALED ROUGHLY \$31 MILLION. BUT THOUGH A CHANGE ORDER FOR ADDED SCOPE (THE $1^{\rm ST}$ FLOOR FITOUT) THE CURRENT TOTAL IS ROUGHLY \$35 MILLION WITH MORE ADDED SCOPE (THE $2^{\rm ND}$ FLOOR FITOUT) STILL EXPECTED.

THE SITE IS EXTREMELY CONGESTED, AND WILL POSE AN OBSTACLE THROUGHOUT THE PROJECT. THIS AREA IS ONE WHICH MAY WARRANT FOCUS FOR A THESIS TOPIC. THE OWNER ACTUALLY PASSED UP THE OPPORTUNITY TO BUY ADJACENT LAND AND THIS MAY BE WORTH INVESTIGATING THE IMPACTS IN TERMS OF SCHEDULE AND COST.

PROJECT SCHEDULE SUMMARY

THE SCHEDULE FOR DCH IS RELATIVELY STRAIGHT FORWARD IN ITS NATURE. THE SUMMARY GANTT CHART IS SHOWN ON THE NEXT PAGE IN FIGURE 1. DESIGN PHASE ACTIVITIES LASTED ROUGHLY 17-18 MONTHS, WHICH ACCORDING TO THE GILBANE APM, IS AVERAGE FOR A MEDIUM SIZE HOSPITAL EXPANSION. THE NTP CAME IN NOVEMBER OF 2007, WHICH HAD SITEWORK AND EXCAVATION BEING COMPLETED IN THE MIDDLE OF A MARYLAND WINTER. WHILE NOT ALWAYS HEAVY WITH SNOWFALL, THE WEATHER DOES TEND TO BE SUBPAR WORKING CONDITIONS BETWEEN THE SNOW AND RAIN WHICH CAN HURT PRODUCTIVITY.

Substructure work is set to begin in March of 2008, once weather has calmed down and begins being more favorable for construction, although can run the risk of a rainy spring season. The substructure finishes out in the Middle of May, allowing the superstructure to start. Steel erection begins June 2^{ND} , right at the start of summer, which aside from being hot and humid in Maryland, the weather generally will be amenable to grane operation and steel placement. Congrete decks will be following behind the metal deck, and in this heat extra care will need to be taken to keep the congrete usable by mixing with ice to stay at an acceptable temperature and ensure proper curing.

THE BUILDING BECOMES WATER TIGHT AT THE VERY BEGINNING OF DECEMBER AT WHICH POINT UTILITY TRADES CAN BEGIN THEIR WORK. MECHANICAL, HAVING ALREADY SET THE ROOF TOP MECHANICAL PLANT IN PLACE BEGINS FROM THE BOTTOM UP WITH THE REST OF THEIR ROUGH-IN. THEY ARE FOLLOWED BY ELECTRICAL, PLUMBING, AND SPRINKLER TRADES AND LASTLY THE INTERIOR PARTITIONS AND OTHER FINISH TRADES.

THREE PHASED OCCUPANCIES ARE INVOLVED IN THIS SCHEDULE. FIRST, THE EMERGENCY DEPARTMENT EXPANSION NEEDS TO BE AVAILABLE BY THE END OF FEBRUARY '09 DUE TO OWNER REQUESTS. THE REMAINDER OF THE EXPANSION WILL BE ONLINE BY EARLY SEPTEMBER '09. RENOVATIONS ARE SLATED TO BEGIN AT THIS TIME WITH EACH FLOOR BEING COMPLETED ONE AT A TIME, AND ALL RENOVATIONS ARE FINISHED BY MARCH '10.

FIGURE 1- DOCTOR'S COMMUNITY HOSPITAL SUMMARY SCHEDULE

ID	0	Task Name	Duration	Start	Finish		010
1		Design Phase	380 days	Thu 6/1/06	Wed 11/14/07	NDJFMAMJJASONDJFMAMJJASONDJFMAMJJASONDJFMAMJJASONDJF Design Phase 11/14/07	F M A M J
2		Procurment/PreCon	183 days	Mon 3/5/07	Wed 11/14/07	Procurment/PreCon 11/14/07	
3		NTP		Wed 11/14/07		NTP ♦ 11/14/07	
4		Sitework/Exterior Demo/Excavation/Unc	,	Mon 11/19/07	Fri 3/28/08	Sitework/Exterior Demo/Excavation/Underpin 3/28/08	
5		Site Utilities (To Building Footprint)	•	Mon 11/19/07	Fri 2/8/08	Site Utilities (To Building Footprint) 2/8/08	
6	+	Bldg Utilities (In Building Foot Print)	30 days	Mon 2/11/08	Fri 3/21/08	Bldg Utilities (In Building Foot Print) 3/21/08	
7		Substructure	53 days	Wed 3/5/08	Fri 5/16/08	Substructure 5/16/08	
8		Caissons	18 days	Wed 3/5/08	Fri 3/28/08	Caissons 3/28/08	
9	+	Footings/Foundation Wall	40 days	Mon 3/24/08	Fri 5/16/08	Footings/Foundation Wall 5/16/08	
10		Superstructure	85 days	Mon 6/2/08	Fri 9/26/08	Superstructure 9/26/08	
11		Strucutral Steel	51 days	Mon 6/2/08	Mon 8/11/08	Strucutral Steel 8/11/08	
12		Welding/Detailing	25 days	Mon 7/21/08	Fri 8/22/08	Welding/Detailing 8 22/08	
13		Metal Decks	30 days	Mon 8/4/08	Fri 9/12/08	Metal Decks 9/12/08	
14		Concrete Decks	30 days	Mon 8/18/08	Fri 9/26/08	Concrete Decks 9/26/08	
15		Top Out	0 days	Mon 8/11/08	Mon 8/11/08	Top Out ♦ 8 11/08	
16		Place Rooftop Mech Plant	5 days	Tue 9/2/08	Mon 9/8/08	9/2/08 🛊 9/8/08	
17		Façade/Exterior	60 days	Mon 9/15/08	Fri 12/5/08	Façade/Exterior ===================================	
18		Exterior CFMF	20 days	Mon 9/15/08	Fri 10/10/08	9/15/08 🍵 10/10/08	
19		Brick Façade	40 days	Mon 9/29/08	Fri 11/21/08	9/29/08 11/21/08	
20		Windows	20 days	Mon 11/10/08	Fri 12/5/08	11/10/08 👛 12/5/08	
21		Roofing	20 days	Mon 10/6/08	Fri 10/31/08	10/6/08 😑 10/31/08	
22		Watertight	0 days	Fri 12/5/08	Fri 12/5/08	Watertight ♦ 12/5/08	
23		Interior Trades	175 days	Mon 11/17/08	Fri 7/17/09	Interior Trades 🐙 7/17/09	
24		1st floor/Emergency Room Fit or	75 days	Mon 11/17/08	Fri 2/27/09	1st floor/Emergency Room Fit out 2/27/09	
30		Activate and Occupy ED	0 days	Fri 2/27/09	Fri 2/27/09	Activate and Occupy ED ♦ 2/27/09	
31		2nd Floor Fit out	75 days	Mon 12/22/08	Fri 4/3/09	2nd Floor Fit out 4/3/09	
37		3rd Floor Fit-out	85 days	Mon 1/26/09	Fri 5/22/09	3rd Floor Fit-out \$\square\$ 5/22/09	
43		4th Floor Fit out	85 days	Mon 3/2/09	Fri 6/26/09	4th Floor Fit out \$\square\$ 6/26/09	
49		5th Floor Fit out	75 days	Mon 4/6/09	Fri 7/17/09	5th Floor Fit out	
55		Activate and Occupy Addition	0 days	Fri 9/4/09	Fri 9/4/09	Activate and Occupy Addition ♦ 9/4/09	
56		Renovations	165 days	Mon 7/20/09	Fri 3/5/10	Renovations	3/5/10
57		2nd Floor	30 days	Mon 7/20/09	Fri 8/28/09	2nd Floor 8/28/09	
58		3rd Floor	45 days	Mon 8/31/09	Fri 10/30/09	3rd Floor 10/30/	09
59		4th Floor	45 days	Mon 11/2/09	Fri 1/1/10	4th Floor 🧫 1/	/1/10
60		5th Floor	45 days	Mon 1/4/10	Fri 3/5/10	5th Floor	3/5/10
61		Renovations Complete and Occupied	0 days	Fri 3/5/10	Fri 3/5/10	Renovations Complete and Occupied	3/5/10

BUILDING SYSTEMS SUMMARY

Scope of Work	SUMMARY FEATURES
DEMOLITION	DEMOLITION OCCURS IN TWO MAIN PHASES EXTERIOR PREP- TO READY EXISTING SITE AND PORTIONS OF EXISTING FAÇADE FOR NEW STRUCTURE (BRICK AND ASPHALT) INTERIOR RENOVATIONS- AS THE 2 ND THROUGH 5 TH FLOORS IN THE EXISTING STRUCTURE ARE RENOVATED (DRYWALL, CASEWORK, PARTITIONS, LIMITED CONCRETE DECK FILL)
	ASBESTOS AND LEAD PAINT ABATEMENT IS EXPECTED IN THE INTERIOR PORTION OF RENOVATIONS. AS OF YET, QUANTITY IS UNDEFINED FOR BOTH. (ORIGINAL CONSTRUCTION IN 1970'S) EXPECTING TO FIND ASBESTOS IN EXISTING PIPE INSULATION EXPECTING LEAD PAINT IN MOST/ALL PAINTED ROOMS CONTRACTOR IS EXPECTED TO REMOVE ANY ASBESTOS ENCOUNTERED, EVEN IF IT IS NOT FRIABLE CONTRACTOR TO SALVAGE EXISTING HOSPITAL ITEMS IN RENOVATION AREA AS DIRECTED BY OWNER. CONTRACTOR IS RESPONSIBLE FOR ALL SALVAGED MATERIAL UNTIL REINSTALLED.
STRUCTURAL STEEL	W-SHAPE COLUMNS AND BEAMS PLACED ON CONCRETE FOOTERS SIZE RANGE W8X30 TO W12X170 PLACED FROM NORTH TO SOUTH VIA A 130 TON TRUCK CRANE TON TRUCK CRANE THE CRANE USES TWO LOCATIONS AS SHOWN IN FIGURE 2 BELOW. FIGURE 2- CRANE LOCATION FOR STEEL ERECTION

Scope of Work	SUMMARY FEATURES
	COMPOSITE SLAB ON METAL DECK WITH SHEAR
	STUDS
	O LIGHTWEIGHT CONCRETE 5" SLAB (3 1/2"
	Topping slab on ½" metal deck)
	O 6x6x8/8 WWM TYPICAL THROUGHOUT FOR
	DECK REINFORCEMENT
	Moment resistance: 6 K-frames located at 6 Different column lines down center of
	BUILDING
	O FULL PENETRATION MOMENT WELDS AT
CAST IN PLACE	GIRDERS TYING INTO THESE FRAMING UNITS
CONCRETE	Caissons, column footers, foundation walls, slab on grade, concrete on metal deck
	DRILLED CAISSONS BEING USED DOWN TO A
	DEPTH OF 50' AT 11 LOCATIONS
	O NO FORMWORK USED; DRILLED AND PLACED DIRECT INTO GROUND (GROUND IS
	FORMWORK)
	O PLAGED VIA PUMP
	o 4000 PSI
	\circ (14) #11 REBAR REINFORGING WITH #3 RING
	TIES 12" O.C. FOR LENGTH OF CAISSON
	FOUNDATION WALLS AND FOOTERS
	0 FORMWORK
	■ FOOTERS- OCCASIONAL USE OF STICK
	BUILT FORM WORK. OFTEN USED
	GROUND AS FORM WORK. FOUNDATION WALL- REUSABLE ,
	PREFABRICATED FORM WORK
	O PLAGEMENT
	■ Footers- Direct Chute
	■ FOUNDATION WALL- PUMP
	o 3000 PSI
	O REINFORCEMENT RANGES FROM #3-#12
	DEPENDING ON LOCATION
	• SLAB ON GRADE
	O ZX EDGE FORMWORK
	O PLACED VIA DIRECT CHUTE
	O 4000 PSI CONCRETE ON 4" CRUSHED GRAVEL FILL AND VAPOR BARRIER
	O 6x6x8/8 WWM REINFORGEMENT
	CONGRETE ON METAL DECK
	O POUR STOPS INCORPORATED IN STEEL WORK
	O PLAGED VIA PUMP
	o 4000 PSI

SCOPE OF WORK	SUMMARY FEATURES
MECHANICAL SYSTEMS	MECHANICAL PLANT FOR ALL AIR SYSTEM LOCATED
	ON ROOF O CHILLER, BOILERS, COOLING TOWER, AHU ALL EXTREMELY LARGE; MUST BE CRANED IN TO PLACE AHU TO BE FABRICATED AND DELIVERED IN 5 PIECES O AHU FED BY CHILLED AND HOT WATER LOOPS
	• TWO MECHANICAL SHAFTS USED FOR DISTRIBUTION ○ ONE AT NORTH END, ONE AT SOUTH END ○ ADDITIONAL ISOLATION EXHAUST AIR FROM SELECTED ROOMS AT ENDS OF WINGS ON NORTH END. ■ HIGH PRESSURE EXHAUST DUCTWORK ○ VAV'S (SOME WITH REHEAT) ARE USED THROUGHOUT THE FACILITY ○ LINEAR RADIANT HEATING PANELS ARE INCORPORATED AT ALL WINDOWS IN THE PATIENT ROOMS • MEDICAL GAS, VACUUM (FED FROM ROOFTOP
	COMPRESSORS) & OXYGEN (FED FROM ON SITE OXYGEN PLANT) LINES FEED EACH PATIENT ROOM
	EACH PATIENT ROOM HAS PRIVATE RESTROOMS
	FIRE SUPPRESSION
	O EXPANDED SPRINKLER SYSTEM INTO ADDITION
	 WET TYPE, ZONE ACTIVATED (4 ZONES PER FLOOR)
	O STANDPIPES AT 4 LOCATIONS (EACH
	STAIRWELL) PER FLOOR- 2 EXISTING
ELECTRICAL SYSTEM	SYSTEM TIES INTO TWO EXISTING 2500 A SWITCH BOARDS BOARDS TO BE RECONFIGURED; CONSOLIDATING SMALLER BREAKERS TO FEED A NEW DISTRIBUTION PANEL TO ALLOW LARGER 800 AMP BREAKERS PUT IN PLACE TO SERVE DISTRIBUTION PANELS IN ADDITION N+1 REDUNDANCY 1000 KW EMERGENCY GENERATOR 5000 GALLON FUEL TANK LOCATED OUTSIDE AWAY FROM BUILDING. REQUIRES UNDERGROUND DUCT BANK TO FEED INTO NEW ELECTRICAL ROOM SIZED FOR EXPANSION ONLY; EXISTING STRUCTURE STILL FEED FROM EXISTING GENERATOR BACK UP PLANT

SCOPE OF WORK	SUMMARY FEATURES
MASONRY	 CMU, FIRE-RATED STAIRWELLS O SELF-SUPPORTING STAIR TOWER O VERTICAL #5 @ 16" □.C, WALL GROUTED SOLID O REQUIRES SCAFFOLDING WHOLE HEIGHT O ANCHORED AT EACH SLAB ON DECK WITH ³/₄" ANCHOR BOLTS WELDED TO ANGLE IRON O BRICK FAÇADE O VENEER, NON-LOAD BEARING CAVITY WALL ASSEMBLY O ERECTED "BY FACE". SLOWER IN OPENING AREAS UP TO BEGIN INTERIOR TRADES, BUT REQUIRES LESS SCAFFOLDING.
EXCAVATION SUPPORT	UNDERPINNING THE EXISTING STRUCTURE WAS NECESSARY DURING EXCAVATION NEAR EXISTING FOUNDATIONS SHEETING AND SHORING WERE SUPPORT METHOD OF CHOICE FOR EXCAVATION GROUND WATER WAS NOT AN ISSUE (ABOVE WATER TABLE), THEREFORE DEWATERING WAS NOT A CONSIDERATION O PUMPS WERE USED IF OCCASIONAL RAIN OR SNOW CREATED STANDING WATER

PROJECT COST EVALUATION

COSTS ON ANY PROJECT ARE ALWAYS AN IMPORTANT METRIC TO ESTABLISH AT THE BEGINNING, AND TO CAREFULLY TRACK THROUGHOUT CONSTRUCTION. SEVERAL METHODS CAN BE USED TO ESTABLISH PROJECTED COSTS. THESE METHODS RANGE FROM A VERY QUICK ROM ESTIMATES BASED ON THE COST OF SOME DEFINABLE UNIT (NUMBER OF BEDS FOR A HOSPITAL, COST PER APARTMENT IN A COMPLEX, TOTAL SEATS FOR A THEATRE) TO DETAILED TAKE OFFS OF EACH SYSTEM IN THE PROJECT TO DEVELOP A FINAL BUDGET.

Cost projections for this project shown below in table 1 are provided courtesy of Gilbane Construction. It looks at total project costs, including a breakdown of some major systems in the project. "Total project" includes all costs (Land, Sitework, Overhead, General conditions) and "Building costs" include only the cost of labor and material actually going in place. It is interesting to note that this original cost did not include the 1st floor Emergency Department Fit out, or the $2^{\rm ND}$ story fitout. These spaces were originally designated as shell space only. One change order has been processed already to add the finish scope of the $1^{\rm st}$ floor emergency department. The total contract at based on this addition stands at roughly \$35 Million.

FOR COMPARISON, IN THIS REPORT TWO METHODS WERE USED TO EXAMINE PROJECT COSTS. ONE WAS A SQUARE FOOT ESTIMATE BASED ON RS MEANS SQUARE FOOT ESTIMATING BOOK. THE EXCERPTS USED FOR DATA ARE SHOWN IN APPENDIX 1. ESTIMATING BY THIS METHOD TAKES A LOOK AT BUILDING PERIMETER, STORY HEIGHT, AND TOTAL SQUARE FOOTAGE AS THE DEFINABLE UNITS ON WHICH AN ESTIMATE CAN BE BUILT. AS SHOWN IN TABLE 2 BELOW, THE FIGURE COMES IN EXTREMELY HIGH COMPARED TO THE GMP SUBMITTED BY GILBANE, EVEN WITH THE ADJUSTMENTS MADE AS OUTLINED IN TABLE 3. MEANS TRADITIONALLY RUNS HIGH, BUT AT ALMOST 200% OF THE ORIGINAL COST, AND 160% OF CURRENT CONTRACT, THIS METRIC CLEARLY WOULD NOT BE ADVANTAGEOUS FOR ANY EARLY COST PROJECTIONS WITHOUT SERIOUSLY IMPACTING WHAT AN OWNER MAY OR MAY NOT CONSIDER FOR THE PROJECT IN TERMS OF SCOPE.

D4 COST ESTIMATES RAN CLOSER TO PROJECT COSTS, BUT WAS STILL 160% OVER ORIGINAL COST AND 134% ABOVE CURRENT CONTRACT. THE SUMMARY OF THE D4 COST ESTIMATE IS BELOW IN TABLE 4. A FULL PRINTOUT OF THE ESTIMATE HAS BEEN INCLUDED IN APPENDIX II. A HOSPITAL EXPANSION/RENOVATION IN UTAH WAS THE CLOSEST PROJECT IN D4. ONLY ONE BUILDING WAS USED FOR COMPARISON. AS PARAMETERS WERE EXPANDED AND EVEN SEEMINGLY CLOSELY RELATED PROJECTS WERE ADDED, THE ESTIMATES BECAME FURTHER AND FURTHER AWAY FROM THE ACTUAL COSTS.

THESE EXTREMELY HIGH COST PROJECTIONS CAN BE ATTRIBUTED TO ONE PLACE VERY QUICKLY. THE ORIGINAL GMP HAD TWO FULL STORIES WORTH OF SHELL SPACE. NO CONSIDERATION WAS MADE FOR THE FINISHES, THE INTENSIVE MEP ROUGH-IN, OR FINAL FIT OUT THAT CLEARLY ADDS SIGNIFICANT COST TO A PROJECT. HOWEVER, EVEN ONCE SOME OF THESE COSTS ARE INCORPORATED, EVEN THE BEST ESTIMATE

(D4) WAS STILL MORE THAN 30% HIGHER. CLEARLY THERE IS CONSIDERABLE ERROR INVOLVED WITH SUCH EARLY ESTIMATING METHODS.

IT IS CONFUSING THAT THE ESTIMATES WERE SO MUCH HIGHER THAN THE PROJECT COST. THIS VERTICAL EXPANSION IS A TRICKY PROJECT, AND IT CAN BE EXPECTED THAT PREMIUMS ARE PAID WHEN EXPANDING NEXT TO AN EXISTING, FULLY FUNCTIONAL HOSPITAL. CLEARLY, GILBANE HAS MADE AN ART FORM OUT OF THE PROCESS AND IS ABLE TO REALIZE CONSIDERABLE SAVINGS AGAINST WHAT THE "AVERAGE" IS BASED ON IN RS MEANS AND D4.

TABLE 1- COST BREAKDOWN

	Cost Bre	KD	OWN		
		OST	Co	ST/SF	
TOTAL PROJ	TOTAL PROJECT (ORIGINAL)		31,318,000	\$	116
BUILDING C	OSTS (ORIGINAL)	\$	26,413,000	\$	98
SYSTEMS					
	MECHANICAL	\$	9,203,000	\$	34
	STRUCTURAL STEEL	\$	1,554,000	\$	6
	ELECTRICAL	\$	3,084,000	\$	1 1
	MASONRY	\$	1,052,000	\$	4
	CONCRETE	\$	1,035,000	\$	4
	SPRINKLER	\$	444,500	\$	2

TABLE 2- SQUARE FOOTAGE ESTIMATE

SQUARE FOOTAGE EST	IMATE	
TOTAL BUILDING AREA	270000	SF
TOTAL BUILDING PERIMETER	1030	LF
STORY HEIGHT	13	FT
RS MEANS VALUE \$	226.80	PER SF

PROJECT TOTAL COST \$ 61,235,757	
----------------------------------	--

TABLE 3- RS MEANS ADJUSTMENTS AND BREAKDOWN

MEANS COST ADJUS	TMENTS A	ND	BREAKDO	WN
ADJUSTMENT FOR STORY HEIGHT	ADD	\$	1.30	PER FT
PERIMETER ADJUSTMENT	DEDUCT	\$	1.60	PER 100 FT
INTERPOLATED RS MEANS VALUE		\$	229.39	PER SF
LOCATION FACTOR			0.99	
FINAL RS MEANS SF COST		\$	226.80	PER SF

TABLE 4- D4 COST ESTIMATE

D4 ESTIMATE	
TOTAL PROJECT COST	\$51,868,273.00
Building Costs	\$47,865,918.00
GENERAL	
REQUIREMENTS	\$ 1,914,590.00
SITEWORK	\$ 2,087,764.00

SITE PLAN OF EXISTING CONDITIONS


SPACE AT THE DOCTORS COMMUNITY HOSPITAL EXPANSION IS IN VERY SHORT SUPPLY. FOUR FACTORS CONTRIBUTE TO THIS REALITY.

- 1. They are not building on an open site. As seen in Figure 3 below, there are 6 other structures, including the one they are expanding, already on site. Structures 7 and 8 are currently under way on the south end of the site. One is a new parking deck; the other is a new Medical Office Building. All of these structures take up space that could be used for lay down, but is clearly not available.
- 2. Construction is occurring on the East side of the current hospital, which abuts a private residence. They are unable to utilize any space beyond the property line, which limits the path way on the East to a mere 25' from the footprint of the expansion. Between this limited road way, and the existing building they are expanding on the other side, access to the construction is extremely limited and creates an exorbitant amount of congestion.
- 3. CONTRACTORS ARE COMPETING FOR SPACE WITH THE OTHER CONSTRUCTION SITE ON CAMPUS. BOTH SITES ARE IN NEED OF LAY DOWN AND MATERIAL STORAGE SPACE, WHICH IS A FINITE QUANTITY. THE APPARENT "GREEN SPACE" IN FIGURE 3 IS UNFORTUNATELY NOT OPEN FIELD, BUT RATHER HEAVILY FORESTED AREAS THAT THEY CANNOT CLEAR TO CREATE MORE SPACE DUE TO ZONING REGULATIONS.
- 4. MUCH OF THE PARKING LOT SPACE MUST REMAIN USABLE SO THAT THEY HOSPITAL MAY CONTINUE FUNCTIONING NORMALLY. BOTH MEDICAL STAFF AND PATIENTS MUST BE ABLE TO ACCESS THE FULLY FUNCTIONAL HOSPITAL THROUGHOUT THE DURATION OF CONSTRUCTION. THIS FACT LIMITS THE AMOUNT OF PARKING LOT SPACE THAT CAN BE USURPED FOR CONSTRUCTION ACTIVITIES.

THESE FACTORS CAUSE A SIGNIFICANT RISK OF IMPACTING THE CONSTRUCTION OF THIS PROJECT. THE CONGESTION CAN LEAD TO PRODUCTIVITY INEFFICIENCIES THAT CAUSE SCHEDULE DELAYS AND COST OVERRUNS. RISK IS AN EVIL THAT MUST BE MANAGED EFFECTIVELY ON ANY CONSTRUCTION PROJECT, AND THIS ONE IS NO DIFFERENT. SPACE LIMITATION IS BY FAR, ONE OF, IF NOT THE LARGEST, AREA OF RISK PRESENT AT THE DCH VERTICAL EXPANSION.

ANOTHER LARGE AREA OF RISK RELATED TO SITE PLANNING IS NON CONSTRUCTION TRAFFIC (VEHICULAR AND PEDESTRIAN). THE HOSPITAL WILL MAINTAIN FULL FUNCTIONALITY THROUGHOUT THE PROJECT. AMBULANCES MUST BE ABLE TO COME AND GO FREELY AND QUICKLY. THIS NEED WILL MAKE IT IMPERATIVE TO HAVE PROMINENT AND CLEAR SIGNAGE TO DIRECT STAFF, PATIENTS, AND CONSTRUCTION TRAFFIC IN THE RIGHT DIRECTION TO: REDUCE CONGESTION, KEEP PEOPLE SAFE, AND NOT IMPACT HOSPITAL OPERATIONS.

FIGURE 3 - DCH SITE PLAN



LOCAL CONDITIONS

DOCTORS COMMUNITY HOSPITAL IS BEING CONSTRUCTED IN LANHAM, MARYLAND, A SUBURB OF WASHINGTON, DC, LOCATED JUST OUTSIDE OF THE CAPITAL BELTWAY ON A 33 ACRE SITE. THE MAJORITY OF THE SITE HAS ALREADY BEEN DEVELOPED BY THE HOSPITAL AND CONSISTS EITHER OF PARKING LOTS OR OTHER BUILDINGS. THE REMAINDER OF THE SITE IS DENSE TREES, WHICH CANNOT BE REMOVED OR DISTURBED DURING CONSTRUCTION DUE TO ZONING ORDINANCES AND BUFFER REQUIREMENTS.

PREFERRED CONSTRUCTION METHODS IN THE DC AREA GENERALLY FOCUS ON LOW FLOOR-TO-FLOOR HEIGHTS DUE TO HEIGHT RESTRICTIONS WITHIN THE DISTRICT. SATISFYING THIS RESTRICTION HAS TYPICALLY LED TO AN INCREASED USE OF CONCRETE STRUCTURES. THIS PROJECT IS NOT SUBJECT TO THESE RESTRICTIONS SINCE IT IS JUST OUTSIDE OF CITY LIMITS, AND AS SUCH, HAS ELECTED TO USE A STEEL SUPERSTRUCTURE.

THIS PROJECT IS NOT SEEKING LEED CERTIFICATION, BUT GILBANE HAS SET A COMPANY POLICY OF ACHIEVING 75% RECYCLING ON ALL PROJECTS. DEBRIS MUST BE SORTED ON SITE BETWEEN TWO DUMPSTERS. ONE IS DESIGNATED FOR "HEAVY DEBRIS", CONCRETE, CMU, BRICK, ETC AND THE OTHER DUMPSTER HAS ALL OTHER CONSTRUCTION WASTE. DUMPSTERS ARE AVERAGING BEING PULLED BETWEEN 1 AND 2 TIMES PER WEEK, AT A COST OF \$400/PULL. EAI, INC, IS RESPONSIBLE FOR TAKING THEM AWAY, AND THEY HANDLE ALL THE RECYCLING NEEDS OF THE PROJECT.

SEVERAL BORINGS WERE TAKEN AROUND THE SITE TO ESTABLISH A GOOD THOUGHT PATTERN ON WHAT TYPES OF SOIL WERE LIKELY TO BE DISCOVERED DURING EXCAVATION. AN EXCERPT OF THIS REPORT CAN BE FOUND IN APPENDIX II, AS WELL AS BORING LOCATIONS. BORING LOGS CONFIRMED WHAT WAS ALREADY SUSPECTED; NO ROCK WAS TO BE ENCOUNTERED DURING EXCAVATION AND THE WATER TABLE WILL NOT BE A FACTOR. WATER LEVELS WERE NOT HIT GENERALLY UNTIL ABOUT THE 30' MARK BELOW GRADE. ALMOST ALL EXCAVATION WOULD STAY ABOVE THIS MARK. AS SUCH, ONLY DEWATERING DUE TO RAIN/SNOW WOULD BE A CONSIDERATION FOR DCH. THE ONLY STRUCTURE THAT GOES DEEPER ARE DRILLED CAISSONS, FOR WHICH WATER LEVELS HAVE MINIMAL IMPACT. SOIL TYPES RANGED FROM LEAN CLAY TO SANDY SILT. NO ROCK WAS DISCOVERED VIA BORINGS, WHICH BODES WELL FOR A SPEEDY EXCAVATION.

AS MENTIONED ABOVE IN THE SITE PLAN SECTION, THIS PROJECT IS VERY TIGHT ON SPACE. AS A RESULT, PARKING IS LIMITED TO ONE FOREMAN TRUCK FOR WORK CREWS PER COMPANY ALLOWED ON SITE IN THE TRAILER COMPOUND. OTHER WORKERS ARE RESPONSIBLE FOR PARKING ELSEWHERE, OFF-SITE. MANY OF THEM HAVE TAKEN TO PARKING AT A LARGE CHURCH LOT ACROSS THE STREET. THIS HAS BEEN A SUFFICIENT SOLUTION TO THIS POINT IN THE PROJECT, AND HAS NO SIGNS OF CHANGING.

CLIENT INFORMATION

DOCTORS COMMUNITY HOSPITAL IS A PRIVATELY RUN, NOT-FOR-PROFIT ORGANIZATION LOCATED IN PRINCE GEORGES COUNTY, MARYLAND, WHICH IS ADJACENT TO WASHINGTON, DC. THEIR GOAL IS TO SERVE THE SURROUNDING AREA OF PG COUNTY AND PROVIDE TOP NOTCH MEDICAL SERVICE TO THOSE PEOPLE IN THE REGION.

THIS EXPANSION WAS BORNE OUT OF A PERCEIVED NEED TO CREATE MORE SPACE TO ADEQUATELY SERVE THE NEEDS OF ITS PATIENTS. CURRENTLY, THE HOSPITAL IS VERY CROWDED, AND MANY ROOMS THAT WERE ORIGINALLY DESIGNED TO BE PRIVATE, INDIVIDUAL ROOMS HAVE BEEN TURNED INTO SEMI-PRIVATE, TWO PERSON ROOMS. THE VERTICAL EXPANSION IS AIMED TO CREATE ENOUGH NEW PATIENT ROOMS THAT THEY CAN CONTINUE TO SERVE THE REGION, BUT OFFER PRIVATE ROOMS FOR ALL INDIVIDUALS THAT REQUIRE OVERNIGHT STAYS AT THEIR FACILITIES. THROUGH THIS PROJECT, COUPLED WITH OTHER CONSTRUCTION UNDERWAY ON THE CAMPUS AS WELL, THEY ALSO HOPE TO EXPAND THEIR INFLUENCE AND REACH INTO NEIGHBORING ANNE ARUNDEL COUNTY FOR PATIENT CARE.

OWNERS WANT IT ALL; AS QUICKLY AS POSSIBLE, AT THE HIGHEST QUALITY, WITH AS LITTLE COST AS POSSIBLE TO THEM. THE DCH PROJECT IS NO EXCEPTION. THROUGH CONVERSATIONS WITH A MEMBER OF THE DCH MANAGEMENT TEAM, THIS MANTRA HELD TRUE. HE DID, HOWEVER, CONCEDE THAT IN THE END, COST WAS MOST IMPORTANT TO THE PROJECT, WITH SCHEDULE FOLLOWING CLOSELY BEHIND. HOLDING THESE ITEMS IN THIS ORDER, THEIR PHILOSOPHY IS BEST EXEMPLIFIED BY BRINING ON A CM IN A GMP CONTRACT VERY EARLY IN THE PROJECT. THEY WERE ABLE TO GATHER FEEDBACK AND CONSTRUCTABILITY REVIEWS EARLY IN THE PROJECT FROM A TEAM WHO HAS A POSITIVE TRACK RECORD IN THE HEALTHCARE INDUSTRY. THIS ALLOWED FOR VALUE-ENGINEERING FEEDBACK EARLY IN THE PROCESS, AND HELPED TO ENSURE REALISTIC EXPECTATIONS FOR THE SCHEDULE OF THE PROJECT.

ONE OF THE BIGGEST CONCERNS FOR THE OWNER IS THAT CONSTRUCTION DOES NOT AFFECT THE CONTINUOUS OPERATION OF THE EXISTING FACILITY. OUTAGES MUST BE WELL-COORDINATED WITH THE OWNER AND MUST OCCUR DURING NON PEAK HOURS IN ORDER TO MINIMIZE THE IMPACT ON THE HOSPITAL. AT DCH, OUTAGES ARE SCHEDULED FOR NIGHT SHIFTS TO MITIGATE ANY INCONVENIENCES, WHICH IS SOMETHING THAT SUBCONTRACTORS MUST BE AWARE OF AND USE MANPOWER ACCORDINGLY. THIS CONNECTION AND OVERLAPPING WITH THE EXISTING SYSTEMS, AND SEAMLESS APPLICATION THEREOF, IS A BIG OPPORTUNITY TO PLEASE THE CLIENT. DURING A PHONE CONVERSATION, IT WAS INDICATED THAT THE BIGGEST FACTOR IN DEEMING THIS PROJECT A "SUCCESS", WILL BE THE FLAWLESS INTERACTION AND OPERATION OF THE NEW EXPANSION WITH THE EXISTING FACILITIES.

SCHEDULE IS THE DRIVING FACTOR FOR THE OWNER, ESPECIALLY AS IT RELATES TO THE PHASED OCCUPANCY. THEY FEEL GRAMPED WITH THEIR GURRENT EMERGENCY DEPARTMENT AND NEED THE NEW SPACE AS SOON AS POSSIBLE. THEY ALSO DESIRE TO GET THE NEW PATIENT TOWER OPEN QUICKLY TO BEGIN OFFERING PRIVATE ROOMS FOR MORE PATIENTS AGAIN.

DANIEL ALEXANDER | CM | DR. MESSNER
DOCTORS COMMUNITY HOSPITAL | LANHAM, MD
SEPTEMBER 29, 2008

AS A RESULT OF THE AFOREMENTIONED SCHEDULE IMPETUS, PHASED OCCUPANCY IS BEING EMPLOYED ON THE DCH PROJECT. EMERGENCY DEPARTMENT OPERATION AND OCCUPANCY BEGINS EARLY IN FEBRUARY '09. BY OPENING IT SOONER, IT WILL HELP TO MORE ADEQUATELY SERVE THE NEEDS OF THE OWNER AND THE REGION. THE LESS CRITICAL, ALTHOUGH WHOLLY IMPORTANT, PATIENT TOWER WILL FOLLOW IN SEPTEMBER. RENOVATIONS ARE SLATED TO FOLLOW THE TOWER, AND WILL BE COMPLETED BY MARCH OF 2010. AT THIS POINT, THE FACILITY WILL BE FULLY FUNCTIONAL AND ALL OCCUPANTS WILL BE IN PLACE.

PROJECT DELIVERY SYSTEMS

Doctors Community Hospital Elected to have this project delivered as a Design-Bid-Build project. CR Goodman Associates was selected to handle the architect duties for this expansion. Their selection was based on a desire from DCH to have a local, medium size firm be the architect. This desire stems from the inherently complex nature of building an expansion next to, and over, an existing hospital that is to maintain full functionality during the construction. Another factor in CR Goodman's favor was two highly favorable recommendation from nearby hospitals who had just undergone renovations designed by the company. They were pleased with the detail orientated nature, and ability to blend existing architecture and new architecture together to create a seamless feel. As illustrated in the chart below, Figure 4, CR Goodman was hired, and is under a Lump Sum contract with DCH.

GILBANE WAS SELECTED AS THE CM AT RISK FOR THIS PROJECT BASED ON A NUMBER OF FACTORS. FIRST AND FOREMOST, ACCORDING TO DCH, WAS THEIR LARGE PRESENCE IN THE MARYLAND MARKET. DCH WAS RELUCTANT TO HAVE SOME LARGE FIRM "SHIPPING" PEOPLE IN FOR THE PROJECT THAT DO NOT HAVE A ROUTINE AND SIZEABLE WORK FORCE IN MD. ANOTHER FACTOR WAS GILBANE'S STELLAR RECORD IN THE HEALTHCARE SECTOR. GILBANE'S REPUTATION PRECEDED THEM, AND THIS FACT WORKED HEAVILY IN THEIR FAVOR. DCH OWNER'S ALSO STATED THAT THEY FELT A CLOSER, BETTER CHEMISTRY WITH THE GILBANE PERSONNEL THROUGHOUT THE SELECTION PROCESS WHICH PUT THEM ABOVE THE 7 OTHER FIRMS VYING FOR THE CONTRACT.


GILBANE ENTERED INTO A GUARANTEED MAXIMUM PRICE CONTRACT WITH DCH. DUTIES UNDER THIS CONTRACT DID NOT ONLY INCLUDE MANAGING THE PROJECT, BUT THEY WERE BROUGHT ON VERY EARLY IN THE PROCESS TO ASSIST WITH DESIGN DEVELOPMENT AND CONSTRUCTABILITY REVIEWS. THE CONTRACT CALLS FOR TYPICAL BUILDER'S RISK INSURANCE AND GENERAL LIABILITY INSURANCES. INTERESTINGLY ENOUGH, ON A PROJECT WITH SUCH A CRITICAL SCHEDULE, NO LIQUIDATED DAMAGES ARE IMPLEMENTED.

DCH IS NOT REQUIRING BONDS ON THE PROJECT IN THE TRADITIONAL FORM. INSTEAD, CONTRACTORS DEFAULT INSURANCE IS BEING IMPLEMENTED. THIS INSURANCE PRACTICE IS HANDLED MORE AT THE CORPORATE LEVEL OF THE COMPANY, AND HAS LESS IMPACT AT THE DAY TO DAY LEVEL IN TERMS OF ADDING BOND COSTS TO CHANGE ORDERS. A MAIN ADVANTAGE TO THIS MODEL IS THAT SHOULD A CONTRACTOR DEFAULT, THE STEP OF A BONDING AGENCIES INVESTIGATION IS FORGONE, AND THE CONTRACTOR HAS BETTER DISCRETION ON HOW TO PROCEED IN A TIMELY MANNER SO AS TO MITIGATE EFFECTS ON THE SCHEDULE. ON A PROJECT WHERE SCHEDULE IS SO IMPORTANT, THIS FACT CAN BE QUITE BENEFICIAL SHOULD THE UNFORTUNATE NEED ARISE TO CALL ON THE INSURANCE.

Overall, the contracts on this project seem to be good choices for the owner. The GMP for Gilbane is a solid choice, and by having them on the project sooner, good insight and VE solutions were able to be established. With an expansion, it was surprising not to see a Cost Plus

FEE FOR THE ARCHITECT'S CONTRACT. WITH THE POSSIBILITY FOR SO MANY UNKNOWNS TO SURFACE RESULTING IN ADDED WORK FOR THE ARCHITECT AS THE EXPANSION AND RENOVATION MORE FORWARD, THIS MAY HAVE BEEN A MORE PRUDENT CONTRACTUAL ARRANGEMENT.

FIGURE 4- OVERALL PROJECT ORGANIZATION CHART




STAFFING PLAN

GILBANE'S STAFFING PLAN IS RELATIVELY STRAIGHT FORWARD, WITHOUT ANY COMPLEX RELATIONS OR SPECIAL POSITIONS AND IS LAID OUT BELOW IN FIGURE 5. THE PROJECT EXECUTIVE OVERSEES THIS PROJECT, ALONG WITH A FEW OTHERS WITHIN THE COMPANY. HE IS GENERALLY NOT ON SITE, AND MAKES APPEARANCES FOR ROUGHLY A DAY EACH WEEK OR LESS. LISA HANCOCK, PROJECT MANAGER, IS THE PRIMARY GILBANE EMPLOYEE IN CHARGE ON SITE. SHE IS SUPPORTED IN HER MANAGEMENT DUTIES BY HER APM, BEN, AND HER PROJECT ENGINEER, ALSO NAMED BEN. IN THE FIELD, GENERAL SUPERINTENDENT ED IS RESPONSIBLE FOR THE CONSTRUCTION ACTIVITIES AND IS SUPPORTED BY TIM.

IT IS CURIOUS TO NOTE THAT ON SUCH A MEP INTENSIVE PROJECT, SYSTEMS WHICH ACCOUNT FOR NEARLY HALF OF THE BUILDING COST, THEY DO NOT EMPLOY AT LEAST A PART TIME, IF NOT FULL-TIME, MEP COORDINATOR. GILBANE HAS SPECIALIZED PART OF ITS COMPANY INTO HOSPITAL CONSTRUCTION, EXPANSION, AND RENOVATIONS. COORDINATION IS GENERALLY HANDLED BY THE APM'S AND PROJECT ENGINEERS.

FIGURE 5- STAFF FLOW CHART



APPENDIX I

FIGURE 6- RS MEANS DATA



Costs per square foot of floor area

Exterior Wall	S.F. Area	100000	125000	150000	175000	200000	225000	250000	275000	300000
EXICI OF TYUII	L.F. Perimeter	594	705	816	783	866	950	1033	1116	1200
Face Brick with	Steel Frame	252.95	246.70	242.50	236.10	233.70	231.80	230.35	*229.15	228.10
Structural Facing Tile	R/Conc. Frame	262.40	256.00	251.80	245.35	242.95	241.05	239.55 ·	238.30	237.30
Face Brick with	Steel Frame	247.30	241.10	236.95	231.20	228.90	227.05	225.55	224.45	223.45
Concrete Block Back-up	R/Conc. Frame	258.50	252.35	248.20	242.45	240.10	238.30	236.85	235.70	234.65
Precast Concrete Panels	Steel Frame	249.85	243.65	239.50	233.55	231.20	229.40	227.90	226.75	225.75
With Exposed Aggregate	R/Conc. Frame	259.35	253.15	249.00	243.05	240.70	238.90	237.40	236.25	235.25
Perimeter Adj., Add or Deduct	Per 100 L.F.	4.15	3.30	2.75	2.35	2.05	1.90	1.60	1.50	1.40
Story Hgt. Adj., Add or Deduct	Per 1 Ft.	1.85	1.75	1.70	1.40	1.35	1.35	1.30	1.30	1.30

The above costs were calculated using the basic specifications shown on the facing page. These costs should be adjusted where necessary for design alternatives and owner's requirements. Reported completed project costs, for this type of structure, range from \$151.70 to \$369.90 per S.F.

Common additives

Unit	\$ Cost	Description	Unit	\$ Cost
L.F.	243	•	Olli	Ç C031
L.F.	480		Fach	299
L.F.	455	9		136
L.F.	690			182
L.F.	180			286
L.F.	325	Double bedside call station		365
				310
Each	1750	Standard call button		157
Each	940	Master control station for 20 stations		5775
Each	2425		Eddi	3773
			Each	2225
Each	26,800			181
Each	2925			345
				16,300
Each	12,500	Sterilizers	Eddi	10,000
Each	22,500	Single door, steam	Fach	161,500
		Double door, steam		207,500
		Portable, counter top, steam		3875 - 6050
		Gas		40,000
		Automatic washer/sterilizer	Each	55,500
	L.F. L.F. L.F. L.F. L.F. L.F. Each Each Each Each	LF. 243 LF. 480 LF. 455 LF. 690 LF. 180 LF. 325 Each 1750 Each 940 Each 2425 Each 26,800 Each 2925 Each 12,500	L.F. 243 Nurses Call Station L.F. 480 Single bedside call station L.F. 455 Ceiling speaker station L.F. 690 Emergency call station L.F. 180 Pillow speaker L.F. 325 Double bedside call station Duty station Each 1750 Standard call button Each 2425 Sound System Amplifier, 250 watts Each 26,800 Speaker, ceiling or wall Trumpet Station, Dietary with ice Each 12,500 Sterilizers Each 22,500 Sterilizers Each 22,500 Sterilizers Double door, steam Double door, steam Portable, counter top, steam Gas	LF. 243 Nurses Call Station Each

150

DANIEL ALEXANDER | CM | DR. MESSNER DOCTORS COMMUNITY HOSPITAL | LANHAM, MD SEPTEMBER 29, 2008

Location Factors

Costs shown in *RSMeans Square Foot Costs* are based on National Averages for materials and installation. To adjust these costs to a specific location, simply multiply the base cost by the factor for that

STATE/ZIP CITY Residential Commercial **ALABAMA** 350-352 354 Birmingham .88 .79 .73 .79 .85 .76 .77 .75 .83 .75 .76 .88 .81 .79 .81 .86 .81 .78 .78 .80 .84 .79 .81 Tuscaloosa Jasper Decatur 355 355 356 357-358 359 360-361 362 363 364 365-366 367 368 Huntsville Gadsden Montgomery Anniston Dothan Evergreen Mobile Selma Phenix City Butler **ALASKA** 995-996 997 998 999 1.27 1.29 1.26 1.30 1.24 1.24 1.22 1.29 Anchorage Fairbanks Juneau Ketchikan **ARIZONA** 850,853 852 Phoenix Mesa/Tempe .89 .85 .87 .86 .89 .84 .86 .86 .83 .79 .85 .81 .86 .80 .83 852 855 856-857 859 860 863 864 865 Globe Tucson Show Low Flagstaff Prescott Kingman Chambers ARKANSAS 716 717 718 Pine Bluff Camden Texarkana .81 .69 .74 .69 .85 .79 .78 .75 .76 .71 .84 .73 .76 .74 .85 .81 .82 .77 .79 .77 718 719 720-722 723 724 725 726 727 728 729 Hot Springs Little Rock West Memphis Jonesboro Batesville Harrison Fayetteville Russellville Fort Smith CALIFORNIA 900-902 903-905 906-908 Los Angeles Inglewood Long Beach 1.08 1.04 1.05 1.04 1.05 1.05 1.04 1.05 1.07 1.07 1.07 1.07 1.07 1.07 1.08 1.09 1.23 1.09 1.13 1.14 1.17 1.13 1.16 1.16 1.16 1.17 910-912 913-916 917-918 919-921 Pasadena Van Nuys Alhambra San Diego Palm Springs San Bernardino 919-921 922 923-924 925 926-927 928 930 931 932-933 934 935 Riverside Santa Ana Anaheim Oxnard Santa Barbara Bakersfield
San Luis Obispo
Mojave 936-938 939 940-941 Salinas Salinas
San Francisco
Sacramento
Palo Alto
San Mateo
Vallejo
Oakland
Berkeley
Richmond
San Pafael 940-941 942,956-958 943 944 945 946 947 948 949 950 951 952 953 San Rafael Santa Cruz San Jose Stockton 1.08 1.07 Modesto

city. The data is arranged alphabetically by state and postal zip code numbers. For a city not listed, use the factor for a nearby city with similar economic characteristics.

similar economic characteristics.										
STATE/ZIP	CITY	Residential	Commercial							
CALIFORNIA (CON 954 955 959 960 961	IT'D) Santa Rosa Eureka Marysville Redding Susanville	1.17 1.11 1.09 1.09 1.09	1.14 1.07 1.07 1.08 1.07							
COLORADO 800-802 803 804 805 806 807 808-809 810 811 812 813 814 815 816	Denver Boulder Golden Fort Collins Greeley Fort Morgan Colorado Springs Pueblo Alamosa Salida Durango Montrose Grand Junction Glenwood Springs	.93 .93 .91 .89 .79 .92 .90 .91 .88 .90 .91 .87	.94 .92 .93 .92 .86 .92 .93 .93 .92 .92 .91 .92 .92							
CONNECTICUT 060 061 062 063 064 065 066 067 068 069	New Britain Hartford Willimantic New London Meriden New Haven Bridgeport Waterbury Norwalk Stamford	1.11 1.11 1.11 1.10 1.11 1.11 1.12 1.11 1.11	1.09 1.09 1.09 1.07 1.08 1.10 1.10 1.09 1.09							
D.C. 200-205	Washington	.96	.99							
DELAWARE 197 198 199	Newark Wilmington Dover	1.04 1.05 1.03	1.04 1.04 1.05							
FLORIDA 320,322 321 323 324 325 326,344 327-328,347 329 330-332,340 333 334,349 335-336,346 337 338 339,341	Jacksonville Daytona Beach Tallahassee Panama City Pensacola Gainesville Orlando Melbourne Miami Fort Lauderdale West Palm Beach Tampa St. Petersburg Lakeland Fort Myers Sarasota	.82 .90 .78 .75 .82 .81 .90 .91 .87 .85 .85 .92 .79 .89	.84 .89 .79 .78 .85 .86 .89 .92 .89 .88 .85 .91 .81 .91							
GEORGIA 300-303,399 304 305 306 307 308-309 310-312 313-314 315 316 317,398 318-319	Atlanta Statesboro Gainesville Athens Dalton Augusta Macon Savannah Waycross Valdosta Albany Columbus	.89 .71 .79 .79 .75 .80 .81 .82 .75 .73 .78	.90 .77 .83 .84 .79 .83 .83 .82 .80 .77 .82							
HAWAII 967 968	Hilo Honolulu	1.22 1.25	1.19 1.21							

APPENDIX II

FIGURE 7- D4 ESTIMATE PRINT OUT

DCH D4 Estimate

Page 1


		DCH Expansi	on - Nov 2007	- MD - Other		
	Prepared By:	Dan Alexander PSU 5th Year Thesis		Prepared For:	Technical Report 1 PSU 5th Year Thesis	
	Building Sq. Size: Bid Date: No. of floors: No. of buildings: Project Height: 1st Floor Height: 1st Floor Size:	Fax: 270000 8/1/2007 5 1 80 13		Site Sq. Size: Building use: Foundation: Exterior Walls: Interior Walls: Roof Type: Floor Type: Project Type:	Fax: 70000 Medical CAS MAS MAS SBS VCT ADD/REN	
Division			Percent		Sq. Cost	Amount
01	General Requirer	ments	3.85		7.09	1,914,591
03	Concrete		12.61		23.24	6,275,563
04	Masonry		0.27		0.50	134,454
05	Metals	a franchista de la companya della companya de la companya de la companya della companya della companya de la companya de la companya della co	6.89		12.69	3,427,509
06	Wood & Plastics		4.85		8.95	2,416,563
07	Thermal & Moist	ure Protection	7.81		14.40	3,887,778
08	Doors & Window	rs .	6.88		12.69	3,425,637
09	Finishes		8.39		15.47	4,177,304
10	Specialties		0.83		1.54	414,850
11	Equipment		0.47		0.87	233,781
12	Furnishings		0.24		0.45	121,202
14	Conveying Syste	ems	3.72		6.86	1,851,800
15	Mechanical		24.01		44.26	11,950,942
16	Electrical	P	19.18		35.36	9,548,535
Total B	uilding Costs		100.00		184.37	49,780,509
02	Site Work		100.00		29.83	2,087,764
Total N	lon-Building Costs		100.00		29.83	2,087,764
Total P	roject Costs	====	-			51,868,273

APPENDIX III

FIGURE 8- BORING LOG EXCERPT

T	D. W. KOZERA, INC. Baltimore, Maryland PROFESSIONAL ENGINEERS & GEOLOGISTS						2.	TEST BORING LOG				Boring No.: B-108 Contract No.: 06139.D Page: 1 of 1			
1 years	Project: Doctor's Community Hospital, East Side Add							I, Ea	ast Side Addi	tion		Gro	und Surf.	El. (±): 202.0	
	Locati	ion:	8118	Good	Luck R	Road						Date Started : 11-29-06			
	Lanham, Maryland										Date Completed : 11-29-06 Contractor : GeoServices Corp., Inc.				
	GROUNDWATER OBSERVATIONS Date Time Depth Casing Caved											Drill		: John Boyce	
	Comple	etion		1 1	1-29 1-29	1	0:00	None 38.5			Rig	Rig : cme 45 #3 Drill Method : 2 1/4" HSA			
	Casing	Pulled		1 1	1-29 1-30	0	1:40 6:40		None — 36.2 33.0 — 34.0			Inspector : A. Zmoda			
	Depth (ft)	Surf. Elev. 202.0	Samples	Blow Counts	"N" Value	Water Level	Graphic	nscs		Description	1	Formation	Stratum	D	
	0 -	-	-	Counts	Value	Level	IXX		Poorly Grade	d Sand FILL, me	nist brown	<u> </u>	Stratum	Remarks	
		200	1	8-7-7	14		~~~	SP	POORLY GR	ADED SAND w	th Gravel	臣	B-2	Asphalt = 0.6'	
	5 -	-	2	7-10-10	20				LEAN CLAY	with Sand, mois	t, brown		B-1	PP = 4.5 tsf	
	_	- 195 -	3	4-6-8	14			CL						m.c. = 19.7%	
	10 -	_	4	3-9-11	20				SANDY SILT	SANDY SILT with Sand lenses, moist, gray B-2	B-2				
	-	- 190 -							and brown	with Sand lense	es, moist, gray		D-2		
G .	.15 -	- - - 185	5	5-7-7	14			ML							
	20	- '					11	SP-	POORLYGR	ADED SAND wi	th Silt	ŧ			
	20 -	- - 180	6	4-6-7	13			SM-	LEAN CLAY	mented lenses, wet, brown Y with Sand and Sand lenses		Patuxent	· B-1	PP = 3.0 to 3.5 tsf	
	25 -	-	7	4-6-8	14				and layers, m	ioist, gray and bi	rown				
	_	- - 175 -						CL						PP = 3.5 to 4.0 tsf	
	30	-	8	5-7-9	16										
	1	- 170 -				Ā			BOODINOD	ADED GALID					
	35	-	9	51-30-24	54				contains ironi	ADED SAND, co te, moist, brown	ome Silt, and tan		B-2		
	1	- 165 -						SP							
ı	40	-	10	15-21-26	47				Bottom of bor	ing at 40.0°					
	and the second														
TEST BORING LO AGEN KOZERA, GOT 1/5/07							не при предваждения выполня дела в при предваждения в предваждени								

FIGURE 9- BORING LOCATIONS



TEST BORING LOCATION PLAN