

# AIRPORT TERMINAL



## FINAL REPORT

PREPARED FOR:

DR. MESSNER

4/7/09

EASTERN  
UNITED STATES

CONSTRUCTION MANAGEMENT OPTION

<http://www.engr.psu.edu/ae/thesis/portfolios/2009/pdy103/index.html>

# PAUL YINGLING

# AIRPORT TERMINAL

EASTERN

UNITED STATES



## GENERAL

- MULTI-USE FACILITY
  - OFFICE SPACE
  - SECURITY CHECKPOINT
  - BAGGAGE HANDLING
- 4 STORIES
- 250,000 SQUARE FEET
- \$185 MILLION
- 300' LONG Poured TERRAZZO CURVED CORRIDOR TO CORRECT ELEVATION DIFFERENCES BETWEEN ADJOINING BUILDINGS

## PROJECT TEAM

- DDI ARCHITECTS / ODELL ASSOCIATES
- OWNER - DEPARTMENT OF AVIATION
- CM - GILBANE / MCKISSACK
- GC - ERNEST BOCK AND SONS
- DESIGN - KBR, BNP RALPH TYLER, URBAN ENGINEERING, AND BRINJAC

## STRUCTURAL SYSTEM AND ENVELOPE

- STEEL COLUMNS AND TRUSSES
- EXISTING CAST-IN-PLACE COLUMNS
- 6" Poured SLAB ON DECK
- CURTAIN WALL
  - GLASS
  - METAL PANELS
- MASONRY 1<sup>ST</sup> FLOOR
- PARADIENE 30 CR FR ROOFING WITH AN SRI OF 87%

## MECHANICAL AND ELECTRICAL

- REMOTE THERMAL PLANT
  - CHILLERS
  - BOILERS
- CRAC UNITS
- NORMAL POWER
  - 480/277, 3 $\phi$ , 4 WIRE AND GROUND
- UPS, CPS, AND BLUE BUSS EMERGENCY POWER
- FIVE HYDRAULIC ELEVATORS

## SUSTAINABILITY

- INTERIOR 3<sup>RD</sup> FLOOR LEED<sup>®</sup> CERTIFICATION

CONSTRUCTION MANAGEMENT OPTION

<http://www.engr.psu.edu/ae/thesis/portfolios/2009/pdy103/index.html>

# PAUL YINGLING

# Table of Contents

<b>EXECUTIVE SUMMARY .....</b>	<b>1</b>
<b>PROJECT OVERVIEW.....</b>	<b>3</b>
<i>Introduction .....</i>	<i>3</i>
<i>Client Information.....</i>	<i>4</i>
<i>Project Delivery System.....</i>	<i>4</i>
<i>Building Statistics.....</i>	<i>5</i>
<i>Building Systems Summary.....</i>	<i>7</i>
<i>Site Plan .....</i>	<i>8</i>
<i>Schedule.....</i>	<i>9</i>
<i>General Conditions Estimate.....</i>	<i>10</i>
<b>ANALYSIS ONE – INTERDISCIPLINARY DOCUMENT COORDINATION .....</b>	<b>11</b>
<i>How It Works .....</i>	<i>11</i>
<i>Project Specific Example .....</i>	<i>12</i>
<i>Possible IDC Solution and Evaluated Impact.....</i>	<i>13</i>
<i>Conclusion.....</i>	<i>14</i>
<b>ANALYSIS TWO – PANELIZED CONSTRUCTION .....</b>	<b>15</b>
<i>Dimensional Limitations.....</i>	<i>15</i>
<i>Cost &amp; Schedule Impact .....</i>	<i>16</i>
<i>Conclusion.....</i>	<i>17</i>
<b>ANALYSIS THREE – PEDESTRIAN REROUTING .....</b>	<b>18</b>
<i>Pedestrian Rerouting .....</i>	<i>18</i>
<i>Steel Truss Redesign.....</i>	<i>19</i>
<i>Conclusion.....</i>	<i>21</i>
<b>ANALYSIS FOUR – ALTERNATIVE GLAZING .....</b>	<b>22</b>
<i>Dual Façade .....</i>	<i>22</i>
Modification .....	23
R-Value Calculation .....	24
Impact of Change .....	26
<i>Photovoltaic Cells.....</i>	<i>27</i>
Architectural Modification .....	27
Calculations .....	28
Educating the Public.....	29
<i>Conclusion.....</i>	<i>30</i>
<b>SUMMARY AND CONCLUSIONS.....</b>	<b>31</b>
<b>APPENDIX A: DETAILED SCHEDULE.....</b>	<b>32</b>
<b>APPENDIX B: PRECAST DETAILS .....</b>	<b>39</b>
<b>APPENDIX C: STRUCTURAL RESULTS .....</b>	<b>44</b>
<b>APPENDIX D: GLAZING SPECIFICATIONS.....</b>	<b>51</b>

## *Executive Summary*

The Airport is one of the largest airports on the eastern seaboard. To ensure their place as one of the most customer-friendly airports in the United States they decided to connect adjacent terminals with an enhanced connector bridge. This report proposes possible construction modifications to the building that relates to course work completed over the past five years of education at The Pennsylvania State University. The analyses are as follows:

- Document Review – to see how further scrutiny of Contract Documents may or may not affect a project
- Panelized Construction – to explore how this form of erection will affect a project
- Pedestrian Flow – to see how the current traffic of pedestrians could be modified
- Alternative Glazing – to explore how the building's envelope could become more energy efficient

Analysis One, Interdisciplinary Document Coordination, researches the current practice of the Gilbane Building Company to assess contract documents before a project is underway and discover possible omissions or errors to reduce the amount of uncertainty that may arise later in the project. An explanation of the procedure is provided and a project specific example is evaluated. The project specific example appraises how the schedule and cost could have possibly been affected if the IDC procedure was implemented.

Panelized Construction, Analysis Two, looks at how the building's existing masonry veneer could be modified. The current cast stone veneer is substituted with an equally aesthetic precast panel. Schedule and cost analyses through both the manufacturer and RS Means help provide the key elements of this research. Dimensional limitations of the delivery method to the site are considered and may affect how the panels are fabricated and erected.

The Structural Breadth, Analysis Three, explores how the sites existing concrete columns could possibly be eliminated. The purpose for this is to demolish the temporary corridor that spans the construction site for added safety for all parties involved. To first have the ability to perform this analysis a pedestrian detour around the job site is proposed to abolish the need for the temporary corridor. Consequently, with the building being erected entirely out of steel creates a more predictable structure while the floors above are being loaded.

The Mechanical Breadth, Alternative Glazing, reintroduces a century old energy efficient design of a dual façade. Due to the current energy crisis many methods, that had been disregarded when energy was inexpensive, are being further studied to bring about a greener future for all. The analysis focuses on the thermal conductivity of a dual façade during winter and summer temperatures and then is compared to the current output of the air handling units.



**AIRPORT TERMINAL  
EXPANSION - EASTERN  
UNITED STATES**

PAUL YINGLING AE SENIOR THESIS 2009



*Credits ♦ Acknowledgements*

Airport Project Team

*My Parents*

All Penn State Faculty and Students

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



## *Project Overview*

### **Introduction**

The purpose for this project is to connect two adjacent terminals at an airport on the east coast. On the site there was an original connector bridge between the terminals, however, after many years of increased travel through the Airport it was decided to construct an entire building to accommodate the guests. The expansion is four stories and 250,000 gross square feet. The ground floor houses the expanded baggage handling conveyors to accommodate more luggage and to ensure that the bags are properly routed to the correct planes. The second floor includes 14 new security checkpoints and expanded retail space. Since the building is located in a prominent area on the premises, the Department of Aviation offices occupy the third floor. Finally, the fourth floor functions as a mechanical space to serve the building occupants.




Figure 1: Exterior, airside, orientation to site plan

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES


PAUL YINGLING AE SENIOR THESIS 2009



## Client Information

The Department of Aviation is the owner. The mission is to rehabilitate one of the top airports in the country. The airport has been ranked among the top user-friendly airports in the country and through the renovation/expansion the DOA hopes to continue the excellent service to their customers. The increases in checkpoints, expanded baggage handling capacity, and retail stores will ensure the airport's popularity for years to come.

## Project Delivery System



The project delivery system is typical of public work projects. Multiple Primes with an overseeing CM Agency to comply with Pennsylvania law. The typical contractor is selected by the lowest bid, that is, if anyone else bids, which was not the case with the GC selection. Bonds and insurance are required on bid day, however kept private. All contracts are lump sum with allowances.

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



## Building Statistics

### *Structural System*

The structural system takes advantage of existing steel piles, as well as, concrete grade beams, mat slab, and columns from the connector bridge between terminals that was demolished. Combinations of both steel and wood piles were used in the subsurface construction of the new building. The slab on grade is bordered with a non-load bearing CMU wall to later be hidden with architectural cast stone veneer. Trusses supported by W14x176 are used on the ground floor to maximize the open space for the complex runs of baggage handling conveyors. The second and third floor of the building uses columns and 26x30 bays with wind connections internally and moment connections on the exterior of the building. The fourth floor consists of trusses. 6 ¼" light weight concrete was originally only to be used on the second floor to ease the deflection of the trusses below, but later was adopted throughout the building.




Figure 2: Aerial photo of steel erection

### *Mechanical*

The heating and cooling for the building is provided by redundant boiler and chiller units located at a satellite thermal plant (50,000 MBTU). There is a total of seven AHU's for basic heating and cooling. The combined capacity of all seven units is 8,836 MBTU and 180,000 CFM. For office spaces terminal air boxes and radiant heat are used for individual control of temperature. Data rooms located in the building CRAC units (Computer Room Air Conditioning) are used and independent from the

# **AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES**

PAUL YINGLING AE SENIOR THESIS 2009



general building HVAC systems. On the first floor where the Tugs (luggage cars) enter and exit the building nine Air Curtains are used in the winter to ensure indoor temperatures are maintained. Each Air Curtain has a capacity of 557 MBTU and 13,062 CFM.

## *Electrical/Lighting*

Again the power is initially provided from two transformers (2,000A – 480Y/277V) located at the satellite plant, from there the power is sent via duct bank to an underground substation. At the substation power is transferred again to multiple transformers to step the voltage down. One path takes the power to two transformers that step the voltage down for 1000A – 208Y/120V power. The second path takes the power to five oil cooled transformers and steps it down and up to 750A – 480Y/277V or 2500 – 480Y/277V. UPS and ‘Blue Buss’ systems are also included in this redundant system, as never to have to close the facility for electrical malfunctions or power outages.

Lighting on the first floor for the baggage handling system is primarily 2x4 linear fluorescents and HID wall washers at the transparoll doors for high visibility where the Tugs enter and exit the Building. On the second floor there are again 4’ linear fluorescents, as well as, compact fluorescents at the entrance to the wanding stations and neon cove lighting in corridor. The third floor is composed of offices which use a wide variety of architectural and accent lighting; however, they are primarily fluorescents.

## *Fire Protection*

The main system in the building is a wet system. For data rooms an iodine gas system is the first system with heat detectors followed by a backup wet system if the dry system fails. The system reports back to the central fire station for the airport. In the event of a fire, hydrants are located on both the outside perimeter and roof of the building.

## *Transportation*

There are two holeless hydraulic elevators and three holed hydraulic elevators. All elevators are rated for a load of two tons and speed of 100 fpm. There are four escalators that transport customers from the first floor to the main entrance at 90 fpm. Escalators are required to exceed the national standard (ASME A17.1) by not less the twice the allowable design load.

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



## Building Systems Summary

Yes	No	Work Scope	If yes, address these questions / issues
X		Demolition Required?	<ul style="list-style-type: none"> <li>Remove existing pipe columns and concrete grade beams</li> <li>Remove existing lighting standard, support pier and footing</li> <li>Remove and salvage existing wall mounted light fixtures &amp; conduit</li> <li>Demolish entire existing concrete stairwell assembly</li> <li>Demolish existing loading dock in its entirety including but not limited to: bollards, bumpers, lighting retaining walls, dock levers &amp; all below grade foundations</li> <li>Remove and salvage existing glazing</li> <li>Demolish temporary egress corridor structure</li> <li>Demolish existing exit doors and all associated signage</li> </ul>
X		Structural Steel Framing	<ul style="list-style-type: none"> <li>A Combination of trusses and columns</li> <li>25 ton hydraulic crane for steel erection</li> </ul>
X		Cast in Place Concrete	<ul style="list-style-type: none"> <li>Plywood and Metal Forming</li> <li>Steel reinforce Grade 60</li> <li>Plain-Steel Wire: ASTM A 82, galvanized</li> </ul>
	X	Precast Concrete	
X		Mechanical System	<ul style="list-style-type: none"> <li>Remote Thermal Plant</li> </ul>
X		Electrical System	<ul style="list-style-type: none"> <li>480/277 3<math>\phi</math> 3200A</li> <li>UPS backup</li> <li>CPS backup</li> <li>Blue Buss backup</li> </ul>
X		Masonry	<ul style="list-style-type: none"> <li>Stone Veneer</li> <li>Non load bearing</li> <li>Walk through masonry scaffold</li> <li>Vertical Support #6 @ 24"</li> </ul>
X		Curtain Wall	<ul style="list-style-type: none"> <li>Stick built</li> <li>Fire rated</li> <li>Insulated</li> </ul>
	X	Support of Excavation	<ul style="list-style-type: none"> <li>Existing conditions</li> </ul>




# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



Site Plan



Paul Yingling  
4-7-2009

**Airport Site Plan**




# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



## Schedule

(See Appendix A for Detailed Schedule)



# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



## General Conditions Estimate

CODE	NAME	UNIT	COST	DURATION	TOTAL
01 11 31.20 (0010)	Construction Management Fees	1%			\$185,000.00
01 31 13.20 (0020)	Clerk	Week	\$590.00	58	\$34,220.00
01 31 13.20 (0180)	Project Manager	Week	\$2,975.00	58	\$172,550.00
01 31 13.20 (0100)	Project Engineer 1A	Week	\$2,100.00	40	\$84,000.00
01 31 13.20 (0100)	Project Engineer 1A	Week	\$1,375.00	40	\$55,000.00
01 31 13.20 (0100)	Project Engineer 1B	Week	\$2,100.00	16	\$33,600.00
01 31 13.20 (0100)	Project Engineer 1B	Week	\$1,375.00	16	\$22,000.00
01 31 13.20 (0240)	General Superintendent	Week	\$3,125.00	58	\$181,250.00
01 31 13.20 (0240)	Superintendent 1A	Week	\$2,750.00	40	\$110,000.00
01 31 13.20 (0240)	Superintendent 1B	Week	\$2,750.00	8	\$22,000.00
01 31 13.20 (0240)	Superintendent 1B	Week	\$2,750.00	8	\$22,000.00
01 31 13.20 (0240)	Superintendent 1B	Week	\$2,750.00	18	\$49,500.00
01 31 13.20 (0240)	Superintendent 1B	Week	\$2,750.00	18	\$49,500.00
01 31 13.20 (0240)	Superintendent 1B	Week	\$2,750.00	18	\$49,500.00
01 31 13.20 (0240)	Superintendent 1B	Week	\$2,750.00	18	\$49,500.00
01 31 13.20 (0240)	Superintendent 1B	Week	\$2,750.00	18	\$49,500.00
01 31 13.20 (0240)	Superintendent 1B	Week	\$2,750.00	18	\$49,500.00
01 31 13.20 (0240)	Superintendent 1B	Week	\$2,750.00	18	\$49,500.00
01 31 13.20 (0290)	Scheduler	Week	\$1,600.00	80	\$128,000.00
01 32 13.50 (0650)	Scheduling Large Job	0.03%			\$55,000.00
01 52 13.40 (0100)	Office Equipment	Month	\$171.00	14.5	\$2,479.50
01 52 13.40 (0120)	Office Supplies	Month	\$93.50	14.5	\$1,355.75
01 52 13.40 (0140)	Telephone Bill	Month	\$88.00	14.5	\$1,276.00
				<b>SUBTOTAL</b>	\$ 1,456,231.25
				Allowances (16.15%)	\$ 1,691,412.60
				Labor Burden (39%)	\$ 2,351,063.51
				Fee:	\$ 2,586,169.86
				<b>TOTAL</b>	<b>\$ 2,586,169.86</b>

# **AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES**

PAUL YINGLING AE SENIOR THESIS 2009



## *Analysis One – Interdisciplinary Document Coordination*

Gilbane offers the service of a preconstruction document review called Interdisciplinary Document Control. The mission statement by Gilbane for this service is as follows.

The Document Coordination department will provide multiple types of document analysis by thoroughly understanding and addressing our internal and external Clients' needs through explicitly defined solutions, combining time tested practices with innovative means and methods, in a relentless pursuit of excellence that surpasses our Customers' expectations

This service is offered to the client at cost in hopes that final costs will be lower. At first, this appears to be the same as coordination drawings that are completed in every construction project. However, this process goes above and beyond the mechanical portions of the drawings. This cost saving technique was offered to the owner of the airport but not purchased.

To perform this analysis I will first explain how it works followed by a preliminary evaluation of the drawings to point out a project specific example. In some cases issues were located and found before all the bids were in and continued until the project schedule was affected.

### **How It Works**

The first step is the Pre-Coordination Survey. The process will determine the level of document completion and create an execution strategy for the amount of available information. Information will be identified for construction disciplines that are reasonably complete and ready for review, as well as, design aspects that are incomplete and unsuitable for review. The lead document reviewer will then assign responsibilities and strategy for the review team. This primary survey of the documents will be presented to the project team and or client.

The second step is the Base Review. The review consists of a checklist of over 450 review tasks between 16 distinct construction disciplines. Review durations vary between three to six weeks with a review team of two to five people. The total man hours of the review can range from 300 to 800 depending on the size of the project. The review tasks may be phased depending on: document release, bidding schedule, and construction disciplines' cost impact.

Communication or reporting is important to analyze the electronic versions of the continuously updated contract documents. All parties are encouraged to either use or develop a customized communication mechanism. Through this monitoring of ongoing program changes can be handled in almost real time.

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



Finally a Debrief Meeting will be scheduled between the IDC team and the design team. The IDC review team presents their findings with the hope of either clarification to the contract documents or changes as necessary. Many of the issues can be resolved at the meeting; however, approximately 10% of the issues are further discussed and rectified as soon as possible.

Unique to this approach is an overall Compliance Check at the end. This process is a comparison of revised documents, addendum, sketches, or bulletins to previously submitted reports to determine if revisions have accrued. Through the use of the previously mentioned communication these areas of concern can be located and checked with little or no loss to the overall schedule of the project.

## Project Specific Example

Through the use of the IDC, a preliminary draft found over 750 items that were either missing or incomplete. Many issues were the result of the design documents only being 60% complete. Since the review is subject to the client's construction schedule these drawing updates were subsequently the best representations as the project moved forward. The drawings were done electronically and the ability to make omissions through the use of copy and paste functions was vast, but easily rectified. The example that I will look at is the ability for better communication through the use of the IDC process and the continually updated design documents.

Throughout the project there were various owner modifications to the original design documents. These changes included schedule accelerations and security modifications. The owner modification of revamped security doors and product non-compliance lead to a bulletin being issued. The bulletin detailed how and where new security doors were to be hung; unfortunately, the HVAC ductwork had already been installed on the floor. Therefore there was a need to hang the doors and avoided the existing duct work.



Figure 3: Ductwork obstruction in plenum space

Figure 3 depicts the area in question where new doors needed to be installed. Due to the weight of the doors support was to be provided from above. Unfortunately, the mechanical contractor did not

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



provide the coordination for the ductwork and agreed to move the duct at cost. Also, Gilbane identified two years prior that there were no sections showing the layering of the ductwork and piping for the entire building. Consequently, this issue was prolonged until the schedule was adversely affected.

## Possible IDC Solution and Evaluated Impact

The lack of the contract documents detailing the layering of the HVAC piping and ductwork resulted in a less than efficient solution to the problem of later modifications to the overall design. To resolve the issue several meetings were scheduled to discuss a solution. And for the lack of a better cliché, time is money. Through the use of the IDC program the coordination effort to remediate the issue could have been more streamlined. The overall solution could have been resolved prior to the installation of the ductwork.




Figure 4: Location where support is needed for glass partition wall

The cost of the IDC procedure to the owner is approximately 10% of the total cost of the project, so in the case of the airport the cost would have been approximately \$185,000. Statistical reviews of previous projects have concluded that using the IDC review can reduce potential change orders in the magnitude of 7-10 times the cost of the review. The potential savings for the owner on this project could have range from \$1-1.5 million dollars. The ability to predict and modify the design throughout the construction phase is ideal; however, it is also important to recognize the issues before all the bids even come in which is the goal of the review. The analysis of removal and relocation of the ductwork is just one of the 750 issues located two years before the scheduled turnover of the floor in question.

There are two specific locations where the glass door support to the structural steel is needed. The total length of duct to be moved is approximately 20' of 26x10 metal ducts. RS Means 2009 was used to estimate the cost of the change and it was assumed that the cost to take down the existing ducts were equivalent to the cost associated with installing the ducts. The cost through the use of RS Means 2009 after calculating the total weight of duct is illustrated below:

Duct Size (L+W+1")	Weight (plf) 22 gauge	Length	Total Weight
37	9.36 lbs	20'	187.2 lbs



# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



RS Means Cost Comparison		
Total Incl. O&P	Weight	Total Cost
\$7.75 per pound	187.5 pounds	\$1,453

Removal and Rerouting Total: \$3,000

## Conclusion

The IDC procedure appears to have many advantages; however the cost saving potential is directly correlated with how complete the design documents are. In the case of the airport some of the designs were incomplete since the security measures are constantly being amended. Another aspect of security that would make this procedure difficult is that some of the design documents are not readily available to distribute for a group review. Therefore I believe in this analysis that the IDC procedure may have aided in the reduction of schedule and overall cost although the Airport is a unique building which may have created unforeseen obstacles that prohibited the implementation of the IDC procedure.



Figure 5: Finished glass partition wall

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



## *Analysis Two – Panelized Construction*

The purpose of this analysis is to learn the possible advantages of precast panels by replacing the existing cast stone veneer with an aesthetically comparable panel. Panelized construction has claimed to have many cost saving advantages, such as: labor, material, and quality improvement. The labor savings are immediately seen as the factories are mechanized and the onsite material is pieced together with cranes rather than manually pieced together and grouted.

With accurate drawings, material savings would result as the manufactured panels generate little to no waste compared to the cast stone that is hand cut in the field. Quality improvement is established by the factory controlled measures that ensure that the color is correct and remains consistent for the duration of the fabrication.



Figure 6: Cast stone mockup

With respect to the airport, the existing cast stone façade required the approval from the architect according to the contract documents and the final approval turned out to be somewhat challenging. After the stone color was eventually approved and installation began the masons noticed that the factory had been delivering two different shades of cast stone. The second issue involved with the stone façade was that the project team had trouble getting the grout color approved. A possible solution for the confusion of getting the proper stone and grout color would be to use precast panels. By using precast panels the submittal would eliminate the need for a mock up since the pseudo cast stone veneer would be assembled as a single panel. As well as, a better chance for the manufacturer to maintain consistent colors in the controlled environment of an offsite fabrication plant.

To perform this analysis a quantity takeoff was performed and found to be that a total of 14,058sqft of cast stone could be replaced with the alternative precast architectural panels. Also, a schedule analysis was performed to identify if there would be any time or cost savings. Finally, an introduction of the quality assurance advantage a precast facade system would have over any potential problems during the submittal process.

### **Dimensional Limitations**

For transport purposes the panels cannot be longer than 12' wide in one direction. Delivery through the use of tractor trailers is the limiting factor so that the vehicles do not require special escorts to have the panels arrive on site. Likewise, there is a 35' limitation on the total length of the long side of the panel. This may become a factor in determining how the panels are fabricated. For example, the



# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



rough opening on the airside of the building is 354' long and 22' high. If the panels are oriented vertically the total number of panels would be 30 12' x 20' panels. However, if the panels are arranged in horizontal stacks of two 35' x 11' panels there would only need to be 22. Reducing the number of total panels consequently reduces the transportation and installation cost.




Figure 7: Panel orientation comparison

## Cost & Schedule Impact

The cost of the existing cast stone is \$57sqft with a total cost of \$801,306. The modified panelized construction costs were provided by Nitterhouse at approximately \$35sqft (comparable to the cost in RS means \$36.68) with a total cost of \$492,030. All costs include fabrication, delivery and installation. Therefore the project cost would diminish by approximately \$310,000, or 0.2% of the total project. The importance of weather proofing the building as soon as possible is accomplished by tying the panels to the superstructure.

Connection details for the installation of the precast are provided in Appendix B. After the panels are installed the CMU can follow. An industry professional suggested eliminating the block wall entirely; unfortunately, the interior use of the building prohibits removal of the CMU.

Connection details for the installation of the precast are provided in Appendix B. After the panels are installed the CMU can follow. An industry professional suggested eliminating the block wall entirely; unfortunately, the interior use of the building prohibits removal of the CMU.

The original scheduled time period for the cast stone veneer was 40 days. Also, the site congestion was increased by the need for scaffold to aid the manual installation. Using the precast




Figure 8: Airside façade

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



system would require a lead time of approximately six months and the installation rate of 20 panels per day. The gross area of stone veneer is 14,058 sqft and the required number of panels is 40. Hence, the total time for the installation of the panels would be three days compared to the 40 days allotted in the original schedule. Three days would complete the major portion of the installation followed by the customized column covers that can be coordinated in the field. Overall there would be 37 extra days that, although the stone was not on the critical path, there would be a less congested site that would allow other trades to move in and occupy the space.

Throughout the construction of the cast stone veneer there was a miscommunication with the architect on what the acceptable grout color was and the specifications were vague on the what submittals were required, particularly for the grout color and mock-up size. The manufacturer of the current cast stone veneer suggests that local specifications be used for the contract documents. Unfortunately, the preparers of the contract documents tend to hurriedly copy and paste typical specifications and many times the errors or omissions are not discovered until the installation of the product begins. To ensure the proper grout color, precast could possibly aid in maintaining the proper and consistent color which the architect requests. Precast submittals are the same as cast stone; however, using a precast system there is a greater chance that the aggregate is consistent in color.

## Conclusion

Through this analysis there is some support for the alternate method of a precast veneer. The savings are minimal to the total project cost, yet the time to complete the enclosure of the first floor is significant. The submittal specifications are included with the precast system, where as the existing cast stone does not included specifications for the exact type, only typical specifications. The area of writing specifications and the time spent reviewing them would be a subject for further research. I believe through the use of IDC, from analysis one, and a precast system, controversies over what the criterion is for the submittal could have been avoided. Figure 9 is an example of how the variations of custom precast architectural features can be used without removing the aesthetics of a comparable cast stone veneer.




Figure 9: Precast stone veneer example

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



## *Analysis Three – Pedestrian Rerouting*

Due to the DOA requirement that customers would not be required to exit the building and walk the approximate 300' to the adjacent terminal, the site team had to develop a plan to reroute pedestrian traffic. To accomplish this it was determined that the existing connector bridge would be used until the first temporary corridor was constructed after the steel erection. The problem that developed was that the existing connector bridge was concrete and the design team had to integrate this into the new building. Cracks developed in the existing concrete columns as the building began to be loaded. Onsite superintendants were required to monitor and report on these findings daily. The



Figure 10: Temporary Connector Bridge

design considered the existing concrete columns to be zero force members and found the cracks to not be of structural significance. Combining existing concrete into a steel building, as well as, continually constructing and demolishing temporary corridors began to slow the project performance down. In retrospect an alternate method of rerouting the airport customers around the site, instead of straight through the middle of the site, would have accelerated the construction schedule. Also, the existing concrete columns could have been completely demolished and steel erected in place of them to create a more predictable structure.

This analysis focuses on the elimination of the concrete piers and the substitution of a modified steel truss system. The elimination of the temporary connector bridge will save the project approximately \$500,000 and create a safer environment for all parties involved. The first accomplishment for this analysis to work is eliminating the pedestrian traffic through the center of the construction site. After the rerouting of the pedestrians has been completed the site will be completely open to accept a modified truss system, provided that the steel calculations are correct.

### **Pedestrian Rerouting**

The Department of Aviation required that the pedestrians have the capability to travel between terminals indoors. To avoid the construction and demolishing of temporary corridors the traffic can be detoured to the bag claim area across the street that is connected to both existing terminals with permanent bridges. The bridges that transport the travelers to the bag claim is supported by a moving walkway that runs approximately 1.4 m/sec. The distance from one terminal to the bag claim is 300';

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



therefore the total detour is 600'. And the total time that a traveler would have to expend to make their connection would be a little over four minutes.

$$(600 \text{ ft}) \times (0.3048 \frac{\text{m}}{\text{ft}}) \times (1.4 \frac{\text{m}}{\text{s}}) / (60 \frac{\text{s}}{\text{min}}) = 4.26 \text{ minutes}$$

Also, for able bodied travelers one can simply exit the terminal and walk under an outdoor covered walkway to the next terminal with no delay.

## Steel Truss Redesign

Originally work in the area surrounding the temporary bridge through the construction site was conducted between the hours of 1am and 6am. With the elimination of the public traffic through the construction site work is able to proceed during the daytime hours which is less costly for an owner and safer for the workers. Also, with the absence of concrete columns for a more slender steel column space on the ground floor will be available to store and install the complicated baggage handling conveyors.





Figure 11: Alternate pedestrian paths



# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



STAAD Pro was utilized to evaluate the stability of a modified truss illustrated on the previous page. Further structural results from STAAD are shown in Appendix C. The truss was analyzed as a simply supported beam and the maximum deflection value, 0.707", was compared to the L/360 value of 3.56". Therefore the truss modification appears to be plausible when analyzed as a simply supported beam. With the original RFI issued for shear appears to be resolved by a steel connection extend to the W14X193.




Figure 12: STAAD loading diagram

<b>Node Displacement Summary</b>									
	Node	L/C	X (in)	Y (in)	Z (in)	Resultant (in)	rX (rad)	rY (rad)	rZ (rad)
Max X	9	2:LOAD CASE	0.004	-0.112	0.000	0.112	0.000	0.000	0.000
Min X	1	4:GENERATEI	-0.134	-0.085	0.000	0.159	0.000	0.000	0.000
Max Y	12	1:DEAD	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Min Y	6	4:GENERATEI	-0.071	-0.707	0.000	0.711	0.000	0.000	0.000
Max Z	1	1:DEAD	-0.019	-0.061	0.000	0.064	0.000	0.000	0.000
Min Z	1	1:DEAD	-0.019	-0.061	0.000	0.064	0.000	0.000	0.000
Max rX	1	1:DEAD	-0.019	-0.061	0.000	0.064	0.000	0.000	0.000
Min rX	1	1:DEAD	-0.019	-0.061	0.000	0.064	0.000	0.000	0.000
Max rY	1	1:DEAD	-0.019	-0.061	0.000	0.064	0.000	0.000	0.000
Min rY	1	1:DEAD	-0.019	-0.061	0.000	0.064	0.000	0.000	0.000
Max rZ	1	1:DEAD	-0.019	-0.061	0.000	0.064	0.000	0.000	0.000
Min rZ	1	1:DEAD	-0.019	-0.061	0.000	0.064	0.000	0.000	0.000
Max Rst	8	4:GENERATEI	-0.071	-0.707	0.000	0.711	0.000	0.000	0.000

The total number of trusses in the building is eight. The modification consists of:

Member Type	Member Length	Weight
<b>W14X120</b>	19.96'	2395.20 lbs
<b>W14X193</b>	22.50'	4342.50 lbs
<b>W14X283</b>	17.00'	4811.00 lbs
	<b>Total weight</b>	<b>5.77 tons</b>



# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



The total weight for the entire modification would be 46 tons. Cost requirements for installation and are assumed to be zero, requiring only the material be priced since the crane is already to be scheduled onsite. Pricing information provided by RS Means 2009 at \$2,338 per ton results in a total price of \$108,003. The cost for the modification is lower than the total cost of the temporary bridge construction.

## Conclusion

The ability for an owner to allow the change of pedestrian rerouting is difficult. Through the evaluation of the schedule the temporary corridors appear not to affect the critical path. From the site consideration for forming the slab on grade around the existing concrete columns to the lack of a fully predictable steel structure, evaluation of the total time that could be saved is abstract; however, approximately 27 working days were directly affected by the continual pedestrian traffic through an active construction zone. Estimates of the total cost saving for this change would be approximately \$391,997; although, with a project cost of \$185million this change would only represent 0.21 percent of the total project. Therefore, I feel that in the public's perception of a longer detour and potential to miss a connecting flight it was in the best interest for the owner to provide a direct temporary path between terminals.

The structural calculations as presented could be an area for further research. The truss system was evaluated as a simply support beam, rather than how it interacts with the remainder of the building. Also, there is a complex baggage handling and screening conveyor system on the first floor which had yet to be fully designed at the time of this report. Design on whether or not the conveyors could be supported from the floor or hang from the truss system have yet to be determined. To date there have been two such structural cases directly related to the existence of the concrete columns. Figure 13 is an illustration of one such case and the recommendation from the structural engineer to install bearing plates that are attached to the existing column. The magnitude of the change order in this case could have been lessened or all together eliminated if the structure was entirely steel.




Figure 13: Steel modification

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



## *Analysis Four – Alternative Glazing*

With the ever rising energy costs in America, the need for an efficient building has become a critical industry issue. The concern for the airport is that the architectural aesthetics may be compromised with an attempt to create a more energy efficient building. To make the analysis even more complicated the main thermal losses in a building occur at the exterior glazing, which happens to be this building's key feature. With more than half the building's façade consisting of a glass curtain wall this analysis focuses on two possible ways to keep the architectural feature and create a more energy efficient building. The two systems researched are the use of a dual façade and the plausibility of using photovoltaic cells on the south facing portion of the buildings' façade.

### **Dual Façade**

The idea of dual façade has been around for over a hundred years, but has yet to fully break into the American market. The Europeans have made use of the dual façade technique for some time now with the foremost manufacturer Permasteelisa, located in Italy. The basic idea is to have airspace from a few inches to a few feet to insulate the building. Additions to this idea have included shades to control the amount of light entering the building, as well as, louvers on the top and bottom of the façade to allow hotter air to vent through the top of the façade during the summer months. As the industry has not fully adopted the method of dual-facades, there may be other modifications to this technique that could be explored through further research. A current and local example of the use of a dual-façade is at the University of Pennsylvania's Levine Hall. "We realized we could achieve a nearly fully glazed exterior envelope while meeting or exceeding energy code requirements," says Richard Maimon, associate in charge with project architect Kieran Timberlake Associates, Philadelphia.(Gorden 2005)




Figure 14: Levine Hall, Pennsylvania University



# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



Advantages from the utilization of a dual façade for an airport setting include, but are not limited to:

- Noise reduction with the close proximity to the tarmac
- Improved insulation and reduced heating loads / costs
- Architectural intent is modified, rather than eliminated, for higher energy performance

There are many variations of how a dual façade can be implemented, for the purpose of this analysis the façade will be defined as a naturally ventilated façade that relies on the stack effect with an airtight internal facade and a non-airtight external façade. The façade is attached to the structure in a cantilever fashion shown below.




Figure 15: Cantilever connection for dual-façade

## **Modification**

The current curtain wall consists of  $\frac{1}{4}$ " green VE2-55 #2 with a  $\frac{1}{2}$ " airspace and  $\frac{1}{4}$ " clear glass interior. The performance specifications are presented in Appendix D and the manufacturer was Viracon, Inc. to maintain consistence with the official specifications. To perform the analysis it will be assumed that the existing glass will be used as the exterior of the double skin to maintain the architectural aesthetics. However, from a constructability aspect the glass will only be laminated, rather than the insulated. Therefore the airspace between panes will be reduced from  $\frac{1}{2}$ " to 0.030". The interior is uncoated  $\frac{1}{4}$ " clear glass with  $\frac{1}{2}$ " airspace in between panes (see Appendix C). To properly control the temperature in the cavity there are louvers installed that can be open in the summer to allow for the stack effect to exhaust the hot air and in the winter the louvers will close to allow for the air to be continuously heated (see Figure 17). Application of the dual façade will occur on the south façade only (8,650 sqft).

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009




Figure 16: Dual-facade makeup diagram

## R-Value Calculation

The window make-up specifications identify both the summer and winter U-Values and the resulting R-Values are reciprocated, illustrated in tables below.

Material	U-Value $\left[ \frac{Btu}{ft^2 \cdot F \cdot hr} \right]$		R-Value $\left[ \frac{ft^2 \cdot F \cdot hr}{Btu} \right]$	
	Winter Conditions	Summer Conditions	Winter Conditions	Summer Conditions
<b>Existing - Silk-Screened Low-E (VE) Insulating glass (50% Coverage V933) VE 2-55</b>	0.310	0.290	3.23	3.45

Material	U-Value $\left[ \frac{Btu}{ft^2 \cdot F \cdot hr} \right]$		R-Value $\left[ \frac{ft^2 \cdot F \cdot hr}{Btu} \right]$	
	Winter Conditions	Summer Conditions	Winter Conditions	Summer Conditions
<b>Exterior - Solarscreen Low-E (VE) Laminated Glass VE 2-55</b>	0.970	0.880	1.03	1.13

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



<b>12" Airspace (sealed in winter and open in summer)</b>	0.017	4.55	60	12
<b>Interior - Uncoated Insulating Glass Clear</b>	0.470	0.490	2.13	2.04
<b>Totals:</b>	<b>0.016</b>	<b>0.066</b>	<b>63.16</b>	<b>15.17</b>

The U-Values are used to calculate the total Btu/hr of heat loss depending on the season and the temperature difference. By multiplying the U-value by the total square feet of the curtain wall a rough estimation is found for the total corrective measures the air handling units will have to provide. The mean temperature difference between the indoor temperature and the outdoor temperature is assumed to be 55° in the winter and 19° in the summer, shown below (values are taken from ASHRAE Fundamentals 2001).

Season	Outdoor Temperature °F	Indoor Temperature °F	Temperature Difference °F
Winter	15	70	55
Summer	89	70	19

Winter Conditions	U-Value $\left[ \frac{Btu}{ft^2 \cdot F \cdot hr} \right]$	Temperature Difference °F	Area $ft^2$	Total $\frac{Btu}{hr}$
Existing - Silk-Screened Low-E (VE) Insulating glass (50% Coverage V933) VE 2-55	0.310	55	8650	147483.00
Dual Facade	0.016	55	8650	7612.00

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



Summer Conditions	U-Value $\left[ \frac{Btu}{ft^2 \cdot ^\circ F \cdot hr} \right]$	Temperature Difference $^\circ F$	Area $ft^2$	Total $\frac{Btu}{hr}$
Existing - Silk-Screened Low-E (VE) Insulating glass (50% Coverage V933) VE 2-55	0.290	19	8650	47661.50
Dual Facade	0.066	19	8650	10847.1




Figure 17: Dual-façade seasonal operation sections

## Impact of Change

The implementation of the dual-façade reduces the heat loss in the winter by 32%, and in the summer by 23%. Overall, the building appears to be more efficient. The total cost of the exterior

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



façade, via a square foot estimate out of RS Means (\$57.10 per sqft), is \$493,915. The following table illustrates the per year savings with the implementation of a dual-façade.

	Months	Btu saved with Dual Façade per month	Cost per Million Btu per month*	Total Savings per year
Winter	5	71.87 million	\$365.40	\$131,309
Summer	7	26.51 million	\$936.30	\$173,749
			<b>Total:</b>	<b>\$305,058</b>

\*Prices obtain from the US Department of Energy

## Photovoltaic Cells

The airport already controls the amount of day lighting through the use of screen printed glass. To increase the amount of light that the airport controls would be the use of photovoltaic glass. The concept is that the glass is imbedded with tiny solar cells that can be integrated into the terminals power supply. Unfortunately, the electrical demand of the building is so large that it may shadow the potential benefit of photovoltaic cells. The possible downfall of the efficient aspect may create a unique opportunity for the architectural aesthetics of the building. To this end, an example would be the



Figure 18: GREENPIX

GREENPIX Zero Energy Media Wall in Beijing China. The story behind the building is to represent the willingness of China to follow suit with the rest of the world in becoming more energy savvy. The city is attempting to have all public transportation to have a zero carbon footprint in the coming years and this architectural feature to the building will accent the forward-thinking mentality to all who visit this city. Also, this analysis will further explore the use of a photo-catalytic coating on the glass. Photo-catalytic coatings (titanium dioxide) is used in combination

with ultraviolet light to break down dirt, keeping the glass clean for maximum potential from the photovoltaic cells.

## Architectural Modification

To maximize the photovoltaic collector's potential they will be incorporated on the south façade of the building, or airside. The management offices are located on the airside of the building and adding the solar cells on the visible portion of the offices' executive views would not be appropriate; therefore, the airside façade will only have approximately 4725 ft<sup>2</sup> (438.95 m<sup>2</sup>) of space to install the cells. The cells will be placed on the façade where the glass is only decorative and not transparent. Again, not to take

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



away from the architect's original aesthetic intention, Polycrystalline photovoltaic collectors from Ertex Solar were chosen and would blend well with the existing glass.



Figure 19: Solar panel comparison to existing architectural glass

Thin films, such as Ertex THRU<sup>®</sup>, could have been used but the transparency of 10% would not offer the interior offices sufficient lighting.

## Calculations

The manufacturer specifications claim that the Polycrystallin has a power producing capacity of 125 W/m<sup>2</sup>. The photo-catalytic coatings ensure that the cells operate under optimal conditions. Another advantage of the coating is there is no need to have window washers, since the glass is 'self cleaning', on the south facing airside of the building which is a secured area.

### Monthly Daylight Averages (hours)

(Data available on NASA's website)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sept	Oct	Nov	Dec
<b>Average</b>	9.68	10.7	11.9	13.2	14.3	14.9	14.7	13.7	12.5	11.1	10	9.4

### Average output for January

$$9.68 \text{ h} \cdot 125 \frac{\text{W}}{\text{m}^2} \cdot 438.95 \text{m}^2 \cdot \frac{1 \text{Kw}}{1000 \text{ W}} \cdot 31 \text{ days} = 16,465 \text{ kWh}$$

### Output per Months (kWh)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sept	Oct	Nov	Dec
<b>Average</b>	16,465	16,439	20,241	21,728	24,323	24,526	25,004	23,303	21,262	18,880	16,461	15,989

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



Output Comparison to Actual Building Demand	
<b>Total Solar Output per year:</b>	244,621 kWh
<b>Average Building Demand per year:</b>	5,125,000 kWh
<b>Supplemented Polycrystalline Impact:</b>	<b>4.8%</b>
	<b>\$26,052.10*</b>

## *Educating the Public*

Many people are aware of the current energy crisis but are not educated as what can actually be done to ease the demand on typical fossil fuels. The idea of photovoltaic cells producing enough energy to supply a technologically complex building becomes unrealistic. Therefore, these architectural features can educate the public. The New Jersey State Aquarium is an example of how the public can be introduced on how to make simple modifications to a building to accomplish moderate energy efficient design in the future. The Aquarium has propellers located atop the building's perimeter that capture the air currents off the Delaware River. While guests wait in line to gain admission, similar to waiting for a flight, there are placards located along the path that explain what the propellers are designed to do.




Figure 20: New Jersey State Aquarium

With respect to the airport, a system similar to BIOHAUSE in Paderborn Germany could be used to educate the public. With the cells placed on the south side, airside, of the building it may be difficult



Figure 21: BIOHAUSE Paderborn Germany

to differentiate between glass and the actual solar cells. Therefore, the landside of the building where passengers are unloading and waiting on flights, there could be a system of LEDs to illuminate the building, as well as, placards explaining to the public the advantages of solar power. The hope for this architectural modification would be that the general public eventually becomes aware of energy efficient design, so that it may become common practice.



# **AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES**

PAUL YINGLING AE SENIOR THESIS 2009



## **Conclusion**

The implementation of both dual-facades and photovoltaic cells are relatively young concepts in the United States. The introduction of these practices depends on the cost of energy, according to industry professionals in The Partnership for Achieving Construction Excellence. The two systems in this analysis rely on ideal conditions and both have high frontend costs associated with them. The installation of the double skin was found to be \$493,915 and under the conditions of this analysis would take less than two years to pay for itself. The cost of the photovoltaic system is moderately less than the dual-façade, but would not offer the owner significant returns for over 17 years after installation. However, both systems could be incorporated into the building that is funded by the government and consequently a key architectural feature of the city's commitment toward energy efficient design. A survey of industry professionals was conducted and the conclusion was that the systems are either too costly or unknown of at this time. This is why it is important that the general public become aware of the potential and it may result in more owners demanding green energy.

# **AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES**

PAUL YINGLING AE SENIOR THESIS 2009



## *Summary and Conclusions*

The Depth, or first two analyses, looked at cost and schedule impacts and the potential savings through the use of the IDC and panelized construction. Analysis One, Interdisciplinary Document Coordination, explored the utilization of further document review in the beginning of a project to lessen the number of RFIs and change orders during construction. A detailed explanation of the IDC was provided and a project specific example was explained. Through the use of RS Means and statistical data from previous projects, the IDC was found to offer significant savings to justify the 10% fee for the service. Analysis Two, Panelized Construction, weighed the potential benefits in term of cost and schedule by replacing the architectural cast stone veneer with precast panels. Dimensional limitations of the factory made panels concluded the manner in which a project team determines the best course of erection is important to save both time and money. The cost was found to save the project approximately \$310,000. The schedule impact was inconclusive, since the veneer was not on the critical path. However, the ability to have a less congested site without scaffolding for an extra 37 days is an unquantifiable advantage to the project team's success.

The Breadth topics, or last two analyses, looked at a structural and mechanical modification without the architectural aesthetics of the building being compromised. Analysis Three, Pedestrian Rerouting, dealt with relocating the travel path for the general public in hopes to create a safer site while improving the structural predictability of the entire building. Utilization of computer software, STAAD Pro, found that extending the truss and eliminating the existing concrete piers was plausible and even would lower the total cost of construction by \$391,997. Analysis Four, Alternative Glazing, examined how the building envelope could be altered to create a more efficient building. The first section looked at a century old construction technique of dual-facades and the associated thermal advantages. The research revealed that the idea was not only cost effective but also had noise reduction capabilities. Secondly photovoltaic solar cells were originally intended to productively aid the buildings electrical demand. The findings showed that the percent change on the building demand was too low and would significantly increase frontend costs with installation ranging from \$6,000 - \$10,000/kW. The total cost of the system presented in the analysis would have incurred the project \$438,950 and the earliest the system would pay for itself would be 17 years. Therefore, the system could be used to educate the public of the future building techniques that they may see in a world with ever rising energy costs.

**AIRPORT TERMINAL  
EXPANSION - EASTERN  
UNITED STATES**


PAUL YINGLING AE SENIOR THESIS 2009



*Appendix A: Detailed Schedule*

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES


PAUL YINGLING AE SENIOR THESIS 2009



Task  
 Split  
 Progress  
 Milestone  
 Summary  
 Project Summary  
 External Tasks  
 External Milestone  
 Deadline

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES


PAUL YINGLING AE SENIOR THESIS 2009



Page 2

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES


PAUL YINGLING AE SENIOR THESIS 2009






# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009




# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



**AIRPORT TERMINAL  
EXPANSION - EASTERN  
UNITED STATES**

PAUL YINGLING AE SENIOR THESIS 2009



*Appendix B: Precast Details*

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES


PAUL YINGLING AE SENIOR THESIS 2009



**Precast Specialties Corp.**

999 Adams Street, P.O. Box 86, Abington, MA 02351

TEL: (781)878-7220 FAX: (781)878-7464



LATERAL TIEBACK TO SHEER WALL


# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



**Precast Specialties Corp.**

999 Adams Street, P.O. Box 86, Abington, MA 02351  
TEL: (781)878-7220 FAX: (781)878-7464



LOAD BEARING CONNECTION DETAIL




# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



**Precast Specialties Corp.**

999 Adams Street, P.O. Box 86, Abington, MA 02351  
TEL: (781)878-7220 FAX: (781)878-7464



LOAD BEARING TO CAST-IN-PLACE CURB


# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



**Precast Specialties Corp.**

999 Adams Street, P.O. Box 86, Abington, MA 02351  
TEL: (781)878-7220 FAX: (781)878-7464



**PANEL TO PANEL CONNECTION**

**AIRPORT TERMINAL  
EXPANSION - EASTERN  
UNITED STATES**

PAUL YINGLING AE SENIOR THESIS 2009



*Appendix C: Structural Results*

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



**Job Information**

Job No.	Sheet No.	1	Rev.
Part			
Ref.			
By		Dhh	5-Feb-09
Checked			
Date			
File		st2.std	DrawTime 25-Feb-2009 16:16

Software licensed to PSJAE

Job Title: \_\_\_\_\_

Client: \_\_\_\_\_

Number of Nodes: 13 Highest Node: 13  
 Number of Elements: 21 Highest Beam: 21

Number of Basic Load Cases: 2  
 Number of Combination Load Cases: 5

Included in this printout are data for: \_\_\_\_\_

All:  The Whole Structure

Included in this printout are results for load cases:

Type	L/C	Name
Primary	1	DEAD
Primary	2	LOAD CASE 2
Combination	3	GENERATED IBC TABLE 1
Combination	4	GENERATED IBC TABLE 2
Combination	5	GENERATED IBC TABLE 3
Combination	6	GENERATED IBC TABLE 4
Combination	7	GENERATED IBC TABLE 5

**Node Displacement Summary**

Node	L/C	X (in)	Y (in)	Z (in)	Resultant (in)	rX (rad)	rY (rad)	rZ (rad)
Max X	9	2LOAD CASE	0.004	-0.112	0.000	0.112	0.000	0.000
Min X	1	4GENERATE1	-0.134	-0.085	0.000	0.159	0.000	0.000
Max Y	12	1DEAD	0.000	0.000	0.000	0.000	0.000	0.000
Min Y	6	4GENERATE1	-0.071	-0.707	0.000	0.711	0.000	0.000
Max Z	1	1DEAD	-0.019	-0.061	0.000	0.064	0.000	0.000
Min Z	1	1DEAD	-0.019	-0.061	0.000	0.064	0.000	0.000
Max rX	1	1DEAD	-0.019	-0.061	0.000	0.064	0.000	0.000
Min rX	1	1DEAD	-0.019	-0.061	0.000	0.064	0.000	0.000
Max rY	1	1DEAD	-0.019	-0.061	0.000	0.064	0.000	0.000
Min rY	1	1DEAD	-0.019	-0.061	0.000	0.064	0.000	0.000
Max rZ	1	1DEAD	-0.019	-0.061	0.000	0.064	0.000	0.000
Min rZ	1	1DEAD	-0.019	-0.061	0.000	0.064	0.000	0.000
Max Rot	6	4GENERATE1	-0.071	-0.707	0.000	0.711	0.000	0.000

Print Time: 25/02/2009 17:01      STAAD Pro for Windows Release 2006      Print Run: 1 of 23

**Beam Displacement Detail Summary**

Displacements shown in **italic** indicate the presence of an offset.

Beam	L/C	d (ft)	X (in)	Y (in)	Z (in)	Resultant (in)
Max X	9	2LOAD CASE	15.389	0.004	-0.112	0.000
Min X	1	4GENERATE1	10.500	-0.134	-0.085	0.000
Max Y	20	1DEAD	12.500	0.000	0.000	0.000
Min Y	6	4GENERATE1	15.389	-0.071	-0.707	0.000
Max Z	1	1DEAD	0.000	0.000	-0.111	0.000
Min Z	1	1DEAD	0.000	0.000	-0.111	0.000
Max Rot	6	4GENERATE1	15.389	-0.071	-0.707	0.000

**Beam End Displacement Summary**

Displacements shown in **italic** indicate the presence of an offset.

Beam	Node	L/C	X (in)	Y (in)	Z (in)	Resultant (in)
Max X	9	9	2LOAD CASE	0.004	-0.112	0.000
Min X	1	1	4GENERATE1	-0.134	-0.085	0.000
Max Y	20	13	1DEAD	0.000	0.000	0.000
Min Y	6	6	4GENERATE1	-0.071	-0.707	0.000
Max Z	1	11	1DEAD	0.000	-0.111	0.000
Min Z	1	11	1DEAD	0.000	-0.111	0.000
Max Rot	6	6	4GENERATE1	-0.071	-0.707	0.000

**Beam End Force Summary**

The signs of the forces at end B of each beam have been reversed. For example this means that the Min Fx entry gives the largest tension value for an beam.

Beam	Node	L/C	Axial (kip)	Fy (kip)	Fz (kip)	Torsion (kip/in)	Bending (kip-ft)
Max Fx	20	1	3GENERATE1	939.470	0.000	0.000	0.000
Min Fx	13	5	4GENERATE1	-366.686	0.000	0.000	0.000
Max Fy	16	2	4GENERATE1	275.754	31.859	0.000	0.000
Min Fy	16	4	4GENERATE1	275.754	-31.859	0.000	0.000
Max Fz	1	11	1DEAD	657.550	0.000	0.000	0.000
Min Fz	1	11	1DEAD	657.550	0.000	0.000	0.000
Max Mx	1	11	1DEAD	657.550	0.000	0.000	0.000
Min Mx	1	11	1DEAD	657.550	0.000	0.000	0.000
Max My	1	11	1DEAD	657.550	0.000	0.000	0.000
Min My	1	11	1DEAD	657.550	0.000	0.000	0.000
Max Mz	1	11	1DEAD	657.550	0.000	0.000	0.000
Min Mz	1	11	1DEAD	657.550	0.000	0.000	0.000

Print Time: 25/02/2009 17:01      STAAD Pro for Windows Release 2006      Print Run: 2 of 23

**Beam Force Detail Summary**

Sign convention as diagrams - positive above line, negative below line except Fx where positive is compression. Distance of A is given from beam end A.

Beam	L/C	d (ft)	Axial (kip)	Fy (kip)	Fz (kip)	Torsion (kip/in)	My (kip-ft)	Mz (kip-ft)
Max Fx	20	3GENERATE1	0.000	939.470	0.000	0.000	0.000	0.000
Min Fx	13	4GENERATE1	0.000	-366.686	0.000	0.000	0.000	0.000
Max Fy	16	4GENERATE1	0.000	275.754	31.859	0.000	0.000	0.000
Min Fy	16	4GENERATE1	22.500	275.754	-31.859	0.000	0.000	0.000
Max Fz	1	1DEAD	0.000	657.550	0.000	0.000	0.000	0.000
Min Fz	1	1DEAD	0.000	657.550	0.000	0.000	0.000	0.000
Max Mx	1	1DEAD	0.000	657.550	0.000	0.000	0.000	0.000
Min Mx	1	1DEAD	0.000	657.550	0.000	0.000	0.000	0.000
Max My	1	1DEAD	0.000	657.550	0.000	0.000	0.000	0.000
Min My	1	1DEAD	0.000	657.550	0.000	0.000	0.000	0.000
Max Mz	1	1DEAD	0.000	657.550	0.000	0.000	0.000	0.000
Min Mz	1	1DEAD	0.000	657.550	0.000	0.000	0.000	0.000

**Beam Maximum Moments**

Distances to maxima are given from beam end A.

Beam	Node A	Length (ft)	L/C	d (ft)	Max My (kip-ft)	d (ft)	Max Mz (kip-ft)
1	11	10.500	1DEAD	Max +ve	0.000	0.000	0.000
			2LOAD CASE	Max +ve	0.000	0.000	0.000
			3GENERATE1	Max +ve	0.000	0.000	0.000
			4GENERATE1	Max +ve	0.000	0.000	0.000
			5GENERATE1	Max +ve	0.000	0.000	0.000
			6GENERATE1	Max +ve	0.000	0.000	0.000
			7GENERATE1	Max +ve	0.000	0.000	0.000
2	1	19.981	1DEAD	Max +ve	0.000	0.000	0.000
			2LOAD CASE	Max +ve	0.000	0.000	0.000
			3GENERATE1	Max +ve	0.000	0.000	0.000
			4GENERATE1	Max +ve	0.000	0.000	0.000
			5GENERATE1	Max +ve	0.000	0.000	0.000
			6GENERATE1	Max +ve	0.000	0.000	0.000
			7GENERATE1	Max +ve	0.000	0.000	0.000

Print Time: 25/02/2009 17:01      STAAD Pro for Windows Release 2006      Print Run: 3 of 23

**Beam Maximum Moments Cont...**

Beam	Node A	Length (ft)	L/C	d (ft)	Max My (kip-ft)	d (ft)	Max Mz (kip-ft)
			6GENERATE1	Max +ve	0.000	0.000	0.000
			7GENERATE1	Max +ve	0.000	0.000	0.000
3	2	15.389	1DEAD	Max +ve	0.000	0.000	0.000
			2LOAD CASE	Max +ve	0.000	0.000	0.000
			3GENERATE1	Max +ve	0.000	0.000	0.000
			4GENERATE1	Max +ve	0.000	0.000	0.000
			5GENERATE1	Max +ve	0.000	0.000	0.000
			6GENERATE1	Max +ve	0.000	0.000	0.000
			7GENERATE1	Max +ve	0.000	0.000	0.000
4	3	15.389	1DEAD	Max +ve	0.000	0.000	0.000
			2LOAD CASE	Max +ve	0.000	0.000	0.000
			3GENERATE1	Max +ve	0.000	0.000	0.000
			4GENERATE1	Max +ve	0.000	0.000	0.000
			5GENERATE1	Max +ve	0.000	0.000	0.000
			6GENERATE1	Max +ve	0.000	0.000	0.000
			7GENERATE1	Max +ve	0.000	0.000	0.000
5	4	15.389	1DEAD	Max +ve	0.000	0.000	0.000
			2LOAD CASE	Max +ve	0.000	0.000	0.000
			3GENERATE1	Max +ve	0.000	0.000	0.000
			4GENERATE1	Max +ve	0.000	0.000	0.000
			5GENERATE1	Max +ve	0.000	0.000	0.000
			6GENERATE1	Max +ve	0.000	0.000	0.000
			7GENERATE1	Max +ve	0.000	0.000	0.000

Print Time: 25/02/2009 17:01      STAAD Pro for Windows Release 2006      Print Run: 4 of 23





# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



Beam	Node A	Length (ft)	LIC	d (ft)	Max Mx (kip-in)	d (ft)	Max Mz (kip-in)
19	8	22.500	1DEAD	0.000	0.000	0.000	0.000
			2LOAD CASE	0.000	0.000	0.000	0.000
			3GENERATE1	0.000	0.000	0.000	0.000
			4GENERATE1	0.000	0.000	0.000	0.000
			5GENERATE1	0.000	0.000	0.000	0.000
			6GENERATE1	0.000	0.000	0.000	0.000
			7GENERATE1	0.000	0.000	0.000	0.000
20	1	12.500	1DEAD	0.000	0.000	0.000	0.000
			2LOAD CASE	0.000	0.000	0.000	0.000
			3GENERATE1	0.000	0.000	0.000	0.000
			4GENERATE1	0.000	0.000	0.000	0.000
			5GENERATE1	0.000	0.000	0.000	0.000
			6GENERATE1	0.000	0.000	0.000	0.000
			7GENERATE1	0.000	0.000	0.000	0.000
21	10	23.000	1DEAD	0.000	0.000	0.000	0.000
			2LOAD CASE	0.000	0.000	0.000	0.000
			3GENERATE1	0.000	0.000	0.000	0.000
			4GENERATE1	0.000	0.000	0.000	0.000
			5GENERATE1	0.000	0.000	0.000	0.000
			6GENERATE1	0.000	0.000	0.000	0.000
			7GENERATE1	0.000	0.000	0.000	0.000

Beam	Node A	Length (ft)	LIC	d (ft)	Max Fz (kip)	d (ft)	Max Fy (kip)
1	11	10.500	1DEAD	0.000	0.000	0.000	0.000
			2LOAD CASE	0.000	0.000	0.000	0.000
			3GENERATE1	0.000	0.000	0.000	0.000
			4GENERATE1	0.000	0.000	0.000	0.000
			5GENERATE1	0.000	0.000	0.000	0.000
			6GENERATE1	0.000	0.000	0.000	0.000
			7GENERATE1	0.000	0.000	0.000	0.000
2	1	19.981	1DEAD	0.000	0.000	0.000	0.000
			2LOAD CASE	0.000	0.000	0.000	0.000
			3GENERATE1	0.000	0.000	0.000	0.000
			4GENERATE1	0.000	0.000	0.000	0.000
			5GENERATE1	0.000	0.000	0.000	0.000
			6GENERATE1	0.000	0.000	0.000	0.000
			7GENERATE1	0.000	0.000	0.000	0.000
3	2	15.389	1DEAD	0.000	0.000	0.000	0.000
			2LOAD CASE	0.000	0.000	0.000	0.000
			3GENERATE1	0.000	0.000	0.000	0.000
			4GENERATE1	0.000	0.000	0.000	0.000
			5GENERATE1	0.000	0.000	0.000	0.000
			6GENERATE1	0.000	0.000	0.000	0.000
			7GENERATE1	0.000	0.000	0.000	0.000
4	3	15.389	1DEAD	0.000	0.000	0.000	0.000
			2LOAD CASE	0.000	0.000	0.000	0.000
			3GENERATE1	0.000	0.000	0.000	0.000
			4GENERATE1	0.000	0.000	0.000	0.000
			5GENERATE1	0.000	0.000	0.000	0.000
			6GENERATE1	0.000	0.000	0.000	0.000
			7GENERATE1	0.000	0.000	0.000	0.000

Beam	Node A	Length (ft)	LIC	d (ft)	Max Fz (kip)	d (ft)	Max Fy (kip)
5	4	15.389	1DEAD	0.000	0.000	0.000	0.000
			2LOAD CASE	0.000	0.000	0.000	0.000
			3GENERATE1	0.000	0.000	0.000	0.000
			4GENERATE1	0.000	0.000	0.000	0.000
			5GENERATE1	0.000	0.000	0.000	0.000
			6GENERATE1	0.000	0.000	0.000	0.000
			7GENERATE1	0.000	0.000	0.000	0.000
6	5	15.389	1DEAD	0.000	0.000	0.000	0.000
			2LOAD CASE	0.000	0.000	0.000	0.000
			3GENERATE1	0.000	0.000	0.000	0.000
			4GENERATE1	0.000	0.000	0.000	0.000
			5GENERATE1	0.000	0.000	0.000	0.000
			6GENERATE1	0.000	0.000	0.000	0.000
			7GENERATE1	0.000	0.000	0.000	0.000
7	6	15.389	1DEAD	0.000	0.000	0.000	0.000
			2LOAD CASE	0.000	0.000	0.000	0.000
			3GENERATE1	0.000	0.000	0.000	0.000

Beam	Node A	Length (ft)	LIC	d (ft)	Max Fz (kip)	d (ft)	Max Fy (kip)
8	7	15.389	1DEAD	0.000	0.000	0.000	0.000
			2LOAD CASE	0.000	0.000	0.000	0.000
			3GENERATE1	0.000	0.000	0.000	0.000
			4GENERATE1	0.000	0.000	0.000	0.000
			5GENERATE1	0.000	0.000	0.000	0.000
			6GENERATE1	0.000	0.000	0.000	0.000
			7GENERATE1	0.000	0.000	0.000	0.000
9	8	15.389	1DEAD	0.000	0.000	0.000	0.000
			2LOAD CASE	0.000	0.000	0.000	0.000
			3GENERATE1	0.000	0.000	0.000	0.000
			4GENERATE1	0.000	0.000	0.000	0.000
			5GENERATE1	0.000	0.000	0.000	0.000
			6GENERATE1	0.000	0.000	0.000	0.000
			7GENERATE1	0.000	0.000	0.000	0.000
10	9	15.389	1DEAD	0.000	0.000	0.000	0.000
			2LOAD CASE	0.000	0.000	0.000	0.000
			3GENERATE1	0.000	0.000	0.000	0.000
			4GENERATE1	0.000	0.000	0.000	0.000





# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



Beam	Node A	Length (ft)	L/C	d (ft)	Max Fx (kip)
2	1	19.981	1 DEAD	Max -ve	0.000 25.690
				Max +ve	
			2 LOAD CASE	Max -ve	0.000 128.451
				Max +ve	
			3 GENERATE1	Max -ve	0.000 35.966
				Max +ve	
			4 GENERATE1	Max -ve	0.000 236.350
	Max +ve				
3	2	15.389	1 DEAD	Max -ve	0.000 -11.102
				Max +ve	
			2 LOAD CASE	Max -ve	0.000 -55.509
				Max +ve	
			3 GENERATE1	Max -ve	0.000 -15.543
				Max +ve	
			4 GENERATE1	Max -ve	0.000 -102.137
	Max +ve				
4	3	15.389	1 DEAD	Max -ve	0.000 11.102
				Max +ve	
			2 LOAD CASE	Max -ve	0.000 55.509
				Max +ve	
			3 GENERATE1	Max -ve	0.000 15.543
				Max +ve	
			4 GENERATE1	Max -ve	0.000 102.137
	Max +ve				
5	4	15.389	1 DEAD	Max -ve	0.000 -1.209
				Max +ve	
			2 LOAD CASE	Max -ve	0.000 -1.209
				Max +ve	
			3 GENERATE1	Max -ve	0.000 -1.209
				Max +ve	
			4 GENERATE1	Max -ve	0.000 -1.209
	Max +ve				

Print Run 17 of 23

Beam	Node A	Length (ft)	L/C	d (ft)	Max Fx (kip)
6	5	15.389	1 DEAD	Max -ve	0.000 1.209
				Max +ve	
			2 LOAD CASE	Max -ve	0.000 6.946
				Max +ve	
			3 GENERATE1	Max -ve	0.000 1.683
				Max +ve	
			4 GENERATE1	Max -ve	0.000 11.124
	Max +ve				
7	6	15.389	1 DEAD	Max -ve	0.000 8.884
				Max +ve	
			2 LOAD CASE	Max -ve	0.000 43.418
				Max +ve	
			3 GENERATE1	Max -ve	0.000 12.157
				Max +ve	
			4 GENERATE1	Max -ve	0.000 79.889
	Max +ve				
8	7	15.389	1 DEAD	Max -ve	0.000 -8.884
				Max +ve	
			2 LOAD CASE	Max -ve	0.000 -43.418
				Max +ve	
			3 GENERATE1	Max -ve	0.000 -12.157
				Max +ve	
			4 GENERATE1	Max -ve	0.000 -79.889
	Max +ve				

Print Run 18 of 23

Beam	Node A	Length (ft)	L/C	d (ft)	Max Fx (kip)
9	8	15.389	1 DEAD	Max -ve	0.000 18.576
				Max +ve	
			2 LOAD CASE	Max -ve	0.000 92.882
				Max +ve	
			3 GENERATE1	Max -ve	0.000 26.007
				Max +ve	
			4 GENERATE1	Max -ve	0.000 170.903
	Max +ve				
10	9	15.389	1 DEAD	Max -ve	0.000 -18.576
				Max +ve	
			2 LOAD CASE	Max -ve	0.000 -92.882
				Max +ve	
			3 GENERATE1	Max -ve	0.000 -26.007
				Max +ve	
			4 GENERATE1	Max -ve	0.000 -170.903
	Max +ve				
11	1	28.250	1 DEAD	Max -ve	0.000 -16.719
				Max +ve	
			2 LOAD CASE	Max -ve	0.000 -21.857
				Max +ve	
			3 GENERATE1	Max -ve	0.000 -109.286
				Max +ve	
			4 GENERATE1	Max -ve	0.000 -30.800
	Max +ve				
12	3	22.500	1 DEAD	Max -ve	0.000 -38.089
				Max +ve	
			2 LOAD CASE	Max -ve	0.000 -190.446
				Max +ve	
			3 GENERATE1	Max -ve	0.000 -53.325
				Max +ve	
			4 GENERATE1	Max -ve	0.000 -350.421
	Max +ve				
13	5	22.500	1 DEAD	Max -ve	0.000 -39.857
				Max +ve	
			2 LOAD CASE	Max -ve	0.000 -199.286
				Max +ve	
			3 GENERATE1	Max -ve	0.000 -55.800
				Max +ve	
			4 GENERATE1	Max -ve	0.000 -368.688
	Max +ve				
14	7	22.500	1 DEAD	Max -ve	0.000 -27.161
				Max +ve	
			2 LOAD CASE	Max -ve	0.000 -135.804
				Max +ve	
			3 GENERATE1	Max -ve	0.000 -38.025
				Max +ve	
			4 GENERATE1	Max -ve	0.000 -249.879
	Max +ve				

Print Run 19 of 23

Beam	Node A	Length (ft)	L/C	d (ft)	Max Fx (kip)
15	4	22.500	1 DEAD	Max -ve	0.000 -39.857
				Max +ve	
			2 LOAD CASE	Max -ve	0.000 -199.286
				Max +ve	
			3 GENERATE1	Max -ve	0.000 -55.800
				Max +ve	
			4 GENERATE1	Max -ve	0.000 -368.688
	Max +ve				
16	6	22.500	1 DEAD	Max -ve	0.000 -39.857
				Max +ve	
			2 LOAD CASE	Max -ve	0.000 -199.286
				Max +ve	
			3 GENERATE1	Max -ve	0.000 -55.800
				Max +ve	
			4 GENERATE1	Max -ve	0.000 -368.688
	Max +ve				

Print Run 20 of 23

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



Beam	Node A	Length (ft)	L/C	d (ft)	Max Fx (kip)
15	11	17.000	7.GENERATE1	Max -ve	0.000 -24.445
				Max +ve	0.000 0.000
			1.DEAD	Max -ve	0.000 0.000
				Max +ve	0.000 0.000
			2.LOAD CASE	Max -ve	0.000 -0.000
				Max +ve	0.000 -0.000
			3.GENERATE1	Max -ve	0.000 0.000
				Max +ve	0.000 0.000
			4.GENERATE1	Max -ve	0.000 0.000
				Max +ve	0.000 0.000
			5.GENERATE1	Max -ve	0.000 0.000
				Max +ve	0.000 0.000
			6.GENERATE1	Max -ve	0.000 0.000
				Max +ve	0.000 0.000
16	2	22.500	1.DEAD	Max -ve	0.000 29.973
				Max +ve	0.000 0.000
			2.LOAD CASE	Max -ve	0.000 149.866
				Max +ve	0.000 41.963
			3.GENERATE1	Max -ve	0.000 41.963
				Max +ve	0.000 0.000
			4.GENERATE1	Max -ve	0.000 275.754
				Max +ve	0.000 185.834
			5.GENERATE1	Max -ve	0.000 185.834
				Max +ve	0.000 35.988
			6.GENERATE1	Max -ve	0.000 35.988
				Max +ve	0.000 28.978
			7.GENERATE1	Max -ve	0.000 28.978
				Max +ve	0.000 0.000
17	4	22.500	1.DEAD	Max -ve	0.000 38.973
				Max +ve	0.000 0.000
			2.LOAD CASE	Max -ve	0.000 194.866
				Max +ve	0.000 54.562
			3.GENERATE1	Max -ve	0.000 54.562
				Max +ve	0.000 358.554
			4.GENERATE1	Max -ve	0.000 358.554
				Max +ve	0.000 241.834
			5.GENERATE1	Max -ve	0.000 241.834
				Max +ve	0.000 46.768
			6.GENERATE1	Max -ve	0.000 46.768
				Max +ve	0.000 35.076
			7.GENERATE1	Max -ve	0.000 35.076
				Max +ve	0.000 0.000
18	6	22.500	1.DEAD	Max -ve	0.000 33.509
				Max +ve	0.000 0.000

Beam	Node A	Length (ft)	L/C	d (ft)	Max Fx (kip)
19	8	22.500	1.DEAD	Max -ve	0.000 13.580
				Max +ve	0.000 67.802
			2.LOAD CASE	Max -ve	0.000 19.013
				Max +ve	0.000 124.939
			3.GENERATE1	Max -ve	0.000 124.939
				Max +ve	0.000 84.198
			4.GENERATE1	Max -ve	0.000 84.198
				Max +ve	0.000 16.296
			5.GENERATE1	Max -ve	0.000 16.296
				Max +ve	0.000 12.222
			6.GENERATE1	Max -ve	0.000 12.222
				Max +ve	0.000 0.000
			7.GENERATE1	Max -ve	0.000 0.000
				Max +ve	0.000 0.000
20	1	12.500	1.DEAD	Max -ve	0.000 671.050
				Max +ve	0.000 0.000
			2.LOAD CASE	Max -ve	0.000 80.250
				Max +ve	0.000 939.470
			3.GENERATE1	Max -ve	0.000 939.470
				Max +ve	0.000 933.660
			4.GENERATE1	Max -ve	0.000 933.660
				Max +ve	0.000 885.510
			5.GENERATE1	Max -ve	0.000 885.510
				Max +ve	0.000 805.260
			6.GENERATE1	Max -ve	0.000 805.260
				Max +ve	0.000 603.945
			7.GENERATE1	Max -ve	0.000 603.945
				Max +ve	0.000 0.000
21	10	23.000	1.DEAD	Max -ve	0.000 671.050
				Max +ve	0.000 80.250

Beam	Node A	Length (ft)	L/C	d (ft)	Max Fx (kip)
12	1	12.500	3.GENERATE1	Max -ve	0.000 939.470
				Max +ve	0.000 0.000
			4.GENERATE1	Max -ve	0.000 933.660
				Max +ve	0.000 0.000
			5.GENERATE1	Max -ve	0.000 885.510
				Max +ve	0.000 0.000
			6.GENERATE1	Max -ve	0.000 805.260
				Max +ve	0.000 0.000
			7.GENERATE1	Max -ve	0.000 603.945
				Max +ve	0.000 0.000

Reaction Summary							
	Node	L/C	Horizontal			Moment	
			FX (kip)	FY (kip)	FZ (kip)	MX (kip-in)	MZ (kip-in)
Max FX	12	1.DEAD	0.000	671.050	0.000	0.000	0.000
Min FX	12	1.DEAD	0.000	671.050	0.000	0.000	0.000
Max FY	12	3.GENERATE1	0.000	939.470	0.000	0.000	0.000
Min FY	12	2.LOAD CASE	0.000	80.250	0.000	0.000	0.000
Max FZ	12	1.DEAD	0.000	671.050	0.000	0.000	0.000
Min FZ	12	1.DEAD	0.000	671.050	0.000	0.000	0.000
Max MX	12	1.DEAD	0.000	671.050	0.000	0.000	0.000
Min MX	12	1.DEAD	0.000	671.050	0.000	0.000	0.000
Max MY	12	1.DEAD	0.000	671.050	0.000	0.000	0.000
Min MY	12	1.DEAD	0.000	671.050	0.000	0.000	0.000
Max MZ	12	1.DEAD	0.000	671.050	0.000	0.000	0.000
Min MZ	12	1.DEAD	0.000	671.050	0.000	0.000	0.000

**AIRPORT TERMINAL  
EXPANSION - EASTERN  
UNITED STATES**

PAUL YINGLING AE SENIOR THESIS 2009



*Appendix D: Glazing Specifications*

# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009




Make-Up Sheet



## Silk-Screened Low-E (VE) Insulating Glass (50% Coverage V933) VE 2-55

### Make-up:



#### Notes:

- 1/4" (6mm) green VE-55 #2 and 50% Coverage V933 #2
- 1/2" (13.2mm) airspace
- 1/4" (6mm) clear

<b>Product</b>	VE 2-55
<b>Transmittance</b>	
Visible Light	22%
Solar Energy	10%
Ultra-Violet*	3%
<b>Reflectance</b>	
Visible Light-Exterior	10%
Visible Light-Interior	18%
Solar Energy	8%
<b>ASHRAE U-Value</b>	
Winter Nighttime	0.31 Btu/(hr x sqft x °F)
Summer Daytime	0.29 Btu/(hr x sqft x °F)
<b>European U-Value</b>	1.6
<b>Shading Coefficient</b>	0.21
<b>Relative Heat Gain</b>	47 Btu/hr x sqft
<b>Solar Factor (SHGC)</b>	0.18
<b>LSG</b>	1.22

\* Ultra-violet defined as 300 to 380 nanometers (nm)



# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009



Make-Up Sheet



## Solarscreen Low-E (VE) Laminated Glass VE 2-55

**Make-up:**



Notes:  
1/4" (6mm) green VE-55 #2  
.030" (.76mm) PVB  
1/4" (6mm) clear

<b>Product</b>	VE 2-55
<b>Transmittance</b>	
Visible Light	42%
Solar Energy	19%
Ultra-Violet*	<1%
<b>Reflectance</b>	
Visible Light-Exterior	8%
Visible Light-Interior	12%
Solar Energy	8%
<b>ASHRAE U-Value</b>	
Winter Nighttime	0.97 Btu/(hr x sqft x °F)
Summer Daytime	0.88 Btu/(hr x sqft x °F)
<b>European U-Value</b>	5.4
<b>Shading Coefficient</b>	0.49
<b>Relative Heat Gain</b>	110 Btu/hr x sqft
<b>Solar Factor (SHGC)</b>	0.42
<b>LSG</b>	1

\* Ultra-violet defined as 300 to 380 nanometers (nm)



# AIRPORT TERMINAL EXPANSION - EASTERN UNITED STATES

PAUL YINGLING AE SENIOR THESIS 2009




Make-Up Sheet



## Uncoated Insulating Glass Clear -

### Make-up:



#### Notes:

- 1/4" (6mm) clear
- 1/2" (13.2mm) airspace
- 1/4" (6mm) clear

<b>Product</b>	Clear -
<b>Transmittance</b>	
Visible Light	79%
Solar Energy	61%
Ultra-Violet*	46%
<b>Reflectance</b>	
Visible Light-Exterior	14%
Visible Light-Interior	14%
Solar Energy	11%
<b>ASHRAE U-Value</b>	
Winter Nighttime	0.47 Btu/(hr x sqft x °F)
Summer Daytime	0.49 Btu/(hr x sqft x °F)
<b>European U-Value</b>	2.8
<b>Shading Coefficient</b>	0.81
<b>Relative Heat Gain</b>	169 Btu/hr x sqft
<b>Solar Factor (SHGC)</b>	0.7
<b>LSG</b>	1.12

\* Ultra-violet defined as 300 to 380 nanometers (nm)