



Project X NYC, NY

Luke Gray

Construction Management

Technical Report 2

Consultant: Dr. Rob Leicht

October 31, 2010

LUKE GRAY CONSTRUCTION MANAGEMENT

PROJECT X NEW YORK

MECHANICAL, ELECTRICAL, LIGHTING

MECHANICAL-AHU'S RANGING FROM 8650-6300CFM ON EACH FLOOR, SUPPLEMENTARY HYDRONIC FIN TUBE BASEBOARD RADIATION ALONG THE PERIMETER

ELECTRICAL-POWER IS DISTRIBUTED WITH 208/120V, 3-PHASE, 4 WIRE PANELS ON EACH FLOOR; DRY TYPE TRANSFORMER

LIGHTING-THERE ARE MANY TYPES LAMPS USED WITHIN THE BUILDING INCLUDING FLUORESCENT, INCANDESCENT, METAL HALIDE, H.I.D. FIXTURES. THE EMERGENCY LIGHTING FOR THE BUILDING IS SUPPLIED BY FLUORESCENT FIXTURES WITH A 90 MINUTE EMERGENCY BATTERY PACK.

ARCHITECTURAL & STRUCTURAL

FOUNDATION-REINFORCED MAT SLAB

FLOOR-10" DEEP TWO-WAY FLOOR SLAB

COLUMN LAYOUT 24' x 24'

EXTERIOR WALLS NATURAL BRICK WITH THREE CURTAIN WALL SLOTS TO BREAK UP THE BRICK FACADE THAT BLENDS SEAMLESSLY INTO THE SURROUNDING HISTORICALLY RICH TOWN-HOUSES

GREEN ROOFS THERE ARE THREE LEVELS OF 12" INTENSIVE GREEN ROOFS

CM-SKANSKA

ARCHITECT-MA ARCHITECTS

STRUCTURAL-ROBERT SILMAN

MECHANICAL-FMC ASSOCIATES

LIGHTING-RS LIGHTING DESIGN

DURATION-AUGUST 2008-JULY 2010

SIZE-54,640SF

BUILDING USE-OFFICES & THEATRE

[HTTP://WWW.ENGR.PSU.EDU/AE/THESIS/PORTFOLIOS/2011/LAG290/INDEX.HTML](http://www.engr.psu.edu/ae/thesis/portfolios/2011/LAG290/index.html)



Executive Summary

Technical report two consists of an extensive schedule and structural cost analysis of Project X. This report includes a detailed project schedule, a site logistic plan, a structural estimate, and general conditions estimate.

The detailed schedule was organized by trade in order to identify gaps in the schedule that can be eliminated in the individual trades to decrease the schedule.

The site logistics identifies the congestion of working in a city location. The site does not offer the subcontractors potential for material storage. Thus, each contractor had to coordinate each delivery to arrive precisely on the day the material was required. Another important lesson learned was the obstacles of getting Department of Transportation approval to close down one of the traffic lanes in order to provide adequate room for material delivery, dumpsters, and crane space.

A Revit Structures three dimensional model was constructed to quantify the concrete needed for the structure. The Revit model does not take into account the concrete in monolithic columns passing through slabs and foundation walls. This is a very important point when considering using Revit for material takeoff. Special attention must be paid to how the model was constructed by the estimator. Further research is needed to discover other materials that might have similar exclusions when doing material takeoffs from Revit. This can prove to be a vital consideration when constructing an estimate for a hard bid project.

The total structural steel and concrete estimate is \$2,595,265. The total general conditions estimate is \$1,704,019 and \$77,455 per month based on a 22 week construction schedule. The general conditions estimate includes the staffing and general condition items. RS Means 2008 Cost works was used for the structural and general conditions estimate.

The new building will serve the community as a playhouse, office support space, as well as university office space. The site rests in a community with rich historical brick building. At the playhouse many special measures were taken to restore the historical features of the building the entrance doors, entrance canopy, masonry facade, signage, and lighting. Understanding the historical requirements upheld by the Greenwich District community was vital to ensuring successful project completion.

The existing four story 33,000SF building consists of four separate townhouses that were merged together during the 1940's. The building has historical and cultural significance in that it houses a 4,400SF playhouse on the ground and basement levels which is scheduled to remain. As part of the project, the interior of the theater will be demolished and rebuilt. Collaboration between the construction manager, architect, surveyor, and engineers was very important to the conservation of the existing walls.

Table of Contents

| | |
|---|-----------|
| A. Detailed Project Schedule..... | 1 |
| B. Site Logistic Plan..... | 2 |
| C. Detailed Structural Systems Estimate..... | 7 |
| D. General Conditions Estimate..... | 15 |
| E. Critical Industry Issues..... | 18 |
| Appendix | |
| Appendix I: Detailed Schedule..... | 20 |
| Appendix II: Details of Structural Systems Estimate..... | 25 |

A. Detailed Project Schedule

The procurement phase consists of a variety of activities. Since design decisions were made during the construction process, the procurement phase of construction was extended, because the project is a fast-track project. The procurement stages include: prepare bidders list, review of bid documents, owner review, finalize bidders, bid period, evaluation of bidder, owner approval of bidders, and awarding subcontractor.

Throughout the construction process there were many complicated hurdles to overcome, for example, the demolition phase which lasted 31 weeks. This phase was extensive, because there were many requirements by New York City Department of Building, Department of Transportation, protective measures taken to protect adjacent structures, a protective walkway, and scaffolding for the alley. The demolition progressed linearly from the Roof Parapet to the 1st floor with duration of 60 days. The longest phase was the demolition of the 2nd floor, which lasted 26 days. This was needed to allow the tradesmen time to demo around theatres walls by hand demolition, which remained in place. In addition, the south and north adjacent buildings needed to be braced.

Excavation and foundations were a great engineering feat. Underpinning and footing heel blocks were needed to ensure there was no settlement of the playhouse's existing brick walls. Other measures included: sheeting and tie backs, addition underpinning of adjacent structures, and installation of a dewatering system. The primary new foundation system is a mat slab. From the foundation stage the project progressed into the building frame and exterior frame.

A Cast-in-place concrete frame supports the 10" two-way concrete slab. The concrete columns and concrete slab were constructed with duration of 5 days per floor. The masonry perimeter walls were laid at a rate of eight days per floor. The concrete superstructure is on the critical path to completion. Since, the superstructure was poured from October to February 24/7 temporary heat was needed to ensure a timely curing of the concrete. Temporary heat was also needed for the building finishes. Following the superstructure on the critical path to completion is the MEP and interior fit out.

The Cellar, Basement and First Floor all have the same square footage. The only difference is there is a telephone closet consisting of Backer Boards, panel boxes for electrical room, and electrical closet for distribution panels on the Cellar Floor. The Second Floor had very similar workflow and durations; therefore only a detailed Second Floor schedule is shown in the detailed schedule. The trades are separated in the schedule to show gaps in the trades that can be clearly identified thereby allowing for compression of the schedule.

B. Site Logistic Plan

The Project was divided into three primary phases. These three phases are illustrated in Figure 1

Stage 1: 5/15/09-9/1/09 this phase include the below grade activities of the demolition, excavation, and foundations.

Stage 2: 9/1/09-5/1/10 this phase includes the building frame, exterior façade, site preparation, site finishes, and interior fit-out.

Stage 3: 10/14/09-10/16/09 this phase is when the domestic water tie was made.

5/12/10-5/15/10 during this time period new sidewalks were poured, trees were planted,

Stage 2 was chosen because it had the most activities due to the numerous trades involved. The building height required trash chutes to be utilized; these were maintained by Skanska throughout the construction. The building consists of 4 segments of brick walls which were laid on the two segments on the outer most north and south first. In order to accommodate the loading of material for the interior fit-out, this is shown in Figure3.

1. The material loading was between columns 6-8 shown on Figure 3 in blue from 11/1/09 to 2/1/10.
2. The material loading was between columns 5-6 shown on Figure 3 in green from 2/1/10 to 2/15/10.
3. The material loading was between columns 6-8 using selected windows only shown on Figure 3 in orange from 2/15/10 to 4/1/10.

One of the lanes on a two way street was closed during the construction to allow for deliveries to be made on a daily basis. Throughout the duration of the construction a crawler crane was used extensively. This crawler crane was placed on the closed traffic lane. The crawler crane was used from the start of construction until the interior finishes activities started. This required a construction barricade to be constructed to allow for construction deliveries and a path for the crane to move. During nonworking hours a pedestrian walk with overhead protection passed in between the barricade and the building footprint.





Figure 1: Shows the Site Logistic Plan for Stage 2



Figure 4: Illustrates the Material Loading Entrance of the building



█ Actual Work
 █ Critical Remaining Work
 ▼ Summary
█ Remaining Work
 ◆ Milestone

C. Detailed Structural Systems Estimate

| Summary of Detailed Structural Estimate | |
|--|-----------------|
| BEAMS | \$ 45,754.77 |
| STRUCTURAL STEEL | \$ 50,650.78 |
| COLUMNS | \$ 309,425.00 |
| COLUMNS (For BUTRICES TO EXISTING MASONRY WALL | \$ 3,891.60 |
| ELEVATED SLABS | \$ 1,445,630.97 |
| SLAB ON GRADE | \$ 10,596.01 |
| FOUNDATION MAT SLAB | \$ 474,486.75 |
| FOUNDATION WALLS | \$ 205,286.79 |
| FOUNDATION FOOTINGS | \$ 30,129.12 |
| FOUNDATIONS GRADE BEAMS | \$ 19,414.15 |
| Total | \$ 2,595,265.94 |

Table 1: Shows the Summary of the Detailed Structural Estimate

A Revit Structures model was constructed to provide the quantity takeoffs. The model can give the construction team a very clear idea of the three dimensional properties of the structure. The columns takeoff of concrete does not include the quantity of concrete that pass through the slabs in monolithic columns. Also the concrete columns that pass through the foundation walls is included in the foundation walls' quantity of concrete and is not included in the columns' quantities; this is shown visually in Figure 6 the column schedule produced by Revit.

Exclusions and Assumptions:

- Stud rails
- Mechanical Shaft openings
- Underpinning with tiebacks of Adjacent and Existing Structure
- Tie backs
- Structural steel required to temporary brace existing masonry walls during construction
- Retaining walls
- Excavation costs
- Waterproofing membrane
- Concrete Stairwells
- Sleeves for conduct and water holes




Figure 4: Shows the Three Dimensional Model of the Revit Structures Model




Figure 5: Shows the East Elevation of the Revit Structures Model

Luke Gray
 NYC New York 10012
 Data Release : Year 2008 Quarter 1
 Labor Type: Standard Union

Unit Cost Estimate

| Quantity | LineNumber | Source | SubContract | Description | Crew | Daily Output | Labor Hours | Unit | Mat. O&P | Labor O&P | Equip. O&P | Total O&P | Ext. Mat. O&P | Ext. Labor O&P | Ext. Equip. O&P | Ext. Total O&P |
|--|--------------|--------|-------------|--|--------|--------------|-------------|------|-------------|-------------|------------|-------------|---------------|----------------|-----------------|----------------|
| BEAMS | | | | \$ 45,754.77 | | | | | | | | | | | | |
| 1126 | 031113202050 | | | C.I.P. concrete forms, beams and girders, interior, plywood, 12" wide, 2 use, includes shoring, erecting, bracing, stripping and cleaning | C2 | 340 | 0.14 | SFCA | \$ 2.52 | \$ 15.68 | \$ - | \$ 18.20 | \$ 2,837.52 | \$ 17,655.68 | \$ - | \$ 20,493.20 |
| 335.2 | 031113202550 | | | C.I.P. concrete forms, beams and girders, interior, plywood, 24" wide, 2 use, includes shoring, erecting, bracing, stripping and cleaning | C2 | 365 | 0.132 | SFCA | \$ 1.88 | \$ 14.62 | \$ - | \$ 16.50 | \$ 630.18 | \$ 4,900.62 | \$ - | \$ 5,530.80 |
| 26.922 | 033105700050 | | | Structural concrete, placing, beam, small, elevated, pumped, includes vibrating, excludes material | C20 | 60 | 1.067 | C.Y. | \$ - | \$ 93.95 | \$ 16.54 | \$ 110.49 | \$ - | \$ 2,529.32 | \$ 445.29 | \$ 2,974.61 |
| 26.922 | 33105350400 | | | Structural concrete, ready mix, normal weight, 5000 psi, includes local aggregate, sand, portland cement and water, delivered, excludes all additives and treatments | | | | C.Y. | \$ 129.72 | \$ - | \$ - | \$ 129.72 | \$ 3,492.32 | \$ - | \$ - | \$ 3,492.32 |
| 2.514044 | 032110600100 | | | Reinforcing steel, in place, beams and girders, #3 to #7, A615, grade 60, incl labor for accessories, excl material for accessories | 4 Rodm | 1.6 | 20 | Ton | \$ 1,164.40 | \$ 2,770.60 | \$ - | \$ 3,935.00 | \$ 2,927.35 | \$ 6,965.41 | \$ - | \$ 9,892.76 |
| 1.196748 | 032110600150 | | | Reinforcing steel, in place, beams and girders, #8 to # 18, A615, grade 60, incl labor for accessories, excl material for accessories | 4 Rodm | 2.7 | 11.852 | Ton | \$ 1,164.40 | \$ 1,652.47 | \$ - | \$ 2,816.87 | \$ 1,393.49 | \$ 1,977.59 | \$ - | \$ 3,371.08 |
| STRUCTURAL STEEL | | | | \$ 50,650.78 | | | | | | | | | | | | |
| 870.8 | 051223400600 | | | Channel framing, structural steel, 8" and larger, field fabricated, incl cutting & welding | E3 | 500 | 0.048 | Lb. | \$ 0.80 | \$ 5.69 | \$ 0.34 | \$ 6.83 | \$ 696.64 | \$ 4,954.85 | \$ 296.07 | \$ 5,947.56 |
| 5422 | 051223400400 | | | Angle framing, structural steel, 4" and larger, field fabricated, incl cutting & welding | E3 | 440 | 0.055 | Lb. | \$ 0.77 | \$ 6.47 | \$ 0.38 | \$ 7.62 | \$ 4,174.94 | \$ 35,080.34 | \$ 2,060.36 | \$ 41,315.64 |
| 17.5 | 051223750300 | | | Structural steel member, 100-ton project, 1 to 2 story building, W8x10, A992 steel, shop fabricated, incl shop primer, bolted connections | E2 | 600 | 0.093 | L.F. | \$ 14.64 | \$ 10.15 | \$ 3.33 | \$ 28.12 | \$ 256.20 | \$ 177.63 | \$ 58.28 | \$ 492.10 |
| 63 | 051223750700 | | | Structural steel member, 100-ton project, 1 to 2 story building, W10x22, A992 steel, shop fabricated, incl shop primer, bolted connections | E2 | 600 | 0.093 | L.F. | \$ 32.48 | \$ 10.15 | \$ 3.33 | \$ 45.96 | \$ 2,046.24 | \$ 639.45 | \$ 209.79 | \$ 2,895.48 |
| COLUMNS | | | | \$ 309,425.00 | | | | | | | | | | | | |
| 158.5 | 033053400920 | | | Structural concrete, in place, column, square, avg reinforcing, 24" x 24", includes forms(4 uses), reinforcing steel, and finishing | C14A | 17.71 | 11.293 | C.Y. | \$ 486.45 | \$ 1,194.08 | \$ 54.57 | \$ 1,735.10 | \$ 77,102.33 | \$ 189,261.68 | \$ 8,649.35 | \$ 275,013.35 |
| 15 | 033053400820 | | | Structural concrete, in place, column, square, avg reinforcing, 16" x 16", includes forms(4 uses), reinforcing steel, and finishing | C14A | 12.57 | 15.911 | C.Y. | \$ 540.50 | \$ 1,676.98 | \$ 76.63 | \$ 2,294.11 | \$ 8,107.50 | \$ 25,154.70 | \$ 1,149.45 | \$ 34,411.65 |
| COLUMNS (For BUTRICES TO EXISTING MASONRY WALL) | | | | \$ 3,891.60 | | | | | | | | | | | | |
| 120 | 036305101530 | | | Chemical anchoring, for fastener 3/4" diam x 6" embedment, incl epoxy cartridge, excl layout, drilling & fastener | 2 Skwk | 72 | 0.222 | Ea. | \$ 7.20 | \$ 25.23 | \$ - | \$ 32.43 | \$ 864.00 | \$ 3,027.60 | \$ - | \$ 3,891.60 |
| ELEVATED SLABS | | | | \$ 1,445,630.97 | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | |
|----------------------------|--------------|--|--|--------|------|--------|--------|-------------|-------------|----------|-------------|---------------|---------------|-------------|---------------|
| 1420 | 033105350400 | | Structural concrete, ready mix, normal weight, 5000 psi, includes local aggregate, sand, portland cement and water, delivered, excludes all additives and treatments | | | | C.Y. | \$ 129.72 | \$ - | \$ - | \$ 129.72 | \$ 184,202.40 | \$ - | \$ - | \$ 184,202.40 |
| 1420 | 033105701500 | | Structural concrete, placing, elevated slab, pumped, 6" to 10" thick, includes vibrating, excludes material | C20 | 160 | 0.4 | C.Y. | \$ - | \$ 35.12 | \$ 6.21 | \$ 41.33 | \$ - | \$ 49,870.40 | \$ 8,818.20 | \$ 58,688.60 |
| 46004 | 031113351150 | | C.I.P. concrete forms, elevated slab, flat plate, plywood, to 15' high, 4 use, includes shoring, erecting, bracing, stripping and cleaning | C2 | 560 | 0.09 | S.F. | \$ 1.73 | \$ 9.52 | \$ - | \$ 11.25 | \$ 79,586.92 | \$ 437,958.08 | \$ - | \$ 517,545.00 |
| 2904 | 031113357080 | | C.I.P. concrete forms, elevated slab, edge forms, 7" to 12" high, 2 use, includes shoring, erecting, bracing, stripping and cleaning | C1 | 198 | 0.162 | SFCA | \$ 0.65 | \$ 17.51 | \$ - | \$ 18.16 | \$ 1,887.71 | \$ 50,851.96 | \$ - | \$ 52,739.67 |
| 3485 | 031113358000 | | C.I.P. concrete forms, elevated slab, perimeter deck and rail, straight, includes shoring, erecting, bracing, stripping and cleaning | C1 | 90 | 0.36 | L.F. | \$ 16.29 | \$ 38.48 | \$ - | \$ 54.77 | \$ 56,770.65 | \$ 134,102.80 | \$ - | \$ 190,873.45 |
| 46004 | 033529300350 | | Concrete finishing, floors, power screed, bull float, machine float & steel trowel (ride-on) | C10E | 4000 | 0.006 | S.F. | \$ - | \$ 0.54 | \$ 0.07 | \$ 0.61 | \$ - | \$ 24,842.16 | \$ 3,220.28 | \$ 28,062.44 |
| 134.538 | 032110600400 | | Reinforcing steel, in place, elevated slabs, #4 to #7, A615, grade 60, incl labor for accessories, excl material for accessories | 4 Rodm | 2.9 | 11.034 | Ton | \$ 1,249.60 | \$ 1,543.62 | \$ - | \$ 2,793.22 | \$ 168,118.93 | \$ 207,675.86 | \$ - | \$ 375,794.79 |
| 134.538 | 032110602200 | | Reinforcing steel, crane cost for handling, minimum, add | C5 | 135 | 0.415 | Ton | \$ - | \$ 55.41 | \$ 7.43 | \$ 62.84 | \$ - | \$ 7,454.76 | \$ 999.62 | \$ 8,454.38 |
| 134.538 | 032110602000 | | Reinforcing steel, unload and sort, add to base | C5 | 100 | 0.56 | Ton | \$ - | \$ 74.21 | \$ 10.04 | \$ 84.25 | \$ - | \$ 9,984.08 | \$ 1,350.76 | \$ 11,334.84 |
| 460 | 033923230200 | | Curing, burlap/poly blanket, 2 ply | 2 Clab | 70 | 0.229 | C.S.F. | \$ 20.11 | \$ 18.88 | \$ - | \$ 38.99 | \$ 9,250.60 | \$ 8,684.80 | \$ - | \$ 17,935.40 |
| SLAB ON GRADE | | | \$ 10,596.01 | | | | | | | | | | | | |
| 32 | 033105350400 | | Structural concrete, ready mix, normal weight, 5000 psi, includes local aggregate, sand, portland cement and water, delivered, excludes all additives and treatments | | | | C.Y. | \$ 129.72 | \$ - | \$ - | \$ 129.72 | \$ 4,151.04 | \$ - | \$ - | \$ 4,151.04 |
| 32 | 033105701500 | | Structural concrete, placing, elevated slab, pumped, 6" to 10" thick, includes vibrating, excludes material | C20 | 160 | 0.4 | C.Y. | \$ - | \$ 35.12 | \$ 6.21 | \$ 41.33 | \$ - | \$ 1,123.84 | \$ 198.72 | \$ 1,322.56 |
| 109.2 | 031113653060 | | C.I.P. concrete forms, slab on grade, edge, wood, over 12", 4 use, includes erecting, bracing, stripping and cleaning | C1 | 350 | 0.09 | SFCA | \$ 0.88 | \$ 9.91 | \$ - | \$ 10.79 | \$ 96.07 | \$ 1,081.84 | \$ - | \$ 1,177.91 |
| 20.57 | 032205500200 | | Welded wire fabric, sheets, 6 x 6 - W2.1 x W2.1 (8 x 8) 30 lb. per C.S.F., A185 | 2 Rodm | 31 | 0.516 | C.S.F. | \$ 19.54 | \$ 72.23 | \$ - | \$ 91.77 | \$ 401.94 | \$ 1,485.77 | \$ - | \$ 1,887.71 |
| 2057 | 033529300350 | | Concrete finishing, floors, power screed, bull float, machine float & steel trowel (ride-on) | C10E | 4000 | 0.006 | S.F. | \$ - | \$ 0.54 | \$ 0.07 | \$ 0.61 | \$ - | \$ 1,110.78 | \$ 143.99 | \$ 1,254.77 |
| 20.57 | 033923230200 | | Curing, burlap/poly blanket, 2 ply | 2 Clab | 70 | 0.229 | C.S.F. | \$ 20.11 | \$ 18.88 | \$ - | \$ 38.99 | \$ 413.66 | \$ 388.36 | \$ - | \$ 802.02 |
| FOUNDATION MAT SLAB | | | \$ 474,486.75 | | | | | | | | | | | | |
| 1172.5 | 031113550050 | | C.I.P. concrete forms, mat foundation, plywood, 2 use, includes erecting, bracing, stripping and cleaning | C2 | 310 | 0.15 | SFCA | \$ 1.31 | \$ 17.22 | \$ - | \$ 18.53 | \$ 1,535.98 | \$ 20,190.45 | \$ - | \$ 21,726.43 |
| 581 | 033105702950 | | Structural concrete, placing, foundation mat, pumped, over 20 C.Y., includes vibrating, excludes material | C20 | 400 | 0.16 | C.Y. | \$ - | \$ 14.05 | \$ 2.48 | \$ 16.53 | \$ - | \$ 8,163.05 | \$ 1,440.88 | \$ 9,603.93 |

| | | | | | | | | | | | | | | | |
|----------------------------|--------------|--|---|--------|------|--------|--------|---------------|-------------|---------|-------------|--------------|---------------|-------------|---------------|
| 581 | 033105350400 | | Structural concrete, ready mix, normal weight, 5000 psi, includes local aggregate, sand, portland cement and water, delivered, excludes all additives and treatments | | | | C.Y. | \$ 129.72 | \$ - | \$ - | \$ 129.72 | \$ 75,367.32 | \$ - | \$ - | \$ 75,367.32 |
| 63.08 | 033923230200 | | Curing, burlap/poly blanket, 2 ply | 2 Clab | 70 | 0.229 | C.S.F. | \$ 20.11 | \$ 18.88 | \$ - | \$ 38.99 | \$ 1,268.54 | \$ 1,190.95 | \$ - | \$ 2,459.49 |
| 62 | 032110601100 | | Reinforcing steel, in place, typical, average, 50 to 100 ton job, #3 to #7, A615, grade 60, incl labor for accessories, excl material for accessories | 4 Rodm | 2.2 | 14.545 | Ton | \$ 1,164.40 | \$ 2,028.48 | \$ - | \$ 3,192.88 | \$ 72,192.80 | \$ 125,765.76 | \$ - | \$ 197,958.56 |
| 62 | 032110601110 | | Reinforcing steel, in place, typical, average, 50 to 100 ton job, #8 to #18, A615, grade 60, incl labor for accessories, excl material for accessories | 4 Rodm | 3.1 | 10.323 | Ton | \$ 1,192.80 | \$ 1,444.67 | \$ - | \$ 2,637.47 | \$ 73,953.60 | \$ 89,569.54 | \$ - | \$ 163,523.14 |
| 6308 | 033529300350 | | Concrete finishing, floors, power screed, bull float, machine float & steel trowel (ride-on) | C10E | 4000 | 0.006 | S.F. | \$ - | \$ 0.54 | \$ 0.07 | \$ 0.61 | \$ - | \$ 3,406.32 | \$ 441.56 | \$ 3,847.88 |
| FOUNDATION WALLS | | | | | | | | \$ 205,286.79 | | | | | | | |
| 100 | 031505953050 | | Form oil, coverage varies greatly, maximum, includes material only | | | | Gal. | \$ 12.30 | \$ - | \$ - | \$ 12.30 | \$ 1,230.00 | \$ - | \$ - | \$ 1,230.00 |
| 3.134 | 033105704950 | | Structural concrete, placing, walls, pumped, 8" thick, includes vibrating, excludes material | C20 | 100 | 0.64 | C.Y. | \$ - | \$ 56.19 | \$ 9.93 | \$ 66.12 | \$ - | \$ 176.10 | \$ 31.12 | \$ 207.22 |
| 11.4 | 033105705100 | | Structural concrete, placing, walls, pumped, 12" thick, includes vibrating, excludes material | C20 | 110 | 0.582 | C.Y. | \$ - | \$ 50.92 | \$ 9.06 | \$ 59.98 | \$ - | \$ 580.49 | \$ 103.28 | \$ 683.77 |
| 171 | 033105705350 | | Structural concrete, placing, walls, pumped, 15" thick, includes vibrating, excludes material | C20 | 120 | 0.533 | C.Y. | \$ - | \$ 46.53 | \$ 8.30 | \$ 54.83 | \$ - | \$ 7,956.63 | \$ 1,419.30 | \$ 9,375.93 |
| 8396 | 031113859260 | | C.I.P. concrete forms, walls, steel framed plywood, over 8' to 16' high, based on 100 uses of purchased forms, 4 uses of bracing lumber, includes erecting, bracing, stripping and cleaning | C2 | 450 | 0.107 | SFCA | \$ 0.44 | \$ 11.83 | \$ - | \$ 12.27 | \$ 3,694.24 | \$ 99,324.68 | \$ - | \$ 103,018.92 |
| 186 | 033105350400 | | Structural concrete, ready mix, normal weight, 5000 psi, includes local aggregate, sand, portland cement and water, delivered, excludes all additives and treatments | | | | C.Y. | \$ 129.72 | \$ - | \$ - | \$ 129.72 | \$ 24,127.92 | \$ - | \$ - | \$ 24,127.92 |
| 8396 | 033529600020 | | Concrete finishing, walls, includes breaking ties and patching voids | 1 Cefi | 540 | 0.015 | S.F. | \$ 0.03 | \$ 1.40 | \$ - | \$ 1.43 | \$ 251.88 | \$ 11,754.40 | \$ - | \$ 12,006.28 |
| 21 | 032110600700 | | Reinforcing steel, in place, walls, #3 to #7, A615, grade 60, incl labor for accessories, excl material for accessories | 4 Rodm | 3 | 10.667 | Ton | \$ 1,107.60 | \$ 1,494.15 | \$ - | \$ 2,601.75 | \$ 23,259.60 | \$ 31,377.15 | \$ - | \$ 54,636.75 |
| FOUNDATION FOOTINGS | | | | | | | | \$ 30,129.12 | | | | | | | |
| 1130 | 031113450050 | | C.I.P. concrete forms, footing, continuous wall, plywood, 2 use, includes erecting, bracing, stripping and cleaning | C1 | 440 | 0.07 | SFCA | \$ 3.52 | \$ 7.87 | \$ - | \$ 11.39 | \$ 3,977.60 | \$ 8,893.10 | \$ - | \$ 12,870.70 |
| 69 | 031113451500 | | C.I.P. concrete forms, footing, keyway, tapered wood, 2" x 4", 4 use, includes erecting, bracing, stripping and cleaning | CARP | 530 | 0.02 | L.F. | \$ 0.23 | \$ 1.71 | \$ - | \$ 1.94 | \$ 15.87 | \$ 117.99 | \$ - | \$ 133.86 |
| 71 | 033105350400 | | Structural concrete, ready mix, normal weight, 5000 psi, includes local aggregate, sand, portland cement and water, delivered, excludes all additives and treatments | | | | C.Y. | \$ 129.72 | \$ - | \$ - | \$ 129.72 | \$ 9,210.12 | \$ - | \$ - | \$ 9,210.12 |

| | | | | | | | | | | | | | | | |
|--------------------------------|--------------|--|--|--------|-----|--------|------|-------------|-------------|---------|-------------|-------------|-------------|-----------|-------------|
| 0.479 | 032110600500 | | Reinforcing steel, in place, footings, #4 to #7, A615, grade 60, incl labor for accessories, excl material for accessories | 4 Rodm | 2.1 | 15.238 | Ton | \$ 1,107.60 | \$ 2,127.43 | \$ - | \$ 3,235.03 | \$ 530.61 | \$ 1,019.17 | \$ - | \$ 1,549.77 |
| 2.782 | 032110600550 | | Reinforcing steel, in place, footings, #8 to #18, A615, grade 60, incl labor for accessories, excl material for accessories | 4 Rodm | 3.6 | 8.889 | Ton | \$ 1,050.80 | \$ 1,236.88 | \$ - | \$ 2,287.68 | \$ 2,923.48 | \$ 3,441.19 | \$ - | \$ 6,364.67 |
| FOUNDATIONS GRADE BEAMS | | | \$ 19,414.15 | | | | | | | | | | | | |
| 504 | 031113500050 | | C.I.P. concrete forms, grade beam, plywood, 2 use, includes erecting, bracing, stripping and cleaning | C2 | 580 | 0.08 | SFCA | \$ 1.70 | \$ 9.20 | \$ - | \$ 10.90 | \$ 856.80 | \$ 4,636.80 | \$ - | \$ 5,493.60 |
| 36.5 | 033105703250 | | Structural concrete, placing, grade beam, pumped, includes vibrating, excludes material | C20 | 180 | 0.356 | C.Y. | \$ - | \$ 31.17 | \$ 5.51 | \$ 36.68 | \$ - | \$ 1,137.71 | \$ 201.12 | \$ 1,338.82 |
| 36.5 | 033105350400 | | Structural concrete, ready mix, normal weight, 5000 psi, includes local aggregate, sand, portland cement and water, delivered, excludes all additives and treatments | | | | C.Y. | \$ 129.72 | \$ - | \$ - | \$ 129.72 | \$ 4,734.78 | \$ - | \$ - | \$ 4,734.78 |
| 2.7857 | 032110600150 | | Reinforcing steel, in place, beams and girders, #8 to # 18, A615, grade 60, incl labor for accessories, excl material for accessories | 4 Rodm | 2.7 | 11.852 | Ton | \$ 1,164.40 | \$ 1,652.47 | \$ - | \$ 2,816.87 | \$ 3,243.67 | \$ 4,603.29 | \$ - | \$ 7,846.95 |

Total \$ 911,783.44 \$ 1,652,245.13 \$ 31,237.42 \$ 2,595,265.94




Figure 6: Illustrates the Column Schedule

| Building Skanska Job No. Construction Cleaning | | | | | |
|--|----------|----------|------------|-------------|--------------|
| All NJ local 593 | Manhours | # Months | Total Hrs. | Rates | Cost |
| Labor foreman cost | 160 | 8 | 1280 | \$87.00 | \$111,360.00 |
| Labor Shop steward cost | 160 | 8 | 1280 | \$85.00 | \$108,800.00 |
| Laborer (3 men) | 320 | 8 | 2260 | \$78.00 | \$176,280.00 |
| | | | | | |
| | | | | 10% mark up | \$40,000.00 |
| | | | | | |
| | | | | Total: | \$436,440.00 |

General Conditions

| Item | Unit Cost | Units month | Quantity | Units | Total | Total cost per mo. | Comments |
|-------------------------|-------------|-------------|----------|------------------------|------------------|--------------------|--|
| Trailer Cost | \$0 | lump sum | | 1 # months | \$0 | \$0 | Used Owner Facility adjacent Building |
| Trailer Infrastructure | \$0 | lump sum | | 1 # months | \$0 | \$0 | Used Owner Facility adjacent Building |
| Temporary Power | \$1,657 | lump sum | | 1 # months | \$1,657 | \$75 | 200 Amp Underground feed |
| Computer Hardware | \$35,000 | lump sum | | 1 # months | \$35,000 | \$1,591 | Server/Computers/Printer/Scanner |
| Temporary Heat | \$408,800 | allow | | 0 # months | \$0 | \$0 | In Trades Budget for Masonry |
| Temporary Heat | \$98,500 | allow | | 0 # months | \$0 | \$0 | In Trades Budget for Building Finishes |
| Temporary toilets | \$0 | | | 22 # months | \$0 | \$0 | In Trades Budget |
| Temporary Fence | \$33.49 | lf | | 100 lf | \$3,349 | \$152 | Plywood, painted 4"x4" frame, 8' high |
| Temporary Fence | \$5.30 | lf | | 120 lf | \$636 | \$29 | Rented Chain Link, 6ft high |
| Sidewalk bridge | \$201.02 | lf | | 100 lf | \$20,102 | \$914 | Heavy duty steel posts & beams, including parapet protection & waterproofing |
| Small tools | \$125 | month | | 22 | \$2,750 | \$125 | |
| Telephone Services | \$245 | month | | 22 # months | \$5,397 | \$245 | Telephone Bill; avg.bill/month incl. longdist. |
| Telephone Equipment | \$0 | month | | 22 # months | \$0 | \$0 | By Owner |
| Field Office Furniture | \$650 | month | | 22 # months | \$14,300 | \$650 | Furniture for 6 people |
| Computer Software | \$750 | month | | 22 # months | \$16,500 | \$750 | Software(P3, Prolog, Suretrack) |
| T1 Conductivity | \$1,000 | month | | 22 # months | \$22,000 | \$1,000 | Internet capability |
| Copy/Fax Machine | \$555 | month | | 22 # months | \$12,210 | \$555 | Rental |
| Business Expense | \$125 | month | | 22 # months | \$2,750 | \$125 | Misc. Business expense |
| Field Office Misc. | \$150 | month | | 22 # months | \$3,300 | \$150 | |
| Clerical Supplies | \$470 | month | | 22 # months | \$10,340 | \$470 | |
| Printing/Drawings Repro | \$800 | month | | 22 # months | \$17,600 | \$800 | |
| Mail and Fedex | \$1,000 | month | | 22 # months | \$22,000 | \$1,000 | |
| OSHA prot. Supplies | \$175 | month | | 22 # months | \$3,850 | \$175 | |
| Dumpsters(field office) | \$0 | month | | 22 # months | \$0 | \$0 | In Trades Budget |
| Progress Photos | \$0 | month | | 22 # months | \$0 | \$0 | By Owner |
| Project Signs | \$250 | month | | 22 # months | \$5,500 | \$250 | |
| EDP | \$650 | month | | 22 # months | \$14,300 | \$650 | |
| Trade labor | \$0 | month | | 22 # months | \$0 | \$0 | In Trades Budget |
| Teamster | \$0 | month | | 22 # months | \$0 | \$0 | In Trades Budget |
| Operating Engineer | \$0 | month | | 10 # months | \$0 | \$0 | In Trades Budget |
| Traffic Control | \$0 | month | | 16 # months | \$0 | \$0 | In Trades Budget |
| Dumpsters | \$4,000 | month | | 0 # months | \$0 | \$0 | In Trades Budget |
| Construction Cleaning | \$13,638.75 | month | | 32 # months | \$436,440.00 | \$13,638.75 | Includes Foreman and 3 Labors |
| | | | | | | | |
| | | | | Total: | \$649,981 | | |
| | | | | Cost per month: | \$21,679 | | |

E. Critical Industry Issues

The 19th annual PACE conference began with the Architectural Engineer Department discussing the research topics of the 2010 and 2011 year. The first topic talk about was The BIM Project Execution Plan, which was developed to provide a practical manual that can be used by the project teams for designing their BIM strategy and developing a BIM Project Plan. The BIM usages were introduced briefly including: building maintenance scheduling, building system analysis, asset management, space management and tracking, disaster planning, record modeling, site utilization planning, construction system design, digital fabrication, 3D control and planning, 3D coordination, field / materials tracking, design authoring, engineering analysis (structural, lighting, energy, mechanical), sustainability (LEED) evaluation, code validation, design reviews, programming, site analysis, phase planning, cost estimation, existing conditions modeling. Dr. Leicht discussed the issues that arise during the BIM implementation of the project. Dr. Leicht highlighted the fact that while utilizing BIM on the project. Surprisingly, 50 percent of the teams' time is spent on developing the process and 50% of the time implementing the BIM technology. This is a significant amount of time spent. To minimize this time the BIM Execution Plan provides the project team with a guide that has potential to efficiently implement building information modeling in construction. The following topics were discussed by Dr. Messner and Dr Riley: AHQ information flow for patient care to hospital facilities, virtual construction simulation, GPIC-Greater Philadelphia Innovation Cluster for energy efficient building, and BIM standards. Following the kick-off meeting the attendees went to break- out sessions I and II.

| A. Sustainability / Green Building | B. Technology Applications | C. Process Innovation |
|---|--|--|
| Session 1A: Educating a future workforce for delivering high performance buildings | Session 1B: Transformation: What are the innovations that will transform our industry | Session 1C: IPD: Exploring the drivers behind highly integrated delivery of projects |
| Session 2A: The Smart Grid: Energy impacts in the building industry | Session 2B: Carrying BIM to the field – new responsibilities, roles, & competencies | Session 2C: Operations & Maintenance process integration in new and retrofit projects |

Table 2|Shows the Main Discussion Topics, identified by the PACE Advisory Board


At the PACE Roundtable break-out session I attended the “Transformation” topic break out session. The question proposed at the discussion was: **What are the innovations that will transform our industry?** During the break out session many topics were discussed including: robots used in the field for layout, prefabrication of precast and MEP systems, prefabrication of patient restrooms, development of BIM model for maintenance department to organize data, commissioning models for project closeout, educating the owner with Revit models, Latista

management for RFI's, developing models to meet the client's needs, developing a data base of case studies that could be used by the industry, interaction of users with model other than designers, meeting the client's needs by virtual simulation of the process, rapid prototype, utilizing BIM for estimates, and ship building prefab concept.


The first subject of interest from the PACE roundtable event was the paperless jobsite. Jim Salvino from Clark Construction Group initiated this topic. Clark is currently using the Vela system for their projects. Vela Field management suite is a web-based platform for all Vela Systems field and management users. Contractors, trades, owners, architects, and engineers access all documents, field activities and reports in one easy-to-use website. Jobsites going paperless through the use of tablet pc. Construction companies can save hundreds of dollars from not reprinting drawings. In addition, the companies will save the trouble of having to track the current working set of drawings through the use of a central online storage site that contains the current drawings. Clark Construction is currently working on testing a large screen monitor that can be used on by the subcontractors attached to their job box. Data can be exchange among contractors, engineers and fabricators through the use of BIM. Subcontractors and Construction Manger Estimators' can use the BIM model for quantity takeoffs. For instance, Skanska used the BIM from Thorton Tomasetti for the New Meadowlands Stadium steel estimate in East Ruthorford, NJ. This approach was very beneficial for the company due to the fact that they were able to accelerate the schedule by four months.

The second relevant topics regarding my senior project is the development of the BIM model for the owner's maintenance department to organize data. Thus far there is not a Building Management System that is integrated into the BIM. To integrate these two into one system would require collaboration between programmers, construction professionals, and owners to develop a prototype for this software. A key factor in order to accomplish this is to identify the projects goals. Mr. John Bechtel from Office of the Physical Plant could potential provide assistance in compiling a list of project goals. Penn State has a history of leadership in commissioning and continuous commissioning. The Pennsylvania State University has updated their buildings into AutoCad and they are considering updating the plans into BIM form. Penn State, like many other owners, is inquiring uses for the BIM model after construction. Currently, Penn State is implementing BIM Execution Plan and requiring subcontractors and vendors to utilize BIM technologies for new construction buildings. In addition, Chris Magent of Alexander Building Construction uses the BIM Execution Plan for their BIM projects.


Break-out session II 's topic was "Carrying BIM to the field – new responsibilities, roles, & competencies". This session addressed the following: rework cost savings, portable targets for using laser scanning, total stations for project controls and layout, document management collaborative systems, and photogrammetry. The third topic of interest to me was field verification of the three-dimensional model. Three-dimensional coordination is very helpful in preventing clashes in the field. However field verification is not as easy. Yet, there is not an easy way of generating documents for the subcontractors and construction managers for installation and field verification. There must be an easier way than manually dimensioning the plan drawings and elevations. This was the main obstacle in implementing the BIM technology for the BIM coordinator and field superintendents from Skanska that worked on the New Meadowlands Stadium in East Rutherford, NJ. Adapting an interface that could potentially dimension and produce field drawings for the project team would be a valuable tool.




█ Actual Work
 █ Critical Remaining Work
 ▶ Summary
█ Remaining Work
 ◆ Milestone



█ Actual Work
 █ Critical Remaining Work
 ▶ Summary
█ Remaining Work
 ◆ Milestone



█ Actual Work
 █ Critical Remaining Work
 █ Remaining Work
 ▶ Summary
 ◆ Milestone



█ Actual Work
 █ Critical Remaining Work
 Summary
 ◆ Milestone
 ◆ Milestone

Appendix II: Detailed Structural Systems Estimate

| Depth (in) | Type | Level | Matt Slab, SOG, Elevated Floor Material Takeoff | | | | Reinforcing | ton/cy | |
|-----------------------------|----------|------------------------|---|---------|--------------|--------------|-------------------------------------|--------|----------------|
| | | | Perimeter ft | Area sf | Volume cy | Volume cy | | ton/cy | ton |
| 5 | SOG | CELLAR FLOOR | 42.60 | 65 | 27.28 | 1.01 | 6x6-W2.0xW2.0W.W.F. | N/A | N/A |
| 30 | Mat Slab | CELLAR FLOOR | 63.82 | 225 | 562.11 | 20.82 | #9 @ 8" Each Way (Top & Bottom) | 0.107 | 2.222 |
| 30 | Mat Slab | CELLAR FLOOR | 376.25 | 6033 | 15082.25 | 558.60 | #9 @ 8" Each Way (Top & Bottom) | 0.107 | 59.631 |
| 8 | Mat Slab | THEATER BASEMENT FLOOR | 28.38 | 50.00 | 33.33 | 1.23 | #5 @12" (Top & Bottom) | 0.109 | 0.134 |
| 5 | Elevated | THEATER BASEMENT FLOOR | 218.83 | 1992 | 830.08 | 30.74 | 6x6-W2.0xW2.0W.W.F. | 0.095 | 0.117 |
| 10 | Elevated | BASEMENT FLOOR | 391.59 | 5629 | 4691.20 | 173.75 | #6 @ 12" OC Each Way (Top & Bottom) | N/A | N/A |
| 10 | Elevated | ENTRY @ 135 MACDOUGAL | 49.67 | 153 | 127.90 | 4.74 | #6 @ 12" OC Each Way (Top & Bottom) | 0.095 | 0.449 |
| 10 | Elevated | ENTRY @ 135 MACDOUGAL | 112.48 | 765 | 637.71 | 23.62 | #6 @ 12" OC Each Way (Top & Bottom) | 0.095 | 2.238 |
| 10 | Elevated | FIRST FLOOR | 374.98 | 5198 | 4331.75 | 160.44 | #6 @ 12" OC Each Way (Top & Bottom) | 0.095 | 15.201 |
| 10 | Elevated | SECOND FLOOR | 496.61 | 7481 | 6234.58 | 230.91 | #6 @ 12" OC Each Way (Top & Bottom) | 0.095 | 21.879 |
| 10 | Elevated | THIRD FLOOR | 399.95 | 5617 | 4680.85 | 173.36 | #6 @ 12" OC Each Way (Top & Bottom) | 0.095 | 16.426 |
| 10 | Elevated | FOURTH FLOOR | 399.95 | 5617 | 4680.85 | 173.36 | #6 @ 12" OC Each Way (Top & Bottom) | 0.095 | 16.426 |
| 10 | Elevated | FIFTH FLOOR | 399.95 | 5617 | 4680.85 | 173.36 | #6 @ 12" OC Each Way (Top & Bottom) | 0.095 | 16.426 |
| 10 | Elevated | SIXTH FLOOR | 399.95 | 5617 | 4680.85 | 173.36 | #6 @ 12" OC Each Way (Top & Bottom) | 0.095 | 16.426 |
| 10 | Elevated | TO ROOF STRUCTURE | 365.04 | 3818 | 3181.54 | 117.83 | #6 @ 12" OC Each Way (Top & Bottom) | 0.095 | 11.165 |
| 10 | Elevated | TO BULK HEAD | 94.5 | 492 | 409.99 | 15.18 | #6 @ 12" OC Each Way (Top & Bottom) | 0.095 | 1.439 |
| TOTAL SLAB CONCRETE: | | | | | 54369 | 54873 | 2032 | | 180.180 |

Table 2: Shows the Mat Slab, Slab on Grade, and Elevated Floor Material Takeoff

| Concrete Structural Framing Schedule | | | | | | |
|--------------------------------------|---------|-----------|------------------|-----------|--------------|--|
| Type | Size | Length ft | Volume cf | Volume cy | Forming sfca | |
| Concrete-Rectangular Beam | 10 x 10 | 16.32 | 11.34 | 0.42 | 40.80 | |
| Concrete-Rectangular Beam | 10 x 10 | 16.32 | 11.34 | 0.42 | 40.80 | |
| Concrete-Rectangular Beam | 10 x 10 | 16.32 | 11.34 | 0.42 | 40.80 | |
| Concrete-Rectangular Beam | 10 x 10 | 16.32 | 11.34 | 0.42 | 40.80 | |
| Concrete-Rectangular Beam | 10 x 10 | 16.51 | 11.47 | 0.42 | 41.28 | |
| Concrete-Rectangular Beam | 10 x 10 | 16.51 | 11.47 | 0.42 | 41.28 | |
| Concrete-Rectangular Beam | 10 x 10 | 16.55 | 11.50 | 0.43 | 41.38 | |
| Concrete-Rectangular Beam | 10 x 10 | 16.55 | 11.50 | 0.43 | 41.38 | |
| Concrete-Rectangular Beam | 10 x 10 | 16.55 | 11.50 | 0.43 | 41.38 | |
| Concrete-Rectangular Beam | 10 x 10 | 16.55 | 11.50 | 0.43 | 41.38 | |
| Concrete-Rectangular Beam | 10 x 10 | 17.29 | 11.49 | 0.43 | 43.23 | |
| Concrete-Rectangular Beam | 10 x 10 | 17.29 | 11.49 | 0.43 | 43.23 | |
| Concrete-Rectangular Beam | 10 x 10 | 17.38 | 12.07 | 0.45 | 43.45 | |
| Concrete-Rectangular Beam | 10 x 10 | 17.38 | 12.07 | 0.45 | 43.45 | |
| Concrete-Rectangular Beam | 10 x 10 | 17.41 | 12.09 | 0.45 | 43.53 | |
| Concrete-Rectangular Beam | 12 x 16 | 15.82 | 21.09 | 0.78 | 58.01 | |
| Concrete-Rectangular Beam | 12 x 16 | 15.82 | 21.09 | 0.78 | 58.01 | |
| Concrete-Rectangular Beam | 12 x 16 | 15.82 | 21.09 | 0.78 | 58.01 | |
| Concrete-Rectangular Beam | 12 x 16 | 15.82 | 21.09 | 0.78 | 58.01 | |
| Concrete-Rectangular Beam | 12 x 18 | 16.29 | 24.44 | 0.91 | 65.16 | |
| Concrete-Rectangular Beam | 12 x 18 | 16.29 | 24.44 | 0.91 | 65.16 | |
| Concrete-Rectangular Beam | 12 x 18 | 16.42 | 24.45 | 0.91 | 65.68 | |
| Concrete-Rectangular Beam | 12 x 18 | 17.46 | 26.19 | 0.97 | 69.84 | |
| Concrete-Rectangular Beam | 36 x 32 | 21.22 | 169.76 | 6.29 | 176.83 | |
| Concrete-Rectangular Beam | 42 x 32 | 21.4 | 199.7333 | 7.40 | 178.33 | |
| Concrete Framing Member: | | | 26.922 cy | | | |

Table 3: Shows the Concrete Beam Schedule

| CONCRETE FRAMING BEAM REINFORCING | | | | | | | | | | | |
|---|------------|-------------|-------------------|----------------|---------------|-----------------|----------------|---------------|-------------------|----------|--|
| Type Footing | Type Rein. | Length (ft) | Quantity Bar/beam | Quantity Beams | Wt./lf lbs/ft | Wt. lbs. | Wt. Ton | Total wt. Ton | Volume Concr.(cy) | ton/cy | |
| BM-1 (10"x10") | #5 | 17 | 3 | 6 | 1.043 | 319.158 | 0.159579 | | | | |
| BM-1 (10"x10") | #5 | 17 | 3 | 6 | 1.043 | 319.158 | 0.159579 | | | | |
| BM-1 (10"x10") | #4 | 2 | 17 | 6 | 0.668 | 136.272 | 0.068136 | 0.387294 | 2.623457 | 0.147627 | |
| BM-1 (10"x10") | #5 | 16 | 3 | 13 | 1.043 | 650.832 | 0.325416 | | | | |
| BM-1 (10"x10") | #5 | 16 | 3 | 13 | 1.043 | 650.832 | 0.325416 | | | | |
| BM-1 (10"x10") | #4 | 2 | 16 | 13 | 0.668 | 277.888 | 0.138944 | 0.789776 | 5.349794 | 0.147627 | |
| BM-1 (10"x10") | #5 | 15 | 3 | 4 | 1.043 | 187.74 | 0.09387 | | | | |
| BM-1 (10"x10") | #5 | 15 | 3 | 4 | 1.043 | 187.74 | 0.09387 | | | | |
| BM-1 (10"x10") | #4 | 2 | 15 | 4 | 0.668 | 80.16 | 0.04008 | 0.22782 | 1.54321 | 0.147627 | |
| BM-1 (10"x10") | #5 | 21 | 3 | 2 | 1.043 | 131.418 | 0.065709 | | | | |
| BM-1 (10"x10") | #5 | 21 | 3 | 2 | 1.043 | 131.418 | 0.065709 | | | | |
| BM-1 (10"x10") | #4 | 2 | 21 | 2 | 0.668 | 56.112 | 0.028056 | 0.159474 | 1.080247 | 0.147627 | |
| BM-2 (12"x16") | #7 | 15 | 3 | 4 | 2.044 | 367.92 | 0.18396 | | | | |
| BM-2 (12"x16") | #7 | 15 | 3 | 4 | 2.044 | 367.92 | 0.18396 | | | | |
| BM-2 (12"x16") | #4 | 4 | 15 | 4 | 0.688 | 165.12 | 0.08256 | 0.45048 | 3.124889 | 0.144159 | |
| BM-3 (12"x18") | #7 | 16 | 3 | 3 | 2.044 | 294.336 | 0.147168 | | | | |
| BM-3 (12"x18") | #7 | 16 | 3 | 3 | 2.044 | 294.336 | 0.147168 | | | | |
| BM-3 (12"x18") | #4 | 4.5 | 16 | 3 | 0.688 | 148.608 | 0.074304 | 0.36864 | 2.715556 | 0.135751 | |
| BM-3 (12"x18") | #7 | 17 | 3 | 1 | 2.044 | 104.244 | 0.052122 | | | | |
| BM-3 (12"x18") | #7 | 17 | 3 | 1 | 2.044 | 104.244 | 0.052122 | | | | |
| BM-3 (12"x18") | #4 | 4.5 | 17.00 | 1 | 0.688 | 52.632 | 0.026316 | 0.13056 | 0.97 | 0.134598 | |
| BM-4(36"x32") | #8 | 21 | 10 | 1 | 2.044 | 429.24 | 0.21462 | | | | |
| BM-4(36"x32") | #6 | 21 | 8 | 1 | 2.044 | 343.392 | 0.171696 | | | | |
| BM-4(36"x32") | #4 | 11 | 42 | 1 | 0.688 | 317.856 | 0.158928 | 0.545244 | 6.287407 | 0.08672 | |
| BM-5(42"x32") | #9 | 21 | 10 | 1 | 3.4 | 714 | 0.357 | | | | |
| BM-5(42"x32") | #6 | 21 | 8 | 1 | 1.502 | 252.336 | 0.126168 | | | | |
| BM-5(42"x32") | #4 | 12 | 42 | 1 | 0.668 | 336.672 | 0.168336 | 0.651504 | 7.407407 | 0.087953 | |
| TOTAL CONCRETE FRAME BEAM REINFORCING: | | | | | | 7421.584 | 3.71079 | | | | |

Table 4: Shows the Concrete Beam Reinforcement

| Steel Structural Framing Schedule | | | | | |
|-----------------------------------|-----------|--------------|---------------------|----------------|---------------|
| Type | Size | Length ft | Weight lbs./lf | Weight lbs. | Weight ton |
| C-Channel | C10X20 | 21.77 | 20.00 | 435.40 | 0.2177 |
| C-Channel | C10X20 | 21.77 | 20.00 | 435.40 | 0.2177 |
| L-Angle | L6X4X5/16 | 21.77 | 10.30 | 224.23 | 0.11 |
| L-Angle | L6X4X5/16 | 21.77 | 10.30 | 224.23 | 0.11 |
| L-Angle | L6X6X5/16 | 24.79 | 12.50 | 309.88 | 0.15 |
| L-Angle | L6X6X5/16 | 7.07 | 12.50 | 88.38 | 0.04 |
| L-Angle | L6X6X5/16 | 15.08 | 12.50 | 188.50 | 0.09 |
| L-Angle | L6X6X5/16 | 16.67 | 12.50 | 208.38 | 0.10 |
| L-Angle | L6X6X5/16 | 11.99 | 12.50 | 149.88 | 0.07 |
| LL-Double Angle | 2L6X6X5/8 | 9.21 | 48.60 | 447.61 | 0.22 |
| LL-Double Angle | 2L6X6X5/8 | 9.21 | 48.60 | 447.61 | 0.22 |
| LL-Double Angle | 2L6X6X5/8 | 9.21 | 48.60 | 447.61 | 0.22 |
| LL-Double Angle | 2L6X6X5/8 | 9.21 | 48.60 | 447.61 | 0.22 |
| LL-Double Angle | 2L6X6X5/8 | 9.21 | 48.60 | 447.61 | 0.22 |
| LL-Double Angle | 2L6X6X5/8 | 9.21 | 48.60 | 447.61 | 0.22 |
| LL-Double Angle | 2L6X6X5/8 | 9.21 | 48.60 | 447.61 | 0.22 |
| LL-Double Angle | 2L6X6X5/8 | 9.21 | 48.60 | 447.61 | 0.22 |
| LL-Double Angle | 2L6X6X5/8 | 9.21 | 48.60 | 447.61 | 0.22 |
| W-Wide Flange | W8X10 | 17.41 | 10.00 | 174.10 | 0.09 |
| W-Wide Flange | W10X19 | 6.72 | 19.00 | 127.68 | 0.06 |
| W-Wide Flange | W10X19 | 6.6 | 19.00 | 125.40 | 0.06 |
| W-Wide Flange | W10X19 | 7.07 | 19.00 | 134.33 | 0.07 |
| W-Wide Flange | W10X19 | 7.05 | 19.00 | 133.95 | 0.07 |
| W-Wide Flange | W10X19 | 7.14 | 19.00 | 135.66 | 0.07 |
| W-Wide Flange | W10X19 | 7.14 | 19.00 | 135.66 | 0.07 |
| W-Wide Flange | W10X19 | 7.14 | 19.00 | 135.66 | 0.07 |
| W-Wide Flange | W10X19 | 7.14 | 19.00 | 135.66 | 0.07 |
| W-Wide Flange | W10X19 | 6.97 | 19.00 | 132.43 | 0.07 |
| Steel Framing Members: | | | 3.831623 ton | | |

Table 5: Shows the Concrete Structural Framing Schedule

| CONCRETE COLUMNS | | | | | | |
|-----------------------------|------------|--------------|--------------------|------------------------|--------------|--|
| Type | Size in | Length ft | Surface Area sf | Material: Volume cf | Volume cy | |
| Concrete-Rectangular-Column | 12" x 12" | 21.75 | 72 | 16.92 | 0.63 | |
| Concrete-Rectangular-Column | 12" x 24" | 21.75 | 112.00 | 26.50 | 0.98 | |
| Concrete-Rectangular-Column | 12" x 24" | 32.42 | 154.00 | 35.38 | 1.31 | |
| Concrete-Rectangular-Column | 12" x 24" | 32.42 | 179.00 | 46.58 | 1.73 | |
| Concrete-Rectangular-Column | 12" x 24" | 32.42 | 180.00 | 47.48 | 1.76 | |
| Concrete-Rectangular-Column | 12" x 24" | 32.42 | 178.00 | 48.54 | 1.80 | |
| Concrete-Rectangular-Column | 12" x 24" | 43.08 | 229.00 | 57.39 | 2.13 | |
| Concrete-Rectangular-Column | 12" x 24" | 43.08 | 229.00 | 57.39 | 2.13 | |
| Concrete-Rectangular-Column | 12" x 24" | 43.08 | 229.00 | 57.39 | 2.13 | |
| Concrete-Rectangular-Column | 12" x 24" | 43.08 | 229.00 | 57.39 | 2.13 | |
| Concrete-Rectangular-Column | 12" x 24" | 8.32 | 49.00 | 14.97 | 0.55 | |
| Concrete-Rectangular-Column | 12" x 24" | 8.32 | 49.00 | 14.97 | 0.55 | |
| Concrete-Rectangular-Column | 12" x 24" | 43.08 | 180.00 | 56.00 | 2.07 | |
| Concrete-Rectangular-Column | 12" x 24" | 8.32 | 49.00 | 14.97 | 0.55 | |
| Concrete-Rectangular-Column | 12" x 24" | 36.32 | 215.00 | 67.64 | 2.51 | |
| Concrete-Rectangular-Column | 12" x 24" | 36.32 | 215.00 | 67.64 | 2.51 | |
| Concrete-Rectangular-Column | 12" x 24" | 43.08 | 229.00 | 57.39 | 2.13 | |
| Concrete-Rectangular-Column | 12" x 24" | 43.08 | 229.00 | 57.39 | 2.13 | |
| Concrete-Rectangular-Column | 12" x 24" | 43.08 | 229.00 | 57.39 | 2.13 | |
| Concrete-Rectangular-Column | 12" x 24" | 54.00 | 332.00 | 99.89 | 3.70 | |
| Concrete-Rectangular-Column | 12" x 24" | 54.00 | 319.00 | 99.67 | 3.69 | |
| Concrete-Rectangular-Column | 12" x 24" | 54.00 | 332.00 | 99.89 | 3.70 | |
| Concrete-Rectangular-Column | 12" x 24" | 54.00 | 319.00 | 99.67 | 3.69 | |
| Concrete-Rectangular-Column | 12" x 24" | 54.00 | 319.00 | 99.67 | 3.69 | |
| Concrete-Rectangular-Column | 12" x 24" | 42.67 | 266.00 | 79.30 | 2.94 | |
| Concrete-Rectangular-Column | 12" x 24" | 52.08 | 313.00 | 97.80 | 3.62 | |
| Concrete-Rectangular-Column | 12" x 24" | 52.08 | 309.00 | 95.88 | 3.55 | |
| Concrete-Rectangular-Column | 12" x 24" | 52.08 | 313.00 | 95.96 | 3.55 | |
| Concrete-Rectangular-Column | 12" x 24" | 52.08 | 308.00 | 95.83 | 3.55 | |
| Concrete-Rectangular-Column | 12" x 24" | 43.33 | 256.00 | 80.00 | 2.96 | |
| Concrete-Rectangular-Column | 12" x 24" | 43.33 | 256.00 | 80.00 | 2.96 | |
| Concrete-Rectangular-Column | 12" x 24" | 32.00 | 189.00 | 59.00 | 2.19 | |
| Concrete-Rectangular-Column | 12" x 24" | 32.00 | 189.00 | 59.00 | 2.19 | |
| Concrete-Rectangular-Column | 12" x 24" | 32.00 | 189.00 | 59.00 | 2.19 | |
| Concrete-Rectangular-Column | 12" x 24" | 32.00 | 189.00 | 59.00 | 2.19 | |
| Concrete-Rectangular-Column | 16" x 24" | 64.42 | 414 | 129.55 | 4.80 | |
| Concrete-Rectangular-Column | 16" x 48" | 25.65 | 273.6 | 136.80 | 5.07 | |
| Concrete-Rectangular-Column | 16" x 48" | 25.65 | 273.6 | 136.80 | 5.07 | |

Table 6: Shows the Concrete Column Schedule

| CONCRETE COLUMNS | | | | | | |
|--------------------------------|------------|--------------|--------------------|------------------------|--------------|--|
| Type | Size in | Length ft | Surface Area sf | Material: Volume cf | Volume cy | |
| Concrete-Rectangular-Column | 18" x 18" | 32.42 | 193 | 67.31 | 2.49 | |
| Concrete-Rectangular-Column | 18" x 18" | 32.42 | 193 | 67.31 | 2.49 | |
| Concrete-Rectangular-Column | 18" x 18" | 43.08 | 257 | 89.44 | 3.31 | |
| Concrete-Rectangular-Column | 18" x 18" | 43.08 | 257 | 89.44 | 3.31 | |
| Concrete-Rectangular-Column | 18" x 18" | 43.08 | 257 | 89.44 | 3.31 | |
| Concrete-Rectangular-Column | 18" x 18" | 43.33 | 258 | 90.00 | 3.33 | |
| Concrete-Rectangular-Column | 18" x 18" | 43.33 | 258 | 90.00 | 3.33 | |
| Concrete-Rectangular-Column | 18" x 18" | 54 | 322 | 112.13 | 4.15 | |
| Concrete-Rectangular-Column | 18" x 18" | 43.08 | 257 | 89.44 | 3.31 | |
| Concrete-Rectangular-Column | 18" x 18" | 43.33 | 258 | 90.00 | 3.33 | |
| Concrete-Rectangular-Column | 18" x 18" | 43.33 | 258 | 90.00 | 3.33 | |
| Concrete-Rectangular-Column | 18" x 18" | 54 | 322 | 112.13 | 4.15 | |
| Concrete-Rectangular-Column | 18" x 36" | 25.65 | 232 | 111.69 | 4.14 | |
| Concrete-Rectangular-Column | 18" x 36" | 25.65 | 232 | 111.69 | 4.14 | |
| Concrete-Rectangular-Column | 18" x 36" | 25.65 | 232 | 111.69 | 4.14 | |
| Concrete-Rectangular-Column | 18" x 36" | 32.42 | 296 | 134.63 | 4.99 | |
| Concrete-Rectangular-Column | 18" x 36" | 25.65 | 232 | 111.69 | 4.14 | |
| Concrete-Rectangular-Column | 18" x 36" | 25.65 | 232 | 111.69 | 4.14 | |
| Concrete-Rectangular-Column | 18" x 36" | 32.42 | 296 | 134.63 | 4.99 | |
| Concrete-Rectangular-Column | 18" x 36" | 32.42 | 296 | 134.63 | 4.99 | |
| TOTAL CONCRETE COLUMNS: | | | 172.63 cy | | | |
| TOTAL CONCRETE COLUMNS: | | | 13732.2 sf | | | |

Table 7: Shows the Concrete Column Schedule

| FOUNDATION WALL CONCRETE | | | | | | | | |
|--|------------------|----------------|---------------|--------------|----------------|-----------------|--------|-----------------|
| Type of Wall | Type of Concrete | Length (ft) | Width (ft) | Area (sf) | Volume (cf) | Volume (cy) | ton/cy | ton |
| Exterior - 8" Concrete | CIP | 17.67 | 0.67 | 12 | 8.15 | 0.30 | 0.107 | 0.032 |
| Exterior - 8" Concrete | CIP | 6.85 | 0.67 | 5 | 3.05 | 0.11 | 0.107 | 0.012 |
| Exterior - 8" Concrete | CIP | 17.67 | 0.67 | 12 | 7.85 | 0.29 | 0.107 | 0.031 |
| Exterior - 8" Concrete | CIP | 6.85 | 0.67 | 4 | 2.75 | 0.10 | 0.107 | 0.011 |
| Exterior - 8" Concrete | CIP | 6.83 | 0.67 | 5 | 3.33 | 0.12 | 0.107 | 0.013 |
| Exterior - 8" Concrete | CIP | 17.67 | 0.67 | 12 | 7.85 | 0.29 | 0.107 | 0.031 |
| Exterior - 8" Concrete | CIP | 6.83 | 0.67 | 5 | 3.04 | 0.11 | 0.107 | 0.012 |
| Exterior - 8" Concrete | CIP | 17.67 | 0.67 | 11 | 7.56 | 0.28 | 0.107 | 0.030 |
| Foundation - 8" Concrete | CIP | 70.63 | 0.67 | 438 | 311.74 | 11.55 | 0.107 | 1.235 |
| Foundation - 1'-4" Concrete | CIP | 18.03 | 1.33 | 201 | 267.94 | 9.92 | 0.107 | 1.062 |
| Foundation - 1'-4" Concrete | CIP | 6.67 | 1.33 | 76 | 100.67 | 3.73 | 0.107 | 0.399 |
| Foundation - 1'-4" Concrete | CIP | 2.87 | 1.33 | 53 | 70.54 | 2.61 | 0.107 | 0.280 |
| Foundation - 1'-4" Concrete | CIP | 10.28 | 1.33 | 155 | 206.67 | 7.65 | 0.107 | 0.819 |
| Foundation - 1'-4" Concrete | CIP | 57.71 | 1.33 | 709 | 945.85 | 35.03 | 0.107 | 3.748 |
| Foundation - 1'-4" Concrete | CIP | 0.58 | 1.33 | 24 | 32.16 | 1.19 | 0.107 | 0.127 |
| Foundation - 1'-4" Concrete | CIP | 26.71 | 1.33 | 336 | 448.11 | 16.60 | 0.107 | 1.776 |
| Foundation - 1'-4" Concrete | CIP | 42.37 | 1.33 | 516 | 688.50 | 25.50 | 0.107 | 2.729 |
| Foundation - 1'-4" Concrete | CIP | 70.63 | 1.33 | 1048 | 1397.20 | 51.75 | 0.107 | 5.537 |
| Foundation - 2' Concrete | CIP | 19.41 | 2.00 | 68 | 135.62 | 5.02 | 0.107 | 0.537 |
| Foundation - 2' Concrete | CIP | 8.50 | 2.00 | 27 | 53.83 | 1.99 | 0.107 | 0.213 |
| Foundation - 2' Concrete | CIP | 19.41 | 2.00 | 61 | 122.95 | 4.55 | 0.107 | 0.487 |
| Foundation - 2' Concrete | CIP | 8.50 | 2.00 | 21 | 41.17 | 1.52 | 0.107 | 0.163 |
| Interior - 12" Concrete | CIP | 7.31 | 1.00 | 127 | 127.37 | 4.72 | 0.107 | 0.505 |
| Interior - 12" Concrete | CIP | 16.50 | 1.00 | 91 | 90.37 | 3.35 | 0.107 | 0.358 |
| Interior - 12" Concrete | CIP | 13.44 | 1.00 | 53 | 53.10 | 1.97 | 0.107 | 0.210 |
| Interior - 12" Concrete | CIP | 10.33 | 1.00 | 37 | 36.66 | 1.36 | 0.107 | 0.145 |
| Interior - 14" Concrete | CIP | 16.50 | 1.17 | 91 | 106.13 | 3.93 | 0.107 | 0.421 |
| TOTAL FOUNDATION WALL CONCRETE: | | | | 4198 | 5280.16 | 195.5615 | | 20.92508 |

Table 8: Shows the Foundation Wall Schedule

| Type | Width (ft) | Depth (ft) | FOOTING CONCRETE | | | Volume (cy) | Perimeter Form (ft) | Forms SFCA |
|--------------------------------|---------------|---------------|------------------|--------------------|----------------|----------------|------------------------|---------------|
| | | | Length (ft) | Quantity (Each) | Volume (cf) | | | |
| F4.0 | 4 | 1 | 4 | 1 | 16.00 | 0.59 | 8 | 32.00 |
| F6.5 | 6.5 | 2.33 | 6.5 | 1 | 98.58 | 3.65 | 13.00 | 84.50 |
| F9.5 | 9.5 | 3.17 | 9.5 | 2 | 571.58 | 21.17 | 19 | 180.50 |
| F7.5'x 24.5' | 7.5 | 2.67 | 24.5 | 1 | 490.00 | 18.15 | 15 | 367.50 |
| F9.5'x24.5' | 9.5 | 3.17 | 24.5 | 1 | 737.04 | 27.30 | 19 | 465.50 |
| TOTAL FOOTING CONCRETE: | | | | | 1913.21 | 70.86 | | |

Table 9: Shows the Concrete Footing Schedule

| Type Footing | Type Rein. | FOOTING REINFORCING | | | Wt./lf lbs/ft | Wt. lbs. | Wt. Ton |
|-----------------------------------|------------|---------------------|--------------------|------------------|------------------|----------------|------------|
| | | Length (ft) | Quantity (Each) | Wt./lf lbs/ft | | | |
| F4.0 | #5 | 4 | 4 | 1.043 | 16.688 | 0.00834 | |
| | #5 | 4 | 4 | 1.043 | 16.688 | 0.00834 | |
| F6.5 | #6 | 6.5 | 8 | 1.502 | 78.104 | 0.03905 | |
| | #6 | 6.5 | 8 | 1.502 | 78.104 | 0.03905 | |
| F9.5 | #9 | 9.5 | 18 | 3.4 | 581.4 | 0.29070 | |
| | #9 | 9.5 | 18 | 3.4 | 581.4 | 0.29070 | |
| F7.5'x 24.5' | #10 | 10 | 24.5 | 4.303 | 1054.235 | 0.52712 | |
| | #7 | 8 | 24.5 | 2.044 | 400.624 | 0.20031 | |
| | #7 | 24 | 7.5 | 2.044 | 367.92 | 0.18396 | |
| F9.5'x24.5' | #11 | 14 | 24.5 | 5.313 | 1822.359 | 0.91118 | |
| | #9 | 9 | 24.5 | 3.4 | 749.7 | 0.37485 | |
| | #9 | 24 | 9.5 | 3.4 | 775.2 | 0.38760 | |
| TOTAL FOOTING REINFORCING: | | | | | 6522.422 | 3.26121 | |

Table 10: Shows the Concrete Footing Reinforcement

| Type | Width (ft) | Depth (ft) | TIE BEAM CONCRETE | | | Volume (cy) | Perimeter Form (ft) | Forms SFCA |
|---------------------------------|---------------|---------------|-------------------|--------------------|----------------|----------------|------------------------|---------------|
| | | | Length (ft) | Quantity (Each) | Volume (cf) | | | |
| TB-1 | 3 | 3 | 15.75 | 2 | 283.50 | 10.50 | 6.00 | 94.50 |
| TB-2 | 2 | 2 | 8.33 | 1 | 33.33 | 1.23 | 4.00 | 33.33 |
| TB-3 | 2.5 | 2.67 | 24.00 | 2 | 320.00 | 11.85 | 5.33 | 128.00 |
| TB-4 | 2.5 | 2 | 17.50 | 1 | 87.50 | 3.24 | 4.00 | 70.00 |
| TB-5 | 2 | 1.5 | 17.50 | 1 | 52.50 | 1.94 | 3.00 | 52.50 |
| TB-6 | 3.33 | 2.5 | 25.00 | 1 | 208.33 | 7.72 | 5.00 | 125.00 |
| TOTAL TIE BEAM CONCRETE: | | | | | 985.17 | 36.49 | | |

Table 9: Shows the Concrete Tie Beam Schedule

| TIE BEAM REINFORCING | | | | | | |
|------------------------------------|------------|-------------|-----------------|---------------|-----------------|----------------|
| Type Footing | Type Rein. | Length (ft) | Quantity (Each) | Wt./lf lbs/ft | Wt. lbs. | Wt. Ton |
| TB-1 | #10 | 15.75 | 14 | 4.303 | 948.8115 | 0.47441 |
| | #6 | 15.75 | 8 | 1.502 | 189.252 | 0.09463 |
| | #4 | 5.5 | 16 | 0.668 | 58.784 | 0.02939 |
| TB-2 | #10 | 8.33 | 6 | 4.303 | 215.0639 | 0.10753 |
| | #6 | 8.33 | 6 | 1.502 | 75.06996 | 0.03753 |
| | #4 | 1.67 | 9 | 0.668 | 10.02 | 0.00501 |
| TB-3 | #10 | 24 | 8 | 4.303 | 826.176 | 0.41309 |
| | #6 | 24 | 8 | 1.502 | 288.384 | 0.14419 |
| | #4 | 4.75 | 24 | 0.668 | 76.152 | 0.03808 |
| TB-4 | #10 | 17.5 | 7 | 4.303 | 527.1175 | 0.26356 |
| | #6 | 17.5 | 5 | 1.502 | 131.425 | 0.06571 |
| | #4 | 4.75 | 24 | 0.668 | 76.152 | 0.03808 |
| TB-5 | #6 | 17.5 | 4 | 1.502 | 105.14 | 0.05257 |
| | #6 | 17.5 | 4 | 1.502 | 105.14 | 0.05257 |
| | #4 | 2.92 | 24 | 0.668 | 46.76 | 0.02338 |
| TB-6 | #10 | 25 | 14 | 4.303 | 1506.05 | 0.75303 |
| | #6 | 25 | 8 | 1.502 | 300.4 | 0.15020 |
| | #4 | 5.33 | 24 | 0.668 | 85.504 | 0.04275 |
| TOTAL TIE BEAM REINFORCING: | | | | | 5571.402 | 2.78570 |

Table 10: Shows the Concrete Tie Beam Reinforcement