# **Southwest Student Housing Building**

1000 Apache Boulevard East, Tempe, Arizona

## **Project Team:**

- Owner Arizona State University
- Architect BOKA Powell
- Structural Engineer Thornton-Tomasetti
- MEP Engineer WSP Flack+Kurtz
- Agency CM Romani Group, Inc.

## Construction:

- Projected schedule 302 days total 125 days Preconstruction 177 days Construction
- 4 weeks for concrete cores
- 2 days for each half-floor

#### **Basics**:

- Purpose Dormitories
- Size 268 units with 528 beds: Area per story - 13,000 ft<sup>2</sup> Total area - 260,000 ft<sup>2</sup>
- Stories 20 stories
- Estimated Total Cost \$37,358,413
- Distinguishing features modular building (3 or 4 modules per floor), prefabricated bathrooms, constructed as a modified lift slab

(Each floor is constructed on the ground in (2) halves, which are separately lifted into place with (6) 75-ton strand jacks, placed at the corners of the finished concrete cores. Interior work starts immediately on each floor once it is constructed and lifted into place.)

## Structural:

- Foundation concrete piers (12 to 60" in diameter) penetrating 12.5 to 47.5' into the ground; piers and mats are located under each core to directly support gravity load
- Superstructure composite floor (3-1/4" lightweight concrete on 3" metal deck) attached to structural steel frame made of wide flange beams (sizes from W14x22 to W24x176) using Hilti fasteners;

Typical bay size: 12'-6"x13'

Ksenia Tretiakova

Structūral Option

 Lateral System - gravity and lateral system are the same: (3) 8" thick concrete cores, 25'x25'on center with a single layer of rebar running through center

## **MEP Systems:**

- Mechanical 1st floor mechanical room contains chillers, pumps and water tanks 4-pipe system with single fan coil units on each pipe supply hot and chilled water; Bathroom exhaust fans located on roof, above stacked bathrooms
- Fire Safety wet system in building, dry system in parking lot; jockey pumps in mechanical room; 1 sprinkler in each sleeping room, foyer and bathroom; all corridors are sprinkled
- Lighting/Electrical 1 main panel at each floor with subs in each unit; Electrical design is currently incomplete and pending.

#### CPEP Website:

http://www.engr.psu.edu/ae/thesis/portfolios/2012/KKT5018/