

Architectural

 Rock faced CMU, red brick, and limestone sills create a new look while maintaining the look of the existing portion of the building.

- Barrelled roofs on the new auditorium and gymnasium update the elevations
- Unionville-Chadds Ford School district administrative offices located at the south of the building.
- New auditorium added to northwest corner of building
 High end finishes including acoustical CMU block, oak molding, and hard wood stage floor
- New gymnasium added to northeast corner of building

Construction

- 4 primary phases with 17 total subphases developed to efficiently complete the project

- Phase 1: Construction of new Unionville-Chadds Ford Administractive Offices
- Phase 2: Construction of new auditorium and renovations of existing classroom space on first, second, and third floor
- Phase 3: Renovation of existing auditorium and completion of classroom renovations
- Phase 4: Demolition of existing 1 story, construction of new gymnasium, renovation of classroom space on first floor.

Owner:

Unionville-Chadds Ford School District

Architect: MM Architects, Inc.

General Contractor: Wohlsen Construction

Site/Civil Engineer: ELA Group, Inc.

Structural Engineer: Joseph Barbato Associates, LLC.

Mechanical/Electrical Engineer: Gipe Associates, Inc.

Kitchen Design Consultant: Clark Food Service Equipment

Building Information

Total Height: 3 Stories Building Area: 319,000 Square Ft Contract Value: \$51,895,000.00 Timeline: June 2009 - Dec 2012

MICHAEL BEAM - CM OPTION

w.engr.psu.edu/ae/thesis/portfolios/2012/MS85153



ADDITIONS AND RENOVATION

Kennett Square, Pennsylvania

Eletrical/Lighting System

- 35000 Volt service entrance
- 2500KVA 34.5/19.9KV to 4.16/2.4KV outdoor oil filled transformer
- 4160 Volt, 3 phase primary system and 480/277V, 3 phase, 4 wire Y secondary system
- Building utilizes both 480/277V and 208/120V power
- Classrooms and corridors use primarily 2' x 4' recessed fluorescent fixtures, F32T8 lamps
- 50W MH Metal halide and Q250 T4 fluorescent lamps used in 9" diameter x 16" long suspended metal cylindrical down fixtures in new auditorium

Mechanical

- 22 Total AHU's: 18 new units and 4 existing units
- 15 new and the 4 existing AHU's located on the roof
- 3 new AHU's located in mechanical rooms
- Primarily DOAS AHU's with several VAV and CAV units
 - DOAS AHU's supply fan loads ranging from 5,500 to 9,900 CFM
- 10 trane BCU's, each interlocking with a specific AHU

Structural System

Foundation

 Structural steel columns on reinforced concrete piers.
 CMU Block foundation walls and reinforced concrete footings

Building Structure

- Predominantly wide flange members with some hollow structural section members
 - Most Common:
 - W10x33
 - W14x90

 Floors either slab on grade or 4" of concrete over metal decking

Roof

- Structural steel trusses and joists - Curved members for barrelled roofs: - 48LH13 joists for new auditorium - W10x39 truss for new gymnasium



Executive Summary

This comprehensive Senior Thesis Final Report has been compiled to present information obtained through research concerning four analysis depth topics and two depth topics in regards to the Unionville High school Building Project. With an overall size of 319,000 square feet and three stories above grade, the UHS building project has four main phases with both additions and renovations.

Analysis 1: Delivery Method Study highlights UHS' use of a Single Prime delivery method and compares this method to the PA mandated Multiple Prime delivery method. Based on past experience, the school district was able to receive a waiver to use a Single Prime. Ultimately, *the district benefited* from this arrangement due to better communication, fewer delays, and even cost savings.

Analysis 2: 4D Safety and Phase Plan discusses the implementation of BIM on the project. With no BIM used as part of the original project design, the possibility of added value existed by introducing BIM in some capacity. Ultimately, a phase by phase safety plan using a 3D model will be developed for use by the School district. Increased information regarding the project leads to a safer project and based on the proposed application, it is believed that the owner would *benefit greatly from implementing BIM*.

Analysis 3: On Site Renewable Energy aimed to add an on-site energy source to the project, which strived for LEED certification but lacked renewable energy. After comparing the two, Photovoltaic Cells were chosen over Wind energy. Following system design and implementation, it was determined that based on use of Purchase Power Agreement, UCFSD stands to *save over \$400,000* over the life of the contract, providing significant benefit to the owner.

Analysis 4: Façade Redesign aimed to improve upon the stick-built façade of the original design. Using Phase 1 as a microcosm of the building, a precast façade panel design was chosen and implementation was studied. Despite a savings in installation duration, added cost, a change in aesthetics, and reduced thermal properties show that *the original façade is a better option for the UHS project*.



Table of Contents

Abstract ————	——————————————————————————————————————
Executive Summary	iii
Table of Contents	iv
Building Introduction	1
Project Information	2
Local Conditions	2
Existing Conditions	4
Client Information	5
Project Delivery System	7
Staffing Plan	9
Building Systems	10
Project Cost Evaluation	18
General Conditions Estimate	20
Detailed Project Schedule	22
Analysis 1: Delivery Method Study	24
Problem Identification	24
Research Goal	24
Research Methods	24
UHS Delivery Method Selection – Single Prime	25
Delivery Method Background Information	27
PA Separations Act	31
Delivery Method Comparison	35
Conclusion and Research Result	40



Analysis 2: 4D Safety and Phase Plan	41
Problem Identification	41
Research Goal	41
Research Methods	42
Background Information	43
Project Phasing Information	44
Case Study	45
UHS BIM Applications	47
Hazardous Area Identification	<u> </u>
Conclusions and Findings	53
Analysis 3: Sustainability – On Site Renewable Energy	54
Problem Identification	54
Research Goal	5 4
Research Methods	54
Background Information	55
Case Studies	61
Renewable Energy Source Selection – Photovoltaic Cells ————	67
Solar Design Parameters	68
Photovoltaic System Design	7 3
Cost Analysis	77
Conclusions and Findings	80
Analysis 4: Façade Redesign – Prefabricated Panel Facade	82
Problem Identification	82
Research Goal	82
Research Methods	83
Background Information	
Current Façade Information	85
Prefabricated Panel Selection	87
Panel Implemenation ————————————————————————————————————	89
Conclusions and Findings	93



Mechanical Breadth: Façade Mechanical Impact	95
Structural Breadth: Façade Structural Impact	99
Sources	104
Acknowledgements	107
APPENDICES	108
APPENDIX A: Phasing Plan and Area Key	108
APPENDIX B: Existing Conditions Site Plan	110
APPENDIX C: Square Foot Estimate Calculations	112
APPENDIX D: General Conditions Estimate Calculations	117
APPENDIX E: Detailed Project Schedule	120
APPENDIX F: Interview with Wohlsen PM Brian Laub	131
APPENDIX G: Delivery Method Diagrams	133
APPENDIX H: Potential Roof Regions for PV Array	136
APPENDIX I: PV Array Shadow Analysis Images	138
APPENDIX J: Selected Roof Regions for PV Array	147
APPENDIX K: Solar Panel & Inverter Specifications	150
APPENDIX L: PVWatts Data Output	157
APPENDIX M: UHS Electricity Cost Savings	159
APPENDIX N: UHS Payback Period	161
APPENDIX 0: Façade Assembly Comparison	163
APPENDIX P: Precast Panel Calculations and Information	165
APPENDIX Q: HAM Toobox Original Façade Analysis	173
APPENDIX R: DesignBuilder Analysis Outputs	176
APPENDIX S: Structural Breadth Hand Calculations	180



Unionville High School Building Introduction

Unionville High School is a public education building located in Kennett Square, Pennsylvania. The Building is 3 stories tall with a total square footage of 319,000 square feet, and houses both Unionville High School as well as the Unionville-Chadds Ford School District Administrative Offices. The project has an initial project cost of around \$52 Million and a schedule spanning from June 2009 to December 2012, the UHS project is a project incorporates demolition, renovations, and new additions.

During the first phase of the project, a brand new wing will be constructed housing new Administrative Offices, classrooms, and science labs. Following this additions completion, the existing administrative offices will be renovated into classroom space. During phase two, a brand new auditorium will be constructed, with more classroom space renovation occurring as well. Phase three will see the existing auditorium renovated into new classroom and athletic education spaces. Finally, Phase 4 will see the construction of a new gymnasium followed by the renovation of the existing gymnasium and demolition of the existing auxiliary gymnasium. A detailed phasing plan and area key are available for APPENDIX A.

Building Information

Building Name	Unionville High School
Location and Site	750 Unionville Road, Kennett Square PA
Occupant Name	Unionville-Chadds Ford School District
Building Area	319,00 Square Feet
Stories Above Grade	3 Stories

Construction Information

Construction Cost	\$51,895,000
Construction Timeframe	June 2009 – December 2012
Contract Type	Hard Bid Public Work
Delivery Method	Single Prime

Project Team

Owner	Unionville-Chadds Ford School District
Architect	MM Architects, Inc.
General (Prime) Contractor	Wohlsen Construction Company



Project Information

Local Conditions

Kennett Square Pennsylvania, known as the "The Mushroom Capital of the World", is home to the Unionville-Chadds Ford school district. Designed at a size of 3 stories above grade with an overall size of 319,000 square feet, the Unionville High School Building will undergo demolition, renovation, and addition during the course of the project. The map below (figure 1) shows an aerial view of the site prior to the beginning of construction. With students onsite it is vitally important that as little of the building is disturbed during construction as possible. Phasing was utilized during this project in order to keep the school in operation and disturb building inhabitants as little as possible. All material removed during the construction process is to be recycled according to LEED requirements.



Figure 1: Aerial View of UHS Project Site



Parking is available for contractors in several locations depending on the current construction phase; the red region shows available contactor parking for phases 1, 2, and part of phase 3, the orange region is available for parking during phase 3, and the blue region shows available parking for phase 4. Parking availability varies throughout the project in order to accommodate both the phasing of the project as well as the UCFSD Administrative Staff; UCFSD Administrative Staff members will park in the blue region until phase 4, when their parking location moves to the red region and the contractors begin to occupy the blue region. Wohlsen on-site staff members are permitted to park in the southwest corner of the blue region at all times, as jobsite trailer are located here. No specific permitting issues have been identified for this public education project.



Existing Conditions

Although there is a middle school in close proximity, this project will deal only with the Unionville High School building. Initally, the project site was home to only the Unionville High School. As a result of this project, the site will now house both the Unionville High School as well as the Unionville-Chadds Ford School District Administration Building. As a result of the construction project, several multi-purpose fields were removed near the north east of the site and in their place went a new parking lot. The parking lot in the front of the existing building was expanded slightly and a one-way vehicular entrance to the parking lot was added from Unionville Willowdale Road.

Site utilities come from both the (magnetic) east and west, with several different branches feeding either the High School or the adjacent middle school depending on specific utilities. A few small access roads links both schools' parking areas and vehicular access paths. No covered pathways or temporary lighting are to be used at any point for students or staff members during the project as there was no need to reroute any pedestrian traffic using the exterior of the building. Several parking areas are shown on the site plan with most belonging to the high school. Throughout the project, contractor parking locations and UCFSD parking locations will vary depending on where construction is occuring during the different phases. An existing condition site plan for all phases can be found in APPENDIX B.



Client Information

Unionville-Chadds Ford School District is a public school district in Pennsylvania, including several other schools besides Unionville High School including Charles F. Patton Middle School and Unionville, Chadds Ford, Hillendale, and Pocopson Elementary Schools. The map below illustrates the layout of the Unionville-Chadds Ford School District and the location of each educational facility, including the Unionville High School Building. Figure 2 shows the entire school dsitrict, with Unionville High School located near the center of the district.



Figure 2: Unionville-Chadds Ford School District

A growing population within the school district led to the need to expand the school district's only high school. In addition to the new building accommodating the growing needs of Unionville High School it would also be the new home to the Unionville-Chadds Ford School District Administrative Offices. While increasing the space of Unionville High School is a key factor, many spaces and features within the high school were well outdated and the old administrative office was well overdue for an upgrade.



Among the outdated facilities within the old building included classrooms, art rooms, lockers rooms, the gymnasium, and namely, the auditorium. Renovations to classroom space will not only improve the look of these spaces but also the functionality and energy efficiency. The new Auditorium will sport hi-tech audio, video, and lighting equipment and an expanded seating capacity, leading to a space that better suit students involved in arts programs throughout the district. Several spaces including the new gymnasium, wrestling area, and locker rooms will improve the portions of the building that directly affect the student athletes and members of the athletic programs for the school.

Cost, while not completely unimportant, is the not the focus of this project. The schedule, on the other hand, is of great importance. As with most educational projects, construction disrupts the flow of everyday life. With a project such as this that includes both new construction and renovation, seamless phasing is even more important. 4 phases and 17 sub phases are to be utilized in order to minimize the construction process' effect on the students, faculty, and other inhabitants of Unionville High School. As a site note, the school required that no smoking occur on site, inside or outside of any structure, at any time.



Project Delivery System

The chart on the next page (figure 3) shows the breakdown of the project from a contractual standpoint. As the Unionville High School Additions and Renovations project is in the public sector, a hard bid method was used during the design phase and a Single Prime Delivery method was used for this particular project. The Owner, Unionville-Chadds Ford School District, is contracted directly with both MM Architects, Inc. and Wohlsen Construction, both of which are Lump Sum contracts. MM Architects has Lump Sum contracts with all engineers for this project, including Gipe Associates, Inc., ELA Group, Inc., and Joseph Barbato Associates, LLC. Wohlsen Construction is acting as the General Contractor and was awarded the Unionville High School Building project after submitting the lowest bid. As the GC for the project Wohlsen owns all contracts (also Lump Sum) with subcontractors, who are prequalified and selected based on the lowest bid. All subcontractors are required to be completely bonded, a key part of the contract in terms of keeping work moving. In addition to managing the contracts of all on-site contractors, Wohlsen is also self-performing some work such as portions of the on-site concrete work and interior carpentry work.

Utilizing a Single Prime project delivery method was the best option for this particular project. The owner has complete jurisdiction over the design and is able to speak directly with both the architect and the general contractor regarding the project. UCFSD has done similar educational construction projects in the past, so their knowledge of the construction industry is above average and although management of the entire project is not feasible, this previous experience allows for effective communication with both Wohlsen and the other parties involved throughout the project. Wohlsen's experience in the educational sector and on prior projects with the client made them an easy choice for UCFSD. Their knowledge of past works offers significant experience and makes them an ideal GC for the project. Despite the lack of a contract between parties, Wohlsen is able to communicate directly with MM Architects, Inc. and all Engineers contracted to them. Open lines of communication not only increase productivity but also help to solve issues as they arise in an efficient manner.





Figure 3: Project Delivery Method



Staffing Plan



Figure 4: Staffing Plan

Wohlsen's staffing plan (figure 4) for the Unionville High School Building project can be seen above. The above plan is consistent with standard Wohlsen staffing plans, utilizing a Project Manager, Project Engineer, Project Assistant, Superintendent, and Foreman. The above staff includes the entire project team, however only the Project Engineer, Superintendent, Foreman, and Intern located on-site at all times. The Project Manager and Director of Public works visit the site as well, with the PM making trips at least once per week. Wohlsen's Director of Safety and other safety department members, although not a member of just this project team, oversees all Wohlsen projects. No safety coordinator was needed on-site for this particular project. Generally speaking, a Project Manager oversees between 2-3 projects and teams, while the Director of Public Works oversees all projects in the public sector. Project assistants generally work with the same PM on all projects, working on 2-3 projects at a time as well.



Building Systems

Demolition

Many new spaces are planned as part of this large public education project. In addition to the new construction on the building, demolition is required as many renovations are to take place during the project. Wrestling, physical education, and fitness and weight room space are set to replace half of the existing gymnasium once demolition of the existing facility have been demolished, and a new gymnasium is set to be constructed on the West side of the building. The existing auditorium is to be renovated into classroom space as a brand new 1,200-seat auditorium set to be built at the North end of the building, certain to become the new focal point of the building.



Figure 4: Demolition during Phase 4

Material to be removed includes structural CMU block, brick, windows, doors, structural steel, cast-in-place concrete, stage flooring, drywall, and roofing materials. Some items, such as acoustical wall panels from the existing auditorium, are to be saved and reused in other locations within the new building. All material is to be demoed by B&P Neal Demolition, who is also responsible for the proper

removal of all materials. One exception is asbestos: the owner, Unionville-Chadds Ford School District, is responsible for all removal of asbestos. Once removed, B&P Neal is required to wait 10 calendar days before they are permitted to return to their demolition duties. During the process, several instances of asbestos occurred including readings from both ceiling and floor tiles. Figure 4 shows demolition during Phase 4 of construction during the Summer of 2011.



Structural

The primary foundation system uses several types and sizes of structural steel columns in tandem with reinforced concrete piers and footers, a 4" concrete slab on grade on top of 4" of crushed stone, and 16" CMU block for the foundation walls. Although primarily made up of W-flange columns, several locations throughout the foundation system utilize hollow structural steel members. HSS8x8x1/2 columns are used on the Western side of the building, while W10x33 and W14x90 are the two most prevalent w-flange sizes used in the foundation system. In most areas, the steel columns and CMU block walls run more than one story and make up the structure for exterior walls for the building. Reinforced concrete piers designed to carry the load of the columns range from 1'10" x 1'10" to 3'0" x 1'10" in size. There are several sizes of strip footings using primarily #5 rebar as well as various column spread footing sizes using #4, #6, and #8 rebar.

The steel erection on this project required the use of a 90-ton crawler crane. The need to move laterally along the portion of the building during each phase of construction made a crawler crane the best choice for this specific project. Structural steel erection is present in each phase, meaning the crane will be used at several points throughout the projects lifetime. Due to the many phases and sub phases during construction, crane location changes several times throughout the project.

The upper floors of the building utilize a structural steel skeleton system composed almost entirely of W-flange beams, primarily W10, W14, W18, and W21 members. In the instance of an elevator shaft, however, 8" CMU block is to make up the structure for the wall. Due to the multiple elevations of the land on site, several types of flooring systems have been designed. A 4" slab on grade on top of 4" crushed rock serves as the flooring system for the portion of the building sitting on soil, while a concrete on metal deck system is to be used when an area is above a preceding floor.



A variety of roofing systems are to be used throughout the building, depending on the area. Due to the large span and the barreled roof design, 48LH13 joists have been chosen as the



Figure 5: Barreled Auditorium Roof

structure for the auditorium roof (figure 5). Each joist has 8 foot wide bays, a curved top chord, and a 7 ½" height between the seat and the bottom chord. The new gymnasium will feature a similar roofing system, utilizing W10x39 truss with a curved top chord.



Cast-In-Place Concrete

All cast-in-place concrete used on the UHS Additions and Renovations project is to be designed per ACI 301. Items using CIP concrete include column piers, spread footings, strip footings, foundation walls, suspended slabs, stairs and access ramps, and retaining walls. All CIP concrete must meet minimum 28-day strength of 4000psi with a slump ranging from 2" to 4".

Formwork and shoring is to be provided by the subcontractor and designed to meet ACI 301 standards. Formwork is to remain in place until the concrete in question has reached at least 90% of its 28 day compressive strength. Form-facing panels are to be used for any smooth-formed finished concrete. These panels are designed to provide continuous smooth concrete surfaces, suitable for an exposed finished face. Plywood, metal, or other materials approved by the owner are acceptable to meet this requirement. Rough-formed concrete will be used in most applications and can also be formed using the same materials listed above. Any cylindrical member, including columns and pedestals, is to be constructed from metal, glass-fiber-reinforced plastic, paper, or fiber tubes that produce minimal or no irregularities on the surface of the concrete.



Figure 6: Ongoing Concrete Pour

Reinforcement and formwork installation must be checked before any concrete placement can occur. Concrete is to be placed in layers such that no new concrete is placed on already hardened concrete, eliminating the possibility of seams or weak planes within the slab (figure 6).

Construction joints are to be provided for any slab that cannot be poured continuously. A mechanical vibrator is to be used in order to ensure equal and should be used only on the newest layer of concrete. Over vibration can compromise the quality of the concrete, so care must be taken when consolidating.



Mechanical

With 319,000 square feet to condition, the Unionville High School Building utilizes 22 Air Handling Units, 4 existing and 18 new. The 4 existing units as well as 15 of the new AHU's are located on the roof, with the remaining 3 new units housed in mechanical rooms within the building. The mechanical rooms housing these units are located on the 2nd and 3rd floors, with AHU's 10 and 11 located in mechanical room 30.9A and AHU 17 located in mechanical room 201.1. All standard classrooms loads are handles by Innovent Laser Dedicated Outside Air Systems (DOAS), with supply fan loads ranging from 5,500 to 9,900 CFM. The auditorium is supplied completely by one unit, an Innovent RHXC Single Zone Heat Recovery VAV Unit with a max supply fan load of 26,000 CFM. Another single zone heat recovery system is used in the Gymnasium, with an Innovent 5000 VAV unit supplying a maximum of 32,000 CFM. In total 11 DOAS, 2 DOAS/VAV, 7 VAV, and 2 CAV units are to be used to service the building.

A total of 10 Blower Coil Units service the building as well, all of which are provided by Trane. Each 4 pipe BCU uses interlocks with a specific AHU and services multiple locations. The maximum loading capacity of the air sides of the units range from 300 to 2,770 CFM, while the cooling coil system loads range from 1.0 to 7.0 GPM and the heat coil loads range from 1.0 to 4.5 GPM. Finally, Vulcan DV-412 baseboard radiators have been used in several locations, generally some of the smaller spaces within the school including special education classrooms and personal offices. Each radiator is to be installed 4" from the top of the finished floor and is designed to handle a capacity of 5,400, 9,000, or 15,300 (corridor) BTU load depending on the space.

The new gymnasium and auditorium are to be fully sprinklered per NFPA 13 specifications. Sprinklers are required in all renovated spaces and every area within the newly built portion of the building, with renovated spaces remaining protected under the existing system. Pendant sprinklers are used in all spaces, most of which have covers. Sprinklers without covers are located in mechanical rooms, storage space, or other rooms with no ceiling.



Electrical

The Unionville High School utilizes a 35000 Volt service entrance into metal-enclosed switchgear provided by S&C Electric Company which feeds into a 2500KVA 34.5/19.9KV to 4.16/2.4KV Outdoor Oil Filled Transformer, through a metering station, and finally into a 1500KVA Oil Filled Transformer with a 4160 Volt, 3 Phase primary, and a 480/277V, 3 phase, 4 wire Y transformer secondary. Due to the varying uses throughout the building, both 480/277V and 280/120V service is used throughout the building. All of the lighting within the building is serviced by 480/277V, 3 phase power as well as all blower coil units (BCU) and air handling units (AHU). All equipment used in the shop is fed with 480/277V power, while kitchen equipment and other miscellaneous items run on 208/120V power.



Lighting

Many different fixtures are used throughout the building based on which area they are serving. Classrooms are designed using a 2' x 4' recessed fixture with a fluorescent troffer and an acrylic diffuser, utilizing a 2, 3, or 4 lamp electronic ballasts (figure 7). 2' x 4' recessed fixtures are also used in the corridors of the buildings, although each fixture used in the corridor uses just two lamps. All 2'x'4 recessed



Figure 7: 2' x 4' Recessed Classroom Fixtures

fluorescent fixtures, classroom and corridor alike, utilize F32T8 lamps. Almost every classroom and restroom is designed with occupancy sensors in order to cut down on unnecessary use of electricity.

With a brand new auditorium comes a state of the art lighting system. The main lighting system for the auditorium uses a 9" diameter x 16" long metal cylindrical fixture. Both Metal Halide and Fluorescent lamps are used with this fixture type using Q500 T4 or 70W MH in the front and majority of the auditorium, or Q250 T4 or 50W MH lamps above the balcony towards the back of the balcony. Two different fixture types (research ongoing) are designed to be mounted on the three catwalks and will be utilized to illuminate the stage during use.



Masonry

Masonry is used on this project both as a load bearing material and an architectural veneer. CMU blocks are used in various locations throughout the building, as well as a portion of the foundation. 20" CMU units are used for the new gymnasium, 16" CMU blocks are used for foundation walls, and 12" CMU are used to construct the walls of the new auditorium. 6" 8" CMU units will be used to construct walls dividing standard classrooms and other standard



Figure 8: Rock Face Architectural Block

spaces.

Rock face architectural block (figure 8) and standard red brick is to be used to make up the building façade. Structural CMU masonry units will sit on the structural steel frame and the façade veneer will be connected using masonry ties or adjustable anchors. Wire ties can be made of a number of materials and can come in

the form of wire ties or corrugated metal ties. Adjustable anchors for units connected to steel framing are designed to allow horizontal or vertical adjustment but to resist tension and compression forces perpendicular to the wall.



Project Cost Evaluation

Construction Cost

The Construction Cost for the Unionville High School Additions and Renovations project is based on figures as of summer 2011. The following items have been excluded in order to arrive at the Construction Cost of the project.

- General Conditions
- Site Work
- Contingency
- Fee
- Controls
- Insurance

All cost data is provided by Wohlsen Construction; approved change orders to date have been

included. A total project size of 319,000 is assumed.

Actual Building Construction Cost

Total Building Construction Cost\$46,051,101.52Total Building Construction Cost/S.F.\$150.30

To calculate Total Building Cost, all line items have been totaled including the items that were

excluded to obtain actual project cost.

Total Project Cost

Total Building Cost\$52,744,833,02Total Building Cost/S.F.\$165.34

Major Building System Costs

	<u>Total Cost</u>	<u>Cost/S.F.</u>
Site Work	\$2,638,575.00	\$8.27
Substructure	\$2,073,459.00	\$6.50
Superstructure	\$3,710,829.32	\$11.63
Building Enclosure	\$5,562,196.13	\$17.44
Roofing	\$2,475,495.00	\$7.76
Fire Protection	\$360,366.25	\$1.13
Mechanical System	\$9,764,531.92	\$30.61
Plumbing System	\$2,610,852.54	\$8.18
Electrical System	\$5,931,113.41	\$18.59



RS Means Square Foot Cost Estimate

In order to develop a Square Foot estimate, the CostWorks software from RS Means was utilized. A square foot estimate was developed to compare to the actual project cost. Below is a chart showing all information used to develop the estimate.

Estimate Parameters

Building Type	School, High, 2-3 Story
Facade	Decorative Concrete Block
Structure	Steel Frame
Area	319,000 Square Feet
Perimeter	4,650 Linear Feet
Stories	3 Stories
Story Height	13.5 Feet

After entering the above information and running the analysis, RS Means CostWorks produced the following results for the Square Foot and Assembly analyses:

RS Means Square Foot Estimate Results

Total Building Cost\$38,878,000.00Building Construction Cost/S.F.\$121.87

RS Means provides information based on general parameters (see above chart). These parameters included building type, size, and location. Also, renovation work costs are not provided by RS Means CostWorks therefore all work was estimated as new construction. Another reason for the lower total building cost and cost per square foot is due to RS Mean's lack of knowledge of what specific spaces are within the building. For example, the new auditorium is fit out with high end finishes. Further information provided by RS Means CostWorks on the square foot estimate can be found in APPENDIX C.

Cost Comparison

	Total Building Cost	Construction Cost/S.F.
Actual Building Cost	\$46,051,101.52	\$150.30
RS Means S.F. Estimate	\$38,878,000.00	\$121.87



General Conditions Estimate

Rather than estimating just one portion of the project (as was done with the structural estimate), the entire project has been accounted for in this general conditions estimate. The source for the information used to develop this general conditions estimate comes from *RS Means Building Construction Costs 2011*.

Several assumptions have been used to produce this estimate:

- Project Information
 - **Project Duration**:
 - 183 Weeks
 - 42 Months (original schedule)
 - Construction Site size
 - 900,000 Square Feet
 - 21 Acres
 - o Construction Site Perimeter
 - Perimeter: 4,300 Linear Feet
- Field Personnel

0

- 'Clerk' has been used to estimate the cost of a Project Assistant
- 'Field Engineer' has been used to estimate the cost of a Project Engineer
- Temporary Utilities
 - The only temporary utilities accounted for in this estimate refer to the utilities providing power, electricity, HVAC, etc. to the trailer. All power and other utilities for the project are assumed to have been provided by existing portions of the building.

Construction fees and contingencies have been excluded from this estimate. Due to the lack of some 'Total Cost' information for certain items used in this estimate, all costs have been quantified using 'Total Cost including O&P' data. Final values include a *location factor of 108.9* and have been rounded to more easily interpret the cost data. Based on these assumptions, the following cost information has been derived.

General Conditions | Total Cost

Total Cost including O&P\$4,020,000.00Total Cost with Location Factor
Construction Cost\$4,400,000.00General Conditions % of Total Cost\$8.5%



At 8.5%, this estimate is within a reasonable range in terms of price relative to the overall project cost. Most costs were calculated to be incurred for the entire duration of the project, but several costs were estimated based on their estimated duration on the project. Small variations may have altered the value of the estimate due to the exclusion of specific items from the estimate, namely items that RS Means did not have a specific value for. A further breakdown of the estimate can be seen below, with the entire project cost being divided into monthly costs for four main categories: Field Personnel, Insurance and Bonds, General Construction Costs, and Office and Storage Space. These values are derived from the General Conditions Cost with the location factor (108.9) applied.

General Conditions | Cost Per Month (including Location Factor)

Project Staff	\$41,500.00
Insurance and Bonds	\$37,000.00
General Construction Costs	\$25,000.00
Office and Storage Space	\$1,000.00
Total Cost	\$104,500.00

With more than \$100,000.00 per month in general conditions costs, it is clear that the schedule must be followed precisely. Not only would a delay produce direct costs, but liquidated damages (agreed upon in the contract) would be incurred as well. Note: Although some costs in the estimate are not incurred for the entire duration of the project, these values have been calculated as a division of the entire cost by the duration of the project in order to provide a rough estimate of monthly costs. This calculation allows for a quick view at which portions of the general condition contribute more to the job cost than others.

All General Conditions estimate information can be found in APPENDIX D.



Detailed Project Schedule

Projects including additions and renovations to a building require that some or most of the building remain in use during the construction process. As a result, the Unionville High School Building Additions and Renovations project follows a carefully designed phased construction schedule. The GMP contract was developed and agreed upon between UCFSD and Wohlsen Construction as a result of a hard bid publics work job. Overall, the project design spanned from June of 2008 until 2009, with construction initially slated to begin on June 22nd, 2009 and finish on December 28th, 2012. As of October 19th 2011 when this report was completed, the estimated finish for the project had moved up roughly three months and is expected to be completed on September 29th, 2012. With multiple phases during construction, the project team was able to develop a schedule in order to efficiently complete building construction while limiting the disruption of everyday life for students and faculty.

Each phase of construction focuses on one portion of construction, although some phases do incorporate multiple areas of the building. The first phase focuses on the addition of a new wing which will house District Offices and classroom space. Phase three focuses on the addition of the new Auditorium as well as the renovation of existing spaces within the building. The existing auditorium is renovated into Choral and Tech Ed rooms during phase three, and phase four sees the demolition of an existing portion of the building in order to make room for the new Gymnasium. Overall the project duration (as of this report) is set to span 39 months from June 15th 2009 until September 28th 2012. The phasing plan, as well as a map outlining the areas of the building, can be seen in APPENDIX A. Phase descriptions and phase timelines are listed below.



Phase Descriptions

- Phase 1: Construction of the New 3 story addition, set to house the Unionville-Chadds Ford School District Administrative Offices, Classrooms, and Science labs.
- Phase 2: Construction of the New Auditorium, Art rooms, and Family and Consumer Classrooms.
- Phase 2A: Renovation of existing Large Group Instruction, Library, Faculty Restrooms, Cafeteria, and Kitchen.
- Phase 2B & 2C: Renovation of existing District Administrative Offices into High School Offices, Science Labs, and Classrooms.
- Phase 2D: Renovation of existing High School Offices, Music Area, and Faculty Dining.
- Phase 2E: Renovation of existing Science Labs and Classrooms.
- Phase 2F: Renovation of existing Classrooms
- Phase 2G: Renovation of the existing Computer Applications Labs and Classrooms.
- Phase 2H, 2I, 2J: Renovation of existing Classrooms.
- Phase 3: Renovation of existing Auditorium into Choral Room and Tech Ed Classrooms.
- Phase 4: Demolition of existing Classroom and Tech Ed Wing and Weight Room.
- Phase 4A: Renovation of existing Gymnasium, Locker and Team Rooms.
- Phase 4B: Demolition of existing Auxiliary gym.

Phase Timelines

Design	June 16 th 2008 – June 12 th 2009
Phase 1	June 15 th , 2009 – June 25 th , 2010
Phase 2	June 9th 2010 – June 23rd 2011
Phase 2A	June 2 nd 2010 – July 28 th 2011
Phase 2B & 2C	June 30th 2010 - December 31st 2010
Phase 2D	January 6 th 2011 - June 27 th 2011
Phase 2E	January 3 rd 2011 – January 21 st 2011
Phase 2F	January 24 th 2011 - February 11 th 2011
Phase 2G	February 14 th 2011 - March 4 th 2011
Phase 2H	March 14 th 2011 - April 1 st 2011
Phase 2I & 2J	April 4 th 2011 – June 3 rd 2011
Phase 3	June 9th 2011 – December 30th 2011
Phase 4	July 7 th 2011 – April 27 th 2012
Phase 4A	May 24 th 2011 - September 28 th 2012
Phase 4B	April 30 th 2012 – June 29 th 2011

Overall, phased construction was easily the best choice for a project of this type. While working during school hours presents many challenges, phased construction allows for the careful planning of construction in order to manage the interaction between construction and everyday life. Thus far, construction has gone accordingly and the schedule has been met. As a result, normal school activities have gone uninterrupted while construction continues to be completed according to schedule. The detailed project schedule can be seen in APPENDIX E.



Analysis 1: Delivery Method Study

Problem Identification

The Separations Acts of 1913 dictates that all public education construction projects in Pennsylvania (among other states) be constructed using a Multiple Prime delivery method. On the Unionville High School Building Renovations and Additions project, however the project team did not feel comfortable using a multiple prime method and sought to employ a Single Prime delivery approach.

Research Goal

This analysis will outline both delivery methods: Multiple Prime and Single Prime. Each delivery method will be studied, outlined, and analyzed. One of the main goals of this analysis is to determine how the Unionville High School project team was able to bypass the Separations Act, why they chose to do this, and the benefits that a Single Prime delivery method has provided to the owner. In addition, both delivery methods will be compared to determine the best option for public education projects in Pennsylvania. Schedule and Cost impacts of each system will be highlighted to provide better insight regarding which of the two systems is superior.

Research Methods

- Research UHS project team's reason for using Single Prime
 - Interview the project team and the owner to understand the reason for using an alternative delivery method.
- Study current delivery method
 - Research other projects using a Single Prime delivery method
 - Projects with similar scopes as well as alternate scopes
- Research Multiple Prime delivery method
 - Research other projects of similar scopes that were delivered using Multiple Primes
 - Research/study The Pennsylvania Separations Act of 1913
- Compare/Contrast both methods
 - \circ $\;$ Determine positives and negatives of each system for this application $\;$
- Determine best system for this project
 - Select delivery method that provides the most quality to the owner and also allows for the most efficient completion of this project
 - Cost, Schedule, and Quality to the Owner



Owner Interview

The owner's representative, Rick Hostetler, was generous enough to take the time to provide me with in an interview regarding this very topic. As stated previously, the school district has past experience with public education construction projects. Rick explained that a multiple prime delivery method has caused issues on the projects that he has been a part of.

In order to receive the exception, Rick and the Unionville-Chadds Ford School District had to apply for a waiver in 2008 from the Pennsylvania Board of Education. The waiver application required sufficient information as to why the school district wanted to use a Single Prime delivery system as opposed to the Multiple Prime delivery system. Rick explained that the communication benefits offered by a Single Prime delivery method would aid the project and ultimately work more effectively for this specific project.

Coordination and collaboration using a multiple prime delivery method is far more difficult than when using a single prime. The main positive to using a single prime delivery method is the *single point of contact*. A single point of contact simplifies the communication process between the owner and the construction project team. Any question, request for information, or issue can be brought to one party who can then move forward to meet the request. With multiple prime contractors, communication becomes more difficult and information transparency is hard to keep.

Ultimately, Rick states in no uncertain terms a Single Prime delivery method has indeed been the right choice. Based on past experiences with a multiple prime system and the UHS' project results up to this point, a Single Prime delivery method has met all of UCFSD's expectation. In terms of logistics, quality, and cost, a Single Prime delivery method has provided the best value for projects.

(Hostetler, Rick)



Unionville High School Project - Use of a Single Prime Delivery Method

Due to the Separations Acts of 1913, all Pennsylvania public education construction projects exceeding \$4,000 are required to use a Multiple Prime delivery method. On the Unionville High School Building Renovations and Additions project, however, a Single Prime Delivery Method was used. An interview with Project Manager Brian Laub of Wohlsen Construction provided useful insight into this specific project. The reasoning for using a Single Prime Delivery method and how the UHS project team went about requesting and receiving the exemption is a product of many factors.

The Unionville-Chadds Ford School District was the driving force behind use of a Single Prime delivery method. With past public education construction project experience, the school district knew from the inception of the project that a Single Prime delivery method was superior to a Multiple Prime delivery method, for their specific situation at least. For this reason, the school district applied for and was granted a waiver from the Pennsylvania Department of Education. Past experience with projects using a Multiple Prime delivery method was the main reason that the district applied for the waiver, as it created numerous issues and even law suits for UCFSD.

A Single Prime delivery method has proved effective for the school district. With one contractor to contact (rather than several) communication is more organized and it is easier for the owner to relay information to the construction team. A major benefit of using a Single Prime delivery method instead of a Multiple Prime delivery method is that the owner does not need to hire a Construction Manager to manage the prime contractors. With only one prime contractor, all information is relayed to that contractor and from there it is relayed to the subcontractors. Without the need for a CM, project costs can be lowered and communication can be increased.

Ultimately, UHS feels as though applying for the waiver to use a Single Prime delivery method was the right decision. Experience with Multiple Prime helped to push them away from that method. As of this report, the project and the delivery method have both been a success. The interview with PM Brian Laub can be seen in detail in APPENDIX F. (Laub, Brian)



Single Prime Delivery Method Background Information

A Single Prime delivery method, also known as Design-Bid-Build, is a project delivery method with one Prime Contractor. Every trade is a separate entity, although each trade reports directly to the prime contractor. The owner for the prospective project uses in-house staff or hires an outside resource to develop the design for the project. Based on this design, competitive bidding is held between interested contractors and the bid is awarded to the lowest responsible and qualified applicant. Depending on the details of the contract, the Prime Contractor that is awarded with the project is free to select the subcontractors that they prefer.

Under this system, the owner has just one point of contact, meaning information can be more easily transferred to the construction project team. All subcontractors are direct subordinates of the prime contractor, and all information is relayed through that prime contractor. This delivery method also allows the owner to maintain contact with the project team through constant communication. An organizational chart for the Single Prime Delivery Method can be found in APPENDIX G.

Case Study - Kennett Square, PA

As a part of their study, the Allegheny Conference performed several case studies. This case study refers to the Kennett Consolidated School District located in Kennett Square, PA. In 2001, the Kennett Consolidated School District had two public education construction projects preparing to begin. For one of them, the district applied for a waiver to use a Single Prime delivery method. The other project was completed using the Pennsylvania mandated Multiple Prime delivery method.



With two projects underway simultaneously, each using different delivery methods, the school distract was able to really see which delivery method was more effective. The Single Prime project was to be additions and renovations to an existing high school while the other project was a new middle school. Overall, the district much preferred the Single Prime approach.

Several key reasons behind this preference are outlined below.

- Schedule Acceleration
 - The Single Prime project completed two months ahead of schedule
- Communication
 - Communication was superior on the Single Prime project than the communication on the Multiple Prime project due to improved dispute resolution and fewer change orders.
- Cost difference
 - The Single Prime project experienced savings of nearly \$300,000, while the multiple prime project came in over budget
- Higher Quality of Work
 - The Single Prime project was completed with work of a higher quality than that of the Multiple Prime project

This particular school district would choose to use Single Prime over Multiple Prime, given that the district had the choice. Increased quality, lower cost, schedule reduction, and communication are only some of the reasons that the Single Prime delivery method is preferred. Having one contractor in charge of the project proved to be more effective than spreading the work out between multiple prime contractors. The increased communication as a result of one prime contractor really benefits the project on the whole.



Multiple Prime Delivery Method Background Information

A delivery method gaining popularity in recent years, especially in the public sector, is the Multiple Prime Delivery Method. In this system, each construction subdivision is bid separately as opposed to all together to a lone prime contractor. Early on in the project's infancy, the owner hires a construction manager to oversee all construction practices throughout the project. Following the design phase, the resulting design documents will be handed over to the construction manager. At this point, the CM will produce specific bid packages for separate trades including structure, mechanical, electrical, and plumbing.

Each bid package is awarded to separate contractors, all of whom are on the same level of the organizational structure within the project team. These contractors are known as prime contractors and report directly to the owner under this system (as opposed to a Single Prime system, where the separate trades report to the lone prime contractor). Ideally, a Multiple Prime Delivery Method aims to produce a project faster than alternate delivery methods. An organizational chart for a Multiple Prime Delivery Method can be found in APPENDIX G.



Case Study

Like the Single Prime delivery method, the Allegheny Conference created a case study for a Multiple Prime Delivery Method for a Pennsylvania Public School. In this instance, the Troy Area School District reported that it had used exclusively a Multiple Prime delivery method for its construction projects. Based on their responses, several issues arose with this type of project delivery method. First, cost overruns were common. Each project experienced increased cost, at a minimum of 3 percent per project. Although this value does not seem overwhelming, on larger scale projects a 3 percent cost increase can create numerous issues. Another common issue was the volume of change orders. Change orders are timely and costly, meaning a large number of them can contribute to both cost and schedule increases, two huge issues in the construction industry. The districts final point against Multiple Prime systems is the increased stress; as a result of poor coordination, extra time needed to be allotted to the project to ensure better communication and coordination within the project team.


Pennsylvania Economy League - Review of The Pennsylvania Separations Act

My research on the debate between Multiple Prime and Single Prime delivery methods for Pennsylvania public school construction projects lead me to an extremely useful document developed by the Pennsylvania Economy League. Produced on November 8th 2007, the Pennsylvania Economy League produced a document titled "A Review of the Effects of the Pennsylvania Separations Act on School Districts" (The Allegheny Conference). This document will be referenced frequently, as the information therein is vitally important to my analysis and provides insight and information regarding this subject that I would otherwise be unable to attain.

Background and The Pennsylvania Separations Act of 1913

Still in effect today, the Pennsylvania Separations Act (PSA) of 1913 is legislation in place to dictate how contracts are structured for public construction projects. The PSA states that any public construction project exceeding \$4,000 is to bid and award separate contracts for the primary trades including heating, ventilation, electrical, and plumbing. A project with multiple prime contractors each holding separate contracts, such as this, is referred to as a Multiple Prime Delivery method. The PSA has been removed in some areas including boroughs, townships, and counties, though the act remains in place regarding Public Education Projects.

The Pennsylvania School code also contains requirements regarding construction to public education buildings. Specifically, section 7-751 states that any construction, maintenance, or repair work performed on education buildings costing in excess of \$10,000 requires separate contacts for each prime contractor (heating, ventilation, electrical, and plumbing) (The Allegheny Conference). The Mandate Waiver Program of the Education Empowerment Act was passed in 2000 and allowed school districts to apply to the Pennsylvania Department of Education (PDE) for a waiver to bypass certain Pennsylvania School Code requirements. As this mandate grants waivers pertaining only to the Pennsylvania School Code, PSA requirements demanding use of a Multiple Prime Delivery method still need to be met.



In 2005, Thomas Stevenson (Republican Representative, Allegheny) sponsored House Bill 2100 which would allow certain entities to select which type of project delivery method to use for construction project (The Allegheny Conference); unfortunately, this bill did not make it out of Committee. Another attempt to get around the PSA legislation came later in 2005. Joseph Petrarca (Democrat, Armstrong/Westmoreland) sponsored House Resolution No. 609. This piece of legislation requested information regarding cost overruns on the Peterson Events Center project located at the University of Pittsburgh. The University of Pittsburgh is a public entity and as such must abide by the requirements of the Pennsylvania Separations Act, meaning that multiple prime contractors and separate contracts must be used. The project reportedly "spent \$28.5 in contract amendments, change orders, and claims settlements, resulting in a 34 percent (cost) overrun, a rate construction experts say is two to four times higher than normal." (The Allegheny Conference).



Education Empowerment Act - Section 751 Mandate Waiver Program

The report by the Allegheny Conference referenced 'Section 751 Mandate Waivers' when referring to alternative delivery methods for public school projects in Pennsylvania. As this piece of legislation relates directly to this Delivery Method discussion, research into the Mandate Waiver program was performed. The Education Empowerment Act was developed in May of 2000. This act, passed by the Pennsylvania General Assembly, aimed to help school districts with low test performance or a history of financial distress (Pennsylvania Department of Education). Every school district (501 districts) in Pennsylvania was eligible to receive aid from the Education Empowerment Act.

Pennsylvania School Code section 751 states that every public school district in the state must award bids to separate contractors for each primary trade, including electrical, ventilation, plumbing, etc. The Pennsylvania Department of Education Mandate Waiver program was established in 2000 and expanded in 2001. Specific to this analysis is Pennsylvania Department of Education Waiver Application Codes K, Construction and KS, Single Prime. These categories were created specifically to allow any of the 501 school districts in Pennsylvania to apply for an alternate to the Multiple Prime Delivery Method. This program was designed to accommodate all school districts in Pennsylvania regarding construction projects and how they are performed. A school districts school board may applied for a waiver in an attempt to "improve its instructional program or operate in a more effective, efficient or economical manner" (Pennsylvania Department of Education).



From 2000 to 2003, the program received a high level of interest. Many school districts applied for waivers during this time period, based on the Pennsylvania Department of Education's report data. The Pennsylvania Department of Education stopped accepting and processing new waiver requests in May of 2003, however, which obviously resulted in decreased inquiries from Pennsylvania School Districts. Based on data collected by the Mandate Waiver Annual Report, 61 schools applied for the Code KSP waiver between the years 2007 and 2009. However, Application Code K, Construction contained the Single-Prime waiver up until December of 2007.

From the program's inception in 2000 until application code KSP was created, 263 Code K – Construction waivers were requested. Although the Single-Prime exception was contained within Code K, there is not sufficient data to determine which of the 263 applications were made specifically for the Single-Prime exception. Of the 23 Code KSP requests made in 2009, 6 were withdrawn, 15 were approved, and just 2 were denied. Table 1 outlines the waiver application data for Code K and Code KSP from 2000 to 2009.

Table 1: Waiver Application Requests by Code (Pennsylvania Department of Education

Code	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	Total
К	2	62	85	28	23	17	21	25	13	24	300
KSP	0	0	0	0	0	0	0	1	37	23	61

Despite the program's success and the interest in mandate waivers, the program ended on June 30th 2010 when the Education Empowerment Act expired. At this point, the Pennsylvania Department of Education no longer has the jurisdiction to grant waiver requests. The program remains closed, and there are no plans to reinstate the program or develop another similar program.



Multiple Prime Delivery System Survey

As mentioned earlier, the Allegheny Conference produced a valuable document outlining the Pennsylvania Separations Act and how exactly it impacted public education construction projects in Pennsylvania. As a part of this document, a survey regarding the use of the Multiple Prime Delivery method yielded valuable and informative results.

Generally speaking, projects using multiple prime contractors caused problems for the school and/or owner in question. The disconnect between the parties leads to a breakdown in communication, which can snowball in to a myriad of other issues. Several school districts reported increased change orders due to the Multiple Prime Delivery Method, as well as an increase in the duration of the schedule and cost overruns.

Downfalls of Multiple Prime Delivery Method

The above survey shed light on several major issues with a Multiple Prime Delivery method for Pennsylvania public education projects. Some of the major issues are:

- Communication breakdown
 - Due to the increased number of contractors, communication between the contractors often insufficient, meaning that construction and facility managers must spend added time to ensure proper communication between the various parties.
- Multiple Parties Involved
 - With several contractors, any issue or change within the project must be relayed to multiple parties rather than just one; keeping in contact with each prime contractor at all times is difficult.
- Increased Error
 - Each contractor must have its own set of drawings, meaning the increased possibility of errors.
 Should a change occur that one prime contractor is unaware of, work could be put in to place that has actually been changed.
- Schedule Delays
 - With multiple prime contractors, the process of completing a change order must go through multiple contractors rather than one. Schedule delays can increase due to the lengthy process needed to complete a change order.
- Poor Coordination
 - Each contractor is responsible to complete its work on time and on budget. Should work be performed by one contractor that interferes with another contractor, there exists the possibility of repeated work.



Single Prime Delivery Method Waiver Survey

The Allegheny Conference on Community Development created a second extremely useful survey regarding this very topic; the survey was developed to determine which school districts attempted to receive permission to use a Single Prime Delivery method and the results of their efforts. The results of the survey are as follows, including a graphic developed by the Allegheny Conference:

Survey Results (figure 9)

- 61 out of 501 school districts in Pennsylvania were granted waivers to use a Single Prime Delivery method
 - Forty-two (42) of these Sixty-one (61) school districts constructed projects using a Single Prime delivery method
 - Roughly 70% of the 61 school districts estimated savings due to the use of Single Prime
- Nineteen (19) school districts applied for the waiver, were granted the wavier, but did not complete projects using a Single Prime delivery method
- Four (4) school districts applied for the waiver but were denied.
- ✤ 436 school districts did not apply for the waiver





Figure 9: School District Survey, Allegheny Conference (The Allegheny Conference)

Pennsylvania Economy League Study Conclusions

Ultimately, the school districts approached for this study preferred a Single Prime delivery method to a Multiple Prime delivery method. The separation of work between multiple prime contracts caused many issues including schedule delays, cost increases, poor communication, and poor coordination. The ability to apply for a waiver in order to bypass the Separations Act Legislation proved useful for all those granted the exception, with savings on total project costs ranging from \$8,000 to \$2,500,000 (The Allegheny Conference).



Multiple Prime – Pros and Cons

The Multiple Prime Delivery Method is a project delivery system that has individual bid packages awarded to multiple prime contractors. The owner will frequently hire a Construction Manager to oversee the project, although the prime contractors are contracted directly to the owner. Pros and Cons for a Multiple Prime Delivery Method are outlined below:

Pros

- Direct Contact With owner
 - Contractors who are selected as Prime Contractors like the opportunity to work directly with the owner
- Increased Expertise
 - Each bid is trade specific, which can result in a Contractor with a higher competency in each area
 - Improved Work Ethic
- Economy of Scale
- No General Contractor
 - Without a GC, or Single Prime Contractor, the GC markup for each subcontract is removed
 - Fewer subcontracts, lowering overhead & profit costs
- Economy of Scale
- Awarding Bids Based on Sequencing
 - o Specific contracts can be awarded only when that specific trade is beginning work

Cons

- Difficult on Complex Projects
 - o Not an optimal delivery system for complex or specialized projects
- Increased Number of Contractors
 - o The increase in prime contractors creates added stress on the owner/administration
 - Increased number of contracts increases cost
- No Definitive Price
- Scope Gap Issues
 - The CM creates bid packages, creating the possibility of scope gaps
 - Scope changes can create change orders
- Increased Error
 - Many sets of drawings, increased chance of error
- Change Orders
 - Frequent change orders can occur as a result of scope gaps
- Poor Coordination
 - Communication can break down, as each trade is contracted specifically to the owner and only worried about its specific tasks
- Cost Increase
 - A high number of change orders can inflate the project's price
 - Each contractor must have its own bond
- Schedule Increase
 - o Coordination issues, change orders, and scope gap can all cause schedule delays



Single Prime – Pros and Cons

With only one prime contractor, a Single Prime Delivery Method offers one point of contact to the owner. Instead of prime contractors bidding on specific bid packages, all trades are bid as subcontracts to the lone prime contractor. Pros and Cons for a Single Prime Delivery Method are outlined below:

Pros

- One Point of Contact for Owner
 - The Owner has just one point of contact, the General Contractor
 - CM will act in the best interest of the Owner
- Competitive Bids
 - Price can decrease as a result of competitive bidding
- Easily Understood
 - o Common delivery method, most contractors have experience with this delivery method
- Better Coordination
 - o Subcontractors report to GC, who reports to Owner
- Complete Design
 - \circ $\;$ The project is designed fully prior to the start of construction

Cons

- No Design Input from Contractors
 - The GC is hired and subcontracts are purchased following design, meaning little to no contractor input on design
- Change Orders
 - Frequent change orders can occur as a result of scope gaps
- Contractors May Take Advantage of the Competitive Process
 - o GC may select cheapest subcontractor, even if they are not of necessary quality/skill
 - Subcontractors may produce lower quality work in order to save on costs
 - Cheaper is better thought process
- Delay Claims
 - o Delays can create claims, disputes, and other issues between subcontractors
- Redesign Disputes
 - o Guidelines must clearly state who is responsible for
- Design Coordination
 - Design is developed by several separate parties, which may make the design process difficult to coordinate



Conclusion and Research Result

After compiling multiple sources of information as a result of research regarding Public Education construction projects in Pennsylvania, it is my opinion that a *Single Prime Delivery Method is superior* to a Multiple Prime Delivery Method. This type of project delivery system is well known by most contractors and easy to perform. In this case, Unionville-Chadds Ford School District has had past experience with Multiple Prime projects that created issues. Disputes and claims have pushed the school district away from this approach and towards a Single Prime Delivery Method.

With a Single Prime Delivery Method, the owner has just one point of contact. With only one prime contractor, the owner can be more confident that the work will be done as desired; the owner will relay desires to the General Contractor, who will then relay that same information to the subcontractors. The GC will most likely act in the best interest of the owner, rather than acting in their own best interest which may occur with a Multiple Prime Delivery Method.

Based on surveys and responses from those who have had experience with both systems, the majority of school districts experienced *cost savings, schedule reduction, and even increased quality* when using a Single Prime Delivery Method. As of this report, the Unionville High School Project is project to finish a full 3 months ahead of the initial schedule.

Unfortunately, the waiver program in Pennsylvania has expired. It is my opinion that the legislation requiring a Multiple Prime Delivery Method for public education construction projects in Pennsylvania needs to be amended. I believe that each school district, or owner, should be free to determine which Delivery Method works best for their project. It is in the best interest of each school to perform the work based on *what will benefit their educational initiative most*. Although research for this analysis showed that a Single Prime Delivery Method was favored to a Multiple Prime Delivery Method, there are certainly owners who would prefer the latter for their specific project.



Analysis 2: 4D Safety and Phase Plan (Critical Industry Issue)

Problem Identification

Unionville High School is an existing building undergoing new additions as well as renovations, serving as home to both the Unionville-Chadds Ford School District Administrative Offices as well as Unionville High School. Construction is broken down in to four main phases and a total of 16 sub phases. The building is scheduled to remain in use throughout the entirety project, meaning that all staff and students will remain in the building during the project's construction. Although standard safety procedures were taken as part of the initial project logistics, a formal safety plan designed specifically for each phase could help to increase safety and decrease the likelihood of accidents.

Research Goal

The UHS project did not use Building Information Modeling in any fashion. In order to develop a safety plan, an adapted form of 4D Phase Planning will be implemented. A basic massing model of the building will be developed and individual models will be created for each phase of the project, showing which areas of the building are under construction during specific time periods. Using these models, a comprehensive safety plan will be developed for each phase; hazardous areas of the building, exits leading to ongoing construction, and streets and parking areas in use during construction will be highlighted and the information will be made available for the use of anyone who may be using the building.

This safety plan will be accessible by anyone via a specially developed website, which will be interactive and will allow anyone to view the safety plan and model for any specific phase of construction. Several kiosks will be placed throughout the school, in neutral locations, to allow quick access to this safety information. The safety planning website will also be available to anyone via a personal computer.



Research Methods

- Outline current structure of construction phases
- Conduct research on similar projects
 - Study similarly phased educational projects, highlight potential dangers
- Develop basic 3D Model of the entire building
- Determine hazardous areas for individual phases
 - Study each phase to pinpoint hazardous areas as well as safe routes to avoid such areas
- Develop safety floor plan/diagram for each phase
- Create individual model for each phase
 - A basic model will show each phase, where construction is occurring, and hazardous areas related to that phase
- Study feasibility of Safety Plan
 - Cost, Implementation, and Value to the Owner



Background Information

The BIM Execution Plan developed by a team at the Pennsylvania State University defines 4D Phase planning as a process using a 3D BIM (Building Information Modeling) model linked with time or the project schedule. This model, known as a 4D model, can be used to effectively plan the phased schedule of a construction project, namely for projects undergoing renovations and additions (Computer Integrated Construction Research Group). This tool is a useful application of BIM and can help an owner and project team visualize how the project is going to be completed.

Generally speaking, 4D BIM models are used to visualize the construction of a project. The main focus is on the actual construction of the project and the different areas of the building that must be completed. In this case, a 4D model is to be developed to provide a comprehensive, phase by phase safety plan. Due to the large number of phases, construction areas and safety hazards are shifting continuously throughout the project. A 4D model will help to visualize which areas of the building are under construction during each phase, which areas of the building are hazardous during each phase, and any other pertinent safety information regarding each specific phase.

For this analysis, the models to be developed will be massing models only. Specific knowledge of materials and finishes in each space is not necessarily essential. Ideally, Revit would be used but due to time constraints, Revit was not used for this study. An interactive website will be developed to illustrate the kiosks that would be used within the school. This BIM application offers numerous benefits to a project and its project team. For the Unionville High School building, the main aim of the 4D Phase and Safety Plan will be to:

- Provide a better understanding of the project schedule
- Provide a visual description of the phased schedule to all building inhabitants
- Provided phasing plans describing work to be done per phase and adjacent occupied areas
- Highlight potentially hazardous areas for each phase
- Identify any space, workspace, or phasing issues
- Provide a better understanding of parking and other site logistics for each phase



UHS Project Phasing Information

The Unionville High School project consists of both new additions and renovations to the existing building. During construction, all students and staff are to remain in the building during the school year. For this reason, the construction team decided that phasing the schedule was the most efficient way to construct the project.

Begging in 2009, the project consists of four main phases and has a total of 16 sub phases. The schedule and work breakdown for each phase is listed below.

Phase Descriptions

- Phase 1: Construction of the New 3 story addition, set to house the Unionville-Chadds Ford School District Administrative Offices, Classrooms, and Science labs.
- Phase 2: Construction of the New Auditorium, Art rooms, and Family and Consumer Classrooms.
- Phase 2A: Renovation of existing Large Group Instruction, Library, Faculty Restrooms, Cafeteria, and Kitchen.
- Phase 2B & 2C: Renovation of existing District Administrative Offices into High School Offices, Science Labs, and Classrooms.
- Phase 2D: Renovation of existing High School Offices, Music Area, and Faculty Dining.
- Phase 2E: Renovation of existing Science Labs and Classrooms.
- Phase 2F: Renovation of existing Classrooms
- Phase 2G: Renovation of the existing Computer Applications Labs and Classrooms.
- Phase 2H, 2I, 2J: Renovation of existing Classrooms.
- **Phase 3**: Renovation of existing Auditorium into Choral Room and Tech Ed Classrooms.
- Phase 4: Demolition of existing Classroom and Tech Ed Wing and Weight Room.
- Phase 4A: Renovation of existing Gymnasium, Locker and Team Rooms.
- Phase 4B: Demolition of existing Auxiliary gym.

Phase Timelines

Phase 1	June 15 th , 2009 – June 25 th , 2010
Phase 2	June 9th 2010 - June 23rd 2011
Phase 2A	June 2 nd 2010 – July 28 th 2010
Phase 2B & 2C	June 30 th 2010 - December 31 st 2010
Phase 2D	January 6 th 2011 – June 27 th 2011
Phase 2E	January 3 rd 2011 – January 21 st 2011
Phase 2F	January 24 th 2011 – February 11 th 2011
Phase 2G	February 14 th 2011 – March 4 th 2011
Phase 2H	March 14 th 2011 – April 1 st 2011
Phase 2I & 2J	April 4 th 2011 – June 3 rd 2011
Phase 3	June 9th 2011 - December 30th 2011
Phase 4	July 7 th 2011 – April 27 th 2012
Phase 4A	May 24 th 2011 – September 28 th 2012
Phase 4B	April 30th 2012 – June 29th 2012



Case Study – American School & University Magazine – Managing a School Construction Project

In 2002, The American School and University Magazine developed a document highlighting construction of educational facilities, with a specific focus on expansion of existing buildings. Many educational projects consist of additions and renovations, which can create a distraction and even safety hazards to building inhabitants. Demolition, a necessary step in a construction project involving and existing building, can be a major factor for any educational project.

In order to ensure safety during demolition, careful steps must be taken. First, swing space of machinery must be studied to determine if there is enough building space to perform demolition while an adjacent space is occupied. Providing temporary space during demotion for displaced building inhabitants will add cost and create discomfort for those who are displaced.

A key component of phasing a project of this type is to ensure that there is proper circulation within the building despite ongoing construction. When constructing an addition on a project, it is common practice to complete the addition portion of the project first. Creating this addition first can reduce rental costs, as building inhabitants who are displaced in future phases can then occupy the newly constructed addition.

Schedules can also vary greatly based on phased construction. Key academic schedule dates, like the first day of class and the final day of the school year, often drive the construction schedule. Other factors include staff and student holidays, providing opportunities for construction when the building is not occupied. For this reason, every educational construction project schedules a specific portion of the work during the summer when school is not currently in session. Another factor that may impact a project of this type is weather. Depending on the work being done, weather can create unsafe conditions. It is important to ensure that no students or staff be affected by unsafe conditions created due to adverse weather.



After scheduling parameters have been met, the actual construction of the project must be determined. Careful planning must occur to ensure that construction activities are safely disconnected from occupied areas of the building. Often times, educational projects are broken into different phases. The phases take numerous variables under consideration, including available utilities, temporary construction protection, signage and the age level of building occupants, air quality within the building, and disposal of construction waste. Each of these factors can pose dangers to building in habitants if not taken under careful consideration. (Rush)



Applications for the UHS project

Often times in today's construction industry a 3D Model is used for detecting clashes between multiple trades, such as MEP and Structure; this is not the case for the Unionville High School project. The original project used no BIM whatsoever, so there is no existing model of the project. Instead, this application will see a 3D model used more as a visual tool. As mentioned previously, ideally, Revit would be used for this application. With Revit, the model can be linked to the schedule and a linked visual can be created showing which areas are being constructed at which time. For this analysis, Google SketchUp was used to develop a simple 3D massing model. The 3D model will be linked to floor plans and the schedule to provide important information regarding the construction process.

Initially, a model of the entire finished building will be constructed. From this, a model for each phase will be extracted. From the uses described within the Penn State BIM Execution Planning guide, the use most closely related to this application is "Space Management and Tracking". By combining the 3D model with site and floors plans analyzed for hazards and dangerous areas, all information regarding safety during the construction process. Following completion, an integrated website will be developed in order to provide access to all information to all building inhabitants.

Using this interactive website, anyone entering the building will have construction information at their fingertips. Several kiosks will be implemented in the building at central locations. Ultimately, the new 4D Safety Plan will provide added value to the owner at little cost by increasing the availability of information regarding the construction process to those utilizing the building.

Note: Due to the time available to complete this analysis, only a sketch up model was used. Provided there was more time available, a Revit model could be constructed, and linked with the schedule to provide a true 4D model for the owner.



Hazardous Areas within each Phase

Each of the 16 phases during the project will be adjacent to a portion of the building that is still in use. The hazardous areas during each phase will be outlined, showing exactly where the work for that phase terminates, thee areas in which contractors will be parking and using vehicles, and any other areas that may present safety risks during that phase. This will provide a visual aid for building inhabitants, allowing them to see which areas of the school are being worked on at which times.

During construction, the existing building will remain in use. This means that areas within the existing building that are adjacent to ongoing construction are at an elevated safety risk do to the high volume of building inhabitants. Each of these areas within each phase will be highlighted on a 3D model, and floor plan. Finally, the front vehicle entrance of the school will always be considered a hazardous area. With just one entrance to the site, this area will be in use constantly due to normal use by staff and students, as well as contractors, delivery trucks, and other construction vehicles.

Ultimately, this phased safety plan will highlight hazardous areas for building occupants. The information within the safety plan will allow occupants to see which areas of the building are under construction at which times, providing a greater knowledge of the construction process. With constant use of the building, it is paramount that no one, contractors and building occupants alike, is put at risk of injury during the project. For this analysis, a phasing and safety plan for Area D will be developed. Due to time constraints, developing the plan for all 16 sub phases was not feasible.



Phase 1

Building Area Construction Dates School in Session? D June 16th 2009 – June 25th 2010 Yes

Phase one is the construction of a brand new wing of the building, located at the southernmost end of the building, and will be the main example of how BIM would be used to implement phase/transition and safety planning on the Unionville High School Project. This wing will be added to the existing building, and as such will create junctions between existing building that is still in use and adjacent construction areas. These areas are located at several points during the phase:

- Connection between new wing (Area D) and existing building (Area E)
- Stair tower at edge of Area E
- Rear Parking Lot

The connection between the two areas will pose the highest risk. The existing building is scheduled to remain in use throughout construction and as such, this area will see a high volume of students and staff during the phase. Next is the stair tower exit door; based on the existing building, school inhabitants are used to using this exit doorway. With construction going on in the location of the rear parking lot, a crane will be on site and material laydown will be occurring constantly. Keeping all building inhabitants out of these areas is of utmost importance in order to ensure project and civilian safety.

The diagrams on the next several pages show information and resources that will be available through the interactive 4D Phase and Safety plan.



Figure 10: Phase 1 Building Breakdown

Figure 10 shows the entire building, highlighting which areas of the building are under construction and which areas are to remain in used during this phase. As you can see, the red area highlights all of Area D, which will be a new wing added to the existing building. During Phase 1, the entire existing building is to remain in use, shown here in blue. This means that a main area of concern is the intersection between area E and area D. Also shown here are parking areas; with students and staff parking on campus every day, it is important to keep construction vehicles and pedestrian vehicles separated. The green areas show parking lots where students and staff can park, while the orange lot shows contractor parking.



Figure 11: Phase 1 - No-Access Areas and Alternate Routes

In figure 11, the exterior of the building is highlighted. The red area shows the area of the project site that will be in use during the construction of Phase 1. Both Area D as well as the rear parking lot will be highly congested with construction workers and vehicles, and as such access is restricted to all building inhabitants. The light blue areas show exterior pathways that can be used as alternatives to those closed due to construction. By providing information regarding alternate routes, building inhabitants can avoid accidental contact with the construction team.





Under Construction



Figure 12: Transition Plan

Figure 12 shows the transition between Phases 1 and 2. Phase 2, which includes work being done in area E (the blue region), is set to begin shortly after the completion of Phase 1 (the red region). For this reason, a seamless transition between phases is extremely important. The first step will be to move all UCFSD Administrative personnel from the existing administrative offices (located in area E) into the new offices in area D. Next, any teachers set to move into a new classroom in area D will be moved. Moving the faculty and staff into new spaces efficiently is extremely important, as each phase is dependent on the phase before it.



Cost and Implementation

BIM software is no small investment, especially if the company in question plans to make BIM a focus in the future. Considerable training must occur in order to provide someone with enough knowledge to develop an effective, accurate BIM model. Additionally, the time needed to develop a phasing or safety plan of this size would be considerable. The cost and time associated beginning a BIM initiative within a company is certainly a major factor.

While no BIM was implemented on the project originally, I believe that integrating BIM into the project would be rather simple. Provided all parties involved have the software and knowledge available to produce BIM models, this application could easily be applied to the Unionville High School Building project. That being said, assuming that all parties involved do have the necessary requirements to implement BIM is a big step.

All things considered, I believe that it is well worth the time, money, and effort for any company involved in the construction industry to start using BIM software. The applications available using this software are vast and the value and even cost savings available are numerous.

Conclusions

Provided that the members of the construction team are able to obtain the software and training necessary to effectively use BIM software, I believe that **this application would be beneficial if implemented**. On this project, the use of BIM to develop a 4D Phase plan which in turn can be developed into a safety plan can provide the owner with added value. On any construction project, especially a school, safety of building occupants is paramount. With student, staff, parents, and many other people frequenting the building constantly, keeping building occupants informed about the goings on throughout the construction project can lead to a lower likelihood of project related accidents and potentially cost savings. The website developed to showcase the proposed plan can be viewed from my CPEP website or directly at [http://www.engr.psu.edu/ae/thesis/portfolios/2012/MSB5153/4D%20Phasing%20and%20Safety%20Plan.html].



Analysis 3: Sustainability – On Site Renewable Energy Source

Problem Identification

The Unionville High School Building consists of new additions as well as renovations, both of which have been designed with state of the art technologies and top of the line finishes. The project has been designed with the goal of achieving LEED silver under the 2007 system; missing in the design, however, is the application of on-site renewable energy. Renewable energy is an area of construction growing in popularity that provides numerous benefits and would be a welcome addition to any project. Implementing a renewable energy system on this project can create savings and help the project and the school district to "go green".

Research Goal

This study will aim to identify which system, Wind or Solar, is the most feasible option for the Unionville High School Building. Incorporating a renewable energy system on the project can not only benefit the owner in the form of cost savings and may also help to improve the projects LEED rating. Each system will be analyzed to determine which of the two is a more appropriate system for this public education application. A system will be selected, designed, and analyzed to determine the constructability of the system. Finally, and a lifecycle cost calculation will be performed to show exactly how this addition would impact the project financially.

Research Methods

- Research Solar and Wind Energy systems
- Check for case studies involving similar solar and wind energy applications
 - **O** Research similar projects that have implemented this technology
- Research financial aid
- Determine which system to use and develop design for the proposed system
- Study any potential changes to structural system
- Update structural system if necessary
- Study feasibility of renewable energy system
 - **O** Cost, Schedule impact, and Constructability



Renewable Energy Background Information

As we all know, today's society is extremely dependent on fossil fuels to produce electricity. In recent years, however, alternative energy sources have become more efficient and have started to relieve some of the stress on fossil fuels. Some of the more prevalent sources of renewable energy include hydropower, biomass, biofuel, geothermal energy, solar energy, and wind energy. The latter two, solar and wind energy will be investigated during this study. As designed, the Unionville High School Building project did not incorporate any renewable energy. Background information, research, and calculations will be used to determine which of the two systems is more appropriate for the UHS project. Once completed, the new UHS building will remain in use for years to come which in turn suggests that there will be ample time to allow for a renewable energy system to pay itself off and even produce a profit.

Photovoltaic Solar Panels

Renewable energy sources are increasing in efficiency and popularity. While many systems remain highly inefficient, the progress made in recent years has been noticeable. Photovoltaic panels are one of the most popular forms of renewable energy available today. Each panel is made up of a collection of many smaller photovoltaic cells, which can range from a few millimeters to a few inches across. On average, photovoltaic solar panels covert roughly 15 percent of the energy retrieved through sunlight into usable electricity (PVPower). These panels are then grouped into arrays, which can be located on the earth's surface or on top of buildings or other structures.

PV arrays consist not only of these solar panels, but also of electrical connections, structural connections, and batteries that store the energy produced by the panels. There are two main types of systems in terms of electricity production, a system tied into the electrical grid (Grid tied and a system dedicated solely to one specific building or a specific portion of the building (Off grid). For the UHS project, a grid tied system would be more appropriate as the school has been in operation for years and is already tied into the electrical grid.



A photovoltaic panel can be one of three primary panel types: Monocrystalline, Polycrystalline, and Thin Film (Amorphous) (PVPower). Monocrystalline panels (figure 13) are made using the



Figure 13: Monocrystalline Solar Panel Image: Courtesy of Atlantech Solar

oldest form of solar cells, which are produced using pieces cut from a single crystal of silicon. Visually, the panels will have a smooth, flat finish similar to a piece of glass. As these panels produce best conversion efficiency of photovoltaic cells today and are the most

expensive panel type.

The second type of photovoltaic panel, Polycrystalline (figure 14), is cut from more than one

crystal of silicon. As a result of the cells coming from pieces of multiple crystals, the finish will appear more like a shattered piece of glass. Although not as efficient as Monocrystalline panels, Polycrystalline panels are the most common panel type. As the efficiency is lower, the cost is also lower than the first panel type.



Figure 14: Polycrystalline Solar Panel Image Courtesy of Atlantech Solar



Figure 15: Thin Film (Amorphous) Solar Panel Image Courtesy of Atlantech Solar

Finally, the third main type of solar panel is Thin Film (figure 15), or Amorphous Silicon. This type of panel is flexible and thinner than the first two types of panel. A thin film of amorphous silicon (meaning non crystalline) is installed over top of a preselected surface, which can be either rigid or flexible. Of the three, Thin Film panels have both the lowest

costs as well as the lowest efficiency. One benefit to this type of panel, however, is that they are not hindered by shading like the other two types. Unfortunately, this type of panel is known to lose power output following installation, especially early on in the panel's life.



Wind Power

Another free source of renewable energy exists in wind power. The wind power industry as we know it began in the late 1970's. In fact, wind energy is one of the world's fastest growing renewable energy sources. As of this report, the United States tops the list of countries producing the most wind generated electricity. Like Solar Power, Wind Power has become more efficient and more affordable in recent history as a result of government incentive programs. A New York Times article from January 27th 2012 states that by the year 2030, the United States will produce up to 20% of all its electricity using wind generated power ("Wind Power").

Caused by heat differences on the earth's surface, wind is a constant and free source of energy. Wind power is created by harvesting the energy produced by wind turbines. Wind turbines can range from hundreds of feet tall to just several feet. There are two main types of wind turbines, vertical axis and horizontal axis. Furthermore, there are three subtypes of vertical axis wind turbines, Darrieus Wind Turbine VAWT (vertical axis wind turbine) and Savonius VAWT. A *Darrieus wind turbine* (figure 16) has a vertical axis and spoke like vertical blades. The principle behind harvesting wind using this type of turbine is *lift*; as wind passes through the turbine, the blades create lift which in turn rotates the turbine. Sometimes referred to as 'eggbeater' turbines because of their appearance, Darrieus turbines provide high efficiency but are not extremely reliable; due to the design, the vertical shaft undergoes large amounts of stress during operation. Another downfall to this type of design is the fact that an external source is needed to provide initial rotation (Meyers, C. Bracken.). Several subtypes of this turbine type exist; the Gorlov Helical wind turbine (figure 17) and Giromill Darrieus wind turbine (figure 18).



Figure 16: Darrieus Wind Turbine Image Courtesy of Winddose.com



Figure 17: Gorlov Helical Wind Turbine Image Courtesy of WindDose.com



Figure 18: Giromill Wind Turbine Image Courtesy of Winddose.com



The second type of vertical axis wind turbine is the *Savonius wind turbine* (figure 19). Unlike the Darrieus wind turbine, Savonius wind turbines are a drag-type turbine. Rather than using blade

like vertical members, scoop like members are mounted on a vertical shaft and used to catch wind. Although they produce a lower efficiency than a Darrieus turbine, Savonius turbines are better in areas experiencing turbulent wind. This type of turbine can generate electricity even in the strongest of winds without sustaining considerable damaged and are a quieter alternative to Darrieus turbines.



Figure 19: Savonius Wind Turbine Image Courtesy of TheGreenTechnologyBlog.com

In addition to vertical axis wind turbines, horizontal wind turbines are also available. This



Figure 20: Horizontal Axis Wind Turbine Image Courtesy of Centurion Energy

turbine style is the turbine that most people associate with wind energy, consisting of a tall vertical shaft with a smaller vertical axis that is connected to the propeller attached at the top (figure 20). Because the electrical generator is attached to the propeller, this type of turbine must be pointed in the direction of the wind. Smaller horizontal axis turbines use a wind vane to determine the direction and point the turbine in the correct direction, while larger turbines use a sensor to achieve the correct position.



Financial Assistance

A large draw to incorporating a Photovoltaic system on a new project in recent years has been the financial aid provided by the government. Part of the American Recovery and Reinvestment Act, the Tax Incentives Assistance Project (TIAP), states that the federal government will provide a credit for up to 30% of the entire cost of the Photovoltaic System as a result of The Business Energy Investment Tax Credit (ITC) (IRS-1). Unfortunately, incentives in the state of Pennsylvania have diminished in the past several years. That being said, the program has not completely shut down and may return upon the government's receiving additional funding. Funding is provided based on when the system is completely installed and in place, ready for use. This means that even if the system installation begins when there are no incentives in place, the program could be providing financial aid again as the system is completed.

A government rebate was also available recently for small businesses looking to implement a Photovoltaic system. For the first 10kW, a rebate of \$2.25 per watt is available. After 10kW, the next 90kW are valued at \$2 per watt and the following 100kW receives \$1.75 per watt. Another incentive program, the Pennsylvania Alternative Energy Credit program, provides incentive based on the amount of electricity produced. The Pennsylvania Alternative Energy Portfolio Standard (AEPS) requires that a certain percentage of electricity sold to customers in Pennsylvania be produced using alternative energy sources ("Pennsylvania AEPS Alternative Energy Credit Program"). For each 1000kWh of electricity, an Alternative Energy Credit is created which can be sold at a value of \$325.00 (as of 2009/2010).

In Pennsylvania, the Solar Energy program dictates that "all or a portion of the construction work associated with the project may be subject to the Pennsylvania Prevailing Wage Act" (Pennsylvania Department of Community & Economic Development, 5). This means that some or all of the work must be done by union workers who are to be paid a prevailing hourly wage. Due to the higher rate of labor, installation costs for PV systems can increase significantly.



Like Solar Power, Wind Power has also decreased in cost in recent years. Thanks to decreased startup costs and government incentives, this renewable energy resource has become both more efficient and more affordable. The 2009 American Recovery and Reinvestment Act also provides a substantial financial incentive for new wind power systems. The Business Energy Investment Tax Credit (ITC) provides a 30% tax credit for new small wind turbine systems. This tax credit includes all expenditures and has no maximum monetary value, although the credit is only available for systems up to 100kW in size (IRS-1).

Another incentive available for wind energy systems is a rebate based on the electricity produced. The Renewable Electricity Production Tax Credit (PTC) is available for a multitude of alternative electricity production systems. For any wind power system completely installed and in service prior to December 31st 2012, \$0.022 (2.2 cents) can be earned per kilowatt-hour of electricity produced. This credit may be earned for up to 10 years following the systems inservice start date and has no limit to the amount of money that can be earned. That being said, if any other federal tax incentives are used by a project, the kWh credit value may be reduced (IRS-2).

Unfortunately, because the school is not a 'for-profit' entity, these federal incentives are unavailable for this project. There is, however, another way to take advantage of these financial incentives. A Power Purchase Agreement can be used to purchase energy at a reduced cost. Basically, the non-profit organization (the school district) will allow a third-party to procure, install, and operate a renewable energy system on its premises. In this case, Unionville High School and the Unionville-Chadds Ford School District would contract the system to a third party, who would completely own the system. This third party would incur all installation and equipment costs in return for the available space to locate the PV array or wind energy system. Once complete, UHS would purchase solar electricity from the third party at a reduced cost. While the incentives would not directly save the school money, the district would incur savings by purchasing solar electricity at a reduced cost. (National Renewable Energy Laboratory)



Solar Case Study 1 - West Sonoma County Union High School District, California

SunPower performed a case study on a project with a similar scope to that of UHS. The West Sonoma County Union High School District aimed to reduce energy cost and save money as a result of budget costs. Their solution was the implementation of a photovoltaic array renewable energy system, which would address both of their goals. (West Sonoma County Union High School District Goes Solar for General Fund Relief)

RGS Energy was awarded the contract from the school district, which included array installations on three high schools. Once completed, the three high schools had systems totaling a combined size of 834kW. The system is estimated to provide around 75% of the high school's energy needs and over the life of the system, the three high schools will save a total greater than \$9 million. (SunPower Corp)



Solar Case Study 2 - Milpitas Unified School District, California

Another case study, performed by Chevron, highlights another similar application. Though a larger application, this system is still comparable to the system that would be installed at UHS. Milpitas Unified School District, located in Milpitas California, wanted to develop its own renewable energy initiative. In 2007, the school district contacted Chevron in order to make their initiative a reality.

The aim of the district's initiative was to develop a system that would have a long lasting impact for the school district. After meeting with Chevron, Milpitas decided to implement solar energy systems on 13 school sites and one district site. In total, the system was 3.4mW in size and was located on parking canopies throughout the school district. In fact, "this system is believed to be provide the largest percentage of solar power system for any K-12 school district in the United States" (Chevron Energy Solutions).

In addition to the cost savings, the new system provides educational opportunities for students within the district. Energy management software has also been implemented across the district to increase the ease with which users can interact with the system. The cost for the system was offset by the California Solar Initiative and in total, the system has lowered the district's cost by over 22% which translates roughly \$12 million savings over the life of the system. (Case Study, Milpitas Unified School District)



Solar Case Study 3 - San Jose Unified School District, California

Chevron performed another case studying, describing the system installed by yet another high school in California. The San Jose Unified School District decided to develop a solar program in order to produce financial savings, educational opportunities, and leadership in the community. In 2007, the district reached out to Chevron and ultimately entered a partnership with Chevron and Bank of America to develop the solar system that it desired. ((Case Study, San Jose Unified School District)

The system is comprised of a 5.5mW installation spanning 14 district sites. Cost savings produced by the system are estimated to be greater than 30% of energy costs and would save the school district a total of more than \$25 million over the life of the system. Financial incentives provide by the California Solar Initiative helped offset the project cost by more than \$11 million. (Chevron Energy Solutions)



Solar Case Study 4 - Bald Eagle Area School District, Pennsylvania

Smart Energy Capital performed a case study on a project much closer in scope to the Unionville High School project. Bald Eagle Area School District, located in Pennsylvania, chose to implement a solar energy system on two of its schools. In 2010 the district entered a partnership with Tremco Roofing and Smart Energy Capitol.

With financial incentives totaling \$1.4 from a Pennsylvania grant, the school district decided to enter a partnership with Tremco and Smart Energy in the form of a Purchase Power Agreement. This agreement, available to nonprofit government entities without access to tax credits and other government incentives, allows the school district to benefit from a solar system owned by a third party. In this case, the third party is SEC BESD Solar One LLC, who owns the solar system to be installed by Tremco and Smart Energy Capitol. (Smart Energy Capitol)

The system will span two schools, the Wingate Elementary School and the Bald Eagle Middle/High Schools. The elementary school system will produce roughly 300,000kWh of solar electricity, while the middle/high school system will produce 670,000kWh. As part of the agreement, the school district will purchase 100% of the electricity produced by the two systems, which should provide more than 50% of the schools' energy needs.

A Purchase Power agreement allows the school to incur no installation, equipment, or maintenance cost. Instead, Tremco roofing will install the systems and provide long term maintenance for all components of the systems while Smart Energy Capital will provide the financial investment. Ultimately, this agreement provides incentives for all three parties. (Smart Energy Capitol). Financially speaking, Bald Eagle High School will pay roughly \$.049 per kWh to Duke Energy for the electricity produced by the PV array, as opposed to standard electric cost of \$.078 per kWh, or a savings of more than 37% (\$.029) per kWh.



Interview with Bald Eagle Area SD Project Manager Rick Vilello

After finding this Bald Eagle Area High School case study during my research, I attempted to reach out to the project team to learn a little bit more about the project. I was able get I contact with Rick Vilello's, who served as the project manager for Bald Eagle Area School District on this particular project.

Rick explained that Tremco Roofing and Smart Energy Capitol had already entered a partnership. Tremco, who was already contracted to install the new roof on a renovation of the high school, initiated contact with the school district regarding installation of a Photovoltaic array. Bald Eagle Area School district then contacted Smart Energy Capitol regarding the project, and the three parties agreed to move forward with the project.

The project began in December of 2010 and the final solar panel was turned on in March 2011. Due to the decreasing value of incentives at the time, the school district decided that this contract structure provided it with the best value. By contracting with Tremco and Smart Energy Capitol to install the array, Bald Eagle School District incurred absolutely no installation, equipment, or maintenance cost for the system. Instead, the district entered a 20 year agreement with a fixed utility rate; the school district would purchase all of the energy produced by the PV arrays for a fixed rate of \$0.049 per kWh. Although this agreement included a fixed rate, Rick clarified that similar projects completed shortly after this one included clauses for inflation of utility prices.

After reviewing their options, Bald Eagle Area School District decided that without federal tax incentives, a project of this type would not be financially feasible. By letting another party own the array and purchasing power from it, the school district lines itself up to save significant money on utilities during the 20 year contract. At the completion of the 20 year contract, the school district will also gain ownership of the entire array and all included equipment.

(Vilello, Rick)



Wind Case Study 1 - Wind Powering America, Wind for Schools Project

In 2005, Wind Powering America launched the Wind for Schools Project, a project set to provide schools throughout the United States with clean, renewable wind energy. The Wind for Schools Project is available in 11 states, including Pennsylvania, and has contributed to more than 70 systems as of 2011. In Pennsylvania, nine projects were either operating, planned, or in

the developmental stage as of this report. Of those nine, five were primary education projects and two were collegiate projects, one of which being the Pennsylvania Wind Application center located at The Pennsylvania State University.

For projects within this program, the primary wind energy source is a SkyStream 3.7, 2.4kW wind turbine. The SkyStream 3.7 is a small horizontal axis wind turbine and stands between 60 and 70 feet in height (Figure 21). Training and curricula are provided to any school taking part in the project in order to create education opportunities from this renewable



Figure 21: SkyStream 3.7 Turbine Image Courtesy of Southwest Wind Power

energy resource. Project funding can be gained by several different avenues, including federal funding, partnerships, state funds, and even local utilities.


Renewable Energy System Selection

After conducting research regarding the two renewable energy sources, Solar and Wind, I have decided to pursue the implementation of a **solar energy system** for the Unionville High School Project. While neither system has a clear cut advantage over the other in terms of federal financial aid, I was able to find more information regarding similar applications for photovoltaic systems. Wind energy is not as prevalent as solar energy, and information on applications for educational buildings is not as readily available.

In studying the Bald Eagle High School project, I learned that an application very similar to what I am targeting is in fact feasible. By utilizing a *Purchase Power Agreement*, Bald Eagle HS was able to benefit from the renewable energy resources despite limited financial aid. I believe that the Unionville High School Project can benefit from a similar agreement, where a third party would own the system while the school purchased power produced by it at a discounted rate.

For this specific project, I do not believe that the photovoltaic system will provide enough energy to fulfill the entire building's needs. For this reason, I aim to implement the largest system possible in order to produce as much electricity as possible. This way, a larger quantity of reduced-cost electricity can be purchased and thus a larger financial savings can be had.



Solar Design Parameters

For any renewable energy system, the project's location is of supreme importance. Unionville High School is located in the Unionville-Chadds Ford School District, which is located in Kennett Square Pennsylvania, which is located in the Southeast of the state (figure 22).



Figure 22: Unionville High School Location



The school sits on a plot of land completely free of adjacent obstructions. No trees, buildings, or other obstructions are close enough to the school to cast shadows on any roofs that may host solar panels. Unionville High School is located at latitude 39.84 N, longitude 75.71 W, and sits 310 feet above sea level ("City Data"). Kennett Square Pennsylvania averages about 4.6 sun hours per day, which will be the basis for all calculations ("Long Term Solar"). Figure 23 below shows all design parameters for the photovoltaic system.

Solar Design Parameters			
Building Type	Educational		
Location	Kennett Square, Pennsylvania		
Latitude	39.84° N		
Longitude	75.71° W		
Elevation	310 feet above sea level		
Roof Orientation	Directly South		
Sun Hours per day	4.6		

Figure 23: Solar Design Parameters

After researching solar panel tilt angles, it appears as though the optimum tilt angle is very close to that of your location's latitude. For this application, the panels will be installed at a tilt angle of **40° N**. Positioning the panels at this angle will provide the most efficient collection of the suns energy, as the panels will remain fixed in one position at all times.



The rooftops to be considered as locations for the PV arrays are all relatively flat roofs, with little to no slope. A number of rooftop mechanical units are spread across these roofs, although there are several locations that have ample room on which to place PV panels. Both roofs on the existing building as well as newly constructed areas will be considered for this analysis. Figure 24 is a map highlighting the potential rooftop areas to place PV panels; the blue areas show potential roof space and the red areas show roof obstructions. After determining the potential areas on which the photovoltaic panels could be placed and the roof obstructions on those areas, there is a total possible area of about **100,000 square feet**. A Google Sketch-Up model was then created and a shadow analysis was run to determine which roof areas are the best fits for solar panels. A larger image highlighting the potential roof areas for the PV array can be seen in APPENDIX H.



Figure 24: Potential Roof Space

The following images detail the shading analysis performed on the Google Sketch-Up model. Each of the images displays the shadows cast by rooftop obstructions and adjacent portions of the building for a different time of year: The Summer Solstice (June 20th), the Autumnal Equinox (September 22nd), the Winter Solstice (December 21st), and Vernal Equinox (March 20th) at both 9:00AM and 4:00PM.













All images showing the shading from rooftop obstructions can also be seen in APPENDIX I.



Photovoltaic System Design

After determining which areas of the building are free of shading, it appears as though there is a total of about **50,000 square feet** of roof space available to place solar panels. The panels will be anchored on the roof, meaning there will be penetrations through the roof. Each connection will be water tight, as to ensure no damage due to the roof penetrations. An alternative would have been a Ballast-mounted system, where the panels are weighed down by heavy blocks; this system was not considered as it could have caused structural design changes and most likely an additional cost increase. The roof areas on which the PV array will be installed can be seen in APPENDIX J. As part of this analysis, several different types of photovoltaic cells were researched. Parameters for each panel are listed in table 2 below.

		-								
Manufacturer	PV Model	Cells	Power	Efficiency	Rated Voltage	Rated	Height	Length	Surface Area	Weight
			(W)	(%)	(V)	Current (A)	(in)	(in)	(Sq. In)	(lb.)
Kyocera	KD320GX-LPB	80	320	-	39.8	7.92	65.5	52	3406	61
Mitsubishi	PV-MLT265HC	120	265	16.0	31.7	8.38	64.0	40	2560	44
BP Solar	BP Q235	60	245	14.1	29.6	7.94	65.5	39.5	2587.25	42
SunPower	E19 / 320	96	320	19.6	54.7	5.86	61.5	41	2521.5	41
Sharp	NU-Q250W2	60	250	-	37.6	8.26	64.5	38	2451	42
Trina Solar	TSM-PC14	72	290	14.9	36.4	7.97	50.25	32	1608	62
SunTech	STP290-24/Vd	72	290	14.9	35.6	8.15	77	39	3003	59.5

Table 2:	PV Panel Specification Comparison
----------	-----------------------------------



After researching the above panels, the **SunPower E19/320W** panel was selected for this application. To convert the system, a **Satcon 375kw PowerGate Plus inverter** was selected. Due to time restrictions, exact calculations were not performed to determine the exact characteristics of the electrical set up for the PV array. With many large AHU units on the roof already, this large inverter can be placed on top of the roof without taking away considerably from the aesthetics of the buildings. This *monocrystalline* panel provides the highest efficiency, lowest weight, and a high power to surface area ratio, meaning that the space taken up by the panel is producing electricity efficiently. Note: This panel will have a high initial cost; this analysis is assuming that UHS will enter into a Purchase Power Agreement with a third party, the initial cost will not be considered. Specifications for the SunPower E19/320W solar panel as well as the Satcon 375kW PowerGate Plus Inverter can be found in APPENDIX K.

Following the selection of the panel, the size of the system must be determined. The system size will be based off of the available roof space and the amount of solar panels that can be installed within the available roof space.



With several areas on the roof available, there will several different string sizes. Each area will be analyzed to determine the number of strings and the number of panels within each region. Firstly, the spacing of each row of panels must be determined. Using basic calculations, it has been determined that each row of panels must be spaced roughly **10.5 feet** from front to front. For added protection against shading, a 10% allowance has been included which will increase the spacing to **12 feet.** The diagram below shows a graphic representation of the panel spacing.



The below equations were used in determining the solar panel spacing.

$$\beta \cong altitude \rightarrow \beta = 40^{\circ}$$

$$\sin(\beta) = \left(\frac{h}{L}\right) \rightarrow \sin(40^{\circ}) = \left(\frac{h}{5.125ft}\right) \rightarrow h = 3.29ft$$

$$5.125^2 = 3.29^2 - d_{1^2} \rightarrow d_1 = 3.93ft$$

$$\cos(26.6^{\circ}) = \left(\frac{d_2}{7.35}\right) \rightarrow d_2 = 6.57ft$$

$$d_1 + d_2 \rightarrow 3.93ft + 6.57ft \rightarrow d = 10.50ft$$

$$\delta = -23.4$$

$$\cos(\theta 2) = \cos(\beta)\cos(\delta) + \sin(\beta)\sin(\delta)$$

$$\cos(\theta 2) = \cos(40)\cos(-23.4) + \sin(40)\sin(-23.4)$$

$$\cos(\theta 2) = -.25 \rightarrow \theta 2 = 63.4^{\circ}$$

During design, roughly 4 feet of space will be left around the perimeter of any roof on which panels are to be installed; this space if left in order to cut down on added wing load and to allow maintenance access to the roof (The German Energy Society 230, 231). Based on these parameters, the maximum amount of panels that can be placed on the available roof space can be calculated.



For the panel quantity calculations each individual roof space (figure 25) was calculated separately; these calculations are listed in the table below.



Figure 25: Roofs Selected for PV Array Installation

Givens:					
N-S Spacir	ng: 12' from fro	ont to front			
# of Rows	= (Length)/(12	2' spacing) + 1	(front edge)		
Panel wid	th (E-W) = 3.4	2ft (Note will	be installed edge	to edge)	
Building	Length (N-S)	Width (E-W)	Number of Rows	Number of Panels	Number of Panels
Area	ft	ft	in Area	in row	in Area
				ĺ	
A1	96	86	9.00	25.15	225
B1	34	75	3.83	21.93	63
D1	40	90	4.33	26.32	104
D2	40	50	4.33	14.62	56
D3	36	52	4.00	15.20	60
E1	140	40	12.67	11.70	132
E2	36	50	4.00	14.62	56
E3	50	42	5.17	12.28	60
E4	24	40	3.00	11.70	33
F1	26	36	3.17	10.53	30
G1	90	52	8.50	15.20	120
H1	36	88	4.00	25.73	100
Total					1039

After calculated each individual area, the system will consist of **1039 individual panels**. Based on the information provided by the manufacturer, the entire size of the system can be calculated as follows:

1039 panels * 320W per panel \rightarrow Total System Power = 332, 480 W or 332. 8kW



Cost Analysis

As stated before, this system was designed to use under a Purchase Power Agreement. This means that a third party owns the system, while Unionville High School will purchase the power produced by the system, meaning that absolutely no up-front costs are incurred by the school.

The average electricity cost at the time that this report was completed in Pennsylvania is around **\$0.96 per kWh**; this value will be used as the baseline for the cost savings analysis (United States Department of Labor). Based on the agreement, Unionville High School will contract with a third party; this contract will spell out exactly how much UHS will pay the third party per kWh. Based on information gathered through research, it is assumed that UHS will pay the third party 63% of today's electricity cost, or **\$0.0605 per kWh**, for the energy produced by the photovoltaic system.

Using PVWatts (developed by the NREL) the yearly savings incurred as a result of the photovoltaic system can be calculated. The data output provided by PV Watts can be seen in APPENDIX L. After using the software to run the calculation, the results came back as follows:

Total System Power = 332, 480 W or 332.8kW

Yearly AC Energy Produced by system = $401307 \ kWh$

Average Electricity Cost in PA =\$0.096 per kWh

401307 kWh * \$0.096 per kwh = \$38,525.47 energy value in year 1

Assuming that UHS will pay just **63%** of the energy value in year one for energy produced by the solar energy system as a result of the PPA contract (based on the Bald Eagle Area High School case study), a savings analysis can be developed. With a typical PPA contract length of 25 years and inflation in energy prices of 1% per year, the savings over the life of the contract come out to be **roughly \$402,590.56**. A spreadsheet detailing the energy savings analysis can be found in APPENDIX M.

Based on the "Tracking the Sun Report IV" document produced by the Berkeley Lab in California, the costs to install PV systems have been declining yearly. The cost to install PV systems in Pennsylvania is listed in table 3 below.

Table 3: Cost of PV Array Installation

State	Year	Size (kW _{dc)}	Cost/W
Pennsylvania	2010	$< 10 \mathrm{kW}_{\mathrm{dc}}$	\$6.8
		$10kW_{dc}-100kW_{dc}$	\$6.3
		> 100kW _{dc}	\$5.6

Because the system is over 100kW, it will be assumed the cost of the system will cost **\$5.6 per Watt.** Given this information, the total cost of the system with no incentives will be as follows:

System Size: 332, 800 watts

332,800 watt system * $5.6 per watt \rightarrow Up front cost =$ 1,863,680

After finding the up-front cost, a lifecycle cost was developed to determine the initial investment for the Photovoltaic Array for the third party involved. Unlike the school district, the third party involved in the Power Purchase Agreement is eligible for government funding. The main sources of funding come from these sources:

Federal Tax Credit	30% of all expenditures, no limit
PA Sunshine Solar Rebate Program	Lesser of \$52,500 or %35 of up-front costs
PA Renewable Energy Tax Credit	15% credit after all other incentives have been used

Total Initial System Cost: \$1,863,600

1,863,000 - (.30)(1,863,000) = 1,304,576

1,304,576 - 52,500 = 1,252,076

\$1,247,076 - (.15)(\$1,247,076) = \$**1**,**064**,**264**



After taking all of these incentives into account, the third party involved in the Purchase Power agreement would incur an up-front cost of: **\$1,064,264.**

As a supplemental study to the cost savings due to reduced electricity costs as a result of a Purchase Power Agreement, an analysis was done to determine what the cost of the system would be if the school decided to incur all costs and own the system itself. With the cost of electricity in year one assumed to be \$0.096 and a yearly inflation of 1%, the end result of this study saw a **40 year payback period for the school**; this is the main reason that a Purchase Power Agreement was the preferred option. Calculations for Unionville High Schools potential payback period can be seen in APPENDIX N.



Schedule Impact

Due to the contract structure of a Purchase Power Agreement, the system will not be a part of this projects budget; as a result, it will have no impact on the completion of the project. That being said, the system will take time to install. If the project team chooses to do so, the PV array could be installed in line with the UHS project phases. Depending on which roof the array is to be installed on, those panels can be installed following the completion of the necessary phase.

For example, Area D is the first phase. Following the completion of Phase 1, all PV panels located on the roof in area D can be installed. The final phase of the Unionville High School Building Renovations and Additions project is Phase 4B, which is the demolition of the existing auxiliary gym. With all other phases completing prior to the end of phase 4B, all roof areas will be completely finished. Based on this method, the entire array can be installed before the finish of the UHS project.

Constructability

This system will be installed following the completion of the necessary roof spaces. Structurally, the existing system is more than capable of handling the added load. The panels, which are roughly 41 pounds each (including the mounting hardware) will add less than 1.5 lb. per square foot. A sample calculation, provided for PV installation area D1, is shown below.

Area $D1 \rightarrow 41$ lb per panel * 104 panels = 4264 lb

Area D1 Area = 40 feet * 90 feet = 3600 square feet

$$\frac{(4264 \ lb \)}{3600 \ sf} = 1.18 \ lb/sf$$

Based on the designed superimposed dead load of 20psf, this additional load is almost negligible and no structural changes will be needed to carry the added load of the PV panels.



LEED Implications

As originally designed, the Unionville High School Building Project was set to earn Silver Certification under the 2007 system. Under the 2009 system, the building qualifies only for LEED Certification. The addition of on-site renewable energy presents the opportunity for additional LEED credits under the Energy and Atmosphere category. EA Credit 2: On-Site Renewable Energy awards anywhere from 1 to 7 credits, depending on what percentage of the buildings overall energy use is produced by the renewable energy. The amount of energy used by Unionville High School was unable to be accurately determined, so the percentage of energy produced by the PV array cannot be calculated. It can be assumed, though, that additional LEED credits can be obtained through the implementation of a PV array on the project.

Findings and Conclusion

Should the school decide to front the entire cost of the system itself, the payback period for this system would be **40 year**, and as such would most likely not be feasible. However, because the school will enter a PPA with a third party, there will be no up-front costs incurred by the school. Assuming that the PPA will incur all initial costs and after performing all necessary research and calculations, it has been determined that the school will see a 25 year savings of roughly **\$402,600**. These savings are the result of UHS purchasing electricity at a discounted rate, **63%** of the current rate, from the third party owner of the photovoltaic system. Ultimately, because no costs are incurred up front by the school, I believe that implementing this type of system *would provide significant value* to the owner and the project.



Analysis 4: Façade Redesign – Prefabricated Panel Façade System

Problem Identification

The original façade designed for the new additions to the Unionville High School building consist of rock-faced CMU blocks, bricks, and limestone lintels. Installation for this system is done piece by piece, known as a 'stick-built' façade. Installation of this system in this manner takes a significant amount of time and even adds time to the entire project schedule. Additionally, this type of system can lead to safety issues, unnecessary sight congestion, and decreased productivity.

Research Goal

A prefabricated façade system will be researched as an alternative to the originally designed system. Research will determine if using another system is feasible and would add value to the project. In order to make these determinations, a cost and schedule analysis will be performed highlighting the positives and negatives of implementing the new façade system. Any changes to the originally designed structural system will be studied, and any necessary additions or changes (including a connection for the new panels) will be designed. Mechanical properties for the new system will also be studied, determining any changes to mechanical loads and the potential for any changes to the existing system.



Research Methods

- Study current façade assembly
- ***** Determine duration and cost of installing the existing façade system
- Study potential prefabricated panel façade systems
 - Utilize past studies on implementation of prefabricated panels
 - Research and compare prefabricated panel manufacturers
- Determine which prefabricate panel façade system to use
 - Select system based on price, lead time, usage on similar projects
- Design Precast Panel
 - Determine installation cost and duration
- ✤ Mechanical Breadth:
 - Analyze effects on mechanical properties of the façade system (mechanical breadth)
 - Aim to improve thermal/mechanical properties with implementation of prefabricated façade panels
 - Compare existing façade with new façade to determine best option
- Structural Breadth:
 - Analyze resultant effects on existing structural system
 - Design any necessary additional structural connections (structural breadth)
- **Study feasibility of prefabricated facade system**
 - **o** Cost, Schedule, Constructability, and Quality to the Owner



Background Information

With a stick built façade as part of the original design, the Unionville High School project has dedicated a significant time within the project schedule to the construction of the façade. A prefabricated façade panel system would provide schedule relief, while also decreasing cost and potentially improving the systems mechanical properties. Prefabricated façade panels can be made of a variety of different sizes and incorporate a number of different building materials. For this reason, I felt that a prefabricated panel would be a suitable alternate to the originally designed façade system.

These panels can be manufactured off site and delivered to the project, decreasing the time that it takes to install the product. Aesthetically, prefabricated panels can be designed to meet almost any criteria. By producing the panels off site, on site labor can be reduced. Additionally, site congestion can be addressed as there is no need to store material as is the case with the original façade design. This analysis will aim to design a prefabricated panel with similar aesthetic qualities while decreasing the time that it takes to install the façade, improving the thermal properties, and lowering the cost.



Current Façade Assembly

The Unionville High School Building is a project undergoing renovations and construction on several new additions. These new additions have a slightly different architectural look than the existing building, with a stick built façade as part of the original design. The façade is to be built by hand, is not load bearing, and is made up of rock face CMU, brick, and limestone lintels. For this analysis, Phase 1 will be studied. Calculations for the entire project will be extrapolated from the information gathered during the analysis of Phase 1.

Rock face CMU units and red face bricks are the primary piece of the façade, making up the majority of the assembly. Also included are courses of darker bricks, located between every two rock face CMU or red brick courses. Limestone lintels rest above every door and both above and below each window (Figure 26). Some areas of the façade are strictly brick course, although the majority of the façade is the assembly as described above. The wall also includes an air cavity, rigid insulation, and CMU interior walls that sit on the steel structure. Although not exactly the same as, the colors and materials are similar to those used in the exiting building.





After consulting the specifications, all CMU and brick units are to be manufactured within 500 miles and made from material harvested within 500 miles of the project site, in Kennett Square Pennsylvania; as a result, an additional goal of this analysis will be to design a prefabricated façade panel that also meets this same 'regional materials' criterion.

Phase 1 has three elevations that this façade system will be installed on: East, South, and West; the North façade is connected to the existing building, and as such will have no facade. After totaling up the facades being studied for this analysis, there is a total of roughly **35,500 square feet** of façade to be redesigned. Based on the information provided by Wohlsen construction, the existing façade assembly will take **three months** from start to finish to completely erect, with a total of 64 working days excluding holidays and weekend days. Including all shipping, material, labor, and installation, the façade for this portion of the building will cost a total of **\$2.2 million**. After subtracting the cost of the foundation **(\$699,000**), which will not be included for either system, and the total cost of all work involving windows and doors **(\$520,950**), which will be the same for both systems, the total cost of the original façade design comes to **\$1.17 million**. One important factor to note is that the original façade does not require a crane, while the prefabricated panel system will. Based on these numbers, the original façade will cost approximately **\$33.05 per square foot**.



Prefabricated Panel System Selection

Prefabricated façade panels have become more and more prevalent in the construction industry in recent years. With the actual production of these panels done in manufacturing warehouses, waste can be minimized and each panel can be produced in shorter time and engineered to exact specifications. As a result of the use of skilled labor, however, it is believed that the price of these prefabbed panels will be greater than the original façade system. The main goal of this façade redesign will be to shorten the project schedule.

Research on the topic revealed that there are a number of prefabricated façade panel manufacturers in the region that my building is in. After thoroughly studying the different options available, I decided to go with **Nitterhouse Concrete Products**. Located in Chambersburg PA, Nitterhouse services the entire state of Pennsylvania, as well as West Virginia, Virginia, Maryland, Delaware, New Jersey, and New York. As part of the requirements for the new Precast Panels, I wanted to ensure that the panels came from within 500 miles of Kennett Square, PA; Chambersburg is just 128 miles away, well within that limit. These panels will be strictly thin brick, but two colors of brick will be used in order to mimic the current architectural features of the rock face CMU façade.



Nitterhouse 9" Precast Sandwich Panel

Mark Taylor, President of Nitterhouse Concrete Products, was kind enough to provide me with all of the information that I needed for my research on precast façade panels. Mark provided me with information and panel specifications for a panel without an air cavity, which the originally designed façade system had. After speaking with him, he told me that the air panel was not necessary within the precast panel as the concretes density would not allow any moisture to pass through the assembly.

Each panel can be made a maximum of 12' wide and a maximum of 40' tall, and the order for this project would require 5 to 6 months of lead time. This is important because a system of this type would have to be decided upon early in the projects lifetime. The system would be 9" total in thickness, with a 3" inside concrete face, 2" of rigid insulation, and 4" of concrete for the outside face, which would be faced with thin brick to achieve a similar architectural finish.

With panels of this size, the installation crew could install 15-20 panels per day; for this analysis, the low end, **15 panels per day**, will be used as the norm. For this particular panel, the cost (including fabrication, delivery, and installation) would be roughly **\$35 per square foot** of panel, or **\$16,800 per 12' x 40' panel**. Based on this information, the total cost of the façade using this precast panel would be roughly **\$1.24 million**, or slightly more expensive than the original system which came in at a total cost of **\$1.17 million**.

\$35 per square foot * 35,500 square feet = \$1,242,500

A visual comparison, developed in Google Sketch Up of the two façade systems and their makeups can be found in APPENDIX O.



Panel Implementation

Based on a simple calculation of 35,500 square feet of total façade divided by 480 square feet (12 feet by 40 feet) for panels, a total of **74 panels** would be needed to complete the façade if each panel were to be uniform. With 15 panels erected each day, the façade system would be completed in **5 working days**.

$$\frac{35,500 \text{ square feet}}{480 \text{ square } \frac{feet}{panel}} = 74 \text{ panels} \rightarrow \frac{74 \text{ panels}}{15 \frac{panels}{day}} = 5 \text{ working days}$$

This calculation is *not accurate*, however, as the façade's design will not allow for 12' wide uniform panels all the way across the elevation. Instead, some panels will have to vary in width, which means the total number of panels will increase and ultimately, the time to erect the panels will increase. The façade's in question will be analyzed and the different size panels will be determined. Each panel will be designed with openings for both windows and doors already formed, and all windows and doors will remain the same as the original design.

Mark stated that the panels can come in sizes up to 12' x 40', or the largest size possible to fit on a flatbed truck. For several reasons, this size will not work for my building. For one, as mentioned above, the façade will not allow the panels to be designed at just one width. Secondly, the new addition tops out at 42' feet, 2' taller than the panel's maximum height. For this reason, the panels will be 1 story in height, and will vary in width. In total, there will be **37** different size panels, with just 4 different panel widths (6', 8, 10', and 12') and two different panel heights (13.5' and 28.5'). Although the panels vary in length, these widths allow a relatively uniform layout. Some panels are the same size, but due to window and door locations will have different opening. In total, there will be **132** panels to complete the façade. Assuming that 15 panels will be erected per day, the façade will take a total of 8.8 or **9** working days. Allowing 1 day for any learning curve, it will be assumed that the new façade will take **10** working days to complete. Images showing the panel layouts can be found in APPENDIX P.

132 panels
$$\rightarrow \frac{132 \text{ panels}}{15 \frac{\text{panels}}{\text{day}}} = 8.8 \approx 10 \text{ working days}$$



While the new façade system installation duration breaks down to roughly 10 working days to install, integrating it with the other work within Phase 1 is not as simple as just plugging it in and assuming a 10 day duration. The current schedule splits the steel erection for Phase 1 into three parts, shown on figure 27 below.



Figure 26: Structure Schedule Breakdown by Area

The schedule for the steel structure for the three areas is as follows:

Area	Start Date	Completion Date	Duration (work days)
Northwest Wing (Red)	July 20 th 2009	November 13 th 2009	82
Southwest Corner (Blue)	July 31 st 2009	December 9 th 2009	90
East Wing (Green)	August 25th	December 17 th 2009	79



Within each of the three areas, the façade is split into several portions, depending on how many exposed elevations exist in each area. These facades are listed below.

Area	Start Date	Completion Date	Duration (work days)
North (Green)	February 11 th 2010	March 15 th 2010	15
East (Red)	December 1 st 2009	December 20 th 2009	15
East (Green)	February 2 nd 2010	March 4 th 2010	22
South (Blue)	January 12 th 2010	February 12 th 2010	29
South (Green)	January 22 nd 2010	February 23 rd 2010	22
West (Red)	December 10 th 2009	January 11 th 2010	21
West (Green)	December 31th 2009	February 2 nd 2010	21

The facades within each of these areas are to be started following the completion of the steel for that particular area, meaning that it can be assumed that the precast façade panels can start at the same time as the originally designed façade. Based on this information, the installation of the new panels can be integrated into the original schedule to truthfully determine how much time can be saved.

Each area within Phase 1 has a different amount of panels. Information regarding how many panels is to be installed within each area is listed below.

Area	Amount of Panels	Days Needed to Complete
North (Green)	10	1
East (Red)	17	2
East (Green)	18	2
South (Blue)	24	2
South (Green)	21	2
West (Red)	18	2
West (Green)	24	2

With an assumed quantity of 15 panels erected each day, the total duration for all of the panels to be installed is actually **13 working days**, or roughly **3 working weeks**. Compared to the original façade, this is a difference of **51 working days** of total duration.



Area	Start Date	Completion Date	Duration (work days)
North (Green)	February 11 th 2010	February 11 th 2010	1
East (Red)	December 1 st 2009	December 2 nd 2009	2
East (Green)	February 2 nd 2010	February 3 rd 2010	2
South (Blue)	January 12 th 2010	January 13 th 2010	2
South (Green)	January 22 nd 2010	January 25 th 2010	2
West (Red)	December 10 th 2009	December 13 th 2009	2
West (Green)	December 31 st 2009	January 4 th 2010	2

Based on those durations, the new schedule for the installation of the façade will be as follows:

Based on these calculations, a total of **132 working days** can be saved when considering each elevation within the phase; this means that the cost of labor to install the original façade would be decreased significantly. As a result of the project being phased so tightly, it is difficult to determine exactly which activities would be altered as a result of the more rapid façade installation, and exactly how many days could be shaved off of the schedule. It is clear, however, that the precast façade panel system *would save time* on the project schedule, and as a result, potentially money.

As a result of the crane having to be on site additional days in order to erect the panels, an added cost will be incurred. Assuming that the same 15 ton crane will be used to erect the panels (the largest of which is 15 tons), a simple calculation was done to determine that added cost of having the crane on site to erect the panels. After integrating the panel erection into the current schedule and merging it with the structural steel erection, which will be entirely complete before any of the facades are installed, it has been determined that the crane will have to remain on site for an additional **13 working days**, or **roughly 3 weeks**. It was decided to install the entire façade after all of the structure was complete for phase one in order to allow the erection of steel to progress as originally scheduled.

Based on this duration, and a cost of **\$1200** per day for the cane to be on site, a total added cost of **\$15,600** will be accrued as a result of using the crane to install the precast wall panels. (Crane Rental Rates)



Cost

After compiling all of the data related to the two systems, I do not believe that it would be beneficial to implement the precast façade panels. With the precast façade panels, the system would be more expensive in terms of initial cost; the material, labor, and shipping total for the original façade comes in at around **\$1.17 million**, while the precast façade system would cost **\$1.24 million**. In addition to this **cost increase of \$700,000** for the initial cost of the façade, an **added \$15,600** in crane costs will be added should the precast panel system be implemented. Overall, the precast panel façade system clearly costs more than the original stick build façade system.

Schedule Impact

As previously stated, the original stick built façade has a much longer installation time than the proposed precast façade panel system: the original façade is scheduled to take roughly 3 months to complete, while the precast panel façade system will take about 3 working weeks to complete. With such a massive difference, it is clear that implementing the precast panels on this project would be a benefit to the schedule.

Constructability

Regarding installation of the panels, the implementation of this system would not cause an issue. With a crane on site (which is large enough to pick the heaviest panel), I believe that installing this precast façade panel system would have worked seamlessly. That being said, a much greater lead time is associated with a precast panel façade system; for this particular system, the lead time would range from 4 to 5 months, meaning that the decision to used precast panels would have to occur at an early stage of the project's lifecycle. Additionally, the precast panels would eliminate the varying architecture seen in the original façade.



Conclusion

The information obtained as a result of the mechanical breadth comparing the two façade assembly's shows that the panel façade system would be inferior to the original façade assembly as well. When comparing the heat loss for the two assemblies using DesignBuilder, the original façade saw an annual heat loss of around **160 kBTU x 10³**, while the new panel façade system experienced greater losses, with a value around **195 kBTU x 10³**; in total, the original façade is roughly %18 more effective thermally. Should the new façade be implemented, additional costs would likely be incurred as a result of the need for increased thermal loads.

Ultimately, *I would not advocate* the implementation of these precast panels for the Unionville High School Building. Based on the information obtained through the research and analyses done regarding the panels shows that the increased cost, change in architectural look, and decreased thermal properties outweigh the savings in schedule. While schedule reduction is of great importance, the other features regarding the implementation of this new precast panel façade system dictate that the original system is in fact a better option.



Mechanical Breadth

As previously mentioned, the current façade system is not load-bearing. Instead, a structural steel frame makes up the superstructure of the building, with CMU interior walls. The façade itself sits on the foundation, while the CMU interior walls rest on beams at each floor level. Following the erection of steel for all new construction phases, the facade will then be installed. Because each piece of the façade assembly much be placed individually, installation for the façade can take up a fair amount of time. At UHS, the façade for Phase 1 (The New Administrative Office addition) took a total of three months (November 9th 2009 to February 10th 2010).

In terms of thermal properties, each piece of the assembly has different characteristics. Each item has a unique R-Value, a measure of thermal resistance. Depending on the combination of materials, a wall assembly will have certain thermal properties. For this particular building, the façade is made up of four primary layers: Veneer, air cavity, insulation, and CMU interior wall. Based on the elevation of the wall, three materials have been used for the façade: Rock Face CMU block, Limestone, and Face Brick. Each piece of both the existing assembly as well as the precast façade panels is listed below, with the corresponding R-values taken from the HAM Toolbox software developed by PSU. Calculations from the HAM Toolbox can be seen in APPENDIX Q. Note: Only Brick and Rock Faced CMU were analyzed using this software, as the Limestone made up a small percentage of all façade area.

Construction Material	R Value (per thickness hr*ft ² *BTU)
4" Face CMU Block	0.69
4" Face Brick	0.64
4" Cast Limestone	0.19
2" Air Cavity	0.98
2" Rigid Insulation	7.90
8" CMU Block	1.03

Table 4: Original Facade Materials R Values



Table 5: Original Façade Assembly R Values

Construction Material	R Value (per thickness hr*ft ² *°F/BTU)
4" Face Brick Layer	0.64
2" Air Cavity	0.98
2" Rigid Insulation	7.90
8" CMU Block layer	1.03
Total	10.56

Table 6: Precast Facade Panel Assembly R Values

Construction Material	R Value (per thickness hr*ft ² *°F/BTU)
3" Concrete Layer	0.44
2" Rigid Insulation	7.90
4" Concrete Layer	0.58
Total: 9"	8.92

As you can see, the precast façade panels are one layer smaller than the original façade, with the elimination of the air cavity. Based on information received while speaking with Mark Taylor of Nitterhouse Concrete products, the air cavity can be removed due to the density of the concrete; there is no danger of moisture reaching the insulation and as such, the cavity can be removed.

After a quick comparison of the two façade assemblies, it is clear that the original façade assembly has a higher R value than the precast façade panels, **10.56** hr*ft²*°F/BTU compared to **8.92** hr*ft²*°F/BTU.

In order to get a better understanding of the thermal properties of the two systems, and the differences that these façade assemblies would have on the building, a simple energy model was developed using the software program DesignBuilder.



A simple model of Area D, or Phase 1, of the Unionville High School was created within the software in order to compare the two façade systems. The model was developed by creating the building and specifying materials for all floors, walls, roofs, and interior spaces. Other than the façade assembly itself, no other features of the building changed between the two analyses. Two types of reports were generated from each analysis: an annual ventilation report and a monthly ventilation report.

Each report analyzed the building to determine how effective the thermal properties of each façade system are. The effective heat gain for the building was the main target output, showing which of the two systems would provide better insulation for the building. After running both tests, the Original Façade tested favorably, as the numbers from HAM toolbox suggested it would.

When studying *monthly* heat loss comparisons, the original façade clearly outperformed the precast façade panels. For each month, the original façade provided better insulation for the building, resulting in the better overall performance of the original façade.

System	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sept	Oct	Nov	Dec
Original	-47000	-34000	-18500	-17000	-3000	4500	14500	15100	3500	-4000	-20500	-32000
Panels	-60000	-46000	-27000	-21000	-5000	8000	18000	19000	3500	-10000	-28000	-455000

Table 4: Monthly heat gain comparison (in kBTU)

Based on a comparison of the *annual* heat gain values for both assemblies (table 4), the original façade experiences a net loss of roughly **160 kBTU x 10^3**. The newly designed precast panel façade, on the other hand, experienced a net loss of roughly **195 kBTU x 10^3**. Comparatively, the original façade system was 18% more effective in terms of its thermal properties. Graphs taken from the DesignBuilder showing this information can be found in APPENDIX R.



Conclusions

Based on the information provided by both the HAM toolbox and DesignBuilder software, it is clear that the original façade assembly provided a higher quality of thermal properties for the building as opposed to the precast panel façade system. With greater losses after applying the new precast panel façade system, it can be assumed that heating and cooling loads necessary for the building would have to increase. As a result of this mechanical load increase, it can also be assumed that **costs increases** would be incurred based on these needs for increased mechanical loads within the building.



Structural Breadth

Research into prefabricated precast façade panels brought up questions regarding the existing structural system and whether or not the original design would be capable of supporting the increased load. This breadth was performed in order to compare the two systems' effects on the originally designed structural system and to ultimately determine whether any changes would need to be made to the structural system.

For this breadth, one specific beam in Area D will be analyzed; located on the second floor between column lines BB and CC and on column line 51, this beam will carry the entire load of two of the largest panels to be installed on the facade. As a **W21x44 at 24'-4" in length**, this specific beam is one of the smaller beams on the exterior of the building and should some of the most dramatic loading differences as a result of the façade change. Figure 28 below shows the location of the beam. The allowable limits for the W21x44 beam are listed below:

Beam	Length	Max Allowable Moment	Max Allowable	Max Allowable Deflection
Type		[¢] Mn	Deflection	due to Live Load
W21x44	24'-4"	331 kip-ft.	1.2"	.81"



Figure 27: Sample Beam Location



Calculations to determine the loading from the original façade were done to set the baseline to compare the new system to. The original façade system is made up primarily of face brick, with an air gap, insulation, and CMU backup wall; only the CMU backup wall is supported by the steel structure, the brick veneer is supported by the foundation and as such was not included in these calculations. Note: the only load that the façade placed on this beam is a one story tall CMU backup wall. Figure 29 below shows the original façade's connection to the structure.



Figure 28: Original Facade Structural Connection

Hand calculations were used to determine the loading, moments, deflections, and results of the two façade assemblies; these calculations are available in APPENDIX #. After performing some calculations on the existing façade, the following information was obtained:

Total Load w (klf)	Total Moment M _u (k-	Total Deflection (in)	Live Load Deflection (in)	
	ft.)			
2.46	182.02	0.53"	0.17"	



Upon checking these results against the member's acceptable values, each check showed that the member was **acceptable** as designed. Now, knowing how the structural member performed under the loading from the original façade, the new precast panel façade was analyzed.

The precast façade is expected to produce increased loading, moments, and deflections as a result of the increased weight. In addition this steel member, located on the second floor, will carry the weight of a panel spanning both the second and third floor, while the original façade required this same member only to support one story of CMU block wall. Made up of 3" of exterior concrete, 2" of rigid insulation, and 4" of interior concrete, each façade panel will weigh 88 pounds per square foot. The structural connection chosen to hang the precast panels was selected from several options from the manufacturer; Figure 30 below shows this detail.



Figure 30: Precast Facade Panel Connection Detail



Again, the same loading calculations were performed to determine how the structural steel member would react when loaded with the new precast panel façade system. It is assumed that two panels will be supported by this single beam, with each panel having one support at each corner; with two panels meeting at the center of the beam, a single point load will be assumed at the center of the beam which will likely contribute to a significantly increased moment. After running the calculations, the following information was obtained:

Total Load w	Point Load	Total Moment M _u	Total Deflection	Live Load
(klf)	(kip)	(k-ft.)	(in)	Deflection (in)
1.57	30.51	301.75	1.15″	0.17"

Compared to the original façade system, the precast panel façade system does in fact produce much greater loads, moments, and deflections. That being said, the existing W21x44 beam still **provides sufficient support** to carry the increased load. For a better comparison, the effects of each façade assembly on the beam are listed below.

	Total Load (klf)	Point Load (kip)	Tot Moment (M _u)	Tot Deflection (in)	LL Deflection (in)
Original Facade	2.46	-	182.02	.53	.17
Precast Facade	1.57	30.51	301.75	1.15	.17

For comparison sake, the 30.51 kip point load due to the precast façade can be converted into a distributed load and combined with the existing distributed, bringing the total distributed load due to the precast façade to 2.82 klf.

Ultimately, the new façade system had the following effects on the structural system:

Total Load Increase (%)	Total Moment Increase (%)	Total Deflection Increase (%)
14.63	65.78	116.98

Hand calculations can be found in APPENDIX S.


Conclusions

As mentioned before, despite these increases, the existing structural member at this location **will support the added load**. That being said, due to the large increases in loading, moment, and deflection, it can be assumed that upsizing of some structural members as a result of the increased load may occur.



Sources

The Allegheny Conference, The Pennsylvania Economy League of Southwestern Pennsylvania. "A Review of the Effects of the Pennsylvania Separations Act on School Districts." *AlleghenyConference.org*. N.p., November 8th, 2007. Web. 1 Feb 2012.

<http://www.alleghenyconference.org/PEL/PDFs/PASeparationsActReport1107.pdf>.

"Case Study, Milpitas Unified School District." Chevron Energy Solutions. N.p., 2009. Web. 13 Feb 2012. http://www.chevronenergy.com/case_studies/musd.asp.

"Case Study, San Jose Unified School District." Chevron Energy Solutions. N.p., 2009. Web. 13 Feb 2012. http://www.chevronenergy.com/case_studies/sjusd.asp.

- Computer Integrated Construction Research Group, . "BIM Execution Planning." *BIM Execution Planning*. The Pennsylvania State University, 2011. Web. 14 Feb 2012. http://bim.psu.edu/.
- "Energy Benchmarking Report fo Bound Brook High School." *NJCleanEnergy.com*. N.p., November 2009. Web. 20 Feb 2012. <www.njcleanenergy.com/.../BBHS Energy Benchmarking Report.pdf>.
- The German Energy Society, . *Planning & Installing Photovoltaic Systems*. Second. London, England: Earthscan, 2009. 230,231.

Hostetler, Rick. Unionville-Chadds Ford School District. Personal Interview. February 28th, 2012.

- IRS. "Business Energy Investment Tax Credit (ITC)." Database of State Incentives for Renewables and Efficiency. U.S. Internal Revenue Service (IRS-2), June3rd 2011. Web. 12 Feb 2012. http://dsireusa.org/incentives/incentive.cfm?Incentive_Code=US02F&re=1&ee=0>. IRS, . "Renewable
- IRS. "Electricity Production Tax Credit (PTC)." Database of State Incentives for Renewables and Efficiency. U.S. Internal Revenue Service (IRS-1), June3rd 2011. Web. 12 Feb 2012. . d=1&ee=1&re=1>.
- "Kennett Square, Pennsylvania." *City Data*. N.p., January 1st 2011. Web. 12 Feb 2012. <http://www.citydata.com/city/Kennett-Square-Pennsylvania.html>.

Laub, Brian. Wohlsen Construction. Personal Interview. February 15th, 2012.



"Managing Energy Costs in Schools." *TouchStoneEnergy.com*. E Source, 2008. Web. 20 Feb 2012. <www.touchstoneenergy.com/efficiency/bea/Documents/Schools.pdf>.

Meyers, C. Bracken. "Types of Wind Turbines." *Centurion Energy*. N.p., February 21st, 2010. Web. 9 Feb 2012. http://centurionenergy.net/types-of-wind-turbines.

National Renewable Energy Laboratory, . United States Government. U.S. Department of Energy. *Power Purchase* Agreement Checklist for State and Local Governments. 2009. Web.

<www.nrel.gov/docs/fy10osti/46668.pdf>

Pennsylvania Department of Community & Economic Development, . State of Pennsylvania. Pennsylvania Department of Community & Economic Development. *Solar Energy Program*. 2009. Web. http://www.newpa.com/webfm_send/1389>.

Pennsylvania Department of Education, . "Education Empowerment Annual Report." *Pennsylvania Department of Education Bureau of Teaching and Learning Support*. N.p., 2007-2008. Web. 6 Feb 2012. http://www.portal.state.pa.us/portal/server.pt/community/education_empowerment_act/7403/education_empowerment_annual_report/510189.

"Pennsylvania AEPS Alternative Energy Credit Program." *The Pennsylvania AEPS Alternative Energy Credit Program*. Pa.Gov, n.d. Web. 8 Feb 2012. http://paaeps.com/credit/index.do.

PVPower, Inc. "How Efficient is Solar Energy?." *PVPower.com*. N.p., 2012. Web. 7 Feb 2012.

<http://www.pvpower.com/howefficientissolarenergy.html>

Rush, Richard D.. "Managing a School Construction Project." *American School & University Magazine*. N.p., August 1st, 2002. Web. 14 Feb 2012.

<http://asumag.com/mag/university_construction_mix/>.

Smart Energy Capitol, . "Bald Eagle Area School District (PA) selects rooftop photovoltaic system from Tremco Roofing and Building Maintenance, and Smart Energy Capital." Smart Energy Capitol. N.p., May 12th, 2010. Web. 13 Feb 2012. .



"Solar Sunlight Hours." *Long Term Solar*. N.p., September 28th, 2011. Web. 12 Feb 2012. http://www.longtermsolar.com/solar-sunlight-hours/.

Taylor, Mark. Nitterhouse Concrete. Personal Interview. January 12th, 2012.

United States. Environmental Protection Agency. *Putting Energy Into Profits*. 2000. Web. state.tx.us/TEP.../c/EPAEnergyStarSmallBusinessGuide.pdf>.

United States Department of Energy, . "Photovoltaic Cells." Energy Efficiency and Renewable Energy. U.S.

Department of Energy, 08/12/2011. Web. 7 Feb 2012.

<http://www.eere.energy.gov/basics/renewable_energy/pv_cells.html>.

United States Department of Labor. Bureau of Labor Statistics. *Average Energy Prices in the Philadelphia Area*. November 2011. Web. http://www.bls.gov/ro3/apphl.htm.

Vilello, Rick. Bald Eagle Area SD. Personal Interview. Jaunary 24th, 2012.

"West Sonoma County Union High School District Goes Solar for General Fund Relief" SunPower Corp. N.p., 2010. Web. 13 Feb 2012.

<http://us.sunpowercorp.com/cs/Satellite?blobcol=urldata&blobheader=application%2Fpdf&blobheader name3=Content-

Disposition&blobheadervalue3=attachment%3B+filename%3D11_701_sp_dealer_wscuhsd_cs_en_ltr.pdf &blobkey=id&blobtable=MungoBlobs&blobwhere=1300271294088&ssbinary=true>.

Wind Power." New York Times [New York] 27th January 2012, n. pag. Web. 9 Feb. 2012. http://topics.nytimes.com/top/news/business/energy-environment/wind-power/index.html.



Acknowledgements

This report is the product of countless hours of research and a vast number of resources. Without the help that I have received, this Thesis would have been impossible to assemble.

Thank you to Unionville High School staff. You were always open to helping me throughout the process and provided my building for this project.

Thank you to Wohlsen Construction, especially Project Manager Brian Laub and Project Manager Mike Bracken. You helped me greatly during the summer when I was on site, as well as during the two semesters following.



Thank you to MM Architects for providing access to drawings of the project, as well as other resources.

Finally, thank you to the AE Staff and my fellow students. Our staff is second to none, and no staff member (whether I had met them prior to this year or not) hesitated to provide assistance.

Thank you to all who helped me throughout the process, your experience, knowledge, and resources have helped me to produce this document.



APPENDIX A – Phasing Plan and Area Key



PHASE	1
Post 2	
	Prester 1



ral practicut







	PHASING R	Ex.
	PHASE 1	33 JUNE, 2009 - 29 JUNE, 2010
	PHASE 2	28 JUNE, 2018 - 81 JULY, 2011
	PHASE 28	14 JUNE 2010 - 18 AUGUST, 2010
	PHASE 28	28 JUNE, 2918 - 11 DECEMBER, 2819
	PHASE 20	IN SOFTEMBER, 2110-21 DECEMBER, 2010
	PHASE 20	63 JANNUARY, 2011 - 01 JAK # 2011
	PHASE IE	ES JADQUART, 2011 - 21 JANUARY, 2011
	PHASE 27	34 JAKKUART, 2011 - 11 FEBRUART, 2011
	PHASE 25	14 FEBRUARY, 2011 - IN MARCH, 2011
	PHASE 24	67 MARCH, 2011 - 25 MARCH, 2011
	PHASE 22	28 MINUTOR, 2011 - 18 MARK, 2011
	PRASE IV	18 MPRIL 2011 - 36 MAY, 2011
-	PHASE 3	IN ALL'S 2011 - 30 DECEMBER, 2011
	PHASE IA	13 JUNE 3911 - 12 AUGUST, 2011
	PRASE 4	62 JACKURARY, 2012 - 28 SEPTEMBER, 2012
-	PHASE IN	10 AME 3PO -12 NOVEMBER 3P3
	PRASE 48	OS NOVEMBER, 2012 - 20 DECEMBER, 2012

PH.1 BID DOCUMENTS



APPENDIX B – Existing Conditions Site Plan



LEGEND										
ITTILITTIES										
ELECTRIC										
YMBOLS SITE PERIMITER SIDEWALK										
UNIONVILLE HIGH SCHOOL DDITIONS AND RENOVATIONS										
EXISTING CONDITIONS SITE PLAN										
SEPTEMBER. 20TH, 2011										
MICHAEL BEAM - CM										



APPENDIX C – Square Foot Estimate Calculations

Square Foot Cost Estimate Report

Estimate Name:	Unionville SF	
	Kennett Square Pennysylvania	
Building Type: Location: Stories Count (L.F.): Stories Height Floor Area (S.F.): LaborType Basement Included: Data Release: Cost Per Square Foot Total Building Cost	School, High, 2-3 Story with Dec WESTCHESTER, PA 3.00 13.50 319,000.00 Open Shop No Year 2011 Quarter 3 \$121.87 \$38,878,000	orative Concrete Block / Steel Frame Frame of the steel

		% of	Cost Per	
		Total	SF	Cost
A Substructure	E	3.2%	3.86	\$1,231,000
A1010	Standard Foundations		1.08	\$345,500
	Strip footing, concrete, reinforced, load 5.1 KLF, soil bearing capacity 3 KSF, 12" deep x 24" wide			
	Spread footings, 3000 PSI concrete, load 100K, soil bearing capacity 6 KSF, 4' - 6" square x 15" de	ер		
	Spread footings, 3000 PSI concrete, load 150K, soil bearing capacity 6 KSF, 5' - 6" square x 18" de	ер		
A1030	Slab on Grade		1.65	\$525,000
	Slab on grade, 4" thick, non industrial, reinforced			
A2010	Basement Excavation		0.06	\$19,500
	Excavate and fill, 30,000 SF, 4' deep, sand, gravel, or common earth, on site storage			
A2020	Basement Walls		1.07	\$341,000
	Foundation wall, CIP, 4' wall height, direct chute, .148 CY/LF, 7.2 PLF, 12" thick			
B Shell		33.4%	40.71	\$12,987,500
B1010	Floor Construction		14.08	\$4,492,000
	Steel column, W8, 100 KIPS, 16' unsupported height, 31 PLF			
	Steel column, W10, 150 KIPS, 16' unsupported height, 45 PLF			
	Floor, concrete, slab form, open web bar joist @ 2' OC, on W beam and column, 25'x25' bay, 29" d	eep, 100 PSF su	F	
	Fireproofing, gypsum board, fire rated, 2 layers, 1" thick, 8" steel column, 3 hour rating, 14 PLF			
B1020	Roof Construction		2.47	\$786,500
	Floor, steel joists, beams, 1.5" 22 ga metal deck, on columns, 25'x25' bay, 20" deep, 40 PSF super	imposed load, 60)	
B2010	Exterior Walls		8.75	\$2,791,000
	Concrete block (CMU) wall, split rib, 8 ribs, hollow, regular weight, 12x8x16, reinforced, vertical #5	232", grouted		
B2020	Exterior Windows		10.77	\$3,435,000
	Aluminum flush tube frame, thermo-break frame, 2.25" x 4.5", 5'x6' opening, 2 intermediate horizon	tals		
	Glazing panel, insulating, 1/2" thick, 2 lites 1/8" float glass, tinted			
B2030	Exterior Doors		0.49	\$157,500
	Door, aluminum & glass, with transom, narrow stile, double door, hardware, 6'-0" x 10'-0" opening			
	Door, steel 18 gauge, hollow metal, 1 door with frame, no label, 3'-0" x 7'-0" opening			
	Door, steel 24 gauge, overhead, sectional, manual operation, 8'-0" x 8'-0" opening			

		% of Total	Cost Per SF	Cost
B3010	Reaf Coveringe		4 13	\$1 318 500
63010	Roofing single ply membrane EPDM 60 mile fully adhered		4.13	\$1,310,500
	Formed roofing, zinc-conner alloy, standing seam 2-1/2" min slope. 020" thick 0.87 PSF			
	Insulation rigid roof deck polyisocyanurate 2#/CE 2" thick			
	Insulation, rigid, roof deck, polyisocyanurate, tanered for drainage			
	Rese flaching aluminum 016" thick fabric 2 sides 025" aluminum regiet 032" counter flaching			
	Roof edges aluminum, durangelic, 050" thick, 6" face			
B3020	Roof Openinge		0.02	\$7,000
63020	Poof batch with our 1" fiberalass insulation 2' 6" x 2' 0" galvanized steel 165 lbs		0.02	\$7,000
C Intorioro		22.20%	27.03	\$8 624 000
C Interiors	Partitiona	22.270	27.03	\$0,024,000
01010	Parations		0.02	\$2,112,000
	1/2" fire reted rungum beerd taged & finished pointed on motel furring			
04000	1/2 The fatedgypsum board, taped & finished, painted on metal furning		4.40	¢ 474 000
C1020	Interior Doors		1.48	\$471,000
	Door, single leat, kd steel frame, nollow metal, commercial quality, flush, 3-0" X 7-0" X 1-3/8"			
C1030	Fittings		1.15	\$365,500
	l oilet partitions, cubicles, ceiling hung, stainless steel			
	Chalkboards, liquid chalk type, aluminum frame & chalktrough			
C2010	Stair Construction		0.56	\$179,000
	Stairs, steel, cement filled metal pan & picket rail, 16 risers, with landing			
C3010	Wall Finishes		3.45	\$1,099,500
	Painting, masonry or concrete, latex, brushwork, primer & 2 coats			
	Painting, masonry or concrete, latex, brushwork, addition for block filler			
	Wall coatings, acrylic glazed coatings, maximum			
	Ceramic tile, thin set, 4-1/4" x 4-1/4"			
C3020	Floor Finishes		6.79	\$2,166,500
	Carpet, tufted, nylon, roll goods, 12' wide, 36 oz			
	Carpet, padding, add to above, minimum			
	Terrazzo, maximum			
	Vinyl, composition tile, maximum			
C3030	Ceiling Finishes		6.99	\$2,230,500
	Acoustic ceilings, 3/4"mineral fiber, 12" x 12" tile, concealed 2" bar & channel grid, suspended sup	oport		
D Services		37.3%	45.40	\$14,481,500
D1010	Elevators and Lifts		1.01	\$323,500
	2 - Hydraulic, passenger elevator, 2500 lb, 2 floors, 100 FPM			
	Hydraulic passenger elevator, 2500 lb., 2 floor, 125 FPM			
D2010	Plumbing Fixtures		4.92	\$1,570,000
	Water closet, vitreous china, bowl only with flush valve, floor mount			
	Urinal, vitreous china, wall hung			
	Lavatory w/trim, wall hung, PE on CI, 20" x 18"			
	Kitchen sink w/trim, countertop, stainless steel, 44" x 22" triple bowl			
	Lab sink w/trim, polyethylene, single bowl, flanged, 23-1/2" x 20-1/2" OD			
	Service sink w/trim, PE on CI, corner floor, 28" x 28", w/rim guard			
	Service sink w/trim, PE on CI,wall hung w/rim guard, 24" x 20"			
	Group wash fountain, stainless steel, circular, 54" diam			
	Shower, stall, baked enamel, terrazzo receptor, 36" square			
	Water cooler, electric, wall hung, wheelchair type, 7.5 GPH			
D2020	Domestic Water Distribution		0.36	\$116,000
	Gas fired water heater, commercial, 100< F rise, 600 MBH input, 576 GPH			
D2040	Rain Water Drainage		0.66	\$209,500

		% of Total	Cost Per SF	Cost
	Roof drain, Cl, soil,single hub, 4" diam, 10' high			
	Roof drain, CI, soil,single hub, 4" diam, for each additional foot add			
	Roof drain, Cl, soil,single hub, 5" diam, 10' high			
	Roof drain, CI, soil,single hub, 5" diam, for each additional foot add			
D3010	Energy Supply		4.78	\$1,523,500
	Commercial building heating system, fin tube radiation, forced hot water, 100,000 SF, 1mil CF, to	tal 3 floors		
D3030	Cooling Generating Systems		15.65	\$4,992,500
	Packaged chiller, water cooled, with fan coil unit, schools and colleges, 60,000 SF, 230.00 ton			
D4010	Sprinklers		2.53	\$806,500
	Wet pipe sprinkler systems, steel, light hazard, 1 floor, 50,000 SF			
	Wet pipe sprinkler systems, steel, light hazard, each additional floor, 50,000 SF			
D4020	Standpipes		0.29	\$92,000
	Wet standpipe risers, class III, steel, black, sch 40, 6" diam pipe, 1 floor			
	Wet standpipe risers, class III, steel, black, sch 40, 6" diam pipe, additional floors			
D5010	Electrical Service/Distribution		0.57	\$181,000
	Service installation, includes breakers, metering, 20' conduit & wire, 3 phase, 4 wire, 120/208 V, 2	2000 A		
	Feeder installation 600 V, including RGS conduit and XHHW wire, 2000 A			
	Switchgear installation, incl switchboard, panels & circuit breaker, 2000 A			
D5020	Lighting and Branch Wiring		10.01	\$3,193,500
	Receptacles incl plate, box, conduit, wire, 8 per 1000 SF, .9 W per SF, with transformer			
	Wall switches, 2.0 per 1000 SF			
	Miscellaneous power, 1.2 watts			
	Central air conditioning power. 4 watts			
	Motor installation, three phase, 460 V, 15 HP motor size			
	Motor feeder systems, three phase, feed to 200 V 5 HP, 230 V 7.5 HP, 460 V 15 HP, 575 V 20 H	P		
	Fluorescent fixtures recess mounted in ceiling, 1.6 watt per SF, 40 FC, 10 fixtures @32watt per 1			
D5030	Communications and Security		4.06	\$1,295,500
	Communication and alarm systems, includes outlets, boxes, conduit and wire, sound systems, 10	0 outlets		+,,,,-,-
	Communication and alarm systems, fire detection, addressable, 100 detectors, includes outlets, b	oxes, conduit and		
	Fire alarm command center, addressable with voice, excl, wire & conduit			
	Communication and alarm systems includes outlets boxes conduit and wire master clock syste	ms, 50 rooms		
	Communication and alarm systems, includes outlets, boxes, conduit and wire, master TV antenna	a systems.100 outle		
	Internet wiring, 2 data/voice outlets per 1000 S.F.	· · · , · · · · · · · · · · · · · · · · · · ·		
D5090	Other Electrical Systems		0.56	\$178.000
	Generator sets w/battery charger muffler and transfer switch diesel engine with fuel tank 250 k	Ŵ	0.00	¢ 11 0,000
E Equipment & Eurnist	ings	4.0%	4.82	\$1,538,000
E Equipment & Funisi	Institutional Equipment	4.070	1 90	\$606 500
	Architectural equipment laboratory equipment counter tops acid proof economy			\$000,000
	Architectural equipment, laboratory equipment, counter tops, staipless steel			
	Architectural equipment, laboratory equipment, cabinets wall open			
	Architectural equipment, laboratory equipment, cabinets, hase, drawer units			
E1090	Other Equipment		2 92	\$931 500
21000	1200 - Auditorium chair fully unholstered spring seat		2.02	\$201,000
	1500 - Lockers steel baked enamel single tier 60" or 72" minimum			
	1 - Elagnoles, aluminum, tanered, ground set, 20' bink, excludes base or foundation			
	1 - Master time clock system master controller clocks & hells 20 room excl wires & conduits			
	Architectural equipment school equipment haskethall backstops suspended type electrically on	erated		
	Architectural equipment, school equipment bleachers-telescoping, manual operation, 15 tion, accur	nomy (per seat)		
	Architectural equipment, school equipment, weight lifting gym universal economy	ieiii (per sear)		
E Special Construction	, as intestance equipment, concert equipment, weight mung gym, universal, coonomy	0.0%	0 00	¢n
		0.070	0.00	φυ

		% of Total	Cost Per SF	Cost
G Building Sitev	work	0.0%	0.05	\$16,000
G2040	Site Development		0.05	\$16,000
	Specialties, flagpole, on grade, aluminum, tapered, 59' high			
Sub Total		100%	\$121.87	\$38,878,000
Contractor'	's Overhead & Profit	0.0%	\$0.00	\$0
Architectur	ral Fees	0.0%	\$0.00	\$0
User Fees		0.0%	\$0.00	\$0
Total Buil	Iding Cost		\$121.87	\$38,878,000



APPENDIX D – General Conditions Estimate Calculations

CSI Division	Item	Туре	Unit	Unit Cost		Total		Total Including O&P	Quantity	Total Cost Includin O&P		g Total Cost Pe Month	
				Material	Labor	Equipment							
General Requirement	'S												
Summary of Work													
01 11 31.20 0350	Construction Management Fees	\$50M job, min	Project				4%	4%		\$	2,080,000.00	\$	49,523.81
Project Management and Coordination													
01 31 13.20 20	Field Personnel	Clerk, average	Week		410		410	630	183	\$	115,290.00	\$	2,745.00
01 31 13.20 120	Field Personnel	Field Engineer, average	Week		1265		1265	1950	183	\$	356,850.00	\$	8,496.43
01 31 13.20 200	Field Personnel	Project Manager, average	Week		2075		2075	3175	183	\$	581,025.00	\$	13,833.93
01 31 13.20 260	Field Personnel	Superintendent, average	Week		1925		1925	2950	183	\$	539,850.00	\$	12,853.57
01 31 13.30 20	Insurance	Builder's risk, standard, minimum	Job					0.24%		\$	124,800.00	\$	2,971.43
01 31 13.90 20	Performance Bond	For buildings, minimum	dol					2.50%		\$	1,300,000.00	\$	30,952.38
Construction Progress	Documentation												
01 32 13.50 650	Scheduling	Rule of Thumb, CPM, Large job (\$50M +)	Job					0.03%		Ś	156,000,00	Ś	3,714,29
Regulatory Requirement	nts												
01 41 26 50 20	Permits	Rule of Thumb, most cities, minimum	dol					0.50%		Ś	2.600.00	Ś	61.90
Quality Control		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,									_,		
01 45 23 50 50	Testing	Steel building minimum	loh					5200	1	Ś	5 200 00	s	123.81
Construction Facilities	1000118	occer banang, mininan						5200			5,200,000	÷	LUIUI
01 15 13 80 1000	Temporary Facilities	Temporary toilets, rent portable toilet, chemical	Fach	0.11	18.65	56	168	180.1	294	¢	52 949 40	¢	1 260 70
01 52 13 20 400	Office and Storage Space	Trailer furnished no bookups 50'x10' buy	Each	23 300	1175	50	24475	27500	1	ć	27 500 00	ć	654.76
01 52 13 20 100	Office and Storage Space	Storage Box 40'x8' rent per month	Each	23,300	1175		2447.5	102	1	ć	27,300.00	ć	4.90
01 52 13:30 1200	Field Office Expense	Talaphana hill ava hill/month ins. long dist	Month	94			94	90	42	ċ	2 7 2 8 00	ć	99.00
01 52 13.20 140	Field Office Expense	Lights and WAC	Month	61			150	167	42	ې د	3,738.00	ç	167.00
Construction Aids	Field Office Expense	Lights and HVAC	WOITT	132			152	107	42	Ş	7,014.00	Ş	107.00
Construction Alds	Cafata	Cofety Councilies and First Aid Kits	Manth	24.5			24.5	27	42	ć	1 124 00	ć	27.00
0154 09.00 6220	salety	Safety Supplies and First Aid Kits	wonth	24.5			24.5	27	42	Ş	1,134.00	Ş	27.00
Equipment Wobilizatio	n An billion theor	Beer laste halles and a mile source alles	E I		CO	446	405	222		6	222.00		
01 54 36.50 20	Mobilization	Doze, loader, backhoe, excav., grader, paver, roller	Each		69	116	185	233	1	\$	233.00	\$	5.55
01 54 36.50 2100	Mobilization	Crane, truck-mounted, over 75 ton	Each		259	46.5	305.5	440	1	\$	440.00	Ş	10.48
Temporary Barriers and	Enclosures		6.14		0.40	0.45	6.00	0.0	100		000.00		20.40
01 55 23.50 50	Roads and Sidewalks	Roads, gravel fill, no surfaceing, 4" gravel depth	5.¥.	4	2.43	0.45	6.88	8.6	100	\$	860.00	\$	20.48
Temporary Barriers and	Enclosures				-					-			
01 56 26.50 250	Temporary Fencing	Rented chain link, 6' high, over 1000' (up to 12 mo.)	L.F.	10.45	9		19.45	25	4300	\$	107,500.00	Ş	2,559.52
Project Identification													
01 56 13.50 20	Signs	High intensity reflectorized, no posts, buy	S.F.	26.5			26.5	29.5	25	Ş	737.50	Ş	17.56
Examination and Prepa	ration		-							<u> </u>			
01 71 23.13 1100	Construction Layout	Crew for layout of bldg, trenching, 2 person crew	Day		690	69.5	759.5	1125	16	Ş	18,000.00	Ş	428.57
Cleaning and Waste Ma	anagement												
01 76 13.20 20	Cleaning Up	After job completion, minimum	Job				0.30%	0.30%		\$	156,000.00	Ş	3,714.29
Commisioning													
01 91 13.50 150	Building Commisioning	Basic building commissioning, maximum	%				0.50%	0.50%		\$	260,000.00	\$	6,190.48
Existing Condtions													
Surveys													
02 21 13.09 20	Topographical Surveys	Topographical Surveying, conventional, minimum	Acre	18.2	340	21	379.2	565	21	\$	11,865.00	\$	282.50
02 21 13.13 320	Boundary and Survey Markers	Lot location and lines, large quantities, average	Acre	51.5	900	55.5	1007	1500	21	\$	31,500.00	\$	750.00
Selective Demolition													
02 41 19.23 800	Selective Demolition, Rubbish Handling	Dumpster, weekly rental, 1 dump/wk, 30 C.Y. capacity	Week	750			750	825	183	\$	150,975.00	\$	3,594.64
Erosion and Sedimenta	tion Controls												
31 25 14.16 1000	Rolled Erosion Control Mats and Blankets	Silt fence, polypropylene, 3' high, ideal conditions	L.F.	0.41	0.58		0.99	1.34	4300	\$	5,762.00	\$	137.19
									Total Cos	t Ś	4.018.028.90	Ś	95,667,35
									Total Cost with Location Facto	ar S	4,375,633,47	Ś	104.181.75
L			1							· · ·	,	<i></i>	

Item	Туре	Total Cost Including O&P		nthly Cost	Monthly Cost W/ Location Factor			
Field Personnel		\$ 1,593,015.00		\$	37,928.93		\$	41,304.60
Insurance and Bonds		\$ 1,424,800.00		\$	33,923.81		\$	36,943.03
General Construction Costs		\$ 961,755.90		\$	22,898.95		\$	24,936.96
Office and Storage Space		\$ 38,458.00		\$	915.67		\$	997.16
	\$ 4,018,028.90		\$	95,667.35		\$	104,181.75	
	Total Cost with Location Factor	\$ 4,375,633.47		\$	104,181.75		\$	113,453.93

Note: These categories have been developed in order to best summarize the items used in the general conditions estimate. Lumping of specific items gives a quick snapshot of which items contributed what quantity of the total cost.



APPENDIX E – Detailed Project Schedule

ID	0	Task Mode	Task Name		Duration	Start	Finish	January 1	October 1	2/15	July 1	April 1	January 1	4/24	October	1/15	July 1	10/7	April 1
1	-	*	Design Deve	elopment	260 days	Mon 6/16/08	Fri 6/12/09	1/13 3	<i>,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,</i>	2/13	0,20 11,	5,21 0,1	12,12	4/24	5,4	1/10	5/2/	10,7	2,17
2		*	Building D	Design	260 days	Mon 6/16/08	Fri 6/12/09		Building Desig	in .	- /1-2								
3		3	Phase 1 - Ar	ea D	270 days?	Mon 6/15/09	Fri 6/25/10				Phase 1 - A	rea D							
4		*	<new tas<="" td=""><td>.k></td><td></td><td></td><td></td><td></td><td></td><td>-</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></new>	.k>						-									
5			Construct	ion Documents	1 day2	Mon 6/15/00	Mon 6/15/00		Cons	truction F	Desuments								
		P	construct	ion bocuments	I day:	141011 0/ 13/ 03	WOII 0/13/05		cons	Tuction L	Jocuments								
6		*	Obtain	Design From Architect	0 days	Mon 6/15/09	Mon 6/15/09	Obtair	n Design From Arc	hitect 💊	6/15								
7		*	Notice	to Proceed	1 day	Mon 6/15/09	Mon 6/15/09		Notice to Pr	roceed _T e	5/15								
8		*	<new 1<="" td=""><td>Fask></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></new>	Fask>															
9		3	Sitework	and Structure	205 days?	Tue 6/16/09	Mon 3/29/10			Sit	ework and Stru	cture							
10		*	Sitewo	rk	66 days	Tue 6/16/09	Tue 9/15/09		c:+	towork =	- 0/15	•							
11		*	Founda	ations	70 days	Tue 7/14/09	Mon 10/19/09	9	-		3/13								
12	_	*	Steel Er	rection	47 days	Tue 10/20/09	Wed 12/23/09	9	Fou	ndations	10/19								
13		*	Roof Co	onstruction	95 davs	Tue 11/17/09	Mon 3/29/10			Steel Er	rection 🗾 1	2/23							
14		*	<new t<="" td=""><td>Taska</td><td></td><td></td><td></td><td></td><td></td><td>Roof Con</td><td>struction</td><td>3/29</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></new>	Taska						Roof Con	struction	3/29							
15	_	~?			72.42	Thu 40 (40 (00					-								
15		7	Façade		73 days?	Thu 12/10/09	Mon 3/22/10				Faç	ade							
16		*	East Ele	evation Building Façade	69 days	Thu 12/10/09	Tue 3/16/10		East Eleva	tion Build	ing Façade 💼	3/16							
17		*	West E	levation Building Façade	39 days	Tue 12/22/09	Fri 2/12/10		West Eleva	ation Build	ding Façade 💼	2/12							
18		*	South E	Elevation Building Façade	36 days	Fri 1/15/10	Fri 3/5/10		South Ele	vation Bu	ilding Facade	3/5							
19		*	North E	Elevation Building Façade	25 days	Tue 2/16/10	Mon 3/22/10		North	Flevation	Building Facade	3/22							
20	_	*	<new 1<="" td=""><td>ſask></td><td></td><td></td><td></td><td></td><td>Horan</td><td>Lievation</td><td>bunung ruçuuc</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></new>	ſask>					Horan	Lievation	bunung ruçuuc								
21	-	3	Stair Tow	ers	40 days?	Thu 3/4/10	Wed 4/28/10				S	tair Towers							
22		*	MEP Ro	ough In	22 days	Thu 3/4/10	Fri 4/2/10												
23	_	*	Interio	- rs/Finishes	27 days	Fri 3/19/10	Mon 4/26/10				MEP Rough I	n 📷 4/2							
24			MED In	stellation	12 days	Man 4/12/10	Wed 4/28/10				Interiors/Finish	ies 📷 4/26							
24		×.	IVIEP IN	stallation	13 days	Wion 4/12/10	wed 4/28/10				MEP Installa	ition 🝵 4/28							
25		**	<new 1<="" td=""><td>Fask></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></new>	Fask>															
				Task		Project Summ	ary 🔍		Inactive Milestone	• •		Manual Summary R	ollup		Deadline	e	+		
Proje	ct: Tech	2 Detailed	Schedule	Split		External Tasks	_		Inactive Summary	∇	V	Manual Summary			Progress	5	-		_ !
Date	: Fri 10/:	14/11	I	Milestone 🔶		External Miles	tone 🔶		Manual Task	E	3	Start-only	E						
				Summary 🖛		Inactive Task			Duration-only			Finish-only	а						
									Page 1										

ID	0	Task Mode	Task Name	Duration	Start	Finish	January 1	October 1	July 1	April 1 8 3/21 8/1	January 1	October 1 9/4 1/1	July 1	10/7	April 1
26		3	First Floor	158 days?	Wed	Fri 6/25/10	1,15	5/25 20/5	Fi	rst Floor	10/10 4/04	5,4 1,2	5/2/	10,7	2, 2,
27		*	MEP Rough In	56 days	Wed 11/18/09	Wed 2/3/10			MEP Rough In	2/3					
28		*	MEP Layout	39 days	Wed 12/2/09	Mon 1/25/10			MEP Layout	1/25					
29		*	MEP Installation	61 days	Wed 12/9/09	Wed 3/3/10				- 2/2					
30		*	Sprinkler Installation	91 days	Thu 12/31/09	Thu 5/6/10				3/3					
31		*	Interiors/Finishes	80 days	Thu 2/18/10	Wed 6/9/10			Sprinkler Installation	3/6					
32		*	Punchlist	9 days	Tue 6/15/10	Fri 6/25/10			Interiors/Finishes	6/9					
33		*	Substantial Completion First Floor	0 days	Fri 6/25/10	Fri 6/25/10		Punchlist 👖 6/25							
34			<new task=""></new>						Substantial Completion F	First Floor 💊 6/25					
35		-	Second Floor	144 days?	Thu 11/19/09	Tue 6/8/10			Ser	and Floor					
36		~ 	MER Rough In	77 days	Thu 11/19/09	Eri 2/5/10			-						
27		~	MEP Rough III	12 days	Thu 12/10/00	FI 3/5/10			MEP Rough In	3/5					
37		×	MEP Layout	42 days	Thu 12/10/09	FII 2/3/10			MEP Layout	2/5					
38		A .	MEP Installation	60 days	Fri 12/18/09	Thu 3/11/10			MEP Installation	3/11					
39		*	Sprinkler Installation	67 days	Fri 1/22/10	Mon 4/26/10			Sprinkler Installation	4/26					
40		*	Interiors/Finishes	76 days	Thu 2/11/10	Thu 5/27/10			Interiors/Finishes	5/27					
41		*	Punchlist	8 days	Fri 5/28/10	Tue 6/8/10			Р	unchlist 📱 6/8					
42		*	Substantial Completion 2nd Floor	0 days	Tue 6/8/10	Tue 6/8/10			Substantial Completion 2	nd Floor 🔹 6/8					
43		\$	<new task=""></new>												
44		3	Third Floor	151 days	Thu 11/26/09	Fri 6/25/10			Th	ird Floor					
45		*	MEP Rough In	81 days	Thu 11/26/09	Thu 3/18/10			MEP Rough In	3/18					
46		*	MEP Layout	50 days	Fri 12/11/09	Thu 2/18/10			MEP Layout	2/18					
47		*	MEP Installation	65 days	Thu 12/24/09	Wed 3/24/10			MEP Installation	3/24					
48		*	Sprinkler Installation	51 days	Wed 2/3/10	Wed 4/14/10			Sprinkler Installation	4/14					
49		*	Interiors/Finishes	84 days	Wed 2/10/10	Mon 6/7/10			Interiors/Finishes						
50		*	Punchlist	8 days	Tue 6/8/10	Thu 6/17/10				Bunchlist = 6/17					
-								1		uneniist <u>I</u> 0/1/		1			
			Task		Project Summa	ary 🖵		Inactive Milestone	φ.	Manual Summary Roll	lup	Deadline	+		
Proie	ct: Tech 2	2 Detailed	I Schedule Split		External Tasks	_		Inactive Summary	∇ ∇	Manual Summary		Progress	-		_
Date	: Fri 10/1-	4/11	Milestone 🔶		External Miles	tone 🔶		Manual Task	C 3	Start-only	E				
			Summary 🗸		Inactive Task			Duration-only		Finish-only	C				
								Page 2							

ID	0	Task Mode	Task Name	Duration	Start	Finish	January 1 1/13	October 1 5/25 10/5 2/	July 1	April 1 /8 3/21 8/1	January 1 12/12 4/24	October 1 9/4 1/15	July 1 5/27	10/7 2	April 1 2/17
5	L	*	Substantial Completion 3rd Floo	or 0 days	Thu 6/17/10	Thu 6/17/10	-,	Sul	bstantial Completion	3rd Floor 💊 6/17	, , , ,	-,	-,		,
5	2	*	Phase 1 - Area D Substantial	0 days	Fri 6/25/10	Fri 6/25/10	D	hase 1 - Area D Substan	tial Completion and (Occupancy • 6/25					
5	3	3	Phase 2 - Area F New Auditorium	272 days	Wed 6/9/10	Thu 6/23/11		nuse 1 - Area o Substan	tar completion and t	Phase 2 - Area F Ne	ew Auditorium Addition				
5	1	-	Addition Sitework	39 davs	Mon 6/28/10	Thu 8/19/10				Sitework					
			5.0.Controls	2.4	M C/20/10	T									
5	`	×.	E & S Controis	z days	Mon 6/28/10	Tue 6/29/10			E 8	15 Controls \pm 6/29					
5	5	A P	Site Demolition	2 days	Wed 6/30/10	Thu 7/1/10			Site	Demolition $\pm 7/1$					
5	7	*	Roads and Sidewalks	37 days	Wed 6/30/10	Thu 8/19/10			Roads an	d Sidewalks 📷 8/19					
5	3	3	Foundations and Structure	119 days	Wed 6/9/10	Mon				Foundations and St	tructure				
5	9	*	Foundations	64 days	Wed 6/9/10	Mon 9/6/10				•	•				
6)	*	Steel Erection	36 days	Wed 7/28/10	Wed 9/15/10			Fo	undations 9/6					
6	1	*	Roof Construction	67 days	Eri 8/20/10	Mon 11/22/10				Steel Erection 📷 9/1	15				
		<u></u>		07 uays					Ro	of Construction	11/22				
6.	2	3	Façade	56 days	Tue 8/31/10	Tue 11/16/10				Façad	e •				
6	3	*	East Elevation Building Façade	31 days	Tue 9/7/10	Tue 10/19/10			East Elevation	n Building Façade 📷 🗄	10/19				
6	1	*	North Elevation Building Façade	e 20 days	Thu 9/16/10	Wed 10/13/10	D		North Elevatio	n Building Facade 💼 1	10/13				
6	5	*	West Elevation Building Façade	56 days	Tue 8/31/10	Tue 11/16/10			West Flevation	Building Facade	11/16				
6	5	*	2nd Floor	160 days	Tue 9/7/10	Mon 4/18/11			West Lievation		11/10				
6	7	*	MEP Installation	111 days	Tue 9/7/10	Tue 2/8/11				-	~				
6	3	*	Structure	28 days	Thu 9/23/10	Mon 11/1/10				MEP Installation	2/8				
			MED Daugh In	10 40.0	T 0/20/40	have an /22 /4/				Structure 📰	11/1				
0	,	×	MEP Rough In	40 days	Tue 9/28/10	MON 11/22/10)			MEP Rough In 💼	11/22				
7)	*	Interiors/Finishes	81 days	Wed 12/15/10	0 Wed 4/6/11				Interiors/Finishe	es 4/6				
7	L	*	Punchlist	8 days	Thu 4/7/11	Mon 4/18/11					Punchlist 👖 4/18				
7	2	*	Substantial Completion	0 days	Mon 4/18/11	Mon 4/18/11				Substantial C	ompletion 🔺 4/18				
7	3	*	3rd Floor	86 days	Tue 9/21/10	Tue 1/18/11									
7	1	*	MEP Installation	39 days	Tue 9/21/10	Fri 11/12/10									
7	5	*	MEP Rough In	40 days	Mon 10/4/10	Fri 11/26/10				MEP Installation	11/12				
_										MEP Rough In 💼	11/26				
\vdash			Task		Project Summ	arv 💻		Inactive Milestone	÷	Manual Summany Re		Deadline			
Dro	iastı Tark	2 Dotall-	sehedule Split		External Tasks			Inactive Summary		Manual Summary		Progress	_		_
Dat	e: Fri 10/:	2 Detaile	Milestone		External Miles	tone +		Manual Task	E	Start-only	. •	D . 699			
			Summary		Inactive Task			Duration-only		Einish-only	-				
-			Summary		macrive rdSK					- initionity	-				
1								Page 3							

ID	Task Mode	Task Nam	e	Duration	Start	Finish	January 1 1/13	Octo	ber 1 /5 2/15	July 1 6/28 11	April 1 /8 3/21 8/1	January 1 12/12 4/24	October 1 9/4 1/15	July 1 5/27	April 1
76	*	Inte	riors/Finishes	22 days	Wed 12/15/10) Thu 1/13/11	-,		,,	-,,	Interiors/Finish	ies 📺 1/13	-,	-,	
77	*	Pun	chlist	3 days	Fri 1/14/11	Tue 1/18/11					Pup	chlist = 1/18			
78	*	Sub	stantial Completion	0 days	Tue 1/18/11	Tue 1/18/11					Contraction Consult	alian 1 (40			
79	*	Audito	rium/Stage/Balcony	259 days	Mon 6/28/10	Thu 6/23/11					Substantial Comple	2001 - 1/18			
80	*	MEF	P Layout	14 days	Tue 10/5/10	Fri 10/22/10									
81	*	MEE	P Rough In	65 days	Tue 10/12/10	Mon 1/10/11					MEP Layout 冒	10/22			
97		Ctru	stura	E6 days	Mon 10/25/10	Mop 1/10/11					MEP Rough In 📱	1/10			
02		500	ciule .	50 days	10/23/10						Structure	1/10			
83	*	Inte	riors/Finishes	143 days	Tue 11/23/10	Thu 6/9/11					Interiors/Finishe	s 6/9			
84	*	Pun	chlist	10 days	Fri 6/10/11	Thu 6/23/11						Punchlist 📱 6/23			
85	*	Sub	stantial Completion	0 days	Thu 6/23/11	Thu 6/23/11					Substa	ntial Completion 💊 6/23	3		
86	-	Phase 2A Kitchen	- Renovate Library, Caf,	41 days	Wed 6/2/10	Wed 7/28/10				Phase 2	A - Renovate Library,	Caf, Kitchen			
87	*	<new< td=""><td>Task></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></new<>	Task>												
88	-	Area E	- 1st Floor	39 days	Thu 6/3/10	Tue 7/27/10					Area E - 1st Floor				
89	*	Den	nolition	5 days	Thu 6/3/10	Wed 6/9/10				D	= 6/9				
90	*	Stru	cture	5 days	Fri 6/18/10	Thu 6/24/10									
91	*	MEF	P Rough In	10 days	Fri 6/18/10	Thu 7/1/10					Structure T 6/24				
92	*	Inte	riors/Finishes	16 days	Fri 7/2/10	Fri 7/23/10				ME	P Rough In 📱 7/1				
93	*	Pun	chlist	2 days	Mon 7/26/10	Tue 7/27/10				Interio	ors/Finishes 🔲 7/23				
94		Sub	stantial Completion	0 days	Tuo 7/27/10	Tuo 7/27/10					Punchlist $\pm 7/27$				
		300		0 days	100 //2//10	100 //2//10				Substantia	Completion 🔹 7/27				
95	\$	Area E	- 2nd Floor	41 days	Wed 6/2/10	Wed 7/28/10					Area E - 2nd Floor				
96	7	Stru	cture	8 days	Wed 6/2/10	Fri 6/11/10				:	Structure 📱 6/11				
97	*	MEF	PRough In	13 days	Wed 6/9/10	Fri 6/25/10				MEP	Rough In 🍵 6/25				
98	*	MEF	P Installation	8 days	Mon 6/28/10	Wed 7/7/10				MEP	Installation I 7/7				
99	*	Inte	riors/Finishes	21 days	Mon 6/28/10	Mon 7/26/10				Interio	ors/Finishes 💼 7/26				
100	*	Pun	chlist	2 days	Tue 7/27/10	Wed 7/28/10					Punchlist 7/28				
								1			,				
			Task		Project Summ	ary 🖵		Inactive Mil	estone	φ	Manual Summary F	Rollup	Deadline	+	
Project	: Tech 2 Detaile	d Schedule	Split		External Tasks	_		Inactive Sur	nmary	Q	Manual Summary		Progress	-	
Date: Fi	ri 10/14/11		Milestone	*	External Miles	tone 🔶		Manual Tas	k	-	Start-only	E			
			Summany		Inactive Task			Duration or	alw.		Finish-only	1			
					uctive rdsk			Durucion-or	,			-			
1								Page 4							

ID	6	Task Mode	Task Name	!	Duration	Start	Finish	January 1	October 1	July 1	April 1	January 1	October 1	July 1	Ap	oril 1
101	Ŭ	*	Sub	stantial Completion	0 days	Wed 7/28/10	Wed 7/28/10	1/13	5/25 10/5 2/1	13 0/28	11/6 5/21 8/1	12/12 4/24	5/4 1/15	5/21	10/7 2/1	<i>′</i>
102		-	Area H	- 1st Floor	41 davs	Wed 6/2/10	Wed 7/28/10			Substa	Area H - 1st Floor					
		-									-					
103		A .	Asbe	stos Abatement	4 days	Wed 6/2/10	Mon 6/7/10			Asbeste	os Abatement I 6/7					
104		*	Struc	ture	18 days	Thu 6/3/10	Sat 6/26/10				Structure = 6/26					
105		*	Four	idations	9 days	Wed 6/9/10	Mon 6/21/10									
106			MED	Pough In	11 days	Mon 6/14/10	Sat 6/26/10				Foundations 📱 6/21					
100		×	WIEP	Kougii ili	11 days	101011 0/ 14/ 10	5at 0/20/10				MEP Rough In 📱 6/26					
107		A	MEP	Install/Test	24 days	Fri 6/18/10	Wed 7/21/10			N	1EP Install/Test 💼 7/21					
108		*	Inter	iors/Finishes	19 days	Wed 6/30/10	Mon 7/26/10									
109		*	Pupe	hlist	2 days	Tue 7/27/10	Wed 7/28/10			In	iteriors/Finishes 💼 7/26					
		<u></u>	T une	inist	2 0095	140 1/21/10	Wed 7720/10				Punchlist $\pm 7/28$					
110		*	Sub	stantial Completion	0 days	Wed 7/28/10	Wed 7/28/10			Substa	antial Completion 🖕 7/28					
111		3	Phase 2B	& 2C - Renovate District	133 days	Wed 6/30/10	Fri 12/31/10				Phase 2B & 2C - Renova	te District Office				
112		-	Office Area E	- 2nd Floor	133 davs	Wed 6/30/10	Fri 12/31/10				Area E - 2nd	Floor				
		-														
113		A "	Dem	olition	15 days	Wed 6/30/10	Tue 7/20/10				Demolition 🔲 7/20					
114		*	Four	dations	12 days	Wed 7/21/10	Thu 8/5/10				Foundations = 8/5					
115		*	Struc	ture	25 days	Thu 7/29/10	Wed 9/1/10									
116				la stall		N/	NA 11/15/11/				Structure 📷 9/1					
110		X .	MEP	Install	84 days	wed //21/10	WON 11/15/10	,			MEP Install	11/15				
117		*	Inter	iors/Finishes	44 days	Tue 10/19/10	Fri 12/17/10				Interiors/Finishes	12/17				
118		*	Punc	hlist	10 days	Mon 12/20/10	Fri 12/31/10				_					
119		*	Sub	stantial Completion	0 days	Fri 12/31/10	Fri 12/31/10				Punchlis	it 👖 12/31				
		_	546.	tanta completion	o uujo						Substantial Completio	n 💊 12/31				
120		3	Phase 2D & Family	 Renovate HS Offices, Music Dining 	123 days	Thu 1/6/11	Mon 6/27/11				Phase 2D - Renov	vate HS Offices, Music &	Family Dining			
121		3	Area E	- 2nd Floor	84 days	Thu 1/6/11	Tue 5/3/11				4	Area E - 2nd Floor				
122		*	Dem	olition	15 days	Thu 1/6/11	Wed 1/26/11									
4.2.2											Demoliti	on 🔲 1/26				
123		A .	Struc	ture	/ days	Thu 1/2//11	Fri 2/4/11				Struc	ture <u> </u>				
124		*	MEP	Rough In	10 days	Thu 1/27/11	Wed 2/9/11				MEP Roug	rh In = 2/9				
125		*	MEP	Install	47 days	Fri 2/25/11	Mon 5/2/11									
											MEP	Install 5/2				
				Task		Project Summ	ary 💭		Inactive Milestone	÷	Manual Summary Ro	llup	Deadline	+		
Project Date:	t: Tech 2 Fri 10/14	2 Detaileo 1/11	I Schedule	Milestene +		External Tasks			Manual Task	~	Mianual Summary		Progress	-		
		.,		winescone •		External Miles	une 🔹		wanuai rask	-	Start-only	-				
				Summary V		macrive 1dSK			Salation-only		rinsirony	-				
									Page 5							

						-									
10	' a	Task	Task Name		Duration	Start	Finish	January 1	October 1	July 1	April 1	January 1	October 1	July 1	April :
ŀ	126	wiode	Inter	iors/Einishes	27 days	Mon 3/29/11	Tuo 5/2/11	1/13	5/25 10/5 2/	/15 6/28 11/8	5 3/21 8/	1 12/12 4/24	9/4 1/15	5/2/	10// 2/1/
	120	~	inter	iors/rinisnes	27 days	1011 3/20/11	106 5/ 5/ 11				Interio	ors/Finishes 📷 5/3			
F	127	*	Punc	hlist	5 days	Wed 4/27/11	Tue 5/3/11								
												Punchlist 🔳 5/3			
	128	*	Subs	stantial Completion	0 days	Tue 5/3/11	Tue 5/3/11								
		_									Substantia	al Completion 🔷 5/3			
	129	3	Area G	- 2nd Floor	123 days	Thu 1/6/11	Mon 6/27/11					Area G - 2nd Floor			
ŀ	120		Dam	alitian	15 daug	Thu: 1/6/11	Wed 1/26/11								
	150	×	Delli	ontion	15 days	110 1/0/11	weu 1/20/11				Demo	lition 🔲 1/26			
F	131	*	Struc	ture	42 days	Wed 1/26/11	Thu 3/24/11					-			
											Str	ructure 📰 3/24			
	132	*	Foun	dations	12 days	Thu 1/27/11	Fri 2/11/11								
											Found	dations 🗧 2/11			
	133	*	MEP	Rough In	66 days	Thu 1/27/11	Thu 4/28/11				MED D	augh In 4/28			
+	124		MED	Install	out and a so	Thu 1/27/11	Man 6/12/11				WILF N	Jugii III 4/20			
	134	×	IVIEP	Install	96 uays	110 1/2//11	10101 0/13/11				MEP	Install 6/13			
F	135	*	Inter	iors/Finishes	41 days	Wed 4/27/11	Wed 6/22/11								
				-							Inte	riors/Finishes 📰 6/22			
	136	*	Punc	hlist	3 days	Thu 6/23/11	Mon 6/27/11								
												Punchlist T 6/27			
	137	*	Subs	stantial Completion	0 days	Mon 6/27/11	Mon 6/27/11				Subst	antial Completion . 6/23	,		
+	129	-	Dhace 25	Popovato Existing	1E dour	Mon 1/2/11	Eri 1/21/11				Dhase 3E Br	ancial completion 🖕 0/2/	_		
	130	-	Classroom	n nellovate Existing	15 uays	101011 1/3/11	FII 1/21/11				Plidse 2E - Ke		'		
F	139	-	Area E -	- 3rd Floor	15 days	Mon 1/3/11	Fri 1/21/11				A	rea E - 3rd Floor			
		1										**			
	140	*	Dem	olition	3 days	Mon 1/3/11	Wed 1/5/11								
											Demo	lition ± 1/5			
	141	*	MEP	Rough In	2 days	Thu 1/6/11	Fri 1/7/11				MEP Rou	$10 \pm 1/7$			
+	142	-	MED	Install	2 days	Tuo 1/11/11	Thu 1/12/11				WILL NOU	Bu T */ /			
		~	IVILI	liistali	5 days	100 1/11/11	1110 1/15/11				MEP I	Install $\pm 1/13$			
	143	*	Inter	iors/Finishes	7 days	Thu 1/6/11	Fri 1/14/11								
											Interiors/Fin	ishes 📱 1/14			
	144	*	Punc	hlist	2 days	Thu 1/20/11	Fri 1/21/11								
						/ /	/ /				Pu	nchlist ± 1/21			
	145	A.	Subs	stantial Completion	U days	Fri 1/21/11	Fri 1/21/11				Substantial Comp	letion 🔺 1/21			
	146	-	Phase 2F -	- Renovate Existing	15 days	Mon 1/24/11	Fri 2/11/11				Phase 2F - I	Renovate Existing Classroo	m		
		~	Classroom	1	,-		-,, -=								
	147	-	Area E -	- 3rd Floor	15 days	Mon 1/24/11	Fri 2/11/11					Area E - 3rd Floor			
												**			
	148	*	Dem	olition	3 days	Mon 1/24/11	Wed 1/26/11				Dom	alition = 1/26			
+	149	-	MED	Pough In	2 days	Thu 1/27/11	Eri 1/29/11				Dem				
	145	X .	IVIEP	Kough in	2 days	Thu 1/2//11	Fri 1/28/11				MEP Ro	ough In $\pm 1/28$			
F	150	*	MEP	Install	1 dav	Thu 2/3/11	Thu 2/3/11								
											ME	P Install ₁₂ 2/3			
\vdash															
				Task		Project Summ	ary 🗸		Inactive Milestone	Φ.	Manual Summary	Rollup	Deadline	+	
1	roject: Teo	ch 2 Detaileo	d Schedule	Split		External Tasks			Inactive Summary	∇ ∇	Manual Summary		Progress	_	
1	ate: Fri 10	0/14/11		Milestone	•	External Miles	stone 🔶		Manual Task]	Start-only	E			
				Summary		Inactive Task			Duration-only		Finish-only	з			
F									Page 6						
									CAPP D						

ID	_	Task	Task Name	Duration	Start	Finish	January 1	October 1	July 1	April 1	January 1	October 1	July 1	April 1
15	1	Mode	Interiors/Finishes	6 davs	Fri 1/28/11	Fri 2/4/11	1/13	5/25 10/5 2/	15 6/28 11/	/8 3/21 8/	1 12/12 4/24	9/4 1/15	5/27 10/7 2	2/17
				,-	,	,.,				Interiors/F	inishes 🔳 2/4			
15	2	*	Punchlist	2 days	Thu 2/10/11	Fri 2/11/11				P	Punchlist $\pm 2/11$			
15	3	*	Substantial Completion	0 days	Fri 2/11/11	Fri 2/11/11								
15	4	-	Phase 2G - Renovate Existing	15 days	Mon 2/14/11	Fri 3/4/11				Phase 2G - Renovati	Pletion 🔹 2/11	and Classrooms		
		_	Computer Labs and Classrooms								**	elassioonis		
15	5	3	Area E - 3rd Floor	15 days	Mon 2/14/11	Fri 3/4/11					Area E - 3rd Floor			
15	6	*	Demolition	5 days	Mon 2/14/11	Fri 2/18/11				_				
15	7	*	MEP Rough In	2 days	Mon 2/21/11	Tue 2/22/11				De	molition $\pm 2/18$			
				2 00/5		100 1/ 11/ 11				MEP	Rough In <u>T</u> 2/22			
15	8	*	MEP Install	3 days	Wed 2/23/11	Fri 2/25/11				м	EP Install $\pm 2/25$			
15	9	*	Interiors/Finishes	10 days	Mon 2/21/11	Fri 3/4/11								
16	0	*	Punchlist	1 day	Fri 3/4/11	Fri 3/4/11				Interiors	/Finishes 📱 3/4			
	-			,							Punchlist $\pm 3/4$			
16	1	*	Substantial Completion	0 days	Fri 3/4/11	Fri 3/4/11				Substantial Co	mpletion 💊 3/4			
16	2	3	Phase 2H - Renovate Existing	15 days	Mon 3/14/11	Fri 4/1/11				Phase 2	H - Renovate Existing Class	srooms		
16	3	-	Classrooms Area E - 2rd Floor	15 days	Mon 3/14/11	Fri 4/1/11					Area E - 2rd Floor			
	-	~				, _,					**			
16	4	*	Demolition	4 days	Mon 3/14/11	Thu 3/17/11					Demolition $\pm 3/17$			
16	5	*	MEP Rough In	5 days	Tue 3/15/11	Mon 3/21/11								
16	6	*	MFP Install	6 days	Thu 3/17/11	Thu 3/24/11				ME	P Kough In <u>T</u> 3/21			
	-	<u> </u>	incl instan	o duys	1110 3/17/11	1110 57 2-17 22				I	MEP Install I 3/24			
16	7	*	Interiors/Finishes	11 days	Thu 3/17/11	Thu 3/31/11				Interio	rs/Finishes 📱 3/31			
16	8	*	Punchlist	2 days	Thu 3/31/11	Fri 4/1/11					D			
16	9	*	Substantial Completion	0 days	Fri 4/1/11	Fri 4/1/11					Punchilst ±4/1			
				,-						Substantial	Completion 🔷 4/1			
17	0	3	Phase 2I & 2J - Renovate Existing Classrooms	45 days	Mon 4/4/11	Fri 6/3/11				Phase	2I & 2J - Renovate Existing	g Classrooms		
17	1	3	Area E - 1st Floor	45 days	Mon 4/4/11	Fri 6/3/11					Area E - 1st Floor			
17	2	*	Demolition	8 days	Mon 4/4/11	Wed 4/13/11								
	_										Demolition I 4/13			
17	3	*	Structure	3 days	Tue 4/12/11	Thu 4/14/11					Structure ± 4/14			
17	4	*	MEP Rough In	12 days	Fri 4/8/11	Mon 4/25/11					450 Douch In - 4/25			
17	5	*	MEP Install	22 davs	Thu 4/14/11	Fri 5/13/11				W	1EP Kough in 🗧 4/25			
		<u> </u>									MEP Install 💼 5/13			
			Task		Project Summ	ary 🖵		Inactive Milestone	φ	Manual Summary	Rollup	Deadline	+	
Pro	ject: Tech	2 Detaile	d Schedule Split		External Tasks			Inactive Summary	V V	Manual Summary		Progress		-
Dat	e: Fri 10/	14/11	Milestone	•	External Miles	stone 🔶		Manual Task	C 3	Start-only	E			
			Summary		Inactive Task			Duration-only		Finish-only	3			
			I											

D	Task Mode	Task Nam	e	Duration	Start	Finish	lanuary 1 1/13	October 1	July 1 2/15 6/28 11/3	April 1 8 3/21 8/1	January 1 12/12 4/24	October 1 9/4 1/15	July 1 5/27	April : 10/7 2/17
176	*	Inte	riors/Finishes	25 days	Tue 4/26/11	Mon 5/30/11	_,	-,	-, , -,, -	Interi	ors/Finishes m 5/30			
177	*	Pun	chlist	4 days	Tue 5/31/11	Fri 6/3/11					Punchlist = 6/3			
178	*	Sub	stantial Completion	0 days	Fri 6/3/11	Fri 6/3/11								
179	-	Phase 3 -	Renovate Existing	147 days	Thu 6/9/11	Fri 12/30/11				Substant	Phase 3 - Renovat	e Existing Auditorium	n	
100	_	Auditoriu	im		Th. 610/44									
180	\$	Area G	- 2nd Floor	147 days	Thu 6/9/11	Fri 12/30/11					Area G	- 2nd Floor		
181	*	Den	nolition	15 days	Thu 6/9/11	Wed 6/29/11					Demolition 🔳 6/2	9		
182	*	Stru	cture	45 days	Tue 6/21/11	Mon 8/22/11					Structure	8/22		
183	*	MEF	P Rough In	22 days	Thu 7/21/11	Fri 8/19/11					MEP Rough In	8/19		
184	*	MER	PInstall	44 days	Wed 9/21/11	Mon 11/21/1	1							
185	*	Inte	riors/Finishes	50 days	Mon 10/17/11	Fri 12/23/11					MEP Instal	11/21		
186		Pun	chlist	5 days	Mon 12/26/11	Fri 12/30/11					Interiors/Finish	es 📰 12/23		
		T un		5 days							Р	unchlist _I 12/30		
187	A.	Sub	stantial Completion	0 days	Fri 12/30/11	Fri 12/30/11					Substantial Com	pletion 💊 12/30		
188	3	Area E	- 3rd Floor	43 days	Tue 6/14/11	Thu 8/11/11					Area E - 3rd	Floor		
189	*	Den	nolition	8 days	Tue 6/14/11	Thu 6/23/11					Demolition $\pi 6/2$	3		
190	*	Stru	cture	5 days	Mon 6/27/11	Fri 7/1/11					Structure = 7/1			
191	*	MEF	P Rough In	10 days	Mon 6/27/11	Fri 7/8/11					Ministration and			
192	*	MER	Pinstall	10 days	Mon 7/11/11	Fri 7/22/11					MEP Rough In 📱 7/5	3		
193	*	Inte	riors/Finishes	17 days	Mon 7/18/11	Tue 8/9/11					MEP Install 📱 7,	/22		
104		0		2 days	M- + 0/10/11	Thu 0/44/44					Interiors/Finishes 🔳	8/9		
194		Pun	chlist	2 days	Wed 8/10/11	Thu 8/11/11					Punchlist $_{\pm}$	8/11		
195	*	Sub	stantial Completion	0 days	Thu 8/11/11	Thu 8/11/11				Sub	stantialCompletion 🔶	8/11		
196	3	Phase 4 - Wing & V	Renovate Exsiting Tech Ed	212 days	Thu 7/7/11	Fri 4/27/12					Phase 4 - Renovate Ex	siting Tech Ed Wing &	& Weight Ro	om
197	3	Area B	- Foundations and Steel	89 days	Thu 7/7/11	Tue 11/8/11					Area B - Found	ations and Steel		
198	*	Den	nolition	22 days	Thu 7/7/11	Fri 8/5/11					Demolition == 1	2/5		
199	*	Fou	ndations	37 days	Mon 8/8/11	Tue 9/27/11					Foundation -	- 0/27		
200	*	Stru	cture	35 days	Wed 9/21/11	Tue 11/8/11					Foundations	9/2/		
											Structure	11/8		
			Tack		Broject Summ			Inactivo Miloctore		Manual Summers	colluna	Deadline		
Declast	Tech 2 Det-"	od Cobodul-	Split		External Tasks	ary 🗸		Inactive Summary		Manual Summary		Progress	· _	
Project: Date: Fri	i 10/14/11	eu schedulê	Milestone 🌢		External Miles	tone +		Manual Task		Start-only	с			
			Summary		Inactive Task	·····		Duration-only		Finish-only	-			

Image: Construction Constr	ID		Tack	Tack Name		Duration	Start	Finich	lanuary 1		Octobor 1		July 1		April 1		lanuaru	1	Octobor	1	July 1			neil 1
210 4.42.8 - Française 52.4 σyr Wei française Mara Française 221 4.7 Ext Bowton Building Façade 32 days Wei J02/11 Wei J02/21 Wei J02/21 <td></td> <td>0</td> <td>Mode</td> <td>Task Ivallie</td> <td></td> <td>Duration</td> <td>Start</td> <td>Fillisti</td> <td>1/13</td> <td>5/25</td> <td>10/5</td> <td>2/15</td> <td>6/28</td> <td>11/8</td> <td>3/21</td> <td>8/1</td> <td>12/12</td> <td>4/24</td> <td>9/4</td> <td>1/15</td> <td>5/27</td> <td>10/7</td> <td>2/1</td> <td>17</td>		0	Mode	Task Ivallie		Duration	Start	Fillisti	1/13	5/25	10/5	2/15	6/28	11/8	3/21	8/1	12/12	4/24	9/4	1/15	5/27	10/7	2/1	17
243	201		3	Area B	- Façade	52 days	Wed	Thu 12/22/11	-,			-,	0/ 20	/ -	-,	-,-		Ar	rea B - Faça	de	-,		, -	
2	202		*	East	Elevation Building Façade	37 days	Wed 10/12/1	1 Thu 12/1/11																
1 1	203		*	Nort	h Elevation Building Facade	34 days	Wed 10/19/1	1 Mon 12/5/11								East Ele	vation Buil	ding Façad	de 📷 12,	/1				
image Description 2 Junit Multiplie Multiplie Multiplie 100 1	204			Sout	h Elevation Ruilding Eacode	22 days	Wed 11/2/11	Thu 12/15/11								North Ele	vation Buil	lding Faça	de 📰 12	/5				
255 of the Weet Elevation Building Facetal: 22.4ays Weet 11/9/11 The 11/9/11 266 35 Area B. First Floor 135 days Weet 11/9/11 The 47/3/12 276 36 MEP Rough in 24 days Weet 11/9/11 The 47/3/12 The 47	204		×	5000	n Elevation Building Façade	52 uays	wed 11/2/11	Thu 12/15/11								South E	evation Bu	ilding Faça	ade 💼 12	2/15				
265 Area E-Frat Floer 105 days Wed To Un (24/24)/2 (11/00 11/21/2) 267 MEP Rough in 24 days Wed 11/20/11 Mon 12/12/2 268 Area E-Frat Floer 104 days Wed 11/20/11 Mon 12/12/2 269 Area E-Frat Floer 64 days Wed 11/20/11 Mon 12/12/2 210 Area E-Frat Floer 64 days Wed 11/20/11 Won 12/12/1 211 Area E-Frat Floer 64 days Wed 11/20/11 Won 12/12/1 212 Area E-Frat Floer 0 days Wed 4/11/2 Twe 4/24/12 213 Area E-Frat Floer 0 days Wed 12/2/12 Med 3/2/12 214 Area E-Frat Floer Corridor 23 days Twe 1/2/12 Med 3/2/12 215 Area E-Frat Floer Corridor 23 days Twe 1/2/12 Med 3/2/12 216 MEP Rough in 15 days Frie/1/2/12 Med 3/2/12 216 Area E-Frat Floer 9 days Wed 1/2/2/12 Med 3/2/12 217 MeP Rough in 15 days Frie/2/1/1 Mn 13/2/12 218 Area E-Frat Floer 9 days Wed 12/2/12 Med 3/2/12 219 South	205		A	Wes	t Elevation Building Façade	32 days	Wed 11/9/11	Thu 12/22/11								West E	levation Bu	uilding Faç	ade 📰 1	2/22				
207 P MEP Rough In 24 days Med 11/30/11 Mon 1/2/12 208 P MEP Rough In 24 days Med 11/30/11 Mon 1/2/12 208 P MEP Rough In 24 days Med 11/30/11 Wol 1/2/12 209 P Structure 6 days Wed 11/30/11 Wol 1/2/12 Wed 12/2/12 210 P Interiory/Finishes 55 days Wed 12/2/12 Tue 1/2/12 Wed 12/2/12 211 P Punchist 10 days Wed 12/2/12 Tue 1/2/12 Wed 12/2/12 Mon 3/2/12 Mon 3/2/12 Med P Rough In 1/2/02 Med P Rough In 1/2/02 <td< td=""><td>206</td><td></td><td>3</td><td>Area B</td><td>- First Floor</td><td>105 days</td><td>Wed</td><td>Tue 4/24/12</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>Area B -</td><td>First Floo</td><td>r</td><td></td><td></td><td></td></td<>	206		3	Area B	- First Floor	105 days	Wed	Tue 4/24/12											Area B -	First Floo	r			
208 MP MPI install 38 days Tue 1/3/12 Thu 2/3/12 209 Structure 6 days Wed 1/3/3/11 Wed 12/7/12 M67 install 2/3 210 Meriors/Finishes 55 days Wed 1/3/11/12 Tue 4/2/12 Wed 1/3/12 Tue 1/2/12 Mon 3/5/12	207		*	MEP	Rough In	24 days	Wed 11/30/1	1 Mon 1/2/12										MED Pou	uah In	. /2				
223 * Structure 6 days Wed 11/30/11 Wed 12/7/11 210 * Interiors/Finishes 55 days Wed 11/20/12 Tue 4/24/12 Structure 11/27 Structure 11/27 Structure 11/27 211 * Punchlist 10 days Wed 4/11/12 Tue 4/24/12	208		*	MEP	Install	38 days	Tue 1/3/12	Thu 2/23/12										WILF KOU	и д н нт 🛄 .	.,.				
Image: Structure in the st	209		*	Stru	cture	6 days	Wed 11/30/1	1 Wed 12/7/11										ME	P Install 💼	2/23				
 Area B - First Floor Corridor Jodays Wed 4/11/12 Tue 4/24/12 Jodays Wed 4/11/12 Tue 4/24/12 Jue 4/24/12 Tue 4/24/12 Tue 4/24/12 Jue 1/24/12 Mon 3/5/12 Area B - First Floor Corridor Jodays Tue 1/21/12 Tue 4/24/12 MEP Layout 1 Jodays Tue 1/21/12 Tue 4/24/12 MEP Layout 1 Jodays Tue 1/21/12 Tue 4/24/12 MEP Layout 1/20 Jodays Tue 1/21/12 Tue 4/24/12 MEP Layout 1/20 Jodays Tue 1/21/12 Tue 4/24/12 MEP Layout 1/20 Methode Summary Expension Building Facade 1/20 Manual Summary Com Annual Summary Progres	210			Into	iors/Einichos	EE dave	Wod 1/25/12	Tuo 4/10/12										Stru	icture I 12	/7				
211 sr Punchist 10 days Wed 4/1/1/2 Tue 4/24/12 Punchist 9/24 212 sr Substantial Completion 0 days Tue 4/24/12 Tue 4/24/12 Substantial Completion 4/24 213 S Area B - First Floor Corridor 29 days Tue 1/24/12 Wed 1/1/2/12 Wed 1/1/2/11 Wed 1/1/2/11 Wed 1/1/2/12 Wed 1/1/2/12 Wed 1/1/2/11 Wed 1/1/2/11 Wed 1/1/2/11 Wed 1/1/2/11 <td< td=""><td>210</td><td></td><td>×</td><td>inter</td><td>iors/ Finishes</td><td>55 uays</td><td>Weu 1/23/12</td><td>100 4/10/12</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>Interiors</td><td>s/Finishes</td><td>4/</td><td>10</td><td></td><td></td><td></td></td<>	210		×	inter	iors/ Finishes	55 uays	Weu 1/23/12	100 4/10/12										Interiors	s/Finishes	4/	10			
212 substantial Completion 0 days Tue 4/24/12 Tue 4/24/12 213 3 Area 8 - First Floor Corridor 29 days Tue 1/24/12 Mon 3/5/12 214 MP Payout 1 day Tue 1/24/12 Wei 1/25/12 Mon 3/5/12 215 MP Payout 1 day Tue 1/24/12 Wei 1/25/12 Mon 1/30/12 215 MP Payout 1 day Tue 1/24/12 Wei 1/25/12 Mon 1/30/12 216 MP Payout 1 day Tue 1/24/12 Mon 1/30/12 Mon 1/30/12 216 MP Payout 1 day Wei 1/25/12 Mon 3/5/12 More 1/30/12 217 Area C - Foundations and Steel 121 days Mon 3/5/12 Mon 3/5/12 218 Area C - Foundations 25 days Fri 1/3/11 Thu 2/2/12 220 Area C - Foundations 25 days Fri 1/2/3/11 Fri 1/2/3/11 222 Area C - Foundations Building Fagade 23 days Wei 1/23/11 Fri 1/2/3/11 222 Area B - First Floor 16 days Fri 1/1/3/11 Fri 1/2/3/11 More Miestone 223 Area B - First Floor	211		A	Puno	chlist	10 days	Wed 4/11/12	Tue 4/24/12											Pund	:hlist 🛯 4,	/24			
213 3 Area B - First Floor Corridor 29 days Tue 1/24/12 Mon 3/5/12 214 MEP Layout 1 day Tue 1/24/12 Wed 1/25/12 MEP Rough in 2 days Fri 1/27/12 Mon 1/30/12 215 MEP Rough in 2 days Fri 1/27/12 Mon 1/30/12 MEP Rough in	212		*	Sub	stantial Completion	0 days	Tue 4/24/12	Tue 4/24/12										Substan	ntial Comple	etion 💊 4	/24			
224 MEP Layout 1 day Tue 1/24/12 Wed 1/25/12 215 MEP Rough in 2 days Fri 1/27/12 Mon 1/30/12 216 MEP Rough in 1 day Tue 1/24/12 Mon 1/30/12 217 MEP Rough in 1 day Fri 1/27/12 Thu 2/16/12 218 Area C - Foundations and Steel 121 days Tue 3/18/11 Thu 2/2/12 220 Area C - Foundations and Steel 121 days Fri 9/23/11 Thu 2/2/12 220 Area C - Façade 88 days Wed 11/9/11 Fri 12/30/11 222 Area C - Façade 88 days Wed 11/9/11 Fri 12/30/11 223 Area C - Façade 23 days Wed 11/9/11 Fri 12/30/11 224 Area B - First Floor 116 days Fri 11/18/11 Fri 12/23/11 224 Area B - First Floor 116 days Fri 11/18/11 Fri 12/23/11 224 Area B - First Floor 116 days Fri 11/18/11 Fri 12/23/11 224 Area B - First Floor 116 days Fri 11/18/11 Fri 12/23/11 225 Area B - First Floor 116 days	213		3	Area B	- First Floor Corridor	29 days	Tue 1/24/12	Mon 3/5/12										А	Area B - Firs	t Floor Co	rridor			
215 MEP Rough In 2 days Fri 1/27/12 Mon 1/30/12 216 MEP Istall 15 days Fri 1/27/12 Thu 2/16/12 217 MEP Istall 15 days Fri 1/27/12 Thu 2/16/12 218 The Area C - Foundations and Steel 12 days Thu 8/18/11 Thu 2/2/12 218 The Area C - Foundations and Steel 12 days Thu 8/18/11 Thu 2/2/12 220 The Structure 95 days Fri 9/2/11 Fri 12/30/11 222 Area C - Foundations and Steel 21 days Wed 11/9/11 Fri 12/9/11 222 Area C - Facade 95 days Fri 9/2/11 Fri 12/9/11 223 Area C - Facade 23 days Wed 11/9/11 Fri 12/9/11 223 Area B - First Floor 116 days Fri 11/2/9/11 Fri 12/9/11 224 Area B - First Floor 116 days Fri 11/18/11 Fri 4/27/12 Project: Tech 2 Detailed Schedule Task Foundatione Manual Summary Olup Decadine Project: Tech 2 Detailed Schedule Task Split External Milestone Manual Task Start-only C	214		*	MEP	Layout	1 day	Tue 1/24/12	Wed 1/25/12																
216 Image: Control of the control o	215		*	MEP	Rough In	2 days	Fri 1/27/12	Mon 1/30/12										м	EP Layout	E1/25				
217 Interiors/Finishes 19 days Wed 2/8/12 Mon 3/5/12 218 Interiors/Finishes 19 days Wed 2/8/12 Mon 3/5/12 218 Foundations and Steel 121 days Thu 8/18/11 Thu 2/2/12 229 Foundations 26 days Thu 8/18/11 Thu 2/2/12 220 Foundations 26 days Fri 9/23/11 Thu 2/2/12 221 Area C - Foundation Building Façade 23 days Wed 11/9/11 Fri 12/30/11 222 North Elevation Building Façade 23 days Wed 11/9/11 Fri 12/30/11 222 North Elevation Building Façade 23 days Wed 11/30/11 Fri 12/30/11 223 South Elevation Building Façade 23 days Wed 11/30/11 Fri 12/30/11 224 West Elevation Building Façade 23 days Wed 11/30/11 Fri 12/30/11 224 West Elevation Building Façade 23 days Wed 11/30/11 Fri 12/23/11 225 Area B - First Floor 116 days Fri 11/18/11 Fri 4/27/12 Manual Summary Progress Fri 10/14/	216		*	MEP	Install	15 days	Fri 1/27/12	Thu 2/16/12										MEP	PRough In :	E 1/30				
11 x* Interiors/Finishes 19 days Wed 2/8/12 Mon 3/2/12 218 3 Area C - Foundations and Steel 121 days Thu 8/18/11 Thu 2/2/12 219 * Foundations 26 days Thu 8/18/11 Thu 2/2/12 220 * Structure 95 days Fri 9/23/11 Thu 2/2/12 221 * Area C - Façade 38 days Wed 11/9/11 Fri 12/30/11 222 * North Elevation Building Façade 23 days Wed 11/2/11 Fri 12/30/11 Fri 12/3/11 223 * South Elevation Building Façade 23 days Wed 11/3/11 Fri 12/3/11 Fri 4/27/12 South Elevation Building Façade 12/2 223 * Mest Elevation Building Façade 23 days Wed 11/3/11 Fri 12/30/11 South Elevation Building Façade 12/23 224 * West Elevation Building Façade 23 days Wed 11/3/11 Fri 4/27/12 Mest Televation Building Façade 12/23 225 * Area B - First Floor 116 days Fri 1/18/11 Fri 4/27/12 Manual Summary Manual Summary Project Summary Fright-Fri 10/14/11 <td></td> <td></td> <td></td> <td></td> <td></td> <td>15 44,5</td> <td></td> <td>N</td> <td>AEP Install</td> <td>2/16</td> <td></td> <td></td> <td></td> <td></td>						15 44,5												N	AEP Install	2/16				
228 Image: Second actions and Steel 121 days Thu B/18/11 Thu 2/2/12 229 Foundations 26 days Thu 8/18/11 Thu 9/22/11 220 Image: Structure 95 days Fri 9/23/11 Thu 2/2/12 221 Image: Structure 95 days Fri 9/23/11 Thu 2/2/12 221 Image: Structure 95 days Fri 9/23/11 Thu 2/2/12 222 Image: Structure 95 days Wed 11/9/11 Fri 12/30/11 222 Image: Structure 95 days Wed 11/9/11 Fri 12/3/11 222 Image: Structure 92 days Wed 11/3/11 Fri 12/3/11 223 Image: Structure 23 days Wed 11/3/11 Fri 12/3/11 224 Image: Structure 23 days Wed 11/3/11 Fri 4/27/12 South Elevation Building Façade 225 Area B - First Floor 116 days Fri 1/18/11 Fri 4/27/12 Mause: Structure Manual Summary Manual Summary Progets Project: Tech 2 Detailed Schedule Date: Firi 10/14/11 Split External Milestone	21/		A .	Inter	iors/Finishes	19 days	Wed 2/8/12	Mon 3/5/12										Interio	rs/Finishes	3/5				
229 Image: Providations of the system of	218		3	Area C	- Foundations and Steel	121 days	Thu 8/18/11	Thu 2/2/12										Area C - Fo	oundations	and Steel				
220 * Structure 95 days Fri 9/23/11 Thu 2/2/12 221 * Area C - Façade 38 days Wed 11/9/11 Fri 12/30/11 222 * North Elevation Building Façade 23 days Wed 11/9/11 Fri 12/9/11 223 * South Elevation Building Façade 23 days Wed 11/23/11 Fri 12/30/11 224 * West Elevation Building Façade 23 days Wed 11/30/11 Fri 12/30/11 224 * West Elevation Building Façade 23 days Wed 11/30/11 Fri 12/30/11 225 * Area B - First Floor 116 days Fri 1/18/11 Fri 4/27/12 Vest Elevation Building Façade Project: Tech 2 Detailed Schedule Project: Tech 2 Detailed Schedule Split External Tasks Inactive Milestone Manual Summary Manual Summary Progress + Milestone Inactive Task Start-only E E + Bate Simmary Inactive Task Inactive Summary Start-only E - - <td>219</td> <td></td> <td>*</td> <td>Four</td> <td>ndations</td> <td>26 days</td> <td>Thu 8/18/11</td> <td>Thu 9/22/11</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>Foun</td> <td>dations 🗖</td> <td>9/22</td> <td></td> <td></td> <td></td> <td></td> <td></td>	219		*	Four	ndations	26 days	Thu 8/18/11	Thu 9/22/11									Foun	dations 🗖	9/22					
221 Image: Structure in the second secon	220		*	Stru	cture	95 days	Fri 9/23/11	Thu 2/2/12												2/2				
222 Image: Control of the second contex and control of the secon	221		_	A	Facada	20 daug	Wed 11/0/11	F=: 12/20/11										structure		2/2				
222 Image: South Elevation Building Façade 23 days Wed 11/9/11 Fri 12/9/11 223 South Elevation Building Façade 23 days Wed 11/23/11 Fri 12/23/11 224 Image: South Elevation Building Façade 23 days Wed 11/30/11 Fri 12/23/11 224 Image: South Elevation Building Façade 23 days Wed 11/30/11 Fri 12/23/11 South Elevation Building Façade 12/23 225 Image: South Elevation Building Façade 23 days Wed 11/30/11 Fri 12/23/11 Fri 12/30/11 West Elevation Building Façade 12/23 225 Image: South Elevation Building Façade 23 days Wed 11/30/11 Fri 12/30/11 Fri 12/30/11 Mest Elevation Building Façade 12/23 225 Image: South Elevation Building Façade 23 days Wed 11/30/11 Fri 12/30/11 Mest Elevation Building Façade 12/23 225 Image: South Elevation Building Façade 11/30/11 Fri 12/30/11 Mest Elevation Building Façade 12/23 226 Area B - First Floor 116 days Fri 11/18/11 Fri 42/7/12 Mest Elevation Building Façade 12/30 Project: Tech 2 Detailed Schedule Task Pr	221		\$	Area C	- Façade	50 days	wed 11/9/11	FII 12/30/11										,	Area C - Faç	ade				
223 South Elevation Building Façade 23 days Wed 11/23/11 Fri 12/23/11 224 * West Elevation Building Façade 23 days Wed 11/30/11 Fri 12/30/11 225 * Area B - First Floor 116 days Fri 11/18/11 Fri 4/27/12 Vest Elevation Building Façade 23 days Wed 11/23/11 Fri 12/30/11 Project: Tech 2 Detailed Schedule Split External Tasks Inactive Milestone Manual Summary Progress Milestone External Tasks Duration-only Start-only E Date: Fri 10/14/11 Inactive Task Duration-only J Inactive Annual Summary J	222		A	Nort	h Elevation Building Façade	23 days	Wed 11/9/11	Fri 12/9/11								North E	levation Bu	uilding Faç	ade 💼 12;	/9				
224 * West Elevation Building Façade 23 days Wed 11/30/11 Fri 12/30/11 225 * Area B - First Floor 116 days Fri 11/18/11 Fri 4/27/12 West Elevation Building Façade 23 days Wed 11/30/11 Fri 4/27/12 West Elevation Building Façade 21 days Fri 11/18/11 Fri 4/27/12 West Elevation Building Façade 21 days Project: Tech 2 Detailed Schedule Split External Tasks Inactive Summary Manual Summary Progress Milestone External Milestone Manual Task Start-only E Summary Inactive Task Duration-only Start-only Imactive Task	223		*	Sout	h Elevation Building Façade	23 days	Wed 11/23/1	1 Fri 12/23/11								South	Elevation B	Building Fa	içade 📺 1	2/23				
225 Area B - First Floor 116 days Fri 11/18/11 Fri 4/27/12 Area B - First Floor Area B - First Floor Project: Tech 2 Detailed Schedule Split Fri 11/18/11 Fri 4/27/12 Inactive Milestone Manual Summary Rollup Deadline Date: Fri 10/14/11 External Tasks Inactive Summary Manual Summary Progress	224		*	Wes	t Elevation Building Façade	23 days	Wed 11/30/1	1 Fri 12/30/11								Wort	Elevation	Puilding E:		2/20				
Project Tech 2 Detailed Schedule Date: Fri 10/14/11 Date: Fri 10/14/11 Project Tech 2 Detailed Schedule Date: Fri 10/14/11 Project Tech 2 Detailed Schedule Split Milestone External Tasks Milestone Inactive Summary Inactive Summary Milestone Inactive Summary Manual Task Duration-only Inactive Summary Manual Summary Finish-only Inactive Summary Milestone Inactive Summary Manual Summary Manual Summary Finish-only Inactive Task	225		3	Area B	- First Floor	116 days	Fri 11/18/11	Fri 4/27/12								west	Lievation	bunung re	Area B -	First Floor	r			
Project Tech 2 Detailed Schedule Task Project Summary Inactive Milestone Manual Summary Rollup Deadline + Date: Fri 10/14/11 Split External Tasks Inactive Summary Manual Summary Progress - Date: Fri 10/14/11 External Milestone External Milestone Manual Task Start-only E Ummary Inactive Task Duration-only Finish-only I	-																							
Task Project: Tach 2 Detailed Schedule Split Inactive Milestone Manual Summary Rollup Deadline + Date: Fri 10/14/11 Milestone External Tasks Inactive Summary Manual Summary Progress - Jummary External Milestone Manual Task Start-only C - -	<u> </u>																							
Project: Tech 2 Detailed Schedule Split External Tasks Inactive Summary Manual Summary Progress Date: Fri 10/14/11 Milestone External Milestone Inactive Task Duration-only Finish-only Inactive Task Duration-only Finish-only Inactive Task Inactive Task					Task 🗾		Project Summ	ary 🖵		Inactiv	e Milestone		÷	,	Manual Sum	mary Roll	up		Deadline	•	+			
Date: Fri 10/14/11 Milestone	Projec	t: Tech	2 Detailed	d Schedule	Split		External Tasks	_		Inactiv	e Summary		V.	- V 1	Manual Sum	mary	-		Progress		-			
Summary Inactive Task Duration-only Finish-only J	Date:	Fri 10/1	4/11		Milestone 🔶		External Miles	tone 🔶		Manua	al Task				Start-only		E							
Page 9					Summary 🖛		Inactive Task			Durati	on-only			F	inish-only		Ъ							
	-									Page					.,									

ID	0	Task Mode	Task Name		Duration	Start	Finish	January 1 1/13	5/25	October 1 10/5	2/15	July 1 6/28	11/8	April 1 3/21	8/1	January	1 4/24	October 1 9/4 1/1	July	L 10/	April 1
226		*	Struc	ture	21 days	Fri 11/18/11	Fri 12/16/11	1,10	5,25	2075	2,25	0/20	11,0	5/21	0,1	12,12	Struct	ture 🔲 12/16	5 5,2,	10,	, ,,,,,,
227		*	MEP	Rough In	43 days	Mon 11/21/1	1 Wed 1/18/12										MFP Roue	h n === 1/18			
228		*	MEP	Install	56 days	Mon 12/12/1	1 Mon 2/27/12										MEP	nstall 2	/27		
229		*	Inter	iors/Finishes	58 days	Wed 1/25/12	Fri 4/13/12										Interiors	/Finishes	4/13		
230		*	Punc	hlist	9 days	Tue 4/17/12	Fri 4/27/12											Punchlist	= A/27		
231		*	Subs	tantial Completion	0 days	Fri 4/27/12	Fri 4/27/12										Substan	tial Completion	▲ 4/27		
232		3	Phase 4A	- Renovate Existing	92 days	Thu 5/24/12	Fri 9/28/12										Phase 4	A - Renovate Exi	isting Gymn	sium, L	ocker & Team
233		3	Roof	in, Locker & Team Kooms	10 days	Thu 5/24/12	Wed 6/6/12												Roof	Ĭ	
234		*	Demo	olition	10 days	Thu 5/24/12	Wed 6/6/12											Demoliti	on 🛯 6/6		
235		3	1st Floo	or	91 days	Fri 5/25/12	Fri 9/28/12												1st Floo	r	
236		*	MEP	Rough In	19 days	Mon 6/4/12	Thu 6/28/12											MEP Roug	- h In 💼 6/28		
237		*	MEP	Install	65 days	Fri 5/25/12	Thu 8/23/12											MEP Inst	all	8/23	
238		*	Foun	dations	5 days	Wed 5/30/12	Tue 6/5/12											Foundatio	ons 1 6/5		
239		*	Struc	ture	20 days	Mon 6/4/12	Fri 6/29/12											Struct	ure 💼 6/29		
240		*	Inter	iors/Finishes	47 days	Fri 7/13/12	Mon 9/17/12											Interiors/Fi	nishes	9/17	
241		*	Punc	hlist	10 days	Mon 9/17/12	Fri 9/28/12												Punchlist	9/28	
242		*	Subs	tantial Completion	0 days	Fri 9/28/12	Fri 9/28/12											Substantial	Completion	9/28	1
243		3	Phase 4B - Gym	- Demolish Esiting Auxiliar	y 45 days	Mon 4/30/12	Fri 6/29/12										Ρ	hase 4B - Demo	lish Esiting /	uxiliary	Gym
244		*	Demolit	tion	22 days	Mon 4/30/12	Tue 5/29/12											Demolition	n 💼 5/29		
245		*	Sitewor	k	23 days	Wed 5/30/12	Fri 6/29/12											Sitew	ork 💼 6/29		
246		*	Project Su Turnover	bstantial Completion and	0 days	Fri 6/29/12	Fri 6/29/12								Pro	ject Substa	antial Comp	letion and Turn	over 💊 6/2	9	
				Task		Project Summ	ary 🖵		Inactiv	ve Mileston		ŵ.		Manual Sur	mmary Roll	up		Deadline			
Project	t. Tech 3	2 Detailor	d Schedula	Split		External Tasks		_	Inacti	ve Summarv		V		Manual Sur	mmary	-		Progress			
Date:	Fri 10/14	4/11	assineatile	Milestone	•	External Miles	stone +		Manu	al Task		C	2	Start-only		E					
				Summary		Inactive Task			Durat	ion-only				Finish-only		3					
-									Page	10				,		_					



APPENDIX F – Interview with Wohlsen PM Brian Laub



Interview with Wohlsen PM Brian Laub

1. Who was the driving force behind using a Single Prime delivery method for the UHS project?

The school district

2. Why was a Single Prime delivery method preferred to a Multiple Prime delivery method?

Because the school had lots of issues and law suits on previous project with using multiple prime contracts.

3. How did Wohlsen/UCFSD get the exemption from the Separation Act to use a Single Prime delivery method in PA?

The school applied for a waiver to have the project be single prime.

4. Has the single prime been a good method during the project or have any issues come up?

It has been a good method for the school as they only have one person they need to contact.

5. What are the major benefits of using Single Prime on a job like this as opposed to Multiple Prime?

The owner does not need to hire a CM to manage the work. They have 1 person to contact it there are issues.

6. Who reports to whom during the project, and why? (ex. Wohlsen reports to Unionville School District, etc)

All of the subcontractors report to Wohlsen and Wohlsen reports to the school district and architect.

7. Are there any downfalls to using a Single Prime delivery method?

Not that I am aware of

8. Do you have experience on other school projects, what delivery method was used on those projects, and what were the differences?

I have been involved in both single and multiple prime contacts on school. The difference is on the multiple primes the control of a prime is harder because they are not reporting directly to you and you are not paying their bills. Sometime they have their own agenda in mind.



APPENDIX G – Delivery Method Diagrams



Multiple Prime Delivery Method





Single Prime Delivery Method





APPENDIX H – Potential Roof Regions for PV Array



Potential Roof Areas for PV Array





APPENDIX I – PV Array Shadow Analysis Images


Shadow Analysis Images

































APPENDIX J – Selected Roof Regions for PV Array Installation



Potential Roof Areas for PV Array





Givens:					
N-S Spacir	ng: 12' from fro	ont to front			
# of Rows	= (Length)/(12	2' spacing) + 1	(front edge)		
Panel wid	th (E-W) = 3.42	2ft (Note will	be installed edge	to edge)	
Building	Length (N-S)	Width (E-W)	Number of Rows	Number of Panels	Number of Panels
Area	ft	ft	in Area	in row	in Area
A1	96	86	9.00	25.15	225
B1	34	75	3.83	21.93	63
D1	40	90	4.33	26.32	104
D2	40	50	4.33	14.62	56
D3	36	52	4.00	15.20	60
E1	140	40	12.67	11.70	132
E2	36	50	4.00	14.62	56
E3	50	42	5.17	12.28	60
E4	24	40	3.00	11.70	33
F1	26	36	3.17	10.53	30
G1	90	52	8.50	15.20	120
H1	36	88	4.00	25.73	100
Total					1039



APPENDIX K – Solar Panel & Inverter Specifications

SUNPOWER

E19 / 320 SOLAR PANEL

MAXIMUM EFFICIENCY AND PERFORMANCE

BENEFITS

Highest Efficiency

SunPower[™] Solar Panels are the most efficient photovoltaic panels on the market today.

More Power

Our panels produce more power in the same amount of space—up to 50% more than conventional designs and 100% more than thin film solar panels.

Reduced Installation Cost

More power per panel means fewer panels per install. This saves both time and money.

Reliable and Robust Design

Proven materials, tempered front glass, and a sturdy anodized frame allow panel to operate reliably in multiple mounting configurations.







The planet's most powerful solar panel.

The SunPower[™] 320 Solar Panel provides today's highest efficiency and performance. Utilizing 96 back-contact solar cells, the SunPower 320 delivers a total panel conversion efficiency of 19.6%. The 320 panel's reduced voltage-temperature coefficient, anti-reflective glass and exceptional low-light performance attributes provide outstanding energy delivery per peak power watt.





SPR-320E-WHT-D

SUNPOWFR

Front Glass

Junction Box

Output Cables

Frame

Weight

E19 / 320 SOLAR PANEL

UM EFFICIENCY AND PERFORMANCE

		_ 1\	MAXIM
	Electrica	l Data	
Peak Power (+5/-39	(iest Conditions (SIC): Irradiance o	Pmax	320 W
Efficiency		η	19.6 %
Rated Voltage		V _{mpp}	54.7 V
Rated Current		I _{mpp}	5.86 A
Open Circuit Voltag	e	V _{oc}	64.8 V
Short Circuit Curren	t	I _{sc}	6.24 A
Maximum System V	oltage	UL	600 V
Temperature Coeffic	ients	Power (P)	-0.38% / K
		Voltage (V _{oc})	-176.6mV / K
		Current (I _{sc})	3.5mA / K
NOCT			45° C +/-2° C
Series Fuse Rating			15 A
	Mechanic	al Data	
Solar Cells	96 SunPower all-b	ack contact monoci	vstalline

96 SunPower all-back contact monocrystalline High transmission tempered glass with

1000mm length cables / MultiContact (MC4) connectors

anti-reflective (AR) coating

(silver); stacking pins 41.0 lbs (18.6 kg)

IP-65 rated with 3 bypass diodes Dimensions: 32 x 155 x 128 (mm)

Anodized aluminum alloy type 6063



Current/voltage characteristics with dependence on irradiance and module temperature.

Tested Operating Conditions				
Temperature	-40° F to +185° F (-40° C to + 85° C)			
Max load	113psf 550 kg/m ² (5400 Pa), front (e.g. snow) w / specified mounting configurations 50 psf 245 kg/m ² (2400 Pa) front and back – e.g. wind			
Impact Resistance	Hail 1 in (25 mm) at 51mph (23 m/s)			
Warranties and Certifications				

Warranties and Certifications				
Warranties	25 year limited power warranty			
	10 year limited product warranty			
Certifications	Tested to UL 1703. Class C Fire Rating			



CAUTION: READ SAFETY AND INSTALLATION INSTRUCTIONS BEFORE USING THE PRODUCT. Visit sunpowercorp.com for details

SUNPOWER and the SUNPOWER logo are trademarks or registered trademarks of SunPower Corporation. © September 2010 SunPower Corporation. All rights reserved. Specifications included in this datasheet are subject to change without notice.

Dimensions

PowerGate Plus 375 kW UL

PVS-375-UL

Satcon PowerGate Plus PV inverters are the world's most widely deployed solutions, powering many of the largest commercial and utility-scale solar installations.

Advanced Performance

With their advanced system intelligence, next-generation EDGE® MPPT technology, and industrial-grade engineering, PowerGate® Plus inverters maximize system uptime and power production, even in cloudy conditions.

Utility-Ready Features

- Open communication protocol, compatible with virtually any third-party monitoring system and easily integrated into SCADA systems allowing fast communications
- Remote control of real and reactive power
- Low-voltage ride through
- Power factor control
- Simplified grid interconnection

EDGE MPPT

- Provides rapid and accurate control that boosts PV plant kilowatt yield
- Provides a wide range of operation across all photovoltaic cell technologies

Printed Circuit Board Durability

 Conformal coated to withstand extreme humidity and air-pollution levels



Profitable PV Power

The Satcon[®] PowerGate[®] Plus 375 kW PV inverters have a significant impact on the profitability dynamic of large-scale solar PV systems. With its system intelligence, next-generation EDGE[®] MPPT technology and industrial-grade engineering, the PowerGate Plus 375 kW inverters maximize system uptime and power production, even in the harshest environments.

Advanced, Rugged, and Reliable

Engineered from the ground up to meet the demands of large-scale installations, Satcon PV inverters feature an outdoor-rated enclosure, advanced monitoring and control capabilities and EDGE, Satcon's next-generation MPPT solution.

Proven Performance

The proven leader in solar PV inverter solutions for commercial installations, Satcon sets the standards for efficient large-scale power conversion.

Increased PV Plant Yield

At the heart of PowerGate Plus is EDGE, Satcon's next-generation power optimization solution. With rapid and accurate MPPT control, EDGE increases PV plant kWh yield by extending the production window of arrays, enabling them to operate at optimal voltage and current levels for longer periods of time—even in varied sun conditions. To maximize efficiency, EDGE improves the performance of all PV technologies, including fixed and tracking solar arrays, enabling you to get the most from your investment.



PowerGate Plus 375 kW UL

Streamlined Design

With all components encased in a single, space-saving enclosure, PowerGate Plus PV inverters are easy to install, operate and maintain.

Rugged Construction

- Engineered for outdoor environments
- Wide thermal operating range: from -4° F to +122° F (-20° C to +50° C) without derating
- Solar shield attached to exterior of enclosure dissipate solar radiation, reduce heat buildup
- Dual cooling fans
- Single cabinet with small footprint

Easy Maintenance

- Modular components make service efficient
- Convenient access to all components
- Customizable large in-floor cable gland plates make installation of DC and AC cables easy
- Integrated DC two-pole disconnect switch isolates the inverter, with the exception of the GFDI (Ground Fault Detection and Interruption) circuit, from the photovoltaic power system to allow inspection and maintenance

Proven Reliability

Rugged and reliable, PowerGate Plus PV inverters are engineered from the ground up to meet the demands of large-scale installations.

Safety

- UBC seismic Zone 4 compliant
- Built-in DC and AC disconnect switches
- Protective covers over exposed power connections

Output Transformer

- Provides galvanic isolation
- Matches the output voltage of the PV inverter to the grid

PowerGate Plus 375 kW Spec	ifications	UL/CSA			
Input Parameters					
Input Voltage Range		320-600 VDC			
Maximum Array Input Voltage		600 VDC			
Maximum Operating Input Cur	rent ¹	1277 ADC			
PV Array Configuration	Negative Ground	•			
	Positive Ground	•			
DC Input Combiner Options					
Combiner Bus Bar Inputs	•	24			
Number of Inputs and Fuses	0 0 0	15 x 160A 20 x 110A 24 x 100A			
Transformer					
Integrated Transformer ²		Yes ³			
Efficiency					
Maximum ⁴		96.3%			
CEC		95.5%			
Output Parameters					
Nominal Power		375 kW			
Nominal Output Voltage		480 VAC			
Output Voltage Range, [-12%/	10%]	422-528 VAC			
Maximum Output Current/Pha	se	451 A			
Standby Consumptions (tare lo including control power and au	osses ıx.)	124 W			
Nominal Output Frequency, 3-	Phase	60 Hz			
Maximum Harmonic Distortion		<3% THD			
Power Factor, Full Load		>99%			
Dynamic Power Factor Contro		+/- 0.8			
Power Curtailment		0-100%, 1% steps			
Environment					
Operating Temperature Range (Nominal Power)		-4° F to +122° F (-20° C to +50° C) (Opt40° C to +50° C)			
Storage Temperature Range		-22° F to +158° F (-30° C to +70° C)			
Cooling		Forced Air			
Noise Level (Distance of 3 m)		<65 dB(A)			
Relative Humidity (Non-Conde	nsina)	up to 90%			



PowerGate Plus 375 kW Specifications	UL/CSA		
Enclosure			
Dimensions (H x W x D)	89 x 166 x 40 in. (226 x 422 x 102 cm)		
Weight ⁵	5,811 lbs. (2641 kg)		
Finish	RAL 7032		
Protection Rating	NEMA 3R/IP44		
Warranty and Services			
Five Year Warranty	•		
Extended Warranty (1 and 5 year increments)	0		
Preventative Maintenance Agreement	0		
Uptime Guarantee ⁶	0		
Design Services	0		
APEX Project Management	0		
Communication Interface			
Modbus RS485	•		
Modbus TCP/IP	0		
Monitoring			
PV View Plus	0		
PV Zone	0		
Third-Party Compatibility	•		
Regulations and Standards Conformity			
UL1741, CSA 107.1, IEEE 1547, IEEE C62.41.2, IEEE C62.45, IEEE C37.90.1, IEEE C37.90.2	•		
UBC Zone 4 Seismic Rating	•		

Standard / Standard Option

Optional

¹ Calculated at nominal power and minimum DC voltage.

- ² The 20% boost tap on the isolation transformer increases the AC voltage output range for applications where the solar array DC operating voltage is at or near the lower end of the DC input range. This boost allows for continued inverter operation at lower DC voltage input levels.
- ³ Inverter and transformer are connected via a 12" throat. See product manual for details.

⁴ Calculated with auxiliary power.

 $^{\scriptscriptstyle 5}$ Dependent on options selected.

⁶ Requires Preventative Maintenance Agreement.

NOTE: All specifications are subject to change.

Output Option	ns	Power Efficienc	Power Efficiency		
PowerGate Plus	375 kW	Power Level	Efficiency*		
UL/CSA 480 VAC Output		10%	92.6%		
		20%	95.4%		
		30%	96.0%		
		50%	96.3%		
		75%	96.2%		
		100%	95.8%		

* 480V model

Energy Equity Protection (EEP)

Satcon provides a wide range of optional value-added services to protect your investment across the entire lifecycle of your project.

Design Services

Satcon's Design Services organization can guide you through all phases of project development using our broad experience and engineering skills.

APEX Project Management

Satcon APEX[™] Project Management ensure that your project comes in on time and on budget.

- Project planning
- Logistics
- Project supervision
- Mitigating risk, maximizing ROI

Warranty and Services

- Help desk
- Training programs
- Support services
- Extended warranty
- Preventative maintenance plans
- 99% Uptime Guarantee

PowerGate Plus Options

- Satcon Smart Subcombiners: Intelligent string monitoring
- Fused input combiners
- Satcon communication card: CCM Gateway
- Weather station
- PV View Plus monitoring system
- PV Zone

www.Satcon.com

Please visit Satcon's Resource Library for additional tools and product information, including:

- Satcon's product configurator
- Satcon's string sizing calculator
- Training and support resources:
 - On-demand video training
 - Articles, white papers and case studies



Satcon Corporate

25 Drydock Avenue, 7th Floor Boston, MA 02210 USA P: +1.617.910.5500 F: +1.617.910.5501

E: sales@satcon.com

Satcon West 46441 Landing Parkway Fremont, CA 94538 USA P: +1.510.897.4900 F: +1.510.897.4901 E: sales@satcon.com

Satcon Canada 835 Harrington Court Burlington, ON L7N 3P3 Canada P: +1.905.639.4692 F: +1.905.639.0961 E: sales@satcon.com

Satcon Germany An der Welle 4

60322 Frankfurt Main Germany P: +49 (0)69 7593 - 8620 F: +49 (0)69 7593 - 8200 E: sales.eu@satcon.com

Satcon International s.r.o. Jankovcova 1037/49 170 00 Praha 7 Czech Republic P: +420.255.729.610 F: +420.255.729.611 E: sales.eu@satcon.com

Satcon Greece

1A Iraklitou St. Patima Halandriou – 152 38 Greece P: +30.210.6654424 F: +30.210.6654425 E: sales.gr@satcon.com

Satcon Shenzhen China

Unit C101-C102, Tower C, Unisplendour Info. Harbor, Langshan Road, Nanshan Dist. Shenzhen 518057, China P: +86.755.6168.2588 F: +86.755.6168.2599 E: sales@satcon.com

Satcon Shanghai China Unit 2902-3, Tower A, City Center of Shanghai, 100 Zun Yi Road, Shanghai 200051, China P: +86.21.6236.8236 F: +86.21.6236.8240 E: sales@satcon.com

www.Satcon.com



© 2012 Satcon Technology Corporation. All rights reserved. Satcon is a registered trademark of Satcon Technology Corporation. All other trademarks are the property of their respective owners. PGP375ULNAEWR010912MS



APPENDIX L – PV Watts Data Output



(Type comments here to appear on printout; maximum 1 row of 80 characters.)

· •
-
- V

Station Identification				
City: Philadelphia				
State:	Pennsylvania			
Latitude:	39.88° N			
Longitude:	75.25° W			
Elevation:	9 m			
PV System Specification	s			
DC Rating: 332.8 kW				
DC to AC Derate Factor: 0.770				
AC Rating: 256.3 kW				
Array Type: Fixed Tilt				
Array Tilt: 40.0°				
Array Azimuth: 180.0°				
Energy Specifications				
Cost of Electricity:	9.6 ¢/kWh			

	Results				
Month	Solar Radiation (kWh/m ² /day)	AC Energy (kWh)	Energy Value (\$)		
1	3.31	26975	2589.60		
2	4.16	30678	2945.09		
3	4.74	36969	3549.02		
4	5.06	37039	3555.74		
5	5.19	37880	3636.48		
6	5.42	37116	3563.14		
7	5.51	38421	3688.42		
8	5.67	39856	3826.18		
9	5.07	35336	3392.26		
10	4.59	34548	3316.61		
11	3.37	25392	2437.63		
12	2.67	21096	2025.22		
Year	4.56	401307	38525.47		

Output Hourly Performance Data

Output Results as Text

About the Hourly Performance Data

Saving Text from a Browser

Run PVWATTS v.1 for another US location or an International location Run PVWATTS v.2 (US only)



APPENDIX M – UHS Electricity Cost Savings

V	Discounted		Savings (Standard less		
Year	Energy Price		PV electricty)		
1	\$	24,271.05	\$	14,254.42	
2	\$	24,513.76	\$	14,396.97	
3	\$	24,758.90	\$	14,540.94	
4	\$	25,006.48	\$	14,686.35	
5	\$	25,256.55	\$	14,833.21	
6	\$	25,509.11	\$	14,981.54	
7	\$	25,764.21	\$	15,131.36	
8	\$	26,021.85	\$	15,282.67	
9	\$	26,282.07	\$	15,435.50	
10	\$	26,544.89	\$	15,589.85	
11	\$	26,810.34	\$	15,745.75	
12	\$	27,078.44	\$	15,903.21	
13	\$	27,349.22	\$	16,062.24	
14	\$	27,622.72	\$	16,222.86	
15	\$	27,898.94	\$	16,385.09	
16	\$	28,177.93	\$	16,548.94	
17	\$	28,459.71	\$	16,714.43	
18	\$	28,744.31	\$	16,881.58	
19	\$	29,031.75	\$	17,050.39	
20	\$	29,322.07	\$	17,220.90	
21	\$	29,615.29	\$	17,393.11	
22	\$	29,911.44	\$	17,567.04	
23	\$	30,210.56	\$	17,742.71	
24	\$	30,512.66	\$	17,920.14	
25	\$	30,817.79	\$	18,099.34	
Life of contract: 25 years					
٦	Total Savings: \$			402,590.56	



APPENDIX N – UHS Payback Period

UHS Payback Period

1	0.0960	\$	38,525.47	
2	0.0970	\$	38,910.73	
3	0.0979	\$	39,299.83	
4	0.0989	\$	39,692.83	
5	0.0999	\$	40,089.76	
6	0.1009	\$	40,490.66	
7	0.1019	\$	40,895.56	
8	0.1029	\$	41,304.52	
9	0.1040	\$	41,717.57	
10	0.1050	\$	42,134.74	
11	0.1060	\$	42,556.09	
12	0.1071	\$	42,981.65	
13	0.1082	\$	43,411.47	
14	0.1093	\$	43,845.58	
15	0.1103	\$	44,284.04	
16	0.1115	\$	44,726.88	
17	0.1126	\$	45,174.15	
18	0.1137	\$	45,625.89	
19	0.1148	\$	46,082.15	
20	0.1160	\$	46,542.97	
21	0.1171	\$	47,008.40	
22	0.1183	\$	47,478.48	
23	0.1195	\$	47,953.27	
24	0.1207	\$	48,432.80	
25	0.1219	\$	48,917.13	
26	0.1231	\$	49,406.30	
27	0.1243	\$	49,900.36	
28	0.1256	\$	50,399.36	
29	0.1268	\$	50,903.36	
30	0.1281	\$	51,412.39	
31	0.1294	\$	51,926.52	
32	0.1307	\$	52,445.78	
33	0.1320	\$	52,970.24	
34	0.1333	\$	53,499.94	
35	0.1346	\$	54,034.94	
36	0.1360	\$	54,575.29	
37	0.1374	\$	55,121.04	
38	0.1387	\$	55,672.25	
39	0.1401	\$	56,228.98	
40	0.1415	\$	56,791.27	
	Total Value	\$	1,883,370.61	

Total System Cost:	\$ 1,863,680.00
40 year payback period	d for UHS



APPENDIX O – Façade Assembly Comparison

Unionville High School | Final Report







APPENDIX P – Precast Panel Calculations and Information



Panel Type Information									
#	Panel Type	Size							
í.		ĺ.							
1	Α	12' X 13.5'							
2	В	8' x 13.5'							
3	С	12' X 28.5'							
4	D	8' x 28.5'							
5	E	6' x 13.5'							
6	F	12' x 13.5'							
7	G	12' x 13.5'							
8	н	6' x 28.5'							
9	1	12' x 28.5'							
10	J	12' x 13.5'							
11	K	12' x 28.5'							
12	L	12' x 13.5'							
13	M	12' x 13.5'							
14	N	12' x 28.5'							
15	0	12' x 28.5'							
16	P	12 x 28.5'							
17	Q	12' x 13.5'							
18	R	12' x 28.5'							
19	S	12' x 28.5'							
20	т	12' x 13.5'							
21	U	12' X 28.5'							
22	V	12' X 28.5'							
23	W	12' X 28.5'							
24	X	12' X 28.5'							
25	Y	12' X 28.5'							
26	Z	12' X 28.5'							
27	AA	10' X 28.5'							
28	BB	10' X 13.5'							
29	CC	12' X 13.5'							
30	DD	12' X 13.5'							
31	EE	12' X 13.5'							
32	FF	12' X 13.5'							
33	GG	12' X 28.5'							
34	НН	12' X 13.5'							
35	11	10' X 13.5'							
36	LI II	12' x 13.5'							
37	KK	12' x 13.5'							



- New Classroom Wing East Elevation
- New Classroom Wing South Side (Elevation 3)
- New Classroom Wing South Side (Elevation 2)
- New Classroom Wing South Side (Elevation 4)
- New Classroom Wing West Side
- New Classroom Courtyard West Side (East Elevation)
- New Classroom Courtyard North Side
 - Classroom Courtyard South Side



East Elevation







West Elevation



North Elevation



Unionville High School | Final Report



South Elevation

















ELEVATION "2" - NEW CLASSROOM WING SOUTH SIDE

SCALE: 1/8"=1'-0"



APPENDIX Q – HAM Toolbox Original Façade Analysis



Brick Veneer

								E CONE Wi	DITIONS- nter	Sum	mer
TOOL NO. 1 R VALUE ANALYSIS							Indoor	emp(*F 70	25	Temp(°F)	50 RH(%)
							Outdoor	10	66	93	68
IATE	ERIAL	s					City	Philade	lphia, PA		•
block, 8 in. 🗾		<u>H</u> e	<u>H</u> elp <u>S</u> TART/CLR			10 2020					
Add Delete		Delete	Move <u>up</u>	p Move <u>d</u> n		Con <u>v</u> ert	(°F) T	WALL SECTION & TEMPERATURE GRADIENTS			
<u>C</u> a	ılc	<u>G</u> raph	<u>P</u> rint	<u>W</u> all	Lyb	TOOLBOX	140 Ext				Int -14
Layer		Generic	Material		Thick.	R Val.	120		EØ		-12
1	brick, (unvntd), 4 in.				3.54	0.64	100		E		-10
2	cavity, 2 in.				2.00	0.98	100		EØ		10
3	rigid ins.,(expand.), 2 in.				2.00	7.90	80		EØ		- 80
4	block, 8 in.				8.03	1.03	60		EA		- 60
5							00		EX		0.
6							40	7////	EØ		- 40
7							20 -		EA		- 20
8							20		EA		20
9							0		EØ		- 0
10							20		EA		- 20
11							-20	0 4	8	12 16	
12									(inches)	
					15 57	10 56	-				


Rock Face CMU Veneer

							CLIMATE CONDITIONS Winter Summer					
TOOL NO. 1						Indoor	70 F	25	75	50		
							Outdoor	10	66	93	68	
MATE	ERIA	LS			City Philadelphia, PA							
block, 8 in. 💽			•	<u>H</u> elp		START/CLR						
Add		De <u>l</u> ete	Move <u>u</u> p	Моу	e <u>d</u> n	Con <u>v</u> ert	(°F) T	(°F) WALL SECTION & TEMPERATURE GRADIENTS				
<u>C</u> a	ılc	<u>G</u> raph	Print	<u>W</u> al	ILyb	TOOLBOX	140 Ext				Int -14	
Layer	-	Generic	Material		Thick	. R Val.	120				-12	
1	bloc	block, 4 in.			4.00) 0.69	100				-10	
2	cavity, 2 in.				2.00	0.98	100		EØ		10	
3	rigid ins.,(expand.), 2 in.				2.00) 7.90	80		EØ		- 80	
4	4 block, 8 in.				8.03	3 1.03	60		EA		- 60	
5							00		EØ			
6							40		EØ		- 40	
7							20		EA		- 20	
8							2.4		EX		20	
9							0		EØ		- 0	
10							-20		EA			
11							-20	0 4	8	12 16	-20	
12	1								(inches)		
					16.03	3 10.61	-	a 12 01				



APPENDIX R – DesignBuilder Analysis Outputs



Annual Heat Loss

Original Façade



Proposed Precast Panel Façade





Monthly Heat Loss

Original Façade





Proposed Precast Panel Façade





APPENDIX S - Structural Breadth Calculations



Michael Beam Structural Breadth Original Facadhe Existing Loads DL: 15 psF Super imposed 45 psF Slab self neight 55 psF Slab self neight allowance 55 psF CMU weight LL: 40 pst class rooms 20 p= P partitions Note: Assume no 22 reductions Beam botwon col. BB and Col CL @ col line 5) Tobutery worldth = 8'-4" + 8" = 9'-0" ++++++++= 6.6 pst W 21 × 44 A Wayne =1. 2 [(5+45+5)[4')]+ 1. 6 (40+20)[4'] = [7.57 K)F Wmy= (.55 prf)(13.5)(0)= 89KIF] - Simplified to all distributed loads W-tot=1.57 +.89 W=2.46 KIP 21'- 4" = 2.46 ksf moments Mu= w2 > Mu= (2.446) (24.33') -> Mu= 182.02 K.Ft - Assume unbraced length = 6.1' OMn @ 6.1'ubl = 331 kip-ft Mu 2 ØMn Lafrom Steel Manual Table 3.10 182.00 2 331 0K



Michael Beam Structural Breadth Original Facack 2 $\frac{\text{Deflectrons}}{\text{Total Load } A = \frac{5 \times 14}{384 \text{EI}} = \frac{5(1-63)(24,83)^4(728)}{384(24000)(843)^4} = 843 \text{ m}^4$ A=.53 in (2 beam's center A = L/246 7.53 = (12.33'.10")/240 7.53 = 1.2 .K. Live Load: w= (20+40) psp. 9'= .54 kip/P+ A= 5 (054) (04,33 × (1708) → ALL = .17" 384 (24000) (843) ALL = 4360 → .17" = (24.33) (10") → .17" - .81" of L



Michael Beam Structural Breadth Arecast Facade 3 DL: 15 pst super imposed 45 pst slab self neight 5 pst self neight allowen 88 pst panel self neight Precast facade Loads USTE ASSUME TO LL reductions P=31.59P W=1.57 KIF New total load w= 1.2[15+45+5)9'] + 1.6[(20+40)9'] P= (88psf. 28.5'+ 24.33' = 30.51 KIP distributed = 1.37 KH (24.332) -> Mu= 1/6.17 K-ft point load = 30.51 (24.33) = 185.58 K-ft Total mu = [301.75 K-ft] MU 2 DMn 301.75 2 331 0Kr Deflections Total lord = 5 w/# + P/3 y 384EI 4BEI 5(1.57)(24.33)(708) (30.51)(24.33)(708) ATOTAL = . 506" + .647 + 384(24000)(843) 48(24000)(843) ATOT = 1.15" A= 1.2" > 1.15" = 1.2" okv ALL = SAME as original = okv Muring vs. Murew > 182.02 vs. 301.75 > \$ 60% Mu increase Result > 21×44 Beam is stall sufficient



