



TOWSON TIGER ARENA

TOWSON, MD

Derek Stoecklein | Construction Management Option

Advisor: Ray Sowers






Project Background

- Overview
- Location
- Site Planning

Fabric Duct System




- Existing System
- Load Calculations
- DuctSox Design
- Comparison

Prefabricated Terra Cotta



- Existing System
- Designed Panels
- Delivery and Connection Details
- Comparison

Production Planning



- Schedule Overview
- Last Planner
- Implementation

Cisco StadiumVision

- Technology at Home
- StadiumVision Overview
- Application at Towson
- Case Studies



Presentation Outline

- I. Project Background
 - I. Overview
 - II. Location
 - III. Site Planning
- II. Fabric Duct System
- III. Prefabricated Terra Cotta
- IV. Production Planning
- V. Cisco StadiumVision
- VI. Conclusion/Recommendation
- VII. Acknowledgments



Building: Towson Tiger Arena

Building Location: Towson University; Towson, MD

Building Size: 120,000 SF

Number of Stories: 4 Stories

Occupancy Type: Sports, Entertainment

Project Cost: \$56 Million

Construction Duration: 18 Months

Project Delivery Method: Design-Bid-Build

Contract Type: Guaranteed Maximum Price (GMP)

Sustainable Design: LEED Gold

Owner: Towson University

Construction Manager: Gilbane Building Company

Architect: Hord | Coplan | Macht

Associated Architect: Sasaki Associates

MEP Engineer: James Posey Associates

Structural Engineer: Faisant Associates

Civil Engineer: Site Resources, Inc.



Presentation Outline

I. Project Background

I. Overview

II. Location

III. Site Planning

II. Fabric Duct System



III. Prefabricated Terra Cotta

IV. Production Planning


V. Cisco StadiumVision

VI. Conclusion/Recommendation

VII. Acknowledgments



Location and Site Planning



Derek Stoecklein | Construction Management Option

ANALYSIS I: DUCTSOX SYSTEM

Derek Stoecklein | Construction Management Option




Presentation Outline

- I. Project Background
- II. Fabric Duct System**
 - I. Existing System**
 - II. Load Calculations
 - III. DuctSox Design
 - IV. Comparison
- III. Prefabricated Terra Cotta
- IV. Production Planning
- V. Cisco StadiumVision
- VI. Conclusion/Recommendation
- VII. Acknowledgments



System Overview

- (2) 47,000 CFM Rooftop Units = 94,000 CFM
- Single Zone Variable Air Volume (VAV) with a CO2 reset
- 2,635,720 CF (Volume of Space)
- 43,340 SF (Area of Floor Space)
- Traditional Sheet Metal Duct
 - 14" to 62" Dia.




Existing System



Presentation Outline

- I. Project Background
- II. Fabric Duct System**
 - I. Existing System
 - II. Load Calculations**
 - I. Mechanical Breadth**
- III. DuctSox Design
- IV. Comparison
- III. Prefabricated Terra Cotta
- IV. Production Planning
- V. Cisco StadiumVision
- VI. Conclusion/Recommendation
- VII. Acknowledgments



Load Calculation (Mechanical Breadth)



1. Ventilation Loads (ASHRAE Standard 62.1)

45,312 CFM

1. Heating and Cooling Loads (Trace)

87,041 CFM Cooling

26,830 CFM Heating




Original Output of AHU 8 – 9	94,000 CFM
Total Calculated Demand	87,041 CFM
Difference	6,956 CFM



EPFN-490



EPFN-445




Load Calculations


Derek Stoecklein | Construction Management Option

Presentation Outline

- I. Project Background
- II. Fabric Duct System**
 - I. Existing System
 - II. Load Calculations
- III. DuctSox Design**
- IV. Comparison
- III. Prefabricated Terra Cotta
- IV. Production Planning
- V. Cisco StadiumVision
- VI. Conclusion/Recommendation
- VII. Acknowledgments



DuctSox System Selection Process



Design Layout

- (2) 46" Dia. x 101' L = (2) Duct Sections Ea.
- (4) 32" Dia. x 144' L = (4) Duct Sections Ea.
- (2) 32" Dia. x 118' L = (3) Duct Sections Ea.
- (2) 32" Dia. x 24' L = (1) Duct Section Ea.
- (1) 32" Dia. x 17' L = (1) Duct Section Ea.

(29) Total Fabric Duct Sections

32	5,585	6,702	7,819	8,936
34	6,305	7,566	8,827	10,088
36	7,069	8,482	9,896	11,310
38	7,876	9,451	11,026	12,601
40	8,727	10,472	12,217	13,963
42	9,621	11,545	13,470	15,394
44	10,559	12,671	14,783	16,895
46	11,541	13,849	16,157	18,466



Presentation Outline

- I. Project Background
- II. Fabric Duct System**
 - I. Existing System
 - II. Load Calculations
 - III. DuctSox Design
- IV. Comparison**
- III. Prefabricated Terra Cotta
- IV. Production Planning
- V. Cisco StadiumVision
- VI. Conclusion/Recommendation
- VII. Acknowledgments



Schedule Comparison			
Standard Fabrication & Deliver			
DuctSox	4 Weeks	Savings	
Sheet Metal Duct	8 Weeks	4 Weeks	
Complete Ductwork Installation			
DuctSox	14 Days	Savings	
Sheet Metal Duct	70 Days	56 Days	
Painting			
DuctSox	0 Days	Savings	
Sheet Metal Duct	30 Days	30 Days	

Total Time Savings		
Description	Days	
Fabrication	20	
Installation	56	
Others	30	
Days	106	
Weeks	21.2	
Months	5.3	
*86 Days on-site labor		

Price Comparison			
Material Cost			
DuctSox	\$37,310.00	Savings	
Metal Duct Total	\$455,000.00	\$ 417,690.00	
Sheet Metal Duct	\$375,000.00		
Sheet Metal Insulation	\$50,000.00		
Paint Metal Duct	\$30,000.00		
Labor Cost			
DuctSox Total	\$ 28,568.00	Savings	
Metal Duct Total	\$375,000.00	\$ 346,432.00	
Sheet Metal Duct	\$265,000.00		
Sheet Metal Insulation	\$50,000.00		
Paint Metal Duct	\$60,000.00		



Total Cost Savings to Towson	
Description	Savings
Material	\$417,690.00
Labor	\$346,432.00
CM Fee (2%)	\$15,282.44
Subtotal	\$779,404.44




ANALYSIS II: PREFABRICATED TERRA COTTA PANELS

Derek Stoecklein | Construction Management Option



Presentation Outline

- I. Project Background
- II. Fabric Duct System
- III. Prefabricated Terra Cotta
 - I. Terra Cotta Overview
 - II. Prefabricated Panel Design
 - III. Comparison
- IV. Production Planning
- V. Cisco StadiumVision
- VI. Conclusion/Recommendation
- VII. Acknowledgments






What is a Terra Cotta Rainscreen?

- Wall panel made from clay
- Hung on structural sub-framing system
- Sub-framing mounts to primary structural wall system
- Clay panels and sub-framing components create cavity in facade
- Pressure equalized




Terra Cotta Rainscreen





Derek Stoecklein | Construction Management Option

Presentation Outline

- I. Project Background
- II. Fabric Duct System
- III. Prefabricated Terra Cotta**
 - I. Terra Cotta Overview
 - II. Prefabricated Panel Design**
 - III. Comparison
- IV. Production Planning
- V. Cisco StadiumVision
- VI. Conclusion/Recommendation
- VII. Acknowledgments



Panel Sizes
Width: 5' -4"
Height: 20' to 37'



Presentation Outline

- I. Project Background
- II. Fabric Duct System
- III. Prefabricated Terra Cotta**
 - I. Terra Cotta Overview
 - II. Prefabricated Panel Design
- III. Comparison**
- IV. Production Planning
- V. Cisco StadiumVision
- VI. Conclusion/Recommendation
- VII. Acknowledgments



6015 SF of Terra Cotta

Stick-Built System

\$65.60 SF

171 Days On-Site Labor

Prefabricated System

\$70.00 SF

24 Days On-Site Labor

Overall

\$46,113 Increase

4 Months On-Site Labor Decrease

Comparision

Cost & Schedule Comparison		
Description	Duration (Days)	Cost
<u>Prefabricated</u>		
TOTAL	119	\$674,510
<u>Stick-Built</u>		
TOTAL	211	\$628,397
<u>Delta</u>		
TOTAL	92	\$46,113



R-Value Comparison ft ² ·°F·h/Btu			
Description	R-Value	Thickness	Subtotals
<u>Existing System</u>			
FOAMULAR 250 Rigid Foam Insulation	5 per inch	3"	15
GlassRoc Exterior Sheating	.51 per SF	5/8"	0.51
		Total	15.51
<u>Prefabricated System</u>			
Optimo Smooth Insulated Metal Panel	7.5 per inch	3 5/8"	27.19
		Total	27.19

Derek Stoecklein | Construction Management Option

ANALYSIS III: PRODUCTION PLANNING OF THE TRUSS PHASE MEPFP

Derek Stoecklein | Construction Management Option



Presentation Outline


- I. Project Background
- II. Fabric Duct System
- III. Prefabricated Terra Cotta
- IV. Production Planning**
 - I. Schedule Analysis**
 - II. Last Planner
- V. Cisco StadiumVision
- VI. Conclusion/Recommendation
- VII. Acknowledgments



Baseline Schedule vs. Actual Schedule

Actual Starts vs. Baseline Analysis	Actual Start Dates				
	Task	Actual Duration	Baseline Start	Actual Start	Delta
	Sprinkler RI @ Trusses	39	7/5/2012	5/3/2012	45
	Storm Rough In Truss Lvl	25	4/12/2012	6/1/2012	36
	HVAC Pipe RI @ Trusses	32	5/30/2012	6/8/2012	7
	Comm Conduit/Cable tray	36	4/24/2012	6/4/2012	29
	Conduit/Wire Truss Lvl	114	4/24/2012	5/16/2012	16
	Duct Rough In	33	5/30/2012	7/30/2012	43
	Duct Insulation @ Trusses	15	7/26/2012	8/29/2012	35
	Paint @ Trusses/Deck	63	8/9/2012	8/17/2012	6
	Lighting @ Truss Level	20	10/5/2012	10/19/2012	10
	Fire Alarm Devices and Test Truss Level	21	10/19/2012	10/29/2012	6
	Electrical Devices @ Truss Level	47	10/19/2012	9/24/2012	19

Actual Starts vs. Baseline Analysis	Actual Finish Dates				
	Task	Actual Duration	Baseline Finish	Early Finish July	Delta
	Sprinkler RI @ Trusses	39	9/4/2012	6/26/2012	50
	Storm Rough In Truss Lvl	25	5/23/2012	7/5/2012	31
	HVAC Pipe RI @ Trusses	32	7/11/2012	7/23/2012	8
	Comm Conduit/Cable tray	36	5/21/2012	7/23/2012	45
	Conduit/Wire Truss Lvl	114	6/25/2012	10/22/2012	85
	Duct Rough In	33	8/8/2012	9/12/2012	25
	Duct Insulation @ Trusses	15	8/22/2012	9/18/2012	19
	Paint @ Trusses/Deck	63	10/17/2012	11/13/2012	19
	Lighting @ Truss Level	20	11/1/2012	11/15/2012	10
	Fire Alarm Devices and Test Truss Level	21	11/15/2012	11/25/2012	6
	Electrical Devices @ Truss Level	47	11/8/2012	11/27/2012	13




Common Construction Productivity Challenges

- Poor or incomplete design and documentation
- Client scope change during construction
- Mistakes during construction
- Delays in decision making or instructions
- Poor planning and communication
- Weather
- Labor skills, availability or disputes
- Incorrect material types or quantity




Presentation Outline

- I. Project Background
- II. Fabric Duct System
- III. Prefabricated Terra Cotta
- IV. Production Planning**
 - I. Schedule Analysis
 - II. Last Planner**
 - I. Overview**
 - II. Implementation
- V. Cisco StadiumVision
- VI. Conclusion/Recommendation
- VII. Acknowledgments



The Last Planner System



Measure progress and remedy issues

4 Levels of Planning

- 1. Master CPM Schedule**
 - Feasibility
 - Long Lead Items
 - Milestones
- 2. Phase Schedule**
 - Pull planning
- 3. Look-Ahead Plan**
 - Detail Tasks
 - Screen Tasks
 - Workflow Plan
- 4. Weekly Work Planning**

Presentation Outline

- I. Project Background
- II. Fabric Duct System
- III. Prefabricated Terra Cotta

IV. Production Planning




- I. Schedule Analysis

II. Last Planner

- I. Overview

II. Implementation

- V. Cisco StadiumVision
- VI. Conclusion/Recommendation
- VII. Acknowledgments



Name	Duration: Re-Seq	Duration: Actual	Duration: Diff	Start: Re-Seq	Start: Actual	Start: Diff	Finish: Re-Seq	Finish: Actual	Finish: Diff
Kinsley - Steel	84 days	109 days	-25d	Mon 1/23/12	Mon 1/16/12	5d	Thu 5/17/12	Thu 6/14/12	-20d
Steel Decking Sequence Duration	84 days	109 days	-25d	Mon 1/23/12	Mon 1/16/12	5d	Thu 5/17/12	Thu 6/14/12	-20d
Erect Catwalk	15 days	38 days	-23d	Thu 4/19/12	Wed 4/11/12	6d	Wed 5/9/12	Fri 6/1/12	-17d
DenverElek - Mechanical	114 days	78 days	36d	Fri 4/20/12	Fri 6/1/12	-30d	Wed 9/26/12	Tue 9/18/12	6d
Storm Rough In Truss Lvl	30 days	25 days	5d	Fri 4/20/12	Fri 6/1/12	-30d	Thu 5/31/12	Thu 7/5/12	-25d
HVAC Pipe RI @ Trusses	31 days	32 days	-1d	Fri 4/27/12	Fri 6/8/12	-30d	Fri 6/8/12	Mon 7/23/12	-31d
Duct Rough In		33 days			Mon 7/30/12			Wed 9/12/12	
Duct Insulation @ Trusses		15 days			Wed 8/29/12			Tue 9/18/12	
DuctSox	14 days			Fri 9/7/12			Wed 9/26/12		
BK Truland - Electrical	110 days	140 days	-30d	Fri 5/11/12	Wed 5/16/12	-3d	Thu 10/11/12	Tue 11/27/12	-33d
Comm Conduit/Cable tray	20 days	36 days	-16d	Fri 5/11/12	Mon 6/4/12	-16d	Thu 6/7/12	Mon 7/23/12	-32d
Conduit/Wire Truss Lvl	45 days	114 days	-69d	Fri 5/11/12	Wed 5/16/12	-3d	Thu 7/12/12	Mon	-72d
Lighting @ Truss Level	20 days	20 days	0d	Fri 8/31/12	Fri 10/19/12	-35d	Thu 9/27/12	Thu 11/15/12	-35d
Electrical Devices @ Truss Level	15 days	47 days	-32d	Fri 9/14/12	Mon 9/24/12	-6d	Thu 10/4/12	Tue 11/27/12	-38d
Fire Alarm Devices and Test Truss Level	20 days	21 days	-1d	Fri 9/14/12	Mon	-31d	Thu 10/11/12	Sun 11/25/12	-31d
NFP - Sprinkler	44 days	39 days	5d	Fri 5/4/12	Thu 5/3/12	1d	Wed 7/4/12	Tue 6/26/12	6d
Sprinkler RI @ Trusses	44 days	39 days	5d	Fri 5/4/12	Thu 5/3/12	1d	Wed 7/4/12	Tue 6/26/12	6d
NLP - Painting	50 days	63 days	-13d	Fri 7/6/12	Fri 8/17/12	-30d	Thu 9/13/12	Tue 11/13/12	-43d
Paint @ Trusses/Deck	50 days	63 days	-13d	Fri 7/6/12	Fri 8/17/12	-30d	Thu 9/13/12	Tue 11/13/12	-43d



Truss MEPF - Baseline Duration

4/12/2012 - 11/15/12

156 Days

Truss MEPF - Actual Duration

5/3/2012 - 11/27/12

149 Days

**Not including overtime*

Truss MEPF- Re-Sequenced "Phased Schedule" Duration

4/12/2012 - 10/11/12

126 Days

Difference of **33 Days** from Actual Completion

= \$354,629 GC Savings

Last Planner System Implementation

Derek Stoecklein | Construction Management Option



ANALYSIS IV: CISCO STADIUMVISION

Derek Stoecklein | Construction Management Option



Presentation Outline

- I. Project Background
- II. Fabric Duct System
- III. Prefabricated Terra Cotta
- IV. Production Planning
- V. Cisco StadiumVision**
 - I. Technology at Home**
 - II. StadiumVision Overview
 - III. Towson Application
 - IV. Case Studies
- VI. Conclusion/Recommendation
- VII. Acknowledgments




The Comfort of Home

- Lazyboy
- Technology
- Cost Effective



Presentation Outline

- I. Project Background
- II. Fabric Duct System
- III. Prefabricated Terra Cotta
- IV. Production Planning
- V. **Cisco StadiumVision**
 - I. Technology at Home
 - II. **StadiumVision Overview**
 - III. Towson Application
 - IV. Case Studies
- VI. Conclusion/Recommendation
- VII. Acknowledgments



The Ultimate Experience

Video Feeds Options
 Sales
 Player Stats
 Directions
 Wi-Fi
 Big Board Interaction
 Suite Features



StadiumVision Overview



StadiumVision Director

StadiumVision Mobile

Connected Stadium



"Meeting the demands of a new generation of fans"




Presentation Outline

- I. Project Background
- II. Fabric Duct System
- III. Prefabricated Terra Cotta
- IV. Production Planning
- V. Cisco StadiumVision**
 - I. Technology at Home
 - II. StadiumVision Overview
- III. Towson Application**
 - I. Electrical Breadth**
 - IV. Case Studies
- VI. Conclusion/Recommendation
- VII. Acknowledgments



Revenue Generation for Towson

- Advertisements
- Point of Sale
- Merchandise
- Promotions
- Purchasing



Tiger Arena StadiumVision Components

Required Rack Equipment v. 3.0	Rack Slot	Amount	Max Power (W)	Power Req. (W)
Cisco 9094 Encoders	1	1	60	60
Cisco D9858 Transcoder	1	1	110	110
Cisco 9887 Receiver	1	1	200	200
Cisco 9900 DCM (Digital Content Manager)	2	1	350	350
Catalyst 3560/3750 Ethernet Switches	1	1	130	130
Catalyst 6504 Switch (Video Distribution System)	5	1	113	113
Thomson/DirectTV COM200	5	2	320	640
Cisco StadiumVision Server, ADE 2140	2	1	600	600
Cisco StadiumVision Reporter	1	1	650	650
Cisco StadiumVision Streamer	1	1	650	650
Rack Total	20	11	-	3503
Adjusted Power (.95 PF)				3687

Rack Details

11 Components
3,687 VA Output
3,840 VA Capacity
120 V, Single-Phase 20A



RP1C

WIRING SCHEDULE: PANEL RP1C																
120/208 VOLTS				3PHASE 4 WIRE				100 AMP MAINS				SURFACE MOUNTED				
CIRC-UIT	POLE	DESCRIPTION	WIRE/CONDUIT	BREAKER	POLE	AMP	A0	B0	C0	CIRC-UIT	POLE	DESCRIPTION	WIRE/CONDUIT	BREAKER		
1	1	CUH-TA-1 (VESTIBULE 124)	#12-3/4" C	1	20					2	2	HAND DRYER MEN'S 131	#8-3/4" C	1	20	
3	3	REC FAN ASSIST 134,135,137	#8-3/4" C	1	20		1.0	1.4		4	4	HAND DRYER MEN'S 131	#8-3/4" C	1	20	
5	5	REC EVENT MGMT 133, 134	#8-3/4" C	1	20				0.8	6	6	REC MEN'S 131	#8-3/4" C	1	20	
7	7	REC WOMEN'S 132	#8-3/4" C	1	20	0.8	0.8			8	8	REC RECEPTION 125, CORR	#10-3/4" C	1	20	
9	9	HAND DRYER WOMEN'S 132	#8-3/4" C	1	20			1.4	0.8	10	10	REC PRESS RM 127	#12-3/4" C	1	20	
11	11	HAND DRYER WOMEN'S 132	#8-3/4" C	1	20					12	12	REC PRESS RM 127	#12-3/4" C	1	20	
13	13	REC PRESS ROOM 127	#12-3/4" C	1	20	0.8	1.0			14	14	REC AVA PRESS RM 127	#12-3/4" C	1	20	
15	15	REC PRESS ROOM 127	#12-3/4" C	1	20			0.8	0.5	16	16	REC METAL DETECTOR 125	#12-3/4" C	1	20	
17	17	REC EVENT STAFF 121	#12-3/4" C	1	20				0.6	18	18	REC METAL DETECTOR 125	#12-3/4" C	1	20	
19	19	REC EVENT STAFF 121, CORR 114	#12-3/4" C	1	20	0.8	0.5			20	20	REC EWC 125	#12-3/4" C	1	20	
21	21	REC SECURITY 122, CORR	#12-3/4" C	1	20			0.8	0.8	22	22	REC AVA SECURITY 122	#12-3/4" C	1	20	
23	23	REC PRODUCTION 129	#10-3/4" C	1	20					24	24	REC PRODUCTION 129	#10-3/4" C	1	20	
25	25	REC PRODUCTION 129	#10-3/4" C	1	20	0.8	0.8		0.8	26	26	REC PRODUCTION 129	#10-3/4" C	1	20	
27	27	REC PRODUCTION 129	#10-3/4" C	1	20			0.8	1.0	28	28	REC PRODUCTION 129	2#10-#10	2	20	
29	29	REC PRODUCTION 129	#10-3/4" C	1	20				0.8	30	30	REC PRODUCTION 129	G-3/4" C			
31	31	REC PRODUCTION 129	2#10-10G-3/4" C	2	20	1.0	1.0			32	32	REC PRODUCTION 129	2#10-#10	2	20	
-	33						1.0	1.0		-	34		G-3/4" C			
35	35	REC PRODUCTION 129	2#10-10G-3/4" C	2	20				1.0	36	36	REC PRODUCTION 129	#10-3/4" C	1	20	
-	37								1.0	38	38	REC TV PRESS ROOM 127	#12-3/4" C	1	20	
39	39	CISCO STADIUM VISION RACK	3#10-10G-3/4" C	2	20			1.9		40	40	SPARE		1	20	
-	41								1.9	42	42	SPARE		1	20	
CONNECTED LOAD =							36.6	KVA		5.5	5.9	7.7	5.5	7.3	4.7	
DEMAND LOAD =							27.1	KVA			11.4	12.2	12.0			
MIN AIC RATING =							10,000	AMPS SYMMETRICAL			NOTE: PROVIDE SEPARATE NEUTRAL FOR EACH CIRCUIT					
											MAIN BREAKER 100 AMPS					
											LOCATION SECURITY 122					

Towson Application

Derek Stoecklein | Construction Management Option

Presentation Outline

- I. Project Background
- II. Fabric Duct System
- III. Prefabricated Terra Cotta
- IV. Production Planning

V. Cisco StadiumVision

- I. Technology at Home
- II. StadiumVision Overview
- III. Towson Application

IV. Case Studies

- VI. Conclusion/Recommendation
- VII. Acknowledgments



“The value that we are receiving from Cisco Stadium Vision far outweighs just a financial investment. We can easily justify it financially, but the value to our brand is immeasurable. We can demonstrate to sponsors and fans that they gain a far better experience, and there is not a more effective way to do it.”
– David Peart, Senior Vice President of Sales and Service, CONSOL Energy Center

CONSOL Energy Center, PA
200% increase in advertisers


300% increase in advertisement and sponsorship revenues

80% of fans retaining the digital content they viewed



Staples Center, LA
9% increase in concession revenue

400% increase in pilot promotions revenue



“Cisco solutions are helping us use our new home to deliver the biggest and best experience in the world of sports and entertainment.”
– Jerry Jones, Owner and General Manager, Dallas Cowboys



Presentation Outline

- I. Project Background
- II. Fabric Duct System
- III. Prefabricated Terra Cotta
- IV. Production Planning
- V. Cisco StadiumVision
 - I. Technology at Home
 - II. StadiumVision Overview
 - III. Towson Application
 - IV. Case Studies

VI. Conclusion/Recommendation

- VII. Acknowledgments





DuctSox

On-Site Schedule Savings: 86 Days

Towson Savings: \$779,404

25% More Efficient than Sheet Metal

Reduction in AHU Fan Size



Prefabricated Terra Cotta

On-Site Schedule Decrease: 4 Months

Towson Cost: (\$46,113)

Improved R-Value: 27.19 > 15.15 ft²·°F·h/Btu

Improved Safety, Quality, and Logistics



Presentation Outline

- I. Project Background
- II. Fabric Duct System
- III. Prefabricated Terra Cotta
- IV. Production Planning
- V. Cisco StadiumVision
 - I. Technology at Home
 - II. StadiumVision Overview
 - III. Towson Application
 - IV. Case Studies

VI. Conclusion/Recommendation

VII. Acknowledgments




Last Planner System

Schedule Decrease: 33 Days

GC Savings: \$354,629

Improved Safety and Logistics



Conclusion & Recommendation

Cisco StadiumVision

Revenue Generation Potential

Creating the Ultimate Experience

Cost and Schedule Increase



Derek Stoecklein | Construction Management Option



Academic Acknowledgments

Penn State Architectural Engineering Faculty

Ray Sowers

Dr. Craig Dubler

Industry Acknowledgments



Special Thanks

Stephanie Fuss

Family and Friends

Acknowledgments

Derek Stoecklein | Construction Management Option



Questions?

Derek Stoecklein | Construction Management Option



Questions?

Derek Stoecklein | Construction Management Option