



© Copyright The Lukmire Partnership, Inc. 2012

Library In Metropolitan Washington, D.C.

Penn State Architectural Engineering Senior Capstone Project

Lowell Stine | Construction | Rob Leicht



Picture Provided by Multivista

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments



Picture Provided by Multivista



Outline

Project Introduction

Early Involvement

Caisson Rebar Cage Prefab

Structural Sequencing

Structural Breadth

Mechanical Room

Acoustical Breadth

Summary of Conclusions

Acknowledgments

Building Name: Library in Metropolitan Washington, D.C.

Location: Metropolitan Washington, D.C. (Undisclosed)

Occupant: County Library & Non-profit Art Group

Function Types: A-3 (Assembly)
B (Business)
M (Mercantile)

Gross Area: 90,000 ft²


Number of Stories: Five Plus Basement

Project Delivery: Design-Bid-Build

Construction Dates: January 2013 – October 2014

Project Cost: \$69.5 Million

- Key
- Existing Buildings
 - Roads
 - Open Space
 - Sidewalks
 - Construction Site
 - Access Road
 - Building Footprint
 - Building Overhang
 - Site Trailers
 - Unloading Area
 - Future Apt. Site



Owner:
Undisclosed County

Architect:
The Lukmire Partnership

Contractor:
Costello Construction

Structural Engineer:
Columbia Engineering

Project Team

Construction Manager:
MBP

Mechanical & Plumbing Engineer:
Mendoza, Ribas, Farinas & Associates

Electrical Engineer:
Mendoza, Ribas, Farinas & Associates

IT/Security:
Wright Engineering

Civil Engineer:
ADTEK

Landscape Architect:
Parker Rodriguez

Interior Design:
The Studio of Sandra Ragan

Lighting Consultant:
MCLA

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Systems

Architectural:

- 50' Cantilever of 3rd thru 5th Floors
- Exposed Structure in Library Space

Structure:

- Concrete Caissons
- Structural Steel
- Composite Slabs

Building Enclosure:

- 53% Curtain Wall – UV Protection
- Terra Cotta Panels
- Architectural CMU's

Mechanical:

- IPEC (Integrated Packages Equipment Center)
- Hydronic In-Slab Heating



Picture Courtesy of The Lukmire Partnership, Inc.



Picture Provided by Multivista



Picture Provided by <http://www.systecon.com>



© Copyright The Lukmire Partnership, Inc. 2012


Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Measurable Success



- 1) Minimize costs and schedule delays from change orders and rework
- 2) Minimize wasted material and labor costs and limit schedule delays
- 3) Shorten structural erection durations
- 4) Cost effectiveness and fewer constructability challenges

Early Involvement in Design Research Analysis



Caisson Rebar Cage Fabrication Analysis

Structural Sequencing Analysis



Mechanical Penthouse vs. IPEC Analysis

Design



Foundation



Structure



Building Systems

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Early Involvement in Design Research Analysis

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Goal

Considerations / Requirements
Specifics of this Project
Typical Problem Areas

Outline

- Project Introduction
- Early Involvement**
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Goal

Considerations / Requirements
 Specifics of this Project
 Typical Problem Areas

Industry Member Interviews

Scopes
 Benefits
 Owner Buy-in
 Future

Similar Topics

#	Criteria	Consistency
1	Owner Buy-in	5 of 5
2	Cost Considerations	5 of 5
3	Scope Included	5 of 5
4	Relationship Outcomes	4 of 5
5	Quality & Project Flow	4 of 5
6	Schedule Considerations	4 of 5
7	Contract Considerations	3 of 5
8	Owner Involvement	3 of 5
9	Future of Early Involvement	3 of 5

Outline

- Project Introduction
- Early Involvement**
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Goal

Considerations / Requirements
 Specifics of this Project
 Typical Problem Areas

Industry Member Interviews


Scopes
 Benefits
 Owner Buy-in
 Future

Mind Maps

Show Topics
 Trace Patterns

Similar Topics		
#	Criteria	Consistency
1	Owner Buy-in	5 of 5
2	Cost Considerations	5 of 5
3	Scope Included	5 of 5
4	Relationship Outcomes	4 of 5
5	Quality & Project Flow	4 of 5
6	Schedule Considerations	4 of 5
7	Contract Considerations	3 of 5
8	Owner Involvement	3 of 5
9	Future of Early Involvement	3 of 5

Mind Maps



Outline


- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Overall Conclusions


Smooth Transition Between Phases

Early Cost Influence

Process Flow



Influence of Cost Curve



Outline

- Project Introduction
- Early Involvement**
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Results

Earlier Involvement is Beneficial

Less Change Orders

Cost Savings

Funding Issues

Scope Selection (Project Specific)

Scope Inclusion Areas

Scopes	Program	Conceptual	Schematic Design	Design Development	Construction Documents	Construction
Contractor	Start-up	Scope Selection & Sign Contract	Sub Selection & Design Input	Sub Selection & Design Input	Design Input & Long Lead Items	Management
MEP	-	Planning, Questions & Sign Contract	Consult w/ Subs	Design Input	Design Input & Long Lead Items	Procurement
Structural	-	-	-	Consult w/ Subs, Design Input & Sign Contract	Design Input & Long Lead Items	Procurement
Curtain Wall	-	-	Consult w/ Subs & Sign Contract	Design Input	Design Input & Long Lead Items	Procurement

Rating Scale

	Owner	CM	Contractor	Design Team
Funding	X	-	-	-
Resources Available	✓	✓	✓	✓
Experience	✓	✓	X	✓

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Caisson Rebar Cage Fabrication Analysis

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab**
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Goal

Determine Appropriate Fabrication Method
Cost Savings
Scheduled Reduction



Picture Provided by Multivista

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab**
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Goal

Determine Appropriate Fabrication Method
 Cost Savings
 Scheduled Reduction

Background

9 Caisson Types (48 Total)
 Prefab to Planned Length
 Planned Lengths Incorrect
 15 Day Delay

Caisson Types

Type	Vertical Rebar #	Qty. of Vertical Rebar	Tie #	# of Ties per LF	Weight of Vertical Rebar (lb/LF)	Weight of Ties (lb/LF)
1a	9	8	4	1	27	6
1b	9	6	4	1	20	6
2a	11	8	4	1	43	9
2b	11	12	4	1	64	11
2c	11	16	4	1	85	13
2d	11	24	4	1	128	15
2e	11	28	5	1	149	21
2f	11	16	4	2	85	27
2g	11	28	5	2	149	41



Picture Provided by Multivista

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab**
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Goal

Determine Appropriate Fabrication Method
 Cost Savings
 Scheduled Reduction

Background

9 Caisson Types (48 Total)
 Prefab to Planned Length
 Planned Lengths Incorrect
 15 Day Delay

Fabrication Methods

100% Planned
 Planed + 10%
 80% of Planned
 10' Sections
 15' Sections

Caisson Types

Type	Vertical Rebar #	Qty. of Vertical Rebar	Tie #	# of Ties per LF	Weight of Vertical Rebar (lb/LF)	Weight of Ties (lb/LF)
1a	9	8	4	1	27	6
1b	9	6	4	1	20	6
2a	11	8	4	1	43	9
2b	11	12	4	1	64	11
2c	11	16	4	1	85	13
2d	11	24	4	1	128	15
2e	11	28	5	1	149	21
2f	11	16	4	2	85	27
2g	11	28	5	2	149	41



Picture Provided by Multivista

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab**
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Results

30' Max Cage Length



Picture Provided by www.rebarsupply.net

Outline


- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Results

- 30' Max Cage Length
- Truck Crane Installation
- Concrete Pump Placement



Picture Provided by www.rebarsupply.net



Picture Provided by Multivista

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Results


- 30' Max Cage Length
- Truck Crane Installation
- Concrete Pump Placement
- High Splice Costs
- Cut-off Higher Productivity



Picture Provided by <http://news.thomasnet.com/>



Picture Provided by www.rebarsupply.net



Picture Provided by Multivista

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab**
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Results

- 30' Max Cage Length
- Truck Crane Installation
- Concrete Pump Placement
- High Splice Costs
- Cut-off Higher Productivity
- Use 100% Prefabricated Method
- Accept Unknowns

Prefabrication Option Comparison

Caisson Types	Base Line	Over 10% Prefab Estimation	Prefab 80% of Estimation	10' Length Sections	15' Length Sections
1a	\$ 1,207.13	\$ 2,018.26	\$ 580.70	\$ 2,545.31	\$ 1,040.01
1b	\$ 1,756.59	\$ 2,059.49	\$ 993.63	\$ 579.61	\$ 285.71
2a	\$ 2,313.82	\$ 2,827.37	\$ 1,856.53	\$ 3,661.62	\$ 1,512.15
2b	\$ 1,845.69	\$ 2,300.02	\$ 937.03	\$ 2,177.57	\$ 260.10
2c	\$ -	\$ -	\$ -	\$ 2,022.40	\$ 1,011.20
2d	\$ 1,516.80	\$ -	\$ 1,516.80	\$ 3,033.60	\$ 1,516.80
2e	\$ 12,484.19	\$12,139.79	\$ 13,377.24	\$ 33,762.24	\$ 15,289.27
2f	\$ -	\$ 243.22	\$ 3,024.00	\$ 3,725.88	\$ -
2g	\$ 1,827.72	\$ 2,183.29	\$ 1,116.59	\$ -	\$ 808.19
Grand Totals	\$ 22,951.94	\$ 32,329.00	\$ 23,402.52	\$ 51,508.23	\$ 21,723.43



Picture Provided by <http://news.thomasnet.com/>



Picture Provided by www.rebarsupply.net



Picture Provided by Multivista

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments


Structural Sequencing Analysis

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing**
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Goal

- Reevaluate Structural Sequence
- Save Erection Costs
- Shorten Erection Schedule



Outline



- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing**
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Goal

- Reevaluate Structural Sequence
- Save Erection Costs
- Shorten Erection Schedule

Background Information

- Current Erection
- Complex Erection Sequence
- 5 Week Delay




Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing**
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Shoring Sequence

Linear





Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing**
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Shoring Sequence

Linear
4-D Comparisons
Slabs After Shoring
Hanger Resizing?



Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing**
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Complexity of Erection

Complex structure
Inconsistent erection sequence

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing**
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Complexity of Erection

Complex structure
Inconsistent erection sequence

Site

Very urban site
Shoring will occupy large area
Tight delivery scheduling



<ul style="list-style-type: none"> 1. Site Fence/ Gate 2. Site Office Trailers 3. Surrounding Buildings 4. Temp. Electric Panel 	<ul style="list-style-type: none"> 5. Soil Stockpile 6. Storage & Laydown 8. Dumpsters 	<ul style="list-style-type: none"> 9. Building Footprint 10. 120 Ton Mobile Crane 11. 200 Ton Crawler Crane 12. Temp. Bathroom 	<ul style="list-style-type: none"> 13. To Be Building Overhang 14. Equipment Ramp to be Removed in this Stage
---	---	--	---

Lowell Stine
 Superstructure
 Site Plan
 Library In
 Metropolitan
 Washington, D.C.
 10/16/13

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing**
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Complexity of Erection

Complex structure
Inconsistent erection sequence

Site

Very urban site
Shoring will occupy large area
Tight delivery scheduling

Safety

High priority
Dangerous welding locations
OSHA compliance



Picture Provided by Multivista



Legend			
1. Site Fence/ Gate	5. Soil Stockpile	9. Building Footprint	13. To Be Building Overhang
2. Site Office Trailers	6. Storage & Laydown	10. 120 Ton Mobile Crane	14. Equipment Ramp to be Removed in this Stage
3. Surrounding Buildings	7. Truck Unloading Area	11. 200 Ton Crawler Crane	
4. Temp. Electric Panel	8. Dumpsters	12. Temp. Bathroom	

Lowell Stine
Superstructure
Site Plan
Library In
Metropolitan
Washington, D.C.
10/16/13

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing**
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Complexity of Erection

Complex structure
Inconsistent erection sequence

Site

Very urban site
Shoring will occupy large area
Tight delivery scheduling


Safety

High priority
Dangerous welding locations
OSHA compliance

Trade Integration

Delay of MEP rough-in start-up

MEP Rough-in Start Dates		
Description	Top-Down Option	Shoring Option
MEP Rough-in Start	10/23/13	11/14/13



Picture Provided by Multivista



<ul style="list-style-type: none"> 1. Site Fence/ Gate 2. Site Office Trailers 3. Surrounding Buildings 4. Temp. Electric Panel 	<ul style="list-style-type: none"> 5. Soil Stockpile 6. Storage & Laydown 8. Dumpsters 	<ul style="list-style-type: none"> 9. Building Footprint 10. 120 Ton Mobile Crane 11. 200 Ton Crawler Crane 12. Temp. Bathroom 	<ul style="list-style-type: none"> 13. To Be Building Overhang 14. Equipment Ramp to be Removed in this Stage
---	---	--	---

Lowell Stine
 Superstructure Site Plan
 Library In Metropolitan Washington, D.C.
 10/16/13

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth**
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Required Shoring Load

Dead Loads
 Live Loads
 $P_u = 291$ psf

$$L = L_0 \times \begin{cases} 0.4 \\ 0.25 + \frac{15}{\sqrt{K_{LL}A_T}} \end{cases}$$

$$P_u = 1.2D + 1.6L$$

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth**
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Required Shoring Load

Dead Loads
 Live Loads
 $P_u = 291 \text{ psf}$

Picking Shoring System

Mabey's Mass Series
 Shoring Towers



Picture Provided by Mabey Inc.



$$L = L_0 \times \begin{cases} 0.4 \\ 0.25 + \frac{15}{\sqrt{K_{LL}A_T}} \end{cases}$$

$$P_u = 1.2D + 1.6L$$

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth**
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Required Shoring Load


Dead Loads
 Live Loads
 $P_u = 291 \text{ psf}$

Picking Shoring System

Mabey's Mass Series
 Shoring Towers

Finalize Shoring Design

Mass 25 - 100 kips
 Space at 20'x18'
 (16) 5'x5' & (2) 5'x10'



Picture Provided by Mabey Inc.



$$L = L_0 \times \begin{cases} 0.4 \\ 0.25 + \frac{15}{\sqrt{K_{LL} A_T}} \end{cases}$$

$$P_u = 1.2D + 1.6L$$

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth**
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Required Shoring Load



Dead Loads
 Live Loads
 $P_u = 291 \text{ psf}$

Picking Shoring System

Mabey's Mass Series
 Shoring Towers

Finalize Shoring Design

Mass 25 - 100 kips
 Space at 20'x18'
 (16) 5'x5' & (2) 5'x10'



Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing**
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Results

3 Week Schedule Savings (with shoring install)


\$30,000 Savings

Better Productivity (Specific Zones)

Recommend the Shoring Sequence

IPEC vs. Mechanical Penthouse		
Criteria & Categories	Top-Down	Shoring
	Constructability	X
Schedule	X	✓
Cost	✓	✓
Site	✓	X
Safety	X	✓
Other Trades	X	✓

Zone Delays



Structure Duration Comparisons

Description	Planned	Top-Down Option	Shoring Option
Steel Erection Start	6/25/13	7/4/13	7/4/13
Structure Complete Milestone	1/1/14	3/7/14	2/13/14
Total Duration (weeks)	28	33	30

Shoring Cost Break Down

Description	Per Tower	Total
Minimum First 4 Weeks	\$1357	\$24,430
Every Week After for 4 Weeks	\$828	\$14,900
Tax (6%)	\$131	\$2,360
Total	\$2,316	\$41,690

Cost Comparisons

Description	Per Tower
General Condition Savings	\$72,000
Shoring Costs	\$41,690
Total Estimated Costs Savings	\$30,000

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room**
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Mechanical Penthouse vs. IPEC Analysis

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room**
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Goals

IPEC & Penthouse Differences
How to Chose Which to Use
Gain Knowledge of Each

Outline


- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room**
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Goals

IPEC & Penthouse Differences
 How to Chose Which to Use
 Gain Knowledge of Each


IPEC

Prefabricated Equipment Module
 4' CMU Base Wall
 One Supplier



Provided by MBP (Construction Documents Courtesy of MBP)

Integrated Packaged Equipment Center (IPEC)



Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room**
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Goals

IPEC & Penthouse Differences
 How to Chose Which to Use
 Gain Knowledge of Each

IPEC

Prefabricated Equipment Module
 4' CMU Base Wall
 One Supplier

Mechanical Penthouse


Site Constructed
 On Concrete Structural Roof
 Multiple Different Suppliers

Mechanical Penthouse



Picture Provided by <http://www.jetsongreen.com/>

Integrated Packaged Equipment Center (IPEC)



Outline


- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth**
- Summary of Conclusions
- Acknowledgments

Acoustical Impacts of IPEC and Penthouse

Library Spaces
Outdoor Environment

Differences

Similar Acoustical Properties
Over Estimates



Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth**
- Summary of Conclusions
- Acknowledgments

Acoustical Impacts of IPEC and Penthouse

Library Spaces
Outdoor Environment


Differences

Similar Acoustical Properties
Over Estimates

Recommendations

IPEC Would Be More Desirable

Noise Levels		
	Limit	Actual
Conference Room	35 dB	37 dB
Property Line	55 dB	57 dB



Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room**
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Results

1 Week On Site vs. 10.5 Weeks On Site

Potential \$1 Million Savings

Flexible Design

Penthouse

Design-Build Package

IPEC vs. Mechanical Penthouse Schedule		
System	Lead Time	Site Install Time
IPEC	1 Long Lead Item (Months)	1 Week
Penthouse	Multiple Shorter Lead Times (Weeks)	10.5 Weeks

IPEC vs. Mechanical Penthouse Costs			
System	Equipment	Enclosure/ Structure	Total
IPEC	\$5,800,000	\$50,000	\$5,850,000
Penthouse	\$4,880,000	\$100,000	\$4,880,000

IPEC vs. Mechanical Penthouse

Criteria & Categories	IPEC	Penthouse
Acoustical	✓	✓
Maintenance	x	✓
Flexibility in Design	x	✓
Responsibility	✓	✓
Constructability	✓	✓
Costs	x	✓
Schedule	✓	x

Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments

Design (Early Involvement)



Foundation (100% Prefabrication Cage Length)



Structure (Shoring Sequence)



Building Systems (Mechanical Penthouse)

Early Involvement

Undetermined Cost Savings
Undetermined Schedule Savings

100% Prefabrication Cage Length


\$0.00 Savings
Account for Caissons in Schedule

Shoring Sequence

\$30,000 Savings
3 Week Schedule Savings

Mechanical Penthouse

Possible \$1 Million Savings
Additional 9.5 Week Mechanical Schedule



Outline

- Project Introduction
- Early Involvement
- Caisson Rebar Cage Prefab
- Structural Sequencing
- Structural Breadth
- Mechanical Room
- Acoustical Breadth
- Summary of Conclusions
- Acknowledgments**

Academic

Michelle Vigeant
 Moses Ling
 Dr. Robert Leicht
 Kevin Parfitt
 Ray Sowers

Special Thanks

Library's Owner
 PACE Industry Members
 Matt Strevig
 Friends and Family




Questions?



Picture Provided by Multivista


Current Structural Schedule



General Conditions Costs

Description	Quantity	Unit	Per/Unit	Total
Site Signage (Fence Cloth)	4,588	SF	\$36.04	\$165,351.52
Perimeter Fencing	1,185	LF	\$6.32	\$7,489.20
Office Trailers (2)	22	Month	\$361.00	\$15,884.00
Air Conditioning	22	Month	\$48.76	\$1,072.72
125 Ton Crane	20	Month	\$16,000.00	\$320,000.00
200 Ton (Crane Steel)			N/A	
1-1/2 CY Excavator	33	Month	\$8,700.00	\$287,100.00
Backhoe 1-1/4 CY	22	Month	\$3,013.00	\$66,286.00
500 BTU Heater	15	Month	\$425.00	\$6,375.00
Portable Toilet	22	Month	\$191.78	\$4,219.16
Permits	\$3,589,000.00	%	0.50%	\$17,945.00
Field Office Bills	22	Month	\$377.00	\$8,294.00
Main Office Expense	\$3,589,000.00	%	3.90%	\$139,971.00
Builders Risk Insurance	\$3,589,000.00	%	0.42%	\$15,000.00
Performance Bond	\$3,589,000.00	%	2.79%	\$100,000.00
Liability Insurance	\$3,589,000.00	%	2.79%	\$100,000.00
Multivista (Construction Documentations/ Webcam)	23	Month	\$1,700.00	\$39,100.00
Project Executive	22	Week	\$2,475.00	\$54,450.00
LEED Submittal Fees	22	Month	\$727.27	\$16,000.00
CM Fees	\$3,589,000.00	%	3.00%	\$107,670.00
Field Engineer	88	Week	\$1,325.00	\$116,600.00
Project Manager	88	Week	\$2,150.00	\$189,200.00
Superintendent	88	Week	\$2,000.00	\$176,000.00
General Purpose Laborer	88	Week	\$1,425.00	\$125,400.00
Schedule Maintainance	\$3,589,000.00	%	0.03%	\$1,076.70
Temp. 600 Amp Elec.	1	EA	\$3,621.00	\$3,621.00
Temp. 75kVA Transformer	1	EA	\$3,993.00	\$3,993.00
Office Trailer Hook-Up	2	EA	\$374.00	\$748.00
After Job Clean-up	\$3,589,000.00	%	0.30%	\$10,767.00
Waste Removal Dumpster	88	Week	\$340.91	\$30,000.00
Site Water	22	Month	\$70.00	\$1,540.00
Commissioning	\$3,589,000.00	%	0.25%	\$8,972.50
Total				\$2,140,125.80
Project Planned Duration (Weeks)				88
Total General Condition Costs per Week				\$24,319.61

Shoring Sequence Schedule



Dead Load Calculations

Dead Load Calculations				
Description	Sizes	lb/LF	Spacing (ft)	lb/SF
Columns	W14x82	82	40x50	2
Trusses	W14x283	283	40	7
	W14x90	90	40	2
	W14x99	99	40	2
End Truss	W14x233	233	50	5
	W14x90	90	50	2
3rd Floor Girder	W36x135	135	40	3
	W24x55	55	40	1
3rd Floor Beams	W27x84	84	10	8
4th Floor Girder	W27x84	84	40	2
4th Floor Beams	W21x50	50	10	5
5th Floor Beams	W27x84	84	10	8
Roof Floor Beams	W21x44	44	5	9
Decking				5
Allowance				8
Total Dead Load (lb/SF)				70

Live Load & Factored Loads

Live Load Calculations			
	Live Load of Construction Surface		50
	# of Floors		4
Live Load Allowance (lb/SF) = L_0			200
	K_{LL}		4
	Tributary Area = A_T	20x18	360
	$SQRT(K_{LL} * A_T)$		37.95
	$0.25 + \{15 / SQRT(K_{LL} * A_T)\}$		0.65
Not smaller than 0.4 so use 0.65			
Live Load Reduced (lb/SF) = L			129
Total Load Calculations			
Total Load = $1.2D + 1.6L$ (lb/SF) = P_u			291
Shoring Tower Estimated Spacing			20x18
Total Estimated Load per Shoring Tower (kip)			105

Live Load Assumptions

Started with 50 psf

Four floors is 200 psf

In live load reduction total is 129 psf

Factored live load would then be 206 psf
(This would be an acceptable live load on four floors of **only structure**)

Zone 2 Acoustics

Transmission Losses (dB)							
Octave-band Center Frequencies	125 Hz	250 Hz	500 Hz	1000 Hz	2000 Hz	4000 Hz	STC Rating
Floor of IPEC	37.0	45.0	54.0	60.0	65.0	47.0	62.0

Absorption Under IPEC Zone 2													
Surface	Area (Sq. ft.)	Absorption Coefficients											
		125 Hz	250 Hz	500 Hz	1000 Hz	2000 Hz	4000 Hz	125 Hz	250 Hz	500 Hz	1000 Hz	2000 Hz	4000 Hz
Concrete	128	0	0	0	0	0	0	1	1	3	3	3	3
Ridged Insulation (3in.)	346	0	1	1	1	1	1	131	207	270	276	270	242
Metal IPEC Bottom	128	0	0	0	0	0	0	19	24	28	50	49	38
Total Absorption (sabins): $a = \sum S\alpha \rightarrow$								151.81	232.96	300.29	328.96	320.77	282.88

Estimated Noise Level in Zone 2						
Octave-band Center Frequencies	125 Hz	250 Hz	500 Hz	1000 Hz	2000 Hz	4000 Hz
TL between IPEC and Under IPEC Zone 2	37	45	54	60	65	47
a_2	152	233	300	329	321	283
Surface Area Between Spaces (sq. ft.)	160					
Noise Reduction of Noise Coming from IPEC	37	47	57	63	68	49
Sound Pressure in IPEC	86	85	84	83	82	80
Sound Pressure in Zone 2 From IPEC Space	49	38	27	20	14	31

Conference Room Acoustics

Transmission Losses (dB)								
Octave-band Center Frequencies		125 Hz	250 Hz	500 Hz	1000 Hz	2000 Hz	4000 Hz	STC Rating
8" reinforced concrete slab		44.0	48.0	55.0	58.0	63.0	67.0	58.0

Absorption of Staff Conference Space													
Surface	Area (Sq. ft.)	Absorption Coefficients											
		125 Hz	250 Hz	500 Hz	1000 Hz	2000 Hz	4000 Hz	125 Hz	250 Hz	500 Hz	1000 Hz	2000 Hz	4000 Hz
Carpet on Foam	409	0	0	1	1	1	1	33	98	233	282	291	299
Gypsum Board, 5/8"	506	1	0	0	0	0	0	279	71	41	20	61	56
Acoustical Ceiling, 3/4"	409	1	1	1	1	1	1	311	381	340	405	405	385
Chairs, Occupied	32	0	0	0	1	1	1	10	13	16	27	28	27
Total Absorption (sabins): $a = \sum S\alpha \rightarrow$								632	562	629	735	784	766

Between Zone 1 and Staff Conference Space							
Surface Area Between Spaces (sq. ft.)	325						
Noise Reduction of Noise Coming from Zone 1	42	48	56	60	65	68	
Sound Pressure in Zone 1	86	85	84	83	82	80	
Sound Pressure in Staff Conference Space from Zone 1	44	37	28	23	17	12	

Between Zone 2 and Staff Conference Space							
Surface Area Between Spaces (sq. ft.)	120						
Noise Reduction of Noise Coming from Zone 2	47	52	60	64	69	72	
Sound Pressure in Zone 2	49	38	27	20	14	31	
Sound Pressure in Staff Conference Space from Zone 2	3	-14	-33	-44	-55	-42	

Between Zone 3 and Staff Conference Space							
Surface Area Between Spaces (sq. ft.)	293						
Noise Reduction of Noise Coming from Zone 3	43	48	57	60	65	69	
Sound Pressure in Zone 3	86	85	84	83	82	80	
Sound Pressure in Staff Conference Space from Zone 3	43	37	27	23	17	11	

Between Zone 4 and Staff Conference Space							
Surface Area Between Spaces (sq. ft.)	144						
Noise Reduction of Noise Coming from Zone 4	46	52	60	63	68	72	
Sound Pressure in Zone 4	86	85	84	83	82	80	
Sound Pressure in Staff Conference Space from Zone 4	40	33	24	20	14	8	

Estimated Sound Pressure Level in Staff Conference Space						
Octave-band Center Frequencies	125 Hz	250 Hz	500 Hz	1000 Hz	2000 Hz	4000 Hz
From Zone 1	44	37	28	23	17	12
From Zone 2	3	-14	-33	-44	-55	-42
From Zone 3	43	37	27	23	17	11
From Zone 4	40	33	24	20	14	8
Add From Zone 1 and 2 Combined	0	0	0	0	0	0
From Zone 1 and 2 Combined	44	37	28	23	17	12
Add From Zones 3 and 4 Combined	2	1	2	2	2	1
From Zones 3 and 4 Combined	45	38	29	25	19	12
Add From Zone (1 and 2) and (3 and 4) Combined	3	3	3	2	2	3
Estimated Sound Level in Staff Conference Space from IPEC	48	41	32	27	21	15
A-Weighting	-15	-8	-3	0	1	1
A-Weighted Noise from IPEC	33	33	29	27	22	16
dB Addition Add	3		2		1	
Result	36		31		23	
dB Addition Add	1				0	
Result	37				23	
dB Addition Add	0					
Sound Level	37 dB					

Equipment

Quantity	Assembly Number	Description	Unit	Material O&P	Installation	Total O&P	Ext. Material O&P	Ext. Installation	Ext. Total
4	D30201061080	Boiler, gas, cast iron, hot water, 1,088 MBH	Ea.	\$ 14,914.90	\$ 4,706.35	\$ 19,621.25	\$ 59,659.60	\$ 18,825.40	\$ 78,485.00
90000	D30301154040	Packaged chiller, water cooled, with fan coil unit, offices, 60,000 SF, 190.00 ton	S.F.	\$ 7.76	\$ 5.19	\$ 12.95	\$ 698,400.00	\$ 467,100.00	\$ 1,165,500.00
40000	D30201081280	Heating systems, CI boiler, gas, terminal unit heaters, 80 MBH, 1,070 SF bldg	S.F.	\$ 10.76	\$ 7.56	\$ 18.32	\$ 430,400.00	\$ 302,400.00	\$ 732,800.00
90000	D30501703680	Split system, air cooled condensing unit, offices, 20,000 SF, 63.32 ton	S.F.	\$ 5.46	\$ 4.64	\$ 10.10	\$ 491,400.00	\$ 417,600.00	\$ 909,000.00
5	D30203301030	Pump, base mounted with motor, end-suction, 4" size, 7-1/2 HP, to 350 GPM	Ea.	\$ 15,015.00	\$ 4,107.50	\$ 19,122.50	\$ 75,075.00	\$ 20,537.50	\$ 95,612.50
2	D30203301020	Pump, base mounted with motor, end-suction, 3" size, 5 HP, to 225 GPM	Ea.	\$ 12,812.80	\$ 3,426.30	\$ 16,239.10	\$ 25,625.60	\$ 6,852.60	\$ 32,478.20
2	D30203301040	Pump, base mounted with motor, end-suction, 5" size, 15 HP, to 1000 GPM	Ea.	\$ 20,720.70	\$ 6,050.15	\$ 26,770.85	\$ 41,441.40	\$ 12,100.30	\$ 53,541.70
11	D30203301010	Pump, base mounted with motor, end-suction, 2-1/2" size, 3 HP, to 150 GPM	Ea.	\$ 11,711.70	\$ 2,994.10	\$ 14,705.80	\$ 128,828.70	\$ 32,935.10	\$ 161,763.80
90000	D30301103400	Packaged chiller, air cooled, with fan coil unit, offices, 6,000 SF, 19.00 ton	S.F.	\$ 9.71	\$ 5.68	\$ 15.39	\$ 873,900.00	\$ 511,200.00	\$ 1,385,100.00
1	D30406101010	Plate heat exchanger, 400 GPM	Ea.	\$ 53,553.50	\$11,745.60	\$ 65,299.10	\$ 53,553.50	\$ 11,745.60	\$ 65,299.10
2	D30402401040	Roof vent. system, power, centrifugal, aluminum, galvanized curb, back draft damper, 2750 CFM	Ea.	\$ 3,578.58	\$11,446.60	\$ 15,025.18	\$ 7,157.16	\$ 22,893.20	\$ 30,050.36
1	D30402401030	Roof vent. system, power, centrifugal, aluminum, galvanized curb, back draft damper, 1500 CFM	Ea.	\$ 2,402.40	\$ 5,061.10	\$ 7,463.50	\$ 2,402.40	\$ 5,061.10	\$ 7,463.50
1.33	D30401161050	AHU, rooftop, cool/heat coils, VAV, filters, 30,000 CFM	Ea.	\$173,173.00	\$17,149.20	\$ 190,322.20	\$ 230,320.09	\$ 22,808.44	\$ 253,128.53
1.1	D30401161030	AHU, rooftop, cool/heat coils, VAV, filters, 15,000 CFM	Ea.	\$116,616.50	\$12,413.80	\$ 129,030.30	\$ 128,278.15	\$ 13,655.18	\$ 141,933.33
Subtotals							\$ 3,246,441.60	\$ 1,865,714.42	\$ 5,112,156.02
Location Scale								91%	\$4,652,061.98
GC OH & Profit								5%	\$232,603.10
Grand Total									\$ 4,884,665.08

Enclosure

Quantity	Assembly Number	Description	Unit	Material O&P	Installation	Total O&P	Ext. Material O&P	Ext. Installation	Ext. Total
		Floor is Same Structural Concrete				\$ -	\$ -	\$ -	\$ -
3000	B10201206400	Steel Joist Roof	S.F.	\$ 5.05	\$ 2.96	\$ 8.01	\$ 15,150.00	\$ 8,880.00	\$ 24,030.00
3000	B30101206500	Single Ply 60 mils, PVC Membrane Roof Coverings Adhered	S.F.	\$ 1.41	\$ 0.92	\$ 2.33	\$ 4,230.00	\$ 2,760.00	\$ 6,990.00
3750	B2010146	Corrugated 22 Ga. Galvanized Steel with Structural Steel Support, Colored	S.F.	\$ 4.19	\$ 3.60	\$ 7.79	\$ 15,712.50	\$ 13,500.00	\$ 29,212.50
3000	D50202360960	Low Bay Lighting Fixtures, 250 watt Metal Halide	S.F.	\$ 4.23	\$ 5.55	\$ 9.78	\$ 12,690.00	\$ 16,650.00	\$ 29,340.00
		Allowance				\$ -	\$ -	\$ -	\$ 12,000.00
Subtotals							\$ 47,782.50	\$ 41,790.00	\$101,572.50
Location Scale								91%	\$92,532.55
Inflation of 3 Years								3%	\$95,308.52
GC OH & Profit								5%	\$4,765.43
Grand Total									\$100,073.95

Equipment

Quantity	Assembly Number	Description	Unit	Productivity (units/day)	Crews	Duration (days)
4	D30201061080	Boiler, gas, cast iron, hot water, 1,088 MBH	Ea.	0.3	3	4.4
2	D30301154040	Packaged chiller, water cooled, with fan coil unit, offices, 60,000 SF, 190.00 ton	Ea.	0.1	3	6.7
2	D30501703680	Split system, air cooled condensing unit, offices, 20,000 SF, 63.32 ton	Ea.	0.4	1	5.0
5	D30203301030	Pump, base mounted with motor, end-suction, 4" size, 7-1/2 HP, to 350 GPM	Ea.	5	1	1.0
2	D30203301020	Pump, base mounted with motor, end-suction, 3" size, 5 HP, to 225 GPM	Ea.	7	1	0.3
2	D30203301040	Pump, base mounted with motor, end-suction, 5" size, 15 HP, to 1000 GPM	Ea.	3	1	0.7
11	D30203301010	Pump, base mounted with motor, end-suction, 2-1/2" size, 3 HP, to 150 GPM	Ea.	7	1	1.6
2	D30301103400	Packaged chiller, air cooled, with fan coil unit, offices, 6,000 SF, 19.00 ton	Ea.	0.3	1	6.7
1	D30406101010	Plate heat exchanger, 400 GPM	Ea.	0.8	1	1.3
2	D30402401040	Roof vent. system, power, centrifugal, aluminum, galvanized curb, back draft damper, 2750 CFM	Ea.	2	1	1.0
1	D30402401030	Roof vent. system, power, centrifugal, aluminum, galvanized curb, back draft damper, 1500 CFM	Ea.	2	1	0.5
1.33	D30401161050	AHU, rooftop, cool/heat coils, VAV, filters, 30,000 CFM	Ea.	0.3	1	4.4
1.1	D30401161030	AHU, rooftop, cool/heat coils, VAV, filters, 15,000 CFM	Ea.	0.3	1	3.7
Total Days						37

Enclosure

Quantity	Assembly Number	Description	Unit	Productivity (units/day)	Crews	Duration (days)
		Floor is Same Structural Concrete				
2400	B10201206400	Steel Joist Roof	L.F.	160	2	7.5
2400	B30101206500	Single Ply 60 mils, PVC Membrane Roof Coverings Adhered	S.F.	250	2	4.8
2400	B2010146	Corrugated 22 Ga. Galvanized Steel with Structural Steel Support, Colored	L.F.	800	1	3
Total Days						15.3