

Thesis Proposal

The Apartment Building
East Coast, USA

B. Kerem Demirci | Construction Option | Advisor: Dr. Messner | 12.15.14



Source: JMAV

EXECUTIVE SUMMARY

The Apartment Building is a high-end residential building located in a historic metropolitan city on the East Coast. It consists of ten stories above grade, amounting to 151,158 SF. The building also has a two-story, 62,250 SF underground parking garage. This proposal identifies key problematic areas of The Apartment Building and describes various analyses that will be completed to address these problems. Below is a summary of the main analyses.

Analysis 1: Apartment Market Demand Evaluation

The critical industry research will focus on an apartment market demand evaluation. The goal of this research is to create a guide to performing a basic market analysis. This research will help determine where and how to begin, where to obtain information, how to implement basic tools and how to apply all this information to a specific project. Once the procedure and tools are identified, a market analysis can be conducted for The Apartment Building in hopes of validating the design decisions that are currently being implemented as well as finding opportunities for design changes that will improve the marketability of The Apartment Building making the project even more successful.

Analysis 2: Exterior Enclosure Acceleration

Analysis 2 looks into methods of accelerating the exterior enclosure that was behind schedule due to a harsh winter. In this analysis will focus on the use of prefabricated brick and masonry panels as opposed to the traditional stick-build system that is being used. An appropriate system will be designed and the cost and schedule impact will be analyzed. In addition a structural and mechanical breadth will be done on the new prefabricated enclosure. A structural analysis will determine if any changes will need to be done to the structure to support the panels and the interface between the panels and structure will be detailed. A mechanical analysis will be done to ensure the new building enclosure is not compromising mechanical performance.

Analysis 3: SIPS Implementation for Interior Fit-out

Due to the stringent schedule dictated by the phased turnover of the building, high level of quality and the repetitive nature of the apartment units, short interval production scheduling will be implemented for interior fit out. An implementation guide will be developed for best practices for SIPS for interior fit out. SIPS will then be implemented on The Apartment Building.

Analysis 4: Tools to Support SIPS Implementation

Building off the SIPS implementation and the BIM execution guide developed in Technical Report 3, Analysis 4 will look into potential BIM uses that can be used to support the implementation of SIPS on interior fit out. It is expected that the quality, predictability and management of the SIPS implementation can be benefitted by applying some BIM uses.

CONTENTS

Executive Summary	i
Project Background	1
Analysis 1: Apartment Market Demand Evaluation *Critical Industry Issue	2
Analysis 2: Exterior Enclosure Acceleration	4
Analysis 3: SIPS Implementation for Interior Fit-out	6
Analysis 4: Tools to Support SIPS Implementation	9
Appendix 1 – Breadth Studies	12
Appendix 2 – Spring Analysis Schedule	13
Appendix 3 – Analysis Weight Breakdown	14
Appendix 4 – MAE Requirements	15

PROJECT BACKGROUND

The Apartment Building is a new high end residential building. The Apartment Building is primarily a post tensioned cast-in-place concrete structure enclosed by stone and brick veneer. The building extends ten stories above grade, reaching a height of 99 feet and totaling approximately 151,000 SF. This space provides room for 165 high quality apartment units that average 767 SF per unit. Ten of the units are designated affordable housing for 40 years which allows the maximum zoning height restriction to increase from 77 feet to 99 feet. Below grade, lie two garage levels that provide 153 parking spaces for the building tenants. A 10,000 SF public pedestrian park along with an outdoor pool is located outside the south face of the building. The ground floor houses amenities such as a lounge, business center, and fitness room. An additional club room is located on the fifth floor. Accessible terraces are located on the fifth and eighth floor and include gas grills, gas fire pits, and water/gas features. The total contract value of the negotiated GMP contract is \$32,752,717, or \$216.75 per SF.



Figure 1: Rendering of the Apartment Building (JMAV)



Figure 2: Site photo during construction

The client for The Apartment Building is BMPI. BMPI is a partnership between three main investors of which one is the owner of the general contractor of this project, John Moriarty & Associates (JMA). The other two partners are a developer out of Boston and a local developer. The goal of BMPI is to promote the growth of an up and coming metro accessible area. The Apartment Building received the notice to proceed on February 11th, 2013 and will reach substantial completion on February 13, 2015, resulting in a duration of roughly 24 months. The post-tensioned concrete structure was completed in June, 2014, roughly 16 months after notice to proceed. Turnover of this building will be done in phases, allowing early revenue for the owner. The first phase of turnover is planned for December 10th, 2014 and includes the garage through the 2nd floor. From this point on the schedule dictates a turnover rate of a floor per week.

ANALYSIS 1: APARTMENT MARKET DEMAND EVALUATION *CRITICAL INDUSTRY ISSUE

PROBLEM IDENTIFICATION

Any building owner must first properly understand the market before developing any project. The general contractor on The Apartment Building is essentially acting as an owner-builder. John Moriarty, the owner of John Moriarty & Associates, is one three main investors of The Apartment Building. As an owner-builder, the ultimate goal of the owner is to maximize the rentability of the apartment units. Decisions made in the planning, design and construction phase of the project can all have an effect on the marketability of the apartment.

BACKGROUND RESEARCH

A commonly used tool to ensure the building is well targeted and competitive and to identify opportunities is market research and analysis. A market evaluation can help determine the most marketable and ultimately profitable unit sizes, unit types (studio, 1 bedroom, and 2 bedroom), appliances, amenities and finishes. The market is constantly fluctuating so it is essential to conduct a proper market evaluation to ensure maximum marketability.

POTENTIAL SOLUTION

As an educational research study, the process of market analysis will be studied. The goal of this research is to create a guide that will help industry members conduct their own market analysis without hiring a professional real estate consultant. This research will help find out where and how to begin, where to obtain information, how to implement basic tools and how to apply all this information to a project. Once the procedure and tools are identified, a market analysis can be conducted for The Apartment Building in hopes of validating the design decisions that are currently being implemented as well as finding opportunities for design changes that will improve the marketability of The Apartment Building making the project even more successful.

The needs and goals of the owner must also be factored into the equation. In order to accurately implement the results of the market analysis with the needs of the owner to make design decisions, the House of Quality will be used. House of Quality is the basic tool of the QFD (Quality Function Deployment) approach. House of quality will help better understand the owner and the market and translating this information into targets for design so educated decisions can be made.

Identifying design considerations that maximize marketability earlier in the design process, as opposed to owner initiated change orders during construction, will be more cost effective and

have minimal a minimal impact to the construction schedule. Understanding the market and what drives the owner, can be beneficial for the contractor and help the contractor keep consistent with the owner's goals

ANALYSIS PROCEDURE

1. Determine if a third party consultant was hired to complete a market analysis on The Apartment Building
2. Research market analysis methods
3. Document the market evaluation process
 - a. General process
 - b. How to begin
 - c. Where to obtain information
 - d. Basic tools
 - e. Best practices
4. Compare findings from market analysis to The Apartment Building
5. Make necessary design changes while implementing a QFD approach using House of Quality

EXPECTED OUTCOME

It is expected that sufficient market research has been done during the programming and design phase of The Apartment Building. The improvements to the design most likely will not be drastic and will be more geared to amenities, appliance, finishes etc.

RESOURCES

- Literature
 - "Real Estate Market Analysis: Methods and Case Studies" (Brett, Schmitz)
- Professional Resources
 - MacWilliams Ballard
 - Cassidy Turley
- Academic Resources
 - Institute for Real Estate Studies (IRES) at Penn State
 - Georgetown University Real Estate faculty
 - Phil Fogarty, Master of Professional Studies in Real Estate student at Georgetown University

ANALYSIS 2: EXTERIOR ENCLOSURE ACCELERATION

PROBLEM IDENTIFICATION

According to the baseline schedule, exterior masonry work was set to begin during the winter. However, a harsh winter affected 26 days of construction which had a negative impact on the schedule. This bad weather delayed the concrete structure and ultimately the exterior enclosure that was planned to begin in the winter. The exterior masonry is a vital component of the building enclosure system which puts it on the critical path making it an essential activity of the overall schedule. The enclosure for The Apartment Building is complex in that it uses a multitude of different materials: brick, architectural masonry units, metal cladding and cast stone. Many types of each material is also used. The Apartment Building uses four types of brick, 3 types of mortar, 6 types of ACMU and 3 types of cast stone. In addition, multiple materials are used on each floor of the buildings as opposed to just one. In a previous interview with the project manager, he mentioned that it was very difficult to get into a productive flow due to the many different material types. This is not ideal especially after the schedule has already been pushed due to weather delays.

BACKGROUND RESEARCH

Prefabrication is the process of assembling certain components of a larger product offsite then transporting these assemblies to the jobsite for installation. Prefabrication can apply to almost any trade in construction. Prefabricated masonry and brick panels have many benefits.

- Decreased site congestion
- Schedule acceleration
- Safer work environment
- Increased quality control
- Less onsite scaffolding
- Prefabrication can be done in any weather

With the benefits come some disadvantages

- Size of the panels are limited by transportation and erection limitations
- Joints between panels may not be desired

There are two common ways of prefabricating brick masonry panels: hand-laying and casting. Once the panels are made they are transported to the job site then installed using a crane.

POTENTIAL SOLUTIONS

This analysis will look into various opportunities to reduce the schedule for the exterior work. Traditional brick installation practices were used. This process is very labor intensive and ultimately inefficient. A possible solution is the use of prefabrication of the exterior masonry into modular panels. An analysis will be completed to study the implementation of prefabricated masonry panels as well as resequencing the installation process.

ANALYSIS PROCEDURE

1. Identify advantages and disadvantages of prefabricated brick system
2. Design an appropriate prefabricated masonry system
 - a. Hand-laying vs. casting
 - b. Determine transportation and hoisting restricts
3. Create sequencing plan for installation and site utilization
4. Perform schedule analysis
5. Perform cost impact analysis
6. Structural analysis
 - a. Detail connections
 - b. Determine is the current structure can support the panels
7. Mechanical analysis
 - a. Compare mechanical properties to original enclosure

EXPECTED OUTCOME

It is expected that implementing prefabricated masonry panels, the overall schedule of the project will be accelerated. This will result reaching water tight status faster and beginning interior work sooner.

RESOURCES

- Professional Resources
 - The Brick Industry Association
 - Precast brick and masonry fabricators
- Academic Resources
 - AE 542: Building Enclosure Science and Design
 - AE 404: Building Structural Systems in Steel and Concrete course material

- AE 308: Introduction to Structural Analysis course material
- Dr. Boothby, Professor of Architectural Engineering
- Dr. Hanagan, Associate Professor of Architectural Engineering

ANALYSIS 3: SIPS IMPLEMENTATION FOR INTERIOR FIT-OUT

PROBLEM IDENTIFICATION

As part of the owner's investment strategy, The Apartment Building is being turned over in phases in order to bring in revenue before the building is entirely complete. With a phased turnover comes many caveats, quality and phasing are critical. If proper quality control measures are not taken, the extended punchlist and project closeout can result in late turnover which ultimately will impact the owner's financial model. During a phased turnover project, construction and occupancy are occurring concurrently there are many factors that can impact the experience of the occupant and ultimately affect their health and safety. It is vital that each floor is turned over on time and at the proper level of quality. The current CPM schedule is only detailed down to the trades per floor. Without further detailed scheduling it is common for the deadlines to not be met.

BACKGROUND RESEARCH

The main idea behind a successful schedule is the lean concept of flow. As defined in, "Lean Thinking," flow is the process of making value without interruption by eliminating wasteful activities and creating sequential arrangements. In this case, value would be defined as timely turnover of each floor and high quality of work so rework is not necessary. The main principles of flow include lining up the essential steps to get the job done without any waste, interruptions, and batching and queuing. This basic lean concept can be applied to any process.

Short interval production scheduling or SIPS, is a method of scheduling that envelops the concept of flow. SIPS is a whole system of production management that focuses on the interconnections between trades and the flow of trades through the building. SIPS focus down to the trade level and takes into account material, labor and other resources of each trade. There are many benefits to using SIPS. Some include: eliminating the stacking of trades, predictability, minimizing learning curve, leveling resources, and quality control becomes an inherent part of the process. SIPS is an iterative process that requires more than a single matrix schedule, which is often confused as a SIPS. The process of implementing SIPS requires full team buy in, continuous communication between trades, and room for buffers.

Hensel Phelps pioneered SIPS to construct the structure of the Tabor Center. Alvin Burkhart, who worked for Hensel Phelps, documented the process and created a guide for successful SIPS implementation. According to the guidelines the SIPS process can be broken up into three main phases.

Phase 1 – Operation, Schedule, Budget, Goals

Phase 2 – Physical Constraints, Resource Requirements, Sequence/Coordination/Balance

Phase 3: Communicate the Plan, Feedback, Follow-through

POTENTIAL SOLUTIONS

Due to the repetitive nature of The Apartment Building, a need for stringent quality control, and the tight schedule constrained by the phased turnover a possible solution is to implement short interval production scheduling as well as and matrix scheduling for interior fit out. SIPS is often confused with matrix scheduling. SIPS is focused at the trade level and the process associated with completing the work. Matrix scheduling is a tool that is used within SIPS to manage the flow of various trades throughout the building. Currently a guide that focuses on SIPS for interior fit out does not exist.

In this analysis, a SIPS planning guide will be created for interior fit out. This guide will include best practices for implementing the SIPS process for interior fit out at the trade level. This guide will include the steps each trade would need to take to create a detailed, resource loaded schedule in order to meet a set interval. The guide will also include how to implement matrix schedules to coordinate the flow of trades through spaces. This SIPS implementation guide will then be used on The Apartment Building.

ANALYSIS PROCEDURE

1. Research projects that have implemented SIPS (Tabor Center, Pentagon, MGM Grand)
2. Develop SIPS Implementation Guide for interior fit out
 - a. Process of creating the schedule
 - i. Setting the interval
 - ii. Breaking down the activities
 - iii. Determining prerequisite activities
 - iv. Calculating production
 - v. Creating a schedule
 - vi. Leveling resources
 - vii. Creating buffers

- viii. Creating a matrix schedule and various visual tools
 - b. Best practices for Implementing the schedule
 - i. Achieving team buy in
 - ii. Methods for continual improvement
 - iii. Tools for production tracking
 - iv. Methods for quality control
 3. Apply the SIPS Implementation Guide to interior fit out work on The Apartment Building as an educational exercise.

EXPECTED OUTCOME

Through creating a guide and implementing SIPS to interior fit out activities on The Apartment Building, it is expected that the flow of work will be improved and waste will be mitigated. The work flow will be more predictable and easier to manage resulting in timely turnover of floors and increased quality control.

RESOURCES

- Literature
 - "Lean Thinking" (Womack, Jones)
 - "Improving Productivity with Short-Interval Scheduling" (Strutt)
 - "The Secret to Short-Interval Scheduling" (Daneshgari, Moore)
- Case Studies
 - Tabor Center chimney wall
 - MGM Grand precast
 - Pentagon Renovation
- Professional Resources
 - Adam Harrison, Project Manager on The Apartment Building
 - Rob Soper , Superintendent at Grunley Construction
- Academic Resources
 - Dr. Rob Leicht, AE 570:Production Management in Construction

ANALYSIS 4: TOOLS TO SUPPORT SIPS IMPLEMENTATION

PROBLEM IDENTIFICATION

As mentioned in Analysis 3, The Apartment Building is being turned over in phases. With a phased turnover, quality control is of higher importance in order to prevent rework in occupied spaces. During the construction of The Apartment Building, many coordination issues arose. For example, sleeves were missed or incorrectly placed during the placement of the concrete floors. Missed sleeves pose a major issue in a post-tensioned concrete slab. The only solution for a missed sleeve is to core drill through the slab, which is extremely risky. If a steel tendon is hit, the tendon could snap and whip through the concrete slab and cause structural damage and become a safety hazard.

On The Apartment Building, Building Information Modeling (BIM) was primarily used only in the design phase by the architect to create the model in 3D. This 3D model was strictly used for design purposes and was not transferred over to the contractor for use during construction. There is a large spectrum of BIM uses that can be applied to the planning, design, construction, and operation phase of the project. There are a multitude of BIM uses that can benefit the construction phase of the project and support the SIPS implementation discussed in Analysis 3.

BACKGROUND RESEARCH

As defined by the National Building Information Modeling Standards Committee, Building Information Modeling (BIM) is a, "digital representation of a physical and functional characteristics. A BIM is a shared knowledge resource for information about a facility forming a reliable basis for decisions during its life-cycle; defined as existing from earliest conception to demolition." BIM is a process, not just a tool. It is the processes of effectively exchanging information between all disciplines to help proctor planning, design, construction and operation decisions.

BIM uses are only as effective as the plan used to implement the information exchanges. The BIM Project Execution Planning Guide (BIMex), is a guide developed by Penn State to provide a structured procedure for implementing BIM on a project.

According to Penn State's BIM Execution Planning website, the five most frequently used BIM uses are 3D coordination, design reviews, design authoring, construction system design, existing conditions modeling. There are roughly 25 various BIM uses that are identified in the BIM Execution Planning website.

POTENTIAL SOLUTIONS

In Analysis 3, SIPS processes will be implemented on interior fit out for the Apartment Building. Building off this, Analysis 4 will look into supplementing the SIPS process with BIM tools that will improve the predictability, quality control, and production control of the SIPS implementation. The BIM Execution Plan that was developed in Technical Report 3 will be revisited and the BIM Uses that can could aid the SIPS implementation will be determined. Once again, QFD tools such as House of Quality will be used when selecting BIM uses to ensure the client's goals are respected. Once BIM uses that support SIPS are identified each BIM use will be further researched and an analysis on the benefits and feasibility will be conducted.

ANALYSIS PROCEDURE

1. Attempt to obtain 3D model from architect
2. Review BIM Execution plan from Technical Report 3 and
 - a. Identify BIM uses that would support SIPS implementation
 - b. Conduct House of Quality analysis when selecting BIM uses
3. Implement BIM uses
4. Conduct a feasibility analysis of implementing each BIM use
5. Assuming SIPS is being implemented, make a final recommendation of which BIM uses should be used.

EXPECTED OUTCOME

It is expected that the quality, predictability and management of the SIPS implementation can be benefitted by applying some BIM uses. Some potential BIM uses are phase planning, clash detection, and site utilization planning.

RESOURCES

- Literature
 - “Implementing Successful Building Information Modeling” (Epstein)
 - “Building Information Modeling: BIM in Current and Future Practice” (Kensek, Noble)
- Professional Resources
 - Adam Harrison, Project Manager on The Apartment Building
 - Moez Jaffer, BIM Manager at Grunley Construction

- Greg McHugh, Senior Project Manager at Grunley Construction
 - Jason Kincaid, BIM Engineer Architect at Grunley Construction
- Academic Resources
 - Dr. John Messner
 - Computer Integrated Construction (CIC) at Penn State
 - BIM Wiki
 - Integrative Collaborative Studio materials

APPENDIX 1 – BREADTH STUDIES

STRUCTURAL BREADTH

Building on Analysis 2, implementing prefabricated panels systems will have an impact on the structures. A structural analysis will have to be performed to ensure the load of the panels can be supported by the concrete structure. In addition, the interface between the prefabricated panels and the structure will be designed and detailed.

MECHANICAL BREADTH

The building enclosure has a large impact on the mechanical system of the building. The prefabricated panel system designed in Analysis 2, will have to be analyzed to ensure the new building enclosure is not compromising mechanical performance.

APPENDIX 2 – SPRING ANALYSIS SCHEDULE

The Apartment Building																															
Spring 2015 Proposed Schedule																															
B. Kerem Demirci																															
	Task	January				February				March				April				May													
		1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4										
		1/5	1/12	1/19	1/26	2/2	2/9	2/16	2/23	3/2	3/9	3/16	3/23	3/30	4/6	4/13	4/20	4/27	5/4	5/11	5/18										
Analysis 1	Apartment Market Demand Evaluation	Research market analysis methods																													
		Document market evaluation process																													
		Conduct market analysis																													
		Apply findings to The Apartment Building																													
Analysis 2	Exterior Enclosure Acceleration	Research prefabricated systems																													
		Design appropriate system																													
		Create sequence and installation plan																													
		Perform schedule analysis																													
		Perform cost impact analysis																													
		Conduct structural analysis and detailing																													
Analysis 3	SIPS for Interior Fit-out	Research SIPS case studies																													
		Develop Implementation Guide																													
		Apply SIPS to The Apartment Building																													
Analysis 4	Tools to Support SIPS	Obtain 3D model from Architect (if possible)																													
		Identify supporting BIM uses																													
		Research and implement BIM uses																													
		Make final recommendations to owner																													
			Spring Break																	Compile Final Report and Presentation				Final Presentations				AE Banquet			

Milestones	Date
Analysis 1 Complete	2/2/2014
Analysis 2 Complete	3/2/2014
Analysis 3 Complete	3/23/2014
Analysis 4 Complete	3/23/2014

APPENDIX 3 – ANALYSIS WEIGHT BREAKDOWN

Table 1 shows the weighting of each analysis as it relates to the overall grade.

Table 1: Grade Breakdown

Analysis	Description	Grade Breakdown
1	Apartment Market Demand Evaluation	25%
2	Exterior Enclosure Acceleration	25%
3	SIPS Implementation for Interior Fit-out	30%
4	Tools to Support SIPS Implementation	20%
	Total	100%

APPENDIX 4 – MAE REQUIREMENTS

Many of the analysis identified in this proposal will incorporate various tools and knowledge that has been obtained in the MAE courses at Penn State. Some of the MAE classes have already been completed while others will be taken concurrently in the spring. Below is a list of some of the courses and the relevant material from these courses that will be used various analysis.

AE 542: Building Enclosure Science and Design

This course will be taken in the spring. This course should provide good information regarding the new prefabricated panel system that is being proposed in Analysis 2. Relevant topics will include structural considerations, control considerations, and thermal property analysis.

AE 570: Production Management in Construction

Core concepts from this course such as production management tools, lean concepts and QFD decision making tools will be utilized in Analysis 1 and Analysis 3. Analysis 1, the apartment market demand evaluation will use the House of Quality to ensure decisions made take the owner and tenant requirements into account. In the SIPS Implementation Guide that will be developed as a part of Analysis 3, various production tracking tools will be identified and suggested to help monitor and control the SIPS process.