Mueller Laboratory Renovation: Final Proposal Revision 2

By Mark Jackson Construction Management Option 4/7/15

Table of Contents

Executive Summary	3
Recycling Opportunities	4
Asbestos Abatement	5
Roof Deck Reniforcement	5
Site Logistics	7
Conclusions	8
Appendix 1	9
Appendix 2	10

Executive Summary

The Mueller building renovation includes the full gutting of four of the building's seven floors. A large portion of the demolished materials will include ductwork and HVAC piping. This large quantity of similar construction debris makes the project a prime candidate for a large scale recycling effort. The possibility of recycling both on site and off site will be discussed. Furthermore, as the project moves from demolition to construction, transitioning methods of recycling will be examined. Associated costs with these methods can also be investigated.

This project also includes abatement of asbestos on the floors being renovated. This abatement takes up a not insignificant part of the schedule. Alternated methods of abatement will be looked at, as well as the legal requirements. Saving schedule time by increasing manpower for abatement, or by canceling the abatement all together, are both possibilities. Each option has its own ramifications on the project cost.

Site logistics are another issue of the project. Located on the busy PSU campus requires a small job site, as well as disturbance to pedestrian traffic in the area. Alternate material storage and contractor parking locations are discussed. Use of space south of the project could open possibilities for a safer, cleaner job site. A more general study of different site possibilities is necessary.

Roof reinforcement is necessary for new air handling units (AHUs) to be installed. Currently the reinforcement is planned to be installed under the roof deck. If the reinforcing is instead placed on top of the roof deck the installation process will be greatly simplified, saving time and eliminating difficult overhead work. Details of attaching of the reinforcing to the top of the roof deck will be examined as a CM depth study.

The project currently calls for all fluorescent light fixtures to be replaced with LED fixtures. LEDs are far more efficient than fluorescent fixtures, and have a very short pay-back period. However, LED fixtures are expensive to upgrade in the future, since the entire fixture must be replaced. Downlight fixtures with Edison-type sockets equipped with screw-in LED bulbs have several advantages over the specified hard-wired LED downlights, including cheaper initial cost and easier upgrade, while still providing identical performance.

Recycling

The Mueller building renovation includes significant gutting of four floors of the building. This demolition will create a large amount of construction waste, which could just be thrown in dumpsters and hauled away. However, Penn State seeks to be as sustainably minded as possible. Penn State currently diverts 60% of its waste from landfills by recycling and composting as much as possible. For all construction work Penn State requires the recycling or reuse of 75% of project waste. The following materials Section 8.11 of Penn State's general conditions for construction contracts states that "The contractor is required to recycle and/or salvage 75% of construction, demolition, and land clearing waste." To that end, Penn State specifically seeks to recycle or reuse the following materials:

- Cardboard
- •Clean dimensional wood
- •Beverage and food containers
- •Brick and CMU
- •Ferrous and non-ferrous metals
- •Recyclable Plastic
- •Gypsum wallboard

- Asphalt and concrete paving
- •Ceiling Tile
- Carpeting
- •Existing Windows
- •Used equipment oil
- •Useable appliances

More study is needed to see exactly how recycling can be implemented on the Mueller renovation. Demolition occurring early in the project will require large dumpsters to hold the ductwork, piping, and other demolition debris that are to be recycled. When the project moves into its construction phase there will be less to be recycled, so large dumpsters, and the jobsite space for them, will no longer be required. This transition between demolition and construction recycling needs to be carefully coordinated.

Another recycling solution was suggested by Dr. Riley during proposal presentations. There exist some companies that, for a fee, take unsorted demolition and construction debris and will sort and recycled them offsite at their own facility. This method would obviously accelerate the project schedule, since workers would not have to sort debris for recycling. Also this would eliminate the need for multiple recycling dumpsters for different materials. However, the cost of this service is unknown, and needs further research.

It is expected that a combination of both onsite and offsite recycling could be implemented to both save schedule time as well as minimize cost. Materials that are easy to sort for recycling, such as large pieces of ductwork and piping, could be recycled on site. More mixed debris such as gypsum, wood, conduit, and other waste could be sorted offsite. Whether such a solution is feasible will be researched next semester.

Knowledge gained from this research can be applied to more than just the Mueller project. Maximizing recycling on both new construction and building renovations is a critical industry issue. Minimizing the waste going to landfills is a huge step in making construction more sustainable. Any methods that make implementation of recycling easier, cheaper, or less time consuming without compromising results will benefit the entire construction industry. Interviewing companies that sort and recycle mixed construction debris may show great promise and encourage growth in this part of the recycling industry. Or perhaps more efficient ways of recycling on site can be found and their effectiveness demonstrated. Either way, studying the best way to recycle construction debris is crucial for sustainable construction.

Asbestos Abatement

In addition to general project waste, the Mueller renovation includes asbestos abatement on 4 of the building's 7 floors. Pennsylvania's Department of Environmental Protection (DEP) requires asbestos abatement prior to any demolition or renovation if the asbestos containing material (ACM) is "friable." The DEP states "any material that may be destroyed, broken or reduced to powder through normal hand pressure is considered friable and subject to regulations regarding abatement."

On the schedule this abatement takes from five to fifteen days for each floor, adding up to forty days of schedule time. If the ACM is not friable, perhaps abatement could be canceled, saving more than a month of schedule time, as well as the costs associated with abatement. Penn State's reasons for pursuing the abatement should be examined, especially since the three unrenovated floors of the building will still have asbestos at the conclusion of the project. If however the ACM is friable and abatement is necessary, methods to speed up the process should be examined. Additional manpower or longer workdays will shorten the schedule, but will have an effect on the project cost. This too can be analyzed.

Roof Deck Reinforcement

Early in the project the roof deck is scheduled to be reinforced from underneath to allow the new heavy air handling units to be placed on the roof deck. W8x40 and W12x65 beams are to be run underneath existing concrete beams supporting the roof deck. These large beams also require complex anchoring the concrete beams they support, as seen in the detail below.




Figure 1. Roof deck reinforcing beams

This installation of steel reinforcement requires the demolition on the sixth floor to be complete. Investigating other ways to reinforce the roof deck, or alternate locations for the air handling units that would not require roof deck reinforcement, could prove valuable. If a solution is found that does not require roof deck reinforcement then the placement of the AHUs is no longer dependent on the completion of the sixth floor demolition. This would lead to both schedule and cost savings. However, if reinforcement is required, alternate methods should be investigated. Perhaps installation of vertical columns instead of horizontal beams could provide the necessary reinforcement. Or, if horizontal reinforcement is necessary, prefabrication of the reinforcement components might save schedule time. Either way, further investigation is warranted.

This research can also fulfil a breadth requirement. Calculating the structural loads of the AHUs on the roof and the resulting required reinforcement delves into Structural breadth. All the loads on the roof, as well as the capability of the existing roof structure, will need to be calculated. If the existing roof framing has additional capacity to allow relocation of the AHUs then a comparative analysis can be undertaken. The two options being compared would be (1) roof reinforcement and (2) AHU relocation. This comparison will include investigation of the associated cost and schedule benefits, labor requirements, and material choices. The results of this investigation will be delivered in the final report and presentation

Site Logistics

From the north side of the Mueller Building to the south side the ground drops roughly 15 feet over a 150 foot run. This ten percent grade carries rainwater off the site to even steeper slopes south of the building, as seen in the topographic map below.




Figure 2. Red lines represent 2 ft contours.

Without proper prevention sediment and other contaminants could run off the site and into storm drains, contaminating a wide area.

On the north side of the site is the access road to the Mueller renovation. It branches off from the PSU Library loading dock. Currently construction dirt, mud, and debris on trucks can easily enter the Library driveway and nearby Curtain road. Furthermore, that stretch of Curtain road is subject to particularly heavy pedestrian traffic both on the sidewalks and crossing the road. Deliveries to the site and trucks hauling away debris have to enter this congested stretch of road

Relocating the site access road to the south could solve these problems. A proposed new job site perimeter is shown below.




Figure 3. New site perimeter and entrance.

The new site entrance is from the south, with the existing service road between Whitmore and Davey Laboratories acting as an access road. The large area between Whitmore and Pond laboratories has only a slight grade, minimizing runoff concerns. This space could contain contractor parking, material storage, and a truck wash station. There is also a redundant sidewalk, such that with careful planning the north-south pedestrian traffic could remain unimpeded. This larger, flatter job site would be safer, less crowded, and minimize contamination of the site's surroundings. Impact to project cost is minimal, while a larger site could speed up the project schedule.

This plan is not perfect. Access to Whitmore Lab would be compromised. Also deliveries would now have to use Pollock road, which also has heavy pedestrian traffic. Only a full investigation weighing benefits and disadvantages will tell whether moving the job site south is feasible.

Conclusions

All of these alternate construction options deserve further investigation. The degree to which recycling and asbestos abatement is pursued will have an effect on both project schedule and cost. Finding an option where roof reinforcement is unnecessary would also cut costs and schedule duration. And examining other possible project parking and delivery areas affect both the project's impact on its community and the environment. Studying each of these options more will quickly show which are not viable and which do have potential to reduce cost, duration, and impact on the building's environment.

Appendix 1: Breadth Studies

Structural Breadth

To reinforce the roof for the new air handler units, 25 steel beams are to be installed underneath the existing concrete beam structure supporting the roof deck. These beams range from W12X26 to W12X65. This task requires the ceiling plenum of the 6th floor to be demolished so the beams can be lifted into place and secured. Installation of these reinforcing beams is on the schedule critical path, since the air handler units can't be placed until the reinforcing is in place. Furthermore, installation is time consuming due to the constraints of working overhead in confined spaces.

As a structural analysis breadth topic, relocation of the reinforcing from underneath the roof deck to on top of the roof deck will be examined. Placing this reinforcing on top of the roof deck should have no effect on the structural strength of the roof. Rooftop placement simplifies installation and is not dependent on the demolition of the $6^{\rm th}$ floor ceiling plenum. Details regarding affixing the reinforcing to the roof deck will be examined as a CM depth topic.

Specific deliverables will include:

- 1. A complete description of the both building's existing roof framing and the increased roof load due to the new air handler units being installed. Calculations showing the necessity of roof reinforcement will be given.
- 2. A complete description, with drawings, of the renovation's current design for under-deck roof reinforcement plan.
- 3. A complete description, with drawings and corresponding calculations, of my proposed roof-top roof deck reinforcement plan.
- 4. A comparison of the existing reinforcement plan and my reinforcement plan, and a recommendation of which plan is best, based on cost and duration.

Electrical Breadth

Fluorescent fixtures are being replaced with LED fixtures throughout the renovation. Replacing 2x4 recessed fluorescent troffers with 2x4 recessed LED troffers has a short payback period due to their high efficiency. LED downlights also are very efficient. However, improvements in LED technology can quickly make current LED fixtures obsolete. Because of this, LED fixtures that can be easily and cheaply upgraded are desirable.

For electrical breadth the recessed LED downlight fixtures will be compared to standard incandescent recessed downlight fixtures with Edison-type sockets that are equipped screw-in LED bulbs. Screw-in LED bulbs are currently available with lumen output, CRI, and color temperature very similar to the project's specified recessed LED downlight fixtures. However, these screw-in LED bulbs are far cheaper. Also, a screw-in LED bulb can be easily replaced in the future with an LED bulb that has a higher CRI, or is more efficient, or has a higher lumen output. Thus, using a screw-in LED bulb satisfies the lighting performance specifications, costs less, and allows for easy future upgrades.

Specific deliverables will include data to showing that Edison-type socket fixtures with screw-in bulbs:

- 1. Offer the same performance as hard-wired LED can lights
- 2. Cost less than hard-wired LED can lights
- 3. Allow for easy future upgrades to even more energy efficient/better CRI LED bulbs.

Appendix 2: Spring Analysis Schedule

Analysis 4	Analysis 3	Analysis 2	Analysis 1																	Re		SP 3	Analysis	Jan	\dagger			Propos
		Asbestos mitigation requirements	AHU placement/roof reinforcement	Leg																Research Asbestos Abatement		smaller AHU	s of Roof Deck	18-Jan		Milestone 1	1/23/15	Proposed Senior Thesis Schedule
s study	ptimiza	itigatio	nent/ro	Legend																s Abate				Jan	25.			s Sched
and 3D	tion	n requir	of reinf														Kecycling	Research		ment				Feb	-			ule
model		ements	orcement													Olisite Lecycling	Officite recu	rch						8-Feb		2	2/13/15 Milestone	
														study	Site lo	CIIIIS	dina							Feb	ŕ			Muell
4	s	2	1	Milestone								CAD SITE IIIOGEI	Detailed site study	Bouch	Site logistics	İ								22-Feb				Mueller Building Renovation
Final rep	Site stud	Abateme	Structura	e Description								Iodel	ite study											1-Mar		3	3/6/15 Milestone	Renovation
Final report complete, 2nd draft of presentation sli	Site study and 3D model complete.	Abatement research and recycling research compl	I/mechanica	on								× 1	· m	R	,	3 0	G	0	z	-	R	P	s	8-Mar		Break	3/8/15- 3/14/15 Spring	
, 2nd dra	del com	ind recy	breadt								Conclu													Mar	ŕ			Mark.
Ift of prese	plete.	cling rese	h complet							Outline report	Conclusions													Mar	22			Mark Jackson
entation slides		arch complete.	Structural/mechanical breadth complete, schedule/cost changes calculated			Presenta	Finalize	Finalize		report														29-Mar		4	4/3/15 Milestone	Construction Option
des complete		ľ	st chan			ntation	" [5-Apr				Option
te.			ges calc				-	n	_	D	_	- ×	, 0	P		m 2	0		_	A	z	-	F	Apr	13.	Apr o	po .	
			ulated.		νzο	-	-	-	A		z	m o	, ш	æ		0	U	n	-	s	т	=		Apr	į.	Apr	,	
																								Apr	36			Adviso
										7	m	ر ۾) Z	A	,		z	9	0	-	z	ш	s	3-May				Advisor: Dr. Riley